UNIVERSITY OF ILLINOIS
LIBRARY
DEC 19 1961
CHICAGO

december 1961
the
institute
of
radio
engineers

Proceedings of the IRE

special issue on
PLASMA



PIONEERS IN MINIATURIZATION

SPECIAL CUSTOM BUILT POWER TRANSFORMERS & REACTORS

New designs for both military and commercial types custom built to YOUR specifications for transistor and tube applications.

Exceptional quality and reliability is provided in all UTC designs. Over 30 years of engineering knowledge and experience backed by complete environmental testing and life testing facilities assure the highest standard in the industry. Full analysis and evaluation of materials are conducted in UTC's Material and Chemical Laboratories. Rigid quality control measures coordinated with exhaustive statistical findings and latest production procedures results in the industry's highest degree of reliability. Range covered in Power Transformers is from milliwatts to 100 KVA.

SOME TYPICAL APPLICATIONS:

Current Limiting
Filament
Isolation
Plate
Transistor Inverter
Transistor Supply

SPECIAL CUSTOM BUILT IRON CORE COMPONENTS FOR EVERY PHASE OF THE ELECTRONICS ART



Write for catalog of over 1,000 STOCK ITEMS with UTC High Reliability IMMEDIATELY AVAILABLE from your local distributor.

POWER TRANSFORMERS • AUDIO TRANSFORMERS
REACTORS • PULSE TRANSFORMERS • ELECTRIC WAVE FILTERS • LUMPED CONSTANT DELAY LINES
HIGH Q COILS • MAGNETIC AMPLIFIERS
SATURABLE REACTORS • REFERENCE UNITS

UNITED TRANSFORMER CORP.

150 VARICK STREET, NEW YORK 13, N.Y.

PACIFIC MFG. DIVISION: 3630 EASTHAM DRIVE, CULVER CITY, CALIF.

EXPORT DIVISION: 13 EAST 40th STREET, NEW YORK 16, N. Y. CABLES: "ARLAB"

VOLUME 49, NUMBER 12

December, 1961

published monthly by The Institute of Radio Engineers, Inc.

Proceedings of the IRE®

contents

Poles and Zeros 1741

B. R. Tupper, Director, 1961–1962 1742

Open Letter from the President, *Lloyd V. Berkner* 1743

PAPERS

Introduction to the Plasma Issue, *D. G. Dow and E. W. Herold* 1747
Plasma Physics—An Elementary Review, *M. P. Bachynski* 1751
Oscillations and Noise in Low-Pressure DC Discharges, *F. W. Crawford and G. S. Kino* 1767
Ionic and Plasma Propulsion for Space Vehicles, *G. R. Brewer, M. R. Currie, and R. C. Knechtli* .. 1789
Transmission of Electromagnetic Waves Through an Ionized Layer in the Presence of a Strong Magnetic Field, *T. B. Harley and G. Tyras* 1822
The Use of Magnetic Fields in the Elimination of the Re-Entry Radio Blackout, *H. Hodara* 1825
RF Reflectance of Plasma Sheaths, *Leonard S. Taylor* 1831
Correction to "A Small-RF-Signal Theory for an Electrostatically Focussed Traveling-Wave Tube," *W. W. Siekanowicz* 1836
Mutual Coupling of Two Thin Infinitely-Long Slots Located on a Perfectly Conducting Plane in the Presence of a Uniform Plasma Layer, *James S. Yee* 1837
Antenna Noise Temperature in Plasma Environment, *M. P. Bachynski, I. P. French, and G. G. Cloutier* 1846
Generalized Appleton-Hartree Equation for Any Degree of Ionization and Application to the Ionosphere, *I. P. Shkarofsky* 1857
The Electrical Conductivity of a Partially Ionized Gas, *Dipak L. Sengupta* 1872
Interaction of Microwaves in Gaseous Plasmas Immersed in Magnetic Fields, *K. V. Narasinga Rao, J. T. Verdeyen, and L. Goldstein* 1877
Frequency Conversion in a Microwave Discharge, *J. R. Baird and P. D. Coleman* 1890
A Plasma Microwave Energy Detector, *R. L. Taylor and S. B. Herskovitz* 1901
Interaction of a Modulated Electron Beam with a Plasma, *G. D. Boyd, R. W. Gould, and L. M. Field* 1906
A Method of Measurement of Flame Attenuation at 200 Mc, *Albert W. Biggs* 1917
Electrical Characteristics of a Penning Discharge, *J. C. Helmer and R. L. Jepsen* 1920
Generation and Application of Highly Ionized Quiescent Cesium Plasma in Steady State, *J. Y. Wada and R. C. Knechtli* 1926
A New Approach to Thermionic Energy Conversion: Space Charge Neutralization by an Auxiliary Discharge, *W. Bernstein and R. C. Knechtli* 1932

CORRESPONDENCE

Stability Criteria for a Tunnel-Diode Amplifier, *H. Boyet, D. Fleri, and C. A. Renton* 1937
Discussion of a Deflection System for a Flat Television Picture Tube, *H. Gruenberg and E. G. Ramberg* 1938
A Resonant Slot Parametric Amplifier, *J. W. Amoss and G. P. Rodrigue* 1939
Low-Frequency Noise in Backward Diodes, *W. C. Follmer* 1939
An Extremely Wideband Tunable *S*-Band Parametric Amplifier, *Martin Grace* 1940
A Tunnel-Diode Frequency Multiplier with Gain, *F. S. Barnes and L. Morris* 1940
Generation of Microwave Harmonics in an Electrodeless Discharge at Low Pressure, *C. B. Swan* 1941
A Ruby Laser Exhibiting Periodic Relaxation Oscillations, *R. E. Johnson, W. H. McMahan, F. J. Oharek, and A. P. Sheppard* 1942
Broad-Band *S*-Band Parametric Amplifier, *Kenneth M. Johnson* 1943
Magnetoresistive Effect as a Possible Memory Device, *C. Pettus and T. Young* 1943
A Generalized Hildebrand's Method for Nonuniform Transmission Lines, *Iwao Sugai* 1944
The Radar Cross Section of the Moon, *T. B. A. Senior and K. M. Siegel* 1944
WWV and WWVH Standard Frequency and Time Transmissions, *National Bureau of Standards* 1945
Notice of Frequency Adjustment WWV WWVH, *National Bureau of Standards* 1945
Rebuttal to "A Note on Sugai's Class of Solutions to Riccati's Equation," *Iwao Sugai* 1946
On the Hues Seen in Fox-Color Images, *C. Burckhardt and M. J. O. Strutt* 1946
A Stability Test for Linear Discrete Systems in Table Form, *E. I. Jury and J. Blanchard* 1947
A Stability Test for Linear Discrete Systems Using a Simple Division, *E. I. Jury* 1948
Duality of Planar Networks, *J. R. James* 1949
Schwarz's Lemma and Linear Passive Systems, *F. M. Reza* 1950

COVER

The interaction of electromagnetic radiation with gases comprised of disassociated ions and electrons, as symbolized on the cover, represents one of several areas of plasma physics treated in this special issue which are becoming of great importance to communications and electronics engineers.

published monthly by The Institute of Radio Engineers, Inc.

Proceedings of the IRE®

continued

Discussion of "Forward Scattering by Coated Objects Illuminated by Short Wavelength Radar," *J. Fisch, K. M. Siegel, and R. E. Hiatt* ... 1951
Inductive Probability as a Criterion for Pattern Recognition, *Bernard Harris* ... 1951
Law for Noise Loading of Multivoice-Channel FD Systems, *C. A. Parry* ... 1952
Reliability Factors in Thermoelectric Generator Design, *M. R. Seiler and T. S. Shilliday* ... 1952
A Proposed Test of the Constancy of the Velocity of Light, *C. K. Gordon, Jr.* ... 1953
Narrow-Band and Wide-Band Noise Figures, *Paul J. Bêneteau* ... 1954
Design of a Helium-Neon Gaseous Optical Maser, *C. F. Luck, R. A. Paananen, and H. Statz* ... 1954
A Critical Note on "Steady-State Analysis of Circuits Containing a Periodically Operated Switch," *J. M. Layton* ... 1955
Cyclic Codes and Transition Coding, *Francis Corr* ... 1956
A Transistor Equivalent Circuit, *Vasil Uzunoglu* ... 1957
A DC Pumped Amplifier with a Two-Dimensional Field Structure, *J. C. Bass* ... 1957
Miniaturized *S*-Band Isolator, *D. Bruce Swartz* ... 1958
Pole-Zero Sensitivity Relationships, *W. E. Newell* ... 1959
A Waveguide In-Line Ferrite Rotary Joint, *H. Saltzman and A. Rossero* ... 1959
Signal-to-Noise Ratios in Photoelectric Mixing, *B. M. Oliver* ... 1960
Efficiency of Frequency Multipliers Using Charge-Storage Effect, *D. J. Roulston* ... 1961
Transistor Storage Time in Circuits with Speed-Up Capacitors, *R. P. Nanavati and R. J. Wilfinger* 1962
Improvement in the Performance of an Automatic Noise Figure Meter with a Liquid-Nitrogen-Cooled Termination, *C. T. Stelzried* ... 1963
A Tunnel-Diode Wide-Band Frequency Doubling Circuit, *Frank D. Neu* ... 1963
A Note on Antenna Breakdown, *E. L. Tarca* ... 1964

REVIEWS

Books:
"Satellite Environment Handbook," Francis S. Johnson, Ed., *Reviewed by M. G. Morgan* ... 1970
"Handbook of Thermophysical Properties of Solid Materials, Vol. IV," A. Goldsmith, T. E. Waterman, and H. J. Hirschhorn, Eds., *Reviewed by James G. Harper* ... 1970
"Static Relays for Electronic Circuits," Richard F. Blake, Ed., *Reviewed by R. P. Burr* ... 1971
"Thermoelectricity: Science and Engineering," by R. R. Heikes and R. W. Ure, *Reviewed by W. H. Clingman* ... 1971
Recent Books ... 1971
Scanning the TRANSACTIONS ... 1972

ABSTRACTS

Abstracts of IRE TRANSACTIONS ... 1973
Abstracts and References ... 1979

INDEX

1961 PROCEEDINGS OF THE IRE INDEX ... *Follows Page* 1994
1961 IRE INTERNATIONAL CONVENTION RECORD INDEX ... *Follows Page* IRE Index-24

IRE NEWS AND NOTES

Current IRE Statistics ... 14A
Calendar of Coming Events and Author's Deadlines ... 14A
Professional Group News ... 15A
Current IRE Standards Available ... 16A
Obituary ... 22A
Program:
Eighth National Symposium on Reliability and Quality Control ... 22A

DEPARTMENTS

Contributors ... 1965
IRE People ... 40A
Industrial Engineering Notes ... 28A
Meetings with Exhibits ... 8A
Membership ... 68A
News—New Products ... 80A
Positions Open ... 105A
Positions Wanted by Armed Forces Veterans ... 124A
Professional Group Meetings ... 76A
Section Meetings ... 72A
Advertising Index ... 141A

BOARD OF DIRECTORS, 1961
*L. V. Berkner, *President*
*J. F. Byrne, *Vice President*
Franz Ollendorff, *Vice President*
*S. L. Bailey, *Treasurer*
*Haraden Pratt, *Secretary*
*F. Hamburger, Jr., *Editor*
*Ernst Weber
Senior Past President
*R. L. McFarlan
Junior Past President

1961
C. W. Carnahan (R7)
B. J. Dasher (R3)
A. N. Goldsmith
*P. E. Haggerty
C. F. Horne
R. E. Moe (R5)
D. E. Noble
B. M. Oliver
J. B. Russell, Jr. (R1)

1961–1962
A. B. Bereskin (R4)
M. W. Bullock (R6)
A. B. Giordano (R2)
W. G. Shepherd
G. Sinclair
B. R. Tupper (R8)

1961–1963
E. F. Carter
L. C. Van Atta

**Executive Committee Members*

EXECUTIVE SECRETARY
George W. Bailey

John B. Buckley, *Chief Accountant*

Laurence G. Cumming, *Professional Groups Secretary*

Joan Kearney, *Assistant to the Executive Secretary*

Emily Sirjane, *Office Manager*

ADVERTISING DEPARTMENT
William C. Copp, *Advertising Manager*

Lillian Petranek, *Assistant Advertising Manager*

EDITORIAL DEPARTMENT
Alfred N. Goldsmith, *Editor Emeritus*
F. Hamburger, Jr., *Editor*
E. K. Gannett, *Managing Editor*
Helene Frischauer, *Associate Editor*

EDITORIAL BOARD
F. Hamburger, Jr., *Chairman*
T. A. Hunter, *Vice Chairman*
E. K. Gannett
T. F. Jones, Jr.
J. D. Ryder
G. K. Teal
Kiyo Tomiyasu
A. H. Waynick


AUDITED PAID CIRCULATION ABC

PROCEEDINGS OF THE IRE, published monthly by The Institute of Radio Engineers, Inc., at 1 East 79 Street, New York, 21, N. Y. Manuscripts should be submitted in triplicate to the Editorial Department. Correspondence column items should not exceed four double-spaced pages (illustrations count as one-half page each). Responsibility for contents of papers published rests upon the authors, and not the IRE or its members. All republication rights, including translations, are reserved by the IRE and granted only on request. Abstracting is permitted with mention of source.

Thirty days advance notice is required for change of address. Price per copy: members of the Institute of Radio Engineers, one additional copy $1.25; non-members $3.00. Yearly subscription price: to members $9.00, one additional subscription $13.50; to non-members in United States, Canada, and U. S. Possessions $18.00; to non-members in foreign countries $19.00. Second-class postage paid at Menasha, Wisconsin, under the act of March 3, 1879. Acceptance for mailing at a special rate of postage is provided for in the act of February 28, 1925, embodied in Paragraph 4, Section 412, P. L. and R., authorized October 26, 1927. Printed in U.S.A. *Copyright © 1961 by The Institute of Radio Engineers, Inc.*

They said "PROVE IT"... AND WE DID!

The moisture-resistance curves show how Type 160P Difilm® Black Beauty® Capacitors outperform all other commercial tubulars



To test tubular capacitors, we figuratively brought jungle conditions into the laboratory. The curves tell what happened.


Difilm Black Beauty Molded Capacitors withstood almost 4000 hours (95 to 100% R. H. at 40 C) with *no change in humidity resistance!*

No other tubulars came close to this performance. Difilm Capacitors proved themselves the *true* answer to moisture problems in entertainment and commercial electronics.



For complete technical data on Difilm Black Beauty Capacitors, write for Engineering Bulletin 2025 to Technical Literature Section, Sprague Electric Company, 235 Marshall Street, North Adams, Massachusetts.

MOISTURE RESISTANCE COMPARISON CHART
FOR TUBULAR CAPACITORS



A. DIFILM® DUAL DIELECTRIC (PAPER and POLYESTER FILM), solid impregnant, molded case

B. PAPER DIELECTRIC, solid impregnant, molded case
C. DIFILM DUAL DIELECTRIC (PAPER and POLYESTER FILM), solid impregnant, dipped coating
D. POLYESTER FILM DIELECTRIC, molded case
E. PAPER DIELECTRIC, wax or oil impregnant, molded case
F. PAPER DIELECTRIC, solid impregnant, waxed cardboard jacket
G. PAPER DIELECTRIC, wax or oil impregnant, waxed cardboard jacket

You can get off-the-shelf delivery at factory prices of Replacement Type TM Capacitors (same construction as O. E. M. Type 160P) in pilot quantities up to 249 pieces from your local Sprague Industrial Distributor.

SPRAGUE COMPONENTS

CAPACITORS
RESISTORS
MAGNETIC COMPONENTS
TRANSISTORS
INTERFERENCE FILTERS
PULSE TRANSFORMERS
PIEZOELECTRIC CERAMICS
PULSE-FORMING NETWORKS
HIGH TEMPERATURE MAGNET WIRE
CERAMIC-BASE PRINTED NETWORKS
PACKAGED COMPONENT ASSEMBLIES
FUNCTIONAL DIGITAL CIRCUITS

SPRAGUE®
THE MARK OF RELIABILITY

'Sprague' and '②' are registered trademarks of the Sprague Electric Co.


Charles Steinberg and others in our Department of Medical and Biological Physics have been engaged in developing a computer system to aid in the diagnosis of heart disease.

Computers Will Aid in the Diagnosis of Heart Disease

The diagnosis of heart disease can be greatly facilitated by making use of the high operational speed and vast memory of a digital computer. A computer system can be programmed to accept the analog electrocardiogram signal from the patient, convert the data to digital form, recognize the important patterns, measure the significant characteristics of these patterns, and indicate the likelihood of a particular cardiac pathology.

It is envisioned that one computer installation will serve many physicians. While a physician is recording a patient's electrocardiogram in the conventional way in his office, he will be able to simultaneously send the signals —via telephone circuits—to the computer center and receive a report within minutes to corroborate his diagnosis.

As a step toward the realization of diagnostic computer centers, an experimental system is being developed at AIL*. One of the most important parts of the system is the computer program that determines the likelihood of cardiac disease. To develop the program, data was collected on 45 subjects, of whom 15 had aortic valvulitis, 15 had hypertension, and 15 were normal. Four kinds of signals were recorded for each subject (see illustration): an electrocardiogram (ECG), a balistocardiogram (BCG), a phonocardiogram (PCG), and an arterial-pulse (AP) recording.



TYPES OF CARDIOGRAMS AND CORRESPONDING WAVEFORMS

* Sponsored by the Heart Disease Control Program, Bureau of State Services Division of Chronic Diseases, U.S. Public Health Service, Washington, D.C.

Discrete portions of each of the four kinds of cardiogram waveforms from each subject were selected for the basic input data. A total of 45 parameters were measured for each of the 45 subjects and consisted mainly of peak amplitudes, durations and intervals.

The means, variances and correlation coefficients were calculated for each of the three groups of subjects. All parameters that were not significant in distinguishing one group from another were eliminated by standard statistical techniques. The remaining parameters were combined in a multidimensional probability-density function.

Three probability-density functions were computed—one for each of the three groups of subjects. For each subject, the ratio of the hypertensive-group probability-density function to the normal-group probability-density function—the hypertensive-likelihood ratio —was calculated. Similarly, the aortic-valvulitis-likelihood ratio—was calculated. The likelihood ratios were then used to determine to which one of the three groups a tested subject belonged. The likelihood ratios enabled the computer system to identify 26 out of 30 subjects who had either hypertension or aortic valvulitis.

The programming of the computer to recognize pathological data was based on manually derived measurements of significant parameters of the waveform data. To automate the technique, a pattern-recognition program for electrocardiograms was developed. One objective was to develop a computer program that would recognize and measure parameters from any electrocardiogram taken with any lead system and from any subject.

The electrocardiogram parameters selected for measurement were the wave onset, wave peak, wave termination, and time intervals in the P, Q, R, S, T and U waves. The program is also designed to recognize whether the P wave is diphasic, bifid or trifid.

The point of greatest negative rate of change—after the R wave and before the S wave—was selected as a reference point that is repetitive in any ECG. Starting at this point, the waveform for one complete heartbeat can be isolated and the starts, peaks and terminations of the P, Q, R, S, and T waves can be recognized, and their amplitudes, durations and intervals can be measured. With this program of pattern recognition, the computer correctly measured 767 out of 770 ECG parameters.

In future phases of this investigation of the use of computers as diagnostic aids, the number of test-subjects will be increased, the likelihood ratio will be computed for other cardiac conditions, and pattern-recognition programs will be developed for other types of cardiac signals.

REFERENCES

W. E. Tolles, C. A. Steinberg, and W. J. Carbery —"Experimental Techniques and Results of a Study Using a Computer as a Diagnostic Aid." Transactions of the New York Academy of Sciences, Ser. II, Vol. 23, No. 3, January 1961, pp. 246-258.

A. E. Rikli, W. E. Tolles, C. A. Steinberg, W. J. Carbery, S. Abraham, C. A. Caceres and A. H. Freiman—"Computer Analysis of Electrocardiographic Measurements." Circulation, Vol. 24, No. 3, September 1961.

A. E. Rikli and C. A. Caceres, Heart Disease Control Program, Division of Special Health Services—Public Health Service, Bethesda, Md. "The Use of Computers by Physicians as a Diagnostic Aid." Transactions of the New York Academy of Sciences, Ser. II, Volume 23, No. 3, pp. 237-239, December 1961.

C. A. Caceres and A. E. Rikli—"The Digital Computer as An Aid in the Diagnosis of Cardiovascular Disease." Transactions of the New York Academy of Sciences, Ser. II, Vol. 23, No. 3, pp. 240-245, December 1961.

A complete bound set of our fifth series of articles is available on request. Write to Harold Hechtman at AIL for your set.

CONTROL
CUTLER-HAMMER
AIL DIVISION
AIRBORNE INSTRUMENTS LABORATORY
DEER PARK, LONG ISLAND, NEW YORK

FILMISTOR®

METAL FILM RESISTORS OFFER 5 DISTINCT TEMPERATURE COEFFICIENTS TO MEET ALL CIRCUIT REQUIREMENTS

RUGGED END-CAP CONSTRUCTION FOR LONG TERM STABILITY

• • •

EXCEPTIONAL RESISTANCE TO MOISTURE AND MECHANICAL DAMAGE

• • •

SURPASS MIL-R-10509 PERFORMANCE REQUIREMENTS

Providing close accuracy, reliability and stability with low controlled temperature coefficients, these molded case metal-film resistors outperform precision wirewound and carbon film resistors. Prime characteristics include minimum inherent noise level, negligible voltage coefficient of resistance and excellent long-time stability under rated load as well as under severe conditions of humidity.


Close tracking of resistance values of 2 or more resistors over a wide temperature range is another key performance characteristic of molded-case Filmistor Metal Film Resistors. This is especially important where they are used to make highly accurate ratio dividers.

Filmistor Metal Film Resistors are automatically spiralled to desired resistance values by exclusive Sprague equipment. The metallic resistive film, deposited by high vacuum evaporation, bonds firmly to special ceramic cores. Noble metal terminals insure low contact resistance.

The resistance elements, complete with end caps and leads attached are molded in dense, high temperature thermosetting material to form a tough molded shell for maximum protection against mechanical damage, moisture penetration and repeated temperature cycling.

Filmistor Resistors, in 1/8, 1/4, 1/2 and 1 watt ratings, surpass stringent performance requirements of MIL-R-10509D, Characteristics C and E. Write for Engineering Bulletin No. 7025 to: Technical Literature Section, Sprague Electric Co., 235 Marshall Street, North Adams, Mass.

For application engineering assistance write:
Resistor Division, Sprague Electric Co.
Nashua, New Hampshire




SPRAGUE COMPONENTS

RESISTORS	INTERFERENCE FILTERS	HIGH TEMPERATURE MAGNET WIRE
CAPACITORS	PULSE TRANSFORMERS	CERAMIC-BASE PRINTED NETWORKS
MAGNETIC COMPONENTS	PIEZOELECTRIC CERAMICS	PACKAGED COMPONENT ASSEMBLIES
TRANSISTORS	PULSE-FORMING NETWORKS	FUNCTIONAL DIGITAL CIRCUITS

SPRAGUE®
THE MARK OF RELIABILITY

'Sprague' and '②' are registered trademarks of the Sprague Electric Co.



A basic formula from Information Theory . . . provides a measure of the amount of information in a particular type of message, such as TV . . . helps determine the frequency bandwidth, for example, required to transmit the messages. Information Theory, pioneered at Bell Laboratories, guides the search for better communications systems.

DISCOVERY


AT BELL TELEPHONE LABORATORIES

New knowledge comes in many forms. Sometimes it comes in a mathematical formula. Usually it comes after much thought and experiment and the fruitful interaction of different minds and abilities. Most often, too, a particular discovery is small. But many small discoveries have a way of leading to big advances at Bell Laboratories—advances like the transistor . . . or, more recently, the gaseous optical maser, forerunner of communications at optical frequencies. Opportunities for discovery are enhanced by the abilities of the scientists and engineers and the range of the facilities at Bell Laboratories, *world center of communications research and development.*

BELL SYSTEM
AMERICAN TELEPHONE & TELEGRAPH CO. AND ASSOCIATED COMPANIES

MICROWAVE ASSOCIATES PROGRESS REPORT

Microwave Power from Varactor Diodes



Efficient conversion of microwave power has been accomplished with a variety of new varactor frequency multipliers developed at the Waveguide Systems Division of Microwave Associates, Inc.

We have produced microwave power of several watts at UHF frequencies, several hundred milliwatts at X-band frequencies, and tens of milliwatts at Ka-band frequencies. The curve above indicates more accurately the power levels achieved by these Microwave Associates units. They employed doublers and triplers.

Efficiencies of these units range from 80 — 90% in the UHF region and from 20 — 30% at X-band. At present, the highest efficiencies are achieved at relatively narrow bandwidths (1%-2%). However, our capabilities are rapidly improving efficiencies for broader band operation. An example of a fixed-tuned broadband unit is a "tripler" which provides an output of 10 milliwatts over a 14% range at X-band.

Because of their efficiency and simplicity, these frequency multipliers are of considerable interest to systems engineers designing radar exciter circuits, low-power transmitters, stable local oscillator and paramp pump sources, and other circuits which require high frequency stability and exceptionally long life. These varactor multiplier circuits are generally passive, requiring neither tuning nor external bias voltage.

Our progress in producing efficient microwave power with all-solid-state techniques is related to performance of the most advanced high-power epitaxial varactors with significantly lower losses. The capabilities of Microwave Associates' Semiconductor Division in producing such varactors is a most positive asset. As this article is being printed, the multiplier performances shown here have already been exceeded.

We are also developing chains of these frequency multipliers to provide moderate amounts of power when driven by transistor oscillators. Efficiencies of these multiplier chains (RF output/DC input) are as good or better than equivalent klystron sources. Compactness and all-solid-state reliability are equally important benefits.

If you have an application for efficient varactor frequency multiplication or would like to discuss the very latest capabilities of these units, please write to Mr. Herbert Cox, Waveguide Systems Division. We'll be pleased to send you a new article on Varactor Frequency Multiplication by Mr. M. E. Hines.

MICROWAVE ASSOCIATES, INC.
WAVEGUIDE SYSTEMS DIVISION

Burlington, Massachusetts • BRowning 2-3000
Western Union Fax • TWX: Burlington, Mass. 942

Export Sales: MICROWAVE INTERNATIONAL CORP.
36 W. 44th Street, N.Y.C., N.Y., U.S.A., Cable MICROKEN

SHOWN ACTUAL SIZE



SIZE 5 COMPONENTS

FOR SERVO SYSTEM MINIATURIZATION

A complete family of Size 5 components for every servo system function is now available from Kearfott. Stainless steel housings, shafts and bearings protect the units against environmental extremes and contribute to stability under shock, vibration, and temperature fluctuations. • Standard 26-v, 400-cps excitation. • Operating temperature range −55° to +125°C.

CHARACTERISTICS

SYNCHROS

	VOLTAGE (400 cps)	T.R.	NULL (mv)	ERROR (min)
Transmitter				
CJO 0565 100	26	.454	34	10
Control Transformer				
Low Z-CJO 0555 100	11.8	1.765	34	10
High Z-CJO 0552 900	11.8	1.765	34	10
Differential				
CJO 0595 100	11.8	1.154	34	10
Resolver				
Low Z-CJO 0585 100	26	1.0	34	10
High Z-CJO 0589 100	26	1.0	34	10

SERVO MOTORS

	J126-06	J126-02
No-Load Speed	9800 rpm	9800 rpm
Stall Torque	0.10 in. oz	0.10 in. oz
Rotor Moment of Inertia	0.175 gm cm²	0.175 gm cm²
Voltage $\phi 1$ / $\phi 2$ (400 cps)	26 / 36-CT	26 / 26
Power Input / Phase	1.7 w	1.7 w

SYNCHRONOUS MOTOR

	CJO 0172 200
Pull-In Torque	0.06 in. oz
Pull-Out Torque	0.10 in. oz
Pull-Out Power	4 w

MOTOR GENERATORS

MOTOR	CJ4 0812 001	CJO 0812 650	CJO 0813 200
Voltage $\phi 1$ / $\phi 2$ (400 cps)	26 / 36-CT	26 / 36-CT	26 / 26
Power / ϕ	1.5 w	1.5 w	1.5 w
No-Load Speed	8000 rpm	8000 rpm	8000 rpm
Stall Torque	0.10 in. oz	0.10 in. oz	0.10 in. oz
GENERATOR			
Voltage (400 cps)	26 v	26 v	26 v
Volts / 1000 RPM	0.1 v	0.1 v	0.5 v
Null	1.3 mv	10 mv	6.7 mv

Size 5 gearheads range in reduction ratios from 20:1 to 1019:1 for servomotors and motor tachometers above. In addition to Size 5 clutches, brakes, and brake-clutches, Size 6 are available.

Write for complete data

KEARFOTT DIVISION
GENERAL PRECISION, INC.

Little Falls, New Jersey

Meetings with Exhibits

● As a service both to Members and the industry, we will endeavor to record in this column each month those meetings of IRE, its sections and professional groups, which include exhibits.

Δ

December 12-14, 1961

Eastern Joint Computer Conference, Sheraton-Park Hotel, Washington, D.C.

Exhibits: Mr. Charles Phillips, 5603 Jordan Road, Washington 16, D.C.

February 7-9, 1962

3rd Winter Convention on Military Electronics, Ambassador Hotel, Los Angeles, Calif.

Exhibits: Mr. Walter E. Peterson, c/o IRE Los Angeles Office, 1435 South La Cienega Blvd., Los Angeles, Calif.

March 1-3, 1962

Eighth Scintillation and Semiconductor Counter Symposium, Shoreham Hotel, Washington, D.C.

Exhibits: Dr. George A. Morton, RCA Labs., Princeton, N.J.

March 26-29, 1962

International Radio & Electronics Show and IRE International Convention, Waldorf-Astoria Hotel and New York Coliseum, New York, N.Y.

Exhibits: Mr. William C. Copp, IRE Advertising Dept., 72 West 45th St., New York 36, N.Y.

April 11-13, 1962

SWIRECO (South West IRE Conference & Electronics Show), Rice Hotel, Houston, Texas

Exhibits: Mr. J. C. Robinson, P.O. Box 1505, Houston, Texas

May 1-3, 1962

Spring Joint Computer Conference, Fairmont Hotel, San Francisco, Calif.

Exhibits: Mr. John W. Ball, Pacific Telephone Co., 3240 Arden Way, Sacramento, Calif.

May 14-16, 1962

NAECON (National Aerospace Electronics Conference), Biltmore Hotel, Dayton, Ohio

Exhibits: IRE Dayton Office, 33 N. Torrence St., Dayton, Ohio

May 23-25, 1962

National Telemetering Conference, Sheraton Park Hotel, Washington, D.C.

Exhibits: Mr. H. W. Royce, Martin Company, Baltimore, Md.


June 12-14, 1962


Armed Forces Communications & Electronics Show, Sheraton Park and Shoreham Hotels, Washington, D.C.

Exhibits: Mr. William C. Copp, 72 W. 45th St., New York 36, N.Y.

(Continued on page 10A)

Complete Sweeping Oscillator and Frequency Marker Systems





- SWEEPING OSCILLATOR
- FIXED "CRYSTAL" MARKERS
- VARIABLE FREQUENCY MARKER

KAY *Vari-Sweeps*®

- Fundamental Frequency — No Spurious Beats
- Built-in Attenuators • Direct Reading Frequency Dials
- Stable Wide Sweeps • Stable Narrow Sweeps
- 1.0 V into 70 ohms, AGC'd

MODEL IF and MODEL RADAR

4-120 MC VARI-SWEEP MODEL IF

Frequency Range: 4 to 120 mc in six overlapping bands.

Sweep Width: Continuously variable to maximum of at least 30 mc (above 50 mc) or 60% of center frequency below 50 mc.

Sweep Rate: Variable around 60 cps. Locks to line frequency.

RF Output: 1.0 V rms into nominal 70 ohms (50 ohms upon request). AGC'd to ±0.5 db over widest sweep and over tuning range.

Zero Reference: True zero line during retrace.

Attenuators: Switched 20, 10 and 3 db: variable 6 db.

Fixed Markers: Up to eleven, pulse-type, crystal-controlled markers at customer specified frequencies. Accurate to ±0.05%.

Variable Marker: "Birdie pip" marker continuously variable from 2 to 135 mc in 6 overlapping bands. Direct-reading frequency dial accurate to within ±1.0%.

Marker Output: Approx. 5 V peak. **Sweep Output:** Approx. 7 V peak.

10-145 MC VARI-SWEEP MODEL RADAR

Same as Model IF in a different frequency range.

Price: $950.00 f.o.b. factory, including cabinet. $1045.00 f.a.s. New York. Crystal markers $20.00 ea.

TWO UNIT SYSTEM 2-220 mc

KAY *Vari-Sweep*

Frequency Range (CW or Sweeping Operation): 2-220 mc, 10 bands. Direct-reading dial.

Sweep Width: Continuously variable to maximum of at least 30 mc (above 50 mc) or 60% of center frequency (below 50 mc).

Sweep Rate: Variable, 10 to 40 cps; line lock.

RF Output: 1.0 V rms (metered) into nom. 70 ohms (50 ohms upon request). AGC'd to ±0.5 db over widest sweep and tuning range.

Attenuators: Switched 20, 20, 10, 6 and 3 db, plus continuously variable 6 db.

Price: $795.00 f.o.b. factory. $875.00 f.a.s. N.Y.

KAY *Vari-Marker* MODEL H

VARIABLE MARKER: (CW or "Birdie pip").

Frequency Range: 1.7 to 230 mc in ten overlapping bands.

RF Level: 1.0 V rms into 70 or 50 ohms, metered.

Flatness: ±0.5 db, AGC'd.

Attenuators: Switched 20, 10, 6, 3 db, continuous 6 db.

Frequency Dial: Direct reading, accurate to ±1%.

Marker Amplitude: Variable to 5.0 volts peak.

HARMONIC MARKER: (Picket-fence pip or CW).

Intervals: Switched 250 kc, 500 kc, 2.5 mc, 5.0 mc, other frequencies can be specified.

Accuracy: ±0.01%.

Price: $845.00 f.o.b. factory. $930.00 f.a.s. N.Y.

Other Vari-Marker Models — Fixed and Variable Markers.

WRITE FOR CATALOG INFORMATION.

KAY ELECTRIC COMPANY

Dept. 1-12, Maple Avenue, Pine Brook, N.J., CApital 6-4000

MINIATURE TRANSFORMERS

delivered in 24 hours

FROM STOCK

FRANCHISED STOCKING DISTRIBUTORS

CALIFORNIA, INGLEWOOD
Newark Electronics Co., Inc.
CALIFORNIA, LOS ANGELES
Graybar Electric Company
Universal Radio Supply Co.
CALIFORNIA, SAN DIEGO
Telrad Electronic Supply
CALIFORNIA, SAN JOSE
Weatherbie Industrial Electric
COLO., DENVER—Ward Terry
CONN., NEW HAVEN—Radio Shack
CONN., WATERBURY—Bond Radio
DIST. OF COL., WASHINGTON
Electronic Wholesalers, Inc.
FLORIDA, ORLANDO
East Coast Radio of Orlando Inc.
ILL., CHICAGO—Newark Elect.
INDIANA, SOUTH BEND—Radio Dist.
IOWA, CEDAR RAPIDS—Deeco, Inc.
KANSAS, WICHITA—Radio Supply
MARYLAND, BALTIMORE
Electronic Wholesalers, Inc.
D & H Dist. Co., Inc. Indus. Sales Div.
MASSACHUSETTS, BOSTON
Radio Shack Corp.
Sager Electrical Supply Co.
MINN., ST. PAUL—Gopher Electronics
MISSOURI, KANSAS CITY
Jones Electronic Sales
MISSOURI, ST. LOUIS
Interstate Supply Co.
NEW JERSEY—Federated Purchaser, Inc.
NEW YORK, LYNBROOK
Peerless Radio Distributors
NEW YORK, MINEOLA
Arrow Electronics, Inc.
NEW YORK, NEW YORK CITY
Harrison Radio
NEW YORK, BUFFALO
Summit Dist. Inc.
NEW YORK, SCHENECTADY
Schenectady Electronics
NEW YORK, UTICA
Valley Electronic Labs, Inc.
OHIO, CLEVELAND
Main Line Cleveland, Inc.
PENNSYLVANIA, ALLENTOWN & EASTON
Federated Purchaser, Inc.
PENNSYLVANIA, McKEESPORT
Barno Radio Co.
PENNSYLVANIA, NORRISTOWN & PHILA.
Philadelphia Electronics, Inc.
TEXAS, DALLAS—All-State Elect.
UTAH, SALT LAKE CITY—S. R. Ross
WASHINGTON, SEATTLE—F. B. Connelley
CANADA, MONTREAL
Atlas Wholesale Radio Inc.



TOROIDS

Custom-engineered to Exacting Specifications.

- Frequency range: 20 cycles—100 kc
- Power level: Up to 150 watts
- Operating temp. range: –65 to 130°C
- Size range: Approximately ¾ to 4" O.D.
- DC current range: Depends on the size, frequency and power level

MICROTRAN Quality and Reliability Guaranteed!



MICRO MINIATURE TRANSISTOR TRANSFORMER

Molded (-M) 7/8" x 25/32" x 17/32"
Hermetic (-H) 15/16" x 11/16", wt. ¾ oz.
Open Frame (-F) 7/16" x 19/32" x ¾", wt. .4 oz.

Part Number	Application	Primary Impedance	Secondary Impedance
MMT1*	Line to Base	600	600
MMT4*	P.P. Coll. to P.P. Base	50,000 C.T.	600 C.T.
MMT7*	Coll. to P.P. Base	25,000	1,200 C.T.
MMT8*	P.P Coll. to P.P. Base	50,000 C.T.	1,200 C.T.
MMT9*	Line to P.P. Base	600 C.T.	1,200 C.T.
MMT11*	P.P. Coll. to P.P. Base or Line	4,000 C.T.	600 C.T.
MMT17*	P.P. Coll. to P.P. Base	10,000 C.T.	200 C.T
MMT18*	P.P. Coll. to P.P. Base	25,000 C.T.	1,200 C.T.
MMT19*	Coll. to P.P. Base	2,500	2,500 C.T.
MMT26*	Line to Base	600 C.T.	600 C.T.

*Add either -H, -M, or -FB to Part No. to designate construction. See catalog for detailed information.



ULTRA MINIATURE TRANSISTOR TRANSFORMER

Open-frame (-F)* Wt. .08 oz. size 3/8" x 3/8" x 11/32"
Molded (-M)* Wt. .14 oz. size ½" x ½" dia.
Nylon Bobbin, Nickel-Alloy Core. Levels to .5w.

Part Number	Application	Primary Impedance (D.C.)	Secondary Impedance
UM28-(*)	Choke	10 hy (0 dc)	
UM29-(*)	Interstage	600 C.T.	600 C.T.
UM30-(*)	Choke	1.5 hy (0 dc)	
UM31-(*)	Interstage	10,000 C.T.	1,200 C.T.
UM32-(*)	Output	1,500 C.T.	600
UM33-(*)	Output	1,000 C.T.	600
UM34-(*)	Driver	10,000 C.T.	600 C.T.

*Add either -F or -M to part number to designate construction. See catalog for detailed information.



TRANSISTOR TRANSFORMER SELECTOR KIT

Save valuable time in optimizing circuitry

Set of 9 transformers covers impedance range of 150 through 200,000 OHMS. Matches most new transistor impedance ratings.

FULL DESIGN DATA ENCLOSED

• Nomographs and circuitry for determining correct impedances • Power versus DBM chart • Guide to MIL-T-27A • Cross Reference index • Outline drawings.



VERI-MINIATURE TRANSISTOR TRANSFORMER

Open Frame (-FB)* Wt. .2 oz. 13/32" x 3/4" x 17/32"
Molded (-M)* Wt. ¼ oz. 5/8" x 5/8" x ½" high

Part Number	Application	Primary Impedance	Secondary Impedance
VM1*	Input	50	600 (1.5 ma.)
VM2*	Input or Interstage	200,000	600 (1.0 ma.)
VM3*	Interstage	25,000	600 (1 ma.)
VM4*	Input or Interstage	200,000	1,200 (.72 ma.)
VM5*	Interstage	50,000	600 (1.0 ma.)
VM6*	Interstage	100,000	1,200 C.T. (.72 ma.)
VM8*	Output	1,250 (2.0 ma.)	3.4
VM10*	Interstage	2,500 (1.5 ma.)	2,500 C.T.
VM11*	Choke	20 hy. (0 ma.)	12 hy. (.5 ma.)
VM13*	Interstage	20,000	1,000 C.T. (.75 ma.)

*Add either -M, or -FPB to part number to designate construction. See catalog. 4 color coded leads, resin impregnated.

MICROTRAN company, inc.
Write TODAY for catalog and price list of the complete MICROTRAN line.
146 E. MINEOLA AVE., VALLEY STREAM, N. Y.

Meetings with Exhibits

(Continued from page 8A)

June 25-27, 1962

Sixth National Convention on Military Electronics, Shoreham Hotel, Washington, D.C.

Exhibits: Mr. Ralph I. Cole, Melpar, Inc., 3000 Arlington Blvd., Falls Church, Va.

August 21-24, 1962

Western Electronics Show and Conference (WESCON), Ambassador Hotel & Memorial Sports Arena, Los Angeles, Calif.

Exhibits: Mr. Don Larson, WESCON, 1435 La Cienega Blvd., Los Angeles, Calif.

August 29-September 1, 1962

Second International Conference on Information Processing, Munich, Germany

Exhibits: Dr. Heinz Billing, Max Planck Institute, Munich, Germany

October 1-3, 1962

Eighth National Communications Symposium, Hotel Utica & Utica Municipal Auditorium, Utica, N.Y.

Exhibits: Mr. R. E. Gaffney, General Electric Co., Light Military Electronics Dept., Utica, N.Y.

October 8-10, 1962

National Electronics Conference, Exposition Hall, Chicago, Ill.

Exhibits: Mr. Rudy Napolitan, National Electronics Conference, 228 N. LaSalle St., Chicago, Ill.

October 29-31, 1962

15th Annual Conference on Electronic Techniques in Medicine & Biology, Edgewater Beach Hotel, Chicago, Ill.

Exhibits: Dr. J. E. Jacobs, 624 Lincoln Ave., Evanston, Ill.

November 13-15, 1962

Northeast Research & Engineering Meeting (NEREM), Somerset Hotel & Commonwealth Armory, Boston, Mass.

Exhibits: Mr. Stewart K. Gibson, c/o IRE Boston Office, 313 Washington St., Newton, Mass.

Δ

Note on Professional Group Meetings: Some of the Professional Groups conduct meetings at which there are exhibits. Working committeemen on these groups are asked to send advance data to this column for publicity information. You may address these notices to the Advertising Department and of course listings are free to IRE Professional Groups.



TAKEN FROM TOMORROW

BIPCO™ Modules — Built-In-Place Components In Modular Form . . .

The Burroughs Corporation announces the commercial availability of tomorrow's techniques . . . today. BIPCO modules combine the reality of performance, low cost and immediate availability, to signal a major transition in the state of the art.

Thin Film Memory Planes and Solid State Multi-element Modules are the first of the BIPCO module family. The Thin Film Memory is capable of storing 20 words of 8 bits each for a total of 160 bits of information, and has a cycle time of 0.2 microsecond. The Solid State Module is a binary coded decimal to decimal diode converter which utilizes 40 diodes in matrix logic.

Burroughs Corporation's breakthrough in Built-in-Pla Components is made possible by the unique combinati of two major new techniques. First, multi-element co ponents are simultaneously fabricated within a single d vice. Second, these elements are placed in a predete mined pattern in such a manner as to facilitate compl internal connections.

This combination of techniques has resulted in BIPC Modular Devices with simple inputs and outputs whi perform functions normally requiring myriads of elemer and connectors.

Write for BIPCO Module Technical Brochure.

ANOTHER ELECTRONIC CONTRIBUTION

Burroughs Corporatio

ELECTRONIC COMPONENTS DIVISIO

PLAINFIELD, NEW JERSEY

Formerly Electronic Tube Division

POWER FROM NICAD


NICKEL CADMIUM RECHARGEABLE BATTERIES

FOR AIRCRAFT ■ MISSILES ■ CONSUMER PRODUCTS ■ ELECTRONICS ■ COMMUNICATIONS


3 TYPES HERMETICALLY SEALED CELLS



BUTTON 20-500 mAh




CYLINDRICAL
100 mAh-4.0 Ah




RECTANGULAR 1.5-2.3 Ah

2 TYPES VENTED CELLS



SINTERED PLATE
500 mAh-240 Ah
(Miniaturized
and Large
Industrial Types)

POCKET PLATE
10 Ah-2048 Ah



NICAD Batteries, in miniaturized Sealed and Vented Cells, are constantly in demand where there is a vital need for highly reliable and durable power sources. Suitable for the most stringent military requirements, these versatile cells are also adaptable to a wide variety of critical commercial, consumer and industrial applications.

Rechargeable, miniaturized, lightweight, NICAD Sealed Cells require no maintenance and operate in any position. High current discharge capabilities and extended shelf life make these cells ideal for battery-powered equipment that must operate instantly and efficiently.

NICAD sintered plate Vented Cells are designed to give exceptionally long life under cycle and float service. They can be stored in any state of charge for long periods without attention or fear of deterioration. They will operate in any position on discharge.

Pocket plate types are ideally suited for standby power and control, signal and alarm systems, emergency lighting, stationary engine cranking, cycling service, switchgear tripping and closing, locomotive starting. They seldom require maintenance, have an exceptionally long life and will maintain sustained voltage at heavy discharge rates. There's no sulphation, no corrosive fumes.

For further information on both Vented and Hermetically Sealed Cells, additional usage and application, write . . .

GOULD-NATIONAL BATTERIES, INC.

NICAD BATTERY DIVISION
GOULD-NATIONAL
BATTERIES, INC.
E-1405 1st National Bank Bldg.
St. Paul 1, Minnesota
NICAD is a trademark of Gould-National Batteries, Inc.



CONSUMER PRODUCTS
Cordless Appliances
Dictating, Recording Equipment
Shavers
Radios
Hearing Aids
Electronic Medical Aids





ELECTRONICS
Instruments
Receivers/Transmitters
Computers
Telemetering
Portable Communications Equipment



MISSILES AND ROCKETS
Control
Guidance
Telemetering



AIRCRAFT
Engine Starting
Emergency Lighting
Controls and Alarms
Rescue Gear



COMMUNICATIONS
Telephone
Telemetering
Microwave

TYPICAL USES



POWER PLANTS
Switchgear Operation
Supervisory Control
Emergency Lighting and Power
Microwave



RAILROADS
Switchgear Operation
Microwave
Engine Starting
Lanterns



INDUSTRIAL
Switchgear Operation
Emergency Lighting
Engine Starting
Flashlights and Lanterns
Cordless Power Tools




MARINE
Engine Starting
Radio and Alarms
Life Boats

NEW SILICON PLANAR 2N2049

3 db MAX. 1kc NOISE FIGURE

EXAMPLE OF LOW-NOISE AMPLIFIER DESIGN



Send for APP 11/2 and APP 36

2N2049

ELECTRICAL CHARACTERISTICS (25°C) JEDEC TO-5

	MIN.	MAX.
I_{CBO} at $V_{CB} = 60$ V, $I_E = 0$		10 mμA
h_{fe} at 1 kc, $I_C = 1.0$mA	75	
h_{ib} at 1 kc, $I_C = 1.0$mA	24	34 ohms
h_{ob} at 1 kc, $I_C = 1.0$ mA	0.1	0.5 μmhos
NF at $I_C = 100$ μA, $V_{CB} = 10$ V, f=1 kc, Rg=2K, BW=1 cps.		3.0 db
h_{FE}, d.c.pulse, IC = 100 μA, $V_{CE} = 10$V	60	

MINIMUM BETA OF 75

Guaranteed noise figure below all other devices, germanium or silicon, results from: high gain (reduces middle frequency shot noise), passivated surface (cuts low-frequency flicker), and alpha cutoff of 0.8mc @ 10μA (shifts high-frequency noise above the audio range). Extremely low leakage (typically 0.4mμA) makes possible low current operation.

PLANAR RELIABILITY, STABILITY

Performance characteristics of the 2N2049 are largely attributed to high degree of uniformity inherent in the Fairchild Planar Process. Parameter stability is assured as all junctions are protected against contamination or environmental change from the start of manufacture by an integral oxide layer.

HIGH YIELD, LOW PRICE

Low price, resulting from high Planar yields, makes it practical and economical to specify the 2N2049 for a wide variety of audio applications, and for differential amplifiers and d-c amplifiers where stability, low leakage, and low noise are prime considerations. Get complete data and pricing information from your Fairchild distributor or sales office. Or write direct.

FAIRCHILD

SEMICONDUCTOR

545 WHISMAN ROAD, MOUNTAIN VIEW, CALIF. • YORKSHIRE 8-8161 • TWX: MN VW CAL 853

A DIVISION OF FAIRCHILD CAMERA AND INSTRUMENT CORPORATION

Current IRE Statistics

(As of October 31, 1961)

Membership—92,914
Sections—111
Subsections—31
Professional Groups—28
Professional Group Chapters—288
Student Branches†—213

† See June, 1961, issue for a list.

Calendar of Coming Events and Author's Deadlines*

1961

Dec. 12–14: Eastern Joint Computer Conf., Sheraton-Park Hotel, Washington D. C.

1962

Jan. 9–11: 8th Nat'l. Symp. on Reliability and Quality Control, Statler Hilton Hotel, Washington, D. C.

Jan. 28–Feb. 2: AIEE 1962 Winter General Mtg., New York, N. Y.

Feb. 7–9: 3rd Winter Conv. on Military Electronics, Ambassador Hotel, Los Angeles, Calif.

Feb. 14–16: Internat'l. Solid State Circuits Conf., Philadelphia, Pa.

Feb. 14–16: Annual Meeting of Biophysical Society, Sheraton Park Hotel, Washington, D. C.

Feb. 19–24: Winter Inst. on Optimum and Adaptive Control Systems Theory, Univ. of Florida, Gainesville.

Mar. 1–3: 8th Scintillation and Semiconductor Counter Symp., Shoreham Hotel, Washington, D. C.

Mar. 26–29: IRE Internat'l. Conv., Coliseum and Waldorf Astoria Hotel, New York, N. Y.

Mar. 28–29: 3rd Symp. on Engrg. Aspects of Magnetohydrodynamics, Univ. of Rochester, Rochester, N. Y.

Apr. 10–12: 2nd Symp. on the Plasma Sheath, New England Mutual Hall, Boston, Mass.

Apr. 11–13: SWIRECO (S.W. IRE Conf. and Electronics Show), Rice Hotel, Houston, Tex.

Apr. 24–26: Symp. on the Mathematical Theory of Automata, United Engrg. Ctr., New York, N. Y. (DL*: Jan. 5, 1962, Symp. Committee, Polytech. Inst. Brooklyn, 55 Johnson St., Brooklyn 1, N. Y.)

May 1–3: Spring Joint Computer Conference, Fairmont Hotel, San Francisco, Calif. (DL*: Nov. 10, 1961, R. I. Tanaka, Lockheed Missiles and Space Co., Palo Alto, Calif.)

May 3–4: 1st International Congress on Human Factors in Electronics, Lafayette Hotel, Long Beach, Calif.

* DL = Deadline for submitting abstracts.

(*Continued on page 15A*)

Make Banquet Reservations Now

Because of the influx of advance reservations for the Golden Anniversary Banquet on March 28, to be held during the IRE International Convention, IRE members are urged to make their reservations at once by sending a check for $15.00 per ticket to the Institute of Radio Engineers, 1 E. 79 St., New York 21, N. Y.

Goldsmith Receives Honor from SMPTE

Dr. Alfred N. Goldsmith (M'12–F'15) Co-Founder of the IRE and Editor Emeritus of the Proceedings has been awarded honorary membership in the Society of Motion Picture and Television Engineers. The SMPTE grants this honor to those who have "performed eminent service in the advancement of engineering in motion pictures, television, or allied arts." Dr. Goldsmith is a Past President of the Society, and has been a member for 33 years.



A. N. Goldsmith


He is a graduate of the College of the City of New York and of Columbia University. He taught electrical engineering at C.C.N.Y. from 1918 to 1923 and was Vice President and general engineer of Radio Corporation of America from 1923 to 1931. Since 1933, he has served as a consulting engineer for RCA, the National Broadcasting Company and Eastman Kodak Company.

Presentation of the honorary membership was made during the 90th convention of the SMPTE. Among the many honors he has received are the IRE Medal of Honor and the Founders Award.

Microwave Tube Congress Call for Papers

The Fourth International Congress on Microwave Tubes will be held September 3–7, 1962 at the Kurhaus Hotel, Scheveningen, Netherlands. Papers are solicited on the following subjects: diodes and grid-controlled tubes; velocity-modulation tubes; traveling-wave tubes; backward-wave tubes; magnetrons and M-type amplifier tubes; parametric devices; gas discharge devices, masers, irasers and lasers; tubes of special design (undulators, Cerenkov Effect, harmonic generators, etc.); noise; electron mechanics; cavities and slow wave structures; space-charge waves; measuring techniques, and technology.

Summaries should be received before March 15, 1962 at the Congress Office typed on a special form obtainable from the Congress Office, Postbox 62, Eindhoven, Netherlands.



IRE President-Elect Patrick E. Haggerty and AIEE President Warren H. Chase exchange greetings at the AIEE Fall General Meeting in Detroit after the Board of Directors of AIEE passed a resolution, approved also by the IRE Board, calling for the formation of a joint committee to explore a consolidation of the two societies. Further details regarding the resolution are given in IRE President Berkner's letter on page 1743 of this issue.

Call for Papers

14th National Aerospace Electronic Conference (NAECON 1962)

May 14–16, 1962

Biltmore Hotel, Dayton, Ohio

The NAECON Conference is sponsored jointly by the Dayton Section of the IRE and the PG on Aerospace and Navigational Electronics. Prospective authors are requested to submit the following by *December 15, 1961:*

1) 100-word abstracts in triplicate, title of paper, name and address
2) 500-word summary in triplicate, title of paper, name and address
3) Biographical sketch of the author(s) in triplicate including education, experience, professional society membership, publications, honors.

Papers presenting original work are suggested in (but not necessarily limited to) these topic areas:

Coherent Optical Radiation Theory and Techniques
Application of Coherent Optical Radiation Devices
Cyrogenics and New Electronic Techniques
Living Systems—Ideas for Weapon Systems
Progress Report on Molecular Electronics
Radio Astronomy Techniques
Radio Astronomy, Present and Future
Communication Satellites, System Design and Potential Use
Inertial Techniques for Aerospace System Navigation and Guidance
A Survey of Earth Aerospace Radio Propagation Phenomena
Instrumentation for Astronauts
Aerospace Medical Electronics
Aerospace Communication and Telemetry
Reconnaissance, Photographic and Electronic
Millimeter Wave Technology
30–300 KMC, Status and Potential Use
New Dimensions in FM
Advances in Computer Technology
Computers as Tools in Modern Engineering Design
Biological Electronics
Systems Management
Adaptive Control Systems
Information Storage and Retrieval
Radiation Weapons
Nuclear Instrumentation for Civil Defence

Note: Only original papers which have not been presented or published prior to the 1962 National Aerospace Electronic Conference will be considered; any necessary military or company clearance must be obtained prior to submittal.

Address all material to G. A. Langston, Chairman, Papers Committee, 4725 Rean Meadow Dr., Dayton, Ohio.

Professional Group News

At its meeting on September 12, 1961, the IRE Executive Committee approved the following new Chapters: PG on **Antennas and Propagation**—Central Pennsylvania Chapter; PG on **Antennas and Propagation** and **Microwave Theory and Techniques** to be combined to form one Joint Chapter—Baltimore Chapter; Joint PG on **Antennas and Propagation** and **Microwave Theory and Techniques**—Orange County Chapter (Los Angeles Section); PG on **Antennas and Propagation** and **Microwave Theory and Techniques** to be combined to form one Joint Chapter—Syracuse Chapter; PG on **Communications Systems**—Monmouth Chapter (New York Section); PG on **Information Theory**—Baltimore Chapter; PG on **Microwave Theory and Techniques**—Florida West Coast Chapter; PG on **Radio Frequency Interference**—Joint New York, Northern New Jersey and Long Island Chapter.

On October 17, 1961, the IRE Executive Committee also approved the following new Chapters: PG on **Communication Systems**—Boston Chapter; PG on **Radio Frequency Interference**—Los Angeles Chapter.

Biophysical Society to Meet In Washington, D. C.

The annual meeting of the Biophysical Society will take place February 14–16, 1962, at the Sheraton-Park Hotel, Washington, D. C.

The program will include symposia and invited speakers in the following areas:

The Excited State and Photobiology—Chairman, Dr. A. Hollaender, Oakridge National Lab.; Dr. M. Kasha, Florida State; Dr. R. Hubbard, Harvard University; Dr. R. Clayton, Oak Ridge; Dr. M. Delbrück, California Inst. Tech.

Biological Replication—Chairman, Dr. F. Crick, Cambridge University; Dr. H. Aposhian, Stanford University; Dr. N. Zinder, Rockefeller Inst.; Dr. H. Taylor, Columbia University; and Dr. D. Mazia, University of California.

Statistics and Dynamics in Biological Systems—speakers to be announced.

There will be no pre-registration fee. For further information write Dr. Dean Cowie, Meeting Chairman, Department of Terrestrial Magnetism, Carnegie Institute of Washington, 5241 Broad Branch Rd. N.W., Washington 15, D. C.

Calendar of Coming Events and Author's Deadlines*

(*Continued from page 14A*)

May 4–5: Bay Area Symp. on Reliability and Quality Control, U. S. Naval Postgraduate School, Monterey, Calif. (DL*: Dec. 15, 1961, F. B. Durand, 553 Connemara Way, Sunnyvale, Calif.)

May 8–10: Electronic Components Conf. Marriott Twin Bridges Hotel, Washington, D. C.

May 14–16: NAECON, Dayton, Ohio.

May 22–24: Nat'l. Microwave Theory and Techniques Symp., Boulder, Colo. (DL*: Dec. 18, 1961, R. W. Beatty, Nat'l. Bur. Standards, Boulder, Colo.)

May 23–25: Nat'l. Telemetering Conf., Sheraton Park Hotel, Washington, D. C.

June 18–19: Chicago Spring Conf. on Broadcast and Television Receivers, O'Hare Inn, Chicago, Ill. (DL*: Feb. 15, 1961, A. Cotsworth, Zenith Radio Corp., 6001 W. Dickens Ave., Chicago 39, Ill.)

June 25–27: 6th Nat'l. Convention on Military Electronics, Shoreham Hotel, Washington, D. C. (DL*: Feb. 1, 1961, J. J. Slattery, The Martin Co., Baltimore 3, Md.)

June 25–30: Symp. on Electromagnetic Theory and Antennas, Tech. Univ. of Denmark, Copenhagen. (DL*: Dec. 1, 1961, H. L. Knudson, Øster Volgade 10 G, Copenhagen K, Denmark)

June 27–29: Joint Automatic Control Conf., New York Univ., New York, N. Y. (DL*: Oct. 15, 1961 (abstracts), Nov. 15, 1961 (papers), H. J. Hornfeck, Bailey Meter Co., 1050 Ivanhoe Rd., Cleveland 10, Ohio)

Aug. 14–16: Internat'l. Conf. on Precision Electromagnetic Measurements (former title: Conf. on Standards and Electronic Measurements), Nat'l. Bur. Standards, Boulder, Colo. (DL*: Mar. 15, 1962, Dr. G. Birnbaum, Hughes Res. Lab., Malibu, Calif.)

Aug. 21–24: WESCON (Western Electronics Show and Conf.), Los Angeles, Calif.

Aug. 27–Sept. 1: 2nd Internat'l. Federation of Information Processing Societies Congress, Munich, Germany.

Sept. 3–7: Internat'l. Symp. on Information Theory, Brussels, Belgium (DL*: Jan. 15, 1962, Dr. F. L. Stumpers, Philips Research Labs., Eindhoven, Netherlands)

Sept. 3–7: 4th International Congress on Microwave Tubes, Scheveningen, Netherlands (DL*: Mar. 15, 1962, Congress Office, Postbox 62, Eindhoven, Netherlands)

Sept.: 10th Annual Engineering Management Conf., New Orleans, La.

Sept. 19–20: 11th Annual Industrial Electronics Symp., Chicago, Ill.

Oct. 1–3: 8th National Communications Symp., Utica, N. Y.

Oct. 8–10: National Electronics Conf., Exposition Hall, Chicago, Ill.

* DL = Deadline for submitting abstracts.

IRE Appoints Secretary For Student Affairs

The Institute of Radio Engineers has appointed Mr. W. Reed Crone to the newly-created post of Student Affairs Secretary of the IRE. He will serve as a member of the IRE Headquarters staff in New York to coordinate and guide the IRE program of activities and services for its rapidly growing student membership.



W. R. Crone

IRE student membership, which has more than doubled in the last decade, now comprises 17,000 students in 500 schools all over the world. The total membership of the IRE, including students, is 91,000.

Mr. Crone will be concerned with the publication of the IRE Student Quarterly as well as the activities of the 212 IRE Student Branches.

Mr. Crone was born in Albert City, Iowa, on January 25, 1931. He received the B.S.E.E. degree from the University of Wisconsin in 1955. Following three years active duty in the Navy he entered Ohio State University where he received the M.S. degree in 1960. Prior to joining the IRE Headquarters staff he was associated with the Denver Research Institute, University of Denver. He is a member of Tau Beta Pi, Eta Kappa Nu, and the IRE.

Symposium on Information Theory To Be Held in Brussels

The IRE Professional Group on Information Theory will sponsor an International Symposium on Information Theory in Brussels, Belgium, September 3–7, 1962. The Symposium will be organized jointly by the Benelux Section of the IRE and the Belgian Society of Telecommunication and Electronics Engineers, with the cooperation of the Université Libre de Bruxelles.

A tentative list of subjects includes: coding and decoding of digital and analog communication, studies of random interference and of information-bearing signals, compression, analyses and design of communication and detection systems, pattern recognition, learning, adaptive filters, automata and other forms of information processing systems, processing of nervous information, human operators, nervous systems, linguistics, and the scientific method. It is hoped than all papers can be printed before the Symposium.

The following deadline schedule has been set: 500-1000 word abstracts should be received by January 15, 1962; full length papers are due April 15, 1962. Authors will be notified of acceptance by February 1, 1962. Abstracts and papers should be submitted to the Chairman of the Organizing Committee, Dr. F. L. Stumpers, Philips Research Laboratories, Eindhoven, Netherlands.

Call for Papers

6th National Convention on Military Electronics (MIL-E-CON 1962)

June 25–27, 1961

Shoreham Hotel, Washington, D. C.

The MIL-E-CON 1962 Convention is sponsored by the IRE Professional Group on Military Electronics. Ralph I. Cole, Director, Government Project Service, Westinghouse Air Brake Co., Falls Church, Va., is Convention President for MIL-E-CON 1962.

Papers presenting original work in military electronics are invited for this meeting. Suggested topics include, but are not limited to, the following:

Current Problems of Space Technology	Guidance and Control
Space Electronics	Inertial Systems
Ranging and Tracking	Reconnaissance Systems
Electronic Propulsion	Communication Systems
Data Handling Systems	Operational Analysis
Molecular Electronics and Systems	Reliability

The technical program will include both classified (confidential) and unclassified sessions, with the Air Force Systems Command sponsoring the classified sessions. An unclassified and bound *Proceedings* of the Convention will be available at the meeting.

Prospective authors are requested to furnish the following information *not later than February 1, 1962:* three copies of a 750-word, unclassified abstract of the proposed paper plus the name and address of the author(s) and name and address of his company or affiliation; three copies of a biographical sketch of the author(s), including education, experience, memberships in professional societies, honors, publications. Each author must obtain the appropriate military and company clearances for his abstract.

Send abstracts to J. J. Slattery, F316, The Martin Co., Baltimore, Md.

CURRENT IRE STANDARDS

Please order by number from IRE Headquarters, 1 E. 79 St., N. Y. 21, N. Y. A 20 per cent discount will be allowed on order for 100 or more copies mailed to one address.

Standard	*Cost*
48 IRE 2., 11., 15.S1 Standards on Antennas, Modulation Systems, and Transmitters: Definitions of Terms, 1948	$0.75
53 IRE 2.S1 Standards on Antennas and Waveguides: Definitions of Terms, 1953, Adopted by ASA. (ASA C16.21-1954.) Reprinted from the December, 1953, Proceedings	$0.75
55 IRE 2.S1 Standards on Antennas and Waveguides: Definitions for Waveguide Components, 1955. Reprinted from the September, 1955, Proceedings	$0.25
59 IRE 2.S1 Standards on Antennas and Waveguides: Waveguide and Component Measurements, 1959. Reprinted from the April, 1959, Proceedings	$0.75
48 IRE 2.S2 Standards on Antennas: Methods of Testing, 1948. Adopted by ASA. (ASA C16.11-1949.)	$0.75
54 IRE 3.S1 Standards on Audio Techniques: Definitions of Terms, 1954. Reprinted from the July, 1954, Proceedings	$0.50
56 IRE 3.S1 Standards on Audio Systems and Components: Methods of Measurement of Gain, Amplification, Loss, Attenuation, and Amplitude-Frequency-Response, 1956 Adopted by ASA. (ASA C16.29-1957.) Reprinted from the May, 1956, Proceedings	$0.80
58 IRE 3.S1 Standards on Audio Techniques: Definitions of Terms, 1958 Reprinted from the December, 1958, Proceedings	$0.60
53 IRE 3.S2 Standards on American Recommended Practice for Volume Measurements of Electrical Speech and Program Waves, 1953. Adopted by ASA. (ASA C16.5-1954.) Reprinted from the May, 1954, Proceedings	$0.50
50 IRE 4.S1 Standards on Circuits: Definitions of Terms in Network Topology, 1950 Reprinted from the January, 1951, Proceedings	$0.50
53 IRE 4.S1 Standards on Circuits: Definitions of Terms in the Field of Linear Varying Parameter and Nonlinear Circuits, 1953. Reprinted from the March, 1954, Proceedings	$0.25
60 IRE 4.S1 Standards on Circuits: Definitions of Terms for Linear Signal Flow Graphs, 1960. Reprinted from the September, 1960, Proceedings	$0.25
60 IRE 4.S2 Standards on Circuits: Definitions of Terms for Linear Passive Reciprocal Time Invariant Networks, 1960. Reprinted from the September, 1960, Proceedings	$0.50
51 IRE 6.S1 Standards on Electroacoustics: Definitions of Terms, 1951. Reprinted from the May, 1951, Proceedings	$1.00

when airborne radar requires the very best:

BOMAC K_u BAND MAGNETRONS

Designers of radar equipment will find Bomac Laboratories' new BLM-071 K_u-band pulse magnetron meets exacting requirements for airborne systems: lightweight, rugged, powerful. This newest contribution from Bomac is a fixed-frequency tube (15.9-16.1 kMc) rated at 100 kW peak, at 0.001 duty cycle.

Cathode structure is greatly improved over similar magnetrons. Operable at high ambient temperatures, with input/output terminals permitting pressurization to 30 psia. Special construction minimizes leakage current. High power output and low operating voltage are combined in a compact, ruggedized unit. Long life. Weight: less than 8½ lbs.

The many advantages to Bomac's BLM-071 magnetron make it readily adaptable to navigation, high-altitude mapping, airport surveillance, and similar applications. Write for full technical details.



FEATURES: Frequency 15.9-16.1 kMc.
Peak Power 100 kW.
Normal efficiency 30%.
Duty cycle 0.001 Max.
Pulse width 0.06 to 1.2 usec.

BOMAC laboratories, inc.
BEVERLY 2, MASSACHUSETTS
A Varian Subsidiary

Other Subsidiaries of Varian Associates:
S-F-D LABORATORIES, INC.
VARIAN ASSOCIATES OF CANADA, LTD.
SEMICON ASSOCIATES, INC.
SEMICON OF CALIFORNIA, INC.
VARIAN A.G. (SWITZERLAND)

P.I.B. Symposium
Call for Papers

The Twelfth Annual International Polytechnic Symposium will be held in the new United Engineering Center, facing the United Nations Plaza, New York City, on April 24–26, 1962. It will be devoted to "The Mathematical Theory of Automata" and will emphasize the application of mathematical techniques to information-handling systems. Proposed topics to be included are as follows:

1) Computability, classes of Turing machines and automata, unsolvable problems, problem complexity.

2) Symbolic logic, methods of programming logical problems, theorem proving, algorithms for quantification theory.

3) Procedures for search and learning, search in discontinuous and discrete systems, random vs systematic methods, convergence and random walk, Pandemonium and Perceptrons.

4) Abstract algebra and linear graphs; applications of lattice theory, semigroups, rings, etc., to coding languages, and sequential transducers; application of linear graphs to route problems, state diagrams, etc.

5) Synthesis procedures, design with "neurons" or other specific types of element, reliability.

The Symposium's objectives are 1) to encourage the development and exposition of basic theories and mathematical tools which will be of help to the engineer in analyzing, designing, and using information-handling systems, and 2) to provide a forum for the exchange of ideas among applied mathematicians, computer engineers and those interested in information theory in the hope of stimulating further development of those branches of mathematics which might be used in a theory of digital devices. The program will contain both invited and contributed papers as well as a round-table discussion of future trends. The Proceedings will be published as Volume XII of the Polytechnic Symposia Series.

This year, the Symposium is organized by the Departments of Electrical Engineering and Electrophysics in cooperation with the IRE Professional Groups on Electronic Computers and Information Theory and the Science and Electronics Division of the AIEE. It is co-sponsored by the Air Force Office of Scientific Research, the Office of Naval Research, and the U. S. Army Signal Corps.

The closing date for submission of contributed papers or 200-word abstracts is January 5, 1962. Further information may be obtained from Professors A. E. Laemmel and E. J. Smith, Co-Chairmen of the Symposium Committee, Polytechnic Institute of Brooklyn, 55 Johnson St., Brooklyn 1, N. Y

IRE Establishes New Section

At its meeting on October 17, 1961, the IRE Executive Committee approved establishment of a new IRE Section, to be known as the France Section and to encompass the entire country of France in Europe.

CURRENT IRE STANDARDS

Please order by number from IRE Headquarters, 1 E. 79 St., N. Y. 21, N. Y. A 20 per cent discount will be allowed on order for 100 or more copies mailed to one address.

Standard	*Cost*
54 IRE 7.S1 Standards on Electron Devices: Definitions of Terms Related to Phototubes, 1954. Reprinted from the August, 1954, PROCEEDINGS	$0.25
56 IRE 7.S1 Standards on Electron Devices: Definitions of Terms, Related to Microwave Tubes (Klystrons, Magnetrons, and Traveling Wave Tubes), 1956. Reprinted from the March, 1956, PROCEEDINGS	$0.50
57 IRE 7.S1 Standards on Electron Tubes: Physical Electronics Definitions, 1957. Reprinted from the January, 1957, PROCEEDINGS	$0.50
50 IRE 7.S2 Standards on Electron Tubes: Methods of Testing, 1950. Part I Reprinted from August, 1950, PROCEEDINGS: Part II Reprinted from September, 1950, PROCEEDINGS	$1.25
52 IRE 7.S2 Standards on Gas-Filled Radiation Counter Tubes: Methods of Testing, 1952. Adopted by ASA. (ASA C60.11-1954.) Reprinted from the August, 1952, PROCEEDINGS	$0.75
56 IRE 7.S2 Standards on Electron Devices: Definitions of Terms Related to Storage Tubes, 1956. Reprinted from the April, 1956, PROCEEDINGS	$0.25
57 IRE 7.S2 Standards on Electron Tubes: Definitions of Terms, 1957. Reprinted from the July, 1957, PROCEEDINGS	$1.00
52 IRE 7.S3 Standards on Gas-Filled Radiation Counter Tubes: Definitions of Terms, 1952. Reprinted from the August, 1952, PROCEEDINGS	$0.50
56 IRE 7.S3 Standards on Electron Tubes: TR and ATR Tube Definitions, 1956. Reprinted from the August, 1956, PROCEEDINGS	$0.50
56. IRE 8.S1 Standards on Electronic Computers: Definitions of Terms, 1956. Reprinted from the September, 1956, PROCEEDINGS	$0.60
59 IRE 8.S1 Standards on Static Magnetic Storage: Definition of Terms, 1959. Reprinted from the March, 1959, PROCEEDINGS	$0.50
43 IRE 9.S1 Standards on Facsimile: Temporary Test Standards, 1943	$0.20
56 IRE 9.S1 Standards on Facsimile: Definitions of Terms, 1956. Adopted by ASA. (ASA C16.30-1957.) Reprinted from the June, 1956, PROCEEDINGS	$0.60
55 IRE 10.S1 Standards on Industrial Electronics: Definitions of Industrial Electronics Terms, 1955. Reprinted from the September, 1955, PROCEEDINGS	$0.50
53 IRE 11.S1 Standards on Modulation Systems: Definitions of Terms, 1953. Reprinted from the May, 1953, PROCEEDINGS	$0.50
58 IRE 11.S1 Standards on Information Theory: Definitions of Terms, 1958. Reprinted from the September, 1958, PROCEEDINGS	$0.50
54 IRE 12.S1 Standards on Radio Aids to Navigation: Definitions of Terms, 1954. Adopted by ASA. (ASA C16.26-1955) Reprinted from the Feburary, 1955, PROCEEDINGS	$1.00
59 IRE 12.S1 Standards on Navigation Aids: Direction Finder Measurement, 1959. Reprinted from the August, 1959, PROCEEDINGS	$1.00
60 IRE 13.S1 Standards on Nuclear Techniques: Definitions for the Scintillation Counter Field, 1960. Reprinted from the August, 1960, PROCEEDINGS	$0.60
49 IRE 14.S1 Standards on Piezoelectric Crystals, 1949, Adopted by ASA. (ASA C83.3-1951, R 1954.) Reprinted from the December, 1949, PROCEEDINGS	$0.80
57 IRE 14.S1 Standards on Piezoelectric Crystals—The Piezoelectric Vibrator: Definitions and Methods of Measurement, 1957. Reprinted from the March, 1957, PROCEEDINGS	$0.60
58 IRE 14.S1 Standards on Piezoelectric Crystals: Determination of the Elastic, Piezoelectric and Dielectric Constants—The Electromechanical Coupling Factor, 1948. Reprinted from the April, 1958, PROCEEDINGS	$0.75
61 IRE 14.S1 Standards on Piezoelectric Crystals: Measurements of Piezoelectric Ceramics, 1961. Reprinted from the July, 1961, PROCEEDINGS	$0.70
55 IRE 15.S1 Standards on Pulses: Methods of Measurements of Pulse Quantities, 1955. Adopted by ASA. (ASA C16.28-1956.) Reprinted from the November, 1955, PROCEEDINGS	$0.60
61 IRE 15.S1 Standards on Radio Transmitters: Definitions of Terms, 1961. Reprinted from the February, 1961, PROCEEDINGS	$0.25
58 IRE 15. TRI IRE Technical Committee Report: Methods for Testing Radiotelegraph Transmitters (Below 50 MC), Reprinted from the January, 1959, PROCEEDINGS	$0.60
49 IRE 16.S1 Standards on Railroad and Vehicular Communications: Methods of Testing, 1949. Reprinted from the December, 1949, PROCEEDINGS	$0.50
47 IRE 17.S1 Standards on Radio Receivers: Methods of Testing Frequency-Modulation Broadcast Receivers, 1947. Adopted by ASA. (ASA C16.12-1949.)	$0.50
48 IRE 17.S1 Standards on Radio Receivers: Methods of Testing Amplitude-Modulation Broadcast Receivers, 1948	$1.00
49 IRE 17.S1 Tests for Effects of Mistuning and for Downward Modulation. 1949 Supplement to 47 IRE 17.S1. Reprinted from the December, 1949, PROCEEDINGS	$0.25
51 IRE 17.S1 Standards on Radio Receivers: Open Field Method of Measurement of Spurious Radiation from Frequency Modulation and Television Broadcast Receivers, 1951. Reprinted from the July, 1951, PROCEEDINGS	$0.50
52 IRE 17.S1 Standards on Receivers: Definitions of Terms, 1952. Reprinted from the December, 1952, PROCEEDINGS	$0.60

COMPUTERS AND OTHER ELECTRONIC INSTRUMENTS demand resistors which give predictable performance in a small space and high ambient temperatures. This is a good description of Corning tin oxide film resistors, which are now competitive in price with other makes.

Tin oxide and glass are among the most stable materials. They are also low in cost.


Couple these materials with exacting methods of manufacture, as we have done, and you have low-cost resistors meeting the pinching specifications required for computers and similar devices.

You have resistors with excellent reactive properties. With a shelf life of 0.1 to 0.2% per year. With noise levels lower than 0.1 microvolt per volt. And with typical values like these:



TYPE	DESCRIPTION	CORNING MODEL	WATTAGE	RESISTANCE (ohms)	TC	LOAD LIFE	OVERLOAD	MOISTURE RESISTANCE
NF	Glass ENCAPSULATED MIL-R-10509C, Char. B	NF60 NF65	⅛ ¼	100 100K 100 348K	150ppm/°C. −55 +150°C.	0.3%	0.03%	0.2% (Char. B)
N EPOXY	MIL-R-10509C, Char. B	N60 N65 N70	⅛ ¼ ½	10 133K 10 499K 10 1Meg	150ppm/°C. −55 +105°C.	0.5%	0.03%	0.5% (Char. B.)
N	MIL-R-10509B, Char. X	N12 N20 N25 N30	¼ ½ 1 2	100 133K 10 500K 10 1.5Meg 30 4.12Meg	150ppm/°C. −55 +105°C.	0.35%	0.1%	0.15% (Char. X)
C	Lowest cost film resistor; silicone insulation MIL-R-11C	C20 C32 C42	½ 1 2	51 150K 51 470K 10 1.4Meg	150ppm/°C. −55 +125°C.	1.5%	0.2%	0.3%

Note: Noise level for all models is less than 0.1 uv/v of applied signal.



For quantities of less than 1000, contact the nearest Corning distributor. For data sheets on Corning Type NF, N, N-EPOXY or C resistors, write CORNING GLASS WORKS, 542 High St., Bradford, Pa.

CORNING ELECTRONIC COMPONENTS
CORNING GLASS WORKS, BRADFORD, PA.

Call for Papers For Symposium on Magnetohydrodynamics

The Third Symposium on Engineering Aspects of Magnetohydrodynamics is to be held at the University of Rochester, Rochester, N. Y. on March 28 and 29, 1962. This meeting is being sponsored by AIEE, IAS, IRE and the University of Rochester. It is planned that the program shall be concerned with plasmas in the presence of a magnetic field and, in particular, with their engineering aspects.

The primary purpose of the meeting is to exchange information among related disciplines on the assumption that the participants will have some degree of competence in one or more broad areas. It is hoped that the meeting will be small enough that extensive discussion may be permitted. Each session will have both invited and contributed papers. Authors of papers will assume audience familiarity with the field and concentrate on what is original and novel in their particular contribution.

Four non-concurrent sessions are planned covering 1) Communications and Diagnostics, 2) Flight Applications, 3) Fusion and 4) Power Conversion. It is intended that the Communications and Diagnostics Session deal with the transmission and receiving of information or energy from plasmas under various conditions; that the Flight Applications Session deal with the propulsion or control of aerodynamic or space vehicles by MHD interaction between the vehicle and its environment; that the Fusion Session deal with the extraction of energy through controlled thermonuclear fusion of light nuclei; that the Power Conversion Session deal with the direct extraction of electrical energy from hot flowing plasmas or conducting liquids. Papers are desired for each of these sessions. Abstracts should be submitted to the appropriate session chairman, as listed below.

The committee strongly recommends that authors submit reproducible copies of their papers by February 1, 1962. These will be reproduced for distribution at the meeting. Abstracts are due December 1, 1961.

In addition, the committee is making arrangements to publish the proceedings either as a separate volume or as part of a technical journal. This will provide a permanent record of the symposium. The committee urges all authors to submit their papers for the proceedings.

The sessions, as planned, are tentative and may, if it later seems desirable, be changed to better describe the subject-matter of the sessions. The members of the Program Committee, who are in charge of the programs in the various sessions, and who will be chairmen of the various sessions, are given below. Abstracts and papers should be submitted directly to them.

Communications and Diagnostics: Prof. S. C. Brown, Physics Dept., Massachusetts Institute of Technology, Cambridge 39.

Flight Applications: Dr. Harry Harrison, Space Propulsion, NASA, 1520 "H" Street N.W., Washington 25, D.C.

Fusion: Dr. R. F. Post, Lawrence Radiation Lab., Livermore, Calif.

Power Conversion: Dr. Stewart Way, Westinghouse Research Lab., East Pittsburgh, Pa.

CURRENT IRE STANDARDS

Please order by number from IRE Headquarters, 1 E. 79 St., N. Y. 21, N. Y. A 20 per cent discount will be allowed on order for 100 or more copies mailed to one address.

Standard	*Cost*
54 IRE 17.S1 Standards on Receivers: Methods of Measurement of Interference Output of Television Receivers in the Range of 300 to 10,000 KC, 1954. Adopted by ASA. (ASA C16.25-1955.)	
Reprinted from the September, 1954, PROCEEDINGS	$0.60
55 IRE 17.S1 Standards on Radio Receivers: Method of Testing Receivers Employing Ferrite Core Loop Antennas, 1955.	
Reprinted from the September, 1955, PROCEEDINGS	$0.50
60 IRE 17.S1 Standards on Television: Methods of Testing Monochrome Television Broadcast Receivers, 1960.	
Reprinted from the June, 1960, PROCEEDINGS	$1.00
53 IRE 19.S1 Standards on Sound Recording and Reproducing: Methods of Measurement of Noise, 1953.	
Reprinted from the April, 1953, PROCEEDINGS	$0.50
58 IRE 19.S1 Standards on Recording and Reproducing: Methods of Calibration of Mechanically-Recorded Lateral Frequency Records, 1958. Adopted by ASA. (ASA S4.1-1960.)	
Reprinted from the December, 1958, PROCEEDINGS	$0.60
53 IRE 19.S2 Standards on Sound Recording and Reproducing: Methods for Determining Flutter Content, 1953. Adopted by ASA. (ASA Z57.1-1954.)	
Reprinted from the March, 1954, PROCEEDINGS	$0.75
51 IRE 20.S1 Standards on Pulses: Definitions of Terms—Part I, 1951.	
Reprinted from the June, 1951, PROCEEDINGS	$0.50
52 IRE 20.S1 Standards on Pulses: Definitions of Terms—Part II, 1952.	
Reprinted from the May, 1952, PROCEEDINGS	$0.50
58 IRE 20.S1 Index to IRE Standards on Definitions of Terms, 1942–1957.	
Reprinted from the February, 1958, PROCEEDINGS	$1.00
59 IRE 20.S1 Standards on Methods of Measuring Noise in Linear Twoports, 1959.	
Reprinted from the January, 1960, PROCEEDINGS	$0.75
51 IRE 20.S2 Standards on Transducers: Definitions of Terms, 1951.	
Reprinted from the August, 1951, PROCEEDINGS	$0.50
51 IRE 21.S1 Standards on Abbreviations of Radio-Electronic Terms, 1951.	
Reprinted from the April, 1951, PROCEEDINGS	$0.50
54 IRE 21.S1 Standards on Graphical Symbols for Electrical Diagrams, 1954.	
Reprinted from the June, 1954, PROCEEDINGS	$1.25
54 IRE 21.S1 Supplement to IRE Standards on Graphical Symbols for Electrical Diagrams, 1954.	
Reprinted from the February, 1961, PROCEEDINGS	$0.25
57 IRE 21.S1 Standards on Letter Symbols and Mathemstical Signs, 1948. (Reprinted 1957.)	
Reprinted from the August, 1957, PROCEEDINGS	$0.60
57 IRE 21.S2 Standards on Reference Designations for Electrical and Electronic Equipment, 1957.	
Reprinted from the November, 1957, PROCEEDINGS	$0.70
57 IRE 21.S3 Standards on Graphical Symbols for Semiconductor Devices, 1957	
Reprinted from the December, 1957, PROCEEDINGS	$0.60
48 IRE 22.S1 Standards on Television: Methods of Testing Television Receivers, 1948. Adopted by ASA. (ASA C16.13-1949.)	$1.00
55 IRE 22.S1 Standards on Television: Definitions of Color Terms, 1955.	
Reprinted from the June, 1955, PROCEEDINGS	$0.60
50 IRE 23.S1 Standards on Television: Methods of Measurement of Television Signal Levels, Resolution, and Timing of Video Switching Systems, 1950.	
Reprinted from the May, 1950, PROCEEDINGS	$0.70
54 IRE 23.S1 Standards on Television: Methods of Measurement of Aspect Ratio and Geometric Distortion, 1954. Adopted by ASA. (ASA C16.23-1954.)	
Reprinted from the July, 1954, PROCEEDINGS	$0.60
55 IRE 23.S1 Standards on Television: Definitions of Television Signal Measurement Terms, 1955.	
Reprinted from the May, 1955, PROCEEDINGS	$1.00
58 IRE 23.S1 Standards on Television: Measurement of Luminance Signal Levels, 1958. Adopted by ASA. (ASA C16.31-1959.)	
Reprinted from the February, 1958, PROCEEDINGS	$0.60
60 IRE 23.S1 Standards on Television: Measurement of Differential Gain and Differential Phase, 1960.	
Reprinted from the February, 1960, PROCEEDINGS	$0.60
61 IRE 23.S1 Standards on Video Techniques: Definitions of Terms Relating to Television, 1961.	
Reprinted from the July, 1961, PROCEEDINGS	$0.50
50 IRE 23.S2 Standards on Television: Methods of Measurement of Time of Rise, Pulse Width, and Pulse Timing of Video Pulses in Television, 1950.	
Reprinted from the November, 1950, PROCEEDINGS	$0.75
60 IRE 23.S2 Standards on Video Techniques: Measurement of Resolution of Camera Systems, 1961.	
Reprinted from the March, 1961, PROCEEDINGS	$0.50
50 IRE 23.S3 Standards on Television: Methods of Measurement of Electronically Regulated Power Supplies, 1950.	
Reprinted from the January, 1951, PROCEEDINGS	$0.75
45 IRE 24.S1 Standards on Radio Wave Propagation: Definitions of Terms Relating to Guided Waves, 1945	$0.20
50 IRE 24.S1 Standards on Wave Propagation: Definitions of Terms, 1950.	
Reprinted from the November, 1950, PROCEEDINGS	$0.60
55 IRE 26.S1 Standards on Graphical and Letter Symbols for Feedback Control Systems, 1955.	

Electronic Giants no bigger than your thumbnail... now through electron-beam welding

High-energy density electron-beam welding techniques, recently developed by the Zeiss Foundation of West Germany and the Hamilton-Standard Division of United Aircraft, markedly improved packaging density and production methods in the field of microelectronics.

In microcircuitry, for example, packaged circuits no bigger than a thumbnail can now be reliably produced. Electron-beam equipment now welds microelectronic components into circuits with pinpoint precision, making intra- and inter-circuit connection, and hermetically encapsulating the completed micromodule.


Only electron-beam welding, performed in a high vacuum, can offer these significant advantages for the field of microelectronics: virtual elimination of contamination; a close control of penetration; low thermal distortion; and close dimensional control. The upper illustration shows weldments of 0.002″ thick copper leads to 0.002″ thick nickel-plated ceramic substrate. In the field of thin films difficult welds are possible with this revolutionary new equipment such as 0.002″ gold tabs to chromium-gold films 3000-A° thick.

Another important use of electron-beam equipment is the welding of ceramics used in vacuum tubes which require extremely high temperature performance. For these procedures, tight ceramic-to-ceramic bonds are necessary — bonds available only through high-energy density electron-beam welding. The lower illustration is a 2 X magnification of two aluminum oxide ceramic wafers ½″ x ¾″ x .010″ thick edge-welded by deflecting the high energy density beam of a Hamilton-Zeiss electron beam welder across the edge surface.

Hamilton-Standard, with over twenty years of metallurgical experience and meeting rigid government specifications, has exhaustively tested the welds produced with Hamilton-Zeiss equipment. The data, which are available for your inspection, demonstrate conclusively that the Hamilton-Zeiss method produces welds in miniature workpieces that are as strong as the original materials themselves. Such results are possible only by the use of high energy density and precision focusing by the Zeiss magnetic lens system which are exclusive features of the Hamilton-Zeiss equipment. Find out what this revolutionary equipment can mean in your business. For full information call Hamilton-Electrona, Inc., exclusive marketing agent for Hamilton-Zeiss equipment in the United States and Canada.

HAMILTON-ELECTRONA, INC.

TIME-LIFE BUILDING, ROCKEFELLER CENTER, NEW YORK 20, N.Y.



Graduate Institute on Optimum and Adaptive Control System Theory

A Graduate Institute on Optimum and Adaptive Control System Theory will be held at the University of Florida, Gainesville, on February 19–24, 1962. It is sponsored by the Engineering and Industrial Experiment Station of the College of Engineering, University of Florida.

In realization of the fact that new concepts of adaptive and optimum control have profoundly changed the field of automatic control and that the majority of professional personnel in the control field have never taken any formal courses in this area, the University of Florida has considered it a worthwhile contribution to offer this Institute, the main purpose of which is tutorial. The invited lecturers for the Institute are as follows: Prof. J. E. Gibson, Purdue University; Prof. M. D. Mesarović, Case Institute of Technology; Prof. H. P. Whitaker, Massachusetts Institute of Technology; Dr. T. J. Williams, Monsanto Chemical Company; Prof. J. Zaborszky, Washington University, and Prof. O. I. Elgerd, University of Florida.

The schedule of meetings is as follows:

Monday, February 19

Registration, Welcome, Introduction by Dr. Elgerd.

"Mathematics of Optimum and Adaptive Control," *Dr. Elgerd.*

"Performance Criteria," *Dr. Zaborszky.*

Tuesday, February 20

Demonstration of Optimum Search by Means of Computer, *Joint effort by Univ. of Florida Simulation Laboratory and Computer System Inc., using a dynamic storage analog computer, DYSTAC.*

"Mathematics of Optimum and Adaptive Control (continued)," *Dr. Algerd.*

"Fundamental Aspects of Multivariable Systems, and Their Optimum Control," *Dr. Mesarović.*

Wednesday, February 21

"Multivariable Systems (continued)," *Dr. Mesarović.*

"Mathematics of Optimum and Adaptive Control (continued)," *Dr. Elgerd.*

"Philosophy and Theory of Adaptive Control," *Dr. Gibson.*

Thursday, February 22

"Adaptive Control Theory (continued)," *Dr. Gibson.*

"Mathematics of Optimum and Adaptive Control (continued)," *Dr. Elgerd.*

"Model Reference Adaptive Control Systems," *Dr. Whitaker.*

Friday, February 23

"Model Reference Adaptive Systems (continued)," *Dr. Whitaker.*

"Mathematics of Optimum and Adaptive Control (continued)," *Dr. Elgerd.*

"Adaptive and Optimum Principles Applied to Process Control," *Dr. Williams.*

Saturday, February 24

"Process Control Applications (continued)," *Dr. Williams.*

"Mathematics of Optimum and Adaptive Control (continued)," *Dr. Elgerd.*

CURRENT IRE STANDARDS

Please order by number from IRE Headquarters, 1 E. 79 St., N. Y. 21, N. Y. A 20 per cent discount will be allowed on order for 100 or more copies mailed to one address.

	Standard	*Cost*
	Reprinted from the November, 1955, PROCEEDINGS	$0.25
55	**IRE 26.S2 Standards on Terminology for Feedback Control Systems, 1955.**	
	Reprinted from the January, 1956, PROCEEDINGS	$0.50
56	**IRE 27.S1 Standards on Methods of Measurement of the Conducted Interference Output of Broadcasts and Television Receivers in the Range of 300 KC to 25 MC, 1956. Adopted by ASA. (ASA C16.25a-1957.)**	
	Reprinted from the August, 1956, PROCEEDINGS	$0.50
58	**IRE 27.S1 Supplement to "IRE Standards on Receivers: Methods of Measurement of Interference Output of Television Receivers in the Range of 300 to 10,000 KC 1954" (Standard 54 IRE 17.S1). Adopted by ASA. (ASA C16.25b-1959.)**	
	Reprinted from the July, 1958, PROCEEDINGS	$0.50
61	**IRE 27.S1 Standards on Radio Interference: Methods of Measurement of Conducted Interference Output to the Power Line from RM and Television Broadcast Receivers in the Range of 300 KC to 25 MC, 1961.**	
	Reprinted from the September, 1961, PROCEEDINGS	$0.60
56	**IRE 28.S1 Standards on Letter Symbols for Semiconductor Devices, 1956.**	
	Reprinted from the July, 1956, PROCEEDINGS	$0.50
58	**IRE 28.S1 Standards on Solid-State Devices: Methods of Testing Point-Contact Transistors for Large-Signal Applications, 1958.**	
	Reprinted from the May, 1958, PROCEEDINGS	$0.70
60	**IRE 28.S1 Standards on Solid-State Devices: Definitions of Semiconductor Terms, 1960.**	
	Reprinted from the October, 1960, PROCEEDINGS	$0.50
61	**IRE 28.S1 Standards on Solid-State Devices: Definitions of Terms for Nonlinear Capacitors, 1961.**	
	Reprinted from the August, 1961, PROCEEDINGS	$0.25
56	**IRE 28.S2 Standards on Solid-State Devices: Methods of Testing Transistors, 1956.**	
	Reprinted from the November, 1956, PROCEEDINGS	$0.80
60	**IRE 28.S2 Standards on Electrostatographic Devices, 1961.**	
	Reprinted from the March, 1961, PROCEEDINGS	$0.50
61	**IRE 28.S2 Standards on Solid-State Devices: Measurement of Minority-Carrier Lifetime in Germanium and Silicon by Method of Photoconductive Decay.**	
	Reprinted from the August, 1961, PROCEEDINGS	$0.60
61	**IRE 30.RP1 IRE Recommended Practices on Audio and Electroacoustics: Loud Speaker Measurements.**	
	Reprinted from the October, 1961, PROCEEDINGS	$0.60

Registration for Copenhagen Symposium

Registration procedure for the Symposium on Electromagnetic Theory and Antennas to be held at the Technical University of Denmark, Copenhagen, June 25–30, 1962 has been announced. The Symposium is sponsored by the International Scientific Radio Union (URSI), the Technical University of Denmark, the Danish Academy of Technical Sciences, and the Danish National Committee of URSI. The Symposium is open to any interested person from any country.

Registrations will be accepted until the last day of the Symposium; however, due to the limitations of hotel space, the Committee can undertake to make reservations only for those who have registered and paid the fee before March 1, 1962. Reservations will be made as close as possible to indicated wishes. Delegates who have registered before this date will also receive, by mail, summaries of the accepted papers. The registration fee is 100 D. cr. A check for this amount should be enclosed with the completed registration form and made payable to "Symposium on Electromagnetic Theory and Antennas," The Technical University of Denmark, Øster Voldgade 10 G, Copenhagen K, Denmark. Registration and hotel reservation forms may be obtained from the Secretary of the Symposium, Prof. H. L. Knudsen at the above address. Registrants will receive the Symposium proceedings free of charge.

Social events and a ladies' program have also been planned including a tour of North Zealand (price: 50 D. cr.), a banquet at the Restaurant Nimb in Tivoli (price: 60 D. cr.) and other activities.

Air Force MARS Announces Schedule

The schedule of broadcasts of the Air Force MARS Eastern Technical Net, operating Sundays from 2 to 4 P.M. EST at 3295, 7540 and 15,715 kc, has been announced as follows:

December 3—To be announced. Dr. A. Rubinoff, Professor of Electrical Engineering, Moore School, University of Pennsylvania.

December 10—"Low Level Illumination," Dr. M. Chwalow, Scientist, Frankford Arsenal, U. S. Army.


December 17—"The Voltage-Tunable Magnetron for Microwave Applications," R. I. Reed and G. A. Krug, Power Tube Dept., General Electric Co.

December 24—No broadcast.

December 31—No broadcast.

January 7—"New Electron Tubes for the Modern Era," Dr. J. E. Beggs, Research Associate, General Electric Research Lab.

January 14—"Thermionic Integrated Micro-Module Circuits for High Temperature Environments," A. P. Haase, Manager, Advanced Development Engineering, General Electric Co.



TEN WATTS PNP

2N1658 2N1659

Looking for a compact 1 to 10 watt Germanium Power Transistor with this kind of top level performance?



ACTUAL SIZE

Top reliability is built into each Honeywell transistor. Vacuum baked, given rigorous life and dynamic tests, each is enclosed in a new cold-welded miniature case with threaded mounting stud.

Designed for general use, the Honeywell 2N1658 and 2N1659 are ideal for servo amplifiers, relay drivers, high power unit driver stages, and as medium power switches. Measuring only 0.35 inches in diameter, they handle one to ten watts!

You'll want data sheets, including characteristic curves and servo amplifier circuit diagram, for your files. Fill out and mail the coupon today!

- *Leakage*—I_{CBO} less than 0.5 ma at 80v, 2N1658—60v, 2N1659
- *Saturation voltage*—$V_{CE\ (SAT)}$ less than 0.25v
- *Floating potential*—V_{EBF} less than 0.25v
- *Thermal resistance*—$\Theta_{J\text{-}MB}$ 5° C/watt max. (T_J max., 100° C)
- *Gain*—h_{FE} 30 min @ 0.2 amp; h_{FE} 20 min @ 1.0 amp
- *Frequency response*—500 kc minimum gain bandwidth product
- *Power dissipation*—15 watts at 25° C, 6 watts at 70° C

(13)

MINNEAPOLIS-HONEYWELL REGULATOR CO.
SEMICONDUCTOR DIV. • MINNEAPOLIS 8, MINN.

Yes, send me bulletins on the new Honeywell 2N1658 and 2N1659.

NAME_____

FIRM_____

ADDRESS_____

CITY_____ ZONE_____

STATE_____ PHONE_____

Honeywell

H HONEYWELL Semiconductor Products

Obituary

The IRE was notified on September 27, 1961 of the death of **Robert R. Gamzon** (M'61), Chairman of the Israel Section. He was born in France on June 30, 1905 and was educated there, studying at the Sorbonne in Paris from which he received the Certificate in general mathematics in 1924 and at the Ecole Superieure d'Electricité, Paris, in 1924–1925. He worked for several French firms including the Ste. SECIM of Paris from 1930 to 1933; the Ets. Bernard Roux, Paris, from 1933 to 1938 where he did research on the recording and printing of records; and from 1938 to 1941, the Ste. Thomson-Houston, Paris, working in the Laboratory of Audio-Research and Transmitters. From 1940 until 1953 he worked with Jewish youth in France during the Nazi persecution and after the war. He joined Amron-Herzlia in Israel in 1953 as Chief Engineer where he stayed until 1957. Since 1958 he had been associated with the Weizmann Institute of Science, Rehovoth, Israel, where he was Senior Research Engineer.

He contributed widely to the establishment of the young radio industry of Israel, particularly in setting up standards and production techniques for radio components, thus helping to make the industry self reliant to a considerable degree.

Mr. Gamzon was a member of the Acoustical Society of America and the Groupement des Acousticiens de la Langue Française. He had been awarded several patents in the field of electroacoustics.



Presentation of the Scott Helt Award of PGB by Raymond Guy, Chairman, to James H. Greenwood a the PGB Annual Fall Meeting, October 6–7, 1961 in Washington, D. C.; Mrs. Greenwood is at lower right.

Eighth National Symposium on Reliability and Quality Control

Statler Hilton Hotel, Washington, D. C., January 9–11, 1962

Tuesday, January 9

Session 1—Keynote Address

"A Management Appraisal of the Reliability Challenge," *C. F. Horne, President, General Dynamics.*

Session 2A—Statistical Techniques

Moderator: *Dr. M. Sobel, University of Minnesota.*

"Statistical Independence in Reliability Equations," *A. M. Breipohl, Sandia Corp.*

"Truncation of Sequential Life Tests," *T. L. Burnett, IBM Corp.*

"Confidence Limits for System Reliability from Component Tests," *Dr. W. S. Connor, Research Triangle Inst.*

Session 2B—Program Management

Moderator: *R. H. DeWitt, Office of Electronics, ODDR&E.*

"Reliability Program Requirements for Aerospace Systems and Subsystems," *Maj. V. J. Bracha, U.S.A.F.*

"PERT-Pep Controls for Reliability and Costs," *Dr. H. A. Romig, Operations Research, Inc.*

"Management of Equipment Reliability Activities and USASRDL," *T. J. Edwards, U. S. Army Signal Research and Development Lab.*

Session 3A—Statistical Techniques

Moderator: *W. R. Allen, Consultant*

"Life and Reliability Testing Based on the Weibull Distribution," *Prof. H. P. Goode, Cornell University.*

"Screening for Critical Variables Affecting Reliability," *Dr. C. H. Li, General Instrument Corp.*

"Factorial Experiments in Reliability Analysis," *C. L. Barron, Honeywell.*

"Statistical Methods as Design Tools, *E. F. Grey, U.S.A.F.*

Session 3B—Quality Control Techniques

Moderator: *L. J. Jacobson, International Resistance Co.*

"Process Acceptance vs Lot Acceptance, *C. R. Clark, Sandia Corp.*

"Martin-Denver Auto QC," *R. A. Bennett, The Martin Co.*

"Precision through Variations Flow Analysis," *N. L. Enrick, University of Virginia*

"QC Management for Time-Compressed R&D Programs," *F. A. Barta, Hughes Aircraft Co.*

Session 4—Panel Discussion

Moderator: *Dr. R. C. Seamans, Jr., Associate Administrator, NASA.*

"Reliability—The Key to Space Operations," A panel of four leaders from govern

Kodak reports on:

pourable polypropylene... interference filters from another viewpoint... the relativity of rapidity

Kodak
TRADE MARK



Possible purpose: potting

If for electrical reasons you need a hydrocarbon potting compound, we shall be glad to send you a free seven-pound sample of this new low-molecular-weight polypropylene. It is a possible alternative to polyisobutylene. It is sticky, stretchy, easily melted, compatible with several other resins and most waxes, and soluble in most aromatic and aliphatic solvents.

Write Eastman Chemical Products, Inc., Kingsport, Tenn. (Subsidiary of Eastman Kodak Company) and ask for amorphous polypropylene.

Chemical tuning

Chemical laboratories without infrared spectrophotometers properly consider themselves underprivileged.

This cute remark could well launch a commercial for spectrophotometers, except that we sell none. We sell optical interference filters, and we are going about it in an unusual and peculiarly constructive fashion: we are trying to bridge the conceptual gap for chemists from spectrophotometers to multilayer filters.

From a chemist's viewpoint, a color filter is just a little thing he slips into a colorimeter for certain analytical determinations. If he happens to be an enthusiastic amateur photographer on the side, he may know of the great variety of dyed-gelatin Kodak Wratten Light Filters.

In an ad in the December 4, 1961, issue of *Chemical & Engineering News* that looks something like the ad you are now reading, we tell the chemists that interference filters "offer means to exploit in a chemical plant the physical phenomena that spectrophotometers exploit in the laboratory.

"Suppose, for fantasy's sake, that you wanted to flood a reaction *preferentially* with energy of exactly that frequency to which a certain carbon-nitrogen bond responds. An interference filter system could probably be made for the job.

"An interference filter is tunable in manufacture for wavelengths from 0.4μ to 12μ. Unlike gelatin or glass filters, its curve doesn't depend on what colorants happen to be available. It can provide a single spectral spike of transmittance but is not limited to that. It can also be designed to cut out energy below a stated frequency or above a stated frequency. It can cut very sharp. It is thermally, chemically, and mechanically rugged. It costs a great deal less than a laser (which, while it can emit Niagaras of monochromatic energy, must work with the quantum states that Nature has in stock). It can be large. It can be designed to monitor a process stream continuously for the presence or absence of any substance possessing a suitable energy-absorbance curve."

If the impression has been given that only chemists can buy the new Kodak Interference Filters, *we have outsmarted ourselves. Anybody with a curve in hand is cordially invited to get in touch with Eastman Kodak Company, Special Products Division, Rochester 4, N. Y.*

Latest advice on instrumentation film

Background: A photographic material is said to be "fast" if it requires little energy to deliver an image. The term comes from an olden time when portraitists were reducing the duration that the subject had to "hold it" from 5 minutes to 1 minute to a few seconds and on down. Only professors and their brighter students had clear notions of what energy meant. When the photographers did acquire an intuitive grasp of the concept, the physicists kept a step ahead of them by pointing out that the time rate of energy delivery to the emulsion was also important. At this, they were probably accused of pedantry, but unjustly.

The common man came to equate speed with merit in photography. The wise men were sad. "No," they countered patiently, "the faster the emulsion the larger the grains must always be. There is no escape." But there was.

Kodak Royal-X Pan Recording Film, given the proper low-contrast development, such as 8 minutes in Kodak Developer DK-50, is the fastest material we have. This holds true both for hand-camera exposure times and for the very short exposure times of high-speed instrumentation. It holds true even when only green light is used, as in recording from certain c-r tubes. Royal-X Pan is very good to have when you need every bit of sensitivity you can get, but it is grainier than other Kodak films. Furthermore, in a high-contrast developer such as D-19 its speed advantage over other good Kodak recording films shrinks and disappears altogether for high contrast and very short exposure times.

Very recent advances in emulsion technology have produced the new *Kodak Double-X Panchromatic Negative Film.* For very short exposure times and 8 minutes in Kodak Developer D-19, it is about as fast as Royal-X Pan Recording Film, but its graininess is much less—on a par with the fine-grain and sharpness formerly attainable only in comparatively slow films.

Another film worth considering for instrumentation work is *Kodak Linagraph Ortho Film.* Its speed has recently been nearly doubled. Special attention has been given to constancy of properties during storage before use. It is a high-contrast film, designed for development to a gamma as high as 1.9. If you want high contrast for very short exposure to green light, Kodak Linagraph Ortho Film is your ticket.

All of which tells you nothing of the physical forms of these and other Kodak films for instrumentation, including color film. If you are aware of the omission, you are a person who should send for the capsule-summary sheet "F3-297" from Eastman Kodak Company, Photorecording Methods Division, Rochester 4, N. Y.

This is another advertisement where Eastman Kodak Company probes at random for mutual interests and occasionally a little revenue from those whose work has something to do with science

ment and industry will discuss the challenge the United States faces in space exploration and the key role reliability plays in this activity.

Wednesday, January 10

Session 5A—Reliability Testing

Moderator: *F. E. Wenger, U.S.A.F.—AFSC.*

"Analysis Testing for Improved Circuit Reliability," *B. J. Grinnell, IBM Corp.*

"Optimum Reliability Testing for Space Systems," *Mrs. C. D. Hock, NASA.*

"Failure Analysis," *E. W. Kimball, The Martin Co.*

"Estimating Guided Missile System Reliability from R&D Systems Firing Tests," *A. Steinberg, U. S. Army Ordnance Missile Command.*

Session 5B—Mathematics and Reliability Models

Moderator: *Dr. B. Epstein, Consultant.*

"Methodology for System Reliability Analysis," *B. Tiger, Radio Corp. of America.*

"Equipment Self-Repair Techniques," *J. Klion, Rome Air Development Center.*

"Mathematical Analysis of Redundant Matrices," *G. D. Weinstock, ITT Labs.*

"Inertial Guidance System Component Reliability," *L. A. Weaver, Honeywell.*

Session 5C—Training Session

Moderator: *L. J. Paddison, Sandia Corp.*

"Reliability Management by Objectives and Results," *Dr. L. W. Ball, Boeing Airplane Co.*

"Practical Statistical Tools for Reliability Measurement and Acceptance," *C. M. Ryerson, EI-TEK Corp.*

"Full Design Definition is Essential to Reliability," *W. L. Hurd, Jr., Lockheed Missile and Space Co.*

"Contractual Reliability—An Education Program," *R. H. Johnson, The Martin Co.*

Session 6A—Reliability Testing

Moderator: *P. D. Darnell, Bell Telephone Lab.*

"CAMESA Reliability Test Program," *A. P. Harris, Canadian Agency.*

"Practical Aspects of a High Reliability Specification," *T. W. Gross, Lockheed Missile and Space Co.*

"Reliability Evaluation by Application Derating," *K. W. Davidson, Texas Instruments, Inc.*

"Acceleration Factor Determination on Glass Capacitors," *L. D. Hines, Corning Glass Works.*

Session 6B—Reliability and Quality Control Education

Moderator: *H. C. Jones, University of Maryland.*

"Effective Reliability—Through Education," *Dr. P. H. Zorger, The Martin Co.*

"AGREE in Action," *G. W. Lindsay, U.S.A.F.*

"A Reliability Slide Rule," *B. Ellison, International Electric Corp.*

"A Comprehensive Education and Training Program for Design Reliability," *F. E. Marsh, Boeing Co.*

Session 6C—Training Session

Moderator: *Dr. L. W. Ball, Boeing Co.*

"The Problem of Human Initiated Failures," *D. Meister, General Dynamics—Astronautics.*

"Reliability Through Process Capability Studies," *G. O. Hawley, Sandia Corp.*

"A Theory of Component Part Life Expectancies," *D. R. Earles, AVCO Corp.*

"A Missile Reliability Reporting System," *I. R. Whiteman, C.E.I.R. Inc.*

Banquet

"A Senator Looks at the Problem of Reliability in National Survival," *H. M. Jackson, U. S. Senator, State of Washington.*
sented by M. P. Smith, General Chairman.

1961 National Reliability Award, *presented by M. P. Smith, General Chairman.*

1961 IRE Professional Group on Reliability and Quality Control Award, *presented by L. J. Paddison, Chairman.*

1961–1962 ASQC Electronics Division Award, *presented by H. D. Voegtlen, Division Chairman.*

Thursday, January 11

Session 8A—Reliability and Quality Control Programs

Moderator: *D. A. Hill, Hughes Aircraft.*

"Reliability Program Based on Bomb Nav. System Experience," *F. W. Blackburn Sperry Rand Corp.*

"Reliability Research on Component for Space," *E. E. Brueschke, Hughes Aircraf Co.*

"Quality Assurance in the Field of Nuclear Ordnance," *C. E. Smith, Jr., Sandi Corp.*

"Reliability Emphasis on Productio Contracts," *J. A. Marshik, Honeywell.*

Session 8B—Maintainability

Moderator: *E. Harwood, Office of Elec tronics, ODDR&E.*

"Simulation of Aircraft Electronic Maintenance," *D. S. Ellis, Hughes Aircraf Co.*

"The Human Element in the Mainte nance Package," *Dr. H. W. Page, IBM Corp*

"Maintainability Prediction and Meas urement," *B. L. Retterer, RCA Service Co.*

"Some Considerations of Schedule Maintenance," *R. Meyers, Internationa Electric Corp.*

Session 9A—Reliability Prediction and Measurement

Moderator: *Dr. N. E. Golevin, Nationa Aeronautics and Space Administration.*

"Operational Reliability of the Athena Computer," *G. P. Anderson, Sperry Rand Corp.*

"Reliability Predictions for Multi-Mode Electronic Systems," *J. A. Connor, Astr Reliability Corp.*

"Correlation of AGREE Testing with Operational Reliability," *G. W. Lindsay U.S.A.F.*

"Development of New Prediction Tech niques," *I. Bosinoff, Sylvania Electric Systems.*

Session 9B—Reliability Design Technique


Moderator: *A. W. Rogers, U.S.A.S.C. R&D.*

"General Usage Assemblies for Navy Electronic Equipment," *T. E. McDuffie New York Naval Shipyard.*

"Increasing Reliability through the QUAD Technique," *R. M. Fasano, Sylvania Electric Products, Inc.*

"Reliability and Forced Air Cooling, *J. L. Keller, Sperry Rand Corp.*

"Determination and Use of Failure Patterns," *R. L. Horn, Boeing Co.*



MODEL	6db BANDWIDTH
TL-2D5A	2 kc
TL-4D9A	4 kc
TL-6D12A	6 kc
TL-8D16A	8 kc
TL-10D18A	10 kc
TL-16D25A	16 kc
TL-20D32A	20 kc
TL-30D45A	30 kc
TL-40D55A	40 kc
TL-45D60A	45 kc
TL-32E48C	32 kc
TL-50D85C	50 kc

(suffix "A" denotes 455 kc center frequency;
suffix "C" denotes 500 kc center frequency)

Clevite Ceramic Ladder Filters

Now in stock in 12 bandwidths... 80 db rejection in 0.1 cu. in.


Clevite ceramic ladder filters provide more selectivity for their size than any conventional i-f filter. They are fixed tuned and need no alignment—are non-magnetic and non-microphonic. Leading manufacturers now have Clevite ladder filters in their communications equipment. Improve your newest design with these unique filters. Write now for complete specifications—Bulletin 94012, or for selectivity curves available on each stock model. ■ Dimensions: 5/16" diameter x 1½" long. ■ Selectivity: 60 db/6db shape factor from 1.3:1 to 2.6:1. ■ Center Frequency Stability: within 0.2% for 5 years, and within 0.2% from −40° to +85° C. ■ Impedance: 1200-1500 ohms. ■ Designed for military environment.

CLEVITE ELECTRONIC COMPONENTS
DIVISION OF CLEVITE 232 FORBES ROAD, BEDFORD, OHIO

Field Sales Offices:
Maplewood, N. J. / Chicago, Ill. / Denver, Colo. / Inglewood, Calif.

want

accurate amplification of low-level signals from DC to beyond 200 kc?



Just use a KIN TEL 121A/A solid-state DC Amplifier

The KIN TEL 121A/A is a non-inverting amplifier with response from DC to beyond 200 kc. It has fixed gains of 0, +1, +10, +20, +30, +50, +100, +200, +300, +500, and +1000, and a control that adjusts any fixed gain from X1 to X2.2. Amplification is stable within 0.01%, accurate within 0.1% for all gains other than +1 (0.2% accuracy at +1), linear within 0.005% for outputs up to ±15 volts DC with loads of 200 ohms or more. Input impedance is greater than 10 megohms (less than 500 pf to 50 kc); output impedance is less than 0.3 ohm and 50 μh. Frequency response is flat within 0.25% to 2 kc, within 4% to 10 kc, within 3 db to 200 kc. Drift is less than ±2.0 μv equivalent input for over 40 hours at +1000 gain. Equivalent input noise at +1000 gain is 3 μv peak-to-peak in a 20-cps band, 3 μv RMS in a 50-kc band. Output capability is ±15 volts into 200 ohms, ±100 ma into 10 to 100 ohms. Amplifier fits standard KIN TEL cabinets and modules. Price $1000.

Representatives in all major cities

COHU ELECTRONICS, INC
KIN TEL DIVISION

5725 Kearny Villa Road, San Diego 12, California
Phone: BRowning 7-6700

Industrial Engineering Notes*

Governmental and Legislative

One-tenth of Federally-supported electronic research and development may consist of "unwitting, needless duplication of effort," a report by the Subcommittee on Reorganization of the Senate Government Operations Committee charged last week. The waste may add up to $200 million out of $2 billion currently expended for this type of work, Sen. Hubert Humphrey (D, Minn.), subcommittee chairman, declared. Reason for the waste, he said, is poor Federal management of information on "tens of thousands" of current projects. Electronic research and development, as supported by the Department of Defense and the National Aeronautics and Space Administration, Sen. Humphrey said, is so vast and complex "that no one really knows who is now doing what, where, and how in experiments." The subcommittee singled out information management in electronics in view of "the crucial importance" of this "dynamic" field of research and development to national security and to rising standards of living. Principal focus of the report is on shortcomings in the Department of Defense's system of storing, indexing, retrieving and disseminating pre-publication scientific information. The report also criticizes information handling by the National Aeronautics and Space Administration. "Space science," it says, "has been slowed by absence to date of a reliable comprehensive NASA system for centrally indexed, broadly and promptly disseminated data on current and completed research and development contracts and subcontracts." As a remedy, Humphrey urged "a national network of electronic information centers, coordinated with a larger network covering all scientific and technical information." He called, too, for a "top policy mandate" in the Executive Office of the President and within Federal agencies for "effective and efficient information management." Humphrey also recommended fullest Federal encouragement to professional scientific organizations and to private companies to help deal with the information challenge ... **The Federal Communications Commission has denied requests to establish AM stereophonic broadcasting.** In an order released October 2, the Commission turned down petitions by Philco Corp., Radio Corporation of America, and Kahn Research Laboratories, Inc., stating there is "little evidence of public need or industry desire" for stereo transmission by standard broadcasting stations. In addition, FCC said, "the pattern of operation of the nearly 4,000 stations now licensed, the needs and purposes served, and the very nature of the service itself are such that the beneficial effects of innovations of this nature are clearly 'de minimus.'" The order said a technical study of the feasibility of AM stereo, similar to the study carried out by EIA's National Stereophonic Radio Committee prior to adoption of rules establishing FM stereo, would be needed before standard stereo broadcasting could come into being. "Preliminary consideration, however, indicates that providing a dual channel transmission system with the requisite separation and without deleterious side effects in an AM system such as standard broadcasting presents an appreciably greater problem than in the case of FM," the order concluded ... **An ad hoc committee of international communications common carriers has recommended formation of a United States Satellite Corporation to build and operate a communications satellite system.** In summary, these were its recommendations:

1. Research, development and experimental trials should be expedited by government and industry and all resources drawn upon to establish the best communications satellite system at the earliest practicable time.


2. A non-profit satellite corporation should be created to develop, construct, operate, manage, and promote the use of communications satellites, in the interests of the United States, in accordance with the public interest objectives specified in the President's Statement on Communication Satellite Policy and the Federal Communications Commission's Supplemental Notice. The satellite corporation would have three directors appointed by the President or his designate to make the appointments, two directors designated by each authorized participant in ownership of the satellites, and a director designated by the carriers which do not own but which may lease satellite facilities.

3. The U. S. carriers authorized by the Commission to provide communications services via satellites should be allowed to participate in joint ownership of the satellites and to include their investments in their rate bases for rate-making purposes, so that rates would continue to be established as at present under regulation by the Commission.

4. Each U. S. carrier should be permitted to establish and operate its own ground stations, participate in joint ownership of ground stations with other carriers or rent capacity in other carriers' ground stations, and to obtain equitable access to and use of the ground stations and satellites, in accordance with public interest objectives set forth in the Supplemental Notice and as authorized by the Commission.

(Continued on page 30A)

* The data on which these NOTES are based were selected by permission from *Weekly Reports*, issues of October 2, 9, 16, and 23, 1961, published by the Electronic Industries Association, whose helpfulness is gratefully acknowledged.



In less time than it takes light to cross this room, a new product, **DELCO'S NEW** high speed **10 MC** silicon modules, could: (1) correct the course of a missile in flight; (2) make it possible for sonar pickups to track and compute the position of targets with microsecond accuracy; and (3) handle any number of other airborne guidance and control functions that previous modules—due to low speed or environmental or performance limitations—could not handle. Delco Radio's 10mc modules, with a maximum gate-switch speed of 40 nanoseconds, convert data 100 times faster—even under the most extreme environmental conditions.


These **SILICON** modules come epoxy encapsulated, and operate over a temperature range of −55°C to +100°C. And these same reliable **DIGITAL** circuits are available packaged on plug-in circuit cards. These Delco **MODULES** are environmentally proved to: **SHOCK**, 1,000G's in all planes. **VIBRATION**, 15G's at 10 to 2,000 cps. **HUMIDITY**, 95% at max. temp. **STORAGE AND STERILIZATION TEMP.** −65°C to +125°C. **ACCELERATION**, 20G's. Designed for systems using from one module to 100,000, and the module's rated performance considers the problems of interconnection. Data sheets are available. Just write or call our Military Sales Department.

Physicists and electronics engineers: Join Delco Radio's search for new and better products through Solid State Physics.

PIONEERING ELECTRONIC PRODUCTS THROUGH SOLID STATE PHYSICS

Division of General Motors • Kokomo, Indiana

DELCO RADIO



Industrial Engineering Notes

(Continued from page 28A)

5. The Commission should, expeditiously, take such further administrative action as may be necessary and proper in furtherance of the proposed plan.

The report stipulates that the corporation be set up so as to prevent control by a single carrier. Each firm participating in ownership of the satellites would have equal representation on the board of directors, provided its contribution is $500,000 or more. RCA Communications, Inc., in a separate statement included in the report said it:

a. believes that the most important activity for satellite communications in the near future is to speed research and development of techniques, systems, and apparatus and proposes to emphasize its efforts in this area with its own funds and facilities and with contract support;

b. desires the freedom to construct and operate its own ground stations for use in satellite communications and is prepared to make the necessary investment;

c. does not have sufficient facts at this time to make a commitment as to investment in the space satellites pending further research and development and a resolution of the parameters of the space satellite system eventually to be used for commercial purposes;


d. pledges its continued best efforts and full cooperation with government and industry in this matter.

Meanwhile, Sen. Russell B. Long (D., La.) has scheduled hearings on the ad hoc committee's report before his Senate Small Business Subcommittee November 8 and 9. Appearing at the hearings will be the entire seven-member FCC. Other witnesses will include Attorney General Robert Kennedy or Assistant Attorney General Lee Loevinger; Edward C. Welsh, Director of the President's Space Council; and Omar Crook, Attorney for the Hawaiian Telephone Co. and chairman of the ad hoc committee. Members of the ad hoc committee are the American Cable & Radio Corp.; American Telephone & Telegraph Co.; Hawaiian Telephone Co.; Press Wireless, Inc.; Radio Corporation of Puerto Rico; RCA Communications, Inc.; South Puerto Rico Sugar Corp.; Tropical Radio Telegraph Co.; The Western Union Telegraph Co. . . . **An intensive program aimed at strengthening the Defense Department's in-house research laboratories and up-grading their technical standards is underway, it was disclosed last week.** The program was established by Defense Secretary McNamara, who said he had "profound concern for the maintenance of a vigorous program and the highest morale within the laboratories throughout the Department of Defense." In a memorandum, Mr. McNamara directed Harold Brown, Director of Defense Research and Engineering, to work with the military departments and officials of the Office of the Secretary of Defense in formulating and

(Continued on page 32A)

THESE 6 NEW MOTOROLA EPITAXIAL MESA SWITCHES REPLACE MICRO-ALLOY, DRIFT and OTHER MESA TYPES

ACTUAL SIZE



REPLACEMENT CHART*

Process Group	2N960	2N961	2N962	2N964	2N965	2N966
Micro-alloy Diffused	2N501 2N846 2N588 2N1500	2N769 2N768	2N1499A	2N779	–	–
Mesa	2N781 2N705 2N710	2N711	2N782	2N1301 2N795 2N1683 2N934	–	2N1300 2N794
Micro-alloy	2N1122A	2N1122	2N393 2N1427 2N1411	–	–	
Surface Barrier	–	2N128	2N210 2N344 2N345 2N346	–	–	–
Alloy	2N583	–	–	2N582 2N584	–	–
Drift	–	2N643 2N644 2N645	2N1450 2N602	–	2N609	2N603

*Interchangeability of types shown is on the basis of performance in most switching circuit applications.

for improved performance of both old and new designs

This new Motorola germanium epitaxial switching series – the 2N960-62, 2N964-66 – will supplant nearly all other germanium micro-alloy, drift, mesa, and other transistor types for high-speed switching applications . . . in many cases at considerably lower prices.

In comparison with the older devices, these six new universal switching transistors offer major design advantages that contribute to improved performance of both old and new designs.

- faster switching time ($\tau_{RE} = 0.6$ nsec)
- guaranteed minimum Beta over wide current range . . . specified at 10, 50 and 100 mA
- low saturation voltage even at 100 mA
- rugged Mesa construction
- the most comprehensive published specifications of any similar switching transistors
- proven reliability from the world's largest manufacturer of germanium epitaxial transistors

For applications where the advantages offered by this new epitaxial series are not essential, Motorola also offers eight new non-epitaxial germanium mesa transistors – the 2N968-75 series – at even lower prices.

MOTOROLA GERMANIUM EPITAXIAL SWITCHING TRANSISTORS							
	2N960	2N961	2N962	2N964	2N965	2N966	UNITS
h_{FE} (MIN) 10, 50, 100 mA	20	20	20	40	40	40	—
$V_{CE(SAT)}$ MAX @ 10 mA	.20	.20	.20	.18	.18	.18	Volts
@ 50 mA	.40	.40	.40	.35	.35	.35	Volts
@ 100 mA	.70	.70	.70	.60	.60	.60	Volts
f_T (MIN) I_E=20 mAdc V_{CB}=1.0 Vdc	300 mc all types						
Q_T (MAX) I_C=10 mAdc I_B=1 mAdc	80	80	90	80	80	90	pc
I_C=100 mAdc I_B=5 mAdc	125	125	150	125	125	150	pc
τ_{RE}	0.6 nsec typical all types						
τ_{FE}	0.5 nsec typical all types						
All types have 150 mW dissipation in free air, 300 mW at 25°C case temperature							




FOR MORE INFORMATION on either of these important new mesa series, contact your Motorola District Office, or call or write: Motorola Semiconductor Products Inc., Technical Information Department, 5005 East McDowell Road, Phoenix 8, Arizona.

MOTOROLA DISTRICT OFFICES:
Belmont, Mass. / Burlingame, Calif. / Chicago / Cleveland / Clifton, N. J. / Dallas
Dayton / Detroit / Garden City, L. I. / Glenside, Pa. / Hollywood / Minneapolis
Orlando, Fla. / Phoenix / Silver Spring, Md. / Syracuse / Toronto, Canada.

MOTOROLA
Semiconductor Products Inc.
A SUBSIDIARY OF MOTOROLA, INC
5005 EAST McDOWELL ROAD • PHOENIX 8, ARIZONA


TOWER FOOTING INSULATORS FOR SELF-SUPPORTING RADIATORS



LAPP


ANTENNA TOWER

INSULATORS






MAST BASE INSULATORS



RADIO GUY INSULATOR



We at Lapp are mighty proud of our record in the field of tower insulators. Over 30 years ago, the first insulated broadcasting tower was erected—on Lapp insulators. Since then, most of the large radio towers in the world have been insulated and supported by Lapp insulators. Single base insulator units for structures of this type have been design-tested to over 3,500,000 pounds.

A thorough knowledge of the properties of porcelain, of insulator mechanics and electrical qualities has been responsible for Lapp's success in becoming such an important source of radio insulators. Write for description and specification data on units for any antenna structure insulating requirement. Lapp Insulator Co., Inc., Radio Specialties Division, 233 Sumner Street, LeRoy, N. Y.

Lapp

Industrial Engineering Notes



(Continued from page 30A)

carrying out a program of strengthening in-house laboratories. He set forth the following policies: In-house laboratories are to be used as a "primary means" of carrying out DOD programs. They are to provide scientific and technical advice on the government's responsibility for development and acquisition of new weapons. "Clear lines" of technical management and responsibility are to be set up for each in-house laboratory. To accomplish this, provisions will be made for extended tours of duty for "officer-scientists" in positions for which they have demonstrated technical proficiency. In addition, procedures will be established by which the principal laboratories of each military service will be brought under "the more effective control" of Assistant Secretaries for R&D of the military departments. Depending on the mission and nature of the work of a particular laboratory, a fraction of the annual laboratory budget will be set aside for work judged by the lab director to be promising or important. Prior approval or review at higher levels will not be needed. Salaries of senior technical personnel will be raised in accordance with existing regulations. In addition, DOD will attempt to secure for its senior personnel "rates of compensation . . . consistent with levels set outside as well as inside the government service." It was understood that a DOD study group is examining problems of organization of in-house laboratories, personnel, and salary; fiscal and budget problems; construction to support RDT&E; morale; and research missions. A report is expected by January 1 . . . **The Federal Communications Commission last week invited comments on its proposal in Docket 13928 to amend Part 2 of its rules in the matter of doppler navigational aids.** While continuing to advocate the development of such civil aids in the exclusive band 13250–13400 mc, the proposal would amend footnote US53 in the frequency allocations table to permit government and non-government airborne doppler radars in the aeronautical radionavigation service to operate in the band 8750–8850 mc only on condition that they accept any interference which may be experienced from radio location stations in the band 8500–10,000 mc.




Military and Space

The Defense Department last week pledged its full support to industry's efforts to develop an operational communications satellite system and set forth technical characteristics which would suit defense needs. In a statement detailing its policies for cooperation with industry, DOD urged establishment of a commercial system "as rapidly as economically and technically feasible." According to the statement, the Department will assist principally by supplying scientific information gained from military developments. In addition, it will



(Continued on page 34A)


• coax and waveguide couplers • attenuators • mounts •

• bolometers • isolators • detectors • frequency meters •

• r. f. probes •

UHF to 90 Gc!

NARDA

can supply you with more than 600 PRECISION microwave instruments, components and hardware!




Write for your free catalog!

• klystron mounts •




• thermistors •

• tuneable shorts •





• ridged waveguides •

• ferrite circulators •



• waveguide adapters & accessories • stands • horns •



• hybrid junctions • instruments and modulators •


SEND FOR FREE CATALOG TODAY!

Address: Department PIRE-1-13

the narda microwave corporation

PLAINVIEW, L. I. NEW YORK - AREA CODE 516 GE 3-9000

It's the Combination that Counts




Packaged oscillator stability can only be as reliable as the crystal source!

Component qualifications for a Bliley crystal oscillator package begin with high precision glass-mounted crystals that will deliver long-term performance with **minimum** aging. In combination with custom built circuitry and temperature control, each unit is individually tested to meet rigid quality standards. This is the essence of **product reliability.**

Typical Bliley oscillator packages are described in Bulletins 520A, 522 and 526.

Bliley ...if you buy quality

BLILEY ELECTRIC COMPANY • Union Station Building • Erie, Pennsylvania



T-2 BULB with telephone slide base; 6–60 volts

TELE-STRIPS®

(MULTIPLE LAMP INDICATORS)

For switchboards and other applications requiring multiple indication with T–2 lamps.

DIALCO **Tele-Strip** No. TS 4220. Accommodates 20 DIALCO Lens Cap Assemblies (Series 402–). Convex or dome lens; 6 colors.

Tele-Strips are available in several styles, and in sizes to accommodate from 2 to 20 Lampholders per strip. Choice of Lens Caps and Colors, or less lens caps for use with designation cards. Also: **Tele-Strips** made to specifications. Submit problem for recommendations.

No. 70428–XP10–1131




(Back mounting, in 9/16" clearance hole)

INDICATOR LIGHTS

FOR WARNING, SIGNAL AND READOUT APPLICATIONS

No. 135–428–1431



(Front mounting, in 11/16" clearance hole)

Two complete Series: For mounting in 9/16" and 11/16" clearance holes. Wide choice of lens styles and colors. All assemblies are available complete with lamp.

Samples on Request at Once — No Charge

For complete data, request 8-page Catalogue L–164.

DIALCO®

PILOT LIGHTS

"The Eyes of Your Equipment"



Foremost Manufacturer of Pilot Lights

DIALIGHT CORPORATION

60 STEWART AVENUE, BROOKLYN 37, N.Y. • HYacinth 7-7600

Industrial Engineering Notes

(Continued from page 32A)

furnish private industry technical specifications and circuit requirements to meet long-line military needs, and aid in the selection of locations for ground facilities. In addition, DOD will provide assistance, when requested, to the Federal Communications Commission, the National Aeronautics and Space Administration, and other agencies in evaluating industry proposals for commercial satellite-based telecommunication systems. It will also make available, when possible, government boosters and launching facilities. The present DOD policy on long-line communications will apply to satellite communications. Military services will use U. S. commercial facilities and provide exclusive military facilities only when commercial facilities to meet military needs do not exist . . . **D. Brainerd Holmes, General Manager of the Major Systems Division of the Radio Corporation of America, has been named Director of Manned Space Flight Programs for the National Aeronautics and Space Administration.** He will take office November 1. Mr. Holmes, 40, will be responsible for direct program supervision of NASA's manned space flight activities at NASA centers and in industry. The activities will include the projected manned lunar landings under Project Apollo. In his position with the Major Defense Systems Division, a unit of RCA Defense Electronics Products at Moorestown, N. J., Mr. Moore has been project manager for the Ballistic Missile Early Warning System. NASA Director James E. Webb also disclosed personnel shifts which will place new emphasis on manned space flight, space sciences, and practical applications of space technology. The personnel changes, effective November 1, include appointment of: Ira H. Abbott, Director of the Office of Advanced Research Programs, as Director of the Office of Advanced Research and Technology; Dr. Homer E. Newell, Deputy Director, Office of Space Flight Programs, as Director of the Office of Space Sciences; Dr. Abe Silverstein, Director of the Office of Space Flight Programs, as Director of the Lewis Research Center, Cleveland, Ohio, a position now vacant; and Robert R. Gilruth, Director of Space Task Group, Langley Field, Virginia, as Director of NASA's new Manned Spacecraft Center, Houston, Texas. Program office directors will report directly to Associate Administrator Robert C. Seamans, Jr. . . . **Research in communications and command control as a function of electronics systems rates higher priority than research leading to reliability of electronic components, according to 49 industrial, academic, and government electronics authorities polled recently by the Defense Department.** In the survey, DOD asked for ideas on the electronic or related research areas of most significance to military and economic or social progress. The responses are contained in a report made public last week.

(Continued on page 36A)

ARNOLD 6T CORES: PROTECTED AGAINST SHOCK, VIBRATION, MOISTURE, HEAT... AVAILABLE FROM STOCK

The hermetically-sealed aluminum casing method developed exclusively for Arnold 6T tape cores is packed full of advantages for you . . . *performance-improving and cost-saving advantages.*

It is compact: you can design for minimum space/weight requirements. It's extra-rigid to protect against strains. And it gives you maximum protection against environmental hazards. Arnold 6T tape cores are guaranteed against 1000-volt breakdown . . . guaranteed to meet military test specs for resistance to shock and vibration . . . guaranteed also to meet military specs for operating temperatures. They require no additional insulation before winding, and can be vacuum-impregnated afterward.

And now a NEW Arnold service: immediate delivery on your prototype or production requirements for Deltamax 1, 2 and 4-mil Type 6T cores in the proposed EIA standard sizes (see AIEE Publication 430). A revolving stock of approximately 20,000 Deltamax cores in these sizes is ready for you on warehouse shelves. Subject to prior sale, of course, they're available for shipment *the same day your order is received.*


Use Arnold 6T cores in *your* designs. Technical data is available; ask for Bulletin TC-101A and Supplement 2A (dated June '60). •Write *The Arnold Engineering Company, Main Office and Plant, Marengo, Ill.*

ADDRESS DEPT. P-12

ARNOLD
SPECIALISTS in MAGNETIC MATERIALS

BRANCH OFFICES and REPRESENTATIVES in PRINCIPAL CITIES • *Find them FAST in the YELLOW PAGES*

1538





Industrial Engineering Notes


(Continued from page 34A)

Emergence of emphasis on communications, according to conclusions gained from the poll, could in one sense be considered secondary to a broader trend elicited by the poll questionnaire. Results show a rather sharp subdivision of current electronics research into two major and several minor areas. The major areas listed are (1) science and technology related to components, and (2) electronic systems research. The components area includes materials research, solid state, microminiaturization and reliability research, and apparently does not take in such components as superpower tubes and antennas. It centers, instead, on solid state research, according to the DOD pollsters. Another important components area includes lasers and components to fill the frequency gap in the millimeter wave region. Systems research, on the other hand, encompasses communications and command control, computers and data processing, bioelectronics, adaptive systems, pattern recognition, artificial intelligence, and similar fields, the report of the survey points out. The full report, "Important Areas of Electronic Research," is available from the Office of Technical Services, U. S. Department of Commerce, Washington 25, D. C. Order PB 171 881. Price $2.25. . . . **The nation's first synchronous satellite for international relay of telephone and telegraph signals will be launched in late 1962, the National Aeronautics and Space Administration announced last week.** Design work on the satellite, called the Syncom, is nearly complete, NASA said. Hughes Aircraft Co. was contracted in August to build three of the experimental high-altitude satellites. Details of the Syncom, released simultaneously by Hughes and NASA, describe it as a 28-inch-diameter, 55-pound cylinder which will be placed in a 22,300-mile orbit. It will be the first satellite to go into synchronous orbit, or one in which the satellite's orbital velocity is matched to the earth's rotation. Syncom will relay telephone and telegraph communications over "near-hemispheric" distances, NASA said. The Hughes announcement said it will be capable of relaying telephone conversations to Europe. Syncom's electronics unit consists of two communications transponders, two command receivers, two telemetering transmitters, and associated power converters and command processing equipment, according to Hughes. It will carry a slotted array antenna for signal transmitting and receiving and four whip antennas in a turnstile arrangement for telemetering and command. Frequencies to be used will be 7500 mc from ground to satellite and 1850 mc from satellite to ground. The first Syncom is expected to have a one-year lifetime.

Industry Marketing Data

Factory sales of transistors in August increased to 17,193,860 units, about 6

(Continued on page 40A)



keep your signals clean with engineered magnetic shielding

Keep stray magnetic fields out of your high gain input transformers and cathode ray tubes. Keep your signals free of noise, hum, cross-talk and distortion. You can do it only with *engineered* magnetic shielding.

These high-permeability shields are made from existing tools in a broad variety of single and multiple structures—cylinders, spheres, truncated cones—for applications ranging from dc into the audio range and higher. They can be used with almost all conventional transformer core and coil assemblies to provide any degree of magnetic, electrostatic or RF shielding against undesired signals of all classes. Reduction of field strengths to 100 db and beyond is common.

With Magnetic Metals shielding, both the electrical and mechanical engineering is already done for you. Simply let us know your requirements . . . We'll engineer the exact type of shielding you need. In selection of raw material, design, fabrication, annealing, testing and gaging, Magnetic Metals has amassed a great backlog of shielding experience. For a better understanding of shielding and help in specifying it, write for our informative booklet, "Magnetic Shielding of Transformers and Tubes."

MAGNETIC METALS

MAGNETIC METALS COMPANY
Hayes Avenue at 21st Street, Camden 1, N.J.
853 Production Place, Newport Beach, California
transformer laminations • motor laminations • tape-wound cores
powdered molybdenum permalloy cores • electromagnetic shields


HIGH-SPEED SWITCHING



Check these CLARE Mercury-Wetted Relays against your design needs

Choice of two basic switches

SPEED TO 200 CPS



This CLARE TYPE HGS is the fastest operating, most sensitive mercury-wetted contact relay obtainable. It will operate at speeds to 200 cps with sensitivity as low as 2.5 milliwatts with a contact rating of 2 amperes, 500 volts (100va max.). Two permanent magnets provide single-side stable and bi-stable adjustments. Available with Form D (bridging) contacts.

LOADS TO 250 VA



This CLARE HG capsule will handle contact loads as high as 5 amperes, 500 volts (250va max.). Operating time may be as low as 3 milliseconds. It is also available equipped with two permanent magnets (HGP TYPE) for single-side stable, bi-stable or chopper operation.


The Clare Mercury-Wetted Relay Principle

The remarkably long life of CLARE mercury-wetted relays is the result of a design principle whereby a film of mercury on the contacts is constantly renewed, by capillary action, from a mercury pool. Both CLARE HGS and HG switch capsules employ this principle. Both switches are sealed in high-pressure hydrogen atmosphere. Certain construction differences, however, give greater speed and sensitivity to the HGS switch.

FOR BILLIONS OF OPERATIONS


Choice of three convenient packages

ENCLOSED MODULES




Both CLARE HGS and HG switch capsules are available in steel-enclosed modules for convenient mounting on printed circuit boards in the same manner as resistors, capacitors and similar components. The enclosure is ruggedly designed and provides both excellent mechanical protection and magnetic shielding. These modules are ideal for design and prototype work.

CONVENTIONAL PLUG-IN RELAYS




CLARE HGS switch capsules are available in single switch units, surrounded by a coil, mounted in high-melting point wax and encased in cylindrical steel containers provided with plug-in base. A smaller type (HGSS) is designed for use where space is limited. HG relays are available with one, two, three, or four capsules, surrounded by a single coil. Also with permanent magnets (HGP) for single-side stable, bi-stable or chopper operation.

PCB ASSEMBLIES



Printed circuit board assemblies are available with either HGS or HG switch capsules to meet design specifications. These may be designed to customer specifications by CLARE or mounted on boards supplied by the customer. Number of relays is limited only by the dimensions of the printed circuit board.



NEW! Design Manual 201A


Complete data on characteristics, circuitry, mountings, coil tables and information for ordering CLARE mercury-wetted contact relays.

See your nearest CLARE representative or address: C. P. Clare & Co., 3101 Pratt Blvd., Chicago 45, Illinois. In Canada: C. P. Clare Canada Ltd., 840 Caledonia Road, Toronto 19, Ontario. Cable Address: CLARELAY.

C. P. CLARE & CO.

Relays and related control components


high voltage connector problems?



ALDEN


solves them by return mail

Alden makes high voltage connectors that are more reliable . . . simpler . . . and less expensive. Connectors you can trust absolutely to tame arc-over and corona problems at voltages as high as 30 KDVC.



A few of the many Alden IMI High Voltage Connectors and tube caps available for solving your problems.

It's done through Alden's exclusive IMI (Integral Molded Insulation) technique. With this unique method, we can mold Kel-F, Polyethylene, or Nylon insulation in a single hot shot directly around leads, contacts, and any special circuit components like chokes, resistors, or corona shells.



This one shot technique saves production costs. These savings are passed on to you. And it actually adds reliability.

Let us prove it. Let us send you complete information by return mail. Better still, send us a sketch. Tell us what you want to connect. Lay out lead lengths, give voltage and current, environmental conditions. We'll send you a sample connector assembly or a proposal specifically tailored to your needs. Just write:

ALDEN

PRODUCTS COMPANY

117 N. Main Street, Brockton, Mass.

IRE People

Dr. Yardley Beers (A'44–M'46) has been appointed Chief of the Millimeter-Wave Research Section, Radio Standards Laboratory, Boulder Laboratories of the National Bureau of Standards, U. S. Department of Commerce. Since July, 1961, Dr. Beers has been acting chief of his present section. He joined the staff of NBS in June, 1960, as a consultant in atomic frequency and time interval standards. Since that time, he has completed a final year in the Physics Department at New York University.

Dr. Beers was a member of the staff of the Radiation Laboratory at M.I.T. from 1942–45; a consultant to the Brookhaven National Laboratories with the Atomic Energy Commission, 1947–59; and a teacher of physics at New York University for 15 years -leaving with the rank of full professor. In 1956, Dr. Beers worked as a Fulbright scholar with the Commonwealth Scientific and Industrial Research Organization in Sydney, Australia. During his stay, he was also visiting professor at the University of Sydney.

Born in Philadelphia, Pa., in 1913, Dr. Beers took his B.S. from Yale University in 1934. After a year of graduate study there, he transferred to Princeton, where he received his M.A. and Ph.D. in Physics in 1937 and in 1941.

His special fields of research interest are: nuclear physics, microwave spectroscopy, and the electronics connected with these fields. He is the author of numerous papers in his fields, a book, "Introduction to the Theory of Error," and chapters in the M.I.T. Radiation Laboratory Series. A Fellow of the Physical Society, Dr. Beers is also a member of the Association of Physics Teachers.

The appointment of **Paul B. Black** (M'46–SM'51) as manager of headquarters marketing for Sylvania Electronic Systems, a division of Sylvania Electric Products Inc., was recently announced. In his new capacity, he will be responsible for coordinating the entire marketing information effort of the division and monitoring the day-to-day marketing activities of the various operations within the division.



P. B. Black

Mr. Black previously served as marketing manager of the Systems Engineering and Management Operation (SEMO) of Sylvania Electronic Systems, and prior to that, he was manager of the B-58 "Hustler" program at the Buffalo, N. Y. Operations, also of Sylvania Electronic Systems. The company is responsible for development and production of the defensive electronic countermeasures system for the supersonic B-58 bomber.

Mr. Black joined Sylvania's Lighting Products Division, Salem, Mass., in 1940 as a lighting engineer. Following World War II military service with the U. S. Army Signal Corps, he rejoined the company at Kew Gardens, N. Y., and was named head of the microwave circuits group in the Physics Laboratory there in 1948. He served successively as engineering manager of the Boston Engineering Laboratory and manager of the Avionics Laboratory, a unit of the Waltham Laboratories of Sylvania Electronic Systems, before appointment as manager of the B-58 program in February, 1956.

Mr. Black is a member of the American Management Association and the Armed Forces Communications and Electronics Association.

W. Roderic Bliss (M'50) has been named Assistant Director of Research, Selas Corporation of America, Dresher, Pa., according to a recent announcement. Mr. Bliss comes to Selas from the Martin Company, Baltimore, Md. where he held the position of Manager, Industrial Development, on the Corporate Planning Staff. Previously, he was Manager of the firm's Electronics Technical Staff in Denver, Colorado. Prior to that, he was Assistant Technical Director of the Central Engineering Laboratories, American Machine and Foundry, Greenwich, Conn. He was also Senior Project Engineer of the Denver Research Institute, Denver, Colorado. In 1950, while President of Decimeter, Inc., Denver, Colo., he was active in the development of an ultrasonic diagnostic instrument for the early detection of cancer.

(Continued on page 42A)

Industrial Engineering Notes

(Continued from page 36A)

million more than the year's low of 11,227,388 units sold in July, when most plants shut down for vacation. Total revenue accrued in August was $25,155,627. Transistors sold at the factory the month before were valued at $17,506,011. Cumulative totals for this year continued to stay well ahead of those for the same period of 1960. Through August, 117,104,130 transistors were sold with a value of $199,781,787. Last year 77,289,560 units worth $193,756,732 were sold.

New from Sprague!



ALL-NEW MADT® TRANSISTORS

Wide Range of Parameters *Plus* Choice of Package Tailored to Meet Your Actual Circuit Requirements

Sprague now offers a complete new line of ultra-high-speed switching transistors. For greater design flexibility, these Micro-Alloy Diffused-Base Transistors provide interchangeability of packages (identical specifications are available in either the TO-9 or TO-18 case).

THIS NEW FAMILY OF SWITCHES OFFERS:

- High BV_{CEO} Ratings
- Low Saturation Voltage
- Low Storage Time
- Low Output Capacitance
- Excellent Frequency Response
- Close Parameter Control in Your Choice of Package

HERE ARE SOME KEY PARAMETERS:

Type No.	JEDEC CASE	Max. I_{CBO} (μa)	Min. BV_{CES} (volts)	Min. BV_{CEO} (volts)	Min. h_{FE}	Typ. f_T (mc)
2N982	TO-18	3	20	15	50	450
2N2168	TO-9					
2N983	TO-18	3	15	15	40	450
2N2169	TO-9					
2N984	TO-18	5	15	10	20	350
2N2170	TO-9					

For application engineering assistance, write Product Marketing Section, Transistor Division, Sprague Electric Co., Concord, N.H.

For complete engineering data, write Technical Literature Section, Sprague Electric Company, 235 Marshall Street, North Adams, Massachusetts.

SPRAGUE COMPONENTS

TRANSISTORS
CAPACITORS
MAGNETIC COMPONENTS
RESISTORS
INTERFERENCE FILTERS
PULSE TRANSFORMERS
PIEZOELECTRIC CERAMICS
PULSE-FORMING NETWORKS
HIGH TEMPERATURE MAGNET WIRE
CERAMIC-BASE PRINTED NETWORKS
PACKAGED COMPONENT ASSEMBLIES
FUNCTIONAL DIGITAL CIRCUITS


SPRAGUE®
THE MARK OF RELIABILITY

'Sprague' and '②' are registered trademarks of the Sprague Electric Co.

CALIBRATED
Thermistor Mounts
For Greater Accuracy in Power Measuring Systems


Model 675-A

Coaxial Thermistor Mount
The Model 675-A is a 200 ohm thermistor mount for use in the 100 to 4000 mc range. Its extremely long thermal time constant virtually eliminates effects of ambient temperature changes. Calibration factor is supplied to an accuracy of 2% at 400, 1000 and 1500 mc.


Models 811, 813 and 815

X-Band Power Standard
This 200 ohm thermistor mount-coupler-temperature chamber combination operates over any specified 200 mc band between 8.2 and 11.2 kmc. The thermostatically controlled constant temperature chamber eliminates effects of ambient temperature changes. An NBS test report is supplied giving the calibration factor to an accuracy of 1%.

Precision Power Bridges
Weinschel Engineering also manufactures precision power bridges for use with these thermistor mounts. These bridges give accuracies to 0.1% of substituted power.

For complete specifications: Write for Weinschel Bulletin #386

WEINSCHEL
ENGINEERING
KENSINGTON, MARYLAND
949-0141 (Code 301)
TWX: KENS 446

Santa Monica,
631 Wilshire Boulevard,
TWX: SMON 7185


IRE People

(Continued from page 40A)

He attended Wesleyan University, then transferred to the University of Massachusetts, where he earned his Bachelor of Science Degree in Physics. He is a graduate, also, of American Management Association courses in General Management and Business Finance. He is a Past Chairman of the Denver Chapter of the IRE.

❖

Robert L. Borchardt (S'49–A'50–M'56) has been appointed National Service Manager for Motorola Communications and Electronics, Inc. In this capacity, he coordinates the firm's nation-wide communications service activities, which include over 800 independent service stations which provide contract maintenance to two-way radio systems and other communications products used by public safety, industrial, transportation, and business organizations. He also directs Motorola's national communications service training program and the Motorola Training Institute, which provides home study on two-way radio servicing techniques.


R. L. Borchardt

Borchardt, with Motorola since 1950, had been Sales Service Manager. He holds a degree in Electrical Engineering from the University of Minnesota, and served as an electronics technician in the United States Navy.

❖

Arthur E. Cooper (S'47–A'50–M'55–SM'59) was recently promoted to manager of research and engineering for IBM's Federal Systems Division.


Mr. Cooper will direct the scientific and engineering activities of the Division in the development of advanced information handling, command and control and space systems for the Federal Government. Engineering laboratories at the IBM Space Guidance Center, Owego, N. Y., and the IBM Command Control Center, Kingston, N. Y., will report to him.


A. E. Cooper

Mr. Cooper has held engineering, laboratory and management positions since he joined IBM in 1950. In 1958 he was promoted to manager of advanced systems research at the Space Guidance Center and in 1959 became manager of the Center's engineering laboratory. He holds Bachelor and Master of Science degrees from Purdue University.

❖

Martin Cooper (M'56) has been promoted to Assistant Chief Engineer by Motorola's Communications Division. In this capacity, he supervises research and development of mobile two-way radio and other communications products.


M. Cooper

Mr. Cooper holds both Bachelor and Master's degrees in electrical engineering from the Illinois Institute of Technology. He joined Motorola in 1954 and was a member of the digital electronics research staff for four years before moving into developmental engineering.

He has five patents pending on his work at Motorola. He is a member of the Electronics Industries Association Committee on Selective Signaling.

❖

Pioneer Electronic Supply Co. announced recently that **John R. DiJulius, Jr.** (A'58) was appointed Industrial Sales Manager, effective Oct. 1, 1961. Formerly a field sales representative for Pioneer in the Cleveland area, Mr. DiJulius, as Industrial Sales Manager, assumes responsibility for the marketing in a three state area of all industrial items to original equipment manufacturers, research facilities, public utilities and city and state governments.


J. R. DiJulius, Jr.

Mr. DiJulius joined Pioneer in 1955 after extensive experience in radio. After serving in World War II as a radio and electronics instructor, he held a Broadcast Engineer's License and was active in the service industry.

❖

D. L. Deal (S'48–A'50–M'55) has been recently appointed Manager of the newly established Product Planning organization of the Air Force Programs Section of the General Electric Company's Heavy Military Electronics Department.

The Product Planning function, headed by Mr. Deal, will analyze and evaluate the

(Continued on page 46A)

ANOTHER ADVANCED MICROWAVE TUBE DEVELOPMENT
FROM RAYTHEON'S SPENCER LABORATORY



K-BAND BWO, QKB 891, of a completely new design is extremely rugged and compact.

New K-band O-type BWO's extend Raytheon compatible line to 26.5 kMc

Advanced design provides 40 mW minimum power output in extremely rugged and compact package.

Size and weight of these two new Raytheon backward wave oscillators are barely half that of units now in use.

The QKB 890 and QKB 891 are designed for such applications as swept local oscillators in ECM receivers and test equipment, driver tubes in frequency diversity radars, and pump tubes for broadband parametric amplifiers. Both tubes utilize PM focusing and have grids for low-voltage pulsed operation. For equipment designs requiring close mounting, only two-inch spacing between tubes is necessary.

Write today for detailed technical data or application service to Microwave and Power Tube Division, Raytheon Company, Waltham 54, Massachusetts. In Canada: Waterloo, Ontario.

TYPICAL OPERATING CHARACTERISTICS

	QKB 890	QKB 891
Frequency Range	12.4-18 kMc	18-26.5 kMc
Power Output	40-180 mW	40-180 mW
Delay Line (tuning)	400-1270V	600-2100V
Anode Voltage (fixed)	125V	150V
Cathode Current	17-21 mA	21-32 mA
Filament Voltage	6.3 Volts	6.3 Volts
Waveguide Coupling..	RG91/U	RG53/U

RAYTHEON

RAYTHEON COMPANY

MICROWAVE AND POWER TUBE DIVISION

HIGH SPEED WITH LOWEST V_{CE}(sat) RATINGS


PLANAR EPITAXIAL PASSIVATED

PUT PEP IN YOUR DESIGNS

The new G-E 2N2193-2195 and "A" series combines three of the most advanced processes in semiconductor technology to bring you new standards of silicon transistor performance, reliability and stability. This series of PEP transistors features greatly improved V_{CE} (sat.) ratings, and can replace standard units without basic circuit changes.

Planar Passivated 2N696-2N699, 2N1613, 2N1711, and 2N1893 silicon transistors are also available. They feature superior h_{FE} holdup at low currents, lower I_{CBO} and I_{EBO}, and remarkable reliability of performance and stability of parameters due to planar passivation.

TYPICAL PULSE GENERATOR CIRCUIT WITH *PEP* TRANSISTORS SWITCHES ½ AMP IN 25 NANOSECONDS




PULSE GENERATOR


Pulse Characteristics:

Amplitude	25 volts
Width	200 nanoseconds
Rise Time	25 nanoseconds
Fall Time	30 nanoseconds
Impedance	50 ohms
Repetition rate	100 kilocycles

Unprecedented versatility is still another unique advantage of General Electric PEP transistors in new and/or existing applications. The pulse generator circuit shown illustrates the versatility of 2N2193 in an existing circuit, without the need for redesigning. Also, by combining low saturation resistance, high voltage, dissipation and frequency response, controlled gain over four decades of current, and low leakage, with the stability of passivation, the 2N2193 approaches "ideal" transistor characteristics. These characteristics make the 2N2193 equally effective in linear or switching applications. Examples: direct conversions of germanium transistor circuits, low level linear amplifiers, power stages, and computer type switching applications.

SILICON TRANSISTORS





PEP *(PLANAR EPITAXIAL PASSIVATED)* TRANSISTORS

Type No.	Description	Notable Advantage
2N2193	Similar to 2N1613 (see chart below)	**V_{CE} (sat) = 0.35 V max.** (@ I_C = 150 ma, I_B = 15 ma) ***V_{CEO} = 50 V min.***
2N2193A	Similar to 2N1613 (see chart below)	**V_{CE} (sat) = 0.16 V Typ.; 0.25 V max.** (@ I_C = 150 ma, I_B = 15 ma) ***V_{CEO} = 50 V min.***
2N2194	Similar to 2N696 (see chart below)	**V_{CE} (sat) = 0.35 V max.** (@ I_C = 150 ma, I_B = 15 ma) ***V_{CEO} = 40 V min.***
2N2194A	Similar to 2N696 (see chart below)	**V_{CE} (sat) = 0.16 V Typ.; 0.25 V max.** (@ I_C = 150 ma, I_B = 15 ma) ***V_{CEO} = 40 V min.***
2N2195	General Purpose Industrial Type	**V_{CE} (sat) = 0.35 V max.** (@ I_C = 150 ma, I_B = 15 ma) ***V_{CEO} = 25 V min.***
2N2195A	General Purpose Industrial Type	**V_{CE} (sat) = 0.16 V Typ.; 0.25 V max.** (@ I_C = 150 ma, I_B = 15 ma) ***V_{CEO} = 25 V min.***

PLANAR PASSIVATED TRANSISTORS

Type No.	h_{FE} @ I_C = 150 ma V_{CE} = 10 V	V_{CE} (sat) (max.) @ I_C = 150 ma I_B = 15 ma	V_{CER} (min.) @ I_C = 100 ma R_{BE} = 10	I_{CBO} (max.)
2N696	20-60	**1.5V**	40V	**1 μa @ 30 V**
2N697	40-120	**1.5V**	40V	**1 μa @ 30 V**
2N698	20-60	**5V**	80V	**5 mμa @ 75 V**
2N699	40-120	**5V**	80V	**2 μa @ 60 V**
2N1613	40-120*	**1.5V**	50V	**10 mμa @ 60 V**
2N1711	100-300*	**1.5V**	40V	**10 mμa @ 60 V**
2N1893	40-120*	**5V**	100V	**10 mμa @ 90 V**

* plus guaranteed minimum h_{FE}'s at several other currents

The silicon oxide is thermally grown during the planar diffusion process. It forms a passivated surface over the junction that provides maximum protection against contamination and degradation of characteristics during the entire life of the transistor. The thin epitaxial layer on low resistivity substrate gives negligible body drop resulting in extremely low saturation resistance and increased uniformity from unit to unit.

For complete technical data on the new PEP and Planar Passivated silicon transistors, call your G-E Semiconductor Products District Sales Manager. Or Write Semiconductor Products Department, Section 23L113, General Electric Company, Electronics Park, Syracuse, New York. In Canada: Canadian General Electric, 189 Dufferin St., Toronto, Ont. Export: International General Electric, 159 Madison Avenue, New York 16, New York.

STOCKED BY YOUR G-E SEMICONDUCTOR DISTRIBUTOR

GENERAL ELECTRIC

Engineers and scientists join the team that is making

THERMIONIC POWER BECOME OF AGE



Since 1956 THERMO ELECTRON has pioneered in the development of thermionic energy converters. Today as thermionics becomes of age, THERMO ELECTRON is a leader in the development of thermionic power systems. Typical of the programs being carried out for military and peactime applications are:

A 250-watt solar thermionic generator for Aeronautical Systems Command for space applications. ASC chose the team of Thermo Electron and Thompson Ramo Wooldridge Inc. TRW provides the system's management and Thermo Electron is developing the thermionic generator.

Isotopic-fueled thermionic generator — The Martin Company selected Thermo Electron to develop this generator which holds promise for applications in space, navigational aids, and remote sites.

A 200-watt gas-heated thermionic generator — the American Gas Association selected Thermo Electron to develop a gas-fired thermionic generator for use in commercial appliances and military and industrial field applications.

These exciting and advanced programs offer challenging opportunities to qualified scientific and engineering personnel. We have immediate openings for scientists and engineers with experience in high temperature material research, vacuum technology and plasma physics. For further information regarding your interest in thermionics, contact Mr. Lawrence T. Sullivan, TWinbrook 4-8700.

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

THERMO ELECTRON
ENGINEERING CORPORATION
85 FIRST AVENUE • WALTHAM 54 • MASS.

LEADERS IN THERMIONIC ENERGY CONVERSION

IRE People

(Continued from page 42A)

Air Force market to determine current and future operational requirements and to forecast anticipated technological trends. Such long-range planning efforts will direct the Department in the development of new products, as well as in the modification of existing equipments, to assure that changing defense needs are met with a continuing program of product improvement.

❖

The appointment of **Peter N. Dudeney** (M'57) to the post of Director, Research and Engineering for Itek Electro-Products Company was announced recently. Mr. Dudeney's new position consolidates under one director two engineering departments from recently merged Hermes Electronics and existing Itek engineering departments. He is responsible for supervision of the Crystal Filter, Digital Equipment, Communications Equipment, Electronic Systems, and Product Development Departments.



P. N. DUDENEY

Mr. Dudeney joins Itek from a position as Director of Engineering at Vitro Electronics, Silver Spring, Maryland. There he supervised the engineering of sophisticated telemetry and surveillance receiving equipment. Previously he had been Vitro's Chief Engineer, a Project Manager for Friez Division of Bendix Aviation, and a consultant on transistor power supplies. His experience in communication engineering covers military and commercial equipment across the frequency spectrum. Among his personal designs are Doppler and four-octave surveillance receivers, and two closed-circuit TV systems.

Mr. Dudeney attended Wandsworth College, London, England, where he was awarded a Higher National Certificate in Electrical Engineering with endorsements in Mechanics and Physics. He is a member of the Institute of Electrical Engineers, and is a Registered Professional Engineer.

❖

Harold L. Flowers (A'43–SM'50), formerly director of weapon systems for the Goodyear Aircraft Corporation in Akron, Ohio, was recently named general manager of engineering for the Electronics Operation of Avco's Electronics and Ordnance Division, Cincinnati, Ohio.




H. L. FLOWERS

Mr. Flowers is a native of Hickory, N. C., where he attended Lenoir Rhyne College and then went on to

(Continued on page 50A)

Yours in this NEW STANDING WAVE INDICATOR

- **Pinpoint resolution for precise attenuation measurements**
- **Scale expansion with no "blind spots," no resetting**
- **Built-in bolometer protection**
- **AC or battery operation**
- **All-solid-state design**



Model 415C Standing Wave Indicator is a new high-gain, low-noise solid state amplifier and voltmeter calibrated for square-law detectors to read directly in SWR or db. The amplifier is tunable, 980 to 1,020 cps, for matching source modulator or for optimizing several instruments in one system. Variable bandwidth (15 to 100 cps) permits both high sensitivity testing and swept-frequency work.

For highest resolution on precise attenuation measurements, you can expand to full scale each 2.5 db portion of any 10 db range with no "blind spots," and the reference is maintained automatically! This expansion gives you 24 calibrated ranges, 0-60 db, in 2.5 db steps. The 415C also reads directly in SWR; it is ideal for measuring reflection coefficient and extremely useful as a null indicator for audio-frequency bridges.

Two peak-limited bias currents, readable on the front-panel meter and adjustable ± 10%, prevent accidental bolometer burnout. Other inputs permit operation with crystals and as a null detector.

The 415C has both an ac output for use as a high-gain tuned amplifier and a dc recorder output. High stability with line changes makes the instrument ideal for long-term monitoring. An internal battery pack (optional) makes the 415C completely portable. It is housed in the new hp modular cabinet, which can mount in half of a rack 7" high, combining conveniently in a single rack width with such companion instruments as hp 431 Power Meter.

SPECIFICATIONS

Frequency:	1,000 cps ±2% by front-panel control. Special-order frequencies available between 400 and 1,500 cps.
Sensitivity:	0.1 μv rms at 200 ohms and 30 cps bandwidth.
Noise Level:	5 db below full scale at 0.1 μv rms sensitivity, minimum bandwidth.
Bandwidth:	Variable, front-panel control, 15 to 100 cps.
Range:	70 db. Input attenuator for 60 db in 2.5 db steps, accuracy ±0.1 db/10 db step. Maximum cumulative error, ±0.2 db.
Expand Accuracy:	±0.05 db from normal to 0.1 db expand; ±0.1 db from normal to other expand ranges
Meter Scales:	SWR 1-4; SWR 3-10; expanded SWR 1⅓ db 0-10; expanded db 0-2.5. Bolo current.
Input:	"Bolo"—200 ohms, bias 8.7 or 4.3 ma; "Crystal"—200 ohms for crystal rectifier; "200 Kilohm"—for crystal rectifier as null detector.
Outputs:	DC (1 ma full scale) for recording. AC (0.25 v rms for full scale deflection) for swept-frequency scope presentation.
Size:	7½" high, 6½" wide, 12½" deep. Weight, 5 lbs.
Accessories Available:	Battery pack.
Price:	$325.00.

Data subject to change without notice. Prices f.o.b. factory

HEWLETT-PACKARD COMPANY

1085D Page Mill Road Palo Alto, Calif., U.S.A.
Cable "HEWPACK" DAvenport 6-7000

Field representatives in all principal areas

HEWLETT-PACKARD S. A.

Rue du Vieux Billard No. 1 Geneva, Switzerland
Cable "HEWPACKSA" Tel. No. (022) 26. 43. 36

FOR YOUR MAGNETIC SHIELDING PROBLEMS...

MUMETAL

IS THE ANSWER!!!

Instant relief to interference caused by extraneous magnetic fields is the net result of shields made of Allegheny Ludlum's Mumetal. These shields protect components against stray external fields or prevent neighboring parts from being affected by a field-generating component inside the shield. In electronics, Mumetal and shielding are practically synonymous terms.

To develop its optimum shielding properties, Mumetal must be properly annealed in a pure, dry, high temperature hydrogen atmosphere after fabrication. When properly annealed, Mumetal has extremely high permeability and is capable of attenuating stray fields to negligible proportions.

In general, high permeability, shielding excellence and strain sensitivity go hand in hand. In the optimum condition, Mumetal is relatively soft. Shields in this condition should be handled with care in order to preserve high permeability and optimum shielding efficiency.

In many applications, fabricating or field conditions are encountered which make it impossible to avoid straining the material after the high temperature hydrogen anneal. Even when strained, Mumetal shields remain effective, with just a small loss of permeability.

The inherent ductility of Mumetal offers fabricating advantages in forming, drawing, and spinning operations.

For all your shielding requirements, insist on Allegheny Ludlum Mumetal. And for more information, ask for a copy of EM12, a 20 page technical Blue Sheet describing Mumetal, its properties, annealing details, etc. Write ***Allegheny Ludlum Steel Corporation, Oliver Bldg., Pittsburgh 22, Pa., Address Dept. IRE-12.***



ALLEGHENY LUDLUM

PIONEERING ON THE HORIZONS OF STEEL





LOOKING FOR BUBBLES ANTENNA SEAL TEST

In the seal test to qualify for the supersonic B-58, Transco L-band antennas are placed in a chamber evacuated to 28.88 inches of mercury (75,000 ft.). Ice cubes keep the water between 33° and 40° so that it will not boil while the test engineer checks for air bubbles. Transco engineers developed special epoxy sealing techniques to pass this severe test. If you have a design or development requirement for antennas or antenna sub-systems, call a Transco application engineer or representative . . . located throughout the United States and Canada . . . or write Transco Products Inc., 12210 Nebraska Ave., Los Angeles 25, California.

TRANSCO



COAXIAL SWITCHES • WAVEGUIDE SWITCHES • ANTENNAS • MICROWAVE COMPONENTS • VALVES • ACTUATORS

(Continued from page 46A)

Duke University at Durham, N. C., where he received the Bachelor of Science degree in Electrical Engineering, graduating Magna Cum Laude.

In 1939 he came to Cincinnati where he earned a cooperative fellowship at the University of Cincinnati that led to a Master of Sciences degree in Engineering in 1941. He was elected to the honorary professional societies, Phi Beta Kappa, Sigma Xi and Tau Beta Pi.

During World War II, he was associated first with the U. S. Army Signal Corps as a radio engineer and research scientist, and then with the Naval Research Laboratory in Washington, D. C., where he worked on research and development of gun laying radars, missile guidance, telemetry and missile-borne radar beacons. In 1950, he joined the Goodyear Aircraft Corporation in Akron where his most recent position was director of weapon systems.

Mr. Flowers is a member of the American Institute of Electrical Engineers and an Associate Fellow of the Institute of Aeronautical Sciences. For his work on fire control radar research at the Naval Research Laboratory, he received the Navy's Meritorious Civil Science Award in 1946.

✣

Jack Germain (S'49–A'51–SM'56) has been promoted by Motorola's Communications Division to Assistant Chief Engineer. In his new post, he supervises engineering development of mobile two-way radios.



J. Germain

He has been with Motorola since 1950, and has four patents pending. He holds an electrical engineering degree from the University of Connecticut and served as an electronics technician in the U. S. Navy. He has served as Chairman of the IRE Chicago Chapter of the Professional Group on Vehicular Communication.

✣

The appointment of **Robert Shaw Green** (S'58–M'59) to the Technical Staff of Auerbach Corporation, Philadelphia, Pa., was recently announced. Mr. Green, who is a member of the Systems Engineering Group, is involved in studies of the control, communication and switching requirements of very large-scale multicomputer systems, and in the evaluation of and recommendations for a communication and control system for the Navy.


Previously, Mr. Green had been employed by the Astro Electronics Division of Radio Corporation of America. While with RCA, he developed a disc file control unit which allows maximum efficiency of information transfer between a computer

(Continued on page 52A)



FOR RELIABLE SYSTEM DAMPING






CLIFTON PRECISION MOTOR RATE TACHOMETERS

Clifton Precision QUALITY is built into this versatile line of full drag cup type Tachometers. They feature high linearity, high output to null ratios, and low inertia.

Other attractive performance characteristics are a 20:1 signal to noise ratio in standard units with ratios up to 100:1 available on special order. Power consumption is also lower than average, being 1.2 watts in typical units.

Current leakage as a variation with temperature has been significantly reduced in these units by use of a new magnet wire. See performance curves below.

Write or call for further information on these quality units to: area 215 MA 2-1000, TWX LNSDWN, PA. 1122(U) or our Representatives.



cppc

CLIFTON PRECISION PRODUCTS CO., INC.

Clifton Heights, Pa.

EMERGENCY LIGHTING & POWER *Anywhere Automatically*

with ATR EMERGENCY LIGHTING & POWER UNIT



Illustrates ATR Emergency Lighting and Power Unit, Model ETS complete with lamps.



for PA SYSTEMS, INTERCOMS and SWITCHBOARDS



for TIME CLOCKS and OTHER RECORDING CLOCKS



for HOSPITAL OPERATING ROOMS

Completely Automatic Standby-Power Units Specially Designed to Permit the Instantaneous Continued Operation of Critical Lighting Equipment, PA Systems, Amplifiers, Intercom Systems, Burglar Alarms, Fire Alarms, Synchronous Electric Clocks, Electric Time and Recording Clocks, Incubators, Gas Valves, Telephone and Test Equipment, and Similar Critical Devices in the Event of 115 Volt AC Commercial Power Line Failure. For Use: In Hospitals, Banks, Hotels, Theatres, Factories, Office Buildings, Schools, Homes, and Many Other Areas of Operation.

SEE YOUR JOBBER OR WRITE FACTORY

• "A" Battery Eliminators • DC-AC Inverters • Auto Radio Vibrators

ATR ELECTRONICS, INC.
Formerly American Television & Radio Co.
Quality Products Since 1931
ST. PAUL 1, MINNESOTA—U.S.A.

IRE People

(Continued from page 50A)

and a disc storage system. He had prime responsibility for the system and logic design of a prototype analyst console to be used by Army Intelligence analysts. He formulated the requirements for an RCA multi-console system using the MOBIDIC computer and consoles. In addition, he had acted as RCA intra-company consultant for determining the machine factors affecting information retrieval with reference to MOBIDIC instruction and systems options. Earlier in his career, he had been engineering consultant for the Mettler Instrument Corporation, designing switching and logic circuits for the control of materials handling machines.

Mr. Green received his Bachelor's degree in Economics, Politics, and Engineering at the Massachusetts Institute of Technology, and his Master's degree in Electrical Engineering at the Columbia University School of Engineering. He also did post-graduate work in computer design theory, advanced engineering, and law.

❖

The appointment of **Kenneth D. Greenhalgh** (M'56) as Manager of the newly established Undersea Acoustics Systems Engineering Subsection of the General Electric Company's Heavy Military Electronics Department has been recently announced. The new Subsection will be responsible for studying and evaluating all undersea warfare techniques and equipments for combating enemy submarines as well as all types of underwater acoustic devices and underwater mine detection and location methods.




K. D. GREENHALGH

Mr. Greenhalgh has played a major role in establishing General Electric's leadership in the sonar field. Graduated from Purdue University in 1942 with a Bachelor of Engineering degree in Mechanical Engineering, he joined General Electric in 1946. Following two years on the Creative Engineering Program, Greenhalgh worked in the Company's General Engineering Laboratory on remote handling equipment, automatic machinery, and acoustic transducers for use in Navy homing torpedoes, and as project engineer for the AN/UQS-1 Mine Detecting Set and the AN/SQG-5 Attack Sonar. In 1952 he transferred to the Heavy Military Electronics Department and was named manager of Sonar Development Engineering in October 1953.

He is a member of the American Society of Mechanical Engineers.

❖

T. A. O. Gross (M'45) was recently elected President of the newly formed Spectran Electronics Corp. which will manufacture magnetostrictive components and multiple filter spectrum analyzers. Prior to joining Spectran, Mr. Gross was with Raytheon Company as manager of electromechanical components operations, and as manager of advanced development in the Missiles Systems Division. He has also served as a consultant to the Department of Defense on magnetics and electronics.



T. A. O. GROSS

Mr. Gross received the B.S. degree from Bowdoin College, Brunswick, Me., in 1940. He holds 25 U. S. and foreign patents in the fields of magnetics and electronics.

The Spectran Vice President and Treasurer is **Frank R. Stevens** (M'56), who has been manager of sales development and manager of the new products department of Raytheon electromechanical components operations. He has also been with the Raytheon Missile Systems Division and with the Dewey and Almy Chemical Company.

James C. Davis, Jr. (A'45–M'55) is Chief Engineer of Spectran and will continue his creative work in the development of new magnetostrictive components. He has a number of inventions to his credit

(Continued on page 54A)

broaden the scope of your technical knowledge through Convenient, Accredited CREI Extension Programs

Prepare for new responsibilities by supplementing or up-dating your education with CREI advanced, specialized courses. Flexible Home Study Programs will fit your busy schedule.

ELECTRONIC ENGINEERING TECHNOLOGY including:
NUCLEAR ENGINEERING TECHNOLOGY
AERONAUTICAL AND NAVIGATIONAL
SERVOMECHANISMS AND COMPUTER
ENGINEERING MATHEMATICS
AUTOMATION AND INDUSTRIAL
ELECTRONICS
COMMUNICATIONS • TELEVISION


HOME STUDY PROGRAMS • RESIDENCE SCHOOL


For full particulars write to:
THE CAPITOL RADIO ENGINEERING INSTITUTE
ECPD Accredited Technical Institute Curricula • Founded 1927
3224 Sixteenth St., N.W., Dept. 2612H
Washington 10, D.C.


HAVE NARROW-BAND FILTER PROBLEMS?

A Midland "off the shelf" miniature crystal filter may be your answer to conserving space and reducing material and manufacturing costs

The Type FB Series is a group of hermetically sealed, eight-crystal, narrow-band filters that provide bandwidths in the range of 2 KC to 30 KC @ 6db, with a center frequency of 10.7 MC. Miniature in size, they are designed to operate in the environmental temperature range of −55°C to +90°C, with an insertion loss of 4db max. and an inband ripple of .8db max. Their specified ultimate rejection is 105db min. The type FB narrow-band crystal filter is ideally suited for design in two-way communication systems, telemetry systems, electronic instrumentation equipment and other applications where small fractional bandwidth filtering plus a high degree of selectivity and temperature stability is required. For further application information, write for ENGINEERING BULLETIN NO. NBS-102.







Specifications

	FB-2	FB-3	FB-5	FB-6	FB-8	FB-10
Center Freq.*	10.7±200 CPS	10.7±225 CPS	10.7±375 CPS	10.7±425 CPS	10.7±750 CPS	10.7±1 KC
BW @ 6 db Min.	2 KC	5 KC	13 KC	15 KC	20 KC	30 KC
BW @ 60 db Max.	3.6 KC	9 KC	23 KC	27 KC	36 KC	53 KC
60 db/6 db BWR Max.	1.8	1.8	1.8	1.8	1.8	1.8
BW @ 80 db Max.	4.5 KC	11.3 KC	26 KC	31 KC	41 KC	60 KC
Ultimate Rejection Min.	105 db	105 db	105 db	105 db	105 db	105 db
Req. Source/Load Resistance (R_o)	130 ohms	330 ohms	1 K ohms	1 K ohms	1.3 K ohms	2 K ohms
Inband Ripple Max.	.8 db	.8 db	.8 db	.8 db	**.8 db	***.8 db
Insertion Loss Max.	4 db	4 db	4 db	4 db	4 db	4 db
BW @ 1 db Min.	1.5 KC	3.8 KC	10 KC	11.5 KC	15 KC	21 KC


* Center freq. is the arithmetic mean of the frequencies at 6 db.
** 1.5 db max. ripple at the operating temperature extremes.
*** 1.8 db max. ripple at the operating temperature extremes.

Operating Temp. Range: −55°C to +90°C
Shock: 200 g
Vibration: 15 g to 2 KC
Max. Input Level: +10 dbm

Midland

MANUFACTURING COMPANY, 3155 Fiberglas Rd., Kansas City 15, Kansas
WORLD'S LARGEST PRODUCERS OF QUARTZ CRYSTALS
DIVISION, PACIFIC INDUSTRIES, INCORPORATED

MID 3-61



Immediate Delivery - From Coast to Coast

The most versatile line of standard, service-proved antennas and transmission lines, complete with system components and mounting hardware, is now stocked coast to coast to assure prompt delivery ..... backed up by full time technical service personnel located nearby, ready to assist you in your program.

Write Dept. F for fully illustrated catalogs

MANUFACTURERS OF THE WORLD'S FINEST
Prodelin Inc
ANTENNAS AND TRANSMISSION LINES

Main Office: 307 Bergen Ave., Kearny, N. J. • **WY** 1-8600 • **California Engineering Offices & Warehouse Stock:** 427 W. 5th St., Los Angeles 13 • **MA** 8-3451 • 870 Tennessee St., San Francisco 7 • **AT** 2-8472

(Continued from page 52A)

and has specialized in transistor circuit development at the Missile Systems Division of Raytheon Company.

❖

The appointment of **James M. Harley** (SM'56) as manager of the systems engineering department at the Reconnaissance Systems Laboratory of Sylvania Electric Products Inc. was recently announced. In his new capacity, he is responsible for the systems synthesis and analysis and the systems engineering of the laboratory's reconnaissance and intelligence programs.



J. M. Harley


The Reconnaissance Systems Laboratory is part of the Mountain View Operations of Sylvania Electronic Systems, a major division of the company, which has over-all responsibility for systems management of GT&E's major government projects.

Prior to his present appointment, Mr. Harley managed the missile and space department of the advanced systems laboratory at the Electronic Defense Laboratories of the Mountain View Operations. Prior to joining Sylvania, he was affiliated with the U. S. Navy Electronic Laboratories in San Diego, Calif., Specialized Instruments Corp. in Belmont, Calif., and Filtron Co., Inc., in Flushing, N. Y. He has served as a consultant to various government agencies on problems of frequency assignment and mutual interference.

He holds a master's degree in electrical engineering from Stanford University and is a member of Phi Beta Kappa and Tau Beta Pi.

❖

E-H Research Laboratories, Inc., recently announced the appointment of **Stuart R. Hennies** (S'44–A'49–M'52) as Chief Engineer. Mr. Hennies came to E-H from Granger Associates where he had also served as Chief Engineer. In his capacity as Chief Engineer with E-H, he will be responsible for coordinating all projects, supervising project managers and acting as design consultant to the project managers in all areas of the Company's technical activities.



S. R. Hennies

As Chief Engineer with Granger Associates, he was responsible for ECM systems, radio propagation research and high frequency communication systems. Prior

(Continued on page 56A)

WHEN THE HEAT'S ON DEPEND ON THESE CTS CERMET RESISTORS

with Space Age 500° C High Stability Metal-Ceramic Element

CTS cermet resistors have exceptionally high stability and reliability . . . tested extensively and proven under extreme environmental conditions . . . achieved by a unique, rugged, hard-surfaced metal-ceramic element processed at over 600°C. Specially adaptable to miniaturization because of high load and heat capabilities in small areas. Wide resistance range.



CERADOT

Solid Cermet Fixed Resistors


50 ohms thru 100K ohms.

.050" dia. x .030" L. Other sizes available with or without leads.

Power rating: 1/10 watt at 125°C.

Kit of 8 different resistance values available at nominal cost.

Request Data Sheet 185 for technical specs.



CeraTrolS®

Series 400


3 Watt 1¼" dia. Semi-Precision Military Variable Resistor

Interchangeable with Style RV4 MIL-R-94 but far exceeds temperature and stability requirements.

Available with 1%, 2% or 3% linearity.

Power ratings: 3 watts at 85°C, 2 watts at 125°C, derated linearly to zero load at 175°C.

Request Data Sheet 179 for technical specs.




CERAFER

Modular Fixed Resistors

- 5 to 300,000 ohms resistance per square. Resistance of 10 ohms to 1 megohm available in short straight paths without resorting to lattice or grid patterns.
- Unaffected by solvents, potting compounds or corrosive atmosphere.
- Resistant to nuclear radiation and high vacuum conditions.

Kit of 10 different resistance values—10 wafers with 2 identical resistors per wafer—available at nominal cost.

Request Data Sheet 181 for technical specs.




CeraTrolS

Series 500

1½ Watt ¾" dia. Semi-Precision Military Variable Resistor

- Interchangeable with Style RV5 MIL-R-94 but far exceeds temperature and stability requirements.
- Available with 1%, 2% or 3% linearity.
- Power ratings: 1½ watts at 85°C, 1 watt at 125°C, derated linearly to zero load at 175°C.

Request Data Sheet 180 for technical specs.



CERATRIM

Series 170

42-Turn 150°C Square Trimmer Resistor

- Available with wire leads or p.c. pins out bottom or side.
- Power Rating: 1 watt at 50°C derated linearly to zero load at 150°C.

Request Data Sheet 178 for technical specs.



CeraTrolS

Series 600

¾ Watt ½" dia. Military Variable Resistor

- Interchangeable with Style RV6 MIL-R-94B but far exceeds temperature and stability requirements.
- Power ratings: ¾ watt at 85°C, ½ watt at 125°C, derated linearly to zero load at 175°C.

Request Data Sheet 175 for technical specs.



CERATRIM

Series 180

25-Turn 200°C Rectangular Trimmer Resistor

- Available with p.c. pins or wire leads.
- Power Rating: 1 watt at 125°C derated linearly to zero load at 200°C.

Request Data Sheet 177 for technical specs.

Founded 1896

CTS *Corporation*

Elkhart, Indiana

Factories in Elkhart & Berne, Indiana; South Pasadena, California; Asheville, North Carolina and Streetsville, Ontario, Canada.

Sales Offices and Representatives conveniently located throughout the world. CTS specialists are willing to help solve your cermet resistor problems.

FXR's FIXED PRECISION ATTENUATORS

6*



Series 175

- OPERATION: Full waveguide bandwidth
- WAVEGUIDE RANGE: 2.6 KMc to 90.00 KMc
- Values factory set between 0.3 and 30.00 db
- Absolute accuracy (including frequency sensitivity)
  ±0.3 db for values to 20 db
  ±0.5 db for values 20 to 30 db
- VSWR: 1.15 max

*

No. 6 of a series of FXR's new precision microwave components designed to meet the ever-growing needs of the microwave industry.

FXR's Fixed Precision Attenuators find use in standardizing the testing of attenuators, directional couplers and similar instruments in the laboratory or on the production line. Attenuation values are almost completely determined by the angular position of an attenuation film in a cylindrical waveguide and are insensitive to frequency or the characteristics of this absorbing film.

MODEL NO.	FREQUENCY RANGE KMc	WAVEGUIDE TYPE RG-( )/U	PRICE
S175A	2.60–3.95	48	$365.00
H175A	3.95–5.85	49	240.00
C175A	5.85–8.20	50	135.00
W175A	7.05-10.00	51	115.00
X175A	8.20-12.40	52	95.00
Y175A	12.40-18.00	91	115.00
K175A, AF	18.00-26.50	53	240.00
U175A, AF	26.50-40.00	96	250.00
Q175A	33.00-50.00	97	475.00
M175A	50.00-75.00	98	425.00
E175A	60.00-90.00	99	675.00

Write for Catalog Sheet No. 175

FXR

THE RF PRODUCTS AND MICROWAVE DIVISION
AMPHENOL-BORG ELECTRONICS CORPORATION

25-26 50th Street, Woodside 77, N.Y.
RAvenswood 1-9000 • TWX: NY 43745

IRE People

(Continued from page 54A)


to his appointment as Granger's Chief Engineer, he developed systems using high power negative grid and traveling wave tubes and for a period of time acted as Manager of Application Engineering.

He was associated with Varian Associates from 1951 through 1956, first as a Microwave Tube Design Engineer specializing in reflex klystrons and later as an Applications Engineer concerned with the utilization of klystrons in radar and microwave relay systems. Prior to 1951, he was with Northrop Aircraft Company where he first served as Radio Control System Project Engineer and later as Assistant Leader of the Telecommunications Group. During World War II, he served with the U. S. Navy as a Radar Maintenance Officer.

A graduate of the University of California with an M. S. Degree in Electrical Engineering, Mr. Hennies is an Associate Member of Sigma Xi.

❖

Philip S. Hessinger (SM'59) has been named a Vice President of National Beryllia Corporation, Haskell, N. J. National Beryllia manufactures beryllium oxide and other high-purity oxide ceramics and ceramic - to - metal assemblies for electronics, nuclear, chemical and metallurgical laboratory, and pyrometry applications.



P. S. HESSINGER

Mr. Hessinger, Vice President and Manager, Research and Development Division, joined National Beryllia in 1960 following ceramic and allied research work and research management at the Ohio State University Research Foundation, Wright Air Development Center, and Mycalex Corporation of America. A graduate of Alfred and Ohio State Universities, he is a member of the American Ceramic Society, the National Institute of Ceramic Engineers and the American Society for Testing Materials.

❖

Captain W. C. Hilgedick, U.S.N. (A'29–SM'47) returned on July 1, 1961 to Lincoln Laboratory, MIT, as Navy Representative. He had been a member of that office from 1952 to 1956.

A graduate of the University of Minnesota with a B.E. degree, Captain Hilgedick did a year of postgraduate work in physics at Tulane. He was a practicing radio engineer at the time he was called to active duty in 1941. The Captain says that his first active naval experience was getting sunk at Pearl Harbor on December 7, 1941.

In 1942, he was ordered into the Bureau of Aeronautics and assigned to the Airborne Radar Program. Subsequently, he headed the Airborne Radar Engineering Branch and then the Electronics Development Laboratory at the Naval Air Development Center, Johnsville, Pa. For two years, before coming to Lincoln, he was attached to the American Embassy, London, in the office of the Naval Attaché, covering electronics research and development in the European theater.

From Lincoln Laboratory, he returned to the Bureau of Aeronautics as head of the Ground Electronics Division. In 1958, he was assigned to the Office of the Secretary of Defense Research and Engineering under Dr. York, in the Office of Foreign Programs. In this capacity, he supervised the Navy's part in the Mutual Weapons Development Program for bilateral participation in technical and financial support of research and development programs which were being conducted in continental NATO countries.

In 1961, Captain Hilgedick was ordered to the Office of Naval Research, Boston Branch, to relieve retiring Captain G. K. Williams, the Commanding Officer. On July 1, 1961, he assumed command of that activity and also the collateral duty as Navy Representative at Lincoln Laboratory.

❖

George H. Houseworth (A'48–M'55–SM'57) has recently received a Navy Sustained Superior Performance Award which was presented at the U. S. Naval Training Device Center, Port Washington, N. Y. The award was based on his work as a member of the Special Projects Office of the Center. He has recently been promoted to the position of Head, Land Warfare and Missile Systems Trainers Division.

Mr. Houseworth received the B.S. and M.S. degrees from the Polytechnic Institute of Brooklyn.

❖

James L. Kimball (S'48–A'50–M'58) project engineer for Cohu Electronics, Inc., Kin Tel Division, has been promoted to assistant chief engineer, it was recently announced. In his new position, he will be responsible for coordinating all engineering activities for Kin Tel.

Kimball has been a design specialist and project engineer for the past six years at Kin Tel, except for a short period when he was supervisor of supporting systems at United Aircraft Corporation's Missiles and Space Division, East Hartford, Conn.

Previously, he was engineer with General Dynamics in San Diego and Pomona on missile test equipment and radar systems, and a field engineer with Northern Natural Gas Company, Omaha, Neb. He earned a B. S. degree in electrical engineering in 1949 from the University of Nebraska and served three years in the U. S. Air Force during World War II.

Kimball is a member of the American Rocket Society.

❖

David G. Koch (S'43–A'45–M'55) has recently been named director of marketing for the Litton Industries Electron Tube Division. He will direct the marketing of klystrons, magnetrons, traveling wave

(Continued on page 59A)

Submarine Cables for Communications, Control & Power



Since 1954 alone, more than 15,000 miles of submarine cable have been delivered from Simplex Wire & Cable Company's Submarine Cable Division at Portsmouth, N. H., the only modern U. S. plant specifically designed for submarine cable production.

SCD offers *complete* capabilities for both commercial and military underwater cable technology...cable and fitting design and manufacture ...laying techniques and supervision for laying... splicing instruction and equipment...planning, manufacture, and emplacement of complete submarine cable systems.

SCD has wharfside facilities for loading two ocean cable ships simultaneously from tanks capable of storing more than 3000 miles of finished cable.



Simplex
WIRE & CABLE CO.
SUBMARINE CABLE DIVISION
Portsmouth, New Hampshire
EXECUTIVE OFFICES: CAMBRIDGE, MASS.

Write today for your free copy of the new SCD Brochure, detailing facilities and capabilities.



Just like $103 million in the bank

In the past 4½ years, Hughes has put more than 7,000 cost improvements into practice—saving $103 million in defense and space dollars. Prudent management *avoided* these expenditures.

Savings like these in money, materials, time and human energy don't just happen. At Hughes, cost improvement is a corporate way of life. From top to bottom, in all plants and departments, employees submit ideas and suggestions without thought to personal gain. A comprehensive, fully organized program encourages these ideas, evaluates them and makes them work.

Typical ways in which cost improvements were applied: Machining time on a wave guide was cut from 3½ hours to 32 minutes each—saving $41,201. Application of a Preferred Parts Program simplified specifications and rationalized tolerances and performance standards—result, $40,000 saved the first two months. One radar reflector dish was redesigned to fit two different units—saving $117,000.

Each improvement results in lower contract costs. Some of the major defense programs that benefit include the Polaris, Titan, Falcon and Mauler missiles, new 3-D radar-computer systems now in service on Navy ships and automatic armament controls for Air Force interceptors.

And new Hughes space projects—the Surveyor moon landing vehicle, the Syncom communications satellite, the ion engine for long space journeys—all will deliver full value for every dollar.

Creating a new world with electronics

HUGHES



Hughes is hiring, but for those who do not wish to make application at the present time and who would like to be notified of future openings in their areas of interest, we maintain an Engineering and Scientific Register. To obtain information regarding current openings or the Register, write to S. L. Gillespie, Dept. N, Hughes Aircraft Company, Culver City, California.

IRE People

(Continued from page 56A)

tubes and other microwave and display devices, which are key components in radar, communications, navigation and other vital defense systems.

Mr. Koch comes to Litton Industries from the Electron Tube Division of Radio Corporation of America, Lancaster, Pa. He was associated with RCA for more than 18 years in engineering, sales and marketing positions, most recently as manager of market planning for microwave tubes.

An electrical engineering graduate of the University of Wisconsin, he received his master's degree in Industrial Management at Stevens Institute of Technology, Hoboken, N. J. He also completed a graduate course in sales and marketing management at the University of Syracuse.

❖

Norman B. Krim (S'33–A'38–M'55) vice president of Raytheon Company, has recently become president and chief executive officer of Radio Shack Corporation. Milton Deutschmann, who founded the electronic distribution firm more than 25 years ago, will retain his position of chairman of the board.



N. B. Krim

Mr. Krim, who joined Raytheon in 1935, has been a vice president of that company since 1950. From 1948 through 1958 he was responsible for Raytheon's sales, manufacturing and engineering of distributor products, receiving tubes, semi-conductors, industrial tubes, and cathode ray tubes. He founded Raytheon's industrial tube and semi-conductor divisions. He holds five United States patents on subminiature tubes. Since 1958, he has played an important part in the Machlett Laboratories acquisition, formed Raytheon's joint venture in addition to corporate studies in Argentina, Brazil, India, and Italy.

Mr. Krim graduated in the Honors Group in 1934 from the Massachusetts Institute of Technology with an S.B. in Electrical Engineering. He has also attended the M.I.T. Graduate School, specializing in electronics and is an alumnus of the Harvard Business School's Advanced Management Program.

Mr. Krim is a member of Tau Beta Pi and Sigma Xi.

Mr. Krim was awarded the Certificate for Exceptional Service to the Naval Ordnance Development in 1945 for his work on the proximity fuse tube.

❖

Dr. Earl R. Lind (S'54–M'56) has joined Electro-Mechanical Research, Inc., as systems analyst on the staff of Dr. Glenn E. Tisdale, manager of the Engineering Department of the Systems Division.



E. R. Lind

Dr. Lind holds BS and MS degrees from the Michigan College of Mining and Technology and a Ph.D. degree from the University of Wisconsin.


Prior to accepting his present position he was a lead engineer at the Advanced Electronics Center of the General Electric Co., Ithaca, New York. His duties there were in the areas of systems analysis and synthesis of missile guidance systems and of radar data processors and correlators for synthetic antenna high-resolution systems and advanced antijamming radar techniques.

In his initial assignment at EMR, Dr. Lind will be engaged in systems analysis of the test-instrumentation subsystem being designed and produced for The Boeing Company's Dyna-Soar space glider.

Dr. Lind is a member of the American Institute of Electrical Engineers and the Research Society of America.

❖

The appointment of **L. H. Lynn** (SM'47) as Manager of the newly established Ordnance Radar Systems Engineering Subsection of the General Electric Company's Heavy Military Electronics Department has been recently announced. The new Subsection will be responsible for designing and developing radars to be used in firing any ground-based ordnance such as field artillery, mortars, air defense missiles, short range tactical missiles, and anti-missile missiles.



L. H. Lynn


Mr. Lynn has contributed to many of General Electric's advances in military communications and electronic systems engineering during his 35 years with the Company. Since 1947 he has supervised the design and development of large ground-based radars such as the AN/FPS-6 Height Finding Radar, the 1-megawatt AN/FPS-8 Search Radar, the AN/FPS-24 Frequency Diversity Radar, and the advanced Nike-Hercules acquisition radar.

Mr. Lynn's long experience in military electronics also has included test, development and design of a variety of equipments such as the BC-191 and BC-375 aircraft transmitters, the Navy SC radar, the Signal Corps armored vehicle radio SCR-506, shipboard transmitters, receivers, radar navigational aids and depth sounders.

He was graduated from Washington University in 1926 with a Bachelor of Science degree in Electrical Engineering.

❖

(Continued on page 60A)



PACE
PANEL METERS
FOR INDUSTRY · LABORATORY · COMMUNICATION

PACE Meters are available in both standard Hi-Torque, external magnet, D'Arsonval type movement or in PACE Magne-Core®, self-shielding, internal magnet design.

An experienced applications-engineering staff is ready to assist in selection of the PACE panel meters best suited to *your* specific needs—whether they be custom meters produced to your specifications or stock meters available at many industrial electronic parts distributors.

Prompt attention and quotation service is given to all inquiries.

Write for new complete catalog P-61.

PACE
METERS BY
PACOTRONICS

PACE ELECTRICAL INSTRUMENTS CO., INC.
A subsidiary of Pacotronics, Inc.
70-31 84th St., Glendale 27, N.Y.

PRECISION
TEST EQUIPMENT

The finest in performance, quality and value. Precision makes all the instruments you need:

- *for Industrial Electronics*
- *for Communications*
- *for F M Radio*
- *for A M Radio*
- *for Monochrome T.V.*
- *for Color T.V.*

Available and on display at leading electronic parts distributors throughout the world.

PRECISION
TEST INSTRUMENTS BY
PACOTRONICS

PRECISION APPARATUS COMPANY, INC.
A DIVISION OF PACOTRONICS, INC.
70-31 84th Street, Glendale 27, L.I., N.Y.

IRE People

(Continued from page 59A)

Dr. Jack Munushian (S'52–A'54–M'60) has been named head of the Solid State Electronics Department at Aerospace Corporation, El Segundo, Calif., it was recently announced. The department is responsible for advanced research in areas of thin films, superconductivity, semiconductor devices and infra-red components.



J. MUNUSHIAN

For the past seven years, Munushian headed the Applied Physics Department at Hughes Aircraft Company. His fields of work have included low temperature physics, traveling wave tubes, microwave circuits and electronic antenna scanning systems.

Munushian earned his Ph.D. degree in electrical engineering at the University of California at Berkeley and his B.S. degree in physics at the University of Rochester, New York. He belongs to the American Physical Society.

❖

William A. Ogletree (A'49–M'55) has been appointed General Manager of the Sarasota Products Division of Electro-Mechanical Research, Inc., it was announced recently.



W. A. OGLETREE

Before joining EMR, he was Vice-President and General Manager of Computer Systems, Inc., Monmouth Junction, N. J. Computer Systems develops and markets a line of analog computers and associated equipment. Prior to this, he was associated with the Burroughs Corporation for seven years. With Burroughs, Mr. Ogletree held positions of increasing responsibility in the engineering, supervision, and management of digital computer projects, and was Manager of Engineering for the Military Electronic Computer Division at the time he left. He has also been associated with the Philco Corp. Research Division where his work was largely in the area of airborne digital data processing development. He has done private consulting work in medical electronics.

Mr. Ogletree holds a BS degree in physics from William and Mary and is a member of Phi Beta Kappa. He is the author of several technical articles and holds a number of patents in digital computer circuitry, and television.

❖

Dr. Satio Okada (M'57) has been named a Research Fellow in the General Dynamics/Electronics Research Division by Dr. Nisson A. Finkelstein, vice president for research and engineering.

This honor has been awarded to Dr. Okada in recognition of his accomplishments in the field of network topology. He is the first recipient of this honor which has been newly established within the Research Division of General Dynamics/Electronics. It is to be awarded to members of the Research Division staff who have made significant technical contributions in a research field over an extended period, and who have received national and international professional recognition.

Dr. Okada was born in Japan and received B.S. and Ph.D. degrees from Tohoku University, Sendai, Japan, in 1932 and 1956 respectively. He has been associated with the Japanese Bureau of Electronic Communications, with Tohoku University as a professor, and Yamagata University as head of the Electrical Engineering Department. In 1954 he joined the staff of the Brooklyn Polytechnic Institute and also served as a visiting lecturer at Columbia University. Dr. Okada became a member of the Research Division of General Dynamics/Electronics in 1960.

During the 29 years in which Dr. Okada has been engaged in his field he has published approximately 85 papers, many of which have made outstanding contributions to the understanding of electrical networks and to the development of a unifying theory of electrical engineering in terms of topological structures and relationships.

❖


Richard W. Peterson (M'58) has been advanced to Assistant Chief Engineer by Motorola's Communications Division. In his new capacity, Peterson supervises development engineering of military and commercial portable two-way radio products. He has been with Motorola since 1954. Peterson is an electrical engineering graduate of the Illinois Institute of Technology.



R. W. PETERSON

❖

Robert Peth (A'53–M'58) has been promoted to Manager of Engineering, Mobile and Portable Communications Products by Motorola's Communications Division. In this position, Peth is responsible for two-way radio product development and systems engineering. Prior to this appointment, Peth had been Chief Engineer.



R. PETH

Peth has been with Motorola in various engineering capacities since 1949. He originated and developed Motorola's

(Continued on page 62A)

To Contractors and Subcontractors on U.S. Government Projects

NEW TRANSISTOR 2N1645

■ HIGH RELIABILITY ■ ONE WATT POWER OUTPUT AT 100 MC/S
■ EFFICIENCY APPROXIMATELY 50%

The 2N1645 is a diffused base germanium mesa transistor for UHF power amplifiers, frequency multipliers, and very high speed, high current switching applications. Typical turn-on and turn-off times under constant voltage drive conditions are less than 5 and 15 nanoseconds respectively. Power output of one-half watt as a doubler may be achieved up to 250 megacycles.


MAXIMUM RATINGS AT 25°C

Collector Current	300 mAdc
Collector Voltage	35 Volts
Emitter Voltage	1 Volt
Junction Temperature	100°C
Power ($T_A = 25°C$)	1 Watt
Power ($T_C = 25°C$)	6 Watts


TYPICAL ELECTRICAL CHARACTERISTICS

f_t	600 mc
REh_{ie} (250 mc)	23 ohms
C_{cb} (dir)	10 pf
h_{fe} (1000 cps)	50
h_{FE} ($I_C = 100$ mA)	35

TYPICAL CURRENT GAIN VS FREQUENCY



FREQUENCY IN MEGACYCLES



TYPICAL CIRCUIT—
160 MC AMPLIFIER

The 2N1645 transistor may be purchased in quantity from Western Electric's Laureldale Plant. For technical information, price, and delivery, please address your request to Sales Department, Room 106, Western Electric Company, Incorporated, Laureldale Plant, Laureldale, Pa. Telephone—Area Code 215—WAlker 9-9411.

LAURELDALE PLANT

Western Electric
MANUFACTURING AND SUPPLY UNIT OF THE BELL SYSTEM

BALLANTINE True RMS VTVM model 350



Measures wide range of waveforms with 1/4% ACCURACY

For highly accurate voltage measurements, the uncertainty introduced by waveform distortion limits the use of average and peak-responding instruments. The Model 350 is a 0.25% accurate, true rms-responding instrument designed to overcome this limitation. It provides the engineer with a rugged, reliable and easy-to-use laboratory or production line instrument. It will measure a periodic waveform in which the ratio of peak voltage to rms is not over 2.

The method of measurement with the Model 350 is similar to balancing a bridge: four knobs are set for minimum indication and the unknown voltage is read directly from a 4 to 5 digit NIXIE® in-line readout. The precision exceeds the stated accuracy by 5 to 10 times. **Price: $720.**

SPECIFICATIONS

Voltage Range..... 0.1 V to 1199.9 V
Accuracy. ¼%, 100 cps to 10 kc, 0.1 V to 300 V; ½% outside these limits
Frequency Range..... 50 cps to 20 kc
Max Crest Factor 2
Input Impedance .... 2 MΩ shunted by 15 pF to 45 pF

Write for brochure giving many more details

— Since 1932 —

BALLANTINE LABORATORIES INC.

Boonton, New Jersey

CHECK WITH BALLANTINE FIRST FOR LABORATORY AC VACUUM TUBE VOLTMETERS, REGARDLESS OF YOUR REQUIREMENTS FOR AMPLITUDE, FREQUENCY, OR WAVEFORM. WE HAVE A LARGE LINE, WITH ADDITIONS EACH YEAR. ALSO AC/DC AND DC/AC INVERTERS, CALIBRATORS, CALIBRATED WIDE BAND AF AMPLIFIER, DIRECT-READING CAPACITANCE METER, OTHER ACCESSORIES. ASK ABOUT OUR LABORATORY VOLTAGE STANDARDS TO 1,000 MC.

(Continued from page 60A)

"Private-Line" system, which minimizes interference for a two-way radio system from other users on the same frequency, and the "Selcal" selective signaling system used by a number of major airlines. He is a graduate of Northwestern University.

❖

Jerome Rothstein (A'46–SM'54) has been named Vice President and Chief Scientist for Maser Optics, Inc., Cambridge, Mass. The position is a new one in the recently formed company, which performs research and development in the field of lasers and coherent optics.

Mr. Rothstein was formerly Senior Scientific Executive for Edgerton, Germeshausen and Grier, Inc. of Boston, Mass. where he conducted studies on the commercial and military applications of masers and lasers, radiation in outer space and ionic propulsion. Prior to that, he was a research physicist with the U. S. Army Signal Research and Development Laboratories, Fort Monmouth, New Jersey.

In his new position, Mr. Rothstein will be responsible for directing research in laser materials and experimental studies in novel laser sources, modulation methods, and pumping techniques.

Mr. Rothstein holds a B.S. in physics, cum laude, from City College of New York, 1938, and an A.M. in Physics from Columbia University, 1940. He is the author of over 100 technical papers and holder of numerous patents on electronic devices and instruments. He is a member of the American Physical Society and the Society of Photographic Scientists and Engineers, a Life Member of the AAAS and a Founding Member of the Biophysical Society.

❖


E. H. Schulz (A'38–SM'46–F'58) has been elected to the Board of Directors of Littelfuse, Inc., Des Plaines, Ill., fuse manufacturer. As a member of the board, Dr. Schulz will contribute greatly to the technical advancement of Littelfuse, one of the nation's largest producers of electronic circuit protection devices. Dr. Schulz is the vice president for research operations of Armour Research Foundation of Chicago.



E. H. Schulz

He received his Bachelor of Science and his Master of Science degrees, both in electrical engineering, from the University of Texas; he was granted his doctorate in the same field from the Illinois Institute of Technology in 1947.

(Continued on page 64A)



AN ACHIEVEMENT IN DEFENSE ELECTRONICS

New Transportable Radar Directs Precision Air Support

Front-line ground forces can now obtain all-weather, close air support, —when and where needed—with the new lightweight AN/TPQ-10. This is the first helicopter-transportable, high-accuracy control radar for precision air support. Developed for the U. S. Marine Corps by General Electric's Heavy Military Electronics Department, the versatile new system can also provide aircraft control for emergency supply airdrops, paratroop placements and aerial mapping. 176-07

HEAVY MILITARY ELECTRONICS DEPARTMENT
DEFENSE ELECTRONICS DIVISION • SYRACUSE, NEW YORK

Progress Is Our Most Important Product

GENERAL ELECTRIC

IRE People

(Continued from page 62A)

Dr. Schulz has served as chairman of the Electrical Engineering Department at ARF (1947–1951), responsible for such fields as electronics, servomechanism computers, electrical materials, electro-mechanical devices and industrial control. In 1951, he was asked to take over the position of acting chairman of the Physics Department, which consisted of some 65 persons engaged in research in the fields of theoretical physics, physics of solids, magnetism, light and optics, nucleonics and acoustics and vibration. He continued in that position until June, 1951, when he was named manager of a newly created Division of Physics and Electrical Engineering Research, a post he held until March, 1953, when he was placed in charge of all research activities of the foundation.

In his present position, Dr. Schulz is responsible for the research staff of 850 scientists and engineers of nine research divisions of various scientific disciplines.

He is a Fellow, American Institute of Electrical Engineers; a past member, IRE board of directors; former president and vice president, Chicago Radio Engineers Club; past president, National Electronic Conference; Fellow, American Association for the Advancement of Science; Member, American Ordnance Association; Associate, Air Force Association and a Member, Western Society of Engineers. He is also a member of the Tau Beta Pi, Sigma Xi, Eta Kappa Nu and Rho Epsilon honor societies.

❖

International Business Machines Corporation announced the appointment of **Lester H. Warren** (SM'59) as director of engineering standards. He will be responsible for the corporation's relations with industry associations concerned with engineering standards.



L. H. Warren

Mr. Warren joined IBM in 1951 as an engineer in the Vestal, N.Y., laboratory. In 1954, he was assigned to the company's product engineering laboratory in Poughkeepsie where he served in associate and staff engineering posts. Subsequently, he was promoted to project manager for standards engineering in Kingston, N. Y. In 1958, he was named manager of standards engineering for IBM's Federal Systems Division.

Mr. Warren is an electrical engineering alumnus of Pratt Institute and Cooper Union. He also attended New York University's School of Engineering. He is a member of the Standards Engineering Society.

❖

Dr. Guy Suits (SM'55–F'56), General Electric vice president and director of research, has been chosen to receive the 1962 Industrial Research Institute Medal. The award was announced October 17, at the fall meeting of the Institute by Dr. Howard S. Turner, Institute president, who is vice president for research and development of the Jones and Laughlin Steel Corporation.



G. Suits

The Industrial Research Institute cites Dr. Suits' "skill and leadership in promoting the growth of an industrial research laboratory enjoying world-wide recognition; one which has provided its scientists with the freedom, opportunity and facilities to pursue fundamental studies in many areas of science and yet is finely integrated with the company's technological requirements for growth and prosperity." In the citation of the Institute Dr. Suits is also honored "for successfully interpreting research results to company management and the general public and for varied technological advisory services to the government of his country."

As director of the General Electric Research Laboratory in Schenectady, N. Y., Dr. Suits heads a total staff of 1200, including a scientific staff of 350. In addition to his achievements in the management of scientific research, Dr. Suits is widely known for his own scientific record. As a physicist, he specialized in gas dynamics and made notable contributions both to the basic science of the electric arc and to the technology based on that science. He now has 76 patents in his name and has published many scientific articles.

During World War II, Dr. Suits served with the Office of Scientific Research and Development, for which he received both the (U. S.) Presidential Medal for Merit, and His Majesty's Medal for Service in the Cause of Freedom (G.B.). In 1946 Dr. Suits organized, staffed, and operated the Knolls Atomic Power Laboratory at Schenectady, which has since grown to a separate operating component of the General Electric Company.

He was born in Oshkosh, Wisconsin, and in 1927 he was graduated from the University of Wisconsin, where he majored in physics and mathematics, and was elected to Phi Beta Kappa, Sigma Xi, Phi Sigma Phi, and Phi Mu Alpha honor societies.

Awarded an exchange fellowship at the Swiss Federal Institute of Technology, Zurich, Switzerland, Dr. Suits was granted the degree of Doctor of Science in 1929. The following year he joined the General Electric Research Laboratory staff as an assistant to Dr. Albert W. Hull. In 1940 he was appointed assistant to the director of the Laboratory, Dr. W. D. Coolidge, and upon the retirement of Dr. Coolidge in 1945 he became director.

In 1937 he was chosen by Eta Kappa Nu, honorary engineering fraternity, to receive its award as the outstanding young electrical engineer of that year. He re-

(Continued on page 66A)


Increased Insulation
BETTER CONNECTIONS
JONES BARRIER
TERMINAL STRIPS

Leakage path is increased—direct shorts from frayed terminal wires prevented by bakelite barriers placed between terminals. Binder screws and terminals brass, nickel-plated. Insulation, black molded bakelite. Finest construction. Add much to equipment's effect.

Jones Means Proven Quality



No. 2-142



No. 2-142-¾ W



No. 2-142-Y

Illustrated: Screw Terminals—Screw and Solder Terminals—Screw Terminal above Panel with Solder Terminal below. Every type of connection.

Six series meet every requirement: No. 140, 5-40 screws; No. 141, 6-32 screws; No. 142, 8-32 screws; No. 150, 20-32 screws; No. 151, 12-32 screws; No. 152, ¼-28 screws.


Catalog No. 22 lists complete line of Barrier Strips, and other Jones Electrical Connecting Devices. Send for your copy.

Jones
HOWARD B. JONES DIVISION
CINCH MANUFACTURING COMPANY
CHICAGO 24, ILLINOIS
DIVISION OF UNITED-CARR FASTENER CORP.

December, 1961
Vol. 49 No. 12

Proceedings of the IRE

Poles and Zeros



Plasma. On those occasions when a Special Issue of the PROCEEDINGS is assembled, the Editor uses this page to say a word about the issue. On this occasion, as usual, the Editor was preparing his "gaseous discharge" when he received a copy of the excellent introduction to this Special Issue. Messrs. Herold and Dow had produced such an all inclusive introduction that the Editor's "discharge" was thoroughly quenched. Your attention, therefore, is directed to the "Introduction to the Plasma Physics Issue," page 1747.

One cannot, however, fail to emphasize and acknowledge the outstanding effort of Guest Editor E. W. Herold and his Co-Guest Editor D. G. Dow. Their work, with the cooperation of the contributing authors, has produced this unusually well balanced treatment of an increasingly important subject. Not only did these editors solicit, review, and accept the eighteen papers that comprise the issue but also they suggested the cover design. As an addenda to this issue, for those with a special interest in the propagation aspects of the subject, watch for the January, 1962, issue of the TRANSACTIONS of the Professional Group on Antennas and Propagation.

Tutorial. The Board of Editors is aware of its primary responsibility to bring to IRE members the most up-to-date material of broad general interest and the most recent advances in all phases of the art. It discharges this responsibility through the pages of the PROCEEDINGS. The Board is equally aware of its obligation to provide IRE members with the opportunity to inform themselves of the essence of areas cognate to their own specialty. To satisfy this latter need and to meet its clear responsibility the Board of Editors has evolved an extensive plan for a series of review and tutorial papers.

To initiate this plan, suggestions were solicited from the Editors of the Professional Group Transactions. This solicitation, supplemented by ideas from the members of the Board, resulted in an initial list of over thirty topics and suggestions for authors for each. The Managing Editor then began the task of inviting selected authors to prepare contributions for publication in the PROCEEDINGS for this series of review and tutorial papers. Through the splendid cooperation of L. A. Zadeh, the series started in the October, 1961, issue. Professor Zadeh, a leading authority on the subject, presented Part I of a survey of time-varying network theory.

It is the hope of the Board of Editors that this new series of papers will enhance the value of the PROCEEDINGS to IRE members. It may not, however, meet the needs and desires of all members. To assure that all subjects of interest are ultimately covered, you are invited to send in your suggestions for topics and authors to the Managing Editor.

Dreams May Come True. For many years there has been an increasing tendency to ask why the profession of radio and electrical engineering should be represented by two professional technical societies. At the grass roots there has been an effort to compensate for this situation by a growing number of cooperative ventures, and this same tendency has been spreading to regional activities as well. Nevertheless, there has been a continuing trend toward the proliferation of meetings, redundancy of subject matter, and conflict of interest where there should be solidarity and a single minded approach to the same area of interest.

October, 1961, may well be a date never to be forgotten in the electrical and radio engineering profession. During that month, through arduous work on the part of members of both IRE and AIEE, through fortuitous circumstances, and through a sincere desire to move in a direction dictated by the clear necessity of the profession as a whole, the Boards of Directors of IRE and AIEE passed resolutions looking toward the possible amalgamation of the two organizations and the formation of a single organization for the entire profession. President Berkner's letter to Section Chairmen giving the background of this entire proposal will be found on page 1743. It deserves your thoughtful consideration.

Student Affairs. Student membership in IRE continues to grow. In recognition thereof and with full realization of the significance of its program for students in the further growth and development of IRE, a new and important post has been added to the headquarters staff. The Executive Committee authorized the organization of student affairs into a separate division of the IRE administration, and the appointment of an appropriate person to be designated as Student Affairs Secretary. It is a pleasure to announce the appointment of W. Reed Crone to this newly created position. The "IRE News and Notes" section of this issue of the PROCEEDINGS provides additional detail. We welcome Mr. Crone and wish him success in this new venture.

Section News. At its meeting in October, the Executive Committee approved the petition for the formation of an IRE Section in France. The section, to be known as the French Section, is Number 111; may it grow and prosper.

Texas claims another big first! The El Paso Section held a regular section meeting at Radio Station XELO in Juarez, Chihuahua, Mexico. They believe this to be the first regular meeting of a United States Section to be held in another country. IRE goes international again!—F. H., Jr.



B. R. Tupper

Director, 1961–1962

Bertram R. Tupper (A'36–SM'46–F'54) was born in Vancouver, British Columbia, on April 15, 1906. He received his B.Sc. degree from the University of British Columbia, Vancouver, in 1928.

After graduation he was employed by the British Columbia Telephone Company in the Transmission Engineering Department. The company was interested in the possibility of serving the Northern British Columbia coast by Radiotelephone, and the North-west Telephone Company, an associate company, was formed for this purpose. As Radio Engineer for the North-west Telephone Company, he took a leading part in building up a large medium frequency point-to-point and ship-to-shore network on the B.C. Coast.

In 1942 he was appointed Radio Consultant to the joint military services in the Pacific Coast area. The Telephone Company acted as prime contractors in providing defense communication in British Columbia and as a result of these defense requirements to the off-shore islands, FM VHF radio systems were built up which provided voice and teletype circuits between the radar sites and operational bases. Since 1958, he has been Chief Engineer of the British Columbia Telephone Company, which is an affiliate of General Telephone and Electronics Corporation, and which recently absorbed the North-west Telephone Company.

Mr. Tupper has served as a member of Sir Robert Watson Watts' Canadian Air Defence Communications Evaluation Committee in 1953–1954. For two years, he has been Chairman of the Electrical Board of Examiners for the Association of Professional Engineers of British Columbia and is a past Chairman of the Vancouver Section of the IRE.

He received the IRE Fellow Award in 1954 in recognition of his application of radio techniques to the extension of toll telephone services in Canada.

Open Letter from the President

The following letter from Lloyd V. Berkner, President of the IRE, is self-explanatory with reference to the actions of the two Boards concerning the possible consolidation of the IRE and AIEE. This letter is published to provide full information to the IRE members.—The Editor

October 20, 1961

Dear Mr. Section Chairman:

At its meeting on October 18, 1961, the IRE Board of Directors took action which makes possible future joint measures by IRE and AIEE aimed towards consolidation of their resources, membership and activities into a single new professional society dealing with the whole range of radio and electrical engineering and related professional interests. At its meeting on October 20, 1961, the Board of Directors of the AIEE took similar action. The action taken by the two Boards at this time is no more than a preliminary step toward the formulation of specific proposals on which each Board and the membership of each society must act subsequently in accordance with their statutes. Nevertheless, the proposal is now at a stage that the IRE Board desires the broadest possible discussion on the part of IRE membership. The Board has therefore instructed me to communicate with the Sections asking for their views after their careful consideration of the substantive effects of the proposal. The resolution of the Board is appended hereto.

Formation of a single professional radio and electrical engineering society through combination of IRE and AIEE is a matter of major international professional importance. I shall endeavor to outline the reasons that have led the IRE and AIEE Boards to join in discussions that open the potentiality of merger of the two societies into a single professional society in our field of technology. All related factors deserve the most mature consideration. But above all, the decision should be reached primarily on the judgment of that course of action that would lead the radio, electrical and electronic profession to develop in the most healthy and fruitful fashion.

The AIEE was founded as a New York corporation in 1884 to meet the professional needs represented in a growing power, telephone and telegraph industry. AIEE now has about 65,000 members, headquarters in the new Engineering Building in New York, and resources of about $1.5 million.

As you well know, the IRE was founded as a New York corporation in 1912 to meet the professional needs represented in radio communications. IRE now has about 92,000 members, its own headquarters in New York and resources of about $4.5 million.

Because of the basic evolution of each Institute toward the broad methods of electronics, on which both societies are founded, there has been an increasing overlap of interest in the two societies. This overlap has been in evidence in a number of ways.

1) Between 5000 and 6000 engineers are members of both AIEE and IRE.
2) Some technical standards committees of the two societies deal with similar standards problems that have produced conflicts. This has led to establishment of joint AIEE-IRE standards committees. Both societies deal with overlapping standards in the international field through ASA and IEC.
3) Standards for admission in the two societies are generally equivalent and by agreement members in a given grade of one society are admitted, upon application, to the corresponding grade in the other without further examination.
4) AIEE and IRE have formed joint student branches at many universities and technical institutes to avoid the obvious conflicts of common interest that arise from similar student interests in the same university departments.
5) Both IRE and AIEE are members of the Engineers' Council for Professional Development (ECPD), where their interests are very similar.

Moreover, the rapid evolution of training in radio, electrical and electronic engineering and in applied physics, in the universities and in industry is toward an identical curriculum for members of the two societies.

6) There is a broad overlap of much of the material published by the two societies.
7) A large number of local and U. S. national meetings are jointly sponsored by IRE and AIEE. The two societies have a major problem in avoiding the duplication and unnecessary proliferation of meetings on similar subjects.
8) AIEE is evolving toward formation of technical groups, very similar in purpose to the Professional Groups of IRE. This evolution promises a great increase in the area of conflict and duplication between the two societies.

The administration of these joint activities is complex and necessarily incomplete and consuming of major time and effort of the profession. Equivalent time on positive professional programs would greatly strengthen the profession.

Moreover, the areas of conflict are steadily enlarging as the advance of electronics brings both societies ever more into the same areas of interest. Typical examples of the problems that could be avoided by synthesis of the two societies are mentioned below:

1) Under one society and one Editorial Board, the publications of the two societies could be tailored for much better coverage of our professional field. Members would have a wider choice of the type of publications individually desired.
2) Meetings in the whole field could be simplified and duplication automatically avoided. Attendance would be improved.
3) The danger of increasing overlap and conflict of the IRE's professional groups and AIEE's technical groups could be avoided. The whole field of professional specialized technical societies could be more rationally covered by 35 to 40 professional groups of the new society.
4) The administration of student sections would be simplified, and one publication, such as the IRE Student Quarterly, would serve the combined student needs.
5) Sectional activities would be simplified, the strengths of small sections enhanced, and activities in professional group chapters would become more rational.
6) Standards activities would be simplified, and dangers of conflict entirely removed, especially in view of IRE's vigorous participation in international standardization.
7) The new society would enjoy the international character of IRE with its attendant advantages. Likewise, it would carry the mantle of a "founder" society brought to it by AIEE.
8) The combined headquarters staffs could provide a much broadened service to our membership, our section organization, our professional group structure, our regional, national and international meetings, our technical committees, and our publication structure through reduction in duplication.

The synthesis of the new society would create an international professional institute with a membership of more than 150,000, an annual budget of about $6,000,000, and publications of great breadth and depth with wider opportunity for choice. The opportunities of its membership would be substantially increased within the new framework that is promised. The present office space controlled by IRE and AIEE appears sufficient to service the new institute, but with the elimination of obvious elements of duplication the service to the membership by the combined headquarters staffs would be substantially broadened.

Over the years there have been a number of joint committees charged with exploring possible areas of mutual interest, beginning with the attempt (1922) to merge the two societies in which Dr. Alfred N. Goldsmith (Founder IRE) and Professor A. E. Kennelly (then Past President of the IRE and President of the AIEE) were active. In spite of their efforts, the attempt failed because of the then preoccupation of AIEE in nonradio activities. The most recent committee was established in 1960, with Donald G. Fink as Chairman for the IRE, which seriously discussed the possibility of merger.

The emergence of electronics in the broad sense has, since that time, brought the two societies into more intimate juxtaposition. Typical is the growing preoccupation of both societies in the fields of surface and satellite communications, automatic control, computer techniques, magnetohydrodynamics and plasma physics (with its promise of nonrotating and more efficient power generation), solid-state physics, information theory, instrumentation, and a host of other new technical developments which are of common concern to both. Only merger of the two societies can avoid an ever larger scale duplication, overlap, and conflict since the membership of the two societies draw their strength in ever greater measure from the same basic scientific elements and the same educational backgrounds.

Therefore, the future of the radio, electrical and electronic professions would appear to be greatly benefited by synthesis of the two societies into a single institute.

For these reasons, the two Boards have felt that thorough exploration of a possible merger would be in the best interests of our members and of the profession.

The steps in this exploration have been as follows:

1) In January, 1961, Junior Past President Ronald L.

McFarlan, acting on my behalf, was invited to meet with the Board of AIEE in New York for discussion of mutual IRE-AIEE problems.

2) On March 20, 1961, the Board of IRE invited President Clarence Linder, AIEE, to join it at a luncheon where the mutual problems of IRE and AIEE and past history of attempts toward merger were discussed fully and frankly. At that meeting it became evident that while many mechanical problems of merger stood in the way, the professional interests of our membership should be the primary objective of closer cooperation.

3) At the Executive Committee meeting of April 27, 1961, I reported on a conversation which I had had with President-elect of AIEE Warren Chase, to explore IRE-AIEE cooperation. It was the consensus of the Executive Committee that I be authorized to appoint a suitable member of IRE to a committee, without limitations of scope, to discuss IRE-AIEE relations in conjunction with a suitably appointed delegate selected by AIEE. The Board of Directors of IRE, at their meeting the next day, April 28, concurred with the recommendation of the Executive Committee, whereupon, I appointed Dr. Patrick E. Haggerty as the IRE representative to that committee and the AIEE appointed Fellow Richard Teare.

4) Haggerty and Teare met in Pittsburgh, Pa., on May 21, 1961. During their discussion it became apparent that continued cooperation was becoming so complex to administer, and the danger of serious conflict was so rapidly increasing, that the possibilities of merger should be considered without delay. In the view of Haggerty and Teare the profession would be greatly strengthened by synthesis of AIEE and IRE into a single radio, electronic, and electrical engineering institute. They specifically recommended that Warren Chase and I appoint an *ad hoc* committee to explore this possibility more critically.

5) Upon this recommendation I acted to appoint P. E. Haggerty (now President-elect IRE) and Ron McFarlan (Junior Past President IRE) and Haraden Pratt (Secretary and Past President IRE), while President Warren Chase of AIEE appointed Clarence Linder (Junior Past President AIEE) and Richard Teare (Chairman AIEE Committee on Coordination). Chase and I served as *ex-officio* members.

6) This quasi-official Committee met in New York on September 13, 1961, to explore the problems of merger. The general recommendations were:

a) That in spite of mechanical problems, the professional advantages outweighed these problems, and that the two Institutes should move actively toward merger into a new professional society.

b) That the Committee should be voted authority by both Boards to draft statutes for a single society into which IRE and AIEE could be merged. These statutes could then be considered by the two Boards and, if satisfactory, referred to the membership of the two societies for adoption.

7) On October 18, 1961, and October 20, 1961, respectively, the IRE and AIEE Boards accepted the report. The Committee on formulation of plans for merger of AIEE and IRE into a single society has been activated with the membership shown in the resolution attached. Statutes and bylaws for eventual consideration by the Boards, publication and final action of the membership, will be drawn in the coming weeks.

As these plans have developed, I have consulted personally with many leaders and Section Chairmen of IRE. In the balance I have encountered a most favorable and enthusiastic response to the preliminary proposals. The feeling seems general that so much professional strength could be acquired by suitable action, that the mechanical problems should be appropriately solved in the interest of professional advantage.

I came away from the discussions of September 13, with the feeling that amalgamation could be accomplished without losing the vital aspects of IRE organization that have made it great. Both AIEE and IRE negotiators have approached the problem with a sense of statesmanship that would look to creation of a new institute having the best characteristics of both the IRE and the AIEE, at the same time dropping outmoded procedures. Both sides recognized that evolution of the profession requires changes from time to time that must be clearly foreseen, and undertaken promptly if the profession is to prosper.

I therefore ask you to discuss this whole matter in your next Section meeting, and advise me of your views before December 1, 1961, so that the drafting committee may have the benefit of your thinking.

Sincerely yours,



L. V. Berkner
President

RESOLUTION

WHEREAS, the Board of Directors of The Institute of Radio Engineers and the Board of Directors of the American Institute of Electrical Engineers have concluded that the advancement of the theory and practice of electrical and radio engineering, and the educational and scientific objectives of both Institutes, may be better served by a merger or consolidation of the two Institutes into one organization in which all present members would be included, and in which they would enjoy the same rights and privileges now conferred upon them

by their separate organizations, and it appearing that such consolidations would not affect the Institutes or their members, now therefore, be it

RESOLVED, that the Board of Directors of IRE deems it advisable, in accordance with the stated objectives of IRE, to move actively toward the consolidation of the activities and organization of IRE with those of the American Institute of Electrical Engineers (AIEE), by consolidation or otherwise, provided that the legal and operational problems incident to such consolidation can be satisfactorily resolved, and

FURTHER RESOLVED, that Lloyd V. Berkner, Patrick E. Haggerty, Ronald L. McFarlan, and Haraden Pratt, be and they hereby are appointed to join with Warren H. Chase, Clarence H. Linder, B. Richard Teare, Jr., and Elgin Robertson, when appointed by the Board of Directors of AIEE, as members of a committee, which shall be authorized and directed to undertake such studies as they shall deem necessary and appropriate to determine the feasibility, practicability and form of such consolidation, and to make a report thereon to the Boards of the two Institutes not later than February 15, 1962, with a view to submission to a vote of the memberships of the two Institutes, and consummation, if so approved, by January 1, 1963, and

FURTHER RESOLVED, that such committee shall be authorized to meet with the officers, directors and representatives of the two Institutes to consider the proposed amalgamation of the two groups and to make available to such persons such documents and information relating to IRE as such committee deems advisable under the circumstances, and

FURTHER RESOLVED, that this committee be directed to prepare, in consultation with representatives of IRE and AIEE, a proposed constitution and bylaws and such other documents as counsel may recommend, with a view to submission thereof to the Boards of Directors of the two Institutes on or before February 15, 1962, and

FURTHER RESOLVED, that the proper officers and directors of the Institute of Radio Engineers be and they hereby are authorized and directed to cause a copy of these resolutions to be delivered to the Board of Directors of the American Institute of Electrical Engineers, and

FURTHER RESOLVED, that these resolutions shall become effective as soon as the President of the Institute of Radio Engineers has been notified in form satisfactory to him and to counsel for the Institute of Radio Engineers that the Board of Directors of the American Institute of Electrical Engineers has adopted resolutions substantially to the effect of these presents.

Introduction to the Plasma Issue*

D. G. DOW†, MEMBER, IRE AND E. W. HEROLD‡, FELLOW, IRE
Guest Editors

THE study of the physics of ionized gases has had a long and complicated history. The word "plasma" was first coined by Langmuir and Tonks in 1929 to denote a gas in which an important fraction of the molecules are dissociated into ions and electrons, the gas as a whole remaining electrically neutral. The laboratory study of plasmas, of course, had been pursued long before that, many important discoveries in the realm of gas discharge phenomena having been made in the 1800's. These studies, continuing into the Twentieth Century as exemplified by the work of Langmuir, served as the foundation for many practical electronic devices used for the generation, rectification, and control of electrical energy. The plasmas used in these devices usually have a low-charge density, and the fractional ionization is ordinarily less than one per cent. This small percentage of ionization is sufficient to provide good electrical conductivity which can be controlled externally, but it is difficult to study theoretically because of the numerous competing processes involving neutral atoms, metastable atoms, ions, electrons, and collective oscillations of ions and electrons.

With the progress made in astronomy and theoretical physics in the early part of the Twentieth Century, it was realized that most of the matter in the Universe, that in the stars, exists in the fully ionized state. Thus, a new form of plasma physics evolved in which the study was largely theoretical, and was concerned with matter at immensely high temperatures and pressures, the latter being balanced by the gravitational forces of the stars. Much of the work currently of interest and many of the men of greatest stature in the field of plasma physics started in the field of astrophysics.

Recently the astrophysicists have tackled problems which are more earthbound, although hardly any less exotic. The advent of an understanding of thermonuclear fusion, and its possibilities for the generation of power, have created a great deal of activity concerned with high density, high temperature plasmas of terrestrial design. Since these cannot be confined by gravitational forces as they are in the stars, magnetic methods of confinement must be used, and a large amount of theoretical and experimental work has been conducted with an eye toward the generation and containment of hot dense plasmas by magnetic fields. In the U.S.A., this area of study began under the AEC-sponsored Sherwood project, which was originally highly classified, and thus developed a language and fraternity of its own before most of it was declassified in 1958.

A third group of investigators in the realm of plasma physics consists of those who were originally aerodynamicists. As airborne vehicles move faster and faster, their effect on the environment increases. One of the principle manifestations of this is the increasing temperature, eventually reaching a range in which appreciable ionization takes place, making the air conductive. The equations of gas dynamics are modified by this conductivity, and thus plasma physics is an important area of study for those in the missile and aircraft fields. In addition, the high temperatures which exist in rocket flames lead to appreciable ionization, and the conductivity of this material may be an important consideration. Recently, the desirability of extremely high velocity rocket exhaust has led to attempts to use electrically-accelerated particles for rocket propulsion.

Finally, we should discuss the field of radio propagation which has made important contributions to the understanding of plasmas and their interaction with electromagnetic radiation. It has long been recognized that portions of the earth's upper atmosphere are ionized enough to cause refraction and reflection of radio waves. The basis for much of the world's long range communication is the fact that the ionospheric layers will reflect radio signals with greater or lesser amounts of attenuation depending on the frequency, ion (and thus electron) density, and altitude (and thus the neutral density). In order to understand and make use of this phenomenon, many contributions had to be made to the understanding of the behavior of the ionosphere and the influence of a plasma on radio signals. Closely related to this has been a study of more recent origin which arises because of the high-speed aircraft and missile phenomena which concern the aerodynamicists. In spite of the plasma sheath surrounding these vehicles, we must communicate with them, and some interesting problems have been attacked, and system proposals have been evolved. The properties of this plasma sheath also result in some interesting radar return properties, with obvious military interest. (It should be noted that the word "sheath" in this context means the layer of plasma surrounding a a vehicle; much earlier, the word was used by Langmuir, and still is used by gas discharge physicists and engineers to denote the non-neutral layer which surrounds the plasma in a discharge. The reader should beware of this ambiguity.)

Plasma physics, then, might be divided up into four major disciplines, separated not so much by the concepts

* Received by the IRE, October 13, 1961.
† California Institute of Technology, Pasadena, Calif.
‡ Varian Associates, Palo Alto, Calif.

used as by their historical aims and the interests of those involved. These might be denoted by the following names: gas discharges, fusion plasma physics (including astrophysical applications), aerodynamical applications, and radio propagation plasma studies. As might be expected, this special issue of the PROCEEDINGS is aimed predominantly at the electronics engineer and emphasizes the fields most concerned with the communication and electronics arts, namely gas discharges and radio propagation. It has been our intention in laying out this issue to make it largely one in which the basic principles and known fundamentals of plasma physics are expounded as they apply to problems in these areas, without concentrating on specific devices and techniques. Wherever possible, the fundamentals are emphasized and detailed engineering concepts omitted. It is our hope that in this way an issue of reasonable size will communicate many of the basic ideas, and stimulate the reader's interest in some of the areas of plasma physics and its engineering applications.

With this background, let us scan this special issue on plasma physics.

Plasma Physics—An Elementary Review, (*Bachynski, p. 1751*). This paper summarizes most of the areas of current interest in plasma physics, and serves as a background article for almost all of the rest of the issue. The thermonuclear problem, astrophysics, propagation, noise, propulsion, and electronic devices are all treated in a form which allows the reader to grasp the basic concepts preparatory to reading the specialized articles.

Oscillations and Noise in Low-Pressure DC Discharges, (*Crawford and Kino, p. 1767*). All laboratory discharges seem to be plagued with an excess amount of low frequency noise. and in special cases, oscillation. In this paper the authors review the history of scientific investigation into this phenomenon, and present in a coherent package the bulk of present day knowledge about this noise as well as some tantalizing suggestions for controlling it. These phenomena take place in two different frequency ranges, the first generally below one megacycle and dominated in some manner by the ionic properties, and the second in the microwave range typically governed by the electron plasma frequency. The complete explanation of the source of either of these forms of noise is still lacking. However, much experimental data exists, and a qualitative picture has been presented which is consistent with the observations.

Ionic and Plasma Propulsion for Space Vehicles, (*Brewer, Currie, and Knechtli, p. 1789*). In their search for higher specific impulse (thrust per unit mass of propellant), rocket experts have turned to electrical acceleration of ions or plasmas as a potentially practical method for obtaining this objective. The engineering techniques required are an interesting mixture of electronics, power conversion, and astronautics. The authors of this paper present an outline of the basic principles underlying this line of approach, and follow with the basic system concepts appropriate to two somewhat different techniques, the ion engine in which ions are accelerated and then mixed with electrons to form a plasma, and the plasma rocket in which the neutral combination of ions and electrons is accelerated. A number of specific techniques are illustrated and the basic technological problems are presented. In this area, as with many space instrumentation problems, high efficiency, high-power electrical sources will be necessary for practical utilization of these techniques.

Transmission of Electromagnetic Waves Through an Ionized Layer in the Presence of a Strong Magnetic Field, (*Harley and Tyras, p. 1822*). This paper attacks the same problem, that is, the enhancement of propagation through a plasma by the use of a magnetic field. The plasma is approximated here by a succession of slabs so that the variations in density may be reasonably represented. A numerical calculation is given showing the transmission as a function of magnetic field for a specific model of density variation.

The Use of Magnetic Fields in the Elimination of the Re-Entry Radio Blackout, (*Hodara, p. 1825*). The effect of a plasma sheath on a re-entering space vehicle is to greatly reduce the high frequency propagation through this sheath. This paper discusses the technique of improving the communication with a space vehicle by imposing a magnetic field near the antenna which reduces the attenuation through the sheath.

RF Reflectance of Plasma Sheaths, (*Taylor, p. 1831*). As noted earlier, the plasma sheath about a re-entering space vehicle not only degrades the communication with it, but also changes markedly the radar return. This paper exhibits a calculation of the reflectance of a plane sheath which can be used as an approximation of the true sheath problem. The result is obtained in analytic form, in general as the ratio of two complex infinite series.

Mutual Coupling of Two Thin Infinitely-Long Slots Located on a Perfectly Conducting Plane in the Presence of a Uniform Plasma Layer, (*Yee, p. 1837*). The plasma sheath about a re-entering body is again considered, this time from a near-field point of view, in which the author considers the mutual coupling between two antennas located on the surface of the body. The result is expressed as a coupling coefficient between the two antennas. It is shown that the coupling is generally less than that which would exist in the absence of the plasma, provided the operating frequency is above the plasma frequency.

Antenna Noise Temperature in Plasma Environment, (*Bachynski, French, and Cloutier, p. 1846*). Again the reentry sheath is considered. In this paper, the authors are concerned with the degree to which the plasma itself contributes noise energy to the antenna. Since the sheath is at an extremely high temperature, even a small degree of coupling to the plasma may result in badly degraded noise performance. The analysis shows a peak in noise temperature in the vicinity of the plasma frequency, above which the noise is principally external, and below which it arises mostly in the vehicle. Because auxiliary

magnetic fields may also be used in these vehicles, the calculations have been extended to include the appropriate anisotropy. The noise then exhibits peaks at both plasma and cyclotron frequencies, but the structure is much more complicated, and general conclusions are harder to draw.

Generalized Appleton-Hartree Equation for any Degree of Ionization and Application to the Ionosphere, (*Shkarofsky, p. 1857*). This paper is motivated by the problems of ionospheric propagation, but may have much broader application. The author formulates the generalized equations for propagation of electromagnetic waves through a plasma, when the collisions result from both electron-neutral and electron-ion collisions in arbitrary mixtures. The analysis is compared with experimental results, and a proposal is made that ionospheric electron temperatures may be measured by correlating sufficient propagation data.

The Electrical Conductivity of a Partially Ionized Gas, (*Sengupta, p. 1872*). The problem of conductivity of a plasma is considered theoretically over the range where both electron-neutral, and electron ion collisions are important. Explicit expressions for both the real and imaginary parts of the conductivity are given in integral form. While these general forms are applicable to any degree of ionization, the author also presents expressions for the same quantities for the case that the plasma is fully ionized, in which case the conductivity may be expressed in terms of known transcendental functions.

Interaction of Microwaves in Gaseous Plasmas Immersed in Magnetic Fields, (*Rao, Verdeyen and Goldstein, p. 1887*). The 1930's saw the discovery of the Luxembourg effect, in which a strong radio transmitter passed its own modulating intelligence onto other signals whose propagation path passed over the region of the transmitter. Correctly explained as a nonlinear plasma effect (cross-modulation) in the ionosphere, the phenomenon has its modern counterpart and extension scaled down to laboratory size by use of microwaves. This paper covers basic studies of plasma characteristics in a strong 5 Gc/sec microwave field, using a weak sensing signal at 6 Gc/sec for the measurements. A magnetic field swept through cyclotron resonance is also used. The data are all taken in the inherently equilibrium state of the afterglow, using pulse techniques; thus, the rise in electron temperature due to absorption of power, and the changes in collision frequency, can be used for analytic comparison of the data with theory. Good qualitative agreement is found.

Frequency Conversion in a Microwave Plasma, (*Baird and Coleman, p. 1890*). Closely related to the above paper, is the present one in which plasma nonlinearity is used in a practical way to get microwave frequency multiplication and frequency mixing. The work indicates that the principal source of nonlinearity is modulation of the electron density at twice the drive frequency. Little or no magnetic field was used. In the experiments, a 9 Gc/sec high-level signal and 11 Gc/sec low-level signal produced a 20 Gc/sec output, about 25 to 30 db down; the same large conversion loss occurred for second harmonic generation. The values agree with those expected from this theory. Thus, the results are still rather far from useful, but it is expected that much higher power densities might improve matters.

A Plasma Microwave Detector, (*Taylor and Herskovitz, p. 1901*). In this paper, the authors describe a novel use of an activated plasma as a microwave detector. This is done in a most unusual way, by detecting the change in recombination radiation, as observed by a photomultiplier. It appears that the presence of microwaves changes the electron temperature slightly so as to reduce the recombination and to quench the light. Greatest sensitivity requires the low electron temperature of the afterglow equilibrium state. As little as a microwatt of input could be detected, which is rather remarkable even though it is considerably poorer than a video crystal. The authors point out that such a plasma detector is burn-out proof and has an extremely wide bandwidth. Several suggestions are proposed which might increase the sensitivity (with a reduction in bandwidth) but they have not yet been tried.

Interaction of a Modulated Electron Beam with a Plasma, (*Boyd, Gould, and Field, p. 1906*). There has been great interest in recent years in the use of electron-beams interacting with a gaseous plasma to produce microwave amplification. This paper describes the first successful experiments of a few years ago, in which the microwave modulation of an electron beam was increased by interaction with a "resonant" plasma. Later, traveling-wave amplification was achieved, by interaction with a slow propagating wave on the plasma column. These two different modes are compared and both theory and experiment are described. In the experiments, both helix coupling at 3 Gc/sec, and cavity coupling at 0.5 Gc/sec are employed. The observed gains of 7 db/cm in the plasma resonance case, though only half of the theoretical, are nevertheless significantly high. In the slow-wave case, about 0.8 db/cm is observed again well below theory. The discrepancies with theory are not unexpected because the theory assumes a uniform, loss-free plasma. Unfortunately, the present interactions are very noisy compared with conventional traveling-wave high-vacuum tubes.

A Method of Measurement of Flame Attenuation at 200 Mc, (*Biggs, p. 1917*). The first plasma ever produced by man on earth was the flame, *i.e.*, a gas ionized by its high temperature. Many years ago, the electrical conductivity of flame was studied, today it is once again of major importance in magnetohydrodynamic power generation or propulsion, and in missile trails. In the paper by Biggs, 200 Mc/sec measurements are described which can be used to obtain conductivity and dielectric constant of flames passing between a two-bar measuring line. Distilled water is used to calibrate, and theoretical curves are shown for electron densities ranging to 10^9 per cm^3.

Electrical Characteristics of a Penning Discharge, (*Helmer and Jepsen, p. 1920*). The Helmer and Jepsen paper concerns a most interesting type of magnetically-confined plasma known as the Penning discharge. Originally proposed as an ionization gauge, this discharge can take place at gas pressures as low as 10^{-12} mm of mercury, ordinarily considered an ultra-high vacuum. This type of discharge is the basis of the getter-ion vacuum pump. In this paper, it is shown that the trapping of electrons along the axis of symmetry is so effective that the axial potential is severely depressed. By a split anode structure, oscillations were obtained from the magnetron-like structure whose cathode is the space-charge cloud. With the normal anode, star-shaped sputtering patterns indicate that complex instabilities are present. Probably the most important result is the discovery that intense, nearly monochromatic, ion beams can be produced by such discharges.

Generation and Application of Highly Ionized Quiescent Cesium Plasma in Steady State, (*Wada and Knechtli, p. 1926*). This next paper covers work on the method of generating plasma which requires no electrical discharge. It has been known that highly ionized plasma can be generated by use of cesium vapor in the vicinity of a hot electron-emitting tantalum cathode. With two such plasma sources facing each other, and only a modest confining magnetic field, the authors show that plasma densities of 10^{12} per cm^3, and 90 per cent ionization, are obtained. This work is of importance in that such plasmas are basically quiescent, and need no applied electric field to maintain them. In practice, such plasmas are useful for physical measurements, in thermionic energy converters and in plasma sources for rocket propulsion.

A New Approach to Thermionic Energy Conversion, (*Bernstein and Knechtli, p. 1932*). The original work on high-efficiency thermionic energy converters used a self-generated cesium plasma resembling that described in the preceding paper. However, a low temperature electron emitter does not ordinarily release enough ionized cesium to make an efficient device. For a long time, workers have been trying to obtain an auxiliary source of ions which would not require too much energy to produce. In the Bernstein and Knechtli paper, such a source is described; while this work was going on, a similar concept was also explored independently in England. The structures devised appear to work well and to make a very important contribution to the low-temperature thermionic energy converter. In this paper, data on an argon plasma source are given; it is calculated that a 1500° K. cathode should be sufficient to provide an over-all efficiency of conversion of 25 per cent, if a sufficiently low work-function anode can be devised (*Editor's note:* a good low work-function anode is still a long way from realization). By modulating the plasma source, it should be possible to generate ac directly.

In concluding this Introduction, the *Editors* wish to thank the special group of reviewers who, although they must remain unnamed, are responsible for the selection of the papers, and much of the detailed editing of the papers.

Plasma Physics—An Elementary Review*

M. P. BACHYNSKI†, SENIOR MEMBER, IRE

Summary—**Although plasma phenomena have been observed in nature since the beginning of time, it is only in recent years that man has recognized the vast potential that plasmas hold for his future activities. One needs only to consider the scale of present day plasma physics experiments in order to realize the emphasis now being placed on the subject. At one extreme, there is the formation of artificial plasmas in nature such as in the Argus experiment and at the other is the study of microplasmas in tiny crystals of semiconducting material.**

This paper summarizes the role plasma physics is playing in present day scientific activities. A brief description is given of plasmas in nature, of the role of plasma physics in attempts at the ignition, control and diagnosis of thermonuclear fusion reactions, of the effect of plasmas on communication and telemetry from space and re-entry vehicles, of propulsion techniques (ionic, magneto-hydrodynamic, plasma) which utilize plasmas, and of the possibilities of incorporating plasmas in practical devices. In conclusion, the future prospects of plasma physics are outlined.

Introduction

LITTLE did prehistoric man realize, as he watched the sun, lightning discharges, the Aurora Borealis, or even his open fire, that he was observing plasma phenomena. Only in recent time has it become evident that the principal state of matter of the Universe is neither solid nor liquid nor gaseous, but plasma—a system including many free electrons and ionized atoms whose mutual interactions markedly affect its properties. This fourth state of matter probably comprises more than 99.9 per cent of the matter in our Universe.

Although an ideal plasma could readily be created in the laboratory many years ago in the form of a partially ionized gas, such investigations were not pursued very actively since the techniques for controlling a plasma were in a primitive state, and it appeared that they bore little relation to phenomena occurring on the earth. Consequently, the astrophysicists who realized the role played by ionized matter in Galactic processes were left unmolested in their ivory towers to make some of the earliest and most significant contributions to plasma physics. It remained for two very recent developments to give the necessary impetus to make plasma physics "fashionable." These were the successful creation of an uncontrolled thermonuclear fusion reaction in the form of the hydrogen bomb and the realization of large rocket thrusts which enabled vehicles to be propelled at hypersonic velocities and hence to open the door to the space age. The hydrogen bomb opened the search for techniques of controlling the thermonuclear fusion reaction for generation of electrical power on earth, while attempts to thrust further and further into space were confronted by communications and guidance problems involving plasma physics phenomena. Even the problem of propulsion in space itself has become a branch of the subject. As a result, plasma physics has become one of the most intensely investigated fields of science (see Fig. 1) with controlled experiments ranging in size from many earth diameters, such as the artificially formed plasmas in high-altitude nuclear explosions of the Argus experiment, to the minute microplasma of importance in tiny crystals of semiconducting material.




Fig. 1—(a) Plasma physics research, 1960 B.C.
(b) Plasma physics research, 1960 A.D.

This paper is intended as a short exposition of the role plasma physics is playing in present day scientific activities; of a number of the ideas presently being investigated and of some hopes for the future. A brief description is given of plasmas in nature, of plasma physics activities in attempts at control, ignition, and diagnosis of thermonuclear fusion reactions, of the interaction of electromagnetic waves with plasma and their effect on communications and on telemetry from space and re-entry vehicles, of plasma propulsion techniques, of the possible practical devices incorporating plasma properties, and of prospects for the future.

* Received by the IRE, August 14, 1961.
† Research Labs., RCA Victor Co., Ltd., Montreal, Can.

Plasmas in Nature

The Sun

The sun[1–3] and its activities, upon which the existence of life on earth fundamentally depends, is a plasma phenomenon. The visible part of the sun or the solar atmosphere can be considered to consist of three layers. The photosphere comprises the visible disk which is a few hundred kilometers thick. Present-day knowledge attributes an average particle density of $10^{16}/cm^3$ to this region with a free electron density of 10^{12} electrons/cm^3. The photosphere is thus a *plasma*. Surrounding the photosphere is a reddish ring approximately ten thousand kilometers thick above which flame-like prominences rise. This is the chromosphere, a very inhomogeneous region consisting principally of hydrogen, helium and calcium, which radiate energy due to electron-proton recombination and excitation of the light elements. Surrounding the chromosphere and extending millions of kilometers into space is a thin, hot atmosphere—the corona. The corona is very tenuous—stars are visible through it and comets traverse it unaltered. A steep temperature gradient extends from the chromosphere to the hotter corona where temperatures exceeding one million degrees exist (see Fig. 2). Although almost all




Fig. 2—Plasma between earth and sun.

known elements are seen in its spectrum, the presence of fully ionized hydrogen and helium ions is of prime significance.

It is now considered that the self-sustaining action of the sun is that of a huge thermonuclear device which releases energy by fusing together protons to form neutral helium atoms. The process can be written in short:

$$4p \rightarrow He^4 + 2e^+ + \text{energy (26.7 Mev)}.$$

This process proceeds at a slow rate establishing temperatures in the interior of the sun exceeding 20 million degrees. Due to the large mass of the sun, the force of gravity is sufficient to prevent the escape of all but the most energetic charged particles (plus radiation) from the hot plasma.

Plasma Phenomena Due to Sun's Radiation

As the ionizing radiation from the sun (principally ultraviolet and X-ray radiation) penetrates deeper and deeper into the atmosphere of the earth it encounters a larger and larger density of gas particles. As a result the radiation produces more and more electrons per unit volume. However, in this process the radiation is absorbed so that a position is reached where the rate of absorption of the radiation is greater than the rate of increase of the atmospheric density. Consequently, the rate of production of electrons decreases as one proceeds to lower altitudes. Hence there exists a height, which depends on the gas density gradient and the absorptivity of the radiation, where the rate of electron production is greatest. By this process, a great natural blanket of plasma, the ionosphere,[4–7] which envelopes the earth from an altitude of approximately 70 to over 300 kilometers, is produced. The various "layers" of the ionosphere (D, E, F in order of increasing altitude and also electron density) represent regions of ionization ranging from 10^4 to 10^6 electrons per cm^3, each merging into the next higher region without pronounced minima. An accurate, detailed explanation of the formation of the ionosphere is not yet available, although the gross features are readily accounted for.

In addition to the ionosphere, whose existence has been known for some time, recent satellite experiments have discovered other plasma effects due (at least in part) to radiation from the sun. These are the Van Allen radiation belts[8,9] (see Fig. 3) in which high-energy




Fig. 3—Van Allen natural radiation zones.

charged particles (principally electrons and protons) are trapped in regions where they execute complicated trajectories which spiral to and fro along geomagnetic lines of force across the earth's equator and, at the same time, drift slowly around the earth. The net result is an

[1] G. P. Kuiper, Ed., "The Sun" ("The Solar System," vol. 1), University of Chicago Press, Chicago, Ill., and Cambridge University Press, Cambridge, Eng.; 1953.

[2] T. G. Cowling, "Nuclear reactions in stars," *Proc. Roy. Soc. (London) A*, vol. 260, pp. 170–174; Feb. 21, 1961.

[3] J. A. Ratcliffe, Ed., "Physics of the Upper Atmosphere," Academic Press, New York, N. Y.; 1960.

[4] "The Physics of the Ionosphere," The Physical Society, London, Eng.; 1955.

[5] Proc. IRE, Special Issue on the Ionosphere, vol. 47, pp. 131–323; February, 1959.

[6] "International Symposium on Fluid Mechanics in the Ionosphere," *J. Geophys. Res.*, vol. 62, pp. 2037–2238; December, 1959.

[7] "Symposium on the Exosphere and Upper F-Region," *J. Geophys. Res.*, vol. 65, pp. 2563–2636; September, 1960.

[8] J. A. Van Allen, "Radiation belts around the world," *Sci. Am.*, vol. 200, pp. 39–47; March, 1959.

[9] P. J. Kellogg, "Electrons of the Van Allen radiation," *J. Geophys. Res.*, vol. 65, pp. 2705–2713; September, 1960.

electric current associated with the belts which should slightly modify the magnetic field at the earth's surface. Particles can escape from the belts by collision with the atmosphere and recombination to form neutral particles. Due to this slow loss, the radiation regions are maintained only as a result of a continual replenishment of particles.

Completely different origins are attributed to the two radiation belts. (The data from U. S. satellite Pioneer V indicates a third radiation region[10] surrounding the earth at a distance of 8–10 earth radii.) The inner belt is ascribed to cosmic rays, which penetrate into the atmosphere forming proton-electron pairs which are "trapped" by the magnetic field of the earth and maintained in the belts. The outer belt is thought to be due to and maintained by streams of neutral plasma consisting mainly of protons and electrons which are ejected from time to time by the sun. This belt changes considerably in extent and intensity depending on the solar activity. These streams are considered to be ejected at very high velocities (1000 km/sec) so that the particles are confined by the magnetic fields associated with such intense electric currents.

Plasma Phenomena Resulting from Solar Disturbances

The emission of radiation and particles from the sun does not by any means proceed at a uniform rate. At times the chromosphere of the sun becomes turbulent and vortices (sunspots) appear. These sunspots reach a maximum (in number and size) about every 11 years. At the maximum the sunspots are found to be concentrated principally in one hemisphere of the sun, and, as the sunspot cycle proceeds, the spots decrease in number and intensity, move nearer the sun's equator and finally disappear at a time of sunspot minimum. These disturbances then proceed to break out again in the opposite solar hemisphere reaching a peak in another eleven-year period. The total sunspot cycle thus takes about 22 years to complete.

The result of the solar eruptions is an enhanced discharge of strongly electrified particles from the surface of the sun forming strong plasma whose fields and particles permeate interplanetary space. Simultaneously, intense ultraviolet and X-ray radiations are emitted which enhance the normal ionization of the earth's atmosphere. The streams of ejected particles travel into space and on occasion are intercepted by the earth. When this happens, about a day after the solar eruption, a *geomagnetic storm* resulting in sharp fluctuations in the strength and direction of the earth's magnetic field occurs. These streams of plasma are able to find their way into a circular zone around the geomagnetic poles (the auroral zone) where electric currents of millions of amperes are generated. This seriously distorts the normal magnetic fields around the polar regions, causing the incoming particles which produce auroras to spread further and further southward. Finally, the particles become trapped in the outer Van Allen radiation region forming a ring current about the equator which falls off slowly and in a few days attains its "normal" value.

At times of sunspot maxima, particularly violent solar eruptions with the projection of hot "fireballs" of material into space are also known. These explosions give rise to the arrival of energetic particles at the earth in about 1–4 hours after the event and long before the slower but more intense main stream of plasma. The density of particles is insufficient to distort the earth's magnetic field, but the particles enter into the polar cap following along the almost vertical magnetic field lines where they cause a prompt blackout of radio communications.

During the periods of sunspot maxima, observations of the solar-induced phenomena have been organized on an international scale. The International Geophysical Year (IGY) thus has been to a large extent devoted to a study of plasmas in nature.

Thermonuclear Plasma

The Thermonuclear Process

It is well known that the nucleus of any atom is composed of a number of protons and neutrons which are held together by strong binding forces and that, by modifying the atomic structure of certain nuclei, energy may be released. In one method, the energy arises from the splitting of *heavy* nuclei into lighter fragments. This process of fission creates a net energy yield due to the fact that the mass of the original nucleus is greater than the sum of the masses of the fragments after fission has occurred. An alternate method is the combination of certain *light* nuclei into heavier components whose mass is less than the sum of the masses of the original constituents. This is the fusion process.

Of the light elements, the two isotopes of hydrogen, deuterium (consisting of one proton and one neutron) and tritium (consisting of one proton and two neutrons) appear among the leading candidates as fuels for fusion reactions. (Hydrogen itself is not practical since its rate of fusion is much slower than either of its two isotopes under the same conditions.) Reactions of principal importance for these constituents are

$$D + D \begin{cases} \nearrow He^3 + n + 3.2 \text{ Mev} \\ \searrow T + p + 4.0 \text{ Mev} \end{cases}$$

$$D + T \rightarrow He^4 + n + 17.6 \text{ Mev}.$$

In each case, energy is released, and although this energy is appreciably less than that released in a fission reaction, the energy per unit mass of fuel is greater from fusion than from fission. Since deuterium occurs in na-

[10] L. V. Berkner, "Science in Space," Goldschmidt Memorial Lecture, XIIIth General Assembly of URSI, London, Eng.; September 6, 1960.

ture (about 1 part in 6000 of the most abundant element in our universe—hydrogen) and can be readily and inexpensively separated from hydrogen, it presents an almost inexhaustible supply of basic fuel for fusion.

The fundamental goal of thermonuclear research is the production of economic power from the controlled release of fusion energy.[11–14] In addition to the low cost and abundance of the fuel required, the fusion reaction holds the promise of being inherently safe in that there would be no possibility of "runaway" reactions. The fusion products are nonradioactive and hence present no disposal problems, and furthermore a controlled fusion device offers the possibility of direct generation of electric power by the elimination of the inefficient heat cycle.

For fusion to occur, the particles must approach sufficiently close to each other for long enough time that the short-range nuclear forces interact causing the nuclei to fuse. This is the so-called Thermonuclear reaction. Due to the positive charge on the nuclei, the particles tend to repel each other strongly. In order to overcome these Coulomb forces, the particles must be made to collide at high velocities corresponding to temperatures of the order of 10^8 °K (for a Maxwellian distribution of particle energies). At such temperatures, attainable only in gases, the gas is fully ionized consisting of ions and free electrons, *i.e.*, a *plasma*. Thermonuclear research is thus concerned with the confinement, heating, and diagnosis of very-high-temperature plasmas.

Confinement

One of the major requirements for thermonuclear fusion is a means to contain the hot plasma[15–18] in a given volume for a sufficient length of time such that an appreciable portion of the nuclei will fuse together. Solid material containers are of no value for this purpose due to the cooling effect on the plasma when it comes into contact with the walls and the consequent quenching of the reaction. It is thus necessary to use a force which acts at a distance, such as gravitational or electric or magnetic fields. For masses of the size encountered in laboratory experiments, gravitational forces are much too weak to be of practical use (although these are precisely the forces which are effective in confining the plasma particles in the sun and other large stellar masses). Static electric fields act in opposite directions on positive ions and electrons causing charge separation which creates opposing fields, making this method ineffective. The only plausible schemes are those involving magnetic fields (either static or slowly varying in time) and possibly combinations of RF electric fields and magnetic fields. Some of the suggested schemes of plasma confinement will now be discussed:

1) Pinch: This is one of the earliest schemes suggested for plasma confinement.[12,13,19,20] It is based on the principle that a current flowing in a conductor produces its own magnetic field which encircles the current [see Fig. 4(a)]. This magnetic field exerts an inwardly directed force which tends to constrict or "pinch" the conductor. A high-temperature plasma is a very good conductor (its resistance can be many times lower than that of copper), so that in the pinch confinement the current is made to flow in the plasma itself. As the current builds up, its associated magnetic field increases in strength and in turn pinches the plasma into a dense, hot region in the center of the container.

The pinch devices need not be linear in configuration. In fact, in order to eliminate end losses, one of the favorite configurations is the torus. ZETA, the British machine at Harwell, is an example of a toroidal pinch device.

Unfortunately, highly constricted columns of plasma are unstable against forces which distort its shape, and any initial disturbances tend to grow in amplitude so that the column rapidly disintegrates. It has been demonstrated that the presence of a longitudinal magnetic field within the plasma-current discharge has a stabilizing influence which inhibits the formation of small "kinks." In addition, theory predicts that external conducting shells may also assist in controlling the instabilities. A great deal of investigation still remains to be done on schemes of this type.

2) Magnetic Mirror: The use of a straight section of tube to contain a thermonuclear plasma requires some suitable technique for "stoppering" the ends of the container. One approach is to wind magnetic field coils about a straight section of tube so as to produce an axial magnetic field which is weak in the central region, but strong at the two ends [see Fig. 4(b)]. The strong fields at the ends tend to repel the charged particles of the plasma and hence tend to move them back towards the central region. These strong fields at the ends, which trap the particles[11–17] thus constitute the "magnetic mirrors."

The requirement for containment of plasma particles by a magnetic mirror is that the particle energy in the

[11] R. F. Post, "Controlled fusion research—an application of the physics of high temperature plasmas," PROC. IRE, vol. 45, pp. 134–160; February, 1957.
[12] "Controlled release of thermonuclear energy," *Nature*, vol. 20, pp. 217–223; January 25, 1958.
[13] Second U. N. Internatl. Conf. on the Peaceful Uses of Atomic Energy, vol. 31: "Theoretical and Experimental Aspects of Controlled Nuclear Fusion," vol. 32: "Controlled Fusion Devices," United Nations, Geneva, Switzerland; 1958.
[14] A. Simon, "An Introduction to Thermonuclear Research," Pergamon Press, New York, N. Y.; 1959.
[15] A. S. Bishop, "Project Sherwood—The U. S. Program in Controlled Fusion," Anchor Books, Doubleday & Co., Inc., New York, N. Y.; 1960.
[16] J. G. Linhart, "Plasma Physics," North-Holland Publishing Co., Amsterdam, The Netherlands; 1960.
[17] M. A. Leontovich, Ed., "Plasma Physics and the Problems of Controlled Thermonuclear Reactions," Pergamon Press, New York, N. Y., vols. 1–4; 1960.
[18] N. R. Nilsson, Ed., *Proc. 4th Internat. Conf. on Ionization Phenomena in Gases*, North-Holland Publishing Co., Amsterdam, The Netherlands, vols. 1, 2; 1960.
[19] R. Latham and J. A. Nation, "Report on linear pinch devices," *Nuclear Instr. and Methods*, vol. 4, pp. 261–272; June, 1959.
[20] R. J. Bickerton, "Brief review of the toroidal stabilized pinch," *Nuclear Instr. and Methods*, vol. 4, pp. 273–278; June, 1959.




Fig. 4—(a) Pinch. A current in a column of plasma creates an encircling magnetic field which exerts an inward force on the charged plasma particles and hence "pinches" them to the center of the tube. The pinch effect unfortunately tends to be unstable. (b) Magnetic mirror. Current carrying coils are wound on a cylinder so as to produce strong magnetic fields at each end. The plasma can then be trapped between the two end "mirrors." (c) Cusp geometry. By suitable arrangement of magnetic field coils "cusp" configuration of confining magnetic fields is possible.

axial direction be small compared with its energy in the perpendicular direction. If the axial velocity of the particle is too great, the mirror fields will not turn the particle back, and hence it will escape. This creates the problem of how the particles should be injected so that trapping by the mirrors will occur. Suggested schemes include the injection of beams of low-energy ions which are given large perpendicular accelerations by RF electric fields as they pass slowly through the central mirror region, thus giving them sufficient transverse energy to be trapped. A second scheme is to inject a beam of high-energy neutral atoms as molecules and break these up as they pass through the confinement volume, thus providing a means for continuous re-injection of energetic particles.

A second problem is that the above-mentioned anisotropies in the velocity-space required for containment of the plasma in a mirror machine can give rise to instabilities. These instabilities are of two types; one is due to unstable electrostatic plasma oscillations which grow at the expense of the electron energy and the second to unstable hydromagnetic disturbances which cause the confining field to become "rippled" and to fluctuate rapidly, which in turn gives rise to enhanced diffusion of particles across the field.

The use of mirror machines is thus not without its problems, and considerable investigations are yet to be made.

3) Other Schemes: Other schemes for the containment of thermonuclear plasmas include the Stellarator,[21] which uses a magnetic field parallel to the axis of a toroidal tube and is produced by external currents flowing in solenoidal windings encircling the plasma. The confining fields are such that the magnetic lines of force generate not a single circle but an entire complex helical or toroidal surface suitable for the trapping of plasma particles. Some of the stability problems of the Stellarator are similar to those of the toroidal pinch, although the much smaller currents in the plasma interact less violently with the confining fields.

Another approach is based on the idea that, as a result of the gyroscopic action, a rotating plasma may be stable. In this "homopolar" device,[15] the application of radial electric and transverse magnetic fields causes the plasma particles to precess about a central axis, creating a centrifugal force which tends to keep the particles away from the axis and trap them in regions of magnetic field which have been caused to "bulge" by the rotating plasma.

Studies of magnetic confinement indicate that magnetic configurations with lines of force curving away from the plasma should be stable while those curving towards the plasma tend to be unstable. This suggests that configurations in which the magnetic lines of force curve everywhere away from the plasma might be stable. Such a scheme is the picket fence or cusp geometry shown in Fig. 4(c). There exists, of course, the problem of "stoppering" the regions of weak confinement. One idea is to use RF electric fields which are nonlinear in space and thus create a net force on the particles which inhibits their escape.[22–24] (Some consideration has been given to complete systems using RF gradient fields, however, tne required power appears excessive compared to other techniques.)

A further idea has been to start from the high-energy side, that is, with a beam of particles having energies greater than those needed for thermonuclear reactions and by injecting and trapping them in a confined region to build up to densities which would sustain the thermonuclear reactions. To achieve this it is necessary to inject a high-energy beam of particles into a strong magnetic field and to dissociate the particles before they come out.

Many other schemes have been proposed and are under investigation.

[21] L. Spitzer, Jr., "The Stellarator Concept," *Phys. of Fluids*, vol. 1, pp. 253–264; July–August, 1958.
[22] H. A. H. Boot and R. B. R. S. Harvie, "Charged particles in a non-uniform radio-frequency field," *Nature*, vol. 180, p. 1187; November 3, 1957.
[23] H. A. H. Boot, *et al.*, "Containment of a fully ionized plasma by radio-frequency fields," *J. Electronics Control*, vol. 4, pp. 434–453; May, 1958.
[24] T. W. Johnston, "Time-averaged effects on charged particles in ac fields," *RCA Rev.*, vol. 21, pp. 570–610; December, 1960.

Heating

A crucial requirement for any thermonuclear machine is the means to heat the plasma to the required high temperatures[11–18] of one hundred million degrees or more. Of the several methods for heating the plasma, the simplest is the ohmic or Joule heating by the currents in the plasma which produce the confining fields. At high temperatures, the power input per unit volume becomes small due to the high conductivity of the plasma, so that interparticle collisions must occur to provide any Joule heating. The collisions, however, tend to diffuse the azimuthal confining fields and the axial stabilizing field into each other. Thus, the Joule heating requirements and those for stability are contradictory.

Another method of heating the plasma (used in mirror machines) is that of "adiabatic compression." In this technique the magnetic field strength of the entire mirror configuration is made to increase with time. Thus, particles (ions and electrons) injected into the machine at times of low field strength will increase their transverse energy as the magnetic field is increased, while their axial energy will remain the same. In fact, it turns out that the increase in transverse energy of the particles is directly proportional to the increase in magnetic field strength.

A plasma can also be heated by pulsing the axial confining field so as to produce an oscillating electric field which encircles the axis of the tube. This induced electric field can increase the energy of the gyrating charged particles. Such a method is aptly called "magnetic pumping." The magnetic pumping technique is particularly effective if the confining field is pulsed at the cyclotron frequency of the positive ions. This is due to the interaction between the oscillating electric field and the gyrating positive particles which move in the same direction and with the same velocity as the electric field so that resonance coupling is possible.

Of importance in the thermonuclear reaction is any process which might cause more energy to leave the reaction than is created and hence cool the plasma. Under the assumption of perfect containment, the basic energy loss is due to bremsstrahlung—radiation from the plasma itself due to deflection (through collision) of the rapidly moving charged particles. If the system is to be self-sustaining, the generated power within the plasma must exceed the radiated power. This occurs above a certain critical temperature, the so-called "ignition temperature." For the D-D reaction, this critical temperature is of the order of 4×10^{8}°K. A second form of radiation loss from the plasma which may be important is synchrotron radiation due to the radial acceleration of particles in a magnetic field.

In addition to the radiation losses from the plasma, particle losses will occur. There will always be a number of particles, particularly electrons, in the high-energy tail of the velocity distribution of particles in the plasma. These electrons are too energetic to be contained by the normal confining field strength and constitute "runaways."

Diagnostics

Since thermonuclear plasma research is in a highly exploratory state, a great number of techniques are necessary to diagnose[13,17] what is actually happening. These constitute such a variety of methods that most experimentalists in physics would be able to recognize at least some techniques with which they are familiar. No attempt will be made to give an exhaustive account of the possible approaches, but the number of different disciplines which can contribute to furthering the knowledge of thermonuclear plasmas will be indicated.

Visual diagnostics such as fluorescent screens and photographic methods are of value in obtaining qualitative information. Fluorescent screens have been used to determine the location of the plasma, ion orbit size and approximate density measurements. The same information can be obtained with fast-shutter photography, while streak photography enables a display of the time history of the position and light intensity of the plasma.

Spectrographic techniques have yielded much quantitative data, such as determination of the ion velocity distribution from Doppler and Stark broadening of the spectral lines, spectral line identification of the plasma species and impurities and determination of electron temperatures by measurement of the intensity ratio of the spectral lines of ionized and neutral species of the plasma. In addition, X-ray energy analysis has been applied to measurement of the radiation emitted from the hot plasma.

Direct current probe techniques have been used with moderate success (the major difficulty being that probes severely perturb the plasma) to obtain indications of electron temperature, ion and electron densities and distribution profiles. Current loops and probes are of value for plotting contours of magnetic field and current distributions. Considerable interest has been shown in solid-state probes based on the Hall effect for similar purposes.

RF techniques have proven extremely useful, since transmission of microwaves through the plasma yields information on the plasma electron density, while a measure of the intensity of RF energy emitted from a plasma yields the kinetic electron temperature. Furthermore, resonance absorption at certain RF frequencies can be used for ion identification since the gyrofrequency of a specific ion depends on its charge to mass ratio. The use of HF radio techniques in plasma diagnostics has in turn stimulated research on the generation of higher and higher frequency coherent EM energy.

Infrared measurements as thermonuclear diagnostics have been limited, due to the slow time response of most long-wavelength I-R detectors. As the time constant of these detectors continues to be improved with the advent of new semiconductor materials and techniques, their utility in such studies will gain prominence.

Many techniques first introduced in nuclear particle physics are of great value. Among these are the determination of temperature and velocity of runaway electrons by use of graded absorbers in front of scintillation counters and similar studies employing nuclear emulsion plates and the use of neutron counters for detecting neutrons, which should arise out of the thermonuclear process, but more usually are formed far too prematurely as a result of acceleration mechanisms, such as instabilities.

Of course, the true criterion of a thermonuclear reaction is to measure more energy being created by the plasma than is being put into the plasma. In the course of achieving this no doubt many byproducts will come to pass which may be of nearly as great importance as the final goal.

Of the numerous experimental approaches under investigation, none is in a position to achieve the "ignition" temperatures where the input energy begins to equal the energy generated. Before this is possible, a tremendous amount of basic knowledge of plasma properties is still required. These investigations point only to further clarification of the severe stability requirements, of the important energy loss mechanisms, of the necessary containment times, the techniques of heating and diagnosing plasma and many other problems. All the different approaches are studies of plasma physics necessary to build up the fundamental behavior of plasmas over the widest possible range of conditions. This is being achieved by the use of many relatively small-scale experiments devised to test crucial limitations and novel ideas in addition to the large machines, which create conditions approaching those in a genuine thermonuclear reaction.

Communications and Plasma Physics

Electromagnetic Wave Interaction with Plasmas

The interest in electromagnetic wave interaction with plasmas is many fold. First, there is the direct application to communication techniques. Secondly, there is the information which can be derived from a knowledge of such interaction. This is the basis for numerous fundamental studies in physics, diagnostic techniques, and in this same category can be included the effects on radar return. In addition, the effect of the plasma environment on the performance of a given system must be considered.

The interaction of an electromagnetic wave with a plasma can be described in terms of a number of "bulk" parameters of the plasma. These parameters in turn depend upon the basic particle interactions. The degree of ionization of the gas or mixture of gases comprising the plasma determines the "electron density" or number of electrons (the most important constituent) contained within the plasma. The interaction of these electrons with neutral atoms, ions, and with each other determines the "collision frequency" of the plasma constituents, *i.e.*, a measure of the average number of collisions an electron undergoes per unit time. Complicating factors are that the collisions can be elastic or inelastic, the electron can be interacting with several particles simultaneously and the nature of the interacting forces is different for electron-neutral particle interaction than for electron-ion or electron-electron collisions. The electron density, collision frequency and external forces determine the "conductivity" (and in turn the current density) of a plasma. For slightly ionized plasmas, the conductivity is almost exclusively due to the more mobile electrons. However, at high degrees of ionization, the ion conductivity becomes of importance. From a knowledge of the time and spatial variation of these quantities (electron density, collision frequency, conductivity), electromagnetic wave interaction with a plasma can, at least in principle, be deduced.

A fundamental quantity which enters into a discussion of the properties of a plasma, particularly when electromagnetic wave interaction is concerned, is the plasma frequency. The plasma frequency (ω_p) for electrons in a plasma, regarding the ions as stationary motionless points is defined as

$$\omega_p = (ne^2/\epsilon_0 m)^{1/2},$$

where

n = the electron number density per unit volume
e = the charge on the electron
m = the mass of the electron
ϵ_0 = the permittivity of free space.

Although the plasma frequency enters into most considerations as a convenient "lumped parameter" having the dimensions of frequency, it also is an inherent property of a plasma. If, in an infinite plasma, a small number of electrons are displaced from their equilibrium position, a restoring space charge field is created which, if the displacing force is suddenly removed, causes the electrons to oscillate about their equilibrium at a frequency proportional to the plasma frequency.

The electromagnetic properties of a plasma[25–28] change markedly depending upon whether the angular frequency of the electromagnetic wave is greater or less than the plasma frequency. For RF frequencies above the plasma frequency, a plasma behaves more or less like a dielectric, the lossiness of which is determined by the collision frequency. At frequencies well below the plasma frequency, the plasma acts like a very good conductor, while at frequencies around the plasma fre-

[25] J. A. Ratcliffe, "The Magneto-Ionic Theory and its Application to the Ionosphere," Cambridge University Press, Cambridge, Eng.; 1958.

[26] B. N. Gershmann, *et al.*, "Propagation of electromagnetic waves in a plasma (ionosphere)," *Upsekhi Fiz. Nauk*, vol. 61, pp. 561–612; 1957. (Translation: AEC-tr-3493.)

[27] L. Smullen, "Interaction between plasmas and electromagnetic fields," *J. Res. NBS*, vol. 64D, pp. 766–767; November/December, 1960.

[28] M. P. Bachynski, *et al.*, "Plasmas and the Electromagnetic Field," McGraw-Hill Book Co., New York, N. Y.; in press.

quency, cutoff or very high attenuation and reflection occurs so that the wave cannot penetrate to any great depth into the plasma.

A plot of the typical variation of the penetration depth of an incident electromagnetic wave into a given plasma with RF frequency is shown in Fig. 5. The effect of increasing electron density is to depress the entire variation, particularly in the dielectric region. Increasing the collision frequency has no effect in the cutoff region, but in the conducting region it increases the depth to which an EM wave can penetrate while it decreases the penetration depth in the dielectric region.




Fig. 5—Variation of depth of penetration of an electromagnetic wave into a plasma. At low frequencies the plasma acts as a conductor, while at high frequencies its behavior is similar to a dielectric. A cutoff region for the electromagnetic waves exists when $\omega \approx \omega_p$.

In the presence of a steady magnetic field, the electromagnetic properties of a plasma are drastically modified. In this case, the plasma behaves as a doubly refracting medium and exhibits band-pass characteristics. That is, for certain frequency ranges, depending upon the plasma properties and the strength and direction of the magnetic field relative to the incident wave, the plasma is transparent to radio waves, while in other frequency ranges it is opaque. This means that for specific conditions, radio energy at frequencies well below the plasma frequency can penetrate through the plasma.

Further electromagnetic wave-plasma phenomena of considerable interest occur when the effects of electron gradients are considered. These nonlinearities in the distribution of the electron density arise as a result of thermal currents in the plasma and give rise to longitudinal waves which travel at very low velocities (some as low as the sound velocity) in the plasma. Thus, the plasma can support a pressure wave in addition to the transverse electromagnetic wave. In most instances, the pressure and electromagnetic waves are coupled, and energy can be transferred from one type of wave motion into the other.

Communications and Natural Plasmas

The fact that an ionized region acts as a conductor and hence is a good reflector for incident radio waves of frequency below the plasma frequency has been utilized for communications for some time. Thus, the *ionosphere* is a naturally occurring plasma, and long-distance communication over the earth via reflection from the ionosphere is feasible for frequencies less than a critical frequency[5] (which depends on angle of incidence as well as the electron density). At these frequencies, the radio energy will be almost totally redirected (reflected) down towards the earth again. This is the basis of the so-called "sky-wave" in modern radio communications. Extensive exploration of the ionosphere has also been carried out by "radio soundings" in which a variable-frequency radio signal is directed at the ionosphere and the reflected wave observed until a frequency is found above which the signal penetrates into the ionosphere, and the reflected wave is appreciably reduced. If the electron density of the ionosphere changes, this critical frequency changes. In this manner, it has been possible to determine the stratification of the ionosphere by virtue of the differing electron densities of the various layers. Fortunately, the electron density is greater in the layers at higher altitudes so that frequencies can be found which penetrate the lower layers but are still reflected by the higher regions of the ionosphere.

The newer communication techniques which use meteor trails are based on the same principles.[29–31] A meteor re-entering the earth's atmosphere creates a column of ionization due to impact on the atmosphere and to ablation of the meteor material. When the electron density is sufficiently large, this cylinder of plasma reflects incident radio energy. The trails are transient phenomena since, due to diffusion, the electron density soon decreases below the critical value for reflection of the electromagnetic energy.

An electromagnetic wave traveling in an ionized region may, under certain circumstances, interact with a second wave in such a way that a modulation imposed on one of the waves becomes transferred to the other. To produce this crossmodulation or *Luxembourg effect*[32–37] (so-called because it was first observed from radio station Luxembourg), a nonlinear medium is required, and the absorption of energy from radio waves by an ionized region provides the necessary nonlinearity. If now another wave (the interacting wave) is absorbed in the same region, the energy from it will in-

[29] P. A. Forsyth and E. L. Vogan, "Forward scattering of radio waves by meteor trails," *Canad. J. Phys.*, vol. 33, pp. 176–188; May, 1955.

[30] P. A. Forsyth, *et al.*, "The principles of JANET—a meteor burst communication system," PROC. IRE, 45, vol. pp. 1642–1657; December, 1957.

[31] R. J. Carpenter, and G. R. Ochs, "The NBS meteor burst communication system," IRE TRANS. ON COMMUNICATIONS SYSTEMS, vol. CS-7, pp. 263–271; December, 1959.

[32] B. D. Tellegen, *Nature*, vol. 131, p. 840; 1933.

[33] G. W. O. Howe, "Accurate measurements of the Luxembourg effect," *Wireless Engr.*, vol. 15, p. 187; April, 1938.

[34] L. G. H. Huxley, "Ionospheric cross-modulation at oblique incidence," *Proc. Roy. Soc.*, vol. A200, p. 486; 1950.

[35] V. L. Ginsburg and A. V. Gurevich, "Non-linear phenomena in a plasma located in an alternating electromagnetic field," *Upsekhi Fiz. Nauk*, vol. 70, pp. 201–246; February, 1960, pp. 393–428; March, 1960.

[36] F. H. Hibberd, "Ionospheric self-interaction of radio waves," *J. Atmos. Terr. Phys.*, vol. 6, pp. 268–279; May, 1955.

[37] V. L. Ginzburg, "Non-linear interaction of radio waves propagating in a plasma," *Zh. Eksp. Teo. Fiz.*, vol. 35, pp. 1573–1575; December, 1958.

crease the velocity of the electrons and hence the frequency of their collisions with the net result that the wanted wave will be more strongly absorbed. Thus in the presence of the interacting wave, the wanted wave will become weaker. If the amplitude of the interacting wave is varied, the velocity of the electrons will follow, and the absorption of the wanted wave will also vary. In this way, the modulation of the interacting wave becomes superimposed on the wanted wave.

Due to the doubly refracting nature of the plasma in a magnetic field, a further effect occurs when radio waves are propagated in a plasma in the direction of the magnetic field lines. This is a rotation of the plane of polarization of the wave, namely *Faraday rotation*. Communication systems whose signals must pass through the ionosphere, for instance, suffer from this effect.

The band-pass behavior of the plasma in the presence of a dc magnetic field discussed earlier, explains "whistler" propagation.[38,39] These decreasing-frequency audio whistles observed by radio means are the result of LF electromagnetic energy being generated by natural lightning discharges and propagating from one earth hemisphere along the magnetic lines of force of the earth to the conjugate positions of their origin in the opposite hemisphere.

At low radio frequencies, the ions in the plasma profoundly affect the electromagnetic characteristics of the plasma.[40,41] As a result, the band-pass structure of the plasma is modified with electromagnetic wave propagation now being possible at very low frequencies. These LF EM waves are the classic *magnetohydrodynamic* or *Alfven* waves[42] that propagate at a velocity which is often nine orders of magnitude less than the velocity of light. Such magnetohydrodynamic waves have been detected both in the laboratory and during the high-altitude nuclear detonations of the Argus experiments[43–45] of 1958.

The Plasma Sheath

A space vehicle moving at hypersonic velocities within a planetary atmosphere will be surrounded by a shock-induced envelope of ionized gas (Fig. 6). This layer of ionized gas or "plasma sheath" can have a profound influence on communications and telemetry to and from the vehicle[46,47] and can also seriously alter the radar reflecting characteristics of the vehicle and hence its radar detectability.




Fig. 6—A plasma sheath surrounds a hypersonic space vehicle as it re-enters the atmosphere.

The effect of the plasma sheath on communications is to attenuate the signal severely and markedly degrade the antenna performance.[48] At typical re-entry velocities for missiles and space vehicles, the signal attenuation is sufficient to cause "blackout," except at extremely high microwave frequencies. For a manned re-entry vehicle which descends slowly in altitude, the plasma sheath ionization can persist over a large part of its flight path. This makes it extremely difficult to guide and control such vehicles from the ground by means of telemetered signals. The same difficulties apply to information transmitted from space probes and other scientific data measurements. Consequently, it is very important to understand the plasma phenomena created on re-entry in order to select the optimum system requirements.

Of great importance for defense applications is knowledge of the behavior of the radar scattering cross sections of ballistic missiles at launch and during re-entry caused by the ionized sheaths and trails of the vehicles. In general, the plasma sheath enhances the scattering cross sections, but under specific conditions, the scattering properties can even be reduced.

Basically, the above phenomena involve the interaction of electromagnetic waves and plasmas. This is, however, only part of the story, since to specify the plasma properties and the plasma geometry at any time, a detailed knowledge of aerophysics for determining the shock front configuration and related aerodynamic flow fields and flow rates is required.[49] These factors, in turn,

[38] L. R. O. Storey, "An investigation of whistling atmospherics," *Phil. Trans. Roy. Soc. (London) A*, vol. 246, pp. 113–141; July, 1953.

[39] R. M. Gallet and R. A. Helliwell, "Origin of 'very-low-frequency' emissions," *J. Res. NBS*, vol. 63D, pp. 21–27; July/August, 1959.

[40] C. O. Hines, "Heavy-ion effects in audio frequency radio propagation," *J. Atmos. Terr. Phys.*, vol. 11, no. 1, pp. 36–42; 1958.

[41] R. E. Barrington and T. Nishizaki, "The hydrogen ion effect in whistler dispersion," *Canad. J. Phys.*, vol. 38, pp. 1642–1652; December, 1960.

[42] A. Alven, "Cosmical Electrodynamics," Oxford University Press, Oxford, Eng.; 1950.

[43] N. C. Christofilos, "The Argus experiment," *J. Geophys. Res.*, vol. 64, pp. 869–875; August, 1959.

[44] P. Newman, "Optical, electromagnetic and satellite observations of high-altitude nuclear detonations: part 1," *J. Geophys. Res.*, vol. 64, pp. 923–933; August, 1959.

[45] A. M. Peterson, "Optical, electromagnetic and satellite observations of high-altitude nuclear detonations: part 2," *J. Geophys. Res.*, vol. 64, pp. 933–938; August, 1959.

[46] M. P. Bachynski, *et al.*, "Electromagnetic properties of high-temperature air," Proc. IRE, vol. 48, pp. 347–356; March, 1960.

[47] A. V. Phelps, "Propagation constants for electromagnetic waves in weakly ionized, dry air," *J. Appl. Phys.*, vol. 31, pp. 1723–1729; October, 1960.

[48] J. W. Marini, "Radiation and admittance of an insulated slotted-sphere antenna surrounded by a strongly ionized plasma sheath," *J. Res. NBS*, vol. 64D, pp. 525–532; September/October, 1960.

[49] W. Rotman and G. Meltz, Eds., "Electromagnetic Effects of Re-Entry," Pergamon Press, New York, N. Y.; 1960.

depend upon the environment in which the body is moving and hence upon upper atmospheric physics as well as depending on the atomic processes of particle interaction in the plasma, dissociation, ionization rates and products, etc. This is, indeed, a formidable problem.

Plasma sheath phenomena have been reported associated with orbiting satellites.[50–56] It is speculated, with some experimental evidence, that due to space charge which may build up on the satellite, a cloud of ions could be projected in front of the satellite. This plasma cloud is thought to be sufficiently dense to reflect HF (megacycle) radio waves at times of intense solar activity. More quantitative measurements are neces ary before the existence of this effect can be proven.

Atmospheric Breakdown

Gas "breakdown" or gas "discharge" in a given region occurs when the number of electrons being created by ionization is equal to or exceeds the number of electrons which are lost through diffusion, recombination and attachment. In the breakdown process,[57–62] the residual electrons in the gas gain sufficient energy from the RF electric fields to cause primary ionization by collision with the neutral constituents. Initially, since there are few electrons, the ionizing collisions are infrequent, but as the number of electrons created increases, an avalanche process is initiated until breakdown occurs. At high pressures, the mean free time between collisions of the electrons is small compared to the RF period so that the electron does not have time to gain much energy before collision. At low pressures, the time between collisions is long so that in the interval the electron gains sufficient energy from the RF fields to cause an ionizing collision. At extremely low pressures, there are few particles for the electrons to collide with, so an optimum pressure exists at which a minimum voltage is required for breakdown.

Thus the electric field strength required to break down a gas at low pressure is, in general, less than that required at atmospheric pressure. As a consequence, even low-power antennas on a high-altitude vehicle may be susceptible to voltage breakdown.[59,62] The effect on the antenna performance when voltage breakdown occurs is to alter the radiation pattern of the antenna, lower the total power radiated, change the pulse shape of the radiated power and modify the input impedance of the device. When the number density of electrons in the discharge is such that the plasma frequency exceeds the RF frequency, little transmission and considerable mismatch will occur.

Direct application of breakdown theories to antenna-voltage breakdown characteristics are difficult due to the complex fields which exist near the antenna and which vary with the antenna configuration. The effect of pulse shape, pulse repetition rate (since electrons may be left in the gas in front of an antenna due to the previous pulse), and peak powers under varying conditions before breakdown occurs are yet not fully understood. The environmental conditions of a space vehicle complicate the problem due to the questionable validity of concepts such as diffusion length at high altitudes, the unknown effects on breakdown of air turbulence, plasma sheaths, etc., around the vehicle and the effects of preionized regions such as the ionosphere in which large initial electron densities exist through which the vehicle must pass.

Plasma Noise

As a result of the interaction between electrons, ions and neutral molecules in a plasma, electromagnetic energy is generated and emitted by the plasma.[63] This emission of "passive" radiation from the plasma can be due to a variety of physical processes such as: bremsstrahlung—the deceleration of particles due to an atomic encounter; the release of energy during recombination of an electron-ion pair; or Cerenkov radiation from the "bow wave" formed when particle velocities exceed the velocity of light in the medium or unstable plasma oscillations arising from gradients of electron density which exist in nonuniform plasmas. The radiated energy is in general noncoherent, varying over a wide continuous spectrum of frequencies and thus appears principally as a noise signal.

This noise can impose limitations on the sensitivity of an antenna receiving system by raising the noise level of the environment in which the transmitting and receiving system operates and hence defeating the advantages

[50] A. Flambard and M. Reysat, "Electromagnetic waves and satellites: echoes from ionized trails of satellies at high frequency," *Onde Elect.*, vol. 38, pp. 830–837; December, 1958.
[51] C. R. Roberts and P. H. Kirchner. "Radio reflections from satellite-produced ionization," PROC. IRE, vol. 47, pp. 1156–1157; June, 1959.
[52] D. B. Beard and F. S. Johnson, "Charge and magnetic field interaction with satellites," *J. Geophys. Res.*, vol. 65, pp. 1–7; January, 1960.
[53] S. Rand, "Wake of a satellite traversing the ionosphere," *Phys. of Fluids*, vol. 3, pp. 265–273; March/April, 1960.
[54] J. D. Krauss, *et al.*, "The satellite ionization phenomenon," PROC. IRE, vol. 48, pp. 672–678; April, 1960.
[55] J. D. Krauss, "Evidence of satellite-induced ionization effects between hemispheres," PROC. IRE, vol. 48, pp. 1913–1914; November, 1960.
[56] J. D. Krauss and R. C. Higgy, "The relation of the satellite ionization phenomena to the radiation belts," PROC. IRE, vol. 48, pp. 2027–2028; December, 1960.
[57] L. Gould and L. W. Roberts, "Breakdown of air at microwave frequencies," *J. Appl. Phys.*, vol. 27, pp. 1162–1170; October, 1956.
[58] A. D. MacDonald, "High-frequency breakdown in air at high altitudes," PROC. IRE, vol. 47, pp. 436–441; March, 1959.
[59] J. B. Chown, *et al.*, "Voltage breakdown characteristics of microwave antennas," PROC. IRE, vol. 47, pp. 1331–1337; August, 1959.
[60] P. M. Platzmann and E. H. Solt, "Microwave breakdown of air in non-uniform electric fields," *Phys. Rev.*, vol. 119, pp. 1143–1149; August 15, 1960.
[61] D. Kelly and H. Margenau, "High frequency breakdown of air," *J. Appl. Phys.*, vol. 31, pp. 1617–1620; September, 1960.
[62] W. E. Scharfman and T. Morita, "Voltage breakdown of antennas at high altitude," PROC. IRE, vol. 48, pp .1881–1887; November, 1960.
[63] G. Bekefi and J. L. Hershfield, "Incident microwave radiation from plasmas," *Phys. Rev.*, vol. 116, pp. 1051–1056; December 1, 1959.

gained in using masers, parametric amplifiers and other low noise receiving devices. The "noise" radiated from a plasma is not, in all cases, necessarily a detrimental effect such as it is in communications. Thus if the spectral distribution of the emitted energy is characteristic of the plasma properties, a measurement of the microwave radiation provides specific information on the plasma. As an example, knowledge of the radiated power gives a measure of the electron temperature in the plasma, and this has been used as a powerful diagnostic technique. Further investigations have been focused on the microwave radiation from plasmas produced by hypervelocity bodies in the hope of providing a means for detection and discrimination of such vehicles as they enter the atmosphere.

A major difficulty in the above-mentioned applications is an understanding of the fundamental processes. For a plasma in a steady state, macroscopic radiative transfer concepts without detailed knowledge of the atomic processes can be applied and the emission spectrum determined from the electromagnetic wave absorption, transmission and reflection properties of the plasma. These determinations are complicated by the nonuniformity and geometrical configuration of the emitting plasma. However, most practical plasmas of interest are not in equilibrium, and as yet a considerable amount of theoretical work remains to be done on nonequilibrium radiation. Furthermore, few reliable quantitative measurements are available to guide the theoretical work.

Plasma Propulsion

General Rocket Considerations

After a vehicle has been placed out of the reach of strong gravitational forces into a low satellite orbit by conventional means (*e.g.*, a chemical rocket), there no longer exists a need for a high-thrust device. One then can look towards more novel methods for reducing the cost of propelling large payloads in space. The use of electrical propulsion techniques for this purpose greatly increases the size of the payload that can be projected into larger orbits.

To show that this is the case, consider some fundamental system parameters of a rocket.[64] The basic parameters are the specific impulse (defined as thrust in weight units/propellant mass flow rate) whose units are seconds and the thrust (in weight units) per unit weight which is a dimensionless parameter. For a rocket to take off from a planet, the thrust per unit weight of the rocket must be greater than one. However, in regions where the forces of gravity are small, even small values of thrust/weight may be useful. In a chemical rocket, the thrust power is limited to the specific energy content within the chemical propellant so that the highest specific impulse possible is desired. In electrical propulsion however, the source of the power and the working fluid are completely separate, hence the optimum specific impulse is not necessarily the greatest one. Thus the source of power increases with increasing specific impulse, and the propellant or working fluid decreases with increasing specific impulse with an optimum specific impulse when the sum weight of the propellant and power plant (*i.e.*, vehicle) is minimized. For operations within the influence of the earth's gravitational field, such as a complete round trip of a lunar mission or the establishment of a communications satellite in a "stationary" 24-hour orbit at a height of 22,500 miles, the optimum specific impulse required ranges from 1500 to 5000 seconds. For interplanetary flights, a specific impulse of 7500 to 20,000 seconds is desirable.

These values of specific impulse are beyond the limit of the energy of conventional rocket propellents so that new methods are required. In Fig. 7 are illustrated the limit of thrust per unit weight and specific impulse of chemical rockets and the regions of operation of some of the devices to be discussed in the sequel.




Fig. 7—General rocket characteristics of some plasma propulsion devices.

Electrostatic or Ion Propulsion

One technique for attaining a large specific impulse is to electrostatically accelerate a beam of charged particles and expel them at very high velocities.[65–68] In this manner, it may be possible to design a low-thrust system suitable for space flight. In its simplest form, an ionic rocket would consist of an ion source to supply the "fuel" and an electrostatic accelerator or gun to accelerate the ions, the ejection of the ions from the device corresponding to the mass flow from an ordinary rocket.

[64] H. S. Seifert, Ed., "Space Technology," John Wiley and Sons, Inc., New York, N. Y.; 1959.

[65] E. Stuhlinger and R. Seitz, "Some problems in ionic propulsion systems," IRE Trans. on Military Electronics, vol. MIL-3, pp. 27–33; April, 1959.

[66] F. Hecht, Ed., *Proc. 10th Internatl. Astronautical Congr.*, London, Eng., 1959, Springer-Verlag, Vienna, Austria, vols. 1 and 2; 1960.

[67] S. W. Kash, "A comparison of ion and plasma propulsion," Proc. IRE, vol. 48, pp. 458–465; April, 1960.

[68] F. I. Ordway, Ed., "Advances in Space Science," Academic Press, New York, N. Y., vol. 2; 1960.

Considerable thought has gone into a choice of fuel for an ionic rocket. The basic requirements are that the ion source yield an ion of sufficient mass (to give an appreciable thrust) and at the expense of a minimum amount of power. Most present experimentation has been with the contact-ionization type of ion source using vapors of alkali metals as the "fuel." In this technique, cesium or rubidium, which have very low ionization potentials, are passed through regions of incandescent tungsten (which has a higher work function than either cesium or rubidium). The alkali atoms readily lose their valence electrons to the tungsten and nearly 100 per cent ionization can be achieved.

A more serious problem in the development of ion rockets is the space charge limitation upon the maximum current densities which can be obtained for a particular accelerating voltage, electrode configuration and propellant. Practical current densities which have been achieved at accelerating voltages below 10 kv are of the order of 12 ma/cm^2 for cesium.

Since ion bombardment can cause serious electrode erosion, secondary-electron emission and impact heating, it is necessary to focus the ion beam to overcome the beam spread resulting from the space charge repulsion of the charged ions. To obtain collimated beams, cylindrical-beam and converging-beam Pierce Gun accelerating systems have been studied.

In order to preserve the electrical neutrality of the ion rocket and to prevent space charge from building up behind the ship and hence inhibiting the ejection of ions, it is necessary to neutralize the "exhaust" of the ion rocket. To achieve space charge neutrality, particles of the opposite charge must be introduced into the exhaust. The entire ensemble, consisting of negative and positive particles and hopefully neutrals due to recombination, is electrically neutral, so in effect, it is a *plasma*. One technique of neutralizing is to inject electrons into the positive-ion beam from electron emitters located around the perimeter of the beam. The electrons are attracted into the ion beam by the space charge fields in the unneutralized portion of the beam and oscillate through the beam, thus giving some degree of neutralization to the ion beam. Since the mass of the electron is a small fraction of the ion mass, an ejection of electrons would make a negligible contribution to the net thrust and is therefore useful solely in an attempt to attain charge neutrality. A further suggestion for an ion rocket which may overcome the charge neutralization problem is to have the rocket composed of ion diodes, each alternately accelerating positive and *negative* ions. The exhaust of such a system would be electrically neutral, and furthermore, if a suitable negative ion of comparable mass to the positive ion were known, then the over-all thrust of the system could be doubled. The difficulty is, of course, in obtaining a suitable negative ion source. Such a dual ion device is illustrated in Fig. 8.




Fig. 8—Positive and negative ion accelerators to achieve space charge neutrality in exhaust of an ion rocket system.

Other charged masses such as colloidal suspensions, dust particles and heavy molecules have been suggested as possible fuel for an ionic propulsion system and are currently being investigated.

Neutral Plasma or Magnetohydrodynamic Propulsion

High specific impulse devices are possible using a partially or fully ionized gas (*i.e.*, a plasma) as the propellant[69–71] in which the ion and electron densities are essentially neutral. Such a device is not affected by the space charge limitations of the ion rocket. Since the plasma is an electrically conducting fluid, electromagnetic fields can be used to interact with it in order to heat the plasma to higher temperatures or to accelerate it to high velocities. Electromagnetic fields can transfer energy to a plasma by two basic methods, namely, Joule heating which increases the thermal energy of the plasma and by the interaction of the plasma current with the magnetic field which creates a force accelerating the plasma and hence increases the energy of motion of the plasma. The manner in which this force interacts with the plasma is strongly dependent on the geometry of the apparatus and on the plasma properties, and is the basis for a number of schemes for plasma propulsion devices.

The plasma arc jet is an example of a device in which a plasma is used to Joule heat a gas. In the plasma jet,

[69] M. Alperin and G. P. Sutton, Eds., *Proc. Symp. on Advanced Propulsion Systems*, Los Angeles, 1957, Pergamon Press, New York, N. Y.; 1959.

[70] M. Camrac, *et al.*, "Plasma propulsion devices for space flight," IRE Trans. on Military Electronics, vol. MIL-3, pp. 34–41; April, 1959.

[71] W. Rayle, "Plasma propulsion possibilities," IRE Trans. on Military Electronics, vol. MIL-3, pp. 42–45; April, 1959.




Fig. 9—(a) Plasma jet. A plasma arc is used to heat a gas to high temperatures. The gas is then passed through an expansion nozzle and forms a high velocity exhaust. (b) MHD accelerator. In the magnetohydrodynamic accelerator an ionized gas is passed through crossed electric and magnetic fields which accelerate this plasma. (c) T tube accelerator. In the T tube, the energy stored in a capacitor bank is discharged into a gas creating a plasma which is accelerated up the stem of the T using magnetic fields.

a dc voltage is applied between the operating electrodes [see Fig. 9(a)] causing a breakdown of the gas in the chamber. The propelled gas is then forced through this electric arc and is heated upon passing through the arc. After heating, the hot gas is expanded in a conventional nozzle. The limitation of specific impulse in the plasma jet is caused by the inability to recover the energy expended on dissociation and ionization of the gas as it passes through the arc. Unless recombination occurs before the gas is expelled from the nozzle, this energy will not appear as kinetic energy of the gas flow and hence is lost.

A device which minimizes the above losses can be made by accelerating a preheated gas using magnetic fields. In this scheme [Fig. 9(b)], a hot gas (~3000°K) is passed into the acceleration chamber where electric currents are caused to flow through the plasma in a given direction. A magnetic field permeates the plasma in a direction normal to the electric current. The action of the current and the magnetic field creates a $J \times B$ (where J is the current density, B the magnetic field) force which accelerates the plasma in a direction perpendicular to both the magnetic field and the electric current.

Considerable experimentation has been performed with the T tube [Fig. 9(c)] in which the gas is highly ionized by passing a large current through the head of the T and then accelerating the plasma up the stem of the tube using magnetic fields. Further sophistication of this device is to use additional magnetic fields orientated along the stem of the T which act as magnetic nozzles increasing the velocity of the plasma and furthermore keeping it away from the walls of the tube to prevent cooling and erosion. In this manner, specific impulses up to 5000 seconds are possible.

Techniques have been developed on a laboratory scale whereby donut-shaped "blobs" of plasma or plasmoids[72,73] can be projected by magnetic forces at speeds exceeding 10^7 cm/sec. Such a plasma gun constitutes another possible means of propulsion.

As the interaction between magnetic fields and plasmas becomes better understood, a greater and greater number of novel propulsion techniques[74,75] will be suggested, and some of these will inevitably prove to be practical.

Plasma Devices

Pre-Plasma-Era Devices

Many years before the full importance of plasmas in the field of science was realized, devices employing plasma were in operation. These devices, of course, did not require a detailed understanding of plasma properties and included the fluorescent lamp, noise sources for the calibration of radio receiving devices and as laboratory standards and transmit-receive tubes for radar applications. The fluorescent lamp, for example, is just a gaseous discharge plasma whose light emission is used to activate the fluorescent material coating of the light tube. Most noise sources for laboratory calibrations are also gaseous discharges operating well below the plasma frequency in the "opaque region." In radar systems, on the other hand, it is necessary to have a switch to disconnect the receiver from the transmission line during the transmitted pulse and to disconnect the transmitter the rest of the time. Such a switch can be obtained

[72] W. H. Bostick, "Experimental study of ionized matter projected across a magnetic field," *Phys. Rev.*, vol. 104, pp. 292–299; October, 15, 1956.

[73] W. H. Bostick, "Experimental study of plasmoids," *Phys. Rev.*, vol. 106, pp. 404–412; May 1, 1957.

[74] M. M. Klein and K. A. Brueckner, "Plasma propulsion by a rapidly varying magnetic field," *J. Appl. Phys.*, vol. 31, pp. 1437–1448; August, 1960.

[75] G. A. Askaryan, "Acceleration of charged particles in travelling or standing electromagnetic waves," *Zh. Eksp. Teor. Fiz.*, vol. 36, pp. 619–621; February, 1959.

using appropriately connected spark gaps which "break down" during transmission and act as a low-impedance device, while normally they are high-impedance open circuits. The T-R tube is merely a sophisticated spark gap which operates at lower voltages (since the gas in the tube is at low pressure) and whose properties are not affected by external environment conditions such as humidity and temperature.

In addition, many important vacuum tube devices of long standing used for rectification and regulation purposes have utilized plasma in their operation. Among these can be listed the ignition, the mercury vapor rectifier and even the common voltage regular tube.

Microwave Devices

Promising applications of the properties of plasmas appear in the field of guidance and generation of high RF energy. Since a column of plasma will support the propagation of various field configurations of electromagnetic waves,[76–80] a considerable effort is presently being devoted to an understanding of "plasma waveguides." The waveguide is the basic component of the microwave system, and its characteristics will determine and limit the other microwave devices which are possible. Since a plasma waveguide exhibits specific mode and band-pass characteristics (which can be controlled by external magnetic fields), waveguide filters are obvious applications. An electromagnetic wave traveling down a plasma column will have its phase and amplitude altered, depending on the plasma properties and configuration and prototype attenuators,[81] and phase shifters have been built in several laboratories. Plasma properties can also be used for waveguide switching.[82–85] In addition, since plasmas exhibit interesting properties such as the Faraday effect, polarization characteristics, double refraction and nonlinearity, they present a host of phenomena that can be utilized for circuit and microwave applications.

It has been demonstrated that slow electromagnetic waves can propagate in a plasma cylinder in the presence of a dc magnetic field. As a consequence, intense investigations are being made in attempts to utilize a plasma[86–92] as the slow-wave structure of traveling-wave tubes. In this manner, the characteristics of the slow-wave structure can be altered externally by changing the plasma properties. By using modulated electron beams[93,94] passing through a plasma, a growth of the modulation has been observed. This has stimulated interest in the possibility of obtaining microwave amplification by such techniques. A diagram of such an electron beam-plasma interaction amplifier is shown in Fig. 10. Suggestions have been put forth in which the nonlinear effects of a plasma at high power levels is utilized as the nonlinear propagating medium of a parametric amplifier. The generation of millimeter waves by plasma techniques, such as high-intensity arcs and harmonic generation where the plasma provides the nonlinearity, excitation of coherent plasma oscillations and their conversions to short wavelength radio waves, etc., is another field of great interest[95–100] and current importance.

In a gaseous discharge (plasma) system, it is possible for metastable states of a given atom to be used as car-

[76] L. D. Smullin and P. Chorney, "Propagation in ion-loaded waveguides," *Proc. Symp. on Electronic Waveguides*, pp. 229–248; April, 1958.

[77] A. W. Trivelpiece and R. W. Gould, "Space charge waves in cylindrical plasma columns," *J. Appl. Phys.*, vol. 30, pp. 1784–1793; November, 1959.

[78] V. B. Fainberg and M. F. Gorbatenko, "Electromagnetic waves in a plasma situated in a magnetic field," *J. Tech. Phys. (USSR)*, vol. 29, pp. 549–562; May, 1959.

[79] V. E. Golant and A. P. Zhilinski, "Propagation of electromagnetic waves through waveguides filled with plasma," *Soviet Tech. Phys.*, vol. 5, pp. 12–21; July, 1960.

[80] L. Goldstein, "Non-reciprocal E-M wave propagation in ionized gaseous media," IRE TRANS. ON MICROWAVE THEORY & TECHNIQUES, vol. MTT-6, pp. 19–29; January, 1958.

[81] P. D. Lomer and R. M. O'Brien, "A microwave pulsed attenuator using an RF excited discharge," *Proc. IEE*, vol. 105, pt. B, suppl. No. 10, pp. 500–504; 1958.

[82] S. J. Tetenbaum and R. M. Hill, "High power magnetic field controlled microwave gas discharge switches," IRE TRANS. ON MICROWAVE THEORY AND TECHNIQUES, vol. MTT-7, pp. 73–82; January, 1959.

[83] R. S. Braden, "A new concept in microwave gas switching elements," IRE TRANS. ON ELECTRON DEVICES, vol. ED-7, pp. 54–59; January, 1960

[84] D. W. Downton and P. D. Lomer, "A pre-TR tube for high mean power duplexing," IRE TRANS. ON MICROWAVE THEORY AND TECHNIQUES, vol. MTT-8, pp. 654–659; November, 1960.

[85] R. M. Hill and S. K. Ichiki, "Microwave switching with low-pressure arc discharge," IRE TRANS. ON MICROWAVE THEORY AND TECHNIQUES, vol. MTT-8, pp. 628–632; November, 1960.

[86] E. V. Bogdanov, *et al.*, "Interaction between an electron stream and plasma," *Proc. Symp. on Millimeter Waves*, Brooklyn Polytechnic Press, Brooklyn, N. Y., pp. 57–72; April, 1959.

[87] G. S. Kino, "A proposed millimetre-wave generator," *Proc. Symp. on Millimeter Waves*, Brooklyn Polytechnic Press, Brooklyn, N. Y., pp. 233–248; April, 1959.
J. R. Baird and P. D. Coleman, "High power gas discharge frequency multiplier," *Proc. Symp. on Millimeter Waves*, Brooklyn Polytechnic Press, Brooklyn, N. Y., pp. 289–300; April, 1959.

[88] Z. S. Tchernov, "Interaction of E-M waves and electron beams with centrifugal electrostatic focusing," *Proc. Symp. on Electronic Waveguides*, Brooklyn Polytechnic Press, Brooklyn, N. Y., pp. 339–344; April, 1959.

[89] A. Javan, "Possibility of production of negative temperature in a gas discharge," *Phys. Rev. Lett.*, vol. 3, pp. 87–89; July 15, 1959.

[90] W. O. Schumann, "The backward wave in a metal waveguide filled with longitudinally magnetized plasma," *Z. Angew. Phys.*, vol. 11, pp. 333–335; September, 1959.

[91] J. M. Anderson, "Possible low-noise electron beam plasma amplifier," *J. Appl. Phys.*, vol. 30, pp. 1624–1625; October, 1959.

[92] G. S. Kino, "Parametric amplifier theory for plasmas and electron beams," *J. Appl. Phys.*, vol. 31, pp. 1449–1458; August, 1960.

[93] G. D. Boyd and L. M. Field, "Excitation of plasma oscillations and growing plasma waves," *Phys. Rev.*, vol. 109, pp. 1393–1394; February 15, 1958.

[94] G. D. Boyd, *et al.*, "Interaction between an electron stream and an arc discharge plasma," *Proc. Symp. on Electronic Waveguides*, Brooklyn Polytechnic Press, Brooklyn, N. Y., pp. 367–378; April, 1958.

[95] K. D. Froome, "A new microwave harmonic generator," *Nature*, vol. 184, p. 808; September 12, 1959.

[96] R. M. Hill and S. J. Tetenbaum, "Harmonic generation in a cyclotron resonant plasma," *J. Appl. Phys.*, vol. 30, pp. 1610–1611; October, 1959.

[97] N. R. Bierrum and D. Walsh, "Harmonics from a microwave gas discharge," *J. Electronics Control*, vol. 8, pp. 81–90; February, 1960.

[98] N. R. Bierrum, *et al.*, "Coherence and bandwidth of a gas discharge harmonic generator," *Nature*, vol. 186, p. 626; May 21, 1960.

[99] K. D. Froome, "Millimetre waves from mercury arc harmonic generator," *Nature*, vol. 186, p. 959; June 18, 1960.

[100] J. M. Anderson, "Microwave detection and harmonic generation by Langmuir-type probes in plasmas," PROC. IRE, vol. 48, pp. 1662–1663; September, 1960.




Fig. 10—Electron beam-plasma interaction amplifier. (From Boyd and Field.[93])

riers of energy to excite specific quantum energy levels of another atom.[101] If the excitation cross section for this process is large, then a "population inversion" or excess of atoms in this excited state will occur. This is precisely the condition required for maser action, and the successful operation of such a quantum plasma device producing maser oscillations at optical frequencies has been achieved recently.[102]

Further schemes have been put forth whereby the ion sheaths surrounding hypersonic re-entry vehicles would be utilized as coherent radiative elements and hence as a plasma antenna. However, considerably more work is still required in this direction. Other novel applications of plasma are also in progress.[103–107]

Electric Power Generation

If a dc magnetic field is applied in a direction perpendicular to a moving conducting fluid, an electric field is generated in a direction normal to both the magnetic field and the fluid flow. If now electrodes connected to an external load are appropriately placed, the electric field will cause a current to flow in the external circuit (as well as in the plasma). Energy is transferred to the load at the expense of the kinetic energy of directed motion of the conducting fluid. This is the basis of the dc magnetohydrodynamic generator.[108,109] The advantages of such magnetohydrodynamic (MHD) devices are that no moving parts, only a moving fluid, is required. The difficulties include characteristics of the working fluid (ionization and dissociation potentials, heat transfer properties), the methods of achieving adequate flow velocities, geometry, contamination and corrosion problems. MHD generators have been proposed for ac power generation[110] as well. These devices can be either pulsed or steady-state.

A plasma device for the conversion of heat into electricity is the thermionic diode[111–124] in which some of the electrons liberated from the cathode have sufficient energy to overcome the internal work function of the cathode and proceed to the anode where they lose their kinetic and potential energy. If the resulting energy level of the electrons in the anode is more negative than the original energy level at the cathode, then the device is capable of driving a current through a load and hence do useful work by this conversion of heat into electricity. The most serious limitation of such a scheme is the space charge of electrons which builds up near the anode and which inhibits electrons emitted from the cathode from reaching the anode. One technique of overcoming the space charge problem is to introduce cesium vapor into the device, which, upon contact with the hot anode, becomes a positive cesium ion and hence tends to neutralize the negative electron space charge. Other suggested schemes for controlling the charge effects include the use of a grid as a third control element and the use of crossed electromagnetic fields. Considerably more study is required on anode work functions

[101] A. Javan, in "Quantum Electronics," C. H. Townes, Ed., Columbia University Press, New York, N. Y.; 1960.
[102] A. Javan, *et al.*, "Population inversion and continuous optical maser oscillation in a gas discharge containing a He-Ne mixture," *Phys. Rev. Lett.*, vol. 6, pp. 106–109; February 1, 1961.
[103] W. Schmidt, "The microwave plasma burner," *Electron. Rundschau*, vol. 13, pp. 404–406; November, 1959.
[104] J. M. Anderson and L. A. Harris, "Negative-glow plasma as a cathode for electron tubes," *J. Appl. Phys.*, vol. 31, pp. 1463–1468; August, 1960.
[105] H. W. Lewis and J. R. Reitz, "Efficiency of the plasma thermocouple," *J. Appl. Phys.*, vol. 31, pp. 723–727; April, 1960.
[106] H. W. Lewis and J. R. Reitz, "Open-circuit voltages in the plasma thermocouple," *J. Appl. Phys.*, vol. 30, pp. 1838–1839; November, 1959.
[107] R. W. Pidd, *et al.*, "Characteristics of a plasma thermocouple," *J. Appl. Phys.*, vol. 30, pp. 1861–1865; December, 1959.
[108] L. Steg and G. W. Sutton, "The prospects of MHD power generation," *Astronautics*, vol. 5, pp. 22–25; August, 1960.
[109] H. Hurwitz, *et al.*, "Influence of tensor conductivity on current distribution in a MHD generator," *J. Appl. Phys.*, vol. 32, pp. 205–216; February, 1961.
[110] I. B. Bernstein, *et al.*, "Magnetohydrodynamics ac power generator," *Proc. Natl. Aerospace Electronics Conf.*, pp. 205–214; May, 1961.
[111] H. Moss, "Thermionic diodes as energy converters," *J. Electronics*, vol. 2, pp. 305–322; January, 1957.
[112] G. R. Feaster, "Thermionic diodes as energy converters—an addendum," *J. Electronics Control*, vol. 5, pp. 142–145; August, 1958.
[113] K. G. Hernquist, *et al.*, "Thermionic energy converter," *RCA Rev.*, vol. 19, pp. 244–258; June, 1958.
[114] G. N. Hatsopoulos and J. Kaye, "Analysis and experimental results of a diode configuration of a novel thermoelectron engine," Proc. IRE, vol. 46, pp. 1574–1579; September, 1958.
[115] W. B. Nottingham, "Thermionic diode as a heat-to-electrical power transducer," *J. Appl. Phys.*, vol. 30, pp. 413–417; March, 1959.
[116] V. C. Wilson, "Conversion of heat to electricity by thermionic emission," *J. Appl. Phys.*, vol. 30, pp. 475–481; April, 1959.
[117] J. M. Houston, "Theoretical efficiency of the thermionic energy converter," *J. Appl. Phys.*, vol. 30, pp. 481–487; April, 1959.
[118] H. F. Webster, "Calculation of the performance of a high vacuum thermionic energy converter," *J. Appl. Phys.*, vol. 30, pp. 488–492; April, 1959.
[119] H. W. Lewis and J. R. Reitz, "Thermoelectric properties of the plasma diode," *J. Appl. Phys.*, vol. 30, pp. 1439–1445; September, 1959.
[120] F. E. Jablonski, *et al.*, "Space-charge neutralization by fission fragments in the direct conversion plasma diode," *J. Appl. Phys.*, vol. 30, pp. 2017–2018; December, 1959.
[121] N. S. Rasor, "Figure of merit for thermionic energy conversion," *J. Appl. Phys.*, vol. 31, pp. 163–167; January, 1960.
[122] P. A. Lindsay and F. W. Parker, "Potential distribution between two plane emitting electrodes: pt. 2—thermionic engines," *J. Electronics Control*, vol. 9, pp. 81–111; August, 1960.
[123] F. G. Block, *et al.*, "Construction of a thermionic energy converter," Proc. IRE, vol. 48, pp. 1846–1852; November, 1960.
[124] E. N. Carabateas, *et al.*, "Interpretation of experimental characteristics of cesium thermionic converters," *J. Appl. Phys.*, vol. 32, pp. 352–357; March, 1961.

under operating conditions and materials to withstand the high temperatures required at the cathodes as well as on the space charge problem.

Semiconductor Microplasmas

A good analogy exists between the process of electrical breakdown in a low-density gas and the "avalanche effect" which occurs in some reverse-biased semiconducting diodes.[125–130] In these devices, a slight increase in the reverse voltage above some critical value causes a very rapid increase in current and the junction is said to "break down." The breakdown occurs due to the multiplication and resulting avalanche of the charge carriers both positive (holes) and negative (electrons) in the depletion layer of the device in a manner analogous to the creation of ionization by electrons in a gaseous discharge. Observations indicate that the breakdown occurs in very minute highly ionized regions or *microplasmas* of about 500 A in diameter. Such devices are of great practical potential for applications which require switching times of milli-microseconds. In addition, a number of other effects[131–133] found in gaseous plasmas may also be observed in semiconductors.

The above are only a few of the devices and applications for which plasmas are suitable. The current intense investigations on the properties of plasmas will undoubtedly result in an "avalanche" of further practical uses.

The Future

Today plasma physics is a challenging field of research in which exist many problems and few satisfactory solutions. It encompasses many disciplines including particle physics, physical electronics, aerodynamics, radiation physics, electromagnetic wave theory, magnetohydrodynamics, thermodynamics, spectroscopy, physical chemistry, quantum mechanics and many others. The interplay between these various fields of study cannot help but further the frontiers of science.

As slowly and surely solutions are found to the many pressing problems of plasma physics, what can we hope to achieve? The promise of the future includes a better understanding of the creation of the Universe and the forces at work in it, an almost inexhaustible supply of electrical power using thermonuclear fusion reactions, reliable communications with space and re-entry vehicles, propulsion devices appropriate for interplanetary travel, devices for producing and amplifying HF radio energy, electrical generators with no mechanical parts, and numerous new semiconductor devices. These are the goals of plasma physics research.

The immediate future must be devoted to a better understanding of the behavior of plasmas and related phenomena under various conditions. The most significant progress is thus most likely to be made in fundamental studies under controlled conditions. Application of the basic knowledge gleaned in this manner will follow immediately.

It is difficult to predict what the long-term future will hold. Will the present hopes and dreams be realized, or will some now incidental and little understood by-product of the present effort prove to be an even greater achievement than our present goals? Only the future will tell. One can, however, safely predict that plasma physics will grow both in importance and in scope. The present problems are indeed formidable, but the richness of the rewards for their solution warrant the interest and effort which is and will be devoted to plasma physics.

---

[125] D. J. Rose, "Microplasma in silicon," *Phys. Rev.*, vol. 105, pp. 413–418; January 15, 1957.

[126] R. Yee, *et al.*, "Avalanche breakdown in *N-P* germanium diffused junctions," *J. Appl. Phys.*, vol. 30, pp. 596–597; April, 1959.

[127] K. S. Champlin, "Microplasma fluctuations in silicon," *J. Appl. Phys.*, vol. 30, pp. 1039–1050; July, 1959.

[128] A. G. Chynoweth and K. G. McKay, "Light emission and noise studies of individual microplasmas in silicon *P-N* junctions," *J. Appl. Phys.*, vol. 30, pp. 1811–1813; November, 1959.

[129] M. Kikuchi and T. Iizuka, "Observation of microplasma pulses and electroluminescence in gallium phosphide single crystal," *J. Phys. Soc. Japan*, vol. 15, p. 935; May, 1960.

[130] C. D. Root, *et al.*, "Avalanche breakdown voltages of diffused silicon and germanium diodes," IRE Trans. on Electron Devices, vol. ED-7, pp. 257–261; October, 1960.

[131] L. M. Roth, *et al.*, "Theory of optical magneto-absorption effects in semiconductors," *Phys. Rev.*, vol. 114, pp. 90–104; April 1, 1959.

[132] M. Glicksman and M. C. Steele, "Plasma pinch effects in indium antimonide," *Phys. Rev. Lett.*, vol. 2, pp. 461–463; June 1, 1959.

[133] M. Date, "Magneto-plasma resonance in semi-conductors," *J. Phys. Soc. Japan*, vol. 15, pp. 1488–1492; August, 1960.

Oscillations and Noise in Low-Pressure DC Discharges*

F. W. CRAWFORD† AND G. S. KINO‡, ASSOCIATE MEMBER, IRE

Summary—**This is a review paper concerned mainly with oscillations and fluctuations which have been observed to occur either spontaneously or as a result of deliberate excitation in low-pressure, hot-cathode plasmas. Experimental observations on high- and low-frequency effects occurring spontaneously are discussed, and speculations are made about the possible generation mechanisms. In many cases, theories of these mechanisms have been treated in experiments involving deliberate excitation of oscillations, and comparisons are made where relevant.**

For device applications, and to relieve the difficulties which occur in quantitative experiments in plasma physics, it is important that the sources of spontaneous oscillations be understood and suppressed, if possible. The paper includes a discussion of work which has been carried out to reduce these effects, and concludes with some suggestions for further lines of attack on the problems.

I. Introduction

THE production of a plasma by means of a discharge in a gas at low pressure is of considerable interest today not only from the point of view of fundamental physics, but also for the possible device applications in fields as widely varied as nuclear fusion, generation of electromagnetic waves, and microwave amplification. The plasma medium is, however, complex. Its motion involves the many degrees of freedom associated not only with its internal space-charge properties and its several ionization processes, but also with the additional hydrodynamic properties analogous to those of a neutral conducting fluid, and the surface motion of a finite medium. It is not surprising then that an unfortunate feature of the plasma is its inclination towards instability, and most properties of a "steady-state" plasma, *e.g.*, number density, current, and maintaining voltage, are found on close examination to be fluctuating with amplitudes far above reasonable estimates for such phenomena as thermal noise. For example, voltage fluctuations at the anode of a discharge tube are typically in the range of hundreds of millivolts to volts. The presence of strong collective processes is indicated, and analysis of the frequency spectrum of the disturbances usually indicates strong components in two distinct ranges: zero to a few Mc, and the microwave band. In this paper we shall call these unwanted fluctuations "noise," regardless of whether they are coherent or incoherent.

* Received by the IRE, August 7, 1961. The research reported in this paper has been jointly sponsored by the Electronics Research Directorate, AF Cambridge Research Labs., Office of Aerospace Res., USAF and by the U. S. Atomic Energy Commission.

† Service de Physique Appliquee, Section d'Ionique Generale, Centre des Etudes Nucleaires de Saclay, Gif-sur-Yvette (Seine-et-Oise), France. Formerly at Microwave Lab., W. W. Hansen Labs. of Physics, Stanford University, Stanford, Calif.

‡ Microwave Lab., W. W. Hansen Labs. of Physics, Stanford University, Stanford, Calif.

For microwave applications such as amplification and frequency generation, it is clearly desirable to minimize the level of the high-frequency fluctuations, but it is also necessary to reduce the low-frequency components since they can cause substantial modulation of propagated or generated signals. Kino and Allen [1] have shown theoretically and experimentally that there is strong phase modulation of propagated signals, and that phase information is lost rapidly near cutoff, while the results of Boyd, Field, and Gould [2]–[5] on microwave amplification in plasmas have indicated amplitude modulation of the output in the tens of kilocycles range to a depth of as much as 30 per cent [3].

Before approaching the problem of suppressing the fluctuations, it is necessary to determine their generation mechanisms and to establish which of them, if any, are present as essential processes in the maintenance of the plasma. This last point is extremely important because it has been recognized for many years that some features of the dc discharge cannot be explained by a steady-state theory. The most notable is the phenomenon known as "Langmuir's paradox." This is the experimental observation that a Maxwellian distribution is maintained in circumstances where the effects of collisions could not offset the depletion of the high-energy tail by wall losses [6], [7]. Refined theoretical calculations showed that strong microscopic interaction processes would be required [8]–[10], but experiment showed that they were not present [11]. There is the possibility of macroscopic effects, and collective oscillations have been postulated as the means for making up the deficiency [12], though the site of origin and nature of their generation is still controversial [13], [14].

The purpose of this paper is to review the experimental and theoretical work which has been carried out on oscillations and noise in dc discharges at pressures where the mean free path for electron-neutral collisions is comparable to the dimensions of the discharge tube. We shall exclude much of the work carried out at higher pressures, the work on oscillations and noise occurring in magnetic fields, and the great volume of work on instabilities peculiar to fusion devices (mainly in the presence of a magnetic field), except where they serve to throw light on an effect of interest. References to noise and oscillation problems at higher pressures are to be found summarized in the work of Cobine and Gallagher [15], Fite [16], Sears [17], and Van der Ziel [18]. An excellent summary of the American work on the problem of instabilities and

TABLE I

Quantity	Symbol	Typical Value	Variation
Radius of column	a	1 cm	
Pressure	p	1.1 μ	Increases with temperature of coolest part of tube. Range 0.2–10μ.
Longitudinal field	E	0.8 v/cm	
Current density	J	0.1 amp/cm^2	
Average number density:			
Neutrals	N	3.9×10^{13}/cm^3	$N=9.7\times10^{15}p/T_N$
Electrons	n_e	10^{10}/cm^3	$n_e=n_i=n$ approximately proportional to current density; depends on pressure. Range 10^8–10^{13}.
Ions	n_i	10^{10}/cm^3	
Temperature:			
Neutrals	T_N	293°K	Range 273°K–320°K
Electrons	T_e	30,000°K	Decreases with increasing pressure or plasma volume; increases slightly with current. Range 10–50,000°K
Ions	T_i	~500°K	Probably increases with T_e
Average collision frequencies:			
Neutral-neutral (elastic)	ν_{NN}	5 kc	$\nu_{NN}=v_{tN}/L_{NN}$
Ion-neutral (elastic)	ν_{iN}	~5 kc	$\nu_{iN}\propto p\cdot\nu_{iN}\ll$collision frequency for charge exchange.
Electron-neutral (elastic)	ν	25 Mc	$\nu\doteq v_{te}/L_{eN}$
Electron-ion (elastic)	ν_{ei}	20 kc	$\nu_{ei}\doteq 2.6nT_e^{-3/2}$ ln Λ where ln Λ is a parameter of the order of 4, tabulated by Spitzer [68].
Electron-electron (elastic)	ν_{ee}	25 kc	$\nu_{ee}=3.1nT_e^{-3/2}$ ln Λ
Ion-wall (recombination)	ν_{iW}	~350 kc	$\nu_{iW}\doteq 2v_{ia}/a$
Electron-wall (recombination)	ν_{eW}	~350 kc	$\nu_{eW}=\nu_{iW}$
Electron-neutral (ionizing)	ν^I_{eN}	~350 kc	$\nu^I_{eN}=\nu_{iW}$
Mean free path:			
Neutral-neutral (elastic)	L_{NN}	4.4 cm	$L_{NN}=4.9/p$
Ion-neutral (elastic)	L_{iN}	5 cm	L_{iN} of same order as L_{NN}
Electron-neutral (elastic)	L_{eN}	5 cm	$L_{eN}\propto 1/p\cdot L_{eN}$ usually in range where it is a rapidly decreasing function of T_e.
Electron-ion (elastic)	L_{ei}	7×10^3 cm	$L_{ei}=v_{te}/\nu_{ei}$
Electron-electron (elastic)	L_{ee}	8.5×10^3 cm	$L_{ee}=v_{te}/\nu_{ee}$
Thermal speed:			
Electrons	v_{te}	1.3×10^8 cms	$v_{te}=6.74\times10^7T_e^{1/2}$
Ions	v_{ti}	$\sim2.5\times10^4$ cms	$v_{ti}=11.1T_i^{1/2}$
Neutrals	v_{tN}	2.0×10^4 cms	$v_{tN}=11.1T_N^{1/2}$
Drift velocities:			
Axial-electrons	v_{ez}	6.3×10^7 cms	$v_{ez}=6.25\times10^{18}J/n_e$
Radial-ions at edge of positive column	v_{ia}	1.7×10^5 cms	$v_{ia}\doteq 325T_e^{1/2}$
Plasma frequency:			
Electrons	f_{pe}	900 Mc	$f_{pe}=8980n_e^{1/2}$
Ions	f_{pi}	1.5 Mc	$f_{pi}=14.8n_i^{1/2}$
Debye length (electrons)	l_e	0.022 cm	$l_e\doteq v_{te}/\omega_{pe}$
Potential drop across sheath	V_s	18 volts	$V_s\doteq 6\times10^{-4}T_e$

oscillations in fusion devices may be found in the book by Glasstone and Lovberg [19].

Our range of interest includes one of the most common experimental discharges, mercury vapor at room temperature, which has a pressure of the order of 1 μ; unless stated, it may be assumed that the experimental data described were taken in this gas. In general, the gas used has little effect on the nature of the phenomena, though there may be variations in degree. Similarly, many mechanisms to be discussed are independent of the type of cathode used. The majority of the work has been carried out with hot cathodes, and except where stated, their use also may be assumed.

After sketching briefly the characteristics of a low-pressure discharge, we shall survey low-frequency and high-frequency phenomena separately, and conclude with some reference to relations between these two ranges and possible techniques for reducing the amplitude of plasma noise.

II. Characteristics of a Typical Low-Pressure Plasma

To give some idea of the ranges of values encountered experimentally, typical figures are quoted in Table I for a mercury-vapor discharge at a pressure of 1.1 μ (~20°C).

Further information on the experimental determination of electron temperatures and general properties of plasmas is to be found in the papers of Killian [20], Klarfeld [21], and Boyd [22], and in the pioneer work of Langmuir and Mott-Smith on the use of probes [23]–[27].

A. Regions of the Discharge

Probe measurements and visual observations of discharges have some measure of correlation, and Fig. 1 shows the appearance of a typical discharge.




Fig. 1—Characteristic regions of a typical low-pressure discharge. I. Cathode sheath. II. Unscattered primaries and ultimates. III. Meniscus. IV. Slowed primaries, secondaries, and ultimates. V. Ultimates. VI. Anode fall. VII. Wall sheath.

Region I: The properties of this region, which are analogous to those of a simple diode in which electrons are emitted at the cathode and ions at the anode, have been treated analytically by Langmuir [28]. In this low potential region, which has a thickness of a millimeter or less [29], electrons are emitted at the cathode, yielding an excess of electron space charge, *i.e.*, an electron sheath, near the cathode. Ions stream toward

the cathode from the main plasma region, forming an ion sheath at the surface of the plasma facing the cathode. The potential drop across region I is of the order of the ionization potential of the gas; consequently very few electrons and ions are produced by collisional ionization in this region. As the number of elastic collisions of electrons with neutrals is also small in this region, the majority of the electrons emerge from region I with energy appropriate to the voltage drop across the sheath, and the electron stream has only a very small velocity spread.

Region II: It had been shown in the early experiments of Langmuir [6] and Dittmer [12], using flat probes to intercept the primary beam from a tungsten filament cathode, that at low anode currents two classes of electrons could be observed: the electrons emerging from region I ("primary" electrons) and a group of electrons with an isotropic Maxwellian velocity distribution ("ultimate" electrons). The ultimate electrons were approximately 1000 times more numerous than the primary ones. However, as current was increased a scattering phenomenon occurred introducing a small additional electron velocity group ("secondary" electrons) with an isotropic Maxwellian velocity distribution, and energies intermediate between the primary and the ultimate groups. Concurrent with this effect was a slowing down of the mean velocity of the primary electrons and a superimposition of an approximately Maxwellian distribution upon it. As a typical result, it was observed that a 50-v beam was slowed to a mean velocity corresponding to 36 v, but some electrons from it could reach potentials as high as 90 v. The anisotropy of the primary beam and the isotropy of the secondary and ultimate groups were established by turning the probe parallel to the primary stream [6]. The results for secondary and ultimate electrons were identical, but no primary electrons were observed.

Druyvesteyn and Warmoltz [30]–[32] were able to show that changes in velocity distribution, space potential, and electron concentration occurred in distinct narrow regions a few tenths of a millimeter thick. These were studied in greater detail by Merrill and Webb [33] using a probe movable with considerable precision. Further work by Emeleus and his co-workers [34]–[42] has shown that the first of these scattering regions lies to the cathode side of, or in, region III.

Region III: This is a bright meniscus-shaped region of the same diameter as the primary beam and with its convex side towards the cathode. It may be bounded on its anode side by a dark layer. Increasing pressure or current moves the meniscus toward the cathode. Continued increase into current saturation may produce a second meniscus near the anode [42].

Region IV: This is a region in which there is considerable "turbulence" [43], [44]. The primary electrons are deviated laterally into approximately conical converging and diverging beams. The converging beams do not appear to cross over, but there may be a bright spot at the focus. The diverging "wings" may have semi-vertical angles up to 30° or more. No definite explanation has yet been given for them. Sturrock [45]–[48] has suggested that they are the result of a wave-damping mechanism, while Emeleus has proposed a wave-diffraction explanation [37].

If anode-cathode spacing is reduced [36], [37], the wings bow in and attach themselves to the anode. Further decrease in spacing causes the wings to disappear and the meniscus to lose definition. Photographs showing these phenomena clearly are given in [35] and [41].

Region V: Further out in the discharge, only ultimate electrons can be detected. Their temperature depends on the factors indicated in Table I and also on the operating point on the current/voltage characteristic: for example, there is a sharp drop in temperature at the point of cathode current saturation [49].

In this region, known as the positive column of the discharge, the theoretical treatment of Tonks and Langmuir [50] assumes that the electrons have a Maxwellian distribution of velocities and that there are radial variations of electron charge density and potential over the cross section of the discharge column. The ions are assumed to move radially outward from their point of generation towards the wall, with a velocity corresponding to free motion over the potential drop through which they fall. The theoretical treatment, which has been confirmed by probe measurements [21], [50], [51], predicts that the density near the wall may be as much as 50 per cent below its value at the center of the column.

Region VI: At the anode of the discharge there is a sheath, the polarity of which is dependent on anode size and current [50]. Most commonly, the anode will be negative with respect to the potential of the positive column (the space potential) by a few volts.

Region VII: At the nonconducting walls of the tube, a thin dark sheath forms. Both the thickness of this sheath and the potential drop across it are dependent on the electron temperature in the positive column. Criteria for the formation of this sheath have been given by Bohm [52] and by Tonks and Langmuir [28], [50].

B. Scattering Effects

It is interesting to observe the effect of crossing two beams of primary electrons. This was explored by Langmuir [6] using identical probe-cathode assemblies mounted at right angles, and by Garscadden and Emeleus [41] using a movable low-voltage electron gun emitting a beam which passed across the main discharge column. Both sets of experiments indicated that the second beam became scattered only if it passed through a volume of plasma in which the primary beam was being, or had been, scattered. In the moving-gun ex-

periment the degree of energy spread of the secondary beam was found to be quite substantial: A 40-v secondary beam traversing a region containing a 22-v primary beam from the cathode obtained an energy spread along its direction of motion corresponding to an excess energy of approximately 8 v, while the cathode beam incurred a spread of 14 v. This implies that there are strong transverse fields, an observation supported by some experiments of Allen, Bailey, and Emeleus [35] in which the cathode beam was split into a number of flat strips by a grid close to the cathode. At the usual position of a meniscus, parallel flow was observed to break down. The beams spread and merged into each other.

The early experiments on scattering failed to explain several features, *e.g.*, the variation of distance to the scattering region with beam voltage and current, and the problem of why only the primary electrons were scattered in a region containing many times more ultimate electrons. The ultimate and secondary electrons could be explained as resulting from elastic and inelastic collisions with neutrals, but the mechanism of the scattering process proved elusive. Both Langmuir and Dittmer realized that high-frequency oscillations in the plasma could produce the effect, but neither succeeded immediately in observing their presence. The issue was, however, reopened by Penning [53], [54], whose experiments verified that such oscillations did exist. The nature of these oscillations, and the experimental data on them, will be taken up again in Section III.

III. High-Frequency Oscillations

A. Waves in a Uniform Plasma

1) Zero Temperature Theory

In order to understand what types of oscillations may occur in a plasma, it is necessary to consider the waves which can propagate through such a medium. When only the high-frequency oscillations are considered, it is usual to adopt a model in which the plasma is regarded as a neutral medium in which the relatively heavy positive ions do not move in response to the RF fields. The first derivation of this type was published as long ago as 1906 by Lord Rayleigh, who found an expression for the natural oscillation frequency of electrons embedded in positive charge [55]. Similar results were obtained by Mott-Smith and by Tonks, their work being quoted by Langmuir [8] in 1928 in a paper which apparently introduced the term "plasma" for the first time. Further extensions of the same principles were given by Thompson [56] and discussed fully in the classic paper by Tonks and Langmuir in 1929 [57], [58].

It is instructive to present here some of these early results, using the Eulerian derivation which is now common, and to consider some of the later implications of this work. We consider a zero-temperature plasma in which the ions are regarded as stationary. All ac quantities will be denoted by the subscript 1. The motion of the electrons within the plasma is given by the Eulerian equation of motion,

$$\frac{\partial \boldsymbol{v}_1}{\partial t} + (\boldsymbol{v}_1 \cdot \nabla)\boldsymbol{v}_1 = -\frac{e}{m_e}\boldsymbol{E}_1, \tag{1}$$

where $-e$ is the electron charge, m_e is the electron mass, $\boldsymbol{v}_1$ is the velocity, and $\boldsymbol{E}_1$ is the electric field strength. For small perturbations we may neglect the second term in this equation and assume that all quantities vary as $\exp(j\omega t)$. Eq. (1) then takes the form

$$j\omega \boldsymbol{v}_1 = -\frac{e}{m_e}\boldsymbol{E}_1. \tag{2}$$

For small perturbations, the current density $\boldsymbol{J}_1$ is

$$\boldsymbol{J}_1 = -en_e\boldsymbol{v}_1, \tag{3}$$

it follows that the current density is related to the field by

$$\boldsymbol{J}_1 = \frac{e^2 n_e}{j\omega m_e}\boldsymbol{E}_1. \tag{4}$$

We may now find the ac charge density $\rho_1 (= -en_{e1})$ by using the equation of continuity:

$$\nabla \cdot \boldsymbol{J}_1 + j\omega\rho_1 = 0. \tag{5}$$

The divergence equation for the electric field is

$$\nabla \cdot \boldsymbol{E}_1 = \frac{\rho_1}{\epsilon_0}, \tag{6}$$

where ϵ_0 is the permittivity of free space. In order to satisfy (4)–(6) simultaneously, we find that

$$\left(1 - \frac{\omega_{pe}^2}{\omega^2}\right)\nabla \cdot \boldsymbol{E}_1 = 0, \tag{7}$$

where

$$\omega_{pe}^2 = \frac{n_e e^2}{\epsilon_0 m_e}. \tag{8}$$

$f_{pe} (= \omega_{pe}/2\pi)$ is usually called the electron plasma frequency. It follows from (7) that either $\nabla \cdot \boldsymbol{E}_1 = 0$, and there is no ac space charge within the volume of the plasma, or $\omega = \omega_{pe}$. Let us consider the first alternative: it will be seen from (4) that Maxwell's equations imply that

$$\nabla \times \boldsymbol{H}_1 = j\omega\epsilon_0\boldsymbol{E}_1 + \boldsymbol{J}_1 = j\omega\epsilon_0(1 - \omega_{pe}^2/\omega^2)\boldsymbol{E}_1, \tag{9}$$

where $\boldsymbol{H}_1$ is the magnetic field intensity. We can regard the plasma as behaving like a medium with dielectric constant $\epsilon = \epsilon_0(1 - \omega_{pe}^2/\omega^2)$. This dielectric constant is negative below the plasma frequency, but positive and smaller in magnitude than the dielectric constant of free space at frequencies above the plasma frequency. When $\omega \neq \omega_{pe}$ there is no space charge within the volume

of the plasma. Consequently, in an infinite plasma, plane electromagnetic waves can propagate at frequencies above the cutoff at the plasma frequency. In a plasma bounded by metal conductors, waves somewhat similar to the usual waveguide modes can propagate above the plasma frequency. With insulating boundaries, it has been shown by Gould and Trivelpiece [59], [60], Smullin and Chorney [61], Fainberg and Gorbatenko [62], and Schumann [63], [64] that waves with a phase velocity slower than the velocity of light in free space can propagate along the plasma column at frequencies below the plasma frequency. These waves have fields which have a maximum amplitude at the plasma surface. The addition of magnetic fields changes this picture radically, as it causes the plasma to behave like a medium with a tensor dielectric constant. Of particular importance is the possibility of a slow backward wave propagating at frequencies above the plasma frequency. This behavior has been demonstrated theoretically and experimentally by Gould and Trivelpiece [59], [60], and discussed theoretically by the authors already mentioned [61], [62], [64].

The alternative solution of (7), $\omega=\omega_{pe}$, implies that there is a possibility of natural oscillations at the plasma frequency. These oscillations, by virtue of (9), have no ac magnetic fields associated with them, and hence are usually referred to as electrostatic oscillations. Because their frequency does not depend on the spatial variation of the fields, they have zero group velocity and are entirely local in character. The behavior is such that the electrons, when disturbed, oscillate about their equilibrium position at the plasma frequency.

2) *Finite Temperature Theory*

In practice, the nonpropagating disturbance at the plasma frequency is not localized because the electrons are not at zero temperature. The Thomsons [65]–[67] took account of the electron temperature and derived a dispersion relation for one-dimensional waves of the form

$$\omega^2 = \omega_{pe}^2 + \frac{\gamma k T_e}{m_e}\beta^2, \tag{10}$$

where k is Boltzmann's constant and β is the propagation constant of the wave. This dispersion relation was based incorrectly on isothermal expansion of the plasma medium, with the result that the constant γ was found to be unity. Subsequent treatments of the type given by Spitzer [68] indicated different values of γ lying between 1 and 3.

Thermal velocities of the electrons in a plasma may also be taken into account by making the alternative assumption of no collisions and working directly with Boltzmann's equation, or by regarding the plasma as a number of electron streams of number density n_r with individual dc velocity v_r, as was done by Pierce and Morrison [69] and Walker [70]. Then for a one-dimensional system, assuming a wave with field components that vary as $\exp[j(\omega t-\beta z)]$, it follows from (1) that the ac velocity of the rth electron stream is

$$v_{1r} = -\frac{eE_1}{jm_e(\omega-\beta v_r)}. \tag{11}$$

By using the familiar relations between current and charge, and the equation of continuity, it is found that the ac charge density associated with this stream is

$$\rho_{1r} = -\frac{je^2 n_r \beta E_1}{m_e(\omega-\beta v_r)^2}. \tag{12}$$

Finally by using the divergence equation for the field, (6), and summing up the total contribution to the charge of all the individual electron streams, we find that

$$\beta E_1 = \sum_{r=1}^{r=s} \frac{e^2 n_r \beta E_1}{m_e \epsilon_0(\omega-\beta v_r)^2} \tag{13}$$

or

$$1 = \sum_{r=1}^{r=s} \frac{e^2 n_r}{m_e \epsilon_0(\omega-\beta v_r)^2}. \tag{14}$$

This is the dispersion relation for a system of s streams of electrons.

If we now regard a plasma as consisting of an infinity of electron streams, so that the number density of electrons contained within the velocity range $v\rightarrow(v+dv)$ is $n_e f(v)dv$, where

$$n_e = \sum_{r=1}^{r=\infty} n_r$$

and $f(v)$ is the velocity distribution, we have in the limit

$$\frac{n_r}{n_e} \rightarrow f(v)dv, \tag{15}$$

and (14) takes the form

$$1 = \omega_{pe}^2 \int_{-\infty}^{\infty} \frac{f(v)dv}{(\omega-\beta v)^2}. \tag{16}$$

An often-quoted form of (16) may be deduced by partial integration:

$$1 = -\frac{\omega_{pe}^2}{\beta} \int_{-\infty}^{\infty} \frac{(\partial f/\partial v)dv}{(\omega-\beta v)}. \tag{17}$$

The integral relation of (17) was first deduced by Vlasov [71], [72] by using Boltzmann's equation. Vlasov integrated this expression by expressing the denominator in terms of an expansion in powers of $\beta v/\omega$ and retaining only terms up to second order in $\beta v/\omega$. He obtained the dispersion relation of (10) with $\gamma=3$. It was pointed out by Landau [73] that such a

procedure is not valid because there is a pole in the integrand at $v=\omega/\beta$, and Vlasov had only considered the principal integral. Using a Laplace transform method, Landau integrated (17), his integral being taken to the right-hand side of the pole at $v=\omega/\beta$. The contribution of the pole in the integrand then yielded the modified dispersion relation

$$\omega^2 = \omega_{pe}^2\left[\left(1+\frac{3kT_e}{m_e}\beta^2\right) - j\pi\left(\frac{\omega}{\beta}\right)^2\left(\frac{\partial f}{\partial v}\right)_{v=\omega/\beta}\right]. \quad (18)$$

For a Maxwellian distribution of electron velocities,

$$f(v) = \left(\frac{m_e}{2\pi kT_e}\right)^{1/2}\exp\left(-m_e v^2/2kT_e\right), \quad (19)$$

we have

$$\omega^2 = \omega_{pe}^2\left[1+\frac{3kT_e}{m_e}\beta^2 + j\left(\frac{\omega}{\beta}\right)^3\left(\frac{m_e}{kT_e}\right)^{3/2} \cdot\sqrt{\frac{\pi}{2}}\exp\left(-m_e\omega^2/2\beta^2kT_e\right)\right]. \quad (20)$$

The additional term in this dispersion relation implied that any wave set up in the plasma would be damped, the damping being most severe for a wave with a phase velocity comparable to the mean velocity of the electrons, a phenomenon now known as Landau damping.

Van Kampen [74], [75], Bohm and Gross [76]–[78], and Berz [79] derived (17) directly from Boltzmann's equation, carefully considering the region near $v=\omega/\beta$. Berz showed that Landau damping becomes appreciable for wavelengths shorter than 20 Debye lengths. Van Kampen, and Bohm and Gross found the following form for the ac perturbation in charge density, $f_1(v)$:

$$f_1(v) = -\frac{\omega_{pe}^2\dfrac{\partial f}{\partial v}}{\beta(\omega-\beta v)} + g_1(v)\delta(\omega-\beta v), \quad (21)$$

where $g_1(v)$ is an arbitrary function of v, and $\delta(\omega-\beta v)$ is Dirac's delta function. This result gives rise to an extra term, $g_1(\omega/\beta)$, on the right-hand side of (17) which represents a periodic motion transported by all electrons at their own velocity. There is, therefore, no unique dispersion relation between ω and β. This feature was considered in great detail in a series of papers by Bohm and Gross [76]–[78], who gave a physical meaning to the damping in terms of trapped electrons. They demonstrated theoretically that a wave of finite amplitude propagating in a plasma medium would interact strongly with electrons traveling at a velocity near to its phase velocity. Electrons moving slightly slower than the phase velocity of the wave would tend to be accelerated and thus absorb energy from the wave; the converse would be true for electrons traveling slightly faster than the wave. For a velocity distribution function which decreases monotonically with velocity, there are more slow electrons than fast ones, so that there is a damping of the wave.

It has been remarked by Allis [80] that in a steady state, $(\partial f/\partial v)_{v=\omega/\beta}=0$, so that there is then no Landau damping and Vlasov's dispersion equation is correct. A class of solutions can be obtained for which $(\partial f/\partial v)_{v=\omega/\beta}=0$, representing undamped disturbances. These can be of large amplitude. They have been examined in detail by Bernstein, Greene, and Kruskal [81], but it is difficult to see under what physical conditions they could be set up. In practice, all waves are damped by collisions which tend to re-Maxwellianize the trapped electrons taking part in such a steady-state wave motion.

Further discussions of plasma wave solutions have been given by Allis [80], Gross and his co-workers [82]–[84], Berz [79], Bohm and Pines [85]–[87], Twiss [88]–[90], Bailey [91], and Piddington [92], [93]. Clear summaries of the issues are given by Van Kampen [74], [75] and Ecker [94]–[96]. The work has been extended to take account of the effect of magnetic field on the propagation of waves in a hot plasma by, among others, Drummond [97], [98], Mower [99], Gordeyev [100], and Bernstein [101]. An alternative physical picture of Landau damping in terms of "phase mixing" has been given by Case [102] and Van Kampen [74], [75].

Recent reviews of the theory of plasma oscillations have been made by Oster [103], Jackson [104], Bernstein and Trehan [105], and Drummond [106]. The last two contain very comprehensive bibliographies.

Another type of damping due to nonlinear effects in a plasma has been discussed by Dawson [107] and Sturrock [45]–[48], who show that a single electrostatic wave may remain undamped. Sturrock shows also that two electrostatic waves of frequencies ω_1 and ω_2, propagating at an angle to each other, can interact to transfer energy into a plane electromagnetic wave of frequency $(\omega_1+\omega_2)$. This model also yields a possible mechanism to explain the strong radiation at $2\omega_{pe}$ observed from the sun.

3) *Experimental Observations*

From the foregoing discussion we might expect to find that there would be oscillations occurring naturally in the discharge near the plasma frequency. Such oscillations would have low group and phase velocities, and would be difficult to detect from outside the chamber. This last point follows from (7), where it may be seen that for a zero temperature plasma the total current is zero at the plasma frequency. When the temperature is finite, the total current is extremely small as compared with either the displacement or conduction current within the plasma, so that the fields outside the plasma due to this type of oscillation should be small.

The first observation of high-frequency oscillations appears to have been made by Penning [53], [54] in 1926. Using a Lecher wire system connected to the elec-

trodes, he observed oscillations around 500 Mc in both argon and mercury under conditions when the scattering phenomenon described in Section II was taking place. Langmuir [8] and Tonks confirmed these observations measuring frequencies up to 1200 Mc in regions of the plasma not traversed by the primary beam, and an additional component of about 100 Mc in the beam region, which appears to have been due to oscillations of the beam alone. Later measurements [57] by these workers showed the relation for the oscillation frequency $f \propto n_e^{1/2}$ to be true within the limits of experimental error. Some additional frequencies observed appear to be related to the effects of heater current and its direction of flow. This effect has been examined in more detail by Armstrong and Emeleus [108] using a tungsten filament at the axis of a cylindrical anode in mercury vapor, argon, and other gases. They discovered that the oscillation intensity diminished considerably during the off-periods when the filament current was interrupted at 2 kc, and that such factors as length and inclination of the filament were important. Further influences on the amplitude and frequency of oscillations were exerted by the choice of operating point on the V/I characteristics (filament current and pressure) of the discharge. Increases in filament current and pressure both caused increases in frequency. Oscillations could be observed even in the Townsend discharge region before a plasma was formed. No essential changes in these results could be observed when the anode voltage was swept at 50 cps. The highest frequency observed was 6 kMc, and up to 1 per cent conversion efficiency could occasionally be obtained. Later experiments by Emeleus and Bailey [109] were directed towards increasing the plasma frequency by increasing the pressure, and 10 kMc was achieved at 70 μ, though the power withdrawable was only 1 μw.

So far we have considered only experiments involving observation of oscillations near the plasma frequency. Early experiments involving simultaneous measurements of electron density and plasma frequency indicated agreement with the theoretical value to within 10 per cent [110]: that there were specific regions of generation, and that there were relations between frequency and tube geometry. These results are discussed in the following Subsections.

B. Beam-Plasma Interactions without Sheaths

1) Basic Mechanisms

The theories that we have discussed described propagation through a plasma which was either at zero temperature or in which the velocity distribution of the electrons was a monotonically decreasing function of velocity. In the latter case, the waves were in some theories undamped and in others damped. Bohm and Gross [76]–[78] discussed the interpretation of the wave solutions when the velocity distribution was not a monotonic function of velocity and showed that under certain conditions growing waves could exist. Physically, the phenomenon is best understood by considering the interaction between two interpenetrating charged beams of different velocity. This was first done almost simultaneously by Haeff [111], [112], Nergaard [113], Pierce [114], [115], and Hebenstreit [116]. They showed that when two beams of velocities v_a and v_b and plasma frequencies $\omega_{pa}/2\pi$ and $\omega_{pb}/2\pi$ interact, the following dispersion equation, which may be derived directly from (14), is valid:

$$\frac{\omega_{pa}^2}{(\omega - \beta v_a)^2} + \frac{\omega_{pb}^2}{(\omega - \beta v_b)^2} = 1. \tag{22}$$

This dispersion equation predicts that when the two beams travel in the same direction with approximately, but not exactly, the same velocities, growing waves can propagate along the system in the direction of motion of the beams. These authors also demonstrated the phenomenon experimentally, using two electron beams.

The same theory describes the interaction of an electron beam with a stationary plasma through which it passes, and was also used by Pierce [117] to explain the ion oscillations which occur when an electron beam in a gassy system passes through the ion cloud generated by its collisions with gas molecules. The dispersion equation becomes

$$\frac{\omega_p^2}{\omega^2} + \frac{\omega_{pb}^2}{(\omega - \beta v_b)^2} = 1 \tag{23}$$

where ω_p is the electron plasma frequency of the plasma through which the beam passes, or the ion plasma frequency of the stationary ion cloud, and ω_{pb} is the plasma frequency of the electron beam. This equation may be written in the form

$$\beta = \frac{\omega}{v_b} \pm \frac{\omega_{pb}}{v_b(1 - \omega_p^2/\omega^2)^{1/2}}. \tag{24}$$

It will be seen that the propagation constant for waves traveling along the beam becomes complex for frequencies below ω_p. There will be the possibility of strong amplification effects at frequencies in the neighborhood of the plasma frequency, the gain becoming infinite when $\omega = \omega_p$. Physically, this effect takes place because, below ω_p, the plasma behaves like a medium of negative dielectric constant in which the space-charge forces due to bunching of the electron beam are reversed in sign from their values in free space.

These results and their interpretations have been discussed at length by Piddington [93], Twiss [118], Sturrock [119], [120], Buneman [121], and Drummond [106]. These authors pointed out that knowing the dispersion relation of a system is not sufficient. For instance, (23) yields complex β, *i.e.*, a growing wave with real ω. But it also implies that with real β, ω can be complex, *i.e.*, the waves will grow in time. However, because this latter instability is "convective," as Sturrock describes it, such a result can only be obtained in

an infinite system, or in one where there is feedback.

Physically, this is because the waves that are present propagate and grow in the direction of motion of the electron beam. The solution with ω complex, *i.e.*, oscillations, cannot apply unless energy can be returned from the output end of the system to the input. This will only occur if there is some additional feedback mechanism not included in the theory.

The results have been generalized by Budker [122], Sturrock [123], Tchernov and his co-workers [124], [125], Trivelpiece [126], Boyd, Field and Gould [2]–[5], and Allen and Kino [127], [128], to take into account the effects of finite diameter of the beam, finite diameter of the plasma, and the presence of a magnetic field in the direction of motion of the beam. Fig. 2 indi-




Fig. 2—Gain/frequency characteristics for beam-plasma interactions in an infinite plasma.

cates the basic conclusions reached by these authors, *i.e.*, that the gain does not become infinite, and that there can be gain above the plasma frequency. In a finite magnetic field, the gain reaches its maximum above the plasma frequency and can remain finite up to a frequency given by

$$\omega = (\omega_{pe}^2 + \omega_{ce}^2)^{1/2}, \tag{25}$$

where $\omega_{ce} = (eB/m_e)$ is the cyclotron frequency of an electron in the magnetic field B.

The original Bohm and Gross [76]–[78] treatment took account of the thermal velocity distribution of the plasma electrons by a simple extension of (23), and resulted in the dispersion relation

$$\frac{\omega_{pe}^2}{\omega^2 - 3(kT_e/m_e)\beta^2} + \frac{\omega_{pb}^2}{(\omega - \beta v_b)^2} = 1. \tag{26}$$

The regions of amplification given by this formula have been studied by Akhiezer and Fainberg [129], Feinstein and Sen [130], Twiss [118], [131], Lampert [132], Sumi [133], [134], Boyd, Field and Gould [3]–[5], Sturrock [119], Filiminov [135], Buneman [136], and Tchernov and Bernashevski [125], who considered the effects of thermal motions in both the beam and the plasma, collisions of electrons with neutrals and ions, and in the case of Sumi, the effect of an electron beam density comparable to that of the plasma. As might be expected, both collisions and finite temperature reduce the gain to a finite value. However, these effects on the gain are not likely to be as great as that of finite beam diameter. In addition, the gain is found to reach its maximum above the plasma frequency, when the electron temperature of the plasma is finite, although it decreases to zero rapidly with further increase in frequency.

2) *Experimental Verifications*

Before considering whether beam-plasma interactions might occur naturally in plasmas, we shall discuss the experimental verification of the contentions made above concerning amplification. The first published confirmation of the effect was presented by Boyd, Field, and Gould [2]–[5] in 1958, and extended subsequently by Tchernov and his co-workers [124], [125], Demirkhanov, Gevorkov and Popov [137], and by Allen and Kino [127], [128].

The type of experimental tube used by Boyd, Field, and Gould [2]–[5] is shown schematically in Fig. 3.




Fig. 3—Typical apparatus for beam-plasma interaction experiments of the type performed by Boyd, Field, and Gould.

Using helices coupled to external waveguides to modulate and demodulate the electron beam, gain was observed over the frequency range 500–4000 Mc. Gain of a few db/cm was observed reaching a maximum at the plasma frequency, as calculated from additional measurements. Allen and Kino [127], [128], using helix coupling to a beam traversing a magnetically-confined synthetic cesium plasma, obtained good agreement with their theoretical analysis of the gain parameter, taking magnetic field and the finite dimensions of the plasma and the beam into account. Typical gain figures were approximately 5–10 db/cm at 1 kMc and approximately 10–15 db/cm at 3 kMc. Tchernov, *et al.* [124], [125], used an experimental arrangement similar to that of Boyd, but with the plasma density increased by immersing the tube in an axial magnetic field. They were able to obtain amplification between 20 and 40 db over the range of plasma frequencies 1–10 kMc. It also appeared that the gain parameter reached a saturation value with increasing current. A possible explanation for this phenomenon, due to the finite diameter of the beam, has been given by Sturrock [123]. The influence of increasing the mercury vapor pressure was studied and it was shown that a smaller discharge current is required to obtain maximum gain with increasing pressure. It is worth noting that, with a Philips-type (PIG) discharge, sufficiently high plasma densities

were obtained for amplification of 8-mm waves with a gain of 10 db/cm [125].

Some attempts were made by Tchernov and Bernaskevski [125] to determine the noise levels in operation. It was found that noise figures as low as 40 db were obtained at pressures of a few microns. However, it appears that in the noise measurements no account was taken of any narrow-band low-frequency modulation present on the output signal, such as might be caused by low-frequency plasma oscillations. They also tested between 2 and 28 kMc a similarity law showing that the gain was fixed, at 10 db/cm in their case, if the beam diameter, measured in wavelengths of the slow wave propagating along it, was kept constant.

Although these experiments showed gain on a modulated beam, we would expect that noise modulation on an otherwise unmodulated beam could also grow, perhaps even to the extent of ultimately breaking up the beam itself. An explanation along these lines was proposed by Haeff [138] for the generation mechanism of solar radio noise, and showed good agreement with observed noise spectra. After unsuccessful attempts by Looney and Brown [139], Kojima, *et al.* [140], and Gordon [141], the first successful laboratory experiments of this nature were performed by Demirkhanov, Gevorkov, and Popov [137], and Kharchenko, *et al.* [142]. Demirkhanov, *et al.*, used an unmodulated beam passing along the axis of a discharge tube. With one tube, oscillations were picked up on a probe within the discharge; with another, on a probe outside. The amplitude of the oscillations was always strongest in the beam region. A cavity perturbation technique was used to measure the electron density in the discharge, and the comparison of the frequency of the highest output amplitude and calculated plasma frequency was always very close. Moving the probe along the direction of motion of the beam electrons showed increasing signal amplitude at first, then a slow decrease. This was probably a result of slowing and scattering of the beam by collisions or by the RF signal itself. Similar results were obtained over a pressure range 1–10 μ in argon, nitrogen, and hydrogen.

Kharchenko and his co-workers [142] investigated this phenomenon at higher pressures (30–100 μ) with an 80-kv electron beam. They observed strong high-frequency signals with a maximum amplitude at the plasma frequency, provided a long enough interaction distance was allowed (10–20 cm).

3) *Natural Oscillations*

We may now speculate as to whether interaction of the type established above can occur naturally in a discharge. The necessary ingredients are there since we have a homogeneous stream of primaries leaving the cathode sheath and entering the plasma. It is, therefore, worth examining some of the experiments in which high-frequency oscillations were investigated spatially in the plasma. The first of these was the scattering experiment of Merrill and Webb [33] mentioned in Section II. They found a remarkable correlation between the scattering regions and the points of maximum oscillation amplitude. There was in each case an equal number of these (usually 2 or 3) with the high-frequency amplitude reaching its maximum approximately midway between the scattering regions (see Fig. 4). The oscillation frequency was close to the




Fig. 4—Typical results of scattering experiments of the type performed by Merrill and Webb. (a) Regions of scattering and positions of RF maxima. (b) Velocity distributions at points 1–5 in (a). (c) The frequency-pulling effect of a probe.

plasma frequency as calculated from probe measurements. Increases in pressure or current moved the scattering regions towards the cathode. The authors explained their results in terms of the phenomenon of velocity modulation, a process novel then, but familiar today in tubes such as the klystron. Assuming that plasma oscillations occurred strongly in the scattering regions, bunching of the primary beam would occur somewhat further towards the anode, impressing an RF current on the probe. Very little variation in maximum RF amplitude could be observed as the probe potential was varied. Twiss [131] analyzed this experiment in terms of growth of noise from the cathode caused by the interaction of primary electrons with the plasma ultimate electrons. He showed that gains as high as 170 db/cm could be expected at the plasma frequency. This gain would yield perturbations in elec-

tron velocity of sufficient amplitude to explain the results observed.

Neill and Emeleus [143], using a filamentary cathode, observed a variation in oscillation amplitude increasing slowly with distance from the cathode to a maximum, then falling away, both increase and fall being complicated by a number of minor peaks. This experiment and that of Merrill and Webb were repeated and extended by Bailey and Emeleus [42], [144]. By ascertaining that similar results were obtained with a back-bombarded flat tantalum cathode, they showed that the more sudden build-up of oscillation amplitude in the case of flat cathodes was associated with geometry rather than cathode material. They also noted the powerful disturbing influence of a probe, which could produce frequency pulling. This, they attributed to reflection of primaries providing a feedback action analogous to that in a reflex klystron. Evidence for this was supplied by the fact that the minor peaks corresponded to the center frequencies of the modes (see Fig. 4). The effect was similar if the wire probe was replaced by a quartz fiber of the same size and was most pronounced when a small flat probe at right angles to the cathode was used.

It is clear that the results obtained for scattering and oscillation amplitude profiles must be considered with caution, particularly in view of the pronounced instability of the meniscus as it is approached by a probe. Bailey and Emeleus [42] found that a magnetic field of the order of 100 gauss exerted a stabilizing influence on the discharge; it yielded purer RF oscillations, and tended to eliminate the pulling effect of the probe. At the same time the magnetic field tended to eliminate the low-frequency oscillations present, a phenomenon discussed in Section VI below. We might associate this result with the elimination of the modulation of the HF signals by LF oscillations. Mahaffey [37] continued the work, using plane oxide-coated cathodes, and made simultaneous measurements of charge density, electron temperature, oscillation intensity, and frequency. A strong tendency was found for oscillations to grow in intensity in the direction of decreasing charge density, and to die out when the beam moved up a density gradient. This result is in agreement with the suggestions of Allis [145], who pointed out that as the primary beam became lost by scattering, an oscillation at the plasma frequency would be cut off as it traveled into a region of higher plasma density, but would be enhanced as it traveled into a region of lower plasma density. In Mahaffey's work, close correlation between the frequency of oscillation and the measured plasma frequency was always observed.

As would be expected from the theoretical work of Sturrock [119]–[120], and Bunemann [121] discussed earlier, there is no clear experimental evidence that natural oscillations can occur without some feedback mechanism present. Either there seems to be growth from noise, or in the experiments in which standing waves along a beam passing through a plasma have been observed, feedback mechanisms have been present which could cause the standing waves. For example, an experiment by Kofoid [146], carried out in argon at 11-μ pressure, involved identical oppositely-directed beams entering through parallel plane electrodes held at space potential. Strong standing waves near the plasma frequency were indicated only when both beams were present. If, however, the electrode potentials were changed to provide sheaths, thereby introducing a feedback mechanism, standing waves were observed with a single beam. This type of oscillation is discussed more fully below.

C. Beam-Plasma Interactions Dependent on Sheaths

The deliberately excited oscillations discussed so far could occur independently of the presence of sheaths. In the case of spontaneous oscillations, the cathode sheath is necessary to form the beam of primaries, but the growth mechanism is, of course, independent of the origin of the beam. In a bounded plasma of dimensions sufficiently small for a primary beam not to break up completely in transit, it is possible that sheaths can provide a feedback mechanism analogous to that in a reflex klystron, the plasma representing a drift space between the sheaths. Standing waves can be set up with wavelengths dependent on factors such as beam velocity and tube geometry.

An observation of standing waves was made by Looney and Brown [139] in an unsuccessful experiment to observe spatially-growing waves on a high-density beam. The reason for their lack of success has been dealt with by Sturrock [123], who develops the appropriate dispersion relation for a thin beam and shows that the interaction distance was too small for a noise signal to grow to a measurable amplitude, the maximum gain being only about 20 db. A schematic of their experiment is shown in Fig. 5. By varying the potentials




Fig. 5—Experimental arrangement used by Looney and Brown.

of the gun and its anode relative to the plasma, ion sheaths could be produced on these electrodes. A movable probe coupled to a receiver could be moved axially along the beam to measure oscillation intensity and frequency. It was found by varying gun current and sheath thickness that standing wave patterns were set up with nodes at the two sheath edges. The number of loops adjusted itself to keep the frequency as close as possible to the beam plasma frequency.

Although Looney and Brown showed that a transit

time mechanism fitted their experimental results, a clearer picture of the mechanism was offered by Demirkhanov, Gevorkov, and Popov [137], who repeated the experiment and showed that the feedback mechanism required to maintain the oscillations is provided by secondary electrons ejected from the anode by the impinging beam. These are trapped in the interelectrode space, where they oscillate. Several frequencies are possible, but we might expect the maximum oscillation amplitude near the plasma frequency.

A similar explanation of these experiments has been given in the unpublished work of Gordon [141]. Using an improved version of the Looney-Brown experimental tube, he was able to show that oscillations only occurred when there was a returning beam of secondary electron. Gordon suggested a theory for the oscillation modes based on a klystron-type mechanism in which the primary beam took no part. It assumed that secondaries were emitted from the reflector, traveled to the gun end of the tube, and were reflected at the sheath there. In his experiment, the oscillation frequency f and transit time τ of the secondaries were related to within a few per cent by the usual expression for reflex klystrons $f\tau = n + \frac{3}{4}$. Gordon also obtained oscillations in another tube when the primary beam was itself reflected by the sheath at the reflector. However, these oscillations were weak. Gordon added further evidence of the disturbing influence of probes in experiments of this nature. He found that the oscillations, and the standing wave pattern associated with them, became erratic when the probe was in the beam. They could be detected from outside, though the field strength decreased rapidly with distance of the probe from the beam edge. Detection became difficult more than a centimeter from the beam.

An even clearer illustration of the klystron-type mechanism had been given earlier by Wehner [147], [148], using a discharge tube of the type shown in Fig. 6 and described by Fetz [149], [150], Schumann [151], and Wehner [152]. This material is reviewed by Gabor [153]. The Wehner oscillator is worthy of interest as one of the few practical devices to emerge as a result of plasma research. It is capable of producing several watts of microwave power up to a few kMc. The primary electron beam emerges from the low-temperature, nonluminous plasma in the gridded cathode container and is reflected by the repeller electrode. Sheaths with potentials up to 1 kv across them can easily be formed on the grid and the repeller. Wehner detected oscillations using a Lecher wire system connected between the repeller and the anode of the device. He was able to observe meniscus-shaped oscillation layers close to the sheaths, and the existence of 5 separate modes over a range of beam voltage and frequency. Good agreement was obtained between these experimental results and a theoretical analysis based on a klystron-type transit-time mechanism.




Fig. 6—The Wehner oscillator.

Although we have shown that this type of oscillation can be induced deliberately, there seem to be no definitive experiments in which such oscillations have been observed to occur naturally.

D. Beam-Surface Wave Interactions

The observation that propagation with phase velocity very much less than that of light occurs below the plasma frequency in finite plasmas has been put on a firm theoretical basis and checked experimentally by Gould and Trivelpiece [59], [60], [126]. As already discussed, they have shown that two basic modes of propagation can occur: surface waves involving only a perturbation of charge at the surface of the plasma, and body waves involving charge density variation within the plasma, which occur only in the presence of a magnetic field. The former effect is unrelated to sheaths since it can occur in a zero temperature plasma which has no sheath. In his experiments, Boyd [2] was able to observe interaction of an electron beam with the surface wave at frequencies below the plasma frequency, producing growth rates of about 1 db/cm. It is possible that such an interaction may be observed with the beam emerging from the cathode region of a discharge, but so far there has been no definite experimental evidence of this effect occurring.

E. Sheath Oscillations

From vacuum tube theory, we are familiar with the concept of negative beam-loading due to the transit time of electrons passing through a gap. It was pointed out by Emeleus [109], [143] that there is the possibility that, if the sheath is regarded as a gap, nonreturning beams traversing sheaths in plasma may maintain oscillations in these regions through such a mechanism.

It may be shown theoretically [141] that the characteristics of such oscillations are

$$\lambda I^{1/2} = \text{a constant} \tag{27}$$

and

$$\lambda V^{1/2} = \text{a constant} \tag{28}$$

for temperature-limited and space-charge-limited emission conditions, respectively, where λ is the free-space wavelength, V is the cathode sheath voltage, and I is the saturated emission current. Gordon [141] suggests that (27) is a direct result of the assumption that the

width of the oscillating region is very small compared with the mean free path for collisions. The presence of such oscillations in cylindrical plasma diodes has been observed by Armstrong and Emeleus [108], and Sluzkin and Maydanov in the USSR, who are quoted by Gordon as having obtained results in good agreement with the theoretical relations given above.

Allis [145] has shown that, through the mechanism of oscillations, a beam of electrons entering a plasma can deliver energy to a region about ten times the cathode sheath thickness, a result corroborated by the experimental observations of Emeleus [154] and Merrill and Webb [33]. It is possible that the oscillations observed in the cathode sheath do not grow from noise alone, but that nonuniformity, or transit time effects in the sheath, may provide a direct feedback mechanism to produce them.

It was pointed out by Langmuir that there is an apparent contradiction associated with the Maxwellian distribution of electron velocities normally observed in low-pressure discharges at points far from the cathode. High-velocity electrons should escape through the sheath to recombine with ions at the wall of the discharge. As the electron mean free paths for collisions are very large, there is no obvious dc mechanism for Maxwellianization, and there should be a lack of high-velocity electrons near the sheath. Gabor [10] called this phenomenon "Langmuir's paradox." It was suggested by both Langmuir [8] and Gabor [10] that strong collective oscillations must be taking place. Gabor, Ash, and Dracott [13] pointed out in a later paper that this type of collective interaction could occur in the sheath, and proposed a mechanism analogous to that of the reflex klystron in which electrons entered the sheath and returned to the plasma, the sheath behaving as a klystron gap. In an elegant set of experiments using a finely collimated high-energy low-current electron beam traveling parallel to a plane plasma-sheath interface, they determined not only the dc field strength in the sheath, but also that of the superposed ac field which was found to be present. Both fields were found to have an approximately linear increase with distance from the plasma. The frequency of the oscillations was about $\frac{1}{5}$ of the plasma frequency.

It is interesting to note that a linear field distribution is isochronous for incoming electrons, *i.e.*, that the transit time is independent of velocity, and that the reciprocal of the transit time for the field distribution, determined experimentally, corresponded to about half the frequency of the sheath oscillations. Physically this means that, depending on its time of arrival, a slow electron may be able to reach the wall, while a fast one arriving a half-cycle later will not. The authors put this forward as a Maxwellianizing mechanism which would offset the loss of high-velocity electrons to the wall that would have to be assumed on a steady-state theory.

Gordon [141] has shown, using an approximate theory, that the wall sheath can absorb energy from an almost Maxwellian distribution of electrons entering and being reflected from it. He has also obtained reasonable numerical agreement with the frequency of oscillations observed in the sheath by Gabor, Ash, and Dracott [13].

The problem of the Langmuir paradox and the oscillation mechanisms that have been demonstrated experimentally lead to serious doubt as to whether a plasma could exist in a low-pressure gas without the presence of oscillations. Certainly it is difficult to understand how a plasma would maintain its essential nature near the wall of a discharge without oscillations, for these high-velocity electrons provide the necessary ionizing collisions. One alternative to the sheath oscillation hypothesis has been advanced by Martin and Emeleus [14], who suggested that high velocity electrons to maintain the tail of the velocity distribution are also generated in the scattering region near the cathode. It is not certain, however, that this mechanism could supply sufficient high-velocity electrons in a long discharge tube.

IV. Low-Frequency Oscillations

A. Ion Waves

Studies of low-pressure discharges in the late 1920's revealed not only the high-frequency oscillations discussed already, but also low-frequency fluctuations in a frequency band from zero to a few megacycles per second. Among the earliest papers dealing with this topic were two contributions by Pardue and Webb published in 1928 [155], [156]. Using a straight uniform tube with an oxide-coated filament at one end and an anode at the other, they explored a pressure range of 15–90 μ in air. They found that the most prominent frequency peaked at about 20 μ, and that several frequencies related to this component were usually present. By analogy to the electron plasma oscillations, they suggested that these might be ion plasma oscillations. The properties of such oscillations were quoted by Langmuir in 1928 [8], and the derivations were published by Tonks and Langmuir in 1929 [57], [58].

1) Theoretical Approaches

Following Tonks and Langmuir, we assume that the unperturbed ions are at rest, so that we can use (2) to represent the ion motion and write for the one-dimensional case

$$j\omega v_{i1} = j\frac{eB}{m_i}\phi, \tag{29}$$

where the subscript i denotes ion parameters. All quantities are taken to vary as $\exp j(\omega t - \beta z)$, and the electric field has been derived from a potential ϕ by writing

$$E = -\nabla\phi = j\beta\phi. \tag{30}$$

By using the relation between current density and velocity, (3), and the equation of continuity, (5), it is

found that the ac charge density of the ions, $\rho_{i1}(=en_{i1})$, is

$$\rho_{i1} = \frac{\rho_i e\beta^2}{m_i\omega^2}\phi. \tag{31}$$

Tonks and Langmuir assumed that the ion oscillations are so slow that the electrons remain in a Maxwell-Boltzmann distribution. With this assumption, we can write

$$\rho_{e1} = -\rho_e\left[\exp\left(\frac{e\phi}{kT_e}\right) - 1\right]. \tag{32}$$

If we assume that $e\phi/kT_e \ll 1$, it follows that

$$\rho_{e1} = -\frac{e\rho_e\phi}{kT_e}. \tag{33}$$

Finally, the application of Poisson's equation yields the relation

$$\beta^2\phi = \frac{\rho_{e1}+\rho_{i1}}{\epsilon_0} = \phi\left(-\frac{e\rho_e}{kT_e\epsilon_0} + \frac{\beta^2 e\rho_i}{\omega^2 m_i\epsilon_0}\right). \tag{34}$$

Assuming $\rho_e=\rho_i$, the phase velocity $v_p(=\omega/\beta)$ of the wave is given by

$$v_p = \left(\frac{kT_e}{m_i}\right)^{1/2}\left(1-\frac{\omega^2}{\omega_{pi}^2}\right)^{1/2}, \tag{35}$$

where the ion plasma frequency $f_{pi}(=\omega_{pi}/2\pi)$ is defined by

$$\omega_{pi}^2 = \frac{n_i e^2}{\epsilon_0 m_i}. \tag{36}$$

It follows from the dispersion relation of (35) that an electrostatic wave can exist between zero frequency and the ion plasma frequency. For $\omega \ll \omega_{pi}$, $v_p \rightarrow (kT_e/m_i)^{1/2}$. The wave then has the characteristics of a sound wave in which the atoms of the gas have the mass of the ions, but the temperature of the electrons and the velocity is independent of the density. Consequently, this type of wave is called an "electrostatic sound wave" [57].

The Tonks and Langmuir theory assumes, essentially, an isothermal expansion of the plasma. A better description has been used by Spitzer [68], introducing a pressure term into the equation of motion of the average electron, or ion. He assumed that the pressure p is a scalar, defined in terms of the mean square velocity fluctuation $p=\overline{m(v-\bar{v})^2}$. If the plasma expands adiabatically, it may be assumed that $p \propto n^\gamma$. By using these assumptions, the following dispersion equation may be derived [157], [158]:

$$1 = \frac{\omega_{pe}^2}{\omega^2-\beta^2 w_e^2} + \frac{\omega_{pi}^2}{\omega^2-\beta^2 w_i^2}. \tag{37}$$

where $w_e=(\gamma_e kT_e/m_e)^{1/2}$ is the electron acoustic velocity and w_i is defined similarly for the ions. When $T_i=0$, the expression reduces to that of (35), if it is assumed that $m_i \gg m_e$, and if T_e in (35) is replaced by $\gamma_e T_e$.

This theory may be easily generalized to take account of the finite dimensions of a plasma and of collisions between electrons and neutrals, ions and neutrals, and electrons and ions [157]–[160]. As for ordinary sound waves, a low-frequency cutoff for the propagation is predicted, dependent on the dimensions of the plasma column. If it is assumed that the potential is zero at the edge of a uniform cylindrical column of radius a, the low-frequency cutoff ω_c of a wave with components that vary as $\exp j(\omega t-\beta z)\cos n\theta$ will be determined by the relation $J_n(\omega_c a/w_e)=0$, where J_n is the nth-order Bessel function of the first kind, $T_i=0$, and $\omega_c \ll \omega_{pi}$. The collision frequency ν between electrons and ions or neutrals is taken into account by replacing the ω^2 in the denominator of the first term of (37) by $\omega(\omega-j\nu)$. In practice, such collisions exert a negligible effect. For instance, when $T_i=0$ the damping term in the propagation constant is of the order $-(j\nu/2\omega)(m_e/m_i)\beta$.

We might expect, then, to observe ion oscillations in a plasma in the two frequency ranges corresponding to cutoff of the ion modes: (1) at the ion plasma frequency, the high-frequency cutoff, and (2) at the low-frequency resonances of a finite plasma.

The type of theory described so far postulates a high electron-electron collision frequency and zero temperature for the ions. The properties of ion waves have been attacked using the collision-free Boltzmann equation by Newcomb [161], Fried and Gould [157], [158], and Bernstein, *et al.* [162], [163]. They showed that if the ions were at zero temperature, waves very similar to those obtained in the early theories were derived. However, if the ions have a finite temperature, there is strong Landau damping, the damping being strongest in the region $T_e \doteq T_i$. This effect is explained physically by Fried and Gould as being due to the majority of the ions traveling at about the same phase velocity as the wave. On the other hand, if there is a relative drift velocity between the ions and electrons, the authors cited above and Bunemann [136], [164], [165] all show that a two-stream instability develops and the ion waves become unstable: for $T_i=0$, only negligible drift velocity is needed for instability. For $T_e=T_i$, the minimum drift velocity for very long wavelength instabilities is

$$v_D = 0.925\left[1+\left(\frac{m_e}{m_i}\right)^{1/2}\right]\left(\frac{2kT_e}{m_e}\right)^{1/2}. \tag{38}$$

Fried and Gould [157] suggested that this type of instability should take place in a mercury vapor discharge, due to the relative longitudinal drift motion of ions and electrons along the positive column. However, as the radial motion of the ions and electrons, the ionizing collisions, and the rate of collisions of ions with the wall in such a discharge were not taken into account in their theory, it is not clear whether the effects predicted should occur in practice.

Bunemann [165], who had previously obtained some of the same results as Fried and Gould, also carried out

computations of the large amplitude oscillations. On the basis of this work, he suggested that such collective interactions could provide a rapid mechanism for restoring grossly non-Maxwellian distributions to near Maxwellian, and thus give rise to an extremely high effective collision frequency between electrons and ions.

2) Oscillations in Beams

The problem of ion oscillations was approached from a different point of view by Pierce [166], who gave a theoretical treatment of the oscillations which occur when an electron beam passes through the ion cloud formed by its collisions with gas molecules. This theory predicted that wave amplification should occur at frequencies below the ion plasma frequency, with maximum gain at the ion plasma frequency. It has been proposed that the feedback mechanism necessary to cause oscillations is supplied by slow secondaries moving in the backward direction. In this case the oscillations would be expected to occur near the ion plasma frequency. Such oscillations were observed unequivocally by Hernqvist [167], [168].

Low-frequency oscillations of other kinds are also observed in electron beams. Some of these oscillations are due to low-velocity secondaries alone, but most are due to ions. Hernqvist [167], [168], Cutler [169], Moreno [170], and Ettenberg and Targ [171] have described these effects. Relaxation oscillations often occur, usually of a modified sawtooth shape, and are probably connected with the ionization and deionization processes occurring in the beam. There is also a class of oscillations connected with interaction of the electron beam with a backward wave propagating along the ion cloud in the presence of a magnetic field. The theory of this effect has been dealt with by Pierce [166] and by Smullin and Chorney [61], [172]. Another class seems to occur in short beams where, as has been pointed out by Jepsen [173], it is extremely unlikely that the beam length is long enough to allow sufficient phase delay around the oscillation loop to yield the two-stream oscillations described by Pierce [166]. A theory of ion oscillations in a gridded drift tube in which the electric field in the drift tube is postulated to undergo one or more space reversals has been given by Jepsen [173], and Smullin and Chorney [61], [172]. They show that when a beam of fast electrons traverses such a region, the beam loading can be negative, and oscillations can occur.

3) Experimental Observations of Ion Oscillations

Tonks and Langmuir [57] searched for evidence of ionic oscillations in a gas discharge plasma with little success, except for an isolated observation of a naturally-occurring frequency component near to the predicted value of plasma frequency. Later, Revans [174], Druyvesteyn and Warmoltz [30], Funk and Seeliger [175], and others have reported naturally-occurring low-frequency oscillations without establishing their exact origin. Direct attempts to set them up and study their characteristics failed for reasons described by Armstrong, Emeleus, and Neill [159], whose experiments involved pulsing between the anode and an electrode immersed in a plasma, and observing the transient at other points along the tube. In view of the low velocity of propagation of ion waves ($\sim 10^5$ cm), phase shift should have been easily measured. Instead, an apparently instantaneous response was observed at all observation points. This result has been confirmed by Kino and Woods [176] using a wide variety of techniques to attempt ion wave excitation.

The presence of a high level of low-frequency noise would mask low-level ion wave amplitudes, and it should be remembered that the dispersion relation was derived using a small-signal approximation. It is possible, of course, that the noise itself propagates as an ion wave, and experiments have been carried out by Thong Saw Pak [177], and Crawford and Lawson [178] to measure propagation velocities of noise in tubes. The former concluded that propagation velocities must exceed 10^7 cm and that the entire positive column was fluctuating coherently. The latter used hot-cathode discharge tubes of the type illustrated in Fig. 7, having a positive column of smaller diameter than the cathode region. By observing potential and number density fluctuations along the tube, these workers were able to show that the noise was generated close to the cathode and that the propagation velocity was $>10^9$ cm over most of the column. This high-velocity mode of propagation can be regarded as a low-frequency version of the surface wave propagation described by Gould and Trivelpiece [59], [60], [126] or, at even lower frequencies, as due to conduction along the column.

Crawford and Lawson also noted that in the first 20 cm or so of the column, after the constriction, there was a smearing of phase, and that the main component of the noise appeared to have a phase velocity of the order of 10^7 cm. The frequency spectrum of the noise, which was typically as shown in Fig. 7, contained two or three low-frequency peaks which varied little in frequency or amplitude with current. This phenomenon was suggestive of sound wave modes, and the experiments were extended by Crawford [160], [179] using different discharge tubes, with a wide range of column diameters, to see whether the frequency peaks were related to each other, and to the column diameter. It was found that the frequency peaks f_0, f_1, and f_2 in any given tube had approximately the same ratio to each other as the three lowest zeros of $J_n(x)$, *i.e.*, the lowest two roots of $J_0(x) = 0$ and the first root of $J_1(x) = 0$. The measured frequency was also inversely proportional to the column diameter of the tube involved. In accordance with the theory for a finite column already described, there was a strong suggestion of the presence of radial sound wave modes, *i.e.*, oscillations at the low-frequency cutoff for




Fig. 7—Discharge tube used in the experiments of Crawford and Lawson with typical low-frequency noise spectra.

sound wave modes. By carrying out temperature measurements on two of the tubes, Crawford was able to arrive at a value of γ_e of the order of 2. Thus the measured frequencies were also in the correct range for ion sound wave modes. However, an objection to this hypothesis is that one of the strongest modes observed corresponds to an azimuthal variation of field. This seems unlikely, since detection of such modes should be difficult on a symmetrically-placed anode, or pickup ring outside the tube.

Some observations of low-frequency resonances reported by Gabovitch, *et al.* [180], who applied a low-frequency signal to a probe whose dc potential was varied, may also have been associated with ion wave oscillations.

Careful examination of noise frequency spectra under widely varying discharge conditions should give further clues as to whether ion waves constitute the basic components. The first comprehensive measurements of this kind were made by Cobine and Gallagher [15] using argon at pressures from 10 μ to 2 mm Hg. Unfortunately, commercial tubes with relatively complicated noise spectra containing a number of peaks were employed. One feature which emerged was that above a certain critical frequency, varying inversely as the atomic weight of the gas, there was a falling-off in high-frequency noise. This effect does not seem to have been observed in work at lower pressures. Cobine and Gallagher also ascertained that fluctuations in light output corresponded in waveform to the voltage fluctuations observed.

Results obtained by Martin and Woods [181] using a tungsten filament and hemicylindrical anode showed spectra containing many peaks whose frequency increased with current, but which were difficult to analyze. However, using tubes with simpler geometries, Crawford [179], [182] has been able to show that frequency components at both extremes of the ion wave spectrum can exist. With uniform tubes having plane cathodes, a high-frequency oscillation near the ion plasma frequency, varying as the square root of the anode current, is observed. Occasionally, fixed peaks suggestive of the sound wave modes are also present in a broader spectrum of oscillations. Complicating the tube or electrode geometry enhances the fixed-frequency effects, probably by introducing more turbulent conditions in the discharge.

Impedance measurements made by Crawford and Lawson [178], [183] have been interpreted theoretically to derive equivalent circuits for a plasma, the parameters of which can be related to diffusion and collision processes occurring in the positive column [183]. The various time-constants and resonances seem to be associated closely with the frequencies at which strong noise components were observed in their experiments.

4) Oscillations at the Cathode Sheath

It was pointed out by Cobine and Gallagher [15] that a small movement of the ion sheath at the column side of the double sheath in front of the cathode would be sufficient to give rise to the oscillation potentials observed. Such a movement could be excited by a two-stream instability due to the primary electrons passing through this sheath. Another possibility closely connected to this one is negative loading of the primary beam by the ion sheath, in the manner described for electron beams by Jepsen [173] and Smullin and Chorney [61], [172]. Neither type of theory has, however, been fully worked out for this case. We would expect, though, that there would be oscillations near the ion plasma frequency of the plasma in front of the cathode. The current-dependent oscillations measured by Crawford, and described in the last paragraph, are probably evidence of the existence of this effect. As confirmation, it is worth noting that the actual values of frequency obtained from several tubes of different diameters, containing various different cathodes, normalized closely with respect to cathode current density in the case of current-dependent frequency variation. This implies that these oscillations were generated close to the cathode. Using tubes with movable anodes, further support has been added to this view by the fact that the frequencies remain unchanged until the anode is brought to a few millimeters from the cathode and begins to disturb such fundamental features of the discharge as the meniscus.

B. Potential Minimum Oscillations

Under space-charge-limited emission conditions, there will always be a retarding potential at the cathode in either a hard tube or a gas discharge tube. This results in the formation of a potential minimum close to the cathode. It was suggested as long ago as 1929 by Kingdon [184] that positive ions could get trapped in this minimum and oscillate there, and that this could occur even at discharge currents in the Townsend region preceding plasma formation. Such oscillations in the pre-plasma state have been reported by Ballantine [185] and others [15], [181], [186], [187].

A theory of potential minimum oscillations has been given recently by Waymouth [188], who has derived a modified form of the Tonks-Langmuir dispersion relation quoted in (35).

In the experiments of Crawford [179], [182] in which an ion plasma frequency proportional to $I_a^{1/2}$ was observed, there was in some tubes a second peak in the spectrum at a frequency approximately 1/10 of this, which moved with increasing anode current according to a power law between $\frac{1}{3}$ and $\frac{1}{2}$. This has not been explained but may well be a potential minimum occillation. Experiments with several tubes indicated that the frequency depended on cathode current density rather than on column current density, and was unaffected by the movement of the anode, as in the case of the first type of current-varying oscillation.

In experiments with fluorescent tubes van Boort and Klerk [189] and Waymouth [188] also observed oscillations, which they postulated were potential minimum oscillations. It may be seen from Waymouth's data that the frequency of these oscillations was proportional to $I_a^{1/3}$. These workers noted that the oscillations measured at the anode of the discharge or on a probe disappeared when the cathode was temperature-limited. Waymouth suggested that this result was evidence that the oscillations took place in the potential minimum and used the vanishing point as a measure of the saturation current of the cathode. However, Crawford and Lawson [178] showed that, as the impedance of the discharge becomes very large when it is temperature limited, any oscillations generated internally would not be observed easily outside the discharge. In one experiment, using a microwave resonant cavity perturbation technique, they were able to show that there were still substantially unchanged fluctuations of charge density in the plasma column, even when the cathode was temperature limited, and no oscillations could be measured on the anode of the discharge.

C. Striations

It has been mentioned earlier that the study of oscillations by use of probes within the discharge is complicated by the disturbing effects of the probe itself, particularly in the vicinity of sheaths. These matters and the feasibility of using external probes are discussed by Emeleus [190], [191], who points out that much valuable information can be obtained by observing the light output from the discharge. The results of such studies by Cobine and Gallagher [15] and Landecker and Robinson [192] indicate close correlation between the frequency spectra of anode voltage and light output fluctuations.

A familiar feature of discharges at pressures of the order of 1 mm is the presence of either fixed or moving striations. Their mechanisms and theory are still not fully understood, but it is indicated by Pupp [193] that they are associated with potential fluctuations of several volts and large changes in electron temperature and concentration. The early experiments of Appleton and West [194] suggest that the striations are accompanied by a high level of low-frequency noise. Druyvesteyn and Penning [29] summarized much of the early work, but did not indicate the existence of striations at pressures below 100 μ. Loeb [195] suggests they may exist down to pressures of about 10 μ, and that they are more likely to occur in impure gases or gas mixtures. Much of the more recent experimental work has been carried out by Dieke and his co-workers [196], [197], and Pekarek [198], [199], and a theoretical discussion has been given by Robertson [200].

There seem to have been no published observations of striations occurring in mercury vapor discharges at a few microns until a paper by Foulds [201] in 1956. In a cold cathode tube, using photocell techniques and a rotating mirror camera, Foulds was able to observe almost regular striations moving toward the cathode and some evidence for irregular striations moving toward the anode. Frequencies and velocities of the order of 10 kc and 2.10^6 cm were involved. This conflicts with some earlier results of McCurdy, *et al.* [202]–[204], who found that pure mercury vapor gave no standing striations. There could possibly have been unobserved moving striations in their experiments, however. The present state of the theory does not allow us to predict the occurrence and characteristics of striations, but the velocities involved agree reasonably well with the results of an experiment of Armstrong, Emeleus, and Neill [159], in which a region of heavy ionization was forced to pulsate under the influence of abrupt changes in electrode potentials.

D. Anode Spots

Armstrong, Emeleus, and Neill [159] have pointed out that instabilities can occur near to the anode of a low-pressure discharge in certain regions of the voltage/current characteristic. Small spots may form, generating low-frequency oscillations which have considerable energy associated with them [205]. The authors describe experiments in which the tube became a source of audible noise.

The exact mechanism of this anode glow instability is still obscure, but it seems to be more pronounced when the anode fall is positive than when it is negative. It is further intensified when there is large curvature of the

glow (for example, when the discharge anode is small or when impurities are present). Pupp's experiments suggest a connection with the existence of striations [206].

Armstrong, *et al.* [159], suggest that pressure instabilities may be responsible. Langmuir [207] showed as long ago as 1923 that steady currents produce differences of gas pressure in a tube, but the subject of instability under these conditions does not seem to have received attention. It may have relevance to the production mechanism of striations.

E. Miscellaneous

Several other mechanisms not included in the foregoing sections have been suggested as being important in noise generation [154]. The majority of these effects are associated with the cathode. It is felt that, although they might occur under special conditions, they are not the major sources of noise in most tubes; neither are they inherent in the maintaining mechanism of the discharge. When the gross components described above have been eliminated, these mechanisms may become important.

Emeleus [154] has suggested that noise could be caused by irregular movements of the boundary between parts of the cathode emitting space-charge-limited and temperature-limited current. Clarke [208] has advanced the hypothesis that a type of flicker effect may occur, enhanced by the presence of positive ions and possibly associated with mode-jumping of standing space-charge waves in the gas very close to the cathode.

Many observations on noise frequency components have shown the presence of harmonics [155], [182]. These might be generated from sinusoidal oscillations by nonlinearities in the plasma or may be evidence of the existence of relaxation oscillations with more complicated waveforms. For example, the discharge might have two stable modes and jump from one to the other [57]. Few details of such mechanisms are available but a possible means by which they might be excited is discussed in Section V.

Two further mechanisms, the levels of which are extremely low relative to the noise actually observed, are shot and thermal effects analogous to the phenomena observed in hard tubes.

V. Interdependence of Low- and High-Frequency Oscillations

Since low- and high-frequency fluctuations have often been observed in the same tubes, we may question whether there is a causal relation between oscillations in these two ranges. Mahaffey [37] has suggested, as a result of experiments in which anode-cathode spacing could be varied, that there may be an association between the occurrence of strong positive ion oscillations and the appearance of a fully-formed meniscus. Allen, Bailey, and Emeleus [35] have also found close association of high- and low-frequency oscillations using a modified form of beam discharge similar to that of Looney and Brown [139], but relying on the cathode for formation of the beam. A flat probe which was placed perpendicular to the beam caused a diffuse glow to appear midway between probe and cathode. High- and low-frequency oscillations were observed to occur together. The glow was unstable and disappeared together with the oscillations, when a fine wire probe was used in an attempt to explore it. This last effect was observed by Bailey and Emeleus [42] who also noted that as current increased and the meniscus became blurred, there was an increase in amplitude of the low-frequency oscillations.

A suggestion advanced by Allen, Bailey, and Emeleus [35] is that the high-frequency interaction between the beam and the plasma electrons builds up so rapidly near the meniscus that the resulting violent disturbance of the discharge might lead to low-frequency ionic or relaxation oscillations. It is further suggested by Emeleus and Mahaffey [209] that transverse ion oscillations might be responsible for the transverse scattering of the cathodic beam described in Section II.

VI. Reduction of Noise in Discharges

The feasibility of reducing noise depends on whether or not the generation mechanism is an inherent process in maintenance of the plasma. Those fluctuations that are caused by the presence of the cathodic electron beam might well be eliminated if the beam could be spread or broken up without loss of energy, and it is possible that if the charge concentration could be made to increase from the cathode outwards, there would be no forward propagation of disturbances. The low-frequency noise involving cathode sheath oscillations might be reduced if the potential of the column edge were clamped firmly, while those disturbances which are of geometrical origin (for example, the effects of a constriction in the discharge) might be reduced by some sort of focusing of the streams passing through.

Some experiments along these lines have already been carried out. Cobine and his associates [15], [210], [211] investigated the effects of a magnetic field transverse to current flow on oscillations in discharges at pressures around 100 μ, and established that the low-frequency effects observed at the anode were reduced when the primaries were deflected to miss the anode. They also discovered that as the magnetic field strength was increased, the over-all noise passed through a minimum and increased again. Similar effects to those in hot cathode tubes were also observed by Ruthberg [212], using cold cathodes. Cobine and Gallagher's results for a transverse field were confirmed by Armstrong, Emeleus, and Neill [159], while the case of an axial magnetic field was examined by Bailey and Emeleus [42]. They found that field strengths of the order of tens of gauss would reduce the low-frequency noise and stabilize the meniscus. They made no comment about the effect of the high-frequency noise component on the amplitude.

These results have been extended by Crawford [179],

who has shown that axial magnetic fields less than 50 gauss can reduce the level of the relatively fixed frequency noise components occurring in long discharge tubes by as much as 20–30 db. Beyond the minimum the noise increases again. This effect may be related to the well-known anomalous diffusion mechanism [52], [213]. The strongly current-dependent mechanisms located in or near the cathode sheath are not affected materially by an axial magnetic field.

The use of an auxiliary electrode to reduce low-frequency fluctuations was investigated by Thong Saw Pak [214]. He describes a tube in which a wire filament was placed at the focus of a parabolic wire gauze electrode, the open side of which faced the anode. Noise figures of the order of 50 db lower than those usually obtained without such an electrode were observed for currents up to about 80 ma, when noise again appeared. Even then, a positive bias on the auxiliary electrode could reduce the noise somewhat.

Further experiments involving fine-mesh grids between cathode and anode of a plasma have confirmed these results, and Johnson, Olmstead, and Webster [215] have coined the apt (but etymologically questionable!) term "Tacitron" for a low-noise device of this type operating in the anode glow mode, and have described its characteristics.

Crawford [179] has carried out experiments with a gridded tube in which the grid-cathode spacing was of the order of a Debye length. The grid potential assumed a value approximately equal to the ionization potential of mercury ($\sim$10 volts) and variation of grid and anode current divided the noise characteristics into two regions: for $I_a/I_g > K$ there was a very low noise level, and for $I_a/I_g < K$ the noise increased sharply. For the tube tested K was approximately constant, and was about 3.

VII. Discussion

Recent years have seen the growth of a complex structure of plasma theory on the foundations laid by Langmuir and his co-workers 30 years ago. The study of wave propagation at microwave frequencies has been carried to a highly sophisticated level, though the models with which this study have been conducted have not always represented accurately the behavior of actual experimental plasmas. Certain of the oscillations which occur naturally in most dc discharges may provide a check on the theories. If these oscillation mechanisms can be elucidated and effectively suppressed, it should be possible to carry out more detailed quantitative experiments to check the theoretical studies of propagation. Such work would be useful not only to the fusion field and to the general study of instabilities, but should also suggest new possibilities in the field of microwave generation [216] and amplification: already, Wehner [147], [148] has demonstrated that reflex klystron-type oscillations involving sheaths can be utilized in wide-band electronically tunable oscillators of reasonable efficiency, while electron beam-plasma interactions offer the intriguing prospect of high-gain microwave amplification. The permeable, structureless nature of this type of amplifier is an attractive possibility for millimeter wave amplification. In addition, there may be entirely new methods for coupling in and out of the system, based on the unusual radial propagation effects in the presence of a magnetic field, on the high rate of amplification, as discussed by Feinstein [217], or on the nonlinear interaction with an electromagnetic wave of the type described by Sturrock [45]–[48]. These coupling mechanisms, which are not necessarily subject to the usual limitations of slow-wave devices, have been discussed by Kino [218]. A major drawback to such devices at the present time is the presence of high- and low-frequency oscillations in the discharge. Broad-banding the device, for example, by using a nonuniform plasma may help to discriminate against low-frequency fluctuations in charge density, but effort is required to reduce spontaneous oscillations which may be generated in the working range.

It is still not clear whether a plasma can exist without self-generated oscillations, but it seems reasonable to assume that all but those required for Maxwellianization of the electron velocity distribution might be eliminated if sufficient care were taken. The presence of the sheath oscillations detected by Gabor, Ash, and Dracott [13] would seem to be necessary for this process. However, because they are at a relatively low frequency compared to the plasma frequency and because their fields are normal to the plasma edge, they may well have only weak fields within the plasma itself. By deliberately increasing the charge density in the direction of the cathodic electron beam, we might cause the effect of the RF oscillations generated in the vicinity of the meniscus to be very weak in the amplifying region also.

Two alternatives would be: 1) to use other types of discharges such as the highly ionized, synthetic cesium plasmas based on the resonance ionization phenomenon first investigated by Langmuir and Kingdon [219] and studied in more detail recently by Allen and Kino [128], D'Angelo and Rynn [220], and Knetchtli and Wada [221], or 2) to use the negative-glow mode which occurs at rather higher pressures and has electron temperatures which can be only a few hundred degrees. These properties and possible applications have been described by Anderson [222], [224] and Harris [223].

Although there is now fairly good qualitative understanding of the mechanisms giving rise to spontaneous RF oscillations, considerably more work is required for a detailed understanding of scattering and Maxwellianization through sheath oscillations. Although Landau damping is now well established theoretically, there does not appear to be any direct experimental confirmation of the phenomenon available. It is understood, however, that several projects are currently in progress to study this effect in electron beams.

Although a wide variety of mechanisms has been suggested for the generation of low-frequency oscillations and noise, there are few convincing demonstrations of the existence of such fundamental phenomena as ion waves and potential minimum oscillations. On the other hand, theoretical explanations of many effects that have

been observed (for example, striations) still have no firm basis. Ion wave phenomena deserve attention because of the part they may play in causing instability and enhanced diffusion across magnetic fields, an effect particularly important in work on thermonuclear fusion. Longitudinal ion waves in the presence of a magnetic field have been reported by Alexeff and Neidigh [225], [226]. There are also possible applications of such longitudinal waves to generation and amplification in the millimeter range [227].

Work on the suppression of low-frequency fluctuations looks promising, and as there seems to be no reason why their existence should be essential to maintenance of a steady-state discharge, it may well be possible to eliminate them by careful design of the apparatus.

List of Symbols

B	magnetic field strength
E	electric field strength
H	magnetizing intensity
J	current density
N	neutral density
T	temperature
a	positive column radius
$-e$	electronic charge
f_p	plasma frequency
k	Boltzmann's constant
m	particle mass
n	number density
p	pressure
t	time
v	velocity
w	acoustic velocity
β	propagation constant
ϵ	permittivity
θ	azimuthal angle
λ	wavelength
ν	collision frequency
ρ	charge density
τ	transit time
ϕ	potential
ω	radian frequency

Subscripts:

e	quantity associated with electrons
i	quantity associated with ions
N	quantity associated with neutrals
1	ac component

References

[1] G. S. Kino and M. A. Allen, "The Effects of Fluctuations on Propagation through a Plasma Medium," Stanford University, Stanford, Calif., Microwave Lab. Rept. No. 802, April, 1961; *Proc. 5th Internatl. Conf. on Ionization Phenomena in Gases*, Munich, Germany, August, 1961.

[2] G. D. Boyd, "Experiments on the Interaction of a Modulated Electron Beam with a Plasma," Electron Tube and Microwave Lab., Calif. Inst. Tech., Pasadena, Calif., Tech. Rept. No. 11; May, 1959.

[3] G. D. Boyd, L. M. Field, and R. W. Gould, "Excitation of plasma oscillations and growing plasma waves," *Phys. Rev.*, vol. 109, pp. 1393–1394; February, 1958.

[4] ——, "Interaction between an electron stream and an arc discharge plasma," *Proc. Symp. on Electronic Waveguides*, Brooklyn Polytechnic Inst., Brooklyn, N. Y., April 8–10, 1958, Interscience Publishers, Inc., New York, N. Y., pp. 367–375; 1958.

[5] F. H. Clauser, "The dynamics of electron beams," *Symp. of Plasma Dynamics*, Woods Hole, Mass., June 9–13, 1958, R. W. Gould, Ed., Addison-Wesley Publishing Co., Reading, Mass., pp. 78–118; 1960.

[6] I. Langmuir, "Scattering of electrons in ionized gases," *Phys. Rev.*, pp. 585–613; November, 1925.

[7] —— Über elektrische Entladungen in Gasen bei niedrigen Drüken," *Z. Phys.*, vol. 46, pp. 271–299; November, 1927.

[8] ——, "Oscillations in ionized gases," *Proc. Natl. Acad. Sci. U. S.*, vol. 14, pp. 627–637; August, 1928.

[9] J. H. Cahn, "Elektronic interaction in electrical discharges in gases," *Phys. Rev.*, vol. 75, pp. 293–300; January, 1949.

[10] D. Gabor, "Wave theory of plasmas," *Proc. Roy. Soc. (London)*, vol. A 213, pp. 73–86; June, 1952.

[11] E. A. Ash and D. Gabor, "Experimental investigations on electron interaction," *Proc. Roy. Soc. (London)*, vol. A 228, pp. 477–490; March, 1955.

[12] A. F. Dittmer, "Experiments on the scattering of electrons by ionized mercury vapor," *Phys. Rev.*, vol. 28, pp. 507–520; September, 1926.

[13] D. Gabor, E. A. Ash and D. Dracott, "Langmuir's paradox," *Nature*, vol. 176, pp. 916–919; November, 1955.

[14] H. Martin and K. G. Emeleus, "The Langmuir paradox in discharge plasma," *Nature*, vol. 177, pp. 943–944; May, 1956.

[15] J. D. Cobine and C. J. Gallagher, "Noise and oscillations in hot cathode arcs," *J. Franklin Inst.*, vol. 243, pp. 41–54; January, 1947.

[16] W. L. Fite, "Final Report on Contract AF 18(600)-487," University of Pennsylvania, Philadelphia, Pa.; August, 1954.

[17] R. D. Sears, "Investigation of Plasma Noise," Armour Research Found., Illinois Inst. Tech., Chicago, Rept. 1982-12; 1960.

[18] A. van der Ziel, "A Study of Noise in Gas Discharge Lamps," ASTIA Document No. AD 204803; November, 1958.

[19] S. Glasstone and R. H. Lovberg, "Controlled Thermonuclear Reactions," D. Van Nostrand Co., Inc., New York, N. Y.; 1960.

[20] T. J. Killian, "The uniform positive column of an electric discharge in mercury vapor," *Phys. Rev.*, vol. 35, pp. 1238–1252; May, 1930.

[21] B. Klarfeld, "The positive column of a gaseous discharge," *J. Phys. Acad. Sci. (U.S.S.R.)*, vol. 5, pp. 913–929; 1941.

[22] R. L. F. Boyd, "The collection of positive ions by a probe in an electrical discharge," *Proc. Roy. Soc. (London)*, vol. A 201, pp. 329–347; April, 1959.

[23] I. Langmuir and H. Mott-Smith, "Studies of electric discharges in gases at low pressure, part I," *Gen. Elec. Rev.*, vol. 27, pp. 449–455; July, 1924.

[24] ——, "Studies of electric discharges in gases at low pressure, part II—typical experimental data illustrating the use of plane collectors," *Gen. Elec. Rev.*, vol. 27, pp. 538–548; August, 1924.

[25] ——, "Studies of electric discharges in gases at low pressure, part III—typical experimental data illustrating the use of cylindrical collectors," *Gen. Elec. Rev.*, vol. 27, pp. 616–624; September, 1924.

[26] ——, "Studies of electric discharges in gases at low pressure, part IV—data on discharges in mercury vapor obtained with cylindrical electrodes," *Gen. Elec. Rev.*, vol. 27, pp. 762–771; November, 1924.

[27] ——, "Studies of electric discharges in gases at low pressure, part V—the use of spherical collectors and the effects of magnetic fields," *Gen. Elec. Rev.*, vol. 27, pp. 810–820; December, 1924.

[28] I. Langmuir, "The interaction of electron and positive ion space charges in cathode sheaths," *Phys. Rev.*, vol. 33, pp. 954–990; July, 1929.

[29] M. J. Druyvesteyn and F. M. Penning, "The mechanism of electrical discharges in gases of low pressure," *Rev. Mod. Phys.*, vol. 12, pp. 87–174; April, 1940.

[30] M. J. Druyvesteyn and N. Warmoltz, "Ein neuer Dunkelraum in der Nähe einer Glühkathode in einer Bogenentladung," *Physica*, vol. 4, pp. 51–68; January, 1937.

[31] ——, "Electron emission of an oxide cathode in an arc discharge," *Physica*, vol. 4, pp. 41–50; January, 1937.

[32] N. Warmoltz, "A second sheath near the cathode of an arc discharge," *Nature*, vol. 138, p. 36; July, 1936.

[33] H. J. Merrill and H. W. Webb, "Electron scattering and plasma oscillations," *Phys. Rev.*, vol. 55, pp. 1191–1198; June, 1939.

[34] T. K. Allen, "A spectroscopic study of plasma-electron oscillations," *Proc. Phys. Soc. (London)*, vol. A 68, pp. 696–700; July, 1955.

[35] T. K. Allen, R. A. Bailey and K. G. Emeleus, "The appearance of some oscillating discharges," *Brit. J. Appl. Phys.*, vol. 6, pp. 320–322; September, 1955.

[36] D. W. Mahaffey and K. G. Emeleus, "Suppression of plasma oscillations," *J. Electronics and Control*, vol. 4, pp. 301–304; April, 1958.
[37] D. W. Mahaffey, "New experimental results for plasma electron oscillations," *J. Electronics and Control*, vol. 6, pp. 193–203; March, 1959.
[38] D. W. Mahaffey, G. C. McCullagh and K. G. Emeleus, "Beam-plasma interaction," *Phys. Rev.*, vol. 112, p. 1052; November, 1958.
[39] E. B. Armstrong, "Plasma-electron oscillations," *Nature*, vol. 160, p. 713; November, 1947.
[40] T. R. Neill, "Plasma electron oscillations," *Nature*, vol. 163, pp. 59–60; January, 1949.
[41] A. Garscadden and K. G. Emeleus, "Exploration of oscillating beam-plasma fields with a transverse electron beam," *J. Electronics and Control*, vol. 9, pp. 473–476; December, 1960.
[42] R. A. Bailey and K. G. Emeleus, "Plasma-electron oscillations," *Proc. Roy. Irish Acad.*, vol. 57A, pp. 53–62; May, 1955.
[43] M. Rosenbluth, "Plasma physics 'quantum' and 'classical,'" *Phys. Today*, vol. 13, pp. 27–30; August, 1960.
[44] K. G. Emeleus, "Turbulence in gaseous conductors," *Proc. Phys. Soc. (London)*, vol. B 64, pp. 166–169; February, 1951.
[45] P. A. Sturrock, "Nonlinear effects in electron plasmas," *Proc. Roy. Soc. (London)*, vol. A 242, pp. 277–299; November, 1957.
[46] ——, "A variation principle on an energy theorem for small-amplitude disturbances of electron beams and electron-ion plasmas," *Ann. Phys.*, vol. 4, pp. 306–324; March, 1958.
[47] ——, "Action-transfer and frequency-shift relations in the nonlinear theory of waves and oscillations," *Ann. Phys.*, vol. 9, pp. 422–434; October, 1960.
[48] ——, "Nonlinear effects in electron plasmas," *J. Nuclear Energy*, pt. C, vol. 2, pp. 158–163; January, 1961.
[49] Thong Saw Pak and H. Martin, "Electron temperature and noise in hot cathode discharges," *J. Electronics and Control*, vol. 2, pp. 128–130; September, 1956.
[50] L. Tonks and I. Langmuir, "A general theory of the plasma of an arc," *Phys. Rev.*, vol. 34, pp. 876–922; September, 1929.
[51] M. Hoyaux and P. Gans, "Some properties of the mercury vapor arc at low pressures," *Proc. 4th Internatl. Conf. on Ionization Phenomena in Gases*, Uppsala, Sweden; August 17–21, 1959, North Holland Publishing Co., Amsterdam, Neth., pp. 364–368; 1960.
[52] A. Guthrie and R. K. Wakerling, "Characteristics of Electrical Discharges in Magnetic Fields," McGraw-Hill Book Co., Inc., New York, N. Y.; 1949.
[53] F. M. Penning, "Scattering of electrons in ionized gases," *Nature*, vol. 118, p. 301; August, 1926.
[54] ——, "Abnormale electronensnelheden en Trilligen van Zeer Hooge Frequentie in Ontladingsbuizen," *Physica*, vol. 6, pp. 241–248; 1926. (In Dutch, with English summary.)
[55] Lord Rayleigh, "On electrical vibrations and the constitution of the atom," *Phil. Mag.*, vol. 11, pp. 117–123; January, 1906.
[56] J. J. Thomson, "The electrodeless discharge through gases," *Proc. Phys. Soc. (London)*, vol. 40, pp. 79–89; March, 1928.
[57] L. Tonks and I. Langmuir, "Oscillations in ionized gases," *Phys. Rev.*, vol. 33, pp. 195–210; February, 1929.
[58] ——, "Note on 'oscillations in ionized gases,'" *Phys. Rev.*, vol. 33, p. 990; June, 1929.
[59] R. W. Gould and A. W. Trivelpiece, "Electro-mechanical modes in plasma waveguides," *Proc. IEE*, vol. 105 B, Suppl. 10, pp. 516–519; May, 1958.
[60] R. W. Gould and A. W. Trivelpiece, "Space charge waves in cylindrical plasma columns," *J. Appl. Phys.*, vol. 30, pp. 1784–1792; November, 1959.
[61] L. I. Smullin and P. Chorney, "Wave propagation in ion-plasma loaded waveguides," *Symp. on Electronic Waveguides*, Brooklyn Polytechnic Inst., Brooklyn, N. Y., Interscience Publishers, Inc., New York, N. Y., pp. 229–247; September, 1958.
[62] Y. B. Fainberg and M. F. Gorbatenko, "Electromagnetic waves in a plasma situated in a magnetic field," *J. Tech. Phys. U.S.S.R.*, vol. 29, pp. 487–500; May, 1959. (Translation in: *Soviet Phys.—Tech. Phys.*, vol. 4, pp. 487–500; May, 1959.)
[63] W. O. Schumann, "On the propagation of electric waves along a dielectrically confined plasma layer," *Z. angew. Phys.*, vol. 10, pp. 26–31; 1958.
[64] ——, "On wave propagation in a plasma between two perfectly conducting planes in an externally impressed magnetic field," *Z. angew. Phys.*, vol. 8, pp. 482–485; 1956.
[65] J. J. Thomson and G. P. Thomson, "Conduction of Electricity through Gases," Cambridge University Press, England, vol. 2, pp. 353–358; 1933.
[66] J. J. Thomson, "Oscillations in discharge tubes and allied phenomena," *Phil. Mag.*, vol. 2, pp. 697–735; March, 1931.
[67] ——, "Electronic waves and the electron," *Phil. Mag.*, vol. 6, pp. 1254–1281; December, 1928.
[68] L. Spitzer, "Physics of Fully Ionized Gases," Interscience Publishers, Inc., New York, N. Y.; 1956.
[69] J. R. Pierce and J. A. Morrison, "Disturbances in a multi-velocity plasma," IRE Trans. on Electron Devices, vol. ED-6, pp. 231–236; April, 1959.
[70] L. R. Walker, "The dispersion formula for plasma waves," *J. Appl. Phys.*, vol. 25, pp. 131–132; January, 1954.
[71] A. A. Vlasov, M.S. thesis, *J. Exp. Theoret. Phys. (U.S.S.R.)*, vol. 8, p. 291; 1938.
[72] ——, "On the kinetic theory of an assembly of particles with collective interaction," *J. Phys. U.S.S.R.*, vol. 9, pp. 25–40; 1945.
[73] L. Landau, "On the vibration of the electronic plasma," *J. Phys. U.S.S.R.*, vol. 10, pp. 25–34; 1946.
[74] N. G. Van Kampen, "On the theory of stationary waves in plasmas," *Physica*, vol. 21, pp. 949–963; 1955.
[75] ——, "The dispersion equation for plasma waves," *Physica*, vol. 23, pp. 641–650; July, 1957.
[76] D. Bohm and E. P. Gross, "Theory of plasma oscillations A: origin of medium-like behavior," *Phys. Rev.*, vol. 75, pp. 1851–1864; June, 1949.
[77] ——, "Theory of plasma oscillations B: excitation and damping of oscillations," *Phys. Rev.*, vol. 75, pp. 1864–1876; June, 1949.
[78] ——, "Effects of plasma boundaries in plasma," *Phys. Rev.*, vol. 79, pp. 992–1001; September, 1950.
[79] F. Berz, "On the theory of plasma waves," *Proc. Phys. Soc. (London)*, vol. B 69, pp. 939–952; September, 1952.
[80] W. P. Allis, "Electron plasma oscillations," *Proc. Symp. on Electronic Waveguides*, Brooklyn Polytechnic Inst., Brooklyn, N. Y., April 8–10, 1958, Interscience Publishers, Inc., New York, N. Y., pp. 149–159; 1958.
[81] I. B. Bernstein, J. M. Greene and M. D. Kruskal, "Exact nonlinear plasma oscillations," *Phys. Rev.*, vol. 108, pp. 546–550; November, 1957.
[82] E. P. Gross, "Plasma oscillations in a static magnetic field," *Phys. Rev.*, vol. 82, pp. 232–242; April, 1951.
[83] P. L. Bhatnagar, E. P. Gross and M. Krook, "A model for collision processes in gases. I. Small amplitude processes in charged and neutral one-component systems," *Phys. Rev.*, vol. 94, pp. 511–525; May, 1954.
[84] E. P. Gross and M. Krook, "Model for collision processes in gases: II. Small amplitude oscillations of charged two-component systems," *Phys. Rev.*, vol. 102, pp. 593–604; May, 1956.
[85] D. Bohm and D. Pines, "A collective description of electron interactions. I. Magnetic interactions," *Phys. Rev.*, vol. 82, pp. 625–634; June, 1951.
[86] ——, "A collective description of electron interactions: II. Collective vs individual particle aspects of the interactions," *Phys. Rev.*, vol. 85, pp. 338–353; January, 1952.
[87] ——, "A collective description of electron interactions: III. Coulomb interactions in a degenerate electron gas," *Phys. Rev.*, vol. 92, pp. 609–625; November, 1953.
[88] R. Q. Twiss, "On Bailey's theory of growing circularly polarized waves in a sunspot," *Phys. Rev.*, vol. 80, pp. 767–768; November, 1950.
[89] ——, "On Bailey's theory of amplified circularly polarized waves in an ionized medium," *Phys. Rev.*, vol. 84, pp. 448–457; November, 1951.
[90] ——, "Propagation in electron-ion streams," *Phys. Rev.*, vol. 88, pp. 1392–1407; December, 1952.
[91] V. A. Bailey, "Plane waves in an ionized gas with static electric and magnetic fields present," *Australian J. Sci. Research Ser. A*, vol. 1, pp. 351–359; December, 1948.
[92] J. H. Piddington, "Growth electric space-charge waves," *Australian J. Phys.*, vol. 9, pp. 31–43; March, 1956.
[93] ——, "Growing electric space-charge waves and Haeff's electron-wave tube," *Phys. Rev.*, vol. 101, pp. 14–16; January, 1956.
[94] G. Ecker, "Zur Statistischen Beschreibung von Gesamtheiten mit Kollektiver Wechselwirkung. I. Grundlagen und Grenzen Kollektiver Beschreibung," *Z. Phys.*, vol. 140, pp. 274–292; March, 1955.
[95] ——, "Zur Statistischen Beschreibung von Gesamtheiten mit Kollektiver Wechselwirkung. II. Die Bedeutung der Beschränkungen des D-Modelles für die Begriffsbildung und Ergebnisse Kollektiver Beschreibung," *Z. Phys.*, vol. 140, pp. 293–307; March, 1955.
[96] ——, "Zur Statistischen Beschreibung von Gesamtheiten mit Kollektiver Wechselwirkung. III. Die Verschiedenen Formulierungen der Trägerkinetik," *Z. Phys.*, vol. 141, pp. 294–306; July, 1956.
[97] J. E. Drummond, "Basic microwave properties of hot magneto-plasmas," *Phys. Rev.*, vol. 110, pp. 293–306; April, 1958.
[98] ——, paper presented at the Lockheed Symposium on Waves in a Plasma, December 1–2, 1960, to be published.
[99] L. Mower, "Conductivity of a warm plasma," *Phys. Rev.*, vol. 116, pp. 16–18; May, 1959.

[100] G. V. Gordeyev, "Plasma oscillations in magnetic field," *J. Exp. Theoret. Phys.* (*U.S.S.R.*), vol. 23, pp. 660–669; 1952. In Russian.
[101] I. B. Bernstein, "Waves in a plasma in a magnetic field," *Phys. Rev.*, vol. 109, vol. 10–21; January, 1958.
[102] K. M. Case, "Plasma oscillations," *Ann. Phys.*, vol. 7, pp. 349–364; July, 1959.
[103] L. Oster, "Linearized theory of plasma oscillations," *Rev. Mod. Phys.*, vol. 32, pp. 141–168; January, 1960.
[104] J. D. Jackson, "Plasma oscillations," *J. Nuclear Energy*, Pt. C, vol. 1, pp. 171–189; July, 1960.
[105] I. B. Bernstein and S. K. Trehan, "Plasma oscillations, I," *Nuclear Fusion*, vol. 1, pp. 3–41; 1960.
[106] J. E. Drummond, "Oscillations in plasma," in "Plasma Physics," McGraw-Hill Book Co., Inc., New York, N. Y., pp. 1–32; 1961.
[107] J. M. Dawson, "Nonlinear oscillations in a cold plasma," *Phys. Rev.*, vol. 113, pp. 383–387; September, 1959.
[108] E. B. Armstrong and K. G. Emeleus, "The generation of high-frequency oscillations by hot-cathode discharge tubes containing gas at low pressure," *Proc. IEE*, vol. 96, pp. 390–394; January, 1949.
[109] K. G. Emeleus and R. A. Bailey, "High-frequency plasma-electron oscillations," *Brit. J. Appl. Phys.*, vol. 6, pp. 127–128; January, 1955.
[110] R. Rompe and M. Steenbeck, "Der Plasmazustand der Gase," *Ergeb. exakt. Naturw.*, vol. 18, pp. 257–376; 1939.
[111] A. V. Haeff, "Space-charge wave amplification effects," *Phys. Rev.*, vol. 74, pp. 1532–1533; November, 1948.
[112] ——, "The electron-wave tube—a novel method of generation and amplification of microwave energy," Proc. IRE, vol. 37, pp. 4–10; January, 1949.
[113] L. S. Nergaard, "Analysis of a simple model of a two beam growing-wave tube," *RCA Rev.*, vol. 9, pp. 585–601; December, 1948.
[114] J. R. Pierce, "Increasing space-charge waves," *J. Appl. Phys.*, vol. 20, pp. 1060–1066; November, 1949.
[115] ——, "Note on stability of electron flow in the presence of positive ions," *J. Appl. Phys.*, vol. 21, p. 1063; October, 1950.
[116] —— and W. B. Hebenstreit, "A new type of high-frequency amplifier," *Bell Sys. Tech. J.*, vol. 28, pp. 33–51; January, 1949.
[117] ——, "Possible fluctuations in electron streams due to ions," *J. Appl. Phys.*, vol. 19, pp. 231–241; March, 1948.
[118] R. Q. Twiss, "On oscillations in electron streams," *Proc. Phys. Soc.* (*London*), vol. B 64, pp. 654–665; August, 1951.
[119] P. A. Sturrock, "Kinematics of growing waves," *Phys. Rev.*, vol. 112, pp. 1488–1503; December, 1958.
[120] ——, "Amplifying and evanescent waves, convective and non-convective instabilities," in "Plasma Physics," J. E. Drummond, Ed., McGraw-Hill Book Co., Inc., New York, N. Y., pp. 124–142; 1961.
[121] O. Buneman, "How to distinguish between attenuating and amplifying waves," in "Plasma Physics," J. E. Drummond, Ed., McGraw-Hill Book Co., Inc., New York, N. Y., pp. 143–164; 1961.
[122] G. J. Budker, "Relativistic stabilized electron beam," *Proc. CERN Symp. on High Energy Accelerators and Pion Physics*, Geneva, Switz., June 11–23, 1956, CERN Service d'Information, pp. 68–75; 1956.
[123] P. A. Sturrock, "Excitation of plasma oscillations," *Phys. Rev.*, vol. 117, pp. 1426–1429; March, 1960.
[124] E. V. Bogdanov, V. J. Kislov and Z. S. Tchernov, "Interaction between an electron stream and a plasma," *Symp. on Millimeter Wave Generation*, Brooklyn Polytechnic Inst., Brooklyn, N. Y., April 1–2, 1959, Interscience Publishers, Inc., New York, N. Y., pp. 57–72; 1959.
[125] Z. S. Tchernov and G. A. Bernashevski, "Amplification of Microwaves by Means of Plasma," presented at the Symp. on Electromagnetics and Fluid Dynamics, Brooklyn Polytechnic Inst., Brooklyn, N. Y., to be published in 1961.
[126] A. W. Trivelpiece, "Slow Wave Propagation in Plasma Waveguides," Electron Tube and Microwave Lab., California Inst. of Tech., Pasadena, Calif., Tech. Rept. No. 7; May, 1958.
[127] M. A. Allen and G. S. Kino, "Interaction of an electron beam with a fully ionized plasma," *Phys. Rev. Lett.*, vol. 6, pp. 163–165; February, 1961.
[128] ——, "Experiments with a Fully Ionized Cesium Plasma," presented at Lockheed Symp. on Waves in a Plasma, Palo Alto, Calif., December 1–2, 1960. To be published.
[129] A. I. Akhiezer and Y. B. Fainberg, "High-frequency oscillations of an electron plasma," *J. Exsptl. Theoret. Phys. U.S.S.R.*, vol. 21, pp. 1262–1269; 1951.
[130] J. Feinstein and H. K. Sen, "Radio wave generation by multi-stream charge interaction," *Phys. Rev.*, vol. 83, pp. 405–412; July, 1951.
[131] R. Q. Twiss, "Discussion on the generation of plasma oscillations," presented at the Conf. on Ionized Media, University College, London; April 7, 1951.
[132] M. A. Lampert, "Plasma oscillations at extremely high frequencies," *J. Appl. Phys.*, vol. 27, pp. 5–11; January, 1956.
[133] M. Sumi, "Theory of excited plasma waves," *J. Phys. Soc.* (*Japan*), vol. 13, pp. 1476–1485; December, 1958.
[134] ——, "Excitation of oscillations in a plasma layer," *Phys. Rev. Lett.*, vol. 2, pp. 37–38; January, 1959.
[135] G. F. Filiminov, "Growing wave propagation in a plasma," *Radiotechnics and Electronics*, vol. 4, pp. 75–87; January, 1959. (In Russian.)
[136] O. Buneman, "Dissipation of currents in ionized media," *Phys. Rev.*, vol. 115, pp. 503–517; August, 1959.
[137] R. A. Demirkhanov, A. K. Gevorkov and A. P. Popov, "The interaction of a beam of charged particles with a plasma," *Proc. 4th Internatl. Conf. on Ionization Phenomena in Gases*, Uppsala, Sweden, 1959, North-Holland Publishing Co., Amsterdam, Neth., vol. 2, pp. 665–669; 1960.
[138] A. V. Haeff, "On the origin of solar radio noise," *Phys. Rev.*, vol. 75, pp. 1546–1551; May, 1949.
[139] D. H. Looney and S. C. Brown, "The excitation of plasma oscillations," *Phys. Rev.*, vol. 93, pp. 965–969; March, 1954.
[140] S. Kojima, K. Kato, and S. Hagiwara, "Oscillations in plasma I," *J. Phys. Soc.* (*Japan*), vol. 12, pp. 1276–1281; November, 1957.
[141] E. I. Gordon, " 'Plasma Oscillations,' the Interaction of Electron Beams with Gas Discharge Plasmas," Ph.D. dissertation, Phys. Dept., Mass. Inst. Tech., Cambridge; January, 1957.
[142] I. F. Kharchenko, *et al.*, "Experimental and theoretical investigation of the interaction of an electron beam with a plasma," *Proc. 4th Internatl. Conf. on Ionization Phenomena in Gases*, Uppsala, Sweden, 1959, North-Holland Publishing Co., Amsterdam, Neth., vol. 2, pp. 671–680; 1960.
[143] T. R. Neill and K. G. Emeleus, "Plasma electron oscillations," *Proc. Roy. Irish Acad.*, vol. 53, pp. 197–222; January, 1951.
[144] K. G. Emeleus, "Plasma electron oscillations," *Appl. Sci. Research*, vol. B 5, pp. 66–68; 1955.
[145] W. P. Allis, "Electron Oscillations in Gas Discharges," presented at URSI Meeting, Commission 7, Boulder, Colo.; 1957.
[146] M. J. Kofoid, "Experimental two-beam excitation of electron oscillations in a plasma without sheaths," *Phys. Rev. Lett.*, vol. 4, pp. 556–557; June, 1960.
[147] G. Wehner, "Plasma oscillator," *J. Appl. Phys.*, vol. 21, pp. 62–63; January, 1950.
[148] ——, "Electron plasma oscillations," *J. Appl. Phys.*, vol. 22, pp. 761–765; June, 1951.
[149] H. Fetz, "On the control of a mercury arc by means of a grid in the plasma," *Ann. Phys.* (*Lpz.*), vol. 37, pp. 1–40; January, 1940.
[150] ——, "Stability of the controlled mercury arc," *Arch. Elektrotech.*, vol. 36, pp. 378–381; June, 1942.
[151] W. O. Schumann, "The stabilization of the controlled vacuum arc and the arc constants," *Arch. Elektrotech.*, vol. 36, pp. 362–377; June, 1942.
[152] G. Wehner, "Sondenuntersuchungen am stabilisierten Quecksilberdampfbogen," *Ann. Phys.* (*Lpz.*), vol. 4, pp. 501–519; July, 1942.
[153] D. Gabor, "Plasma oscillations," *Brit. J. Appl. Phys.*, vol. 2, pp. 209–218; 1951.
[154] K. G. Emeleus, "Oscillations and fluctuations in gas discharges," *Nuovo cimento* (*Suppl. 10*), vol. 3, pp. 490–495; March, 1956.
[155] L. A. Pardue and J. S. Webb, "Ionic oscillations in the glow discharge," *Phys. Rev.*, vol. 32, pp. 946–949; December, 1928.
[156] ——, "Ionic oscillations in the glow discharge," *Phys. Rev.*, vol. 31, p. 1122; June, 1928.
[157] B. D. Fried and R. W. Gould, "On the Detection of Ion Oscillations in a Mercury Discharge," Space Tech. Labs., Los Angeles, Calif., Rept. STL/TR 60-0000 GR 413; December, 1960.
[158] ——, "Longitudinal ion oscillations in a hot plasma," *Phys. Fluids*, vol. 4, pp. 139–147; January, 1961.
[159] E. B. Armstrong, K. G. Emeleus, and T. R. Neill, "Low-frequency disturbances in gaseous conductors," *Proc. Roy. Irish Acad.*, vol. A 54, pp. 291–310; December, 1951.
[160] F. W. Crawford, "Electrostatic sound wave modes in a plasma," *Phys. Rev. Lett.*, vol. 6, pp. 663–665; June, 1961.
[161] W. Newcomb, USAEC Repts. 239 and 326; Washington, D. C.; June, 1955.
[162] I. B. Bernstein, *et al.*, "Ion wave instabilities," *Phys. Fluids*, vol. 3, pp. 136–137; 1960.
[163] I. B. Bernstein and R. M. Kulsrud, "Ion wave instabilities," *Phys. Fluids*, vol. 3, pp. 937–945; November, 1960.
[164] O. Buneman, "Instability, turbulence, and conductivity in current-carrying plasma," *Phys. Rev. Lett.*, vol. 1, pp. 8–9; July, 1958.

[165] ——, "Maintenance of equilibrium by instabilities," *J. Nuclear Energy*, pt. C, vol. 2, pp. 119–134; January, 1961.
[166] J. R. Pierce, "Possible fluctuations in electron streams due to ions," *J. Appl. Phys.*, vol. 19, pp. 231–236; March, 1948.
[167] K. G. Hernqvist, "Plasma ion oscillations in electron beams," *J. Appl. Phys.*, vol. 26, pp. 544–548; May, 1955.
[168] ——, "Plasma oscillations in electron beams," *J. Appl. Phys.*, vol. 26, pp. 1029–1030; August, 1955.
[169] C. C. Cutler, "Spurious modulation of electron beams," PROC. IRE, vol. 44, pp. 61–64; January, 1956.
[170] T. Moreno, "Spurious modulation of electron beams," PROC. IRE, vol. 44, p. 693; May, 1956.
[171] M. Ettenberg and R. Targ, "Observations of plasma and cyclotron oscillations," *Proc. Symp. on Electronic Waveguides*, Brooklyn Polytechnic Inst., Brooklyn, N. Y., April 8–10, 1958, Interscience Publishers, Inc., New York, N. Y.; 1958.
[172] P. Chorney, "Electron-Stimulated Ion Oscillations," Res. Lab. of Electronics, M.I.T., Cambridge, Mass., Tech. Rept. 277; May, 1958.
[173] R. L. Jepson, "Ion oscillations in electron beam tubes; ion motion and energy transfer," PROC. IRE, vol. 45, pp. 1069–1080; August, 1957.
[174] R. W. Revans, "The transmission of waves through an ionized gas," *Phys. Rev.*, vol. 44, pp. 798–802; November, 1933.
[175] W. Funk and R. Seeliger, "Untersuchungen über die inneren Schwingungen von Niedervoltbogen," *Z. Phys.*, vol. 113, pp. 203–217; July, 1939.
[176] G. S. Kino and H. A. Woods, unpublished work.
[177] Thong Saw Pak, "Noise from hot cathode discharges," *Proc. Phys. Soc. (London)*, vol. B 68, pp. 292–296; May, 1955.
[178] F. W. Crawford and J. D. Lawson, "Some Measurements of Fluctuations in a Plasma," Microwave Lab., Stanford University, Stanford, Calif., M.L. No. 753, October, 1960; *J. Nuclear Energy*, Pt. C; July, 1961.
[179] ——, "Low-Frequency Fluctuations in a Plasma," Internatl. Conf. of Ionization Phenomenon in Gases, Munich, Germany, August 26–30, 1961, to be published.
[180] M. D. Gabovitch, L. L. Pasechik, and V. G. Yazevo, "Observation of ion oscillations in a plasma," *Soviet Phys. JETP*, vol. 11, pp. 1033–1035; November, 1960.
[181] H. Martin and H. A. Woods, "Low-frequency noise spectra of hot-filament, low-pressure discharge tubes," *Proc. Phys. Soc. (London)*, vol. B 65, pp. 281–286; April, 1952.
[182] F. W. Crawford, "Frequency Spectra of Low-Frequency Fluctuations in a Plasma," Stanford University, Stanford, Calif., Microwave Lab. Rept. No. 762; November, 1960.
[183] ——, "Impedance Characteristics of a Low-Pressure Mercury-Vapor Plasma," Stanford University, Stanford, Calif., Microwave Lab. Rept. No. 761; November, 1960.
[184] K. H. Kingdon, "Rectification by oscillation of positive ions about the potential minimum of a thermionic triode," *Phys. Rev.*, vol. 33, p. 1075; June, 1929.
[185] S. Ballantine, "Fluctuation noise due to collision ionization in electronic amplifier tubes," *Physics*, vol. 4, pp. 294–306; September, 1933.
[186] K. G. Emeleus and N. R. Daly, "Ion oscillations in a cathode potential minimum," *Proc. Phys. Soc. (London)*, vol. 69 B, pp. 114–115; January, 1959.
[187] ——, "Initiation of hot cathode discharges," *Brit. J. Appl. Phys.*, vol. 6, pp. 370–372; July, 1955.
[188] J. F. Waymouth, "The measurement of thermionic emission in discharge tubes," *Sylvania Technologist*, vol. 13, pp. 2–10; January, 1960.
[189] H. J. J. Van Boort and M. Klerk, "High-frequency oscillations in low-pressure mercury arcs," *Appl. Sci. Research*, vol. B 5, pp. 69–74; 1955.
[190] K. G. Emeleus, "Plasma studies survey of experiments, I. Mainly optical studies," *J. Nuclear Energy*, Pt C, vol. 2, pp. 65–68; January, 1961.
[191] ——, "Plasma studies survey of experiments, II. Mainly Probe studies," *J. Nuclear Energy*, Pt. C, vol. 2, pp. 69–72; January, 1961.
[192] K. Landecker and B. J. Robinson, "Study of high-frequency fluctuations from light sources using phototubes and tuned RF amplifiers," *Proc. Phys. Soc.*, vol. B 66, pp. 737–742; September, 1953.
[193] W. Pupp, "Oszillographische Sondenmessungen an laufenden Schichten der positiven Saüle von Edelgasen," *Z. Phys.*, vol. 36, pp. 61–66; January, 1935.
[194] E. V. Appleton and A. G. D. West, "Ionic oscillations in the striated glow discharge," *Phil. Mag.*, vol. 45, pp. 879–881; May, 1923.
[195] L. B. Loeb, "Fundamental Processes of Electrical Discharge in Gases," John Wiley and Sons, Inc., New York, N. Y., pp. 563–574; 1939.
[196] H. Y. Loh and G. H. Dieke, "Fluctuations in gas discharges," *J. Opt. Soc. Am.* vol. 37, pp. 837–848; October, 1947.
[197] T. Donahue and G. H. Dieke, "Oscillatory phenomena in direct current glow discharges," *Phys. Rev.*, vol. 81, pp. 248–261; January, 1951.
[198] L. Pekarek, "Factors affecting the self-excitation of low-frequency oscillations in an electric discharge," *Czech. J. Phys.*, vol. 8, pp. 32–45; 1958.
[199] ——, "New method of measurement of relaxation times in glow discharge plasma," *Proc. 4th Internatl. Conf. on Ionization Phenomena in Gases*, Uppsala, Sweden, 1959, North-Holland Publishing Co., Amsterdam, Neth., vol. 2, pp. 306–308; 1960.
[200] H. S. Robertson, "Moving striations in direct current glow discharges," *Phys. Rev.*, vol. 105, pp. 368–377; January, 1957.
[201] K. W. H. Foulds, "Moving striations in low-pressure mercury vapor," *J. Electronic and Control*, vol. 1, pp. 270–278; November, 1956.
[202] W. H. McCurdy, "The striated discharge in mercury vapour," *Phil. Mag.*, vol. 48, pp. 898–917; November, 1924.
[203] K. T. Compton, L. A. Turner, and W. H. McCurdy, "Theory and experiments relating to the striated glow discharge in mercury vapor," *Phys. Rev.*, vol. 24, p. 597; 1924.
[204] W. H. McCurdy and P. Dalton, "Low voltage discharges in He," *Phys. Rev.*, vol. 27, p. 163; 1920.
[205] K. G. Emeleus and A. H. Gregg, "The association of ionic oscillations with negative glow and anode glow," *Phil. Mag.*, vol. 16, pp. 1079–1082; December, 1933.
[206] W. Pupp, "Influence of the anode on the stability of discharges in argon," *Z. Phys.*, vol. 34, pp. 756–761; October, 1933.
[207] I. Langmuir, "The pressure effect and other phenomena in gaseous discharges," *J. Franklin Inst.*, vol. 196, pp. 751–762; December, 1923.
[208] W. W. H. Clarke, "The influence of cathode standing waves on valve stability," *Brit. J. Appl. Phys.*, vol. 6, pp. 433–441; July, 1955.
[209] K. G. Emeleus and D. W. Mahaffey, "Plasma oscillations," *J. Nuclear Energy*, pt. C, vol. 2, pp. 117–118; January, 1961.
[210] J. D. Cobine and C. J. Gallagher, "Effect of magnetic field on oscillations and noise in hot-cathode arcs," *J. Appl. Phys.*, vol. 18, pp. 110–116; January, 1947.
[211] J. D. Cobine and J. R. Curry, "Electrical noise generators," PROC. IRE, vol. 35, pp. 875–879; September, 1947.
[212] S. Ruthberg, "Cold cathode gas tubes as noise generators," *Phys. Rev.*, vol. 70, p. 112; July, 1946.
[213] K. F. C. Hoh and B. Lehnert, "Diffusion processes in a plasma column in a longitudinal magnetic field," *Phys. Fluids*, vol. 3, pp. 600–607; July, 1960.
[214] Thong Saw Pak, "New effects of an auxiliary cathode on a discharge at low pressure," *J. Electronics and Control*, vol. 3, pp. 471–480; November, 1957.
[215] E. O. Johnson, J. Olmstead, and W. M. Webster, "The tacitron, a low noise thyratron capable of current interruption by grid action," PROC. IRE, vol. 42, pp. 1350–1362; September, 1954.
[216] G. C. McCullagh, "A simple plasma oscillator," *J. Sci. Inst.*, vol. 38, p. 164; April, 1961.
[217] J. Feinstein, "Condition for radiation from a solar plasma," *Phys. Rev.*, vol. 85, pp. 145–146; January, 1952.
[218] M. A. Allen and G. S. Kino, "Beam Plasma Amplifiers," presented at IRE WESCON, San Francisco, Calif., August 22–25, 1961.
[219] I. Langmuir and K. H. Kingdon, "Thermionic effects caused by vapors of alkali metals," *Proc. Roy. Soc. (London)*, vol. A 107, pp. 61–79; 1925.
[220] N. D'Angelo and N. Rynn, "Diffusion of a cold cesium plasma across a magnetic field," *Phys. Fluids*, vol. 4, pp. 275–276; February, 1961.
[221] R. C. Knechtli and J. Y. Wada, "Generation and measurement of highly-ionized quiescent plasmas in steady state," *Phys. Rev. Lett.*, vol. 6, pp. 215–217; March, 1961.
[222] J. M. Anderson, "Ultimate and secondary energies in the negative glow of a cold-cathode discharge in helium," *J. Appl. Phys.*, vol. 31, pp. 511–515; March, 1960.
[223] J. M. Anderson and L. A. Harris, "Negative glow plasma as a cathode for electron tubes," *J. Appl. Phys.*, vol. 31, pp. 1463–1468; August, 1960.
[224] J. M. Anderson, "Possible low noise beam-plasma amplifier," *J. Appl. Phys.*, vol. 30, pp. 1624–1625; October, 1959.
[225] I. Alexeff and R. Neidigh, "Apparent Observation of Ionic Sound Waves in a Plasma," Oak Ridge Natl. Lab., Tenn., Rept. No. 61-2-57; February, 1961.
[226] ——, "Apparent observation of ionic sound waves in a plasma," *Bull. Am. Phys. Soc.*, vol. 6, pp. 309–311; April, 1961.
[227] G. S. Kino, "A proposed millimeter wave generator," *Proc. Symp. on Millimeter Waves*, Brooklyn Polytechnic Inst., Brooklyn, N. Y., March 31, April 1–2, Interscience Publishers, Inc., New York, N. Y., pp. 233–248; 1959.

Ionic and Plasma Propulsion for Space Vehicles*

G. R. BREWER†, M. R. CURRIE†, SENIOR MEMBER, IRE, AND
R. C. KNECHTLI†, MEMBER, IRE

Summary—**The propulsion of future space vehicles by means of electrical engines appears to be the most practical and effective method for long interplanetary missions. The basic principles of the major class of such electrical engines, *viz.*, those utilizing ionic or plasma acceleration, involve technologies familiar to and largely stemming from the work of electronics engineers and plasma physicists. This paper describes the various methods under investigation today for the acceleration and neutralization of charged particles for use in propulsion. The several topics discussed include the problem of beam neutralization, cesium ion engines, electron-bombardment engines, and magnetic plasma acceleration.**

Introduction

THE SUBJECT of electrical propulsion represents an exciting new area of applied science and technology which is rapidly growing in interest and importance and which has, literally, an unlimited future. Electrically propelled spacecraft provide the only feasible means for exploring the further reaches of our solar system, for economically transporting large manned expeditions and heavy payloads to our neighboring planets and for probing the solar system away from the ecliptic plane.

It is inevitable that such vast new concepts as this build on fundamental knowledge and experience in a variety of fields and, in turn, provide strong motivation for vigorous new work and progress in these areas. This is certainly the case here. From an over-all viewpoint a nuclear-electric propulsion system consists of three major components: a lightweight nuclear reactor, an efficient method for converting thermal energy to electrical energy, and the thrust unit itself. The first two of these are giving strong impetus to fundamental and applied work in the areas of new types of high-temperature reactors and methods of direct energy conversion such as thermionic and MHD devices.

The third major component, the electrical thrust unit, is the subject of this paper. As will be shown, it builds directly on the broad field of electronics concerned with plasma physics and devices, beam and particle dynamics, electron optics and electron tube technology. The purpose of this paper is to discuss electrical propulsion devices from this point of view. Rather than present a detailed picture of the increasing number of specific engineering developments in this field, we intend that the discussion shall relate the general directions of current efforts to basic problems in plasma physics, ion beam generation and control, and particle dynamics. We take the point of view that the rapid development and future success of electrical propulsion will depend upon continued fundamental research in these areas and that, conversely, progress in electrical propulsion will have a significant impact on these basic areas in terms of new understandings and new tools for attacking problems of fundamental importance. In short, electrical propulsion is a field which is fertile for invention, research, innovation, and cross-fertilization with other major areas of applied physics and electronics.

The concept of the ion rocket engine has existed for many years. In 1906 R. H. Goddard mentioned it in his notebook [1], and in 1929 H. Oberth devoted a chapter of his book, *Wege zur Raumschiffahrt* [2], to the concept. However, active research and development effort has only taken place during the last few years; some of the earliest articles on electrical propulsion in the U. S. literature were written in 1954 by Dr. Ernst Stuhlinger, now of NASA, who has continued to provide much of the stimulus and leadership for this program. Although a large and growing body of literature on the subject exists, no attempt is made here to give a complete list of references.

The importance of electrical propulsion can be seen from the following basic relations. Thrust is equal to the rate of change of momentum imparted by the exhaust of a rocket engine. For simplicity, let it be assumed that all particles in the exhaust have the same velocity v_{ex}. Then the thrust T is simply

$$T \equiv \dot{m}_p v_{ex}, \tag{1}$$

where $\dot{m}_p$ is the propellant mass flow rate. If this thrust lasts for a time τ, the total impulse imparted to the vehicle is equal to $T\tau$.

The *specific impulse*, defined as the impulse per unit weight of propellant exhausted, is

$$I_{sp} \equiv \frac{T\tau}{w_p} = \frac{T}{\dot{w}_p}, \tag{2}$$

where $w_p = m_p g$ is the propellant weight exhausted in time τ. This gives the specific impulse as thrust per unit of propellant weight flow rate. Combining (1) and (2), we obtain

$$I_{sp} = \frac{v_{ex}}{g} \text{ seconds}, \qquad (g = 9.8 \text{ m/second}^2) \tag{3}$$

which identifies specific impulse as a measure of the exhaust velocity.

Consider, now, the equation of motion in free space for a vehicle whose mass M and velocity v are functions of time:

$$Mdv = -v_{ex}dM. \tag{4}$$

* Received by the IRE, October 3, 1961.
† Hughes Research Laboratories, Malibu, Calif.

For an initial mass M_i starting from rest, (4) gives

$$v = I_{sp} g \ln \left(\frac{M_i}{M} \right). \tag{5}$$

Thus, the effectiveness of mass expenditure to gain velocity is a function of specific impulse, *i.e.*, from a mass point of view, a given velocity increment is achieved more efficiently with a system having high specific impulse.

With low specific impulse chemical rockets, the mass loss is very high. These systems, of course, have high thrust and are needed for overcoming gravitational forces and injecting payloads into orbit. However, for many projected space missions starting from an earth orbit, the tremendous mass of a chemical or even nuclear rocket, which is necessary to deliver a heavy payload, is completely unfeasible. The specific impulse of a chemical rocket is limited to values below about 400 seconds; the primary limitation is imposed by the maximum reaction temperature and minimum molecular weight of the fuel. By choosing hydrogen for the propellant, the direct nuclear heat transfer rocket (*e.g.*, Rover) is expected to increase the specific impulse to 800 and perhaps even 1000 seconds; here the temperature limitations of the material establish an upper limit. Because of their high thrust, chemical and nuclear rockets will be important for near-earth missions. However, many interplanetary and deep-space scientific missions requiring heavy payloads are impossible to accomplish with foreseeable chemical or nuclear vehicles. Low thrust propulsion systems operating over long periods of time and having very high specific impulse values are mandatory in such cases.

It is clear that the acceleration of ions to any desired velocity by electrostatic or electromagnetic fields is unrelated to thermal heating; *i.e.*, in the former process, the specific impulse can be adjusted to any desired value. The power required to accelerate the particles is proportional to the product of thrust and velocity. The weight of the nuclear-electric power supply increases roughly in proportion to power. Therefore, depending upon the mission, there exists an optimum exhaust velocity or specific impulse which results in minimum over-all weight (*i.e.*, compromise between power system weight and propellant weight). This optimum specific impulse is larger for longer missions and heavier payloads but is invariably above several thousand seconds, varying from roughly 5000 seconds for a 5000-pound payload in a Mars orbit using the Atlas-Centaur booster and a 60-kw power supply, to more than 10,000 seconds for a 15-ton terminal mass in a Jupiter orbit using Saturn and a 1-Mw power supply. Thus, nuclear-electric propulsion systems constitute an ideal solution for the types of missions discussed above.

Many detailed calculations have shown that for a given over-all initial weight and, for example, for a round-trip mission to and from a Mars parking orbit, payloads of up to four or more times those possible with direct nuclear rockets or, conversely, much shorter mission durations with the same payload weight will result. For more ambitious space experiments (*e.g.*, to Jupiter) the figures are even more impressive. Often a factor of ten increase in payload or a considerable reduction in initial vehicle weight can be attained. It should be noted that these calculations include the nuclear-electric power supply as part of the propulsion system. However the use of the power supply for wideband data transmission and for primary power for other purposes at the destination makes the effective payload weight ratios between electric and nuclear systems even higher.

There are several varying approaches to the electrical generation of thrust. These are usually classified as electrothermal, electrostatic, and electromagnetic. All have in common the requirements for very long life, high power efficiency, and high propellant utilization efficiency.

Of the above types of electrical propulsion, this paper will be concerned only with the latter two approaches. The thermal arc jet is not a true electric thrust unit in the sense of overcoming material temperature limitations and thus permitting very high specific impulse. In it, a high-current arc is used to resistively heat a propellant gas (*e.g.*, hydrogen) to high temperatures. The gas is then expanded through a nozzle where the thermal energy is converted to directed kinetic energy. It is limited to specific impulses in the neighborhood of 1000 seconds, the efficiency decreasing very rapidly beyond that point.

The electrostatic engine appears to offer the possibility of efficiently achieving higher specific impulses than the other types, *i.e.*, in the range of several thousand seconds and higher. Ion propulsion is very simple in concept since it involves the imparting of energy to ions by electrostatic acceleration. To serve as a reference, Fig. 1 shows specific impulse as a function of net accelerating voltage for some of the common propellants. However, in transforming this essentially simple idea to practical fruition, there are a number of problems involving fundamental considerations in plasma physics and electronics. First, an efficient ion source is required. A number of such sources are possible: contact ionization, Penning discharges, magnetically stabilized arcs, and various combinations of these. All are the subject of intensive research efforts, the results of which will add significantly to the technology of this and related fields in physics and electronics. Second, sophisticated high-perveance ion-optical acceleration and focusing systems are mandatory with a perfection exceeding even that required by electron guns and beams for use in high-power microwave tubes. Third, space-charge-neutralization mechanisms are required which introduce intriguing new concepts such as synthetic nonthermal plasmas and the basic questions relating to them.

The other major class of electrical propulsion engines involves the direct acceleration of plasmas by magnetic




Fig. 1—Curves showing specific impulse as a function of net accelerating voltage for various propellant gases (singly ionized) in electrostatic rocket engine.

fields. This class is usually limited to the range of specific impulses between roughly 2000–5000 seconds. Here the problem of achieving space-charge neutrality is not present. Again, a number of mechanisms for acceleration are possible, including the use of dc crossed electric and magnetic fields (MHD types), traveling-wave systems, and quasi-stationary RF systems. These involve problems which are fundamental to other fields (*e.g.*, energy conversion and high-temperature plasma generation and containment) as well as to the attainment of high-efficiency thrust devices.

In this review paper it is hoped that discussion of some of the basic problems in achieving practical e'ectric propulsion systems and of the broad current approaches to their solution will stimulate increased interest and imaginative effort in this field on the part of investigators in applied physics and electronics, on whose technology this new art is directly based.

I. Basic Problems

In the process of developing electric propulsion systems, there are several technical objectives and problems which are common to the various types of systems outlined above. Obviously, the primary objective involves the devising of field configurations (electric and/or magnetic) capable of accelerating charged particles in a controlled manner to the desired exhaust velocity.

One of the primary considerations in the invention of propulsion systems is efficiency—efficiency both in use of the electrical power and of the propellant. In the elementary equations presented above, it was shown that the performance of the space vehicle is critically dependent on the weight of both the electric power generating system and the propellant that must be carried. It is therefore essential to devise propulsion systems which will convert as much as possible of the electrical power available in the vehicle into useful thrust, and power efficiencies larger than about 80 or 90 per cent are desirable. Fortunately, work to date, which will be reported in more detail below, indicates that such efficiency values are attainable. The propellant-utilization efficiency should be high (greater than 90 per cent) for the simple reason that we do not wish to carry excess propellant which would decrease the performance of the space craft. As we shall see later, in the electrostatic rocket even higher ionization or propellant-utilization efficiency is essential, in order to reduce the effects of charge-exchange reactions.

The second serious consideration is neutralization of the charges associated with the particles of the exhaust beam. As mentioned earlier, the class of electric engines in which the acceleration of the charged particles results from magnetic fields will presumably exhaust a neutral beam, *i.e.*, the accelerated and exhausted medium will be very close to a true plasma. In the case of electrostatic rockets, on the other hand, the acceleration of the charged particles is accomplished by means of electric fields; therefore only one species can be accelerated in a given region. In this case, the charges must be separated. In order to prevent buildup of space-charge forces at the engine exhaust, the accelerated charges must be neutralized by the injection of particles of the opposite sign. (We do not mean that the positive and negative particles must recombine, but merely that in any given region of the exhaust beam, there must be an equal number of positive and negative charges.)

Since the electrostatic rocket imparts acceleration to the positive and negative charges separately, some mechanism must be provided to ionize the neutral propellant particles. As we shall see, the ionization mechanisms used in the engines to be considered are contact ionization of cesium on tungsten and ionization by electron impact. This ionization must be accomplished with the minimum possible loss of energy, in order to maintain high over-all efficiency. Not only must the ionization process be efficient in terms of the energy required to create the ions, but the mechanism must be capable of supplying a relatively high density of ion current to the accelerator system. Typical ion current densities of the two mechanisms mentioned above are 10 to 20 ma/cm^2. These values are sufficiently high to allow the development of electric engines suitable for space missions; however, higher-density sources are definitely needed for future engines, and this consideration does form a fundamental limitation on the performance of electric propulsion engines.

Another fundamental limitation is the erosion of electrodes involved in the acceleration of the charged particles due to impingement of the charged particles on these electrodes. The electric propulsion engines that we are describing here will be used for space vehicles in in-

terplanetary travel, and the mission times involved are measured in years. Therefore, a serious constraint on the design of the engines is that the total erosion of the electrodes must be small enough that it does not interfere with engine operation over lifetimes of tens of thousands of hours. This imposes, for example, the condition of very careful control over the ion optical characteristics of the accelerator structure so that the impingement of the accelerated ions on any of the surrounding electrodes may be avoided. In the electrostatic rocket, a maximum of about one ion can be allowed to strike the accelerating electrode for each 100,000 ions emitted from the ionizer, *i.e.*, an interception ratio of about 10^{-5}.

In the rest of this paper, we shall discuss the several types of electric propulsion engines from the point of view of these basic objectives, and attempt to show how these fundamental problems are being approached. In other words, we shall try to understand the physics involved rather than the details of the engineering of these engines. The reader must bear in mind, however, that there are many engineering and technological problems which must be solved, and, in many cases, the development of electric engines will depend as much on a solution of these engineering problems as on the invention of solutions to the more fundamental ones.

II. Electrostatic Acceleration

Electrostatic acceleration is characterized by the *separate* acceleration by electrostatic fields of the positive and negative charges; *i.e.*, ions are created by some ionization process prior to acceleration. In the cesium-type engine this ionization occurs at a hot tungsten surface; in the Penning or Kaufman engine the ionization mechanism is electron impact. This class of engines also has the common requirement for neutralization of the exhaust ion beam by the injection of charged particles of the opposite polarity. We shall describe first this common problem of neutralization, followed by discussions of several of the electrostatic engines being investigated today.

A. Neutralization

As mentioned earlier, in the electrostatic rocket the ionized propellant particles are accelerated separately from the negative particles, after which electrons are injected to neutralize the positively charged beam. The successful neutralization of the space-charge fields of this ejected ion beam is one of the most difficult and controversial problems in the ion engine today. Progress in this technical area could spell the difference between success and failure of an ion engine in producing useful thrust in space (we can easily be misled by successful tests in a ground-based laboratory, where electrical conditions can be quite different from those in space). The real test of the requirement for and the effectiveness of neutralization must await a space flight; in the meantime, some demonstrations of neutralization in practical engines have been made in laboratory tests. We shall try to present here a brief but fairly complete picture of the neutralization problem, indicating insofar as possible all sides of this controversial subject; it will be clear, however, that many important questions remain unanswered. In addition to its obvious application to electrical propulsion, a neutralized and directed beam of ions represents a new and novel form of plasma with many interesting properties and with potential uses so far almost completely unexplored.

There are two types of neutralization which must be clearly differentiated:

1) Current Neutralization: A positive ion beam which is ejected from an electrically isolated space vehicle will produce on this vehicle a net negative charge. This charge will build up very quickly to such a magnitude that all of the ions will be pulled back. It is necessary, therefore, to eject an equal current of negative charges along with the positive ions. This step is essential in order to maintain the entire space vehicle electrically neutral. In principle, we could accomplish this current neutralization merely by ejecting negative particles (*e.g.*, electrons) from any part of the vehicle [see Fig. 2(a)], and they would ultimately be attracted toward the cloud of positive ions [see Fig. 2(b)].





Fig. 2—(a) Illustration of current neutralization of a space vehicle by ejection of equal numbers of electrons and ions per second, but from opposite ends of the vehicle. The charge inside a surface surrounding the vehicle can be made equal to zero. (b) The fields of the charges ejected as shown in (a) will attract the more mobile electrons toward the ions, leaving an uncompensated region of positive charge near the vehicle.

2) Charge Neutralization: The question of the need for detailed neutralization of the *charge* in the ejected ion beam is currently the controversial aspect of this problem. The following discussion will be limited to the need for charge neutralization, since this is the aspect of the neutralization problem requiring more discussion and study at present; it is tacitly assumed here that the requirement of current neutralization is met exactly.

TABLE I




Since this neutralized ion beam can be thought of as possessing many of the properties of a very energetic non-thermalized synthetic plasma, with interesting possible applications other than propulsion, we shall treat this subject in a fair amount of detail, and include some of the experiments which have been performed. We can perhaps see this problem in broad perspective by examining Table I, which will be referred to during the subsequent discussion.

In order to obtain charge neutrality of the ion beam, negative particles must be injected either into or close to the ion beam. A heavy particle such as a negative ion offers certain advantages as the neutralization particle; however, the far more copious supply of electrons available makes the electron the more attractive negative particle to use for neutralization. Therefore, we shall confine our discussion to the use of electrons as the neutralizing particles.

The fundamental purpose of neutralizing an ion beam, of course, is to eliminate, or to reduce to the point of ineffectiveness, any electric fields in the vicinity of this beam which can diminish the thrust obtainable from the ion engine. Since the thrust is proportional to the product of the beam current and the ejected velocity of the propellant, any fields which act to reduce either the beam current or the ejected velocity will adversely affect the thrust; mere transverse expansion of the beam after leaving the engine will not produce such a counter thrust.

At this point we can distinguish two broad classes of ion beams, giving rise to different neutralization problems:

1) The Broad Beam: This class of beam corresponds to an aspect ratio [3] considerably greater than unity; *i.e.*, the area of the beam is considerably greater than the square of the spacing between the ionizer and the accelerating electrode. This beam in idealized form can be thought of as originating in a large accelerator structure with a grid over the accelerator electrode aperture. Because of the shape of this beam, the electric flux lines will be predominantly axial, *i.e.*, from the positive charges in the beam to negative charges on the outer surface of the accelerator electrode [see Fig. 3(a)]. These axial field lines will act to reduce the velocity of the ejected particles and therefore to diminish the thrust obtainable. In fact, *if* the proper boundary conditions are forced along the outer edge of the beam (to ensure that all of the flux lines will be truly axial in direction), the ions will be stopped and will form a "virtual cathode" at a distance from the accelerator electrode equal to the accelerator-ionizer spacing [4]. A close analogy can be drawn between this "one-dimensional" flow of ions and



(a) (b)

Fig. 3—The effect of the shape factor of the ion beam on the axial electric field, which, if unneutralized, will accelerate the electrons axially. (a) Schematic configuration—broad beam. (b) Shape of the flux lines in the case of a thin strip or pencil beam.

the flow of charged particles between planar grid surfaces, as treated by Fay, Samuel, and Shockley [5].

This "broad" type of ion beam obviously exhibits attractive advantages, in that it provides relatively high values of thrust density (thrust per unit of ion source area); however, if unneutralized, the strong axial fields can reduce the exhaust velocity of the propellant and/or, in the extreme case, produce "turn around" [6] so that particles are returned to the accelerator, thus reducing the exhaust current.

2) The "Thin" Beam: A "thin" beam is one for which the transverse dimension at a point near the engine is small compared with the acceleration distance (*i.e.*, $R \ll 1$). The electric flux lines associated with the charges of this beam will be predominantly transverse to the beam boundary [see Fig. 3(b)] so that the space charge will result in a transverse beam spread rather than in a decrease in axial velocity of the particles, as in the "broad" beam. A thin beam can travel long distances from the engine unneutralized. This beam has the severe disadvantage, however, of very low thrust density and is therefore impractical for space propulsion.

3) The "Intermediate" Beam: From the above arguments, it appears that practical ion engines will be designed in an "intermediate" range (which turns out to be an aspect ratio roughly equal to unity measured for each individual beam) but in some type of cluster so that the desired thrust density can be achieved. The problem, then, is to design the individual beams to behave somewhat as a thin beam and arranged just close enough together to give an efficient engine design without danger of the system degenerating into a broad beam with subsequent problems of "turn around" and return current.

The broad or intermediate ($R \approx 1$) types of beams, in which neutralization appears to be a definite requirement, will be discussed below. But first let us try to provide a more quantitative justification for the need for charge neutralization in an ejected ion beam by means of the following examples:

1) One serious consequence of the lack of neutralization will be the transverse spreading of the beam due to space-charge forces. A typical cesium ion beam of current density 10 ma/cm^2 at an exhaust potential of 10 kv and an initial diameter of 9 cm will double in diameter in a distance of less than 2 cm. This spreading is so rapid as to invalidate the simple beam-spread theory used, but the example does serve to illustrate the seriousness of the spreading problem. While such spreading may not reduce the engine thrust, it must be considered in the engine design in order to avoid any interception, etc.

2) If the same beam is considered as in one-dimensional flow, with entirely axial electric fields, the velocity of the ions will be reduced to zero due to the space-charge fields, in a distance of only 0.7 cm! This "turn around" will return particles to the engine and will obviously reduce or even eliminate the thrust.

We shall assume now that neutralizing electrons are injected either into or in close proximity to the ion beam. The next question is: How intimately should the electrons and ions be mixed? Since the currents in the electron and ion beams must be equal and opposite, we can write

$$I_i = q_i v_i = -I_e = -q_e \hat{v}_e,$$

where q denotes the charge per unit length of electrons or ions and v the velocity ($\hat{v}$ represents the average velocity). If the electrons are mixed intimately so that the current *density* j in the ion and electron beams is equal, then

$$j_i = \rho_i v_i = -j_e = -\rho_e \hat{v}_e$$

(ρ denotes the charge per unit volume).

We really do not know as yet whether the neutralization must be effected on a microscopic scale, with equal values of ion and electron charge per unit volume, or merely equal charge per unit length. The choice will depend on the seriousness of possible instabilities which may be excited by less than perfect neutralization.

In any event, these equalities require in turn that the ion velocity be equal to the electron velocity. The next question to be resolved, then, is whether equality of velocity must be true on an absolute basis, with essentially all of the electrons moving with the velocity of, and in the same direction as, the ions, or whether it is sufficient to require that the average velocity of the electrons be equal to, and in the direction of, the ion motion. The latter possibility would allow the existence of double-streaming electrons, *i.e.*, electrons moving both away from and toward the engine with a net average drift velocity away from the engine. One can understand how this situation might arise by thinking of the neutralized ion beam as a "plasma bottle" [7] (see Fig. 4) with the electrons moving around inside and being reflected at the edges and at the end by an electron sheath, thus giving rise to both transverse and axial components




Fig. 4—Schematic representation of the "plasma bottle" concept of a neutralized ion beam. The plasma sheath at the end and edges and the potential "hill" at the engine end will confine the electrons to the interior of this "bottle." These reflections can give rise to a counter-streaming effect as shown. The potential in the plasma column will be uniform at a value roughly kT_e/e above the space potential.

of electron velocity. If the electrons cannot be returned from the end of the plasma column, *i.e.*, if they are forever lost from the system, then the neutralization requirement means that the electron and ion velocities must be equal on an instantaneous basis. For most reasonable values of specific impulse, the ejection velocity of the ions is considerably less than the mean thermal velocity of the electrons emitted from the thermionic emitter. Therefore, if the electron and ion velocities must be equal on an instantaneous basis, some kind of interaction mechanism must be used to reduce the mean velocity of the electrons to that of the ions. The term "mean velocity" denotes here the average over the velocity distribution of the electrons, but the electrons all have the same direction: away from the engine.

In the counter-streaming case, where the electrons are contained within a plasma bottle, we see that there are two possibilities. First, this mixture could result in a truly neutral plasma with the net volume charge density equal to zero throughout the volume of the bottle. This condition obviously satisfies all the requirements of neutralization and, if stable, forms the most ideal situation. The second possibility is that the beam is neutral on the average only, *i.e.*, there can be small volumes throughout the bottle in which the net charge is not zero, though by integrating over the entire bottle the total net charge will be equal to zero. The local fields resulting from the localized regions of nonzero charge density can give rise to instabilities and may cause the electrons either to return to the engine or to scatter transversely. In general, it is believed that this type of plasma will probably be satisfactory if the instabilities are of such a nature that they do not grow in amplitude with either time or distance.

Let us discuss the plasma bottle concept in a little more detail, with the object of showing that in this model charge neutralization can occur in either a laboratory or a space situation and under conditions where the injected axial electron velocity exceeds the ion velocity. Consider that the ejected "plasma" consists of three particle streams: 1) the outgoing ion stream of current density j_i, velocity v_i, and an electron gas with a velocity distribution which may be considered to be made up of two counter-streaming components; 2) the outgoing electron stream of current density j_e' and average stream velocity v_e'; and 3) a returning electron stream of current density j_e'' and average stream velocity v_e''. The outgoing electrons are reflected by the sheath at the end of the plasma bottle (considered, for the moment, to be of finite extent) so that the reflected electron velocity is given (under the assumption of ion mass much larger than electron mass) by

$$v_e'' = - v_e' + 2v_i, \tag{6}$$

which can be seen easily by transforming to a coordinate system moving with the end of the plasma sheath, *i.e.*, at velocity v_i.

We have assumed that the total electron and ion currents are equal. There is no loss of generality in assuming that the current densities are also equal; which must certainly be true on the average over the beam cross section. Then

$$j_i = \rho_i v_i = - (j_e' - j_e'') = - (\rho_e' v_e' - \rho_e'' v_e''). \tag{7}$$

We can define an *average* electron velocity $\hat{v}_e$ as

$$j_e' - j_e'' \equiv j_{et} = \hat{v}_e(\rho_e' + \rho_e''), \tag{8}$$

where j_{et} is the total net electron current density, which has been assumed equal to the ion current density. By combining (7) and (8), we find that

$$\hat{v}_e = - \frac{\rho_i v_i}{\rho_e' + \rho_e''} . \tag{9}$$

The condition for the ion beam to be charge neutralized is that

$$\rho_i = \rho_e' + \rho_e'', \tag{10}$$

i.e., that the net charge density be zero. Therefore, under the neutralized condition we see from (7) and (10) that

$$\hat{v}_e = v_i, \tag{11}$$

and this condition applies *independent of the velocity of the incident electrons*, v_e'. The importance of this conclusion lies in the fact that in general the ion velocity is less than the mean thermal velocity of emission of an electron from a hot cathode. Therefore, if the above conclusion were not valid, some mechanism for slowing down the injected electrons below their mean thermal velocity would be required in order to ensure that $v_e = v_i$.

In the above analysis it was not necessary to use (6); therefore, the conclusion applies not only to the steady-state space situation, where the end of the ion beam is moving away from the engine, and to the transient situation in a ground-based laboratory test during the time of transit of the ions from engine to the beam collector electrode, but also to the steady-state laboratory test, where the collector electrode is electrically

"floating" in potential so that an electron reflecting sheath exists at the collector surface. From (7), (10), and (11), we can show by using (6) that $\rho_e' = \rho_e''$, *i.e.*, that the densities of incident and reflected streams are equal in the space situation. In the laboratory floating collector case, (6) becomes $v_e' = -v_i$, and $\rho_e' = \frac{1}{2}\rho_i(1+v_i/v_e')$, $\rho_e'' = \frac{1}{2}\rho_i(1-v_i/v_e')$ [*i.e.*, the densities of incident and reflected electron streams are not equal]; the reflected density is lower because electrons are collected by the collector electrode.

As mentioned earlier, a second possible model of the neutralized ion beam (in addition to the plasma bottle with counter-streaming electrons discussed above) involves the neutralization by equality of the ion velocity and the average electron velocity with the electrons moving randomly away from the engine. This condition requires, however, that the electrons move very slowly. (In fact, if the ions and electrons have the same average directed velocity, this would correspond to the average directed velocity of electrons emitted from a cathode at a temperature of the order of 100°K, for a cesium ion beam at 2500 volts.) Even in this case, however, processes like those described for the plasma bottle model appear inescapable at the beam front and edges.

We shall now discuss briefly some of the experimental techniques which have been used to inject electrons into an ion beam and to measure the degree of neutrality of that beam. Perhaps the most sophisticated system which has been used involves the injection of electrons from both sides of an ion beam into a region constituting a potential trap for electrons [8]. This trap can be created by an arrangement of electrodes similar to that shown in Fig. 7, which creates a potential distribution as shown in Fig. 5. It is seen that this potential distribution represents the accelerator-decelerator mode of operation, in which the neutralizing system is maintained at a potential higher than that of the accelerator electrode to provide a potential "hill" that prevents electron flow into the accelerator region. In addition, the potentials on the several neutralizing electrodes are adjusted to provide a region free of axial fields, into which the electrons are injected, followed by a small




Fig. 5—Potential distribution along the axis of a cesium ion engine shown in Fig. 7; the neutralizing electrodes shown there produce the potential trap for electrons drawn here.

potential "hill" that the electrons must pass over in order to leave the trap. Electrons injected from each side of this trap region execute both transverse and longitudinal oscillatory motion and can interact with the ions. The average residence time of the electrons in the trap is quite long compared with any oscillation or collision period, and there are several mechanisms which could make the electrons random and mix them intimately with the ion beam. It is, however, rather unlikely that this interaction could lead to a truncation of the electron velocity distribution (so that it is not Maxwellian), or to some other process which would allow the electrons to emerge from the trap with an average velocity equal to the ion velocity. At any rate, the intimate mixing in the trap region results in a more uniform distribution of electrons over the cross section of the ion beam upon emergence from the engine and, in particular, results in lower transverse oscillatory energy. If this process takes place, the electrons will not execute violent lateral excursions, but will progress in an orderly one-dimensional pattern along the ion beam.

The effectiveness of the system shown in Figs. 5 and 7 in neutralizing both solid cylindrical beams and large, thin, hollow ion beams has been demonstrated by measuring the transverse spread of the beam due to space-charge forces [9]. When electrons are injected under the correct potential conditions, this transverse spread can be made zero indicating essentially no space-charge forces in the ion beam. Under these neutralized conditions, it has also been found possible to isolate the ion beam collector from the rest of the system electrically, and still to maintain the neutralized state of the beam (that is, to have the beam remain collapsed).

Somewhat simpler means of injecting electrons into an ion beam have also been used; *e.g.*, wrapping an electron-emitting filament around the outer edge of the beam, or arranging such a filament through the center of the beam. In these experiments the electron-emitting cathode was located outside the engine, *i.e.*, downstream from the point of emergence of the beam from the engine.

In a very careful series of experiments, Sellen, *et al.* [10], have applied pulse techniques to studies of the neutralization problem for beams of high aspect ratio ($R \approx 10$ to 30). By means of the pulse method which they use they have been able to study the behavior of the ion beam in the transient state before and after injection of neutralizing electrons from symmetrically arranged impregnated cathodes close to the edge of the ion beam. They found, for example, that with careful adjustment of these neutralizing emitters, in both potential and position, it is possible to neutralize a broad beam in such a way as to eliminate the turn-around effect which occurs without the electron injection (*i.e.*, without electron injection the space-charge forces cause this broad beam to turn around and return to the engine after moving only a short distance, while with neutralizing electrons the beam will move all the way to the

collector). It is possible that these experiments also involved the creation of a potential trap in the ion beam by the potential and placement of the electron emitters.

In addition to the pulsed-beam neutralization experiments described above, Eilenberg, *et al.* [11] have measured the degree of neutralization of a hollow-ring cesium ion beam by pulsing the beam and measuring the current induced in a surrounding loop by the pulse of charge passing through it. The oscilloscope traces in Fig. 6 show these induced currents. This figure shows the collector, grid, and loop (top to bottom) currents for the unneutralized beam (*i.e.*, without injection of neutralizing electrons in the engine); it is seen that current is induced in the loop as the pulse of charge approaches and departs from the loop. The grid and collector currents are very low in this unneutralized case because the space-charge spread of the beam between the engine and collector is so large that only a small part of the beam actually strikes the collector. When the beam is neutralized by injection of electrons (in a trap system of the type shown in Fig. 7) the loop current vanishes, as shown in Fig. 6 (no net charge in the beam), but the grid and collector exhibit displacement and conduction currents, respectively, as expected. Quantitative analysis of these data reveal that the beam was at least 99 per cent neutralized (*i.e.*, the imbalance in charge per unit length was less than 1 per cent) in the neutralized state. The beam could be altered from the neutralized to the unneutralized state by slight adjustments of the potential in the electron trap region.

These experiments certainly show that with proper injection of electrons in both a broad and an intermediate beam, charge neutralization is obtainable in a laboratory experiment. However, these experiments do not yet allow us to distinguish between the counterstream and the single-stream models discussed above.




Fig. 6—Schematic diagram of the pulsed beam experiment. The currents induced in the collector, grid, and ring electrode (top to bottom) are reproduced from oscilloscope traces in the insets.

It is evident from the foregoing discussion that the neutralized exhaust beam from an ion engine possesses some of the characteristics of the usual plasma. The greatest similarity results from the neutrality condition, *i.e.*, equal electron and ion densities. Also, the formation of sheaths reflecting the electrons at the edges of the plasma bottle has an analogy in the ambipolar diffusion of conventional plasmas. On the other hand, the ion beam possesses directed motion of high velocity (ion velocities typically 7×10^6 cm/second); the ions will have a longitudinal "temperature" corresponding to that of the emitter (typically 1400°K) and a transverse temperature several times this value (because of the beam compression in the accelerator). Measurement of the electron velocity distribution [12] has shown it to be approximately Maxwellian with a temperature in excess of 10,000°K, and electrons have been detected moving in the "reverse" direction, *i.e.*, from collector to engine. Thus, the ion engine system has provided us with a rather novel form of plasma, a highly energetic or directed nonthermalized plasma, which should find application in other areas of electronics and physics.

B. Cesium Ion Engine

A simplified schematic diagram of a typical cesium ion engine is shown in Fig. 7. At the left we see the propellant heating and storage system, where cesium, the propellant, is converted into a vapor and caused to flow up to and through the ionizer. At the surface of the ionizer, the cesium atoms are converted into cesium ions. These positive ions are accelerated by means of an electric field in the accelerator region and then ejected through the neutralizer region as shown. The space-charge fields of the ejected ions must be neutralized; otherwise these fields give rise to image charges on the vehicle which retard the ions, thereby diminishing or possibly eliminating completely the thrust of the engine. In order to neutralize this ion beam space charge, we must inject negative particles, *e.g.*, electrons, into the beam. A practical system for accomplishing this electron injection is also shown in Fig. 7. In this system, electrons are injected from a cathode surrounding the ion beam and are mixed with the ions in the electron trap created by the electrodes shown.

The electrode system marked "neutralizer region" in Fig. 7 serves two functions: 1) The shapes and potential differences of the electrodes have been designed so as to achieve most efficiently the injection of electrons for neutralization. 2) The electrodes are held at an average potential well above the accelerator in order to decelerate the ion beam. Essentially all modern cesium ion engines operate in this so-called accel-decel mode. In this mode, the final exhaust of the propellant takes

place at or near the potential V_f corresponding to the final or decelerator electrode, but between this electrode and the ionizer the accelerator electrode is arranged at potential V_a. The fraction V_a/V_f is called the accel-decel ratio; typical values are approximately 2 to 10. This system will produce a potential distribution along the beam similar to that illustrated in Fig. 5. The principal reason for operation in this mode is that the potential hill between the decelerator and accelerator electrodes prevents electrons in the ion beam from being attracted into the accelerator region and thereby bombarding the ionizer, which would result in subsequent power loss and possible overheating.

Let us discuss now some of the considerations entering into the design of the accelerator system of such a cesium ion engine, starting from the basic requirement that the engine produce a certain value of thrust with a specified value of specific impulse. These two parameters, thrust and specific impulse, are usually chosen as criteria in specifying the performance of the rocket, for the reason that mission analyses show that the flight time for a given mission is dependent almost entirely on the thrust level, whereas the mass which can be carried, *i.e.*, the payload, is dependent almost entirely on the specific impulse. Let us accept thrust level and specific impulse as the fundamental parameters and work out the "paper" design of an accelerator system. The total ion current I_i needed to produce the desired thrust can be expressed in terms of this thrust level and the specific impulse value from (1) and (3), as follows:

$$I_i = \dot{n}_p e = \frac{\dot{m}_p}{m_i} e = \frac{T}{I_s} \frac{e}{m_i g}$$

$$= 32.8 \times 10^4 \frac{T(\text{lb})}{I_s(\text{sec})} \text{ amperes (for cesium)}, \quad (12)$$

where $\dot{n}_p$ represents the number of ions of mass m_i ejected per second.




Fig. 7—Schematic diagram showing the various components of an ion engine. The complex shape of the accelerator electrodes provides close control of the ion trajectories to avoid electrode impingement and erosion. The electrode system in the neutralizer region provides the potential distribution necessary to allow the neutralizing electrons to enter the ion beam and to leave the engine along with the ions.

It is convenient to express the geometrical structure of the accelerator of the engine in terms of a parameter called the perveance, which is defined as the total ion beam current divided by the three-halves power of the accelerator voltage:

$$P_i = I_i / V_a^{3/2}.$$

The expressions for the perveance of structures possessing planar, cylindrical, or spherical symmetry can be easily derived from the corresponding Child-Langmuir equations [13] for space-charge-limited emission in these geometrical forms. From these equations, the emitter current density J_i is given by

$$J_i = \frac{4}{9} \epsilon_0 \sqrt{\frac{2e}{m}} V_a^{3/2} \delta$$

$$= 2.335 \times 10^{-6} \sqrt{\frac{m_e}{m_i}} V_a^{3/2} \delta, \quad (13)$$

where m_i/m_e represents the ratio of mass of the appropriate ion to the electron; for example, for cesium $m_i/m_e = 1837 \times 134 = 246{,}000$. Thus, the current density of cesium ions is about 500 times less (for a given accelerator electrode potential V_a and given geometrical structure) than that for the electrons. δ is a geometrical factor and can be written.

$$\delta = \frac{1}{d^2} \quad \text{for planar structures,} \quad (14a)$$

$$\delta = \frac{1}{r_a r_e \beta^2} \quad \text{for concentric cylinders,} \quad (14b)$$

$$\delta = \frac{1}{4\pi \bar{r}_e^2 \alpha^2} \quad \text{for concentric spheres,} \quad (14c)$$

where d is the distance between emitter and accelerating electrode, r_a and r_e are the radii (cylindrical) of the accelerator electrode and emitter, respectively, and $\bar{r}_e$ is the radius (measured from the center of curvature of the sphere) of the emitter. α and β are functions of the radius ratio tabulated by Langmuir [14].

It is sometimes convenient to refer the ion perveance P_i to an equivalent electron perveance P_e. This latter value is obtained by multiplying the ion perveance by the square root of the ratio of ion mass to electron mass, as follows:

$$P_e = P_i \sqrt{\frac{m_i}{m_e}} = 493 P_i \text{ (for cesium)}. \quad (15)$$

The cesium-type electrostatic ion engine is very similar in concept and design to electron guns used in microwave tubes, and the considerable body of knowledge which has been accumulated in past years on this subject can be applied directly to these engines. The perveance parameter P is useful because it is a function of only the geometrical configuration of the accelerator

structure, *i.e.*, it is related to the total area divided by some function of the distance from the accelerating electrode to the emitter.

The total ionizer area needed to supply the beam current I_i is then given [from (12)] by

$$A_i = \frac{I_i}{J_i} = 32.8 \times 10^4 \frac{T}{I_s J_i} \text{ cm}^2 \text{ (for cesium)}, \quad (16)$$

where J_i represents the ionizer current density (in amp/cm² of ionizer) which is assumed in the design. The final or decelerator potential V_f, which will produce the propellant exhaust velocity corresponding to the specified specific impulse, is

$$V_f = \frac{1}{2}\frac{m_i}{e} v_p^2 = \frac{1}{2}\frac{m_i}{e}(I_s g)^2$$

$$= 6.65 \times 10^{-5} I_s^2 \text{ volts}. \quad (17)$$

Let us discuss for a moment a simple planar engine consisting of the accelerator region only (no decelerator). With the above equations we can show, perhaps a little more clearly, the source of the thrust obtainable from an electrostatic propulsion engine. The thrust obtainable from an ion engine per unit of ionizer area may be considered in terms of a unit called the specific thrust T_s. From (1) and (12), for this simple engine,

$$T_s \equiv \frac{T}{A_i} = \frac{m_i v_p I_i}{e A_i} = \frac{m_i}{e}\sqrt{2\frac{e}{m_i} V_a}\, J_e. \quad (18)$$

The current density J_e can be obtained from (13) and (14a), from which (18) becomes

$$T_s = \frac{8}{9}\epsilon_0 \left(\frac{V_a}{d}\right)^2. \quad (19)$$

The electric field at the anode of a space-charge-limited planar diode can be shown to be $E_a = (4/3)(V_a/d)$. Thus, we can write (19) as

$$T_s = \tfrac{1}{2}\epsilon_0 E_a^2. \quad (20)$$

The reader will recognize that this equation represents the stress transmitted across a unit area of surface at which the electric field has the value E_a. In this simple idealized example, we are considering a plane-parallel electrode system of unit area in which a space-charge-limited current flows. This current flows through the anode plane, which is permeable to the charged particles. The electric field at this anode plane produces a stress or force which accelerates the particles outward from the engine; this force (or thrust) may be thought of as "pushing" the engine in the opposite direction to the motion of the propellant particles. The purpose of the neutralization system is to prevent the existence of any longitudinal components of electric field *outside* the engine, since these would act in the opposite direction, pulling the ions back to the engine and so reducing the thrust.

In the design of an ion propulsion engine, we have seen that analysis of the intended mission provides information on the desired values of specific impulse and thrust. We have seen also that these numbers are sufficient to determine the total current, the mass flow rate, and the potential difference between the emitter and the final or decelerator electrode, and therefore to determine also the total power which must be used to accelerate the ion beam. A knowledge of ionizer characteristics allows us to choose an acceptable value of emitter current density, from which the total emitter area can be determined. There are several geometrical forms in which the ionizer, and therefore the entire engine, can be arranged to produce this required area: 1) a planar structure with grids across the accelerator aperture, 2) an array of small solid-beam accelerators with an open accelerator aperture (Fig. 8), 3) an accelerator to produce a long narrow strip beam, and 4) a structure producing a thin hollow-ring beam (Fig. 9). The gridded design, form 1), is very susceptible to electrode erosion, since in this design it is difficult to control the optical characteristics in such a way as to prevent interception in the accelerating electrodes, which, in addition, are relatively weak structurally. The linear strip system, form 2), is difficult to maintain in accurate




Fig. 8—Schematic drawing of a multiple-solid-beam ion engine.




Fig. 9—Artist's cutaway sketch of a cylindrical hollow-ring ion engine with neutralizer system similar to that shown in Fig. 7 and with a laboratory-type axial feed system (Hughes Aircraft Company).

alignment. Therefore, the hollow-ring system and the multiplicity of solid-beams system, each of which possess certain advantages and disadvantages, are the two in most common use today. The hollow-ring geometry is simply the strip beam bent around into a circle, but this arrangement allows the electrode alignment to be maintained accurately, and the beam can be neutralized in detail by the electron injection and trapping system shown in Fig. 9 (which is similar to that in Fig. 7).

Let us now turn to two of the more detailed but important problem areas in the cesium ion engine: the ionizer and the ion trajectory problem.

The process of converting the cesium atoms to ions is one of the interesting physics problems associated with the ion engine. For purposes of this discussion we can show one practical way of accomplishing this ionization process (see Fig. 10). The cesium atoms are fed from behind a porous tungsten pellet; they migrate along the walls of the very thin capillary tubes between the grains of tungsten and emerge on the top surface, from which they are emitted predominantly as ions. This process of contact ionization of alkali metals on hot tungsten has been studied in great detail by Taylor and Langmuir [15]; the valence electrons of the low-ionization-potential alkali metals remain with the higher-work-function tungsten surface as the particle is evaporated from this surface. Thus, the current-voltage characteristics appear as in Fig. 11 [16], where they are seen to be similar to the saturation characteristics of an electron emitter. Below the level of maximum space-charge-limited emission, the cesium supply is excessive and many particles evaporate as neutrals; above this level all of the ions which the surface is capable of supplying can be drawn off so that the neutral efflux is low. For proper control of the optical properties of the accelerator, the source should be operated space-charge limited; thus the optimum point of operation is at the "knee" of the curves in this figure.

Although cesium has many undesirable properties, it is usually chosen as the propellant chiefly because it is the most easily and effectively ionized on those atoms with a mass that ensures an optimum specific impulse or propellant velocity at reasonable values of voltage. Other propellant materials are being investigated and may eventually replace cesium, but cesium will be used in almost all of the first-generation ion engines.

Another very serious problem in ion engines is the erosion of the accelerating electrode that can result from bombardment by high-velocity cesium ions. Sputtering studies have shown that as many as ten atoms of the engine electrodes can be eroded away by the impact of one cesium ion. This electrode erosion may ruin the operation of the engine over the long periods (*e.g.*, one year to Mars) for which an ion engine must be operated. For satisfactory long-time operation, therefore, it appears that a maximum of about one ion can be allowed to strike the accelerating electrode for each 100,000 ions which leave the ionizer. The ions which do impinge on the electrodes can arise from any of several defects and phenomena in the ion engine; the principal cause is incorrect design of the ion-optical characteristics of the accelerator structure. It is therefore extremely important to be able to control very accurately the trajectories of the accelerated ions so that they flow in a uniform and "laminar" manner through the accelerator and neutralizer regions of the "gun." This process is somewhat analogous to the problem of designing optical lenses that will produce images free of aberrations. Such close control of the ion-optical design of the accelerator structure makes use of techniques which were found essential in the design of high-current-density electron guns for beam-type microwave tubes.

Perhaps the most significant advance in the design of electron guns, including the effects of space charge, was




Fig. 10—A simplified diagram of a porous tungsten contact ionizer for cesium. The cesium atoms diffuse through the hot (1150°C) tungsten and migrate onto the surface. Under proper conditions, the evaporation from this surface consists predominantly of ions with a few neutral cesium atoms.




Fig. 11—Porous-tungsten cesium ion emitter characteristics as a function of accelerating voltage. The solid lines show the ion current for several values of cesium flow rates (or cesium vapor pressure), and the dashed lines show the evaporation rate of neutral cesium particles. (Data courtesy of Dr. Otto Husmann.)

made by Pierce [17]. Although the Pierce design technique has proved extremely useful and has formed the basis for the design of many guns over the past ten years or so, it suffers from a fundamental limitation when applied to the design of those high-perveance guns which do not have a grid across the accelerator electrode aperture. That is, the ideal Pierce gun can be divided into two regions: 1) the region of rectilinear electron flow, in which the potential is given by the Langmuir relations for space-charge-limited flow for the geometry used, and a unipotential electrode is designed to effect the proper electrical boundary conditions at the beam edge, and 2) a thin electric aperture lens in the vicinity of the anode. When this method of analysis and design is used, it is assumed that trajectories in the two regions can be joined smoothly and that no appreciable distortion of the ideally shaped electric fields exists away from the immediate vicinity of the anode aperture. Since higher perveance guns do exhibit a considerable distortion of electric field due to the aperture in the accelerating electrode, this simple design criterion must be modified somewhat. Modified techniques of design of high perveance electron guns [18], including the use of an automatic ion trajectory tracer with space-charge simulation, have been found to be similarly successful in the design of ion accelerators. For example, by the use of these proven design techniques, ion guns have been built which exhibit laminar beam flow and electrode interception values of 10^{-4}–10^{-5} or less of the emitted current, values which are lower by orders of magnitude than those observed in engines designed by less careful techniques, and which are good enough now for a long mission. These excellent optical characteristics must of course be obtained consistent with uniform emitter current density.

A second cause of ion interception on the engine electrodes can arise from ions which deviate from their laminar or design trajectories as a result of emission from the ionizer with a transverse component of velocity. This transverse thermal spreading is a rapidly decreasing function of acclerator potential, and with correct design of the accelerator electrode aperture, it can be made negligible at usual operating voltages.

A third cause of ion interception results from ions created in the flow region of the accelerator and decelerator by charge-exchange reaction between the cesium atoms in this region and the moving ions. Since the accelerator structure is usually designed so as to control the trajectories of ions originating at the ionizer, those charge-exchange ions created elsewhere in the flow region can be accelerated so that they impinge on the engine structure, thus producing erosion. There are at least two ways of controlling this process: 1) reducing the atom density in the flow region by decreasing the neutral efflux from the ionizer, and 2) performing additional design studies (*e.g.*, on a trajectory tracer) on the engine so as to deflect the charge-exchange ions from the electrodes.

The process of cesium ionization by contact with hot tungsten provides one of the principal advantages of the cesium ion type of electrostatic propulsion engine, in that the ionization is effected at a well-defined and carefully shaped equipotential surface. This emitter surface can form the basis for accurate design of the ion-optical characteristics of the accelerator in much the same way as a space-charge-limited electron cathode forms the basis for design of Pierce-type electron guns.

The cesium ion engine is seen to be amenable to accurate design, based on both analytical and carefully controlled experimental techniques, which yields very predicatable engine performance. These engines are capable of supplying ion beams of attractive densities (particle densities of the order of 10^{11} ions/cm^3 and current densities of 20 to 80 ma/cm^2 in the exhaust beam). These ion beams have been successfully neutralized (at least as far as laboratory tests can determine).

As shown in Fig. 12, the cesium ion engine can be made to be quite efficient. The principal energy loss is in the form of power required to heat the ionizer to the necessary emitting temperature. Some additional power is required to heat the neutralizer filament and the cesium boiler, but, for reasons mentioned before, no power dissipation due to current interception on the electrodes is tolerable. Fig. 12 shows the efficiency (power into the beam to produce thrust divided by the total input power) as a function of specific impulse of the exhaust beam. This curve is derived from calculations based on experimental data on operating engines and other sources. It is seen that efficiency values in excess of 80 per cent are possible for specific impulses of interest for space missions.

Cesium ion engines of the type shown in Figs. 8 and 9 have been built and are undergoing extensive laboratory development and evaluations [19], [20]. Progress in cesium ion engines has been very rapid in the past year: feasibility has been demonstrated, neutralization has been successfully accomplished in a laboratory environment, erosion has been reduced to the point where lifetime appears long enough for space missions, etc. The cesium ion engine therefore appears to be an ef-




Fig. 12—Power efficiency of a cesium ion engine vs specific impulse for a value of ionizer current density equal to 20 ma/cm^2. These data were calculated from measured data of current density vs ionizer temperature and of ionizer heating power requirements. The power input includes that required to heat the neutralizer emitter.

ficient, practical, and effective device for the propulsion of space vehicles, an engine around which plans can now be made for future space exploration. These engines have been built so far to produce thrust levels of several millipounds, but larger thrust unit engines appear quite feasible, and such engines can be clustered for even higher thrust levels, *e.g.*, 1.5-pound thrust for a 300-kw system or even 10-pound thrust for a 2-Mw system. These engines can also be built efficiently at the micropound thrust level for propulsion of lightweight scientific packages out of the plane of the ecliptic. Engines such as those shown in Figs. 9 and 14 are currently being developed [21] for use in the first space test of an electrical propulsion engine in late 1962.

C. Penning Discharge Ion Engines

A second important class of ion engines employs a fundamentally different type of ion source in which the propellant gas is ionized by electron bombardment. Since for any reasonable geometries and particle densities the mean free path for ionization (of the order of meters) is much larger than the dimensions of the ionization chamber, it is evident that the efficiency of such a source depends upon increasing the mean lifetime of the primary electrons. Such an increase can be accomplished by the use of Penning-type discharges in which magnetic and electric fields are arranged so as to trap the electrons and thus increase the ionization probability. Such sources have been found to have good power efficiency (in terms of energy expended per ion produced) and relatively high propellant utilization efficiency, together with the other obvious advantages of mechanical simplicity and ability to use a number of different types of propellant gases. The major problem concerns the design of high-quality ion optical systems for low electrode interception, and hence for long life.

The most advanced engine of this type utilizes a configuration proposed by Kaufman [22]; it is shown schematically in Fig. 13. The ionization chamber is composed of a cylinder with the neutral propellant gas introduced at one end and the ions extracted at the other. The center portion of the cylinder (*i.e.*, the anode for the discharge) is maintained at a positive potential with respect to the ends of the cylinder, thus providing electron trapping in the longitudinal direction. Electrons are emitted from a filament located on the axis. The longitudinal magnetic field prevents the electrons from reaching the anode directly; in the crossed electric and magnetic fields, they tend to spiral around the axis, thus increasing their mean lifetime and the probability of making an ionizing collision. A plasma is formed which fills the discharge chamber out to the screen; ions are extracted from this plasma boundary by an array of accelerating electrodes.




Fig. 13—Schematic illustration of the type of Penning-discharge ion engine proposed by Kaufman [22].

The energy range of interest for the primary electrons is dependent upon the ionization potentials of the propellant gas. To date, only mercury vapor has been utilized extensively in this type of ion engine. The ionization cross sections for single and double ionization of mercury have broad maxima at roughly 50 and 100 volts, respectively. Consequently, the energy range of interest for production of singly-charged ions is from about 30 to 70 ev. It should be noted, however, that the threshold potential for removal of a second electron from a singly-ionized mercury atom is 29.4 volts [23]. Although no data seem to be available on the cross section for this process, it might be expected that it would have a maximum somewhat below 100 ev; therefore, caution must, in general, be exercised in interpreting performance data and in adjusting conditions so that the ratio of doubly- to singly-charged ions is kept very small.

The low-velocity electrons in the plasma have been estimated [22] to have a temperature corresponding to about 5 ev for the case of mercury with an axial plasma resistivity of less than 0.01 ohm-cm.

Optimum magnetic field strength is dictated by a compromise between ionization efficiency and plasma resistivity in the radial direction. A strong magnetic field is evidently necessary in order to obtain high ionization efficiency. On the other hand, if the magnetic field is too high, the plasma resistivity in the radial direction is increased, thus resulting in heating losses, increased diffusion losses of low-velocity electrons, and a radial inflow of ions. A radial inflow of ions leads to nonuniform ion current density through the accelerator system and results in deteriorated optics and increased electrode erosion. Optimum magnetic fields of the order of a few tens of gauss have been found in the experimental engine configurations studied thus far.

When the electron mean free path $\bar{l}$ is much greater than the cyclotron radius r_c the plasma resistivity in the radial direction is increased by a factor proportional to $(\bar{l}/r_c)^2$. From this, the functional dependence of the radial potential difference can be simply calculated [22] to be

$$\Delta V_{\text{rad}} \sim \frac{j\sqrt{T_e}}{L r_c^2 n_-^2 \sigma_{\text{eff}}}, \tag{21}$$

where L is the length of the ionization chamber, j is the discharge current, T_e the effective electron temperature, n_- the electron density and σ_{eff} the total effective collision cross section. This relationship has been used to guide scaling studies on this type of source. However, it is evident that much more work is required before an adequate theoretical understanding of this type of ion source is attained; this may constitute a fruitful field for further research.

Fig. 14 pictures a typical engine configuration based on these concepts. Such units have been investigated and developed by the NASA Lewis Research Center. Typical performance of a 10-cm source operating at a specific impulse of 5500 seconds with mercury as the propellant has been given as follows [24]: An ion beam of 130 ma was obtained with a magnetic field of the order of 20 gauss; a discharge in the ionization chamber of 1.7 amperes at 50 volts, and a net acceleration voltage of 3000 volts. This corresponds to an average beam current density over the beam cross section of about 1.6 ma/cm², or of the order of several ma/cm² in the screen apertures. Current densities in this range appear to be typical for this type of source. The over-all power efficiency under these conditions was about 70 per cent, including filament power, magnet power, and power lost due to electrode interception. A measure of ionization efficiency is the cost in energy of producing one ion, which in this case was about 700 ev/ion. Propellant-utilization efficiency was about 80 per cent. The thrust corresponding to these numbers would be of the order of 3 millipounds.

Various studies of geometry and effects of magnetic field have been made. For example, ionization efficiency depends upon the manner in which the propellant gas is introduced; best results have been obtained when it is injected through the distributor on the axis where the density of high-velocity ionizing electrons is highest. It has been observed that grid erosion near the axis is greater than that near the periphery indicating a similar variation of ion beam current density due, at least in part, to the radial potential difference previously discussed.

A scaling study was carried out [25] with beam sources 5, 10, and 20 cm in diameter, designed for constant current densities in the extracted beams and otherwise identical in proportions. Some typical data are indicated in Fig. 15, where energy per ion is plotted as a function of magnetic field for the three sources. Here the ion-chamber potential difference was 50 volts, which was approximately optimum in the three cases; the specific impulse was held constant at 7000 seconds (4900 volts) as well as beam current density. It is seen that roughly the same performance is achieved for the larger sources. This similarity is more striking if plotted as a function of the product of magnetic field and diameter (*e.g.*, curves reach a minimum at 16 and 32 gauss for the 20- and 10-cm sources, respectively). The efficiency of the smaller source was, however, quite poor. Note from (21) that for a cyclotron radius proportional to diameter D (in this case at 64 gauss), with $L \sim D$, T_e and σ_{eff} constant, and $j \sim j_0 D^2$, where j_0 is the beam current density and $n_- \sim j_0$, we find that

$$\Delta V_{\text{rad}} \sim (Dj_0)^{-1}. \tag{22}$$

Thus, at small diameters, the radial potential difference increases, reaching a point where much of the power goes into heating of the plasma. It has also been verified that with increased current density j_0 the ionization efficiency goes up.

Fig. 16 shows a curve of expected power efficiency as a function of specific impulse for this type of engine.




Fig. 14—Artist's cutaway drawing of the electron-bombardment engine being investigated at the NASA Lewis Research Center.




Fig. 15—Results of scaling experiments [25] showing the ionization efficiency (energy per beam ion) as a function of magnetic field, for Penning-discharge engines of three different diameters.




Fig. 16—Power efficiency as a function of specific impulse for Penning-discharge engines of the type being studied at NASA Lewis Research Center. Performance close to that shown has been demonstrated in several laboratory tests.

Some of these relatively high efficiencies have already been obtained on experimental engines, indicating the promise of this approach.

An area for intensive investigation in the development of the Penning-discharge source for long life is the ion optics system. In fact, it poses a challenging problem: the study of the boundary condition for injection of ion trajectories into the electrode system. It is evident that the shape of the plasma boundary or sheath can be varied over a wide range (indicated in Fig. 17) by the potential and shape of the extraction electrode. Thus, geometry and potential configuration must be adjusted to achieve high-perveance laminar optics and, at the same time, to maintain optimum plasma boundary shape. Interception on the acceleration electrode of the engines discussed above has been of the order of 1 per cent, which can no doubt be improved considerably by systematic study of this interesting optics problem.

No special neutralization mechanisms have been developed for the Penning engine. This opens, therefore, an area for further study, as was carried out in the case of the cesium engine. Neutralization has been accomplished in the laboratory testing of these engines simply by electrons from a hot filament stretched across the beam, as well as by trapping secondary electrons from the electrodes and beam collector over the length of the beam. Because of heavy sputtering, an array of filaments stretched across the ion beam is not attractive for practical space applications.

As previously mentioned, all the results to date have been obtained with mercury as the propellant. The study of other types of gases seems to offer possible further gains in efficiency, current density, etc. We direct particular attention to the use of cesium. Although it is not generally true that higher ionization efficiencies can be obtained for lower ionization potentials, data [23] show that the ionization efficiency (in terms of ion pairs per cm mm Hg at 1 mm Hg) is the same, within a factor of two, as that for mercury, with the peak occurring at less than 20 ev for primary electrons as compared with about 50 to 70 ev for mercury. In addition, the ionization potential leading to doubly-ionized cesium is 36.9 volts with a first ionization potential of 3.9 volts, compared with the respective figures of 29.4 volts and 10.4 volts for mercury [23]. Thus, it would appear that there might be a much greater and more favorable range of discharge voltage over which conditions could be adjusted for higher efficiency without establishing production of doubly-ionized cesium. Besides higher efficiency, we might hope that a denser, lower-temperature plasma would result, thus leading to higher ion current density and improved optics. Also, the lower discharge voltage with cesium could reduce or suppress the problem of sputtering of the hot electron-emitting filament.

Another kind of ion source which utilizes a Penning- or PIG-type discharge is the so-called grid-type ion source used at the Oak Ridge National Laboratory in separating stable isotopes and in controlled fusion research. This type of source is shown schematically in Fig. 18. Here the ion beam is extracted normal to the direction of the magnetic field which constricts the discharge. Although high ($\sim$100 ma/cm^2) current densities are obtained at typical acceleration potentials of the order of 25 kv, this configuration has not been applied to the range of parameters of interest for propulsion purposes. Luce [26], however, has conducted some electrode erosion studies using this source and has discussed its application to ion engines.

D. The Duoplasmatron-Type Ion Engine

A third major class of sources which is being extensively investigated and developed for the electrostatic acceleration of dense ion beams is based on the so-called Duoplasmatron concept of Von Ardenne [27]. As in the Penning-type source, ionization is achieved by electron bombardment and the ion beam is extracted from a plasma. Of all such bombardment sources, the Duoplasmatron is capable of producing the highest ion current densities. Densities two or three orders of magnitude greater than those attained by means of contact ionization *i.e.*, of the order of amperes or even tens of amperes per cm^2, are possible (although they have not




Fig. 17—Illustration showing how the shape of the plasma boundary or sheath can vary as the field configuration in the accelerating region changes. The interesting problem is posed of suitably shaping the plasma meniscus so as to "match" the plasma system optimally to an ion optical system.




Fig. 18—Schematic drawing of the grid-type Penning-discharge source developed at the Oak Ridge National Laboratory [26].

yet been achieved in well-focused beams). This characteristic, together with an inherently high ionization efficiency and the prospects for eventually reaching high power efficiencies, makes this class of sources of considerable interest for development as part of an ion thrust system for propulsion. Although major problems exist in reducing electrode erosion, increasing emission area, and controlling and focusing the output beam, it is believed that these may not constitute fundamental limitations and that, with intensive and imaginative effort, the inherent promise of the Duoplasmatron-type ion engine may eventually be realized. It should be noted that such development may also have great importance to other areas of plasma research and application (*e.g.*, injection sources for controlled fusion experiments, or linear accelerators).

Fig. 19 illustrates the basic Duoplasmatron configuration. A low-pressure arc is produced between a filament (or thermionic cathode) and the anode, which typically operates in a potential range from somewhat above the ionization potential of the working gas to about 100 volts. An "intermediate electrode," conical in shape and held either at an intermediate potential or sometimes floating, serves to constrict the discharge and increase the plasma density. This is the form originally suggested by Von Ardenne in 1946 for use as an ion source for experiments in isotope separation. The addition of a high (essentially axial) magnetic field between the tip of the baffle and the anode (Von Ardenne [27]) acts to constrain the discharge further. These dual constraints—mechanical and magnetic—produce a very dense plasma in the extraction orifice. Since neutral particles have to pass through this cloud of hot dense plasma to escape from the source, the propellant-utilization efficiency can be high. A very dense ion beam is obtained from the plasma by means of large negative potential (typically 10 to 60 kv) applied to the extractor electrode.

The complex geometry of the Duoplasmatron makes exact analysis of its operation impossible. However, the basic mechanisms which determine its characteristics can be discussed qualitatively, and can serve as a guide in its development. The arc inside the source has the typical characteristics of a low-pressure discharge in which the electron mean free path is of the same order as the discharge length. A positive sheath close to the cathode supports a potential difference approximately equal to the ionization potential of the working gas. Following this cathode drop there exists a region of small potential gradient which contains an essentially neutral plasma; here, ionization as well as randomizing elastic collisions occur. The pressure in the arc region is typically of the order of ten to several hundred microns.

In such a discharge *per se* the plasma density would not normally be sufficiently great to permit extraction of large ion currents. As mentioned previously, this is accomplished through the use of magnetic and mechanical constraints. The magnetic field has two functions: first, it gives rise to electron reflection (Penning-discharge effect), and second, it exerts a magnetic confining effect on the arc which serves to constrict it and to reduce radial diffusion losses. Both effects increase the plasma density.

Fig. 20 indicates schematically a typical magnetic field configuration in the neighborhood of the baffle canal and the anode [28]. The magnetic field, usually of the order of several kilogauss, is highly convergent in this region. In fact, it can be regarded as a magnetic mirror configuration [29] in which electrons entering with an initial transverse velocity component can be reflected. It should be noted that because of the geometry there must exist a region of crossed E and B fields which gives rise to transverse velocities and thus cycloidal motions which emphasize this effect. Total reflection can occur for a large part of the incident electron current.

The electrons that are trapped by the magnetic field and reflected along their original path can be reflected again by the original electric field existing in the arc discharge, thus giving rise to electron trapping similar to that present in the Penning discharge. Such trapping may last until collisions or field inhomogenieties allow




Fig. 19—Basic Duoplasmatron configuration.




Fig. 20—Magnetic field configuration in the neighborhood of the baffle canal and anode of a Duoplasmatron ion source. The converging magnetic field constitutes a magnetic "mirror" for reflection of electrons. It also constricts the discharge and reduces radial diffusion losses.

the electrons to reach the anode. The probability of ionization by the primary electrons is increased by increasing their effective lifetime, which, combined with a decreased rate of radial electron diffusion, leads to higher ionization density and power efficiency. High-energy axial electrons which penetrate the mirror region can be reflected back into the plasma by the negative extractor potential.

It is evident that the magnetic field can also exert a confining effect on the plasma which guides it through the baffle and extraction orifice and reduces the effective plasma boundary surface area and diffusion losses. The current density in the baffle canal is greater than that on either side of the baffle; most of the current passing through the baffle consists of electrons. The potential gradient which supports this current is sustained by a positive space charge in the anode side of the canal and a corresponding negative space charge on the cathode side [30]. As the canal length is increased, the tendency toward neutrality in this region becomes larger. Various estimates place the electron temperature in the baffle region of the order of 10^5°K, with somewhat lower temperatures ($\sim 10^4$°K) in the extraction region. The ion temperature was estimated by Von Ardenne [27] at several times 10^3°K.

The discussion thus far has considered the Duoplasmatron only as a high-density ion source per se, with the potential of high propellant utilization and power efficiency. Its ultimate success as an ion engine configuration will depend in large measure on the development of high-quality ion optical systems which are compatible with practical ranges of specific impulse (5000 to 15,000 seconds) and with very low electrode erosion rates, which is also true of other types of sources. There are, in addition, a number of practical engineering problems relating to cooling, efficient magnetic circuits, and weight reduction. Most of the research effort to date has been concerned with understanding the basic mechanisms in order to improve the efficiency of the Duoplasmatron as an ion source. A great deal of additional effort must be directed toward solving these other problems before its full potentiality as an ion engine can be realized.

Although the ion-beam extraction process is space-charge limited, measurements often show significant deviations from a 3/2 power dependence of current on extraction voltage. In addition to the possibility of partial neutralization of the positive space charge by trapped electrons in the extraction region, it is evident that the shape of the plasma boundary from which positive ions are extracted is a sensitive function of the potential distribution, geometry, and magnetic field configuration in the region of the extraction orifice. Indeed, the plasma meniscus can be given almost any desired shape by appropriate adjustment of these conditions [31]; it can be made either convex or concave, and can have widely differing surface areas.

A very interesting problem in the Duoplasmatron, as in the Penning-type engine, is that of suitably shaping the plasma meniscus so that the plasma system can be "matched" to an ion optical system. Not only does the meniscus shape constitute the initial boundary condition for the analytical design of optimum optics, but also it influences the over-all operation in a more subtle way. For example, the exact shape of the plasma bubble which is formed at the extraction orifice by the combination of electric and magnetic fields and geometry has a pronounced effect on propellant efficiency. High propellant efficiency is, of course, important in itself; but it is also critical in reducing erosion. Neutrals which leak out of the plasma complicate seriously the problem of beam formation and electrode erosion because of charge exchange with energetic ions.

In the specific impulse range of interest, the cross section for charge exchange of the positive ion is at least two orders of magnitude larger than that for other reactions with neutrals present in the acceleration region. In the high-density beams produced by this type of source, this constitutes a major prblem. Even with refined optics, ions generated by charge exchange with the neutral efflux will bombard the extractor electrodes and release new neutrals due to sputtering. The resulting erosion of material can be serious. More fundamental data on sputtering as a function of electrode material, ion energy, and atomic weight of the ions are required in reaching practical solutions to the problem of long engine life.

Only the axially symmetric pinhole-type source has been considered here. It is evident that these ideas can be extended to rectangular and annular slit configurations so that total current can be increased, and several laboratories are pursuing these approaches. Also, some major modifications of Von Ardenne's original work hold considerable promise; these involve extending the magnetic field into the cathode region itself and varying the cathode, anode, and extraction orifice locations and geometries.

In short, the promise of this general kind of source for ion propulsion, as well as other applications, makes it a fruitful area for research, invention, and development. Energy expenditures as low as 450 ev/ion and propellant efficiencies of the order of 90 per cent have been demonstrated. Although the high-current-density capabilities have not been realized simultaneously with reasonably good optics, the practical current densities achieved to date are still higher than those obtained with other sources. It is expected that the space-charge-neutralization techniques developed in connection with the cesium ion engines may also be applied in this case.

E. Oscillating Electron Engines

1) Basic Principle: All the engines of the class which we shall call "oscillating electron engines" have in common the presence of high-energy axially oscillating electrons. A number of them have in common other features which in many respects may be regarded as dual to

those of the ion engines described above. It seems appropriate to begin the discussion of this class of engine with an idealized model, in order to emphasize their common features. After analysis of this model, a detailed description of actual engines from a more unified view will be possible.

The principle of the oscillating electron engine in its idealized form is shown in Fig. 21. Electrons emitted from a cathode are accelerated electrostatically and focused into a beam in region I. They are slightly decelerated in region II, and are made to pass through region III in an axial stream. Ions which neutralize the electron space charge are then injected into region III. The potential maximum to the left of region III prevents the flow of ions from region III to the cathode. In region IV a potential gradient is caused in the plasma; it reflects those electrons which do not have a sufficient energy to pass the potential barrier, and accelerates the ions. Most of the reflected electrons will then be reflected again by the cathode and oscillate back and forth between the cathode and region IV until they are ultimately collected in region II or III by one of the positive electrodes. The accelerated ions are ejected axially to the right of region IV with an energy approximately corresponding to the potential difference between the cathode and region III. Also, those electrons which are energetic enough to pass the potential ΔV will escape, together with the ions; in fact, the potential ΔV must be adjusted to just such a value that the number of electrons escaping from region IV will be equal to the number required for neutralization of the ejected ion beam. From there on, the processes of neutralization of the energetic plasma beam ejected from region IV are the same as those described for the ion engine.

The possible existence of a potential gradient of finite axial extent in a plasma beam was first pointed out by Rose [32] and Saltz, *et al.* [33]. Qualitatively, if an electron-velocity distribution of finite width exists, the existence of a potential gradient in a neutral or near-neutral plasma can be understood as follows: As the potential decreases in axial direction, part of the electrons are reflected; this diminishes the electron density. This same potential decrease accelerates the ions, and hence the ion density decreases. By maintaining the proper balance between the two mechanisms, it is possible to keep electron and ion density equal or nearly equal; the difference between both densities is then just sufficient to make up the space-charge contribution to the gradient of electrostatic potential, when such a contribution is required for a self-consistent solution of the equations of motion of the particles and of Poisson's equation.




Fig. 21—Principle of accelerated electron engine.

It is important to observe that the potential gradient in a region such as IV can exist in a plasma as a consequence of two separate causes. In one case, the presence of an electrode close to cathode potential around the plasma beam in region IV and penetration of the vacuum field into the plasma are essential. Electrostatic forces between this electrode and the ions cannot be ignored; they directly cause the acceleration of the ions. Momentum is imparted to the vehicle via this electrode and via the electrostatic fields accelerating the ions. In the other case, penetration of external electrostatic fields into the plasma is negligible; electrostatic forces between plasma and electrodes in region IV are insignificant, and most of the potential gradient in region IV results from space-charge fields. Momentum is then imparted to the ions in region IV through these space-charge fields. In other words, it is transferred in region IV from the energetic electrons entering region IV to the accelerated ions leaving region IV via the space-charge field existing in region IV. The momentum of the high-energy electrons entering region IV from region III has been imparted to them by electrostatic forces in region I. The momentum imparted to the vehicle therefore corresponds in this idealized case to the vehicle's reaction to these forces in region I.

A quantitative analysis of the conditions for momentum transfer by space-charge forces in region IV (momentum transfer from energetic electrons to the ions) is given in the Appendix. This analysis is based upon the observation that, in the absence of electrostatic forces between plasma and electrodes in region IV, all the momentum gained by the accelerated ions leaving region IV comes from the energetic electrons entering region IV from region III. This leads, as shown in the Appendix, to the following interesting relation between the density of oscillating electron current j_{e3}' flowing toward region IV (from the left) and the ion current density j_i accelerated through region IV:

$$j_{e3}' \simeq \frac{1}{2}\sqrt{\frac{\overline{m_i}}{m_e}}\sqrt[4]{\frac{\overline{W_{i4}}}{W_{i3}}}\cdot j_i \tag{23}$$

where

m_i = ion mass,

m_e = electron mass,

W_{i3} = average energy of ions entering region IV from region III,

W_{i4} = average energy of ions ejected to the right after acceleration through region IV.

Eq. (23) shows that the electron current density j_{e3}', most of which is reflected by the potential gradient in region IV, is much larger than the ion current density accelerated through this region. This is in agreement with what one intuitively expects when considering the transfer of momentum between light electrons and heavy ions as described above. The net electron current density emerging to the right of region III, together with the ion current density j_i, is given by

$$|j_e| = |j_{e3}'| - |j_{e3}''| = j_i. \tag{24}$$

This relation results from the condition that the total current density j_i+j_e emerging from the plasma accelerator be zero, a condition enforced by the processes outlined in the earlier discussion of ion beam neutralization.

It may be of some interest to observe that for desirable ion current densities j_i, the electron current density j_{e3}' becomes quite large; *e.g.*, for $j_i=1$ ampere/cm², $\sqrt{m_i/m_e}=500$, and $W_{i4}/W_{i3}=10^4$, $j_{e3}'\simeq 2500$ amperes/cm². This result, however, is of no particular concern, as j_{e3}' consists of currents due to multiple reflections between the cathode and region IV. The net current density which must be emitted by the cathode in this example equals only $|j_e| = |j_e'| - |j_e''| = j_i = 1$ ampere/cm², plus the contribution corresponding to the current ultimately collected on the positive electrode.

Although some emphasis has been given above to the direct transfer of momentum from electrons to ions in region IV by space-charge forces, it is not yet clear which conditions prevail in actual oscillating electron engines. It may be plausible, in fact, that part of the momentum transfer to the ions occurs directly through electrostatic forces between electrodes and ions, another part of the momentum being transferred from the energetic electrons through space-charge forces. In either case, however, oscillating electrons exist in region III and are ultimately collected by a positive electrode. It is clear that this collected (or "intercepted") electron current must, in any event, be kept as small as possible for reasons of efficiency; it represents a power loss which is basically unnecessary. For this reason, good focusing of the beam of oscillating electrons in regions II and III is essential. In the engines considered so far, this is done by means of a dc magnetic field, as in a Penning discharge. If the cathode is itself immersed in the focusing dc magnetic field, it is of interest to ask how the plasma beam can escape from the diverging magnetic field at the end of the engine without being itself caused to diverge intolerably. Although a theoretical answer to this question does not seem to exist yet, Meyerand's experiments [33], [34] (described below) on oscillating electron ion engines seem to indicate that, in fact, such a plasma beam divergence can be avoided.

A further quantity to be evaluated is the plasma density $n_i=n_e$ required in region III for a given ion current density j_i in the plasma beam escaping to the right of region IV. If the rate of ion generation in region IV can be neglected as compared with the rate of ion injection or generation in region III, it is seen that

$$n_i = \frac{j_i}{e\bar{v}_{i3}}, \tag{25}$$

where $\bar{v}_{i3}$ is the average axial velocity of ions leaving region III toward region IV. For $j_i=1$ ampere/cm² (which is a respectable ion current density) and $v_{i3}=2\cdot 10^5$ cm/second (which corresponds to argon ions at an energy of the order of 1 ev),

$$n_e = n_i \cong 3\cdot 10^{13} \text{ particles/cm}^3.$$

Although this plasma density is relatively high, it does not appear excessive for an intense hot-cathode Penning-type discharge; this shows, therefore, the potential capability of this type of engine for achieving quite high thrust densities at a high specific impulse.

A few additional observations can be made about the rate of ion generation in region IV. In the above calculations, this rate was assumed to be zero. In some engines (*e.g.*, Meyerand's oscillating electron ion engine), however, this rate is finite. The consequences of having a finite rather than vanishing rate of ion generation in region IV are:

1) Requirement for a lower plasma density in region III than predicted by (25). This lowering of the plasma density, however, will not be larger, typically, than one order of magnitude.
2) Introduction of an undesirable velocity spread for the accelerated ions.

It is now possible to see the following striking analogies between the oscillating electron engines and accelerated ion engines:

1) Electrostatic acceleration of electrons, which is dual to electrostatic acceleration of ions.
2) Minimization of electron collection by the accelerating electrode through electron focusing (electrostatic and magnetic); is dual to suppression of ion interception by careful electrostatic ion focusing in the ion engine (even though electron interception here is very much higher than ion interception in ion engines).
3) Ion injection for space-charge neutralization, which is dual to electron injection in the ion engine.
4) Prevention of ion flow to the cathode by an ion deceleration potential maximum (region II), which is dual to the prevention of electron flow to the ion emitter by a potential minimum in the ion engine.

The major basic difference between the oscillating electron engine and the ion engine is possibly the process of momentum transfer from electrons to ions, which was discussed above.

The actual oscillating electron engines to which the above considerations pertain differ from one another primarily in their methods of ion generation or ion

injection (in region III of Fig. 21). Three types of ion source have been considered so far:

1) Ion generation through the oscillating electrons themselves (Penning discharge).
2) Ion generation by an arc.
3) Ion generation by contact ionization of cesium.

Type 1) was investigated by Meyerand, *et al.* [33], [34] in the oscillating electron engine; type 2) was first proposed and investigated by J. S. Luce [35]; type 3) is being investigated by W. Eckhardt. This list, of course, does not exhaust the types of ion source which can be considered or which may be in a preliminary state of investigation.

2) The Oscillating Electron Ion Engine: The oscillating electron ion engine as invented and investigated by Meyerand, *et al.*, is sketched in principle in Fig. 22; a typical axial potential distribution is also shown qualitatively in Fig. 22. It is seen that this potential distribution is closely similar to that in Fig. 21, with the difference that the well-defined potential maximum of region II in Fig. 21 does not exist; it is replaced by a moderate potential gradient in region III. The ions are generated by collisions between the fast electrons and neutral gas molecules or atoms admitted into region III. This device is therefore seen to be a modification of a hot-cathode Penning discharge.




Fig. 22—Oscillating electron ion engine (modified Penning discharge).

Typical performance obtained to date by an engine of this type is, according to Meyerand:

Specific impulse—up to 3000 seconds with argon.
Beam power efficiency—25 per cent.
Ion current density in escaping plasma beam—of the order of several amperes/cm².

"Sputtering of the cathode (lanthanum hexaboride) was visible after several hundred hours of operation, but did not interfere with normal operation of the device. Appreciably less than 50 per cent of the total ion current went to the cathode. No data on fuel-utilization efficiency seem available yet.

The most important result from Meyerand's experiments appears to be attaining ion current densities above 1 ampere/cm² in the plasma beam, an achievement which appears rather outstanding at the present state of the art.

3) The Arc-Type Engine: In the arc-type engine, ions are generated in what corresponds to region III of Fig. 21 by means of a high-intensity vacuum arc. The type of arc developed by Luce [35] at Oak Ridge has been proposed for this purpose. Because of the high ion density (up to about 10^{14} ions/cm³) and the high degree of ionization (resulting in good fuel utilization efficiency), this type of arc has definite merits as an ion source for an accelerated electron engine. The arc will be established between a hollow cathode and a cylindrical anode, the accelerated electron beam being injected through the cathode hole. Two possible disadvantages of this type of arc are the relatively fast rate of erosion (sputtering) of the cathode of the arc, and the requirement for a relatively strong axial dc magnetic field in the arc region. The latter, of course, is also a requirement for Meyerand's Penning-type oscillating-electron ion engine.

4) Accelerated-Electron Cesium Ion Engine: It is conceivable that the ions in region III of Fig. 21 could be provided by means of a cylindrical cesium ion emitter, producing ions by contact ionization. In principle, such an ion emitter could be made by a method similar to that described for the cesium ion engine. Possible advantages of the accelerated-electron cesium ion engine then appear to be: 1) the ability to draw the maximum ion current density available from the ionizer, without limitations imposed by the perveance of the accelerating ion gun electrodes, and 2) better thermal efficiency, because the thermally radiating area (approximately equal to the area of the plasma beam cross section) can be made much smaller than the ion emitting area. A reduction of one order of magnitude in radiative heat loss does not seem impossible.

Further apparent advantages of the accelerated-electron cesium ion engine over other types of oscillating electron engines are: 1) better fuel utilization efficiency; and 2) better control of the potentials in regions I and II to minimize the back-flow of ions onto the cathode, minimize the power loss, and suppress the cathode sputtering associated with this ion back-flow.

Questions still to be resolved about this type of engine are the details of potential distribution in the vicinity of the ion-injecting cylinder through which the electron beam passes in region III, the optimization of the electron beam focusing in region III (it is possible that an appreciable dc magnetic field may be required), and a detailed understanding of the plasma potential gradient needed in region IV. No experiments have been performed as yet on the accelerated-electron cesium ion engine.

III. Magnetic Plasma Acceleration

The dual to electrostatic acceleration of charged particles is magnetic acceleration; Coulomb forces are used in the former, Lorentz forces in the latter.

In magnetic plasma acceleration, the accelerating force is given by $\boldsymbol{F}=q\boldsymbol{v}\times\boldsymbol{B}$, where q is the charge of the accelerated particle, $\boldsymbol{v}$ its velocity, and $\boldsymbol{B}$ the magnetic induction. Because the average value of $\boldsymbol{F}$ can be finite even when both $\boldsymbol{v}$ and $\boldsymbol{B}$ are time varying and quasi-periodic, the possibility exists, in principle, of accelerating a plasma with either dc or ac magnetic fields. Both methods are being investigated and will be discussed below.

A. DC Magnetic Plasma Acceleration

1) Theory: A schematic of a dc magnetic plasma accelerator is shown in Fig. 23. An electron current I is emitted from a cathode, passed through the plasma which is to be accelerated, and collected by an anode; a dc magnetic field perpendicular to both the direction of plasma flow and of electron current flow is provided. As a result, a volume force

$$\boldsymbol{f}=\boldsymbol{j}\times\boldsymbol{B}$$

is exerted on the plasma by the flowing electron current and is available to accelerate the plasma.




Fig. 23—Principle of dc magnetic plasma acceleration.

Both the current flow perpendicular to a dc magnetic field and the momentum transfer from the electron current I to the ions and neutrals of the gas imply collision processes. Because these collisions are necessary, it also follows that a finite ohmic plasma resistivity ρ is unavoidable. Therefore, joule heating of the plasma must necessarily accompany its acceleration by continuous Lorentz forces. It is therefore of interest: 1) to evaluate the importance of this joule heating, 2) to compare it with the transfer of ordered kinetic energy by Lorentz forces, and 3) to determine what basic limits are imposed on this type of plasma accelerator as a consequence of joule heating [36].

The kinetic power u_k transferred to the plasma is given by

$$u_k = T(v_2 - v_1) = IhB(v_2 - v_1), \tag{26}$$

where

T = total thrust,
v_2 = exit gas velocity,
v_1 = input gas velocity,
I = total current flowing across magnetic field H between cathode and anode,
$B=\mu_0 H$ = magnetic induction,
h = distance between cathode and anode.

The power lost by joule heating of the plasma is given by

$$u_j = R_p I^2, \tag{27}$$

where R_p is the total plasma resistance between the cathode and anode.

From (26) and (27) the efficiency η of a dc magnetic plasma accelerator is seen to be

$$\eta \cong \frac{u_k}{u_k + u_j} = \frac{1}{1 + \dfrac{R_p}{hB(v_2 - v_1)}\cdot I}. \tag{28}$$

From (26) I can be expressed as a function of the thrust T; substituting $I=T/hB$ into (28) yields

$$\eta = \frac{1}{1 + R_p\cdot\dfrac{T}{h^2B^2(v_2 - v_1)}}. \tag{29}$$

These expressions are only rather crude approximations. End effects, Hall currents, boundary layer effects, power to maintain the magnetic field are all neglected; a constant channel cross section (which may not be optimum) is assumed. Nevertheless, these expressions are helpful in gaining an insight into the nature and importance of the fundamental limitations of this acceleration mechanism. To this end, it is useful to express the total plasma resistance R_p in terms of the plasma resistivity ρ_p, which is a more fundamental and more readily evaluated quantity. Under the assumption of constant plasma resistivity ρ_p throughout the region of current flow, this leads from (29) to

$$\eta \cong \frac{1}{1 + \dfrac{\rho_p}{B^2}\cdot\dfrac{T}{V(v_2 - v_1)}}. \tag{30}$$

where V is the volume of interaction space. Eq. (30), although approximate, is important because it shows which parameters should be optimized. For a given mission, the total thrust T will be prescribed; the specific impulse, and therefore the exhaust velocity v_2, will also be prescribed. For an effective plasma accelerator, $v_2 \gg v_1$; hence, $v_2 - v_1 \simeq v_2$. The parameters remaining available for optimization are, therefore:

1) The plasma resistivity ρ_p,
2) The magnetic induction B,
3) The volume of the interaction space V.

According to (30), it is desirable: 1) to minimize ρ_p, and 2) to maximize B^2V.

In order to evaluate the plasma resistivity ρ_p and de-

termine how far it can be reduced, it is necessary to consider how the plasma can be injected into a Lorentz accelerator. In the devices considered and tested to date [37], the plasma is generated by a plasma jet [38]. This implies gas temperatures of the order of 1 ev. At such temperatures, a fractional ionization of the order of a few per cent can be achieved by seeding the gas with an alkali metal of low ionization potential (*e.g.*, Cs, Na, or K). This degree of ionization is high enough to make electron-neutral collisions negligible as compared with Coulomb (electron-ion) collisions. The resistivity of such a plasma can therefore be made about as low as that of a fully ionized gas of corresponding temperature. The resistivity of a fully ionized plasma is given by [39]

$$\rho_p = 6.53 \cdot 10^3 \frac{\log \Lambda}{T_e^{3/2}} \text{ ohm cm}, \tag{31}$$

where $\log \Lambda$ is a slowly varying function of density and temperature whose value is between 6 and 9 in the range of parameters of interest here and T_e (this should not be confused with those equations where T is used for thrust) is the electron temperature in °K. For a temperature between 5000°K and 10,000°K, this leads to a plasma resistivity of the order of $\rho_p \simeq 0.1$ ohm-cm. To reduce ρ_p below this value would require a higher electron temperature. With a plasma jet, this is not practical because of materials and life problems. An alternative process providing additional heat to the electrons is the joule heating itself, which results from the current flow through the interaction space of the plasma accelerator. An upper limit to the electron temperature, however, is probably set by the heat transfer from the plasma to the electrodes with which it is in contact, and by the subsequent electrode cooling and erosion problem. The existence of sheaths at the electrodes and of temperature gradients through the plasma cross section makes difficult a more accurate evaluation of the maximum tolerable electron temperature and of the minimum corresponding plasma resistivity in the present state of the art.

The maximum tolerable value of B^2V in (30) is determined by the following considerations:

1) Since engine weight tends to increase with volume, it will usually be desirable to keep V reasonably small. Hence, to maximize B^2V, it is more desirable to make B large than to make V large. (Note that B^2V is proportional to the total stored magnetic energy W_m. Since the solenoid power or the weight of permanent magnet material needed for the required magnetic field is approximately proportional to W_m, it does not matter, from the standpoint of cost of the field, whether B^2 or V is increased.)

2) The upper limit to B is determined by the condition that the required current flow in the direction of the applied electric field and perpendicular to the magnetic field can take place and that the momentum transfer from the electrons to the ions and neutrals be effective. In order to determine this upper limit to B, it is necessary to investigate in more detail the flow of electron current perpendicular to a dc magnetic field in an ionized gas. To this end, it is convenient to proceed from the following equation, which relates electron current density $\boldsymbol{j}$, electric field $\boldsymbol{E}$, and magnetic field $\boldsymbol{B}$ in a partially ionized gas [40]:

$$\boldsymbol{j} \cong \frac{1}{\rho_p}\left[\boldsymbol{E} + (\boldsymbol{v} \times \boldsymbol{B}) - \frac{1}{n_e e}\cdot \boldsymbol{j} \times \boldsymbol{B}\right] + \frac{2}{B^2}\cdot\left[\frac{R_{ce}\cdot R_{ci}}{\lambda_{ei}\cdot\lambda_{ia}}\right]^{-1}\cdot[\boldsymbol{j} \times \boldsymbol{B}] \times \boldsymbol{B}, \tag{32}$$

where

R_e = cyclotron radius of particle considered,
e = charge of electron (absolute value),
m = mass of particle considered,
λ = mean free path,
e = electron,
i = ion,
index a = neutral,
$\boldsymbol{v}$ = velocity of mass motion of whole gas,
$1/\rho_p = n_e e^2 \tau_{ei}/m_e$ = plasma conductivity with $1/\tau_{ei}$ = electron-ion collision frequency,
n_e = electron density.

Eq. (32) was obtained using the following simplifying assumptions, which are valid in the plasmas under consideration:

1) gravity forces on the plasma are negligible,
2) $\lambda_{ia}/\lambda_{ea} \ll m_i/m_e$,
3) $\lambda_{ei} < \lambda_{ea}$,
4) $n_e/n_a < 10^{-1}$,
5) the gradient of electron pressure is small compared with other forces per unit volume.

Eq. (32) is needed to find the components of the current density $\boldsymbol{j}$ and of the thrust density $\boldsymbol{f} = \boldsymbol{j} \times \boldsymbol{B}$. The y direction is chosen parallel to the applied dc electric field; the z direction is parallel to the applied dc magnetic field. A further simplifying assumption is made as follows:

$$2\left(\frac{\lambda_{ia}}{R_{ci}}\right)\left(\frac{\lambda_{ei}}{R_{ce}}\right) \gg 1. \tag{33}$$

This inequality is satisfied for magnetic inductions $B \geq 0.1$ weber/m^2 at plasma densities $n_i = n_e < 10^{15}$ cm^{-3} and electron temperatures $T_e \geq 1$ ev. Eq. (32) then yields

$$j_x \simeq -\frac{1}{\alpha B} j_y, \tag{34}$$

$$j_y \simeq \frac{1}{1 + \alpha^2 B^2}\cdot\frac{E_y'}{\rho_i}, \tag{35}$$

where

$$\alpha = \frac{2}{B}\cdot\frac{\lambda_{ia}}{R_{ci}} = \frac{2e}{\nu_{ia}m_i},$$

$\nu_{ia} \equiv$ ion-neutral collision frequency,

$$E_y' = E_y - v_x B,$$

$$\rho_i = \frac{m_i}{2n_e e^2 \tau_{ia}} \equiv \text{plasma resistivity to ion flow.}$$

From (34) and (35), the components of the thrust density $\boldsymbol{f} = \boldsymbol{j} \times \boldsymbol{B}$ (thrust per unit volume) are found to be

$$f_x \cong \frac{j_0 h B}{1 + \alpha^2 B^2}, \tag{36}$$

$$f_y \cong \frac{1}{\alpha B}\cdot f_x, \tag{37}$$

$$f \cong \sqrt{f_x^2 + f_y^2} = \frac{j_0 h}{\alpha}\cdot\frac{1}{\sqrt{1 + \alpha^2 B^2}}, \tag{38}$$

where

$$j_0 = \frac{E_y'}{\rho_i}.$$

Because of the assumption of (33), the results of (34) to (38) do not hold for $\alpha B \to 0$ or $\alpha B \ll 1$, even though they are still approximately valid when αB is somewhat smaller than 1. They are, of course, quite good approximations for $\alpha B \geq 1$. Further, for reasons of efficiency [see (30)], very small values of αB are of no interest for the purpose of propulsion. Therefore, (34)–(38) are valid within the range of values of magnetic field of practical interest.

Considering at the same time the efficiency given by (30) and the thrust density given by (38), it becomes apparent that an approximate optimum value for the magnetic field is given by the condition

$$\alpha^2 B^2 \simeq 1, \tag{39}$$

which may be rewritten, by definition of α, as

$$R_{ci} \simeq 2\lambda_{ia}. \tag{40}$$

This result [41] shows for the optimum magnetic field a value such that the ion cyclotron radius is about twice the ion-neutral mean free path. This follows from the predominant importance of the last term of (32), when $R_{ce} < \lambda_{ei}$. This result differs markedly from that which would be obtained in a fully ionized gas, where the last term of (32) would not exist; in that case the optimum magnetic field would correspond to the condition $R_{ce} \simeq \lambda_{ei}$ and would be much smaller.

2) *Experiments:* Experimental results in apparent agreement with the theory outlined above have been obtained in a dc magnetic plasma accelerator by Demetriades [42]. They are summarized below as an indication of the present state of the art. A schematic representation of the plasma accelerator is shown in Fig. 24; a diagram of the complete experimental apparatus is given in Fig. 25. Of most interest is a series of measurements of thrust as a function of dc magnetic field. These measurements, shown in Fig. 26, provide an experimental verification of (38) and condition (40) for the optimum magnetic field. For the conditions of the experiment shown in Fig. 26, B_{opt} can be




Fig. 24—Schematic diagram of arc jet plasma source and dc magnetic plasma accelerator.




Fig. 25—Schematic diagram of experimental apparatus showing dc magnetic plasma accelerator mounted on thrust stand within vacuum tank. Arc jet is mounted in vacuum tank door.




Fig. 26—Experimental data showing accelerator thrust as a function of applied magnetic induction.

evaluated from the following values of the parameters estimated by Demetriades for this experiment:

Ion-neutral mean free path—$\lambda_{ia} = 1/n_a\sigma_{ia}$,
Neutral density—$n_a = 10^{16}$ atoms/cm^3,
Gas—argon,
Ion-neutral collision cross section [43]—$\sigma_{ia} = 4 \cdot 10^{-16}$ cm^{-2},
Relative ion-neutral velocity—$v = 2.3 \cdot 10^2 \sqrt{T_i} \simeq 1.85 \cdot 10^5$ cm/second,
Electron density—$n_e = 10^{14}$ cm^{-3},
Electron temperature—$T_e \cong 10{,}000$°K,
Ion temperature—$T_i = 6400$°K.

The theoretical magnetic field for maximum thrust in the x direction, then, is given with $R_{ci} = 2\lambda_{ia}$ by

$$B_{\text{opt}} = \frac{\nu_{ia} m_i}{e} \simeq 0.15 \text{ weber}/m^2.$$

The experimental value, according to Fig. 26, is $B \simeq 0.3$ to 0.4 weber/m^2. Considering the uncertainty in the evaluation of σ_{ia} and ν_{ia}, agreement between theory and experiment appears reasonably good. It is clear, in particular, that the criterion $R_{ce} \simeq \lambda_{ei}$, which would prevail in a fully ionized plasma, does *not* apply to those experiments. Indeed, the condition $R_{ce} \simeq \lambda_{ei}$ would lead to an optimum magnetic induction of about $2.5 \cdot 10^{-2}$ weber/m^2, for the values of electron density (about 10^{14} cm^{-3}) and electron temperature (about 10,000°K) estimated for these experiments.

Further results of interest from the Demetriades experiments are:

Maximum specific impulse achieved—2400 seconds,
Maximum acceleration efficiency—44 per cent.

While the above theoretical considerations and experimental results show that Lorentz force plasma accelerators hold basically good promise for the achievement of high specific impulse with good efficiency and high thrust density, a number of problems still remain to be investigated. The limitations imposed by overheating of the electrodes by the hot plasma stream [45], boundary layer effects, and end effects still remain to be investigated in more detail, particularly at higher specific impulse. While, from the results obtained to date, specific impulses up to about 5000 seconds with efficiencies above 60 per cent can probably be expected, it is not clear how much more will ultimately be achieved.

B. AC Magnetic Plasma Acceleration

In dc magnetic plasma acceleration, important limitations seem to be imposed by the presence of electrodes in direct contact with the hot plasma. A possibility of avoiding these difficulties while still applying the concept of magnetic plasma acceleration by $j \times B$ Lorentz forces is to produce induced currents in the plasma by time-varying (ac) fields, thus obviating in principle the need for physical contact between plasma and electrodes. A further advantage of currents induced by ac fields is the possibility of exerting accelerating forces on the plasma without the need for any particle collisions. For this reason, the use of plasmas with very low resistivity is, in principle, possible. This contrasts with dc magnetic plasma acceleration, where a finite plasma resistivity has been shown to be basically unavoidable. (Because, however, the effect of plasma resistivity in the dc case was found in itself to be tolerable, the latter advantage is probably of more academic than practical significance.)

1) Traveling-Wave Magnetic Plasma Acceleration: One class of ac magnetic fields available for plasma acceleration is traveling fields, or magnetic "traveling waves"; the other, of course, is stationary fields.

Traveling-wave devices may be subdivided [46] for convenience into the following categories: 1) magnetic piston plasma accelerators, 2) traveling-wave plasma bunch accelerators, and 3) traveling-wave plasma ring accelerators.

a) Magnetic piston plasma accelerators: A schematic illustration of a magnetic piston device is shown in Fig. 27. The pressure p exerted by the magnetic field on the plasma, if the penetration of the magnetic field into the plasma is limited to a surface region, is given by

$$p = \frac{\mu_0 H^2}{2} \cdot \tag{41}$$

A simple derivation of this relation will be given for a one-dimensional case because it provides some insight into the physical significance of (41). Consider a slab of plasma as illustrated in Fig. 28. Let a field H be established in the z direction at the left of the plane x_1. As this field tends to penetrate into the plasma, it induces a current density j_y. Then, from Maxwell's equa-




Fig. 27—Magnetic piston.




Fig. 28—Magnetic pressure on plasma slab.

tion $\nabla \times H = j$, it follows that, for this one-dimensional case,

$$j_y = -\frac{\partial H_z}{\partial x}. \tag{42}$$

The force per unit volume exerted on the plasma in the surface region is given by $f = j \times B$:

$$f_x = j_y B_z = \mu_0 j_y H_z. \tag{43}$$

From (42) and (43),

$$f_x = \mu_0 H_z \frac{\partial H_z}{\partial x} = -\frac{\mu_0}{2}\frac{\partial}{\partial x}(H_z^2).$$

Integrating f_x between $x = x_1$ and $x = x_2$ to obtain the force per unit area yields the pressure p exerted by the magnetic field on the plasma:

$$p = -\frac{\mu_0}{2}\int_{x_1}^{x_2}\frac{\partial}{\partial x}(H_z^2) = \frac{\mu_0(H_1^2 - H_2^2)}{2} = \frac{\mu_0 H^2}{2}$$

if $H_1 = H$ and $H_2 = 0$.

This elementary derivation illustrates the fact that the pressure exerted by a traveling magnetic field acting as a piston on a plasma does result from the Lorentz force $j \times B$. A further consequence evident from this derivation is that the full magnetic pressure is exerted on the plasma only if the magnetic field is prevented from penetrating through it (otherwise, the above derivation leads to $p = (\mu_0/2)(H_1^2 - H_2^2)$, with $p = 0$ when $H_2 = H_1$!). This means that the diffusion of the magnetic field into the plasma must be slow compared with the time available for plasma acceleration. In order to determine, in principle, the feasibility of magnetic piston acceleration of a plasma, it is necessary to consider the process of diffusion of a magnetic field into a plasma. This process is expressed by the following diffusion equation [47]:

$$\frac{\partial H}{\partial t} = D \cdot \nabla^2 H, \tag{44}$$

where

$D = \rho/\mu_0 =$ diffusion coefficient of the magnetic field in a plasma of resistivity ρ, (45)

$\mu_0 =$ permitivity of vacuum $= 4\pi \times 10^{-7}$ henry/m.

Let τ be the time available for acceleration of the plasma, l the depth to which the magnetic field is allowed to diffuse into the plasma during this time τ, and v_d the mean velocity of diffusion of the magnetic field during this time τ. The condition determining the maximum tolerable rate of diffusion of the magnetic field into the plasma is then

$$v_d \tau < l.$$

Further, by definition of v_d and D,

$$v_d \simeq \frac{D}{l}.$$

Hence,

$$D < \frac{l^2}{\tau}. \tag{46}$$

The time τ available for acceleration is related to the available acceleration length L and to the final plasma velocity v_p by

$$\tau = \frac{2L}{v_p}, \tag{47}$$

which is valid under the assumption that $v_p \gg v_1$, if v_1 is the initial plasma velocity (before acceleration) and if the accelerating force is constant during the time interval τ. The following condition results from (45)–(47), for the plasma resistivity ρ:

$$\rho \leq \mu_0 \cdot \frac{l^2 v_p}{2L}.$$

For a representative numerical application, let

$l = 10^{-2}$ m,
$2L = 0.5$ meter,
$v_p = 10^5$ m/second,
$\mu_0 = 4\pi \cdot 10^{-7}$ henry/m.

Then

$$\rho \leq 2.5 \cdot 10^{-5} \text{ ohm-meter}$$

or

$$\rho \leq 2.5 \cdot 10^{-3} \text{ ohm-cm}.$$

Assuming the degree of ionization of the plasma to be high enough that Coulomb collisions will predominate over electron-neutral collisions leads, with (31), to the following limit for the electron temperature T_e of the plasma:

$$T_e > 6 \text{ ev (about } 70{,}000^\circ\text{K}).$$

This calculation is, of course, only approximate, and it aims only at determining orders of magnitude. As such, it shows that the requirement imposed on plasma resistivity and temperature, while not trivial, is not unrealistic. By proper preionization, or plasma injection, such plasma temperatures should, in principle, be attainable. For this reason also, plasma acceleration by a traveling magnetic piston as illustrated in Fig. 27 appears, in principle, possible.

Two modifications [48] of the device in Fig. 27 are shown in Figs. 29 and 30. In the device in Fig. 29 a "biasing" magnetic field is applied before the (traveling) field of the magnetic piston is applied. The purpose of this biasing field is to provide a magnetic insulation between the plasma and the walls. Special care has to be taken to avoid excessive trapping of this field in the accelerated plasma. In the device of Fig. 30 the traveling magnetic field is made sinusoidal; plasma bunches can be trapped every half wavelength in the vicinity of the axis, in the region where the magnetic field is minimum.




Fig. 29—Magnetic piston with "biasing" magnetic field.




Fig. 30—Sinusoidal magnetic traveling-wave plasma accelerator.

Plasma will tend to accumulate in the dotted regions, and to be carried with the magnetic field. For a high enough plasma conductivity (small rate of diffusion of magnetic field into plasma), conditions similar to those described above will prevail, with the advantage that the shape of the lines of force of the magnetic field will tend to reduce the plasma diffusion to the walls. In the plane AA one has, with a circular cylindrical symmetry, a "cusped" field which, while it leads to a finite rate of plasma leakage, keeps this leakage below that which would exist in the absence of a magnetic field.

b) Traveling-wave plasma bunch accelerator: An alternative possibility exists for operating a device of the type shown in Fig. 30: if the plasma conductivity does not satisfy the condition of (33), the plasma will "leak" through the saddle points of the magnetic field, from one minimum to the preceding one, and so on. In this process, however, as a consequence of the relative motion between plasma and magnetic field, transverse azimuthal currents perpendicular to the magnetic field are induced in the plasma, and the resulting $j \times B$ force will still tend to accelerate the plasma, even though the force is more evenly distributed throughout the plasma volume than in the case of the magnetic piston. The advantage of this mode of operation is that it conceivably permits quasi-continuous operation, where the plasma is fed continuously into one end of the device, and is dragged and accelerated by the traveling magnetic field to the other end of the accelerator. One penalty for this mode of operation, as compared with the magnetic piston, is the requirement for a higher ac magnetic field for a given average thrust density.

c) Traveling-wave plasma ring accelerator: The principle of a traveling-wave plasma ring accelerator is illustrated in Fig. 31. It does not differ basically from that of a magnetic piston device of the type in Fig. 30. Although the concept of magnetic pressure $p_m = \frac{1}{2}\mu_0 H^2$ could also be applied to the plasma ring device, it is




Fig. 31—Traveling-wave plasma ring accelerator.

preferable to consider directly the interaction between the magnetic field and the azimuthal current induced in the plasma ring by the change of magnetic flux enclosed by the plasma ring as a consequence of slippage between traveling magnetic field and plasma ring. For this process of plasma acceleration to be effective, the total slippage has to be kept smaller than one-fourth the wavelength of the traveling magnetic field. This condition is equivalent to the condition of (46) derived for the magnetic piston devices and leads to similar requirements for the plasma conductivity. More detailed calculations [49] show that the $j \times B$ forces exerted on the plasma ring not only accelerate the plasma axially, but also tend to make the ring collapse radially inward. It appears possible, however, to prevent the rate of inward radial acceleration from being excessive in relation to the rate of axial acceleration.

d) Limitations and experimental results: One important feature of all traveling-wave devices is that the energy stored in the accelerating magnetic field is at least of the same order of magnitude as the kinetic energy of the plasma being accelerated. Hence if the traveling-wave circuit were simply terminated in a matched load, this flux of magnetic energy would be lost; because it is at least equal to the flux of kinetic energy of the plasma, quite poor efficiencies would result. One way to avoid this waste is to recuperate the magnetic energy at the output of the accelerating circuit by feeding it back through an appropriate feedback circuit to the input of the accelerating circuit; the accelerating circuit is then part of a race-track circuit.

While loss of magnetic energy at the end of the traveling-wave circuit could, in principle, be avoided, ohmic losses in the conductors of the circuit causing the magnetic field cannot be suppressed. Because of the relatively low frequencies involved (typically of the order of 1 Mc or less), these losses can be kept relatively small, at least in those cases (magnetic piston, plasma rings) where the penetration of the magnetic field into the plasma or the slippage are kept small. Indeed, in those cases, the magnetic pressure on the plasma is of the same order of magnitude as the magnetic pressure on the conductor. If the magnetic field at the conductor leads to a pressure p, it can be shown [50] that the power dissipated per unit area of conductor is, for copper at room temperature,

$$P_1 = 4.15\sqrt{f_{\mathrm{Mc}}} \times p_{at} \ \mathrm{kw/cm^2},$$

where

f_{Mc} ≡ frequency of ac field in Mc/sec,
p_{at} ≡ magnetic pressure in atmospheres.

The pressures involved in plasma acceleration being substantially smaller than one atmosphere, one can expect

$$P_1 \ll 1 \text{ kw/cm}^2.$$

In comparison to this, the kinetic power transferred per unit area of accelerated plasma is

$$P_{k1} \cong p \cdot v_p \cong 10^{-2} p_{at} v_p \text{ kw/cm}^2,$$

where

p = magnetic pressure in Newton/m^2,
p_{at} = magnetic pressure in atmospheres,
v_p = plasma velocity in m/second.

It is interesting to evaluate P_1/P_{k1} from the above relations, assuming p to be about the same on plasma and conductors

$$P_1/P_{k1} \simeq \frac{415 \cdot \sqrt{f_{Mc}}}{v_p} \ll 1.$$

With $v_p = 10^4$ to 10^5 m/second, it is seen that the ohmic circuit losses can be kept relatively unimportant, even if the conductor surfaces would much exceed the surface over which the magnetic pressure is exerted upon the plasma.

An additional feature common to these traveling-wave devices, where near synchronism is required between traveling magnetic field and plasma, is the necessity of increasing progressively with distance the phase velocity of the accelerating magnetic field wave; *i.e.*, a "tapered" traveling-wave circuit is required. This applies to the magnetic piston devices; it also applies to the traveling-wave plasma ring accelerator described above.

A further requirement common to all traveling-wave accelerators is low plasma resistivity. In all the above cases, plasma resistivity has been shown to lead to unwanted effects (diffusion of the field into the plasma, slippage of plasma rings). In other words, electron collisions with ions or neutrals are to be minimized. It could be asked at this point how momentum is transferred to the ions in the absence of electron-ion collisions. In all traveling-wave devices, the current flow is indeed carried by the electrons; the Lorentz force $j \times B$ acts, therefore, on the electrons, and the electrons alone will first be accelerated. However, as the electrons are accelerated and leave the ions behind, a charge separation occurs and leads to a space-charge field; this space-charge field then accelerates the ions and decelerates the electrons until they all have the same average velocity. This process is analogous to ambipolar diffusion and is effective as long as the Debye length is small compared with the dimensions of the plasma. One exception occurs when the electron current flow is closed on itself, as in a plasma ring; in this case, an azimuthal electron current can flow without dragging ions with itself and without charge separation. This exception is important because it makes the flow of a net electric current transverse to the magnetic field possible. However, the axial motion of electrons, under the accelerating $j \times B$ force, does not lead to a closed path of electron current. For this reason, momentum is transferred by space-charge fields from electrons to ions in the axial direction without need for collisions. Returning to the requirement for minimizing electron-ion and electron-neutral collisions leads to the need for highly ionized plasmas of relatively high temperature (typically above 5×10^4 °K, as shown above). For this reason, it does not seem practical to ionize the gas and accelerate it by means of the same electromagnetic field. Separate ionization and injection seems necessary for traveling-wave devices. (It is indicated below that similar requirements on low plasma resistivity and separate plasma generation are also apparent in stationary ac field plasma accelerators.)

This list of requirements is rather severe; even so it is not exhaustive. In experiments performed by Penfold [51] the basic principle of this acceleration mechanism has been demonstrated. Plasma rings with velocities of about 1.2×10^7 cm/second ($I_{sp} \simeq 10^4$ seconds) have been obtained; evidence has been found for plasma ring currents of at least several hundred amperes.

2) Stationary AC Magnetic-Field Plasma Acceleration: It is also conceivable that currents can be induced into a plasma by means of a stationary ac magnetic field and that accelerating forces can be obtained by the interactions between these currents and the inducing magnetic field. One model of a device based upon this principle is shown in Fig. 32. The ac magnetic field is produced by a single-turn coil which is made part of a tank circuit by connection to an appropriate capacitor. A plasma ring is produced by preionization of the gas in the vicinity of the "exit" of the coil, as shown ideally in Fig. 32. The ac magnetic field induces an azimuthal current in the plasma ring; this results in a force $j \times B$ as shown in Fig. 32. For optimum conditions the current density j should be in phase with the ac magnetic field H; hence, it should be in quadrature with the induced electric field, except for the phase shift of the electrons produced by the acceleration itself. This means that the plasma ring should have only negligible ohmic resistance; in this case, as well as in that of traveling-wave acceleration, electron-ion and electron-neutral collisions are, if anything, detrimental. In the extreme, if the plasma ring were purely resistive (instead of inductive) as a consequence of high ohmic resistivity, j and B would be in quadrature and the average force would be zero.




Fig. 32—Stationary ac magnetic field plasma accelerator.




Fig. 33—Hydromagnetic plasma gun.

The requirement for minimizing collisions and plasma resistivity appears to be in contradiction with the need of collisions for ionizing the gas. For this reason, preionization of the gas or separate injection of the plasma seems necessary. This can be done on a pulse basis (where plasma rings are formed or injected periodically while the accelerating ac field is off). This procedure has been used by Miller [52] in the experiments in which he provided a preionizing coil in the vicinity of the region where the plasma ring was wanted. In Miller's experiment, the frequency (55.5 Kc/sec) and strength (up to 1 weber/m^2) of the ac magnetic field were chosen of such magnitude that the plasma ring was accelerated away from the coil within about $\frac{1}{4}$ cycle. Acceleration efficiencies of the order of 5 per cent have been measured, with axial exit velocities up to 10^5 m/second; energies up to 25 joules per pulse were transferred from the circuit to the axial motion of the gas.

An alternative mode of operation, still pulsed, would consist in using higher ac frequencies and lower field strengths, with the result that the plasma ring would remain several ac periods in the ac field. Because little analytical work and no experimental work seem to be available on this mode of operation, a more extensive treatment does not seem indicated at this time.

Finally, it is possible to consider cw operation. This implies continuous gas feeding and ionization in the accelerating region. Because of the apparent conflict between ionization and acceleration pointed out earlier, no satisfactory solution to the problem of CW stationary ac magnetic plasma acceleration has yet been reported.

In conclusion, although the idea of plasma acceleration by stationary ac magnetic fields seems interesting, both the problems of proper plasma or gas injection and the problem of optimization of the circuit geometry for optimum utilization of the ac magnetic field still remain to be solved.

C. Pulsed Magnetic Plasma Acceleration

An example of a pulsed magnetic field plasma accelerator is shown in Fig. 33. This "hydromagnetic plasma gun," in the form invented by Marshall [53], consists of two coaxial conductors with provision for pulsed admission of gas bursts through openings in the center conductor. Shortly after a burst of gas is admitted between the two coaxial conductors, the power from a high-voltage capacitor bank is suddenly applied. The gas is ionized, a large radial current flows through it, and an azimuthal magnetic field is established by the flow of the current through the central conductor. This azimuthal magnetic field interacts with the radial plasma current to produce axial $j \times B$ forces which result in a magnetic pressure of the order of $\mu_0 H^2/2$. In this respect, this device is analogous to the magnetic piston type of accelerators described above. The essential differences are that, in the hydromagnetic plasma gun: 1) current flow through the plasma results from direct contact to the electrodes instead of being induced, and 2) the magnetic field is not supported by a slow-wave circuit, but by a simple coaxial line.

Basic limitations to this type of plasma accelerator may result from

1) Difficulty of efficient energy transfer from the capacitor bank or pulsing circuit to the coaxial line,
2) Loss of magnetic energy tending to escape or be reflected from the end of the plasma gun,
3) Power loss due to physical contact between the plasma and electrodes,
4) Disadvantage of requiring a pulsed power supply.

Typical characteristics quoted for the performance of such a plasma accelerator are [53]:

Output gas (H_2) velocity—1.5×10^5 m/second.
Total kinetic energy of gas, per pulse—1200 joules.
Total efficiency of energy transfer from capacitor bank to directed kinetic energy—23.5 per cent.
No evidence of electrode erosion was observed under proper timing of the electrical pulse with respect to the gas burst.

These results so far appear encouraging. Because of the limitations suggested above, much still remains to be done before it will be possible to state how much performance can be improved. Further investigations of modifications of the Marshall gun [54] have led so far to results very similar to those quoted above, the major difference being that lower specific impulses (about 6000 seconds) have been obtained with heavier gases, with about the same efficiency.

IV. Electromagnetic Plasma Acceleration

In a nonuniform ac electromagnetic field, a charged particle of charge e experiences an average force given by [55]

$$F = \frac{-e^2}{\epsilon_0 m \omega^2} \cdot \nabla E^2. \tag{48}$$

Although it does not appear explicitly, the effect of the ac magnetic field is also included in (48). [The magnetic field has been eliminated by the use of Maxwell's equation $\nabla \times E = -\mu_0(\partial H/\partial t)$, to arrive at (48).]

In a plasma, the force of (48) will be acting mainly on the electrons and will produce a force f per unit volume given by

$$f = -\left(\frac{\omega_p}{\omega}\right)^2 \nabla \left(\frac{\epsilon_0 E^2}{2}\right), \tag{49}$$

where $\omega_p \equiv$ electron plasma frequency. (Momentum transfer from electrons to ions is caused by space-charge forces in the same process as described above.)

In electromagnetic plasma acceleration, forces of the type given by (49) are produced by nonuniform RF fields and are being used to accelerate plasmas. It may be observed that when the RF field penetration inside the plasma is negligible (which it will tend to be at high plasma densities), (49) can be integrated to lead to a puressure $p = \epsilon_0 E^2/2$ from the RF field on the plasma surface. A more rigorous derivation would lead to

$$p = (1/2)(\mu_0 H^2 + \epsilon_0 E^2),$$

which may also be interpreted as radiation pressure.

A general feature of (48) and (49) is that they indicate that the RF fields will tend to push the plasma toward regions of minimum RF electric field. When the RF electric field is parallel to the plasma surface, the plasma can actually be pushed toward these regions where the RF vacuum field would be minimum. When the RF electric field is parallel to the gradient of the plasma density, this conclusion is no longer always true; it applies only when the frequency of the RF fields is higher than the electron plasma frequency. If the RF frequency is lower, a "peeling" effect takes place at the plasma surface and tends to draw the plasmas toward the region of maximum RF electric fields [50].

The only attempt at electromagnetic plasma acceleration reported to date is that of Swartz, *et al.* [56]. In these experiments, fields substantially parallel to the plasma density gradient were used, as shown in Fig. 34. For this reason, plasma acceleration could only be obtained for the relatively low plasma densities corresponding to a plasma frequency below that (140 Mc) of the applied RF fields ($n \lesssim 3 \times 10^8$ electrons/cm^3). Under these conditions, plasma acceleration up to velocities of the order of 2.5×10^4 m/second (specific impulse of 2500 seconds) has been observed. Because of the low plasma density, however, resulting thrusts would be too low to be of practical interest, even if higher microwave frequencies were used.




Fig. 34—Electromagnetic plasma accelerator.

In conclusion, the basic principle of electromagnetic plasma acceleration has been demonstrated. To make it useful for propulsion purposes, however, it will be necessary to devise means of applying the electromagnetic RF fields perpendicular to the density gradient of the plasma, avoiding RF electric fields normal to the plasma surface and thus being able to operate with relatively high plasma densities where the plasma frequency exceeds the frequency of the accelerating RF fields.

V. Space Simulation

We shall discuss here fairly briefly some of the problems associated with the testing and evaluation of performance of electrical propulsion engines. As we shall see, the simulation of space environment for an electrical propulsion engine is somewhat more complex than the usual space-simulation problem; however, adequate and detailed ground testing of these engines is an essential step in their development. There are a number of reasons for the importance of this ground testing, including the relatively high cost of conducting space tests, the much greater detail with which the physical phenomena can be studied on the ground, the ease of making changes and adjustments in the experiment, etc. All point toward very comprehensive ground tests prior to the real test in space.

Since electrical propulsion engines are to operate in the excellent vacuum of space, it is obvious that they must be tested under conditions where the background gas pressure will not influence the operation. The tolerable level of background pressure depends, of course, on the mean free path of the ions in this residual gas but will in general be of the order of 10^{-7} mm Hg. Additional features of the physical environment simulation which may be desirable are: 1) cold surfaces to simulate the regions of infinite space as far as radiation from the engine is concerned, 2) artificial solar radiation to simulate the power received from the sun, and 3) possibly other types of radiation such as gamma rays, cosmic rays, etc. All these physical environment factors have been successfully simulated in various test chambers. The most difficult aspects of space simulation, as far as electrical engines are concerned, are the electrical conditions. It is apparent that the walls and col-

lector of the test chamber must not act as sources of electrons; *i.e.*, suitable grids or other barriers must be arranged so that the bombardment by ions or other particles does not cause emission of electrons which can get into the beam and influence its behavior. A second and equally important aspect of the electrical simulation problem arises because in the space environment the ion beam is sent into essentially an infinite region with no boundary condition beyond the edges of the space vehicle. In the ground-based test chamber, walls must be imposed around the engine and beam in order to provide the vaccum and a collector must be provided to collect the ion beam; both of these arrangements impose artificial boundary conditions at the edges and the end of the ion beam. Programs are under way to develop improved techniques of simulating electrically the conditions of space in a finite-size ground-based chamber; we hope that by the time of the first electrical engine flight test we shall have improved facilities for more reliable testing of these engines on the ground.

Conclusions

This paper has dealt with some of the fundamental concepts and problems which lie at the heart of a rapidly growing scientific and engineering effort in the field of electrical propulsion. No attempt has been made to include complete references to the many important contributions to this field, nor to some of the interesting approaches based on modification of the basic types of ion sources and acceleration mechanisms presented here. It is hoped, however, that the discussion has served to emphasize both the strong dependence of progress in this field on broad areas of plasma physics and electronic technology, and the fact that it remains a fertile field for basic investigation and invention.

Electrostatic engines have received more attention to date than those based on direct acceleration of plasmas and are consequently somewhat nearer the stage of practical usefulness. Of these, the cesium ion engine is the most refined in terms of progress toward meeting all of the difficult requirements of practical thrust units, *i.e.*, high efficiency, excellent optics (low electrode erosion for long life), and techniques for controlled neutralization of the exhaust beam. This may be because the cesium ion engine is amenable to analytical treatment and is better understood than plasma devices. At any rate, this type of engine may well provide the ultimate optimum answer for systems requiring a specific impulse of 8000 seconds and higher. Although the thrust density is low, units of 20- to 30-millipound thrust can be clustered to provide total thrusts of the order of pounds for megawatt-level systems. However, each of the basic types of engines discussed here has its particular attractive features (*e.g.*, high thrust density in the case of the Duoplasmatron and oscillating-electron engines) and will, no doubt, find its own area of application.

The fact that the electrical propulsion concept is fast becoming an engineering reality is borne out by the plans of NASA to begin the flight testing of small prototype ion engines (at the several-millipound-thrust level) in late 1962. These tests will be carried out on ballistic trajectories using the Scout launch vehicle as the booster. The principal purpose of these tests will be to demonstrate thrust, with the additional objectives of studying the neutralization problem in an actual space environment and correlating the performance in detail with data obtained under laboratory conditions. Orbital testing of electrical propulsion system is projected at a future date.

It is evident that progress in electrical propulsion will be very closely related to the development of lightweight nuclear-electric power systems, and an intensive effort is required in this direction. The performance of an electrically propelled vehicle depends strongly on achieving high power levels at low weight-to-power ratios (in most mission analyses a ratio of around 10 pounds/kw is assumed). The SNAP-8 program, which is sponsored jointly by the NASA and AEC, is aimed at developing 30 kw at a weight-to-power ratio of around 50 pounds/kw. This power system (or a 60-kw version) will probably be used in the first orbital testing of electrical thrust units. Detailed design studies (*e.g.*, SPUR) indicate the feasibility of using high-temperature operation to attain thrust levels from 300 kw to the megawatt level at thrust-to-weight ratios of 8 to 10 pounds/kw. It is probable that, by using direct conversion concepts currently under study, ratios as low as 3 pounds/kw may be achieved early in the next decade, *i.e.*, by the time ionic and plasma propulsion comes into large-scale use for the exploration of the solar system.

Appendix

Momentum Transfer Between Electrons and Ions in Accelerated Electron Engines

This calculation is intended to determine the rate of momentum transfer from energetic electrons to ions in a region in which a plasma potential gradient exists in the absence of electrostatic forces between plasma and electrodes. Such a region would be the equivalent of region IV of Fig. 21 and will be referred to simply as region IV. It should, however, be observed that, in the absence of electrode fields, it does not appear possible in a one-dimensional situation to maintain such a region at a fixed region in space; it appears that it should move in space (*e.g.*, at the beam front) with the mean velocity of the accelerated ions [57]. Assuming now that the axial electrostatic forces between plasma and electrodes in region IV are negligible, the flux of momentum flowing into the plasma from the left of region IV must be equal to the flow of momentum carried by the plasma out to the right of region IV:

$$\frac{du_{\text{in}}}{dt} = \frac{du_{\text{out}}}{dt}, \tag{50}$$

where

$\frac{du_{\text{in}}}{dt}$ = flux of momentum into region IV (from left),

$\frac{du_{\text{out}}}{dt}$ = flux of momentum out of region IV (with plasma beam to right).

Assuming most electrons to be reflected in region IV and assuming the ion energy in region III to be much smaller than the electron energy leads to the following expression, for the flow of momentum du_{in}/dt into region IV:

$$\frac{du_{\text{in}}}{dt} = n_{e3} m_e \bar{v}_{e3}^2, \tag{51}$$

where

n_{e3} = electron density in region III,
m_e = mass of the electron,
v_{e3} = axial electron velocity in region III,
$\bar{v}_{e3}^2$ = mean square axial electron velocity in region III.

(Note that because of the assumption of near total reflection, $(n_{e3}/2)$ electrons/cm^3 will have a velocity directed toward region III and experience a change of momentum equal to $2m_e v_{e3}$ upon reflection; also, the velocity distribution of electrons flowing in $+x$ and $-x$ direction will be nearly identical.)

Assuming, at the exit of region IV, the electron energy to be much smaller than the energy of the accelerated ions leads, for the flux of momentum leaving region IV, to

$$\frac{du_{\text{out}}}{dt} = n_{i3} m_i \overline{v_{i3} v_{i4}}, \tag{52}$$

where

n_{i3} = ion density in region III,
m_i = ion mass,
v_{i3} = axial velocity of ions flowing toward region IV,
v_{i4} = axial velocity of ions leaving region IV.

Eqs. (51) and (52) express that the momentum flux into region IV is essentially carried by the electrons, while the momentum flux out of region IV is essentially carried by the accelerated ions [in effect, the latter assumption means that $(m_i + m_e)v_{i4} \simeq m_i v_{i4}$].

Using (50)–(52), it is possible to relate the oscillating electron current density in region III to the ion current density emerging in the plasma beam to the right of region IV. To this effect, the following quantities are defined:

j_{e3}' = density of electron current flowing in $+x$ direction (away from cathode) in region III.
j_{e3}'' = density of electron current flowing in $-x$ direction in region III.
$j_{e3} = j_{e3}' + j_{e3}'' = |j_{e3}'| - |j_{e3}''|$.
j_i = density of ion current flowing in $+x$ direction (no ions reflected toward $-x$ direction exist with the potential distribution shown in Fig. 21).

Using (50)–(52) the following relation is found between j_{e3}' and j_i:

$$\frac{j_{e3}'}{j_i} = \frac{1}{2} \sqrt{\frac{\overline{m_i}}{m_e}} \cdot \sqrt{\frac{\bar{v}_{i4}}{\bar{v}_{i3}}}.$$

with the simplifying assumptions, in (52) and (51), that $\overline{v_{i3} v_{i4}} \cong \bar{v}_{i3} \cdot \bar{v}_{i4}$, and $\overline{v_{e3}^2}/\bar{v}_{e3} \cong \bar{v}_{e3}$.

Under these conditions,

$$\bar{v}_{i4}/\bar{v}_{i3} \cong \sqrt{W_{i\,\text{out}}/W_{i\,\text{in}}},$$

where $W_{i\text{out}}$ is the average energy of ions leaving region IV (to the right) and $W_{i\text{in}}$ is the average energy of ions in region III (at the entrance to region IV). Hence,

$$j_{e3}' \simeq \left[\frac{1}{2} \sqrt{\frac{\overline{m_i}}{m_e}} \cdot \sqrt[4]{\frac{W_{i\,\text{out}}}{W_{i\,\text{in}}}} \right] \cdot j_i. \tag{53}$$

Q.E.D.

Acknowledgment

In an attempt to present in this review paper as broad a discussion as possible of the ion and plasma propulsion field, we have made use of material from many sources. We would particularly like to acknowledge valuable discussions with R. N. Seitz, NASA Marshall Space Flight Center; Harold Kaufman, NASA Lewis Research Center; Dr. Sam Nablo, Goodrich-High-Voltage Astronautics; Dr. R. G. Meyerand, United Aircraft Corporation; Dr. S. T. Demetriades, Northrop; and S. L. Eilenberg, Dr. W. Eckhardt, and Dr. O. Husmann of Hughes Research Laboratories.

References

[1] R. H. Goddard, Notebook (dated September 6, 1906), *Astronautics*, vol. 4, pp. 24–27; April, 1959.
[2] H. Oberth, "Wege zur Raumschiffahrt," R. Oldenbourg, Munchen-Berlin, Germany; 1929.
[3] It is well known that the perveance of an electron or ion gun structure is dependent only on a dimensionless factor relating to the geometrical form of this structure. Specifically, it is the area of the emitter A_i divided by the square of the emitter-anode spacing d (for a plane-parallel system); the "aspect ratio" R is defined as $R \equiv \sqrt{(4A_i/d^2)}$.
[4] D. B. Langmuir, "Space Technology," John Wiley and Sons, Inc., New York, N. Y., pp. 9–18; 1959.
[5] C. E. Fay, A. L. Samuel, and W. Shockley, "On the theory of space charge between parallel plane electrodes," *Bell Sys. Tech. J.*, vol. 17, pp. 49–79; January, 1938.
[6] Ramo-Wooldridge Research Laboratory Staff, "Electrostatic propulsion," PROC. IRE, vol. 48, pp. 477–491; April, 1960.
[7] W. H. Wells, Jet Propulsion Laboratory, Pasadena, Calif., Tech. Release No. 34-118; 1960.
Also, W. Eckhardt, private communication.
[8] J. E. Etter, *et al.*, "Neutralization of ion beams," in "Electrostatic Propulsion," Academic Press, Inc., New York, N. Y., pp. 357–372; 1961.
[9] G. R. Brewer, J. E. Etter, and J. R. Anderson, "Design and Performance of Small Model Ion Engines," presented at American Rocket Society Meeting, Los Angeles, Calif.; May, 9 1960.
See also, [8].
[10] J. M. Sellen, *et al.*, "Beam diagnostic techniques," in "Electrostatic Propulsion," Academic Press, Inc., New York, N. Y., p. 451; 1961.
See also, J. M. Sellen and R. F. Kemp, "Cesium Ion Beam Neutralization in Vehicular Simulation," presented at American Rocket Society Meeting, Los Angeles, Calif., Paper No. 61-84-1778; June 13–16, 1961.
[11] S. L. Eilenberg, R. A. Hubach, and J. W. Ward, Hughes Research Labs., Malibu, Calif., private communication.

[12] S. L. Eilenberg, Hughes Research Labs., Malibu, Calif., private communication.
[13] See, for example, K. Spangenberg, "Vacuum Tubes," McGraw-Hill Book Co., Inc., New York, N. Y., p. 170; 1948.
[14] I. Langmuir and K. Blodgett, "Currents limited by space charge between coaxial cylinders," *Phys. Rev.*, vol. 22, pp. 347–356; 1923.
——, "Currents limited by space charge between concentric spheres," *Phys. Rev.*, vol. 24, pp. 49–59; 1924.
[15] J. B. Taylor and I. Langmuir, "The evaporation of atoms, ions and electrons from cesium film on tungsten," *Phys. Rev.*, vol. 44, pp. 423–458; September, 1933.
[16] These data were obtained from a comprehensive study of surface ionization being carried out by Dr. O. Husmann, Hughes Research Labs., Malibu, Calif.
[17] J. R. Pierce, "Rectilinear electron flow in beams," *J. Appl. Phys.*, vol. 11, pp. 548–554; March, 1940.
[18] G. R. Brewer, "Note on the determination of electrode shapes for a Pierce-type electron gun," *J. Appl. Phys.*, vol. 28, p. 634; May, 1957.
[19] M. P. Ernstene, *et al.*, "Development of High Efficiency Cesium Ion Engines," presented at National IAS-ARS Joint Meeting, Los Angeles, Calif., Paper No. 61-83-1777; June 13–16, 1961.
[20] J. E. Etter, *et al.*, "The Development of a Flight Test Ion Engine," presented at American Rocket Society Meeting, Los Angeles, Calif., Paper No. 61-81-1775; June 13, 1961.
[21] J. R. Anderson, *et al.*, "Evaluation of Ion Engine Performance," Am. Roc. Soc., Paper No. 2185-61; October 9–13, 1961.
[22] H. R. Kaufman, "An Ion Rocket with an Electron Bombardment Source," Lewis Research Center, Cleveland, Ohio, NASA Technical Note D-585; 1960.
[23] A. von Engel, "Ionized Gases," Oxford Clarendon Press, New York, N. Y., ch. 3; 1955.
[24] H. R. Kaufman and P. D. Reader, "Experimental Performance of Ion Rockets Employing Electron-Bombardment Ion Sources," presented at Am. Rocket Soc. Electrostatic Propulsion Conf., Monterey, Calif., Paper No. 1374-60; November 3, 1960.
[25] P. D. Reader, "Experimental Effects of Scaling on the Performance of Ion Rockets Employing Electron Bombardment Ion Sources," presented at National IAS-ARS Joint Meeting, Los Angeles, Calif.; June 13, 1961.
[26] J. S. Luce, "Ion Erosion of Accelerating Electrodes in Space Vehicles," presented at Am. Rocket Soc. Meeting, Los Angeles, Calif., Paper No. 1159-60; May 9, 1960.
[27] M. Von Ardenne, "Electronenphysik, Ionenphysik und Übermikrosckopie," VEB Deutscher Verlag der Wissenschaften, Berlin, Germany, p. 554; 1956.
[28] R. J. Hayes, C. A. Heubner, and J. M. Glassmeyer, "The
[28] X. X. Hayes, X. X. Heubner, and X. X. Glassmeyer, "The Duo-Plasmatron Ion Rocket," MIT, Cambridge, Mass., M.S. Thesis; 1960.
[29] L. Spitzer, "Physics of Fully Ionized Gases," Interscience Publishers, Inc., New York, N. Y., 1955.
[30] B. S. Burton, "The Duoplasmatron; Theoretical and Experimental Studies," presented at Electrostatic Propulsion Conf., Monterey, Calif.; November, 1960.
[31] Dr. S. Nablo, Goodrich-High-Voltage Astronautics, Burlington, Mass., private communication.
[32] D. Rose, "Acceleration of a neutralized ion beam," Research Labs. on Electronics, M.I.T., Cambridge, Mass., RLE Quarterly Rept. No. 53, p. 3; April 15, 1959.
[33] F. Salz, R. G. Meyerand, *et al.*, "Electrostatic potential gradients in a Penning discharge," *Phys. Rev. Lett.*, vol. 6, pp. 523–525; November 10, 1961.
[34] J. W. Davis, *et al.*, "Theoretical and Experimental Descriptions of the Oscillating Electron Ion Engine," presented at National IAS-ARS Joint Meeting, Los Angeles, Calif.; June 13–16, 1961.
[35] J. S. Luce, "Intense gaseous discharges," *Proc. 2nd U. N. Internatl. Conf. on Peaceful Uses of Atomic Energy*, Geneva, Switzerland, vol. 31, pp. 305–314; 1958.
[36] The assumption in the present considerations is that plasma heat is considered nonrecuperable and is therefore equivalent energy loss.
[37] S. T. Demetriades and R. W. Ziemer, "Direct Thrust and Efficiency Measurements of a Continuous Plasma Accelerator," *Am. Rocket Soc. J.*, to be published.
[38] G. M. Giannini, "The Arc Jet," presented at 2nd Symp. on Advanced Propulsion Concepts, Boston, Mass.; October 7–8, 1959.
[39] L. Spitzer, "Physics of Fully Ionized Gases," Interscience Publishers, New York, N. Y., p. 84; 1956.
[40] S. Chandrasekchar, "Plasma Physics," University of Chicago Press, Chicago, Ill., p. 211, Eq. (134); 1960.
[41] The importance of the last term of (32) in a non-fully-ionized gas and the subsequent condition (40) for the optimum magnetic field have been brought to the authors' attention by Dr. S. T. Demetriades. Because of its apparent agreement with experimental results of Demetriades, the above theory has been outlined in spite of its possibly controversial character.
[42] S. T. Demetriades, "Operating Characteristics of Continuous MGD Engines," Norair Div., Northrup Co., Hawthorne, Calif., Rept. ASG-TM-61-6; 1961.
[43] Because of the lack of data on μ_{ia}, it is assumed that the ion-neutral collision cross section equals the neutral-neutral collision cross section. This, of course, may be a poor approximation.
[44] The acceleration efficiency is the efficiency of transfer of ordered kinetic energy from the electric power supply to the plasma beam injected into the plasma accelerator.
[45] It is possible that overheating of the electrodes could be limited to some extent by the existence of a temperature gradient across the plasma streams. Preliminary experimental evidence to this effect has been obtained by S. T. Demetriades (private communication).
[46] This subdivision is somewhat superficial, of course, as in all three cases the force exerted on the plasma does result from the interaction between a traveling magnetic field and the currents which it induces in the plasma.
[47] T. G. Cowling, "Magnetohydrodynamics," Interscience Publishers, Inc., New York, N. Y., p. 4; 1957.
[48] Devices of the type shown in Figs. 27 and 29 have been proposed by M. U. Clauser, "The magnetic induction plasma engine," Space Technology Lab., Los Angeles, Calif., Rept. No. STL/TR-60-0000-00263; August 19, 1960.
Devices of the type shown in Fig. 30 have been proposed by R. X. Meyer, ("Magnetic Plasma Propulsion by means of a Traveling Sinusoidal Field," in "Plasma Acceleration," S. W. Kash, Ed., Stanford University Press, Stanford, Calif., p. 37; 1960) and are presently being investigated at the Space Technology Labs., Los Angeles, Calif.
[49] W. Eckhardt, private communication.
[50] D. Dow and R. C. Knechtli, "Plasma containment by r.f. and d.c. field combinations," *J. Electronics and Control*, vol. 7, pp. 316–343; November, 1959.
[51] A. S. Penfold, "Experimental Results Concerning the Electromagnetic Acceleration of Plasma Toroids," presented at 4th AFOSR Contractor's Meeting on Ion and Plasma Acceleration, Beverly Hills, Calif.; April 20–21, 1961.
[52] D. B. Miller, "Acceleration of Plasmas by Inductively Generated Electro-Magnetic Fields," University of Michigan Research Institute, Ann Arbor; April, 1961.
[53] J. Marshall, "Hydromagnetic plasma gun," in "Plasma Acceleration," S. W. Kash, Ed., Stanford University Press, Stanford, Calif., pp. 60–72; 1960.
[54] B. Garovity and P. Gloersen, "Experimental Performance of a Pulsed Gas Entry Coaxial Plasma Accelerator and Applications to Space Missions," presented at Am. Rocket Soc., New York, N. Y., Paper No. 1535-60; December, 1960.
[55] H. A. H. Boot, *et al.*, "Containment of a fully ionized plasma by r.f. fields," *J. Electronics and Control*, vol. 4, pp. 434–453; April, 1958.
[56] T. T. Reboul, C. D. Gordon, and G. A. Swartz, "Plasma Acceleration by a Quasistatic RF Electric Field Gradient," presented at ARS Meeting, Washington, D. C., Paper No. 1532-60; December 5–8, 1960.
[57] W. Eckhardt, private communication. This remark applies in particular to the model proposed by D. Rose for a plasma potential gradient due to the electron velocity distribution.

Transmission of Electromagnetic Waves Through an Ionized Layer in the Presence of a Strong Magnetic Field*

T. P. HARLEY†, MEMBER, IRE, AND G. TYRAS†, MEMBER, IRE

Summary—It is well known that the dielectric property of an ionized gas in the presence of a steady magnetic field is of tensorial character. Two of the three distinct components of this tensor are functions of the steady magnetic field. Generally, these two components decrease in magnitude with an increase of the steady magnetic field, thereby improving transmission of an RF wave.

The effect of a strong steady magnetic field on the transmission of an RF wave through a homogeneous and a stratified layer of ionized gas is illustrated by means of graphs. The graphs are based on certain fixed values of electron densities and collision frequencies and on certain fixed values of a steady magnetic field oriented parallel or normal to the interface, while the normally incident plane wave is either linearly or circularly polarized.

It was found that the best improvement in transmission is obtained when the steady magnetic field is normal to the interface and the oncoming plane wave is circularly polarized.

Introduction

A HYPERSONIC vehicle reentering the earth's atmosphere produces a strongly ionized, highly inhomogeneous plasma sheath about itself. This plasma sheath may degrade the transmission of RF energy for communication, guidance, and so forth, to a point below discernment. A steady magnetic field of sufficient strength produces the macroscopic effect of reducing the magnitudes of certain components of the permittivity tensor and thus tends to improve the transmission through the sheath.

The phenomena associated with the propagation of electromagnetic waves through homogeneous anisotropic plasma are well understood at present mainly due to work done in connection with ionospheric propagation.[1,2] The effect of a strong magnetic field (stronger than the earth's magnetic field which is about 0.4 gauss) on propagation was also investigated by Poeverlein,[3] who analyzed the effect of a strong steady magnetic field on the components of the permittivity tensor and predicted improvement of transmission for sufficiently strong, steady magnetic fields. This paper utilizes the results obtained by Tyras and Held[4] for analysis of transmission through inhomogeneous anisotropic plasma. The formula for the power transmission coefficient was programmed for the type 704 IBM digital computer to obtain the results in this paper.

The Transmission Formula

The theory of propagation through anisotropic layers may be found elsewhere.[4] Here we review only briefly the pertinent formulas leading to the results presented in this paper.

Consider the geometry of a stratified plasma in Fig. 1.




Fig. 1—Stratified plasma model.

The power transmission coefficient or the ratio of the transmitted power intensity to the incident power intensity for normal incidence of a plane wave linearly polarized along the x axis propagating in the positive z direction, is given by

$$\frac{P^t}{P^i} = |A^o|^2 \cos^2\phi + |A^e|^2 \sin^2\phi, \tag{1}$$

where $\theta = \pi/2$ (steady magnetic field in the plane of the interfaces) and

$$\frac{P^t}{P^i} = \tfrac{1}{2}\{|A^o|^2 + |A^e|^2\}, \tag{2}$$

* Received by the IRE, August 24, 1960; revised manuscript received, July 13, 1961. This paper was presented at the 4th Natl. Convention on Military Electronics, Washington, D. C., June 27–29, 1960.

† The Boeing Co., Aero-Space Div., Seattle, Wash.

[1] J. A. Ratcliffe, "The Magneto-Ionic Theory and Its Applications to the Ionosphere," Cambridge University Press, Cambridge, Eng., pp. 15–20; 1959.

[2] K. G. Budden, "Radio Waves in the Ionosphere," Cambridge University Press, Cambridge, Eng., pp. 47–57; 1961.

[3] H. Poeverlein, "Peculiar wave propagation characteristics of a plasma with constant magnetic field," paper delivered at AFCRC Plasma Sheath Symp., Boston, Mass.; December 7–9, 1959.

[4] G. Tyras and G. Held, "On the propagation of electromagnetic waves through anisotropic layers," IRE Trans. on Antennas and Propagation, vol. AP-7, Special Supplement, pp. S296–S300; 1959.

when $\theta=0$ (steady magnetic field normal to the interfaces). If the incident plane wave is circularly polarized, that is $E_{oy}{}^{i}=\pm jE_{ox}{}^{i}$ and $\theta=\pi/2$, one gets

$$\frac{P^t}{P^i}=\tfrac{1}{2}\{\,|\,A^o\,|^2+|\,A^e\,|^2\}. \tag{3}$$

When $\theta=0$

$$\frac{P^t}{P^i}=\begin{cases}|\,A^e\,|^2 & \text{when} \quad E_{oy}{}^{i}=+jE_{ox}{}^{i}\\ |\,A^o\,|^2 & \text{when} \quad E_{oy}{}^{i}=-jE_{ox}{}^{i}.\end{cases} \tag{4}$$

The A's are given by

$$A^{o,e}=(1+\tanh\gamma_o{}^{o,e})\exp\left(-j\sum_{k=1}^{m}\psi_k{}^{o,e}\right)\cdot\prod_{k=1}^{m}\frac{1+\tanh\gamma_k{}^{o,e}}{1+\tanh\gamma_{k-1}{}^{o,e}\tanh\beta_k{}^{o,e}}, \tag{5}$$

where for both superscripts o and e

$$\tanh\gamma_i=\frac{n_i-n_{i+1}}{n_i+n_{i+1}}$$

$$\tanh\beta_i=\tanh(\gamma_i+\beta_{i+1})\exp(-j2\psi_i)$$

$$\psi_i=\frac{2\pi}{\lambda}n_il_i. \tag{6}$$

Note that $n_0=n_{m+1}=1$ and $\beta_{m+1}=0$. The n's are the indices of refraction given by the Appleton-Hartree formula

$$\left.\begin{matrix}n^o\\ n^e\end{matrix}\right\}=\sqrt{\epsilon\mp\eta}, \tag{7}$$

when the steady magnetic field is in the z direction and

$$n^o=\sqrt{\zeta}$$

$$n^e=\sqrt{\frac{\epsilon^2-\eta^2}{\epsilon}} \tag{8}$$

when the steady magnetic field is in the x-y plane. The parameters ϵ, ζ, and η are complex if the plasma is lossy and are given by

$$\epsilon=1-\frac{p^2(1-\sigma^2+q^2)}{\Delta}-j\frac{qp^2(1+\sigma^2+q^2)}{\Delta},$$

$$\zeta=1-\frac{p^2}{1+q^2}-j\frac{qp^2}{1+q^2},$$

$$\eta=\frac{\sigma p^2(\sigma^2-1+q^2)}{\Delta}-j\frac{2\sigma qp^2}{\Delta},$$

$$\Delta=[(\sigma+1)^2+q^2][(\sigma-1)^2+q^2], \tag{9}$$

where the p's, q's, and σ's are the ratios of plasma, collision, and the cyclotron frequency, respectively, to the carrier frequency.

Analysis of Results

The graphs of Fig. 2 show the power transmission coefficient for a single homogeneous layer of plasma with




Fig. 2—Transmission through a one-layer plasma subjected to different values of steady magnetic-field strengths. $l=60$ cm; $N=10^9$ electrons per cubic centimeter; and $V=10^8$ collisions per second.

an electron density of 10^9 electrons per cubic centimeter, a collision frequency of 10^8 collisions per second, and a layer thickness of 0.6 m. Several values of the steady magnetic field strengths are considered when the latter is oriented either normal or parallel to the interface and when the normally incident plane wave is either linearly or circularly polarized.

The graph of Fig. 3 depicts the situation of a stratified plasma under conditions similar to those above. The description of the stratifications is listed in Table I, and the total layer thickness is approximately 0.6 m as before. The plasmas in Table I are approximations of representative models for what may be considered as reentry-type inhomogeneous plasma.

It may be seen from the graphs of Figs. 2 and 3 that, in general, the magnitude of the transmitted power is a function of the wave polarization and the orientation and the magnitude of the steady magnetic field. The earth's magnetic field, which for the purpose of this paper was assumed to be 0.4 gauss, has no apparent effect on these changes in transmission.

It is interesting to examine the phenomena in transmission produced by a steady magnetic field stronger than that of the earth. Consider first the case of the steady magnetic field in the plane of interface ($\theta=\pi/2$), which is represented by curves 1, 2, and 3 of Figs. 2 and 3. We note that curve No. 1 is not affected by the steady magnetic field. This is not surprising, since in this case




Fig. 3—Transmission through an eight-layer plasma subjected to different values of steady magnetic-field strengths.

TABLE I

Stratification Number	Thickness (meters)	Electron Density (electrons per cubic centimeter)	Collision Frequency (collisions per second)
1	0.05	2.1×10^5	2.1×10^8
2	0.08	1.2×10^6	3.4×10^8
3	0.08	1.1×10^7	6.3×10^8
4	0.08	1.0×10^8	1.2×10^9
5	0.07	9.0×10^8	2.3×10^9
6	0.10	4.1×10^9	3.6×10^9
7	0.06	1.8×10^{10}	1.3×10^9
8	0.05	3.1×10^{10}	2.1×10^8

the alternating component of the electric field is along the steady magnetic field and thus there is no interaction. When the alternating electric field is perpendicular to the steady magnetic field, some interaction is expected to occur, and this can be noted by examination of the graphs.

The most pronounced effects of the steady magnetic field on transmission should, of course, be expected in the case where the magnetic field is normal to the interface so that the alternating electric field is always normal to it. Here we observe that the left-hand and right-hand circularly polarized waves are affected differently by the steady magnetic field. Moreover, the transmission curve of the linearly polarized signal always lies between transmission curves for left-hand and right-hand circularly polarized waves.

At lower frequencies, when the indices of refraction n' and n'' are much larger than unity, examination of the graphs of Figs. 2 and 3 will reveal that the transmission of the signal is independent of frequency. This comes about from the asymptotic behavior of (5). In the case of a homogeneous layer when the steady magnetic field is normal to the interface ($\theta=0$), it can be shown that

$$|A^{o,e}|^2 \xrightarrow[\omega\to 0]{} \frac{16c^2(\omega_o^2+\nu^2)}{l^2\omega_p^4}. \tag{10}$$

where $\omega_o = eB_o/m$, $\omega_p = e\sqrt{N/m\epsilon_o}$, and ν are the cyclotron, plasma, and collision frequency, respectively. A similar asymptotic limit can be derived for the case of the steady magnetic field in the plane of the interface.

Conclusions

It has been shown that a steady magnetic field of sufficient strength will enhance the transmission of radio waves through an ionized layer. The following further remarks are appropriate:

1) Transmission is generally better when the steady magnetic field is normal to the interface than when it is in the plane of the interface.
2) Improvement in the transmission due to a steady magnetic field is more pronounced at lower frequencies.
3) At frequencies low enough, the transmission is frequency independent and is proportional to the square of the steady magnetic field.

Acknowledgment

Thanks are extended to T. G. Dalby of The Boeing Company for his encouragement throughout the course of this investigation.

The Use of Magnetic Fields in the Elimination of the Re-Entry Radio Blackout*

H. HODARA†

Summary—**This paper reviews first the most significant results concerning wave propagation through the plasma sheath surrounding a re-entering missle; second, it presents a new evidence showing that the re-entry radio blackout can be eliminated when a static magnetic field of the order of 500 Gauss is applied through the sheath. The evidence is based on the results of an analysis of transmission and reflection losses taking place at a plasma-air interface. The analysis also shows that in the special case of the absence of collisions, ($\nu=0$) maximum transmission occurs when the signal frequency (ω) is half the gyrofrequency (ω_b); the ratio of transmitted to incident power, in this case, equals approximately the ratio of gyro to plasma frequency. This result is also shown to hold when collisions are present, provided that $\nu^2 \ll (\omega_b - \omega)^2$.**

Introduction

HYPERSONIC space vehicles re-entering the atmosphere are surrounded by a sheath of ions and free electrons known as a "plasma sheath." The mechanism by which the sheath is formed is described elsewhere and need not be repeated here.[1] The presence of the sheath reflects and attenuates propagating electromagnetic waves so severely that radio communications with re-entering space vehicles are temporarily interrupted. This interruption or "radio blackout" is a problem of concern, in particular with future manned flights when continuous radio contact with the ground is necessary.

Extensive work is being done on the radio-blackout problem. Several solutions have been proposed, such as recombination,[2] transpiration cooling,[3] and shaping of the re-entering vehicle;[4] all three methods attempt to reduce the electron concentration in the plasma sheath. Another method currently in use is to transmit above the plasma resonant frequency, as the attenuation is much less severe.[5] Finally, a method advocated by the author[6–8] and others[9] consists of altering the electromagnetic properties of the plasma by superposing a static magnetic field. Several comparative analyses of the above methods have been published;[10,11] the present paper discusses only the magnetic-field approach and presents new evidence showing that the re-entry radio blackout can be eliminated with relatively low magnetic fields of a few hundred Gauss.

Electromagnetic Properties of Plasma—Physical Justification of the Static Magnetic-Field Approach

The electromagnetic properties of plasmas have been discussed extensively in the literature and more recently in connection with microwave tubes[12] and the re-entry problem.[13] Electromagnetic plasma properties are best expressed in terms of three basic parameters: 1) electron-plasma resonant frequency ω_p, 2) electron collision frequency ν, and 3) electron gyrofrequency ω_b.

The plasma resonant frequency varies directly with the square root of the electron density N and plays a role which is analogous to that of the cutoff frequency of a waveguide; a lossless plasma cannot support wave propagation at frequencies below ω_p. The plasma resonant frequency is

$$\omega_p = \sqrt{\frac{Q^2}{M}\frac{N}{\epsilon_v}}. \tag{1}$$

(Q, M, and ϵ_v are, respectively, charge and mass of the electron and dielectric constant of free space in mks units.)

The collision frequency is a measure of the attenuation of electromagnetic waves in the plasma. When the collision frequency is zero, the attenuation is zero; as shown in another section of this paper, the attenuation is also zero when $\nu = \infty$.

* Received by the IRE, August 28, 1961. Portions of this paper are abstracted from the author's Ph.D. dissertation at the Illinois Institute of Technology, Chicago, Ill.

† The Hallicrafters Co., Chicago, Ill.

[1] W. B. Sisco and J. M. Fiskin, "Electromagnetic Wave Propagation in Shock Ionized Media," Douglas Aircraft Co., Long Beach, Calif., Engineering Paper No. 633; October, 1958.

[2] J. S. Butz, Jr., "Hypersonic aircraft," *Aviation Week*, vol. 70, pp. 156–169; June 22, 1959.

[3] K. R. Stehling, "Re-entry cooling," *Space/Aeronautics*, vol. 32, pp. 43–45; September, 1959.

[4] "Telemetry Blackout and Re-entry Radar Cross-Section for Different Re-entry Vehicles," Aeronutronic Div. of Ford Motor Co., Newport Beach, Calif., Tech. Rept. No. U-1029; October 20, 1960.

[5] K. M. Baldwin, O. E. Bassett, and E. I. Hawthorne, "Telecommunication during Re-entry," Avco Research: Symp. on the Plasma Sheath, Boston Mass.; December 7–9, 1959.

[6] H. Hodara, H. R. Raemer, and G. I. Cohn, "Space Communications during Re-entry," presented at the meeting of the IRE Professional Group on Space Electronics and Telemetry, Chicago, Ill.; February 12, 1960.

[7] H. Hodara, H. R. Raemer, and G. I. Cohn, "A new approach to space communications," *Proc. XIth Internatl. Astronautical Conf.*, Stockholm, Sweden; August 16–20, 1960.

[8] H. Hodara, "A New Approach to Space Communications during Re-entry," presented at 15th Annual Meeting, American Rocket Society, Washington, D. C., Paper No. 1529–60; December 5–8, 1960.

[9] G. T. Flesher, "On the Elimination of Communications Dropout during Space Vehicle Re-entry," *NAECON Proc.*, Dayton, Ohio; May 2–4, 1960.

[10] E. F. Dirsa, "The telemetry and communication problem of re-entrant space vehicles," Proc. IRE, vol. 48, pp. 703–713; April, 1960.

[11] I. L. Carbine, H. G. Adam, and W. C. Bunyea, "The Problem of Miss-Distance Measurement for Intercept of a Re-entry Body," New Mexico State University, Physical Science Lab., University Park, N. M., BTL P. O. No. D-232136; December 29, 1960.

[12] R. F. Whitmer, "Principles of microwave interactions with ionized media," *Microwave J.*, pt. II, Electron-Cyclotron Resonance, vol. 2, pp. 47–50, Sylvania Products Co., Microwave Physics Lab.; March, 1959.

[13] M. P. Bachynski, I. W. Johnston, and I. P. Shkarotsky, "Electromagnetic properties of high temperature air," Proc. IRE, vol. 48, pp. 347–356; March, 1960.

In the presence of a static magnetic field B_0, a free electron describes a circular motion in a plane normal to the field lines. It revolves at the gyrofrequency ω_b. The gyrofrequency increases directly with the strength of the magnetic field; it is a vector quantity defined by

$$\omega_b = -\frac{Q}{M} B_0. \tag{2}$$

(For an electron, $Q<0$ and ω_b has the same sense as B_0.)

The presence of a static magnetic field alters the electrons' motion in the plane transverse to B_0, thus introducing new propagation modes. Consider, for instance, an electromagnetic wave at a frequency $\omega<\omega_p$ in a collisionless plasma ($\nu=0$). When $B_0=0$, no propagation is possible. As B_0 increases, the radius of the electron's orbit decreases. When B_0 is infinite, the orbit's radius is zero and the electrons' motion in the transverse plane is frozen; no interaction takes place between electrons and an electromagnetic plane wave whose wave front is normal to B_0. Under these conditions, the medium is no longer dispersive; a "spectral window" is opened through which a plane wave travels as if in vacuum.

The preceding reasoning suggests the possibility that windows exist in the plasma over a finite frequency band for finite values of B_0. In particular, attention is directed to the existence of windows in the band of frequencies below plasma resonance. The spectral characteristics of a collisionless plasma in the presence of a static magnetic field are illustrated in Fig. 1; their derivation is given elsewhere.[8] The results are not new, as they stem from the classical Appleton-Hartree formula; they are presented graphically in terms of normalized frequencies

$$\Omega = \frac{\omega}{\omega_p} = \frac{f}{f_p} \tag{3a}$$

$$m = \frac{\omega_b}{\omega_p} = \frac{f_b}{f_p} \tag{3b}$$

Similar spectral characteristics have been published previously in unnormalized form.[12] Fig. 1 reveals the existence of a window below the gyrofrequency when a right-handed (RH) circularly polarized wave propagates in the direction of B_0 (longitudinal field). This mode of propagation is of interest since the location of the window is not dependent on the plasma resonant frequency. The window's location is determined solely by the strength of the static magnetic field independent of the electron density, provided that the plasma is collisionless. For instance, an unbounded collisionless plasma with 10^{12} electrons/cm^3 sustains wave propagation with no attenuation up to about 1 kMc when a static magnetic field of 357 Gauss is applied. On the other hand, Fig. 1 shows that, under the same conditions, a left-handed (LH) circularly polarized wave is transmitted free of attenuation down to about 1.2 kMc, provided the applied field is at least 2000 Gauss. It does pay to select the "RIGHT" mode in order to eliminate radio blackout during re-entry.




Fig. 1—Spectral characteristics of collisionless plasma with dc magnetic field. Shaded areas are regions of no propagation.

Plane-Wave Analysis

The re-entry radio blackout is caused by the plasma cutoff characteristics, the attenuation losses due to collisions, the reflections taking place at interfaces or in regions of rapidly varying electron density, and the changes in the antenna-radiation pattern. The results on which the elimination of radio blackout is predicated in this paper are based entirely on a plane-wave analysis. Associated with a plane-wave analysis are several sources of errors. To mention a few: first, the signal wavelength is often long with respect to the thickness of the sheath, and second, the near fields from the antenna cannot be neglected. Considerable work, both experimental[14] and theoretical,[15–18] is being carried on in connection with the effects of the plasma sheath on the radiation pattern of antennas. Results from this work seem to confirm the validity of the plane-wave analysis.[18] Measurements of signal-attenuation loss at about 200 Mc for a dipole transmitting antenna immersed in a plasma stream 3 inches in diameter shows favorable comparison between experimental results and the results of a plane-wave analysis.[19] This last investigation supports the static magnetic-field approach based on such an analysis.

[14] R. L. Chuan, H. H. Kuehl, and Z. Kaprielian, "A Study of the Transmission of Radio Signals from a Hypersonic Vehicle," University of Southern California, Los Angeles, Calif., USCEC Rept. 70-101; June 30, 1960.

[15] J. R. Wait, "The Electromagnetic Fields of a Dipole in the Presence of a Thin Plasma Sheath," Natl. Bureau of Standards, Boulder, Colo., NBS Rept. 6083; April 4, 1960.

[16] H. H. Kuehl, "Radiation from a Gap-Excited Cylinder Surrounded by a Uniform Plasma Sheath," University of Southern California, Los Angeles, Calif., USCEC Rept. 71-202; June 30, 1960.

[17] C. M. Knop, "The radiation fields from a circumferential slot on a metallic cylinder coated with a lossy dielectric," IRE Trans. on Antennas and Propagation, vol. AP-9; November, 1961.

[18] H. Hodara and G. I. Cohn, "Radiation characteristics of slot antennas in the presence of a lossy anisotropic plasma sheath," *Proc. NEC*, Chicago, Ill.; October, 1961.

[19] P. W. Huber and P. G. Gooderun, "Experiments with Plasmas Produced by Potassium-Seeded Cyanogen Oxygen Flames for Study of Radio Transmission at Simulated Re-entry Vehicle Plasma Conditions," NASA, Washington, D. C., Tech. Note D-627; Washington, D. C.; January, 1961.

Effect of a Static Magnetic Field on Signal Transmission through Plasma

Attenuation and Phase Shift

The plane-wave theory yields the value of attenuation α and phase shift β when collisions are present in the plasma.[8] The results are presented graphically in Figs. 2–6 for an RH wave; the collision-frequency parameter ν is normalized with respect to ω_p as follows:

$$q = \frac{\nu}{\omega_p} = \frac{\nu/2\pi}{f_p} . \tag{4}$$

The curves in the figures display the well-known fact that collisions remove the discontinuities in the spectrum and make propagation possible at all frequencies with varying degrees of attenuation. Furthermore, the range over which the phase function β is linear increases with the collision frequency. The peaks and valleys of the β-curves (Figs. 5 and 6) are typical of the rapid phase variations exhibited by lossy media near resonance or cutoff.

Of major interest is the reduction in attenuation brought about when a static magnetic field is applied.




Fig. 2—Normalized attenuation vs normalized frequency, RH wave. Variable static longitudinal magnetic field m; fixed collision frequency $q=0.1$.






Fig. 3—Normalized attenuation vs normalized frequency, RH wave. Variable static longitudinal magnetic field m; fixed collision frequency $q=1.0$.



(a)



(b)

Fig. 4—(a) Normalized attenuation vs normalized frequency, RH wave. Variable static longitudinal magnetic field m; fixed collision frequency $q=5.0$. (b) Normalized loss reduction vs normalized frequency.




Fig. 5—Normalized phase shift vs normalized frequency, RH wave. Variable static longitudinal magnetic field m; fixed collision frequency $q=0.05$.




Fig. 6—Normalized phase shift vs normalized frequency, RH wave. Variable static longitudinal magnetic field m; fixed collision frequency $q=0.5$.

The reduction caused by the magnetic field is more significant at low ($q<1$) collision frequencies. From the data of Figs. 2–4, a loss reduction factor R in decibels is plotted vs Ω. The factor R gives the loss reduction with several values of applied static magnetic field at various collision frequencies. R is given by:

$$R(\text{db}) = 20 \log_{10} \frac{E_{q,m}}{E_{q,0}} = (20 \log_{10} e)(\alpha_{q,0} - \alpha_{q,m})z. \quad (5)$$

$E_{q,m}$ is the reduction in the electric-field amplitude over a distance of z-meters in the plasma for a given normalized collision frequency q and gyrofrequency m. $E_{q,0}$ is the reduction under the same conditions when the static magnetic field is absent ($m=0$). $\alpha_{q,m}$ and $\alpha_{q,0}$ are the attenuation factors in nepers per meter at some collision frequency q for gyrofrequencies m and zero, respectively. The abscissa R in Fig. 4(b) is normalized with respect to z and ω_p ($c_v = 3\times10^8$ m/sec, $8.68 = 20 \log_{10} e$); the relative decibel reduction in attenuation attained with a magnetic field increases directly with the operating frequency, the plasma resonant frequency and the thickness of the sheath.

On the other hand, there is little improvement in loss reduction at high collision frequencies ($q=5$) when moderate magnetic fields are used ($m=0.5$). For instance, assume a plasma resonant frequency of 10 kMc, a collision frequency of 6 kMc ($q=0.1$), a sheath thickness of 4 cm, a magnetic field of 357 Gauss ($m=0.1$), and an operating frequency of 500 Mc. Under these conditions, the loss reduction is 7 db; if the magnetic field is increased fivefold, the reduction in attenuation is 35 db. When collisions increase to 50 kMc ($q=5$), the absolute attenuation is considerably lessened while the relative loss reduction caused by a static magnetic field is minor; thus, 2000 Gauss are required to further reduce the attenuation by 2 db. The benefits to be derived from the application of a static magnetic field are significant at collision frequencies below plasma resonance; for a given magnetic field, the loss reduction factor R increases considerably as ν decreases. When the re-entry blackout occurs, ν is believed to be of the order of $0.1\ f_p$;[11] under such conditions, an extrapolation of the curves of Fig. 4(b) shows a 70-db reduction in attenuation when the applied static magnetic field is 350 Gauss, if $f=500$ Mc and $f_p=10$ kMc.

Reflection Losses

The presence of a plasma-air interface creates additional losses in the signal transmitted through the sheath. In the present paper, an expression is derived for the power transmitted into a semi-infinite plasma slab. The slab has constant electron density and constant collision frequency; it is threaded by a static magnetic field normal to the interface and parallel to the direction of propagation. Work is in process to extend the analysis to a plasma sheath of finite thickness; however, the results obtained from the present analysis are of considerable interest. When a linearly polarized TEM wave impinges on the interface, both RH and LH waves are generated. Straightforward application of Maxwell's equations and boundary conditions yields the following expressions for the reflected fields in terms of the incident fields E_{x1}^+ and H_{y1}^+:

$$E_{x1}^- = \frac{1 - y_R y_L}{(1 + y_R)(1 + y_L)} E_{x1}^+, \quad (6)$$

$$E_{y1}^- = j \frac{y_R - y_L}{(1 + y_R)(1 + y_L)} E_{x1}^+, \quad (7)$$

$$H_{x1}^- = - j \frac{y_R - y_L}{(1 + y_R)(1 + y_L)} H_{y1}^+, \quad (8)$$

$$H_{y1}^- = - \frac{1 - y_R y_L}{(1 + y_R)(1 + y_L)} H_{y1}^+. \quad (9)$$

The subscript 1 refers to free space, the superscripts + and − refer respectively to incident and reflected waves. The symbols R and L indicate RH and LH waves, and the subscript 2 in the expressions which follow refers to the plasma medium.

$$E_{x2}^{R,L} = \frac{1}{1 + y_{R,L}} E_{x1}^+ \quad (10)$$

$$H_{y2}^{R,L} = \frac{y_{R,L}}{1 + y_{R,L}} H_{y1}^+. \quad (11)$$

The other components are related by

$$E_{x2}^R = j E_{y2}^R, \quad (12)$$

$$E_{x2}^L = - j E_{y2}^L, \quad (13)$$

$$H_{x2}^R = j H_{y2}^R, \quad (14)$$

$$H_{x2}^L = - j H_{y2}^L. \quad (15)$$

y_R and y_L are the wave admittances of the plasma normalized with respect to the characteristic admittance of free space. y_R and y_L are identical to the complex index of refraction of the plasma for the RH and LH mode; they are given by the following:

$$y_R = \sqrt{1 + \frac{1}{\Omega[(m - \Omega) + jq]}} \quad (16)$$

$$y_L = \sqrt{1 - \frac{1}{\Omega[(m + \Omega) - jq]}}. \quad (17)$$

In the absence of collisions, (16) and (17) reduce to the familiar expressions for the index of refraction in terms of the denormalized parameters ω_b and ω_p:

$$y_R = \sqrt{1 + \frac{\omega_p^2}{(\omega_b - \omega)\omega}} \quad (18)$$

$$y_L = \sqrt{1 - \frac{\omega_p^2}{(\omega_b + \omega)\omega}}. \quad (19)$$

The power transmitted into the plasma is calculated as follows:

$$P_+ = \tfrac{1}{2}\Re(\boldsymbol{E} \times \boldsymbol{H}^*). \tag{20}$$

$\Re$ means "real part of," and the asterisk indicates conjugate values. Substitution of (6) to (15) into (20) gives the transmitted to incident power ratio p:

$$p = \frac{P_r}{P_{in}} = \frac{P_r}{\tfrac{1}{2}E_x{}^+H_y{}^+} \tag{21}$$

$$p = \frac{2\Re y_R{}^*}{|1 + y_R|^2} + \frac{2\Re y_L{}^*}{|1 + y_L|^2}. \tag{22}$$

The power ratio for the *RH* wave is

$$p_R = \frac{2\Re y_R{}^*}{|1 + y_R|^2} = \frac{y_R + y_R{}^*}{|1 + y_R|^2}. \tag{23}$$

Similarly for the *LH* wave,

$$p_L = \frac{2\Re y_L{}^*}{|1 + y_L|^2} = \frac{y_L + y_L{}^*}{|1 + y_L|^2}, \tag{24}$$

and the total transmitted to incident power ratio p is given by

$$p = p_R + p_L. \tag{25}$$

The ratio is plotted in Fig. 7 for the collisionless case ($q = 0$). It reaches a peak at $\omega = \omega_b/2$. When $\omega_b < 0.10\ \omega_p$, the maximum ratio is approximately $m = \omega_b/\omega_p$. For instance, let $f_p = 10$ kMc; if a static magnetic field of 350 Gauss corresponding to a gyrofrequency of 1 kMc is applied, the maximum amount of power transferred into the plasma is 10 per cent of the incident power at 0.5 kMc. Increasing the static field fivefold only gives a 3-db improvement in power transfer. If the incident wave is right-handed polarized, no LH is generated in the medium and 3-db additional power penetrates the plasma, but no propagation takes place above gyrofrequency. When collisions are present, several important results stem from Figs. 8–10. For a given collision frequency, reflection losses at the interface are reduced when a static magnetic field is applied. The reduction is more significant at lower collision frequencies. For instance, if $\nu = 200$ Mc, $f_r = 2$ kMc and $\boldsymbol{B}_0 = 350$ Gauss, reflection losses are reduced approximately by 5 db below 200 Mc. Under the same condition, except for $\nu = 10$ kMc, a static field of 3500 Gauss reduces reflection losses by only 1.8 db. Another important result is the fact that when large magnetic fields are applied ($m = 5$), the collisions have little influence on reflection losses. In this case, reflection losses are determined mostly by the operating frequency. For low static fields the mismatch at the interface is lessened as the collision frequency increases. High collision frequencies not only decrease attenuation losses through the plasma but also decrease the reflection losses at the plasma-air interface. The reason for the reduction in reflection losses as collisions




Fig. 7—Transmitted to incident power ratio vs normalized frequency, RH wave. Variable static longitudinal magnetic field m; fixed collision frequency $q = 0$.




Fig. 8—Transmitted to incident power ratio vs normalized frequency, RH wave. Variable static longitudinal magnetic field m; fixed collision frequency $q = 0.1$.




Fig. 9—Transmitted to incident power ratio vs normalized frequency, RH wave. Variable static longitudinal magnetic field m; fixed collision frequency $q = 1.0$.




Fig. 10—Transmitted to incident power ratio vs normalized frequency, RH wave. Variable static longitudinal magnetic field m; fixed collision frequency $q = 5.0$.

increase is easily seen from Maxwell's second equation when $\omega_b = 0$:

$$\nabla \times \boldsymbol{H} = j\omega\epsilon_v \check{\epsilon}_r \boldsymbol{E}. \tag{26}$$

$\check{\epsilon}_r$ is the complex relative dielectric constant given by[8]

$$\check{\epsilon}_r = \epsilon_r + \frac{\sigma}{j\omega\epsilon_v} = 1 + \frac{\omega_p^2}{j\omega(\nu + j\omega)}. \tag{27}$$

Substitution of (27) into (26) gives

$$\nabla \times \boldsymbol{H} = \omega_p^2 \epsilon_v \frac{\nu}{\nu^2 + \omega^2} \boldsymbol{E} + j\omega\epsilon_v \left(1 - \frac{\omega_p^2}{\nu^2 + \omega^2}\right) \boldsymbol{E}. \tag{28}$$

The first term on the RHS of (28) is the conductance current in phase with $\boldsymbol{E}$. The second term is the displacement current. Rewriting (28),

$$\nabla \times \boldsymbol{H} = \sigma \boldsymbol{E} + j\omega\epsilon_v\epsilon_r \boldsymbol{E}, \tag{29}$$

σ is the effective conductivity of the medium and ϵ_r the effective relative dielectric constant; they are given by the following:

$$\sigma = \omega_p^2 \epsilon_v \frac{\nu}{\nu^2 + \omega^2} \tag{30}$$

$$\epsilon_r = 1 - \frac{\omega_p^2}{\nu^2 + \omega^2}. \tag{31}$$

σ becomes zero at $\nu = 0$ as well as $\nu = \infty$; it follows that signals through the plasma suffer little attenuation at low collision frequencies:

$$\nu^2 \ll \omega^2 \tag{32a}$$

if

$$\omega_p^2 \ll \omega^2. \tag{32b}$$

Similarly, they suffer little attenuation at high collision frequencies:

$$\nu^2 \gg \omega^2 \tag{33a}$$

if

$$\frac{\nu}{\omega} \gg \frac{\omega_p^2}{\omega^2}. \tag{33b}$$

The low attenuation at high collision frequencies occurs because the electrons, having a mean free path of small duration, do not have enough time to abstract energy from the incoming wave and convert it into incoherent radiation.

The conductivity is maximum at $\nu = \omega$; maximum attenuation, however, does not occur at this frequency since it depends on the power factor of the medium, that is, on σ as well as $\omega\epsilon$.

From (16) and (17) it is seen that the curves for power transfer in the collisionless slab (Fig. 7) apply to the lossy plasma provided that

$$q^2 \ll (m - \Omega)^2 \tag{34a}$$

or

$$\nu^2 \ll (\omega_b - \omega)^2. \tag{34b}$$

Conclusion as to the Practical Feasibility of the Static Magnetic-Field Approach

The preceding discussion shows that magnetic fields of a few hundred Gauss are sufficient to reduce appreciably the attenuation loss through the plasma sheath and the reflection loss at the plasma-air interface during re-entry, thus possibly allowing uninterrupted communications. Justification of the plane-wave analysis is borne out by recent experimental work at NASA[19] and theoretical work by the author.[18]

A feasible antenna system is described by Carbine, *et al.*, in a recent report.[11] The antenna is circularly polarized, of the spiral type, 12 in in diameter, and designed to operate at 250 Mc. The magnetic field is generated by means of a 1000-turn coil and no. 10 aluminum wire. The coil weighs about 35 lbs and dissipates 150 watts; a standard 28-v dc source is used. The magnetic-field intensity is expected to reach about 500 Gauss at the boundary layer, where the plasma sheath reaches its highest electron concentration. To save power consumption, the system would be programmed to be turned on shortly prior to re-entry.

RF Reflectance of Plasma Sheaths*

LEONARD S. TAYLOR†, MEMBER, IRE

Summary—**The wave equation for the propagation of a TE wave in a plane stratified plasma sheath is solved by the method of series, and an expression for the reflection coefficient is abstracted. In special cases the series may be identified with certain known functions, and simple formulas for the reflectance are obtained. In general, however, the reflection coefficient appears as the ratio of complex infinite series.**

I. Introduction

THE presence of ionized layers about reentry and other high speed vehicles in the atmosphere has created interest in the propagation of electromagnetic radiation in stratified plasmas. In these layers, ionization levels of the order of a per cent at temperatures of several thousand degrees Kelvin are achieved. In view of the physical dimensions of the objects and the wavelengths involved, it is often a legitimate approximation to consider the interaction of the field and the plasma in terms of a plane wave propagating into a plane stratified medium.[1] This approximation is also valid when the application of the results to ionospheric soundings are required. The present study, which is largely a review, shall be restricted to the TE wave geometry (Fig. 1). It is assumed that the plasma is bounded to the right by a plane infinite metal wall.




Fig. 1—TE wave geometry.

This latter assumption offers no real restriction since, in most cases, we are assured on physical grounds that the radiation does not effectively penetrate deeply into the plasma, particularly when high ionization densities exist in the plasma. Thus the insertion of a wall at these depths will not affect the situation, and offers mathematical advantages. We shall also assume that the variation of ionization density may be adequately represented as a parabolic function of the depth. Thus the results will encompass certain special solutions previously obtained[2,3] but not those cases[4,5] of density variations with z^{-2} or e^z, which have been considered at length elsewhere. Although the results are sufficient to determine the fields in the plasma, primary interest will be centered in the (voltage) reflection coefficient R of the sheath.

II. The Wave Equation

To begin, we review the theoretical background of the wave equation for the field component. In a medium stratified the in z-direction, Maxwell's equation for the propagation of a TE wave ($E_y = E_z = 0$) reduce to the scalar set,[6]

$$\begin{aligned}
&\frac{\partial H_z}{\partial y} - \frac{\partial H_y}{\partial z} - \frac{i\epsilon\omega}{c} E_x = 0 \\
&\frac{\partial H_x}{\partial z} - \frac{\partial H_z}{\partial x} = 0 \\
&\frac{\partial H_y}{\partial x} - \frac{\partial H_x}{\partial y} = 0 \\
&\frac{\partial E_x}{\partial z} + \frac{i\omega\mu}{c} H_y = 0 \\
&\frac{\partial E_x}{\partial y} - \frac{i\omega\mu}{c} H_z = 0 \\
&H_x = 0,
\end{aligned} \tag{1}$$

where we use Gaussian units and assume that the fields vary as $e^{i\omega t}$. Eq. (1) shows that H_y, H_z, E_x are functions of y and z only. When we eliminate the magnetic field components, and assume $\mu = 1$, these equations reduce to the scalar wave equation

$$\nabla^2 E_x(y, z) + n^2 k_0^2 E_x(y, z) = 0, \tag{2}$$

where $n^2 = \epsilon$ and $k_0 = \omega/c = 2\pi/\lambda_0$. A separation of variables in conjunction with the boundary conditions is sufficient to show that

$$E_x(y, z) = u(z) e^{ik_0(\sin\theta_i)y} \tag{3}$$

* Received by the IRE, September 5, 1961. This work was supported by Air Force Contract 30(602)-1968.

† General Electric Space Sciences Lab., Valley Forge, Pa.

[1] The reader is referred to L. M. Brekhovskikh, "Waves in Layered Media," Academic Press, Inc., New York, N. Y., 1960, as a general reference.

[2] F. A. Albini and R. G. Jahn, "Reflection and transmission of electromagnetic waves at electron density gradients," *J. Appl. Phys.*, vol. 32, pp. 75–82; January, 1961.

[3] L. S. Taylor, "Microwave reflection and absorption by a nonuniform plasma sheath," *Proc. 2nd Symp. on Engineering Aspects of Magnetohydrodynamics*, Philadelphia, Pa., March, 1961; Columbia University Press, New York, N. Y.

[4] L. S. Taylor, "Electromagnetic propagation in an exponential ionization density," IRE Trans. on Antennas and Propagation, vol. AP-9, pp. 483–487; September, 1961.

[5] L. S. Taylor, "Reflection of a TE wave from an inverse parabolic ionization density," IRE Trans. on Antennas and Propagation, vol. AP-9, p. 582; November, 1961.

[6] M. Born and E. Wolf, "The Principles of Optics," Pergamon Press, Inc., New York, N. Y., pp. 50–54; 1959.

where θ_i is the angle of incidence and $u(z)$ satisfies

$$\frac{d^2u(z)}{dz^2} + k_0^2(n^2 - \sin^2\theta_i)u(z) = 0. \tag{4}$$

The form of (3) is an expression of the generalized Snell's Law, $k \sin\theta = \text{constant}$.

The dielectric constant which appears in (1) is, in general, complex. It is related to the complex conductivity by the usual formula

$$\epsilon = \epsilon_0 + 4\pi\sigma/i\omega, \tag{5}$$

where we take $\epsilon_0 = 1$ in the plasma and $\sigma = J/E$; σ may be derived[7] by considering the motion of electrons in the plasma (neglecting the ion current) as the sum of the individual electron velocities. The individual electron velocities may be represented as a sum of the isotropic thermal velocity $\dot{r}(t)$ plus a field-induced drift velocity $\dot{r}'(t)$. The equation of motion of an individual electron (charge $-e$, mass m) can therefore be written as

$$\begin{aligned}\ddot{r}_{tot}(t) &= \ddot{r}(t) + \ddot{r}'(t)\\ &= \boldsymbol{F}(t)/m + r'(t)\cdot[\text{grad}_r \boldsymbol{F}(t)]/m\\ &\quad + \dot{r}'(t)\cdot[\text{grad}_{\dot{r}} \boldsymbol{F}(t)]/m - e\boldsymbol{D}e^{i\omega t}/m\\ &\quad + 8\pi e\boldsymbol{P}e^{i\omega t}/3m,\end{aligned} \tag{6}$$

where $\boldsymbol{F}(t)$ represents the stochastic force due to collisions between the electron and the other particles and $\boldsymbol{D}$ is produced by the sources of the external field, which may be regarded as the true charges on a parallel plate capacitor. Eq. (6) is derived by considering that the radiation-induced motion is a small perturbation of the thermal motion. The terms $\text{grad}_r \boldsymbol{F}(t)$ and $\text{grad}_{\dot{r}} \boldsymbol{F}(t)$ represent the small change of the collisional forces due to the radiation-induced displacement and velocity. The terms in $\dot{r}(t)$ and $\boldsymbol{F}(t)/m$ refer to the thermal motion only and may be cancelled. Thus

$$\begin{aligned}\ddot{r}'(t) &= r'(t)\cdot[\text{grad}_r \boldsymbol{F}(t)]/m + \dot{r}'(t)\cdot[\text{grad}_{\dot{r}} \boldsymbol{F}(t)]/m\\ &\quad - e\boldsymbol{D}e^{i\omega t}/m + 8\pi e\boldsymbol{P}e^{i\omega t}/3m.\end{aligned} \tag{7}$$

The average of the first term on the right of (7) is zero for collisions with neutral particles. For collisions with ions, this term has been shown by Darwin[8] to cancel the polarization field created by the displacement of the other electrons in the plasma so we may write

$$\ddot{r}'(t) = \dot{r}'(t)\cdot[\text{grad}_{\dot{r}} \boldsymbol{F}(t)]/m - e\boldsymbol{E}e^{i\omega t}/m. \tag{8}$$

After averaging over the orbits of the individual electrons, (8) yields the celebrated Lorentz phenomenological equation,

$$\overline{m\ddot{r}'(t)} = -m\nu_c\overline{\dot{r}'(t)} - e\boldsymbol{E}e^{i\omega t}, \tag{9}$$

for the motion of electrons in a plasma. The parameter ν_c is best described as a coefficient of dynamical friction. In the case of a slightly ionized gas, with isotropic scattering of the electrons by heavy neutral particles, ν_c may indeed be shown to be the electron collision frequency.[9] In other cases, it is customary to refer to ν_c as the effective collision frequency in the medium. Integrating (9) and comparing the current density so obtained with the driving field, yields the complex conductivity

$$\sigma(z) = -iN(z)e^2/m(\omega - i\nu_c), \tag{10}$$

where $N(z)$ is the electron number density.

Combining (10) with (4) and (5), we find

$$\frac{d^2u(z)}{dz^2} + k_0^2\left[\cos^2\theta_i - \frac{4\pi e^2N(z)}{m\omega^2(1 - i\nu_c/\omega)}\right]u(z) = 0. \tag{11}$$

It shall be assumed that ν_c may be treated as a constant independent of z. This assumption requires justification in individual cases, but following an argument similar to one introduced previously,[2] the comparative sensitivity of the dielectric constant to variations of ν_c and N may be estimated from

$$\frac{\left(\frac{\partial\epsilon}{\partial z}\right)_{\nu_c}}{\left(\frac{\partial\epsilon}{\partial z}\right)_{N}} = \frac{\left(\frac{\partial\epsilon}{\partial N}\right)_{\nu_c}\frac{dN}{dz}}{\left(\frac{\partial\epsilon}{\partial\nu_c}\right)_{N}\frac{d\nu_c}{dz}} = (1 - i\omega/\nu_c)\frac{d[\ln N]}{d[\ln\nu_c]}. \tag{12}$$

Thus the effect of collision frequency variations is small when the variation in the electron concentration is large compared to the variation in the collision frequency (especially in the case $\omega \gg \nu_c$, which is of particular interest). In Fig. 2, we display the results of aerodynamic calculations for a typical case of interest.[10] The magni-




Fig. 2—Aerodynamic electron densities and collision frequencies about a spherically blunted cone at Mach 21 and 160,000-foot altitude.

[7] O. Theimer and L. S. Taylor, "The dependence of the plasma conductivity on frequency and collision time," *Ann. Phys.*, vol. 11, pp. 377–392; November, 1960.

[8] C. G. Darwin, "The refractive index of an ionized medium. II," *Proc. Roy. Soc. A*, vol. 182, pp. 152–166; April, 1943.

[9] L. S. Taylor, "The conductivity of slightly ionized gases," *The Physics of Fluids* (to be published).

[10] H. G. Lew and V. A. Angelo, "Plasma Sheath Characteristics about Hypersonic Vehicles," GE Space Science Lab., Philadelphia, Pa., Tech. Information Ser. No. R60SD356; 1960.

tude of the quantity $d[\ln N]/d[\ln \nu_c]$ is of the order of 10 in this case. Finally, we write (12) in the form

$$\frac{d^2u(z)}{dz^2} + [\beta^2 - \gamma N(z)]u(z) = 0 \tag{13}$$

where

$$\beta = k_0 \cos\theta_i$$
$$\gamma = 4\pi e^2/mc^2(1 - i\nu_c/\omega) = \gamma_0/(1 - i\nu_c/\omega). \tag{14}$$

III. The Series Solution for the Reflection Coefficient

Under the assumption

$$N(z) = \sum_{r=0}^{M} q_r z^r \tag{15}$$

(M finite), the coefficients of the wave equation are everywhere holomorphic, it is possible to solve the wave equation by the method of series, and the series converge for finite z.[11] Thus,

$$u(z) = \sum_{s=0}^{\infty} c_s z^s. \tag{16}$$

This solution contains two arbitrary constants, c_0 and c_1. We rewrite the above in the form

$$u(z) = c_0 \sum_{s=0}^{\infty} a_s z^s + c_1 \sum_{s=0}^{\infty} b_s z^s, \tag{17}$$

where

$$a_1 = b_0 = 0, \qquad a_0 = b_1 = 1. \tag{18}$$

Therefore

$$u(0) = c_0, \qquad \left.\frac{du(z)}{dz}\right|_{z=0} = c_1. \tag{19}$$

In the left-hand plane, the wave consists of an incident wave of unit amplitude plus a reflected wave. Remembering that we have taken the positive exponential for the time dependence

$$u(z) = e^{+i\beta z} + Re^{-i\beta z}, \tag{20}$$

for $z \leq 0$ where R is the (complex) voltage reflection coefficient. The continuity of the field and its first derivative at $z = 0$ now requires that

$$c_0 = 1 + R$$
$$c_1 = i\beta(1 - R). \tag{21}$$

It is most convenient to work in terms of the normalized impedance

$$Z = \frac{1 + R}{1 - R} = i\beta c_0/c_1. \tag{22}$$

[11] E. G. C. Poole, "Introduction to the Theory of Linear Differential Equations," Dover Publications, Inc., New York, N. Y., pp. 4–6; 1960.

Finally, we apply the boundary condition $u(z_1) = 0$. Thus

$$c_0 \sum_{s=0}^{\infty} a_s z_1^s + c_1 \sum_{s=0}^{\infty} b_s z_1^s = 0. \tag{23}$$

As a result,

$$Z = -i\beta \sum_{s=0}^{\infty} b_s z_1^s \Big/ \sum_{s=0}^{\infty} a_s z_1^s, \tag{24}$$

completing the formal solution.

It is evident on physical grounds that at large z_1, the impedance becomes independent of z_1. This occurs when, because of the processes of refraction and absorption, the field does not penetrate effectively to the wall. We shall refer to this circumstance as the "infinite depth" case, and denote it by the subscript ∞.

Example: $N(z) = Constant$

As a first example, we consider the trivial case $N(z) = N$. Writing

$$\beta^2 - \gamma N = \alpha^2, \tag{25}$$

we have immediately

$$u(z) = c_0 \sum_{s=0,\ \text{even}}^{\infty} \frac{(-1)^{s/2}\alpha^s z^s}{s!} + \frac{c_1}{\alpha} \sum_{s=0,\ \text{odd}}^{\infty} \frac{(-1)^{(s-1)/2}\alpha^s z^s}{s!}. \tag{26}$$

Thus

$$Z = -\frac{i\beta}{\alpha} \sum_{s=0,\ \text{odd}}^{\infty} \frac{(-1)^{(s-1)/2}\alpha^s z_1^s}{s!} \Big/ \sum_{s=0,\ \text{even}}^{\infty} \frac{(-1)^{s/2}\alpha^s z_1^s}{s!}. \tag{27}$$

Of course, we recognize the series, with the result

$$Z = -\frac{i\beta}{\alpha} \tan \alpha z_1 = -\frac{\beta}{\alpha} \frac{e^{2i\alpha z_1} - 1}{e^{2i\alpha z_1} + 1}. \tag{28}$$

Taking the principal value (arg $\alpha < \pi$), we have in the case of infinite plasma depth

$$Z_\infty = \beta/\alpha. \tag{29}$$

Thus

$$R_\infty = \frac{\beta - \alpha}{\beta + \alpha}. \tag{30}$$

(Recalling that

$$\alpha^2 = k_0^2[n_p^2 - \sin^2\theta_i], \tag{31}$$

where n_p is the complex index of refraction of the plasma, we find

$$R_\infty = \frac{\cos\theta_i - \sqrt{n_p^2 - \sin^2\theta_i}}{\cos\theta_i + \sqrt{n_p^2 - \sin^2\theta_i}} \tag{32}$$

correctly.[12]) It may be noted that no rearrangement of the series solution was necessary to separate (26) into terms proportional to c_0 and c_1. This will occur whenever $N(z)$ is expressed in even powers of z only.

IV. Thin Sheath Case

Considering only plasmas which zero electron density at $z=0$, (13) may be written as

$$\frac{d^2u(z)}{dz^2} + [\beta^2 - \gamma(q_1z + q_2z^2 + \cdots)]u(z) = 0. \quad (33)$$

Thus the recursion relation for the coefficients of the series solution is

$$(n+2)(n+1)c_{n+2} + \beta^2c_n - \gamma q_1c_{n-1} - \gamma q_2c_{n-2} - \cdots = 0. \quad (34)$$

The first few coefficients are c_0, c_1,

$$c_2 = -\frac{\beta^2}{2}c_0,$$

$$c_3 = \frac{1}{6}(\gamma q_1c_0 - \beta^2c_1). \quad (35)$$

For sheaths that are thin compared to a wavelength, with a low electron density gradient, it is appropriate to retain only these first terms, with the result

$$u(z) \approx c_0\left[1 - \frac{\beta^2}{2}z^2 + \frac{1}{6}\gamma q_1z^3\right] + c_1\left[z - \frac{\beta^2z^3}{6}\right] \quad . \quad (36)$$

$$Z \approx -i\frac{\beta z_1 - \beta^3z_1^3/6}{1 - \beta^2z_1^2/2 + \gamma q_1z_1^3/6} \cdot \quad (37)$$

Thus

$$R = \frac{Z-1}{Z+1} \approx -\frac{1 + i(\beta z_1) - (\beta z_1)^2/2 + (\gamma q_1/\beta^3 - i)(\beta z_1)^3/6}{1 - i(\beta z_1) - (\beta z_1)^2/2 + (\gamma q_1/\beta^3 + i)(\beta z_1)^3/6} \cdot \quad (38)$$

(Thus, if the terms in $(\beta z_1)^3$ may be ignored also, we find $|R| = 1$.)

In general, the series are poorly convergent and best suited to machine computation, even for sheaths only a few wavelengths thick. If the variations in electron density are small over distances comparable to a wavelength, however, perturbation solutions of the wave equation may be employed.[13]

[12] N. K. H. Panofsky and M. Phillips, "Classical Electricity and Magnetism," Addison-Wesley Publishing Co., Reading Mass., p. 180; 1955.

[13] M. Klein, H. D. Greyber, J. I. F. King, and K. A. Brueckner, "Interaction of a Non-Uniform Plasma with Microwave Radiation," General Electric Co., Philadelphia, Pa., Tech. Information Ser. No. R59SD467; 1960.

V. Parabolic Density Profile

For many applications, a density variation

$$N(z) = q_1z + q_2z^2 \quad (39)$$

adequately represents the profile. We first consider two special cases of this formula.

Case 1: $q_2 = 0$

In the case of a linear ramp in electron density $q_2 = 0$, and the wave equation is

$$\frac{d^2u(z)}{dz^2} + [\beta^2 - \gamma q_1z]u(z) = 0. \quad (40)$$

It is indeed possible to carry out the series solution by the method discussed. The series thus obtained could then be identified with the Airy functions. In the present case, this is quite artificial and it is preferable to transform directly, writing

$$\zeta = -(\beta^2 - \gamma q_1z)/(\gamma q_1)^{2/3}. \quad (41)$$

We have Airy's equation:

$$\frac{d^2u}{d\zeta^2} - \zeta u = 0. \quad (42)$$

Thus

$$u = A\mathfrak{A}i(\zeta) + B\mathfrak{B}i(\zeta). \quad (43)$$

Extensive numerical results, based on calculations with somewhat different boundary conditions have been given previously.[2] In the present case, writing

$$\zeta_0 = \zeta(z=0) = -\beta^2/(\gamma q_1)^{2/3}$$
$$\zeta_1 = \zeta(z=z_1) = (-\beta^2 + \gamma q_1z_1)/(\gamma q_1)^{2/3} \quad (44)$$

and noting that

$$c_0 = u(z=0) = A\mathfrak{A}i(\zeta_0) + B\mathfrak{B}i(\zeta_0)$$
$$c_1 = \left(\frac{du}{dz}\right)_{z=0} = (\gamma q_1)^{1/3}[A\mathfrak{A}i'(\zeta_0) + B\mathfrak{B}i'(\zeta_0)]$$
$$u(z_1) = 0 = A\mathfrak{A}i(\zeta_1) + B\mathfrak{B}i(\zeta_1) \quad (45)$$

where the prime indicates differentiation with respect to ζ, we find

$$Z = \frac{i\beta}{(\gamma q_1)^{1/3}} \cdot \frac{\mathfrak{A}i(\zeta_0)\mathfrak{B}i(\zeta_1) - \mathfrak{A}i(\zeta_1)\mathfrak{B}i(\zeta_0)}{\mathfrak{A}i'(\zeta_0)\mathfrak{B}i(\zeta_1) - \mathfrak{A}i(\zeta_1)\mathfrak{B}i'(\zeta_0)} \cdot \quad (46)$$

In the limiting case of infinite depth,

$$0 < \arg \zeta_1 = \tfrac{1}{3}\arg \gamma < \pi/3, \quad (47)$$

and we may employ the asymptotic forms[14]

$$\mathfrak{A}i(\zeta_1) \sim \frac{1}{2\sqrt{\pi}}\zeta_1^{-1/4}\exp(-\tfrac{2}{3}\zeta_1^{3/2})$$
$$\mathfrak{B}i(\zeta_1) \sim \frac{1}{\sqrt{\pi}}\zeta_1^{-1/4}\exp(\tfrac{2}{3}\zeta_1^{3/2}). \quad (48)$$

[14] A. Erdelyi, "Asymptotic Expansions," Dover Publications, Inc., New York, N. Y., p. 95; 1956.

Whence

$$Z_\infty = \frac{i\beta}{(\gamma q_1)^{1/3}} \mathfrak{A}i(\zeta_0)/\mathfrak{A}i'(\zeta_0). \tag{49}$$

As described previously, the wall has disappeared back into the plasma. The condition $|\zeta_1| \gg 1$ is a rough estimate of the depth to which the field penetrates.

For steep density gradients, $|\zeta_0| \ll 1$, and the relation between the Airy function and the modified Bessel functions

$$\begin{aligned}\mathfrak{A}i(\zeta_0) &= \tfrac{1}{3}\zeta_0^{1/2}[I_{-1/3}(\tfrac{2}{3}\zeta_0^{3/2}) - I_{1/3}(\tfrac{2}{3}\zeta_0^{3/2})] \\ &\approx [3^{2/3}\Gamma(2/3)]^{-1} - [3^{4/3}\Gamma(4/3)]^{-1}\zeta_0 \end{aligned} \tag{50}$$

yields

$$Z_\infty = -i\beta[3^{2/3}\Gamma(4/3)/\Gamma(2/3)](q_1\gamma)^{-1/3}. \tag{51}$$

Case 2: $q_1 = 0$

In the event of a purely parabolic density variation[15] the wave equation

$$\frac{d^2u(z)}{dz^2} + [\beta^2 - \gamma q_2 z^2]u(z) = 0 \tag{52}$$

may be transformed by the substitutions

$$\begin{aligned}\xi &= (4\gamma q_2)^{1/4} z \\ \rho &= \tfrac{1}{2}[\beta^2(\gamma q_2)^{-1/2} - 1]\end{aligned} \tag{53}$$

into the Weber equation

$$\frac{d^2u}{d\xi^2} + [\rho + \tfrac{1}{2} - \tfrac{1}{4}\xi^2]u = 0. \tag{54}$$

In the present instance, it is useful to treat this equation in the following way: The usual transformation

$$u = e^{-\xi^2/4}v \tag{55}$$

is even in ξ (or z) and will not affect the identification of the appropriate coefficients. Upon substitution we find

$$\frac{d^2v}{d\xi^2} - \xi\frac{dv}{d\xi} + \rho v = 0. \tag{56}$$

The series solution leads to the recursion relation

$$a_{r+2} = \frac{r - \rho}{(r+1)(r+2)} a_r. \tag{57}$$

Thus

$$\begin{aligned} v_1 &= 1 - \frac{\rho}{2!}\xi^2 + \frac{\rho(\rho-2)}{4!}\xi^4 \\ &\quad - \frac{\rho(\rho-2)(\rho-4)}{6!}\xi^6 + \cdots \\ v_2 &= \xi - \frac{\rho-1}{3!}\xi^3 + \frac{(\rho-1)(\rho-3)}{5!}\xi^5 \\ &\quad - \frac{(\rho-1)(\rho-3)(\rho-5)}{7!}\xi^7 + \cdots . \end{aligned} \tag{58}$$

From (24) the impedance is

$$Z = -i\beta\frac{v_2(\xi_1)}{v_1(\xi_1)}\left(\frac{dz}{d\xi}\right). \tag{59}$$

In general, it is at this point that numerical work is required. In the present instance, however, these series may be identified with the Kummer series, which is derived from the confluent hypergeometric function[16]

$$\Phi(a, c; x) = 1 + \frac{a}{c}x + \frac{a(a+1)}{c(c+1)}\frac{x^2}{2!} + \cdots . \tag{60}$$

Thus

$$\begin{aligned} v_1 &= \Phi(-\tfrac{1}{2}\rho, \tfrac{1}{2}; \tfrac{1}{2}\xi^2) \\ v_2 &= \xi\Phi(\tfrac{1}{2} - \tfrac{1}{2}\rho, \tfrac{3}{2}; \tfrac{1}{2}\xi^2). \end{aligned} \tag{61}$$

Whence

$$Z = -i\beta\xi_1(4\gamma q_2)^{-1/4}\frac{\Phi(\frac{1}{2} - \frac{1}{2}\rho, \frac{3}{2}; \frac{1}{2}\xi^2)}{\Phi(-\frac{1}{2}\rho, \frac{1}{2}; \frac{1}{2}\xi^2)}. \tag{62}$$

But for Re $\{x\} \to \infty$

$$\Phi(a, c; x) \sim [\Gamma(c)/\Gamma(a)]e^x x^{a-c}. \tag{63}$$

Whence, in the case of infinite depth,

$$Z_\infty = -i\beta(\gamma q_2)^{-1/4}\Gamma(-\tfrac{1}{2}\rho)/2\Gamma(\tfrac{1}{2} - \tfrac{1}{2}\rho). \tag{64}$$

The gamma functions of complex argument have been tabulated.[17] Using this table, we find for example at $\lambda_0 = 3$ cm, $\nu_c/\omega = 0.1$ and $q_2 = 10^{12}$, $Z_\infty = 0.29 - 0.27i$, $|R_\infty| = 0.58$.

The result obtained in the foregoing paragraph now reduces the solution of the more general problem ($q_1 \neq 0 \neq q_2$) to a simple transformation. Writing the wave equation as

$$\frac{d^2u}{d\xi^2} + (\rho + \tfrac{1}{2} + \tau\xi - \tfrac{1}{4}\xi^2)u = 0, \tag{65}$$

[15] Since the writing of this article, an extensive treatment of this problem apropos to the ionosphere has been given by K. G. Budden, "Radio Waves in the Ionosphere," Cambridge University Press, England; 1961. (The formula for the reflection coefficient in this case was first given by O. E. H. Rydbeck, *Chalmers tek. Högskol. Handl.*, No. 34; 1944.) Many of the results obtained in this paper have also been independently obtained by D. J. BenDaniel and H. Hurwitz, Jr., "WKB Matching Conditions at Gradual Interfaces," GE Res. Lab., Internal Rept., Schenectady, N. Y. (to be published).

[16] Bateman Manuscript Project, "Higher Transcendental Functions," McGraw-Hill Book Co., Inc., New York, N. Y., vol. 1, ch. 6; vol. 2, ch. 8; 1955.

[17] U. S. Natl. Bur. Standards, Washington, D. C., "Tables of the Gamma Function for Complex Arguments," Applied Mathematics Series 34; 1954.

where $\tau = -\gamma^{1/4} q_1 (4q_2)^{-3/4}$, and completing the square with the substitutions

$$\xi = \xi' + 2\tau, \qquad \rho = \rho' - \tau^2, \tag{66}$$

reduces (65) to the Weber equation (54). Thus we recognize the series solution in the primed variables as

$$u = e^{-\xi^2/4} \left[A\Phi(-\tfrac{1}{2}\rho', \tfrac{1}{2}; \tfrac{1}{2}\xi'^2) + B\xi'\Phi(\tfrac{1}{2} - \tfrac{1}{2}\rho', \tfrac{3}{2}; \tfrac{1}{2}\xi'^2) \right]. \tag{67}$$

The coefficients c_0 and c_1 and the ratio A/B are obtained in (45). The relation[16]

$$\frac{d}{dx}\Phi(a, c; x) = \frac{a}{c}\Phi(a + 1, c + 1; x) \tag{68}$$

which may be derived by term-by-term differentiation of (60) has been used to arrive at the following expression for the impedance:

$$Z = + i\beta(4\gamma q_2)^{-1/4} \times \left[2\tau\Phi(\tfrac{1}{2} - \tfrac{1}{2}\rho', \tfrac{3}{2}; 2\tau^2) - \frac{A}{B}\Phi(-\tfrac{1}{2}\rho', \tfrac{1}{2}; 2\tau^2) \right] \times \left[(1 - 2\tau^2)\Phi(\tfrac{1}{2} - \tfrac{1}{2}\rho', \tfrac{3}{2}; 2\tau^2) + \tfrac{4}{3}\tau^2(1 - \rho')\Phi(\tfrac{3}{2} - \tfrac{1}{2}\rho', \tfrac{5}{2}; 2\tau^2) + \frac{A}{B}\tau\{\Phi(-\tfrac{1}{2}\rho', \tfrac{1}{2}; 2\tau^2) + 2\rho'\Phi(1 - \tfrac{1}{2}\rho', \tfrac{3}{2}; 2\tau^2)\} \right]^{-1}, \tag{69}$$

where $\xi_1' = \xi'(z = z_1)$,

$$\frac{A}{B} = -\xi_1'\Phi(\tfrac{1}{2} - \tfrac{1}{2}\rho', \tfrac{3}{2}; \tfrac{1}{2}\xi_1'^2)/\Phi(-\tfrac{1}{2}\rho', \tfrac{1}{2}; \tfrac{1}{2}\xi_1'^2). \tag{70}$$

In the case of an infinite effective depth, (70) reduces to

$$\frac{A}{B} = -\frac{\Gamma(-\frac{1}{2}\rho')}{\sqrt{2}\Gamma(\frac{1}{2} - \frac{1}{2}\rho')}. \tag{71}$$

VI. Conclusion

The methods outlined in the present work may be extended to electron density distributions containing cubic and higher order terms, either as outlined in Section IV, or by development of the wave function in functional series. In the latter case, it is possible to employ limiting forms to determine the solution in the infinite depth case. The utility of such formulas is limited, however, by the difficulty in abstracting numerical results from such formal solutions.

Correction

W. W. Siekanowicz, author of "A Small-RF-Signal Theory for an Electrostatically Focussed Traveling-Wave Tube," which appeared on pp. 1888–1901 of the November, 1960, issue of Proceedings, has called the following to the attention of the *Editor*.

On page 1891, (17) and (18), the denominator of the third term within the parentheses should be

$$2u_0^2 \text{ instead of } u_0^2.$$

On page 1892 (36), the upper term in the parentheses to the left of the equal sign should be

$$^{n+1}Q_{3a}.$$

The right-hand side of (45) should read as follows:

$$-2|\hat{K}|^2 \left\{ \frac{\omega_a}{u_a}(rg + d) + j2\omega_a\tau_i[e^{(\phi - j\theta_e)} - 1] \right\} \sin\theta.$$

On page 1893 (55), the term to the left of the equal sign should be

$$^{n}Q_{las}.$$

Mutual Coupling of Two Thin Infinitely-Long Slots Located on a Perfectly Conducting Plane in the Presence of a Uniform Plasma Layer*

JAMES S. YEE†, MEMBER, IRE

Summary—The investigation of antenna coupling was motivated by a study of communication with a hypersonic vehicle which upon re-entry, introduces a plasma sheath over the antennas. The model chosen for analysis consists of two infinitely-long thin slots on a ground plane covered by a uniform plasma layer which is assumed to be a lossless gaseous dielectric slab having a dielectric constant less than unity but greater than zero. The coupling effects are described in terms of a mutual admittance parameter in an equivalent π network from which other admittance parameters are derivable. The problem is formulated by spatial Fourier transforms which, upon inversion, would yield the desired results. The transform integral for the case of a thick plasma layer is evaluated approximately by the method of steepest descent. The results are explained in terms of multiple reflections of rays by the sharply defined plasma-air interface. When the quantities are plotted as functions of slot separation, the perturbations show up in the form of ripples about the curve for the unbounded plasma. In a realistic situation, there is no well-defined boundary and the rippling may show up in a statistical manner. The coupling effect is found to be less serious in the presence of a plasma than in its absence. When the operating frequency is appreciably higher than the plasma frequency, the change in driving point admittance is small. Also, inside a thick plasma layer, no unattenuating pole waves are excited.

I. Introduction

When two identical antennas are located near one another, mutual coupling effects exist. Various authors have studied the mutual coupling problem with regard to certain antenna geometry and antenna operating characteristics. For example, Lucke [1] studied the mutual admittance between slots located on the surface of a large-radius cylinder and compared the results with those in an infinite ground plane. Nishida [2], [3] investigated the effect of mutual coupling between two parallel slits located on a ground plane and on a cylinder on leaky-wave propagation. Edelberg and Oliner [4] considered mutual coupling effects in large slot antenna arrays.

The problem considered in this paper was motivated by a study of communication with a hypersonic re-entry vehicle such as the Dyna-Soar which introduces an additional interface into the antenna geometry. This interface is due to the plasma sheath that is created about the vehicle upon re-entry. When antennas are located within this sheath, it is important to investigate the effects which the sheath may have on the antenna operating characteristics. When the sheath is treated in its most elementary form as a gaseous dielectric slab [5], [6], the sheath problem in many respects resembles the solid dielectric interface problem of surface waves which has been studied quite extensively [7]—[10]. The techniques of analysis employed by these people are quite applicable to the present problem.

In this paper an attempt is made to study the effects of the plasma sheath on the antenna admittance parameters. The sheath is assumed to have a real dielectric constant less than unity but greater than zero. This assumption implies that the operating frequency is greater than the plasma frequency and that the electron-neutral particle collision frequency is negligible in comparison with the operating frequency. Because of the way the admittance parameters are defined, the problem is essentially one of finding the surface current due to the slot on the ground plane which is covered by a uniform plasma sheath.

II. Field Formulation

Consider a two-dimensional, double-layer problem as shown in Fig. 1. In this figure two parallel, infinitely-long thin slots (S_1 and S_2) separated by a distance z_0 are located on the surface of a perfectly conducting plane. Above this ground plane is a uniform plasma layer (Region II). It has a thickness a and equivalent electromagnetic parameters σ_2, μ_2, and ϵ_2, which are the conductivity, permeability, and permittivity of the region. On top of the plasma layer is free space (Region I) with equivalent electromagnetic parameters σ_1, μ_1, and ϵ_1. Let S_1 be the origin of a rectangular coordinate system. If $e^{i\omega t}$ time dependence is assumed, ω being the operating angular frequency, the fields are completely determined in each region by solving the differential equation for Hy^{I} and Hy^{II}:




Fig. 1—Uniform plasma layer on two thin, infinitely-long slots in a perfectly conducting plane.

* Received by the IRE, September 27, 1961.
† Antennas and Radomes Unit, Boeing Co., Seattle, Wash.

$$\frac{\partial^2 H_y^{\mathrm{I}}}{\partial x^2} + \frac{\partial^2 H_y^{\mathrm{I}}}{\partial z^2} + k^2 H_y^{\mathrm{I}} = 0 \qquad a \leq x < \infty \tag{1}$$

$$\frac{\partial^2 H_y^{\mathrm{II}}}{\partial x^2} + \frac{\partial^2 H_y^{\mathrm{II}}}{\partial z^2} + n^2 k^2 H_y^{\mathrm{II}} = 0 \qquad 0 \leq x \leq a \tag{2}$$

where

$$k^2 = \omega^2 \mu_1 \epsilon_1 \quad \text{and} \quad n^2 = \frac{\mu_2 \epsilon_2}{\mu_1 \epsilon_1} \qquad 0 < n \leq 1.$$

Other field components can be derived in terms of Hy^{I} and Hy^{II} from Maxwell's equations:

$$E_x^{\mathrm{I,II}} = -\frac{1}{i\omega\epsilon_{1,2}} \frac{\partial H_y^{\mathrm{I,II}}}{\partial z} \tag{3}$$

$$E_z^{\mathrm{I,II}} = \frac{1}{i\omega\epsilon_{1,2}} \frac{\partial H_y^{\mathrm{I,II}}}{\partial x} \tag{4}$$

$$E_y^{\mathrm{I,II}} = 0 \tag{5}$$

$$H_x^{\mathrm{I,II}} = H_z^{\mathrm{I,II}} = 0. \tag{6}$$

Let ϕ_1 and ϕ_2 be the spatial Fourier transforms of Hy^{I} and Hy^{II} respectively; then the transform pair associated with the magnetic field in each region is:

Region I

$$a \leq x < \infty$$

$$\phi_1(x, h) = \int_{-\infty}^{\infty} H_y^{\mathrm{I}}(x, z) e^{-ihz} dz \tag{7}$$

$$H_y^{\mathrm{I}}(x, z) = \frac{1}{2\pi} \int_{-\infty}^{\infty} \phi_1(x, h) e^{+ihz} dh \tag{8}$$

Region II

$$0 \leq x \leq a$$

$$\phi_2(x, h) = \int_{-\infty}^{\infty} H_y^{\mathrm{II}}(x, z) e^{-ihz} dz \tag{9}$$

$$H_y^{\mathrm{II}}(x, z) = \frac{1}{2\pi} \int_{-\infty}^{\infty} \phi_2(x, h) e^{+ihz} dh. \tag{10}$$

In terms of the Fourier transforms ϕ_1 and ϕ_2, the differential equations (1) and (2) reduce to one variable:

$$\frac{d^2\phi_1}{dx^2} - \lambda^2 \phi_1 = 0 \tag{11}$$

$$\frac{d^2\phi_2}{dx^2} - \mu^2 \phi_2 = 0 \tag{12}$$

where

$$\lambda^2 = h^2 - k^2 \tag{13}$$

$$\mu^2 = h^2 - n^2 k^2 \tag{14}$$

and the solutions of which can be written:

$$\phi_1 = A_1 e^{-\lambda x} \tag{15}$$

$$\phi_2 = A_2 e^{-\mu x} + A_3 e^{+\mu x} \tag{16}$$

where the real part of λ is positive when $|h| > k$ and equal to $+i\sqrt{k^2 - h^2}$ for outgoing waves when $|h| < k$.

The appropriate boundary conditions are the usual continuity of tangential fields along the interface and the vanishing of Ez^{II} everywhere along the ground plane except the slots which are assumed to be delta sources with voltages V_1 and V_2, respectively. The transforms ϕ_1 and ϕ_2 must necessarily satisfy similar conditions which are:

$$\phi_1\Big|_{x=a} = \phi_2\Big|_{x=a} \tag{17}$$

$$\frac{1}{\epsilon_1}\frac{d\phi_1}{dx}\Big|_{x=a} = \frac{1}{\epsilon_2}\frac{d\phi_2}{dx}\Big|_{x=a} \tag{18}$$

$$\frac{d\phi_2}{dx}\Big|_{x=0} = i\omega\epsilon_2 \left[\int_{S_1} E_{z_1}^{\mathrm{II}} e^{-ihz} dz + \int_{S_2} E_{z_2}^{\mathrm{II}} e^{-ihz} dz \right]. \tag{19}$$

Since the electric fields across the slots are constant, they are given by:

$$E_{z_1}^{\mathrm{II}} = V_1 \delta(z) \qquad \text{Slot 1 } (z = 0) \tag{20}$$

$$E_{z_2}^{\mathrm{II}} = V_2 \delta(z - z_0) \qquad \text{Slot 2 } (z = z_0) \tag{21}$$

where $\delta(z)$ and $\delta(z - z_0)$ are Dirac-Delta functions.

Incorporating the boundary conditions in (17), (18), and (19) leads to a set of three simultaneous equations for the coefficients A_1, A_2, and A_3:

$$e^{-\lambda a} A_1 - e^{-\mu a} A_2 - e^{+\mu a} A_3 = 0 \tag{22}$$

$$\frac{\lambda}{\epsilon_1} e^{-\lambda a} A_1 - \frac{\mu}{\epsilon_2} e^{-\mu a} A_2 + \frac{\mu}{\epsilon_2} e^{+\mu a} A_3 = 0 \tag{23}$$

$$\mu A_2 - \mu A_3 = -g(h) \tag{24}$$

where

$$g(h) = i\omega\epsilon_2 (V_1 + V_2 e^{-ihz_0}).$$

The solutions for the coefficients are:

$$A_1 = \frac{-2\, g(h)\epsilon_1}{e^{-\lambda a}(e^{+\mu a} + e^{-\mu a})(\mu\epsilon_1 \tanh \mu a + \lambda\epsilon_2)} \tag{25}$$

$$A_2 = \frac{-g(h)(\mu\epsilon_1 + \lambda\epsilon_2) e^{+\mu a}}{\mu(e^{+\mu a} + e^{-\mu a})(\mu\epsilon_1 \tanh \mu a + \lambda\epsilon_2)} \tag{26}$$

$$A_3 = \frac{-g(h)(\mu\epsilon_1 - \lambda\epsilon_2) e^{-\mu a}}{\mu(e^{+\mu a} + e^{-\mu a})(\mu\epsilon_1 \tanh \mu a + \lambda\epsilon_2)}. \tag{27}$$

In terms of the transforms, the magnetic field in each region is:

Region I

$$a \leq x < \infty$$

$$H_y^{\mathrm{I}}(x, z) = -\frac{1}{2\pi} \int_{-\infty}^{\infty} \frac{2g(h)\epsilon_1 e^{-\lambda(x-a)} e^{+ihz} dh}{(e^{+\mu a} + e^{-\mu a})(\mu\epsilon_1 \tanh \mu a + \lambda\epsilon_2)} \tag{28}$$

Region II

$$0 \leq x \leq a$$

$$H_y^{II}(x, z) = -\frac{1}{2\pi}\int_{-\infty}^{\infty} \frac{g(h)(\mu\epsilon_1 + \lambda\epsilon_2)e^{+ihz}}{\mu(1 + e^{-2\mu a})(\mu\epsilon_1 \tanh \mu a + \lambda\epsilon_2)} \cdot \left[e^{-\mu x} + \frac{\mu\epsilon_1 - \lambda\epsilon_2}{\mu\epsilon_1 + \lambda\epsilon_2} e^{-2\mu a}e^{+\mu x}\right] dh. \quad (29)$$

III. Admittance Parameters

In discussing the admittance characteristics of one slot in the vicinity of another it is convenient to represent the fields by a four-terminal π network as shown in Fig. 2. The circuit elements (Y_{11}) and (Y_{22}) are self-admittances of the respective slots. The mutual admittance (Y_{12}) is a measure of the coupling of one slot into the other. The circuit equations are:

$$I_1 = Y_{11}V_1 + Y_{12}V_2 \quad (30)$$

$$I_2 = Y_{21}V_1 + Y_{22}V_2. \quad (31)$$




Fig. 2—Equivalent circuit representation.

Define

$$Y_{12} = \frac{I_{21}}{V_1} \quad (32)$$

where I_{21} is the short-circuited current $(V_2 = 0)$ induced in slot S_2 due to the voltage excitation of V_1 in S_1. Similarly, the driving point admittance $(Y_1'$ and $Y_2')$ for each slot in the presence of the other is:

$$Y_1' = \frac{I_1}{V_1} \quad \text{when} \quad I_2 = 0$$

$$= Y_{11} - \frac{Y_{12}^2}{Y_{22}} \quad (33)$$

$$Y_2' = \frac{I_2}{V_2} \quad \text{when} \quad I_1 = 0$$

$$= Y_{22} - \frac{Y_{12}^2}{Y_{11}}. \quad (34)$$

The next step is to relate the circuit quantities to the appropriate fields. The surface current, I_{21}, per unit length in y is given by the magnetic field evaluated on the ground plane $x = 0$. It is defined as

$$\mathbf{a}_z I_{21} = \mathbf{a}_x \times \mathbf{a}_y H_{y_{21}}^{II}(0, z). \quad (35)$$

The voltage excitations of slot S_1 and S_2 are given by the line integrals of the tangential electric fields over the apertures. These are

$$V_1 = \int_{S_1} E_{z_1}^{II} dz = \int_{S_1} V_1\delta(z)dz \quad (36)$$

$$V_2 = \int_{S_2} E_{z_2}^{II} dz = \int_{S_2} V_2\delta(z - z_0)dz. \quad (37)$$

The assumption of delta slot sources reduces the mathematical complexities of the problem by avoiding a complicated integration of the field distribution over the apertures as shown in (36) and (37). In view of (35), the mutual admittance Y_{12} per unit length in y as defined in (32) is simply:

$$Y_{12} = -\frac{H_{y_{21}}^{II}(0, z_0)}{V_1}. \quad (38)$$

IV. Evaluation of Hy_{21}^{II}

To determine Y_{12} as shown in Section III, it is necessary to evaluate the integral for the magnetic field Hy^{II} at S_2 due to S_1 when $V_2 = 0$. This integral can be shown to exist for all physical situations. Of special interest is the case for an electrically thick plasma layer which most likely resembles the situation during re-entry. Fortunately, the integral for this case can be evaluated approximately by the method of steepest descent. Another case which is worth considering but is not discussed in this paper is that of an electrically thin plasma layer. The expression for Hy^{II} in this case is left in the integral form.

A. In the Presence of a Thick Plasma Layer

From (29) and when $x = 0$, $z = z_0$, and $V_2 = 0$, Hy_{21}^{II} becomes:

$$H_{y_{21}}^{II}(0, z_0) = -\frac{i\omega\epsilon_2 V_1}{2\pi} \cdot \int_{-\infty}^{\infty} \frac{(\mu\epsilon_1 + \lambda\epsilon_2)\left(1 + \frac{\mu\epsilon_1 - \lambda\epsilon_2}{\mu\epsilon_1 + \lambda\epsilon_2} e^{-2\mu a}\right)e^{+ihz_0}}{\mu(1 + e^{-2\mu a})(\mu\epsilon_1 \tanh \mu a + \lambda\epsilon_2)} dh. \quad (39)$$

Let

$$\Gamma(h) = \frac{\mu\epsilon_1 - \lambda\epsilon_2}{\mu\epsilon_1 + \lambda\epsilon_2}. \quad (40)$$

As shown in Appendix I, $\Gamma(h)$ can be interpreted as the reflection coefficient of the magnetic field due to the interface in the h domain. Hy_{21}^{II} can now be expressed as:

$$H_{y_{21}}^{II}(0, z_0) = -\frac{i\omega\epsilon_2 V_1}{2\pi}\int_{-\infty}^{\infty} \frac{1 + \Gamma e^{-2\mu a}}{1 - \Gamma e^{-2\mu a}} \frac{e^{+ihz_0}}{\mu} dh. \quad (41)$$

In the complex h plane, because of the multiple-valued behavior of λ and μ the integrand of (41) possesses two branch point singularities when $\lambda = 0$ and $\mu = 0$, and possible simple poles when $1 - \Gamma e^{-2\mu a} = 0$. These poles, if they exist, give rise to characteristic propagating modes

that can be excited inside the plasma layer. However, because the index of refraction is greater than zero and less than unity, $0<n\leq 1$ (medium II is less dense than medium I), it is shown in Appendix III that there are no simple poles on the negative real axis in the h plane. Therefore, along the path of integration of the integral in (41), $1-\Gamma e^{-2\mu a}\neq 0$.

Because $\Gamma\leq 1$ and Reμ is positive as shown in Appendix II, it is clear that $\Gamma e^{-2\mu a}$ is always less than unity. Hence, it is permissible to expand:

$$[1-\Gamma e^{-2\mu a}]^{-1}=\sum_{m=0}^{\infty}(\Gamma e^{-2\mu a})^m. \tag{42}$$

From (42) the integral in (41) becomes a series of integrals:

$$H_{y_{21}}^{II}(0,z_0)=-\frac{i\omega\epsilon_2 V_1}{2\pi}\left[\int_{-\infty}^{\infty}\frac{e^{+ihz_0}}{\mu}dh+2\int_{-\infty}^{\infty}\frac{\Gamma e^{-2\mu a}e^{+ihz_0}}{\mu}\sum_{m=0}^{\infty}(\Gamma e^{-2\mu a})^m dh\right]. \tag{43}$$

Let

$$I_0=\int_{-\infty}^{\infty}\frac{e^{+ihz_0}}{\mu}dh$$

$$I_1=2\int_{-\infty}^{\infty}\frac{\Gamma e^{-2\mu a}e^{+ihz_0}}{\mu}dh$$

$$I_2=2\int_{-\infty}^{\infty}\frac{\Gamma^2 e^{-4\mu a}e^{+ihz_0}}{\mu}dh$$

$$\vdots$$

$$I_m=2\int_{-\infty}^{\infty}\frac{\Gamma^m e^{-2m\mu a}e^{+ihz_0}}{\mu}dh. \tag{44}$$

As shown in Appendix II, Re μ is always positive along the integration contours. It is apparent that as $a\rightarrow\infty$, a situation in which the slots are immersed in an unbounded plasma medium, all the terms except I_0 vanish. In terms of the reflection coefficient (Γ), I_0 represents contribution when there are no reflections ($\Gamma=0$), and I_1 represents the contribution due to rays emanating from S_1 toward the interface, which partially reflects them toward S_2. These reflected rays may be interpreted as coming from image sources located at $X=\pm 2a$. The strength of these rays is weighed by the appropriate reflection coefficient. Similarly, I_2 can be interpreted as a contribution from rays that have gone through two bounces of reflection by the interface. Alternately, these reflected rays come from image sources located at $X=\pm 4a$, the strength of which is weighed by Γ^2. Fig. 3 presents a physical picture of the reflection of rays that have gone through one bounce and two bounces to reach Slot S_2. It is clear that I_3 and I_4 through I_m represent contributions due to three, four, and m reflection bounces from the interface. The significance of these multiple reflection terms becomes less and less as the number of reflection bounces increases. For a relatively thick plasma, the first few terms should be sufficient.

The integral I_0 is evaluated in the complex h plane.




Fig. 3—Arrival of rays from slot S_1 to slot S_2.

The integrand has a branch point singularity when $\mu=0$. It has no poles; hence, it can be concluded that there are no waveguide-type modes excited in an unbounded plasma. By Cauchy's theorem on contour integration, the integral along the real axis is equivalent to the branch-cut integration as shown in Fig. 4. Hence:

$$I_0=\int_{-\infty}^{\infty}\frac{e^{+ihz_0}}{\mu}dh=\int_{\text{Branch Cut}}\frac{e^{+ihz_0}}{\mu}dh. \tag{45}$$

Let

$$h=-nk\sin\tau \quad \text{where} \quad \tau=\xi+i\eta. \tag{46}$$

The new contour in the complex τ plane is shown in Fig. 5. To be consistent with the convergence requirements along the contour, it is necessary that

$$\mu=\sqrt{h^2-n^2k^2}=-ink\cos\tau. \tag{47}$$

In terms of τ, the integral I_0 becomes [11]:

$$I_0=\frac{1}{i}\int_p e^{-inkz_0\sin\tau}d\tau=\frac{\pi}{i}H_0^{(2)}(nkz_0). \tag{48}$$

The perturbation terms I_1 and I_2 through I_m which involve the powers of Γ are more difficult to evaluate. The integrand has two branch points which arise when $\lambda=0$ and $\mu=0$. However, for a thick plasma when $a>z_0$ and $nka\gg 1$, the contribution from the μ branch may be approximated by the method of steepest descent and the contribution from the λ branch will be negligible.

Consider the general term I_m which is:

$$I_m=2\int_{-\infty}^{\infty}\frac{\Gamma^m e^{-2m\mu a}e^{+ihz_0}}{\mu}dh. \tag{49}$$

It was stipulated that μ has a positive real part. Because $a>z_0$, the integral will converge along the contour of integration.




Fig. 4—Contour of branch-cut integration of I_0 in the h plane.




Fig. 5—Contour of branch-cut integration of I_0 in the τ plane.




Fig. 6—Contour of the μ branch-cut integration of I_m in the τ plane.

Let

$$z_0 = r_m \sin \theta_m \tag{50}$$

$$2ma = r_m \cos \theta_m. \tag{51}$$

Hence:

$$\theta_m = \tan^{-1}\left(\frac{z_0}{2ma}\right) \tag{52}$$

$$r_m^2 = (2ma)^2 + z_0^2. \tag{53}$$

In terms of τ, (49) becomes:

$$I_m = \frac{2}{i}\int_D \Gamma^m e^{+inkr_m \cos(\tau+\theta_m)} d\tau. \tag{54}$$

The contour of integration is shown in Fig. 6.

The integrand is stationary when:

$$\frac{\partial}{\partial \tau}\cos(\tau + \theta_m) = -\sin(\tau + \theta_m) = 0$$

$$\tau_m = \pi - \theta_m \tag{55}$$

where θ_m is the angle of incidence of a ray from S_1 that has gone through m bounces of reflection to reach S_2.

By using the method of steepest descent and when $nkr_m \gg 1$, (54) becomes [12]:

$$I_m = \frac{2}{i}\Gamma^m(\tau_m)\int_D e^{inkr_m \cos(\tau+\theta_m)} d\tau$$

$$= \frac{2\pi}{i}\Gamma^m(\pi - \theta_m) H_0^{(2)}(nkr_m)$$

$$= \frac{2\pi}{i}\Gamma^m(\theta_m) H_0^{(2)}(nkr_m). \tag{56}$$

The above development brings out the phenomenon of multiple reflections by the plasma-air interface. The λ branch-cut integration contributes because of the refracted rays. However, inside the plasma region it is reasonable to expect such contributions to be negligible in the case of a thick plasma layer. In the neighborhood of the branch point when $\lambda = 0$; $h = -k$:

$$\mu^2 \sim k^2(1 - n^2)$$

$$\Gamma \sim 1. \tag{57}$$

In view of the approximation in (57), the general term I_m becomes:

$$I_m \sim 2\int_{\lambda \text{ branch}} \frac{e^{-2mak(1-n^2)^{1/2}} e^{+ihz_0}}{k\sqrt{1 - n^2}}\, dh. \tag{58}$$

The expression of (58) is analytic near the branch point $h = -k$ in the h plane; hence, the net contribution along both sides of the λ branch cut is zero.

If the branch-cut integration is carried out asymptotically, each term is attenuated by an exponential factor of $e^{-2mka(1-n^2)^{1/2}}$; where $m = 1, 2 \cdots$.

In summary of the preceding development, the magnetic field $Hy_{21}^{II}(0, z_0)$ in Region II in the presence of a thick plasma is:

$$H_{y_{21}}{}^{II}(0, z_0) = -\frac{\omega\epsilon_2 V_1}{2}\left[H_0^{(2)}(nkz_0) + 2\sum_{m=1}^{\infty}\Gamma^m(\theta_m) H_0^{(2)}(nkr_m)\right] \tag{59}$$

where θ_m and r_m are defined by (52) and (53).

B. In the Presence of a Thin Plasma Layer

When Hy_{21}^{II} is in the presence of a thin plasma layer, the image sources are located close together, and the incident angles for all rays from S_1 are almost at grazing with the interface ($\theta_0 \cong 90°$). This gives a reflection coefficient magnitude of almost unity. The series obtained in (59), when applied to the present case, converges too slowly to be of use. Therefore, the integral must be evaluated in another way.

It is convenient to write the $Hy_{21}^{II}(0, z_0)$ integral as:

$$H_{y_{21}}{}^{II}(0, z_0) = -\frac{i\omega\epsilon_2 V_1}{2\pi}\int_{-\infty}^{\infty}\frac{e^{+ihz_0}}{\mu}\cdot\left[\frac{\mu\epsilon_1 + \lambda\epsilon_2\tanh\mu a}{\lambda\epsilon_2 + \mu\epsilon_1\tanh\mu a}\right]dh. \quad (60)$$

When $ka \ll 1$ and $\tanh \mu a \cong \mu a$ (60) becomes:

$$H_{y_{21}}{}^{II}(0, z_0) = -\frac{i\omega\epsilon_2 V_1}{2\pi}\int_{-\infty}^{\infty}\frac{e^{+ihz_0}(\epsilon_1 + \epsilon_2\lambda a)}{(\lambda\epsilon_2 + \mu^2\epsilon_1 a)}\,dh. \quad (61)$$

The expression for $Hy^{II}(0, z_0)$ in (61) needs to be evaluated, either analytically or numerically. It is possible by employing Watson's lemma to arrive at an asymptotic series which is valid for large slot separation and finite plasma thickness. However, an expression which is valid for small z_0 has yet to be found. Because the plasma is physically thin, it is reasonable to look for major contributions to come from the situation when there is no layer and perturbations because of the layer.

In terms of a typical operating frequency employed in a hypersonic re-entry vehicle, a frequency in the X-band region (10 kMc), the thin plasma case is not too applicable. Under almost every flight environment, the plasma sheath created about the vehicle is many wavelengths thick.

V. Examination of Theoretical Results

In Section IV, the magnetic field or the surface current on the ground plane at $z = z_0$, the location of the second slot S_2 has been evaluated for three different situations: 1) unbounded plasma medium, 2) thick plasma layer, and 3) no plasma (free space).

When the surface current is known, it is possible to determine the various admittance parameters defined in Section III.

A. Mutual Admittance

The mutual admittance parameter Y_{12} is related to the surface current by (32). The results for Y_{12} under various situations can be readily tabulated as follows:

1) unbounded plasma medium:

$$Y_{12}{}^{P} = \frac{\omega\epsilon_2}{2}H_0{}^{(2)}(nkz_0); \quad (62)$$

2) thick plasma layer:

$$Y_{12}{}^{P} = \frac{\omega\epsilon_2}{2}\left[H_0{}^{(2)}(nkz_0) + 2\sum_{m=1}^{\infty}\Gamma^m(\theta_m)H_0{}^{(2)}(nkr_m)\right]; \quad (63)$$

3) no plasma (free space):

$$Y_{12}{}^{a} = \frac{\omega\epsilon_1}{2}H_0{}^{(2)}(kz_0). \quad (64)$$

To illustrate the effect of the plasma layer on Y_{12}, the ratio of the absolute value of $Y_{12}{}^{P}$, and $Y_{12}{}^{a}$, $|Y_{12}{}^{P}/Y_{12}{}^{a}|$ is plotted as a function of the slot separation kz_0 for two different plasma-layer thicknesses: 1) $ka \to \infty$, and 2) $ka = 10$. Fig. 7 presents the results for $n = 0.9$ ($\omega_p/\omega = 0.436$), for $n = 0.7$ ($\omega_p/\omega = 0.714$), and for $n = 0.5$ ($\omega_p/\omega = 0.865$).

In the thick plasma-layer case, the reflections from the plasma-air interface cause the curve to ripple about the dominant term. The perturbations become greater as the index of refraction departs further from unity. This is reasonable because as the two media become more different, the interface causes larger reflections. The effect is demonstrated for the cases of $n = 0.9$, $n = 0.7$, and $n = 0.5$. Fig. 8 shows three reflection-coefficient Γ curves as a function of the index of refraction n. Another point of interest is that mutual admittance in the presence of a plasma layer, whether it is thick or unbounded, is less than when there is no plasma. In the unbounded case, the ratio approaches the asymptotic ratio of $n^{3/2}$ for fairly small kz_0 (*e.g.*, $kz_0 = 1$).

B. Self-Admittance

The results in Section V-A for the mutual admittance can easily be extended to the present situation for self-admittance (Y_{11}) by letting z_0 approach the half width of the slot, which is assumed to be thin. If W is the slot width, then Y_{11} for the three different situations is as follows:

1) unbounded plasma medium:

$$Y_{11}{}^{P} = \frac{\omega\epsilon_2}{2}H_0{}^{(2)}\left(nk\frac{W}{2}\right); \quad (65)$$

2) thick plasma layer:

$$Y_{11}{}^{P} = \frac{\omega\epsilon_2}{2}\left[H_0{}^{(2)}\left(nk\frac{W}{2}\right) + 2\sum_{m=1}^{\infty}\Gamma^m(\theta_m \sim 0)H_0{}^{(2)}(2nkma)\right]; \quad (66)$$

3) no plasma (free space):

$$Y_{11}{}^{a} = \frac{\omega\epsilon_1}{2}H_0{}^{(2)}\left(k\frac{W}{2}\right). \quad (67)$$

C. Driving Point Admittance

The driving point admittance (Y_1') for each slot in the presence of the other as defined in Section III in terms of the other admittance parameters, is given by either (33) or (34). Since slot S_1 and slot S_2 are identical, the self-admittance Y_{11} of slot one and Y_{22} of slot two are equal. Values for Y_{12} and Y_{11} under various conditions may be obtained from expressions given in this section. With these known parameters, the driving point admittance (Y_1') may be readily evaluated. In the absence of mutual effects, Y_1' reduces to the self admittance Y_{11} of the slot. Fig. 9 is a plot of the ratio of the absolute values of $Y_1'^{P}$ and $Y_1'^{a}$ as a function of the slot separation kz_0. The quantity $Y_1'^{P}$ is the driving point




Fig. 7—Mutual admittance ratio vs slot separation.




Fig. 8—Reflection coefficient vs angle of incidence.




Fig. 9—Driving point admittance ratio vs slot separation.

admittance of slot S_1 in the presence of a plasma medium, and $Y_1'^a$ is the same parameter in free space. Two cases are shown in Fig. 9, unbounded plasma and a thick plasma layer. For the particular parameters shown, the curves for both cases indicated that the perturbations introduced by the plasma medium were not too serious. Of course, these variations in Y_1' affect the input VSWR of the antenna to a certain extent. Fortunately, the effect may not be too appreciable.

VI. Conclusions

The plasma model of an equivalent lossless, gaseous dielectric slab may have been too elementary to be realistic for re-entry conditions. The least realistic is perhaps the sharply defined plasma-air interface. However, such a model was employed to minimize the mathematical complexities of the problem. The situation when the equivalent dielectric constant of the plasma layer is negative has not been considered in detail because the region of interest is the operating frequency above the plasma frequency. In view of the foregoing investigation, several interesting points concerning the effects of a plasma layer on the antenna admittance characteristics have been uncovered.

1) There are no unattenuating pole waves excited inside the plasma layer whose equivalent dielectric constant is less than unity but greater than zero. However, the statement may not be true when the operating frequency is below the plasma frequency. Under this situation, the equivalent dielectric constant is negative.
2) Mutual coupling is less serious in the presence of a thick or unbounded plasma layer than in free space. In an unbounded plasma layer, the reduction approaches the asymptotic value of $n^{3/2}$ for small slot separations. When the plasma is thick, because of reflections from the interface, the mutual admittance parameter ripples about the value for the unbounded case. However, in an actual re-entry situation, the plasma-air boundary will not be sharply defined and these variations will probably appear in a statistical manner centering on the value for the unbounded case.[1]
3) The driving point admittance is not seriously affected by the presence of a thick layer of weakly ionized plasma whose index of refraction for the operating frequency is close to unity. When the slot is matched initially to free space, it will remain fairly well matched in the presence of the plasma layer.

Appendix I

It is possible to show that $\Gamma=(\mu\epsilon_1-\lambda\epsilon_2)/(\mu\epsilon_1+\lambda\epsilon_2)$ is equivalent to the reflection coefficient of the magnetic field when a plane wave is incident on the plasma-air interface. When the magnetic-field vector is normal to

[1] The reason for the decrease in coupling as shown in Fig. 7 is that the slots in the presence of a plasma medium are less heavily excited. The equivalent voltage of excitation for slot S_1 is $V_{eq}=\epsilon_2 V_1$. This means that an aperture antenna which is initially matched to free space will be a less efficient radiator in the presence of a thick or unbounded plasma layer. A part of incident power at the aperture will be reflected and the amount is proportional to

$$\left|\frac{1-\epsilon_2/\epsilon_1}{1+\epsilon_2/\epsilon_1}\right|^2.$$

However, if some automatic tuning device is incorporated in the feeding network of the antenna such that a match to the intrinsic admittance of the plasma medium is maintained, then the amount of power appearing at the aperture will be the same. Under this condition, the mutual coupling for the two slots actually increases. The plasma medium in essence brings the two slots closer together. The ordinate for the curves shown in Figs. 7 and 9 should be multiplied by the factor $1/n^2$.

the plane of incidence and parallel to the plasma-air interface, the ratio of the reflected magnetic field (H_{y_2}) and the incident magnetic field (H_{y_0}) is given by (19) in Stratton [13]. This equation is:

$$\Gamma = \frac{H_{y_2}}{H_{y_0}} = \frac{\mu_2 k_1 \cos\theta_0 - \mu_1 k_2 \cos\theta_1}{\mu_2 k_1 \cos\theta_0 + \mu_1 k_2 \cos\theta_1} \tag{68}$$

where θ_0 is the angle of incidence and θ_1 is the angle of refraction. Since $\mu_1 = \mu_2$ (68) can be written:

$$\Gamma = \frac{\epsilon_1 k_2 \cos\theta_0 - \epsilon_2 k_1 \cos\theta_1}{\epsilon_1 k_2 \cos\theta_0 + \epsilon_2 k_1 \cos\theta_1} . \tag{69}$$

Let

$$h = -k_2 \sin\theta_0 = -k_1 \sin\theta_1. \tag{70}$$

The relationship in (70) is merely a statement of Snell's Law of Refraction across the interface. In view of (70) and to be consistent with the convergence requirements of the context of the paper, the parameters λ and μ must necessarily be:

$$\lambda = -ik_1 \cos\theta_1 \tag{71}$$

$$\mu = -ik_2 \cos\theta_0. \tag{72}$$

In terms of λ and μ, the reflection coefficient from (69) becomes:

$$\Gamma = \frac{\mu\epsilon_1 - \lambda\epsilon_2}{\mu\epsilon_1 + \lambda\epsilon_2} . \tag{73}$$

Appendix II

It is also possible to show that μ always has a positive real part along the real axis in the h plane. For the time dependence of $e^{i\omega t}$, assume:

$$k = k_1 - ik_2 \tag{74}$$

where

$$k_2 \ll k_1.$$

In the h plane, the integration along the real axis from $-\infty$ to $+\infty$ lies in the strip $-ink_2 < \beta < +ink_2$, as shown in Fig. 10. Inside the strip, let ϕ_1 be the phase of $h+nk$ and ϕ_2 be the phase of $h-nk$.




Fig. 10—Phase of μ in the h plane.

Because

$$\mu = \sqrt{(h - nk)(h + nk)} \tag{75}$$

the phase of μ is one half the sum of ϕ_1 and ϕ_2.

$$-\pi \leq \phi_1 \leq 0 \quad \text{and} \quad 0 \leq \phi_2 \leq \pi. \tag{76}$$

Hence:

$$|\text{ phase } \mu| = \tfrac{1}{2}|\phi_1 + \phi_2| < \frac{\pi}{2} . \tag{77}$$

Eq. (77) proves that the real part of μ is always positive. Because of this requirement, when transforming into the τ plane, μ must take on the negative sign.

$$\mu = -ink \cos\tau. \tag{78}$$

The above proof is similar to problem 3 in Noble [12].

Appendix III

Existence of Unattenuating Pole Waves

Starting with the integral for Hy_{21}^{II} as in (41):

$$H_{y_{21}}{}^{II}(0, z_0) = -\frac{i\omega\epsilon_2 V_1}{2\pi} \int_{-\infty}^{\infty} \frac{1 + \Gamma e^{-2\mu a}}{1 - \Gamma e^{-2\mu a}} \frac{e^{+ihz_0}}{\mu} dh. \tag{79}$$

It is necessary to examine the situation when $1 - \Gamma e^{-2\mu a} = 0$. Solutions to this characteristic equation give rise to pole singularities of the integrand. Their contributions can be evaluated by residue technique. Physically, these singularities represent characteristic wave modes which can be excited inside the plasma layer. These modes are similar to waveguide modes. Because of the multiple-valued behavior of the parameters λ and μ, the solutions must be examined rather critically to make sure that they are consistent with the stipulations of the problem. Mathematically, the poles must be located on the proper Riemann sheet in which the integration is carried out. A more general and thorough investigation of the existence of pole waves has been conducted by Karbowiak [10]. The results shown here are consistent with Karbowiak's findings. Consider the characteristic equation:

$$1 - \Gamma e^{-2\mu a} = 0 \tag{80}$$

where

$$\Gamma = \frac{\mu\epsilon_1 - \lambda\epsilon_2}{\mu\epsilon_1 + \lambda\epsilon_2}$$

$$\lambda^2 = h^2 - k^2$$

$$\mu^2 = h^2 - n^2k^2.$$

After some algebraic manipulation, this equation can be written:

$$\mu\epsilon_1 \tanh \mu a + \lambda\epsilon_2 = 0$$

$$\tanh \mu a = -\frac{\lambda}{\mu} \frac{\epsilon_2}{\epsilon_1} . \tag{81}$$

Eq. (81) is exactly the same equation that Karbowiak [10] studied in his paper.

To analyze the outgoing waves in the $+z$ direction, it is necessary to concentrate on possible poles on the negative real axis in the h plane. Medium II is less dense than medium I.

Hence:

$$n^2 = \frac{\epsilon_2}{\epsilon_1} \leq 1. \tag{82}$$

Eq. (82) implies operation above the plasma frequency. For discussion, divide the negative real axis into three ranges as shown in Fig. 11.




Fig. 11—Range of values of λ and μ in the h plane.

For k and n real, depending on the range of h, the parameters λ and μ may be real or imaginary along the real axis.

Range 1, $-k \leq -h \leq -\infty$
λ = real
μ = real
Range 2, $-nk \leq -h \leq -k$
λ = imaginary
μ = real
Range 3, $0 \leq -h \leq -nk$
λ = imaginary
μ = imaginary.

An investigation of (81) reveals that if λ is negative real, solutions are possible in Range 1. However, this stipulation of λ negative real violates the radiation condition of the fields in Region I. Therefore, the solutions are not admissible. Similarly, there are no solutions in Ranges 2 and 3. Hence, it is concluded that there are no unattenuating pole waves when medium II is less dense than medium I.

The above argument, however, does not rule out the possible existence of leaky waves. The poles that give rise to these waves are complex roots of the characteristic (81). They lie on the improper sheet of the Riemann surface on which the integration is carried out. In evaluating the transform integral by approximate techniques, it is customary to deform the contour into the one of steepest descent. A part of this deformed contour may lie in the improper sheet enclosing the leaky-wave poles which will contribute to the expansion of the integral. A leaky wave, unlike a surface wave, is characterized by a complex propagation constant along the interface, both in the longitudinal and in the transverse directions. It attenuates or leaks longitudinally but grows transversely. This report has not investigated the leaky-wave question thoroughly enough to ascertain its existence. Hence, its contribution to coupling cannot be evaluated. Intuitively, its contribution to coupling will probably be negligible because of its existence along the plasma-air interface which is quite remote from the slots in the thick plasma case.

The situation is different when medium II is more dense than medium I. In this case the index of refraction, $n = \sqrt{\epsilon_2/\epsilon_1}$, is greater than unity, and it can be demonstrated by similar argument that there are admissible solutions to the characteristic equation when $-k \leq -h \leq -nk$. Moreover, these poles waves can be shown to be slow waves (surface waves). It is possible to visualize three configurations that may give rise to pole waves:

1) medium I—free space
   medium II—solid dielectric
2) medium I—uniform unbounded plasma
   medium II—free space
3) medium I—free space
   medium II—plasma layer whose index of refraction is negative.

The first configuration corresponds to a dielectric slab on the ground plane and has been studied by Tai, Whitmer, Attwood [7], [8], [9], and others. The second situation may correspond to an elementary model of the ionosphere and conducting Earth. Also, it may represent a simplified model of a hypersonic vehicle upon reentry; Region I is then the plasma region and Region II is the region behind the shock and the surface of the vehicle. Finally, the third case corresponds to a situation when the operating frequency is below the plasma frequency of the layer.

Acknowledgment

The author wishes to express his appreciation to C. W. Armstrong, Chief of the Antennas and Radomes Unit, for the encouragements and support in the course of this investigation.

References

[1] W. S. Lucke, "Mutual Admittance of Slots in Cylinders," Stanford Res. Inst., Menlo Park, Calif., Tech. Rept. No. 36; February, 1953.
[2] S. Nishida, "Coupled leaky waveguides I: Two parallel slits in a plane," IRE Trans. on Antennas and Propagation, vol. AP-8, pp. 323–330; May, 1960.
[3] S. Nishida, "Coupled leaky waveguides II: Two parallel slits in a cylinder," IRE Trans. on Antennas and Propagation, vol. AP-8, pp. 354–360; July, 1960.
[4] S. Edelberg and A. A. Oliner, "Mutual coupling effects in large antenna arrays: Part I—Slot array," IRE Trans. on Antennas and Propagation, vol. AP-8, pp. 286–297; May, 1960.
[5] R. F. Whitmer, "Principles of microwave interactions with ionized media, part, I," *Microwave J.*, vol. 2, pp. 17–19; February, 1959.
[6] R. F. Whitmer, "Principles of microwave interactions with ionized media, part II," *Microwave J.*, vol. 2, pp. 47–50; March, 1959.
[7] C. T. Tai, "The effect of a grounded slab on the radiation from a line source," *J. Appl. Phys.*, vol. 22, pp. 405–414; April, 1951.
[8] R. M. Whitmer, "Fields in nommetallic waveguides," Proc. IRE, vol. 36, pp. 1105–1109; September, 1948.
[9] S. S. Attwood, "Surface wave propagation over a coated plane conductor," *J. Appl. Phys.*, vol. 22, pp. 504–509; April, 1951.
[10] A. E. Karbowiak, "Radiation and guided waves," IRE Trans. on Antennas and Propagation (special suppl.), vol. AP-7, pp. s191–s200; December, 1959.
[11] A. Sommerfeld, "Partial Differential Equations," Academic Press Inc., New York, N. Y., p. 89; 1949.
[12] B. Noble, "The Wiener-Hopf Technique," Pergamon Press, Inc., New York, N. Y., pp. 34–35; 1958.
[13] A. Stratton, "Electromagnetic Theory," McGraw-Hill Book Co., Inc., New York, N. Y., ch. IX; 1941.
[14] E. C. Jordan, "Electromagnetic Waves and Radiating Systems," Prentice-Hall, Inc., chs. 11 and 15; 1950.
[15] N. W. McLachlan, "Complex Variable Theory and Transform Calculus," Cambridge University Press, Cambridge, Eng.; 1953.

Antenna Noise Temperature in Plasma Environment*

M. P. BACHYNSKI†, SENIOR MEMBER, IRE, I. P. FRENCH†, AND G. G. CLOUTIER†

Summary—The total noise power available at a receiving antenna on a hypervelocity space vehicle is determined by considering the engulfing plasma sheath as a uniform slab of plasma. The noise emission from the plasma is treated as a boundary-value problem which for this simple model can be completely solved. The effect of the hot vehicle surface and other external sources is included.

The general conclusions are that for an isotropic plasma the main noise contributions result from the vehicle surface for RF frequencies well below the plasma frequency, from external sources for RF frequencies well above the plasma frequency, and from direct emission by the plasma for RF frequencies about the plasma frequency. The noise power from the plasma is the most significant and exhibits a pronounced peak at an RF frequency just above the plasma frequency.

The effect of an anisotropic plasma sheath (due to an auxiliary magnetic field carried by the vehicle) has been investigated for magnetic field orientations normal to and parallel to the plasma. The anisotropy completely alters the spectral characteristics of the available noise power resulting in several frequency regions of weak and intense noise emission.

I. Introduction

THE advent of space exploration and missile technology has posed many communication and diagnostic problems. Among these is the behavior of antennas in an ionized environment such as the plasma sheath which forms about a hypersonic vehicle in a planetary atmosphere. Such information is essential in order to optimize systems parameters for communications and telemetry and for possible investigations of the engulfing shock front and plasma environment.

One topic of current interest is the noise power available to a receiving antenna located on board a hypervelocity vehicle. In this paper, the plasma sheath is approximated by a uniform plasma slab and the noise emission spectrum from the plasma determined from the absorptivity using a generalized form of Kirchhoff's law. In addition, the effect of the hot vehicle surface and external sources can be included by utilizing the reflectivity and transmissivity of the plasma. A numerical example illustrates the analytical considerations. Optimum frequencies for either maximum or minimum noise signals and for rapid transition regions can be ascertained from the analysis. Finally, the effect of anisotropy in the plasma (due to an auxiliary magnetic field on the space vehicle) is investigated and the spectral characteristics determined.

* Received by the IRE, August 14, 1961. Some of the computations of the electromagnetic parameters were performed under Contract No. AF19(604)-7334 with the AF Cambridge Res. Labs., and under Contract No. GX9-998054-0001-70-Q82 with RCA Moorestown, Missile and Surface Radar Div.

† Res. Labs., RCA Victor Co. Ltd., Montreal, Canada.

II. Antenna Noise Power

A receiving system under normal operating conditions will be subjected to two sources of noise—the noise signals originating from external sources which are received by the receiving antenna and the noise generated in the receiver components. In this treatise, the receiver noise will be omitted entirely, and only the effect of external sources on the receiving antenna considered.

The noise power P available to a receiving antenna (assumed to be matched to its surrounding environment) in a frequency interval between f and $f+\Delta f$ is given by:

$$P = \gamma A \Phi \Delta f,$$

where

γ = polarization coefficient (for instance, if the noise signal is randomly polarized, $\gamma = \frac{1}{2}$),

A = effective antenna area,

Φ = energy or power flux density at the receiving antenna,

Δf = frequency interval under consideration.

Let a radiating body with emissive power P_ω (where P_ω is the radiated power in a direction normal to the surface of the radiating body per unit frequency interval, per unit solid angle and per unit surface area for a given polarization) subtend a solid angle Ω_s at the receiving antenna (Fig. 1). The solid angle $\Omega_s = a_0/r^2$, where a_0




Fig. 1—Geometry for determining noise power available at receiving antenna.

is the projected area normal to and a distance r from the receiving antenna. Let the beam of the receiving antenna power pattern subtend a solid angle Ω_a where in the plane of the emitting body, $\Omega_a = A_0/r^2$. The power emitted per unit area of the radiating body is $4\pi P_\omega$, so that the power emitted by the area a_0 "seen" by the receiving antenna is $4\pi P_\omega a_0$. Hence, the flux density of power at the receiving antenna is

$$\Phi = 4\pi P_\omega a_0 / r^2.$$

Note that if the projected area of the emitting surface just fills the antenna beam or is larger than the projected area intercepted by the antenna beam, then the receiving antenna sees an area $a_0 = A_0$. In this case $a_0/r^2 = A_0/r^2 = \Omega_a$, the solid angle of the power pattern beam of the receiving antenna. If the emitting area a_0 is less than the area A_0 intercepted by the receiving antenna power pattern at the source, then the antenna "sees" only the area a_0. In this case we can write

$$\frac{a_0}{r^2} = \Omega_a \cdot \frac{\Omega_s}{\Omega_a}.$$

Thus, in summary, the total power flux density at the receiving antenna is

$$\Phi = 4\pi P_\omega \Omega_a \qquad \Omega_a \leq \Omega_s, \tag{2a}$$

$$\Phi = 4\pi P_\omega \Omega_a \left(\frac{\Omega_s}{\Omega_a}\right) \qquad \Omega_a \geq \Omega_s. \tag{2b}$$

The effective area of an antenna is[1]

$$A = \frac{\lambda^2}{4\pi} G_{\max}, \tag{3a}$$

and the solid angle of the power pattern of a receiving antenna is

$$\Omega_a = 4\pi / G_{\max}, \tag{3b}$$

where the antenna power gain $G(\theta, \phi)$ is defined in the usual manner, as:

$$G(\theta, \phi) = \frac{P(\theta, \phi)/\text{unit solid angle}}{P_{\text{total}}/4\pi} = \frac{4\pi P(\theta, \phi)}{\iint_{4\pi} P(\theta, \phi) d\Omega},$$

and $G_{\max}$ is the maximum value of $G(\theta, \phi)$; θ, ϕ are the elevation and azimuth spherical coordinates.

Utilizing (2) and (3) in (1), the total noise power is

$$P = \gamma 4\pi \lambda^2 P_\omega \Delta f \left(\frac{\Omega_s}{\Omega_a}\right), \tag{4}$$

where we take $\Omega_s/\Omega_a = 1$ when the solid angle of the source at the antenna exceeds the antenna beam angle, *i.e.*, $\Omega_s \geq \Omega_a$.

The available noise power attains a particularly simple form when appropriate forms for the emissive power P_ω are chosen. Thus, for equilibrium radiation:

1) Rayleigh-Jeans Approximation—in the Rayleigh-Jeans limit[2] (appropriate for long wavelengths such as those corresponding to microwave frequencies),

$$P_\omega = \frac{\kappa T_{\text{eff}}}{2\pi\lambda^2}$$

where κ is Boltzmann's constant and T_{eff} is the effective temperature of the emitting body. (For a black body, T_{eff} is the actual body temperature). Consequently, the available noise power is

$$P = 2\gamma\kappa T_{\text{eff}} \Delta f \left(\frac{\Omega_s}{\Omega_a}\right). \tag{5}$$

2) Kirchhoff's Law—a general formulation[3,4] of Kirchhoff's law for the energy radiated by a body, which enables the effective temperature to be evaluated from the electromagnetic properties of the body, gives

$$P_\omega = \frac{\kappa T}{2\pi\lambda^2} A_\omega$$

where A_ω is the power absorptivity of the body (an absorptivity of unity corresponds to a black body) and T is the temperature of the body. Thus the available noise power is

$$P = 2\gamma\kappa T A_\omega \Delta f \left(\frac{\Omega_s}{\Omega_a}\right), \tag{6}$$

so that

$$T_{\text{eff}} = T A_\omega.$$

The noise power at the receiving antenna can thus be calculated provided the absorptivity A_ω of the emitting body is known.

If more than one source of noise power lies in the beam of the receiving antenna, the contribution of each source must be evaluated as indicated above, and the sum of the individual contributions will give the total available noise power at the receiving antenna.

III. Noise Power Emission from an Isotropic Plasma Slab

In order to calculate the noise emission from a body, it is sufficient to know the absorptivity of the body. The absorptivity A_ω is defined as the fraction of energy absorbed by a body when a plane-polarized electromagnetic wave is incident upon it. Thus,[3,4]

$$A_\omega = \frac{\int_V \frac{1}{2} \operatorname{Re}(\boldsymbol{J} \cdot \boldsymbol{E}^*) dV}{\int_S \frac{1}{2} \operatorname{Re}(\boldsymbol{E}_i \times \boldsymbol{H}_i^*) dS}. \tag{7}$$

[1] J. C. Slater, "Microwave Transmission," Dover Publications, Inc., New York, N. Y., ch. 6, p. 264; 1959.

[2] F. K. Richtmeyer and E. H. Kennard, "Introduction to Modern Physics," McGraw-Hill Book Co., Inc., New York, N. Y., ch. 5; 1942.

[3] S. M. Rytov, "Theory of Electrical Fluctuations and Thermal Radiation," Academy of Sciences Press, Moscow, USSR; 1953.

[4] M. L. Levin, "The electrodynamic theory of thermal radiation," *Dokl. Akad. Nauk, USSR*, vol. 102, p. 53; 1955. Also see *Soviet Phys. JETP*, vol. 4, p. 225; 1957.

where J and E are the current density and the electric field in the body due to an incident electromagnetic field (E_i, H_i) on the body. The numerator represents the energy absorbed due to Joule losses by the body and can in principle be obtained from the electromagnetic properties of the body. The denominator represents the energy incident on the body.

The evaluation of the absorptivity is a boundary-value problem which has only been solved for very simple geometries.

Consider a uniform, infinite plasma slab of thickness d. Assume that the plasma is in thermal equilibrium, that the electron density is uniform and isotropic throughout the plasma and that the boundaries are infinitely sharp. This simple model neglects diffraction effects (since the slab is infinite), but does include interference phenomena (due to multiple internal reflections). These interference effects markedly affect the noise power emitted by the slab (as will be shown). An approximation to a more realistic plasma model which has gradual boundaries and nonlinear electron distributions can be made by applying this approach to a layer of uniform plasma slabs, each with different electrical properties.

Considering a plane electromagnetic wave to be normally incident on the plasma slab, applying Maxwell's equations and matching wave solutions at the boundaries, it is easy to obtain the fraction of incident electromagnetic energy which is transmitted through and reflected from the plasma slab. The power absorptivity can then be obtained from

$$A_\omega = 1 - R_\omega - T_\omega, \tag{8a}$$

where R_ω, T_ω are the power reflectivity and power transmissivity, respectively, of a plane wave incident normally on the slab surface. The corresponding expressions for the transmissivity and reflectivity in terms of the electromagnetic properties and thickness of the plasma slab are[5]

$$T_\omega = [(P^2+Q^2)(\sinh^2 \alpha d + \sin^2 \beta d) + 2P \cosh \alpha d \sinh \alpha d + \sinh^2 \alpha d + \cos^2 \beta d - 2Q \sin \beta d \cos \beta d]^{-1}, \tag{8b}$$

$$R_\omega = (L^2+M^2)(\sinh^2 \alpha d + \sin^2 \beta d) T_\omega, \tag{8c}$$

where

$$P = \frac{\beta}{2k} \frac{(k^2 + \alpha^2 + \beta^2)}{\alpha^2 + \beta^2}, \qquad Q = \frac{\alpha}{2k} \frac{(k^2 - \alpha^2 - \beta^2)}{\alpha^2 + \beta^2},$$

$$L = \frac{\beta}{2k} \frac{(k^2 - \alpha^2 - \beta^2)}{\alpha^2 + \beta^2}, \qquad M = \frac{\alpha}{2k} \frac{(k^2 + \alpha^2 + \beta^2)}{\alpha^2 + \beta^2}.$$

[5] I. P. French, G. G. Cloutier, and M. P. Bachynski, "Electromagnetic Wave Propagation and Radiation Characteristics of Anisotropic Plasmas," RCA, Montreal, Canada, Res. Rept. 7-801, 8, November, 1960.

$k = 2\pi/\lambda$ = wave number,

$\alpha/k = [\frac{1}{2}(|K| - K_r)]^{1/2}$ = normalized attenuation coefficient of the plasma,

$\beta/k = [\frac{1}{2}(|K| + K_r)]^{1/2}$ = normalized phase coefficient of the plasma,

$K = K_r - jK_i$ = dielectric coefficient of the plasma with real part K_r and imaginary part K_i, and

$|K| = [K_r^2 + K_i^2]^{1/2}$.

The dielectric coefficient of a plasma depends on the electron density, collision frequency, RF frequency, magnetic field strength and orientation should a magnetic field be present.

For a uniform plasma in the absence of magnetic fields and neglecting ion effects, the dielectric coefficient of the plasma is[6]

$$K = K_r - jK_i = \left(1 - \frac{\omega_p^2}{\omega^2} \frac{1}{1 + \nu^2/\omega^2}\right) - j\left(\frac{\omega_p^2}{\omega^2} \frac{\nu/\omega}{1 + \nu^2/\omega^2}\right),$$

where

ω_p = the plasma frequency $= (ne^2/m\epsilon_0)^{1/2}$, and ν the electron collision frequency considered to be independent of electron velocity. A discussion of the validity of this assumption and extensive numerical results have been presented by Shkarofsky, *et al.*[7]

n = the electron density

e, m = the electronic charge and mass, respectively, and


ϵ_0 = the permittivity of free space.

Choosing a fixed slab thickness ($d/\lambda_p = 2.5$, where λ_p is the wavelength corresponding to the plasma frequency and hence is a measure of electron density), typical variations of the transmissivity, reflectivity and absorptivity for a plasma slab as a function of ν/ω_p are shown in Fig. 2(a)–(c). These results will be utilized in Section IV.


Note the sharp transitions which occur around the region where the plasma frequency equals the RF angular frequency. At low collision frequencies, the reflectivity is very large for frequencies below the plasma frequency and small for RF frequencies above the plasma frequencies. The reverse is true for the transmissivity. The absorptivity, however, has a peak around the plasma frequency. This is due to the fact that for $\omega < \omega_p$ the reflections are so large that very little energy penetrates into the plasma, while for $\omega > \omega_p$ the plasma is

[6] M. P. Bachynski, I. P. Shkarofsky, and T. W. Johnston, "Plasmas and the Electromagnetic Field," McGraw-Hill Book Co., Inc., New York, N. Y. (in press).


[7] I. P. Shkarofsky, M. P. Bachynski, and T. W. Johnston, "Collision frequency associated with high temperature air and scattering cross-sections of the constituents," in "Electromagnetic Effects of Re-Entry," Pergamon Press, New York, N. Y.; 1961.



(a)



(b)



(c)

Fig. 2—(a) Transmissivity (T_ω) of an isotropic plasma slab as a function of RF frequency for various electron collision frequencies for a thickness $d/\lambda_p = 2.5$. (b) Reflectivity (R_ω) of an isotropic plasma slab as a function of RF frequency for various electron collision frequencies for a thickness $d/\lambda_p = 2.5$. (c) Absorptivity (A_ω) of an isotropic plasma slab as a function of RF frequency for various electron collision frequencies for a thickness $d/\lambda_p = 2.5$.

very nearly transparent and hence very little energy is absorbed. The peak absorption thus occurs in the region $\omega \approx \omega_p$, where the attenuation coefficient is high and a considerable amount of the incident energy penetrates the first boundary. As the collision frequency is increased, the reflectivity decreases and the absorptivity increases. In addition, the characteristic variations are much less abrupt. Another feature characteristic is the presence of undulations in the spectrum of the reflectivity, transmissivity and absorptivity. These undulations are due to the interference effects resulting from internal reflections from the slab boundaries. The undulations can be quite marked for low collision frequencies and are smoothed out at high collision frequencies. This type of behavior is characteristic for a large range of slab thicknesses[5] $(0.5 < d/\lambda_p)$.

IV. Antenna Noise Temperature in Plasma Environment

Of vital significance is the noise power received by an antenna located in a hypervelocity space vehicle. An understanding of the noise power spectrum is essential in order to determine the systems performance of the communications equipment and possibly guidance apparatus of the vehicle. In addition, the noise power spectrum may be utilized as a diagnostic tool and yield information regarding the environment through which the vehicle traverses.

A receiving antenna located in a space vehicle will be subjected to three main sources of external noise, namely RF emission from the engulfing plasma sheath, noise emission from the hot surface of the vehicle itself which finds its way into the receiving antenna, and noise sources external to both the vehicle and the plasma sheath. The latter sources may, for instance, be due to noise emission from the earth or from the sun or as a result of atmospheric absorption, depending upon antenna orientation.

As a model upon which to base an illustrative example, consider a hypersonic vehicle surrounded by a plasma sheath as shown in Fig. 3. The region of the plasma




Fig. 3—Receiving antenna in hypersonic space vehicle. External sources of noise power are 1) the plasma sheath, 2) the hot vehicle itself, and 3) sources external to both the vehicle and the plasma such as the earth or the sun.

sheath facing the antenna is assumed to be a plane, parallel slab with sharp boundaries and uniform, isotropic electrical properties. The portion of the plasma "seen" by the antenna will have a large radius of curvature so that, to a very good approximation, the plasma can be considered as a planar slab. Hence, the analysis of the previous section applies. In addition to the noise power emitted by the plasma, noise emission from the hot surface of the vehicle which is *reflected* from the plasma sheath into the receiving antenna and noise radiation from other external sources which is *transmitted* through the plasma sheath must be considered in order to obtain the total noise power at the receiving antenna. The mismatch introduced by the plasma to the receiving antenna is not considered in this analysis. (A similar model has been assumed by Di Felice and Ward[8] who, in their analysis, neglect the important interference effects due to internal multiple reflections within the plasma sheath.)

For purposes of computation, assume that the solid angle of each of the radiating sources subtended at the antenna at least fills the receiving antenna beam so that it is permissible, to set $\Omega_s/\Omega_a = 1$. Further, consider the emitted noise power to be randomly polarized so that the polarization coefficient γ can be set equal to one-half. The total noise power received is then proportional to the sum of:

1) The plasma temperature times the absorptivity of the plasma.
2) The effective vehicle temperature times the reflectivity of the plasma (neglecting multiple reflections which may occur in the region between the vehicle and the plasma sheath and considering the reflection coefficient to be the same as the normal incidence reflectivity. Both of these conditions are very nearly true. Multiple reflections between the surface of the vehicle and the inner surface of the plasma are effective only in the region $1 \leq \omega/\omega_p \leq 1.3$. In this region, the contribution from the plasma is dominant since, in general, the temperature of the plasma is much greater than the temperature of the vehicle).
3) The effective temperature of outside external sources times the transmissivity of the plasma sheath.

The total noise power at the receiving antenna is thus

$$P = \kappa[A_\omega T_p + R_\omega T_v + T_\omega T_{ex}] = \kappa T_n \qquad (9)$$

where

T_p = the temperature of the plasma
T_v = the temperature of the vehicle
T_{ex} = the temperature of any source external to both the vehicle and the plasma sheath
T_n = the total effective noise temperature.

As an illustrative example, choose for the plasma parameters $d/\lambda_p = 2.5$, $\nu/\omega_p = 10^{-2}$. This could, for example, correspond to a plasma of electron density n 4×10^{12} electrons/cc, collision frequency (ν) 1.12×10^9 sec^{-1} and of thickness (d) equal to 4.18 cm. All are typi-

[8] B. L. Di Felice and T. J. Ward, "An Experimental Method to Determine the Optimum Frequency for Hypersonic Vehicle Communications and Radar," RCA Airborne Systems Div. (DEP), Camden, N. J., TR60-597-15; 1960.

cal values for a hypersonic re-entry vehicle.[9] Let the temperature of the plasma be 5000°K, the temperature of the space vehicle 500°K and the temperature of an outside source 300°K (the receiving antenna looking at the earth, for instance). The noise temperature contributions from each of these sources and the total effective noise temperature as function of the normalized parameter ω/ω_p (effectively, frequency for a given plasma) are shown in Fig. 4. The main feature of the spectral behavior is the rapid increase in noise power as the RF frequency passes through the plasma frequency and the peak of noise emission at a RF frequency just higher than the plasma frequency. The general characteristic of the noise emission spectrum resembles the absorptivity spectrum with both the high and low frequency (relative to plasma frequency) regions pushed up. A general conclusion is that for RF frequencies much lower than the plasma frequency, the main noise source is the hot surface of the vehicle itself; for RF frequencies much greater than the plasma frequency, the greatest noise contribution arises from sources outside both the vehicle and the plasma, while in the frequency region about the plasma frequency the noise signal originates principally in the plasma sheath.




Fig. 4—Effective noise temperature for a hypersonic space vehicle (isotropic plasma with $\nu/\omega_p = 10^{-2}$ and $d/\lambda_p = 2.5$).

V. Effect of Magnetic Fields on Antenna Noise Temperature

Considerable speculation has been made on the possibilities of utilizing an auxiliary static magnetic field inside a space vehicle in order to alter the characteristics of the surrounding plasma sheath and hence permit modes of transmission in which RF frequencies well below the plasma frequency will readily penetrate through the plasma and hence establish reliable communications between the vehicle and an outside station. It is the purpose of this section to investigate the effect of an auxiliary dc magnetic field on the available noise temperatures at a receiving antenna in a space vehicle.

As is well known, in the presence of a static magnetic field, a plasma becomes anisotropic and can support two different waves for any direction of propagation (*i.e.*, the plasma is doubly refracting). Considering a uniform, anisotropic slab of plasma with a plane electromagnetic wave incident normally on the plasma boundaries, the transmissivity, reflectivity and absorptivity of the slab can be obtained from (8) provided the appropriate value of the dielectric coefficient for the plasma is used. For a uniform anisotropic plasma, the dielectric coefficient (neglecting the effects of ions) is[6]

$$K = \frac{B \pm \sqrt{B^2 - 4AC}}{2A}, \tag{10}$$

where

$A = [\epsilon_{11} \sin^2\theta + \epsilon_{33} \cos^2\theta]$
$B = [(\epsilon_{11}^2 - \epsilon_{12}^2) \sin^2\theta + \epsilon_{11}\epsilon_{33}(1 + \cos^2\theta)]$
$C = [\epsilon_{33}(\epsilon_{11}^2 - \epsilon_{12}^2)]$
θ = the angle between the magnetic field direction field direction and the incident electromagnetic wave,

and

$$\epsilon_{11} = 1 + \frac{\omega_p^2(1 - j\nu/\omega)}{[\nu + j(\omega - \omega_b)][\nu + j(\omega + \omega_b)]} \tag{11a}$$

$$\epsilon_{12} = \frac{\omega_p^2}{\omega^2} \frac{\omega\omega_b}{[\nu + j(\omega - \omega_b)][\nu + j(\omega + \omega_b)]} \tag{11b}$$

$$\epsilon_{33} = 1 - \frac{\omega_p^2}{\omega^2} \frac{j\omega}{\nu + j\omega} \tag{11c}$$

$\omega_b = \left|\frac{e}{m} B_0\right|$ = the electron gyrofrequency corresponding to a static magnetic field of strength B_0.

The above expressions simplify considerably when the direction of propagation is either parallel to the magnetic field ($\theta = 0°$) or perpendicular to the magnetic field ($\theta = 90°$). For these two cases, the dual valued dielectric coefficient is:[6]

1) Longitudinal propagation ($\theta = 0°$)

$$K_- = \left(1 - \frac{\omega_p^2}{\omega} \frac{(\omega - \omega_b)}{\nu^2 + (\omega - \omega_b)^2}\right) - j\left(\frac{\omega_p^2}{\omega} \frac{\nu}{\nu^2 + (\omega - \omega_b)^2}\right) \tag{12a}$$

$$K_+ = \left(1 - \frac{\omega_p^2}{\omega} \frac{\omega + \omega_b}{\nu^2 + (\omega + \omega_b)^2}\right) - j\left(\frac{\omega_p^2}{\omega} \frac{\nu}{\nu^2 + (\omega + \omega_b)^2}\right) \tag{12b}$$

[9] M. P. Bachynski, T. W. Johnston, and I. P. Shkarofsky, "Electromagnetic properties of high temperature air," Proc. IRE, vol. 48, pp. 347–356; March, 1960.

where K_- corresponds to the circularly polarized wave rotating in the same sense as negative particles (electrons) gyrate in the magnetic field (electron cyclotron wave), and K_+ corresponds to the circularly polarized wave rotating in the same sense as positive particles gyrate in the magnetic field (ion cyclotron wave).

2) Transverse propagation ($\theta = 90°$)

$$K_0 = \left(1 - \frac{\omega_p^2}{\omega^2}\,\frac{1}{1+\nu^2/\omega^2}\right) - j\left(\frac{\omega_p^2}{\omega^2}\,\frac{\nu/\omega}{1+\nu^2/\omega^2}\right) \tag{13a}$$

$$K_x = \left(1 - \frac{\omega_p^2}{\omega^2}\,\frac{(\omega^2-\omega_p^2)(\omega^2-\omega_b^2-\omega_p^2)+\nu^2\omega^2}{[\nu^2-(\omega^2-\omega_b^2-\omega_p^2)]^2+\nu^2[2\omega-\omega_p^2/\omega]^2}\right)$$
$$-j\left(\frac{\omega_p^2}{\omega^2}\,\nu\omega\,\frac{[\nu^2+\omega^2+\omega_b^2-\omega_p^2]+(\omega_p^2/\omega^2)(\omega_p^2-\omega^2)}{[\nu^2-(\omega^2-\omega_b^2-\omega_p^2)]^2+\nu^2[2\omega-\omega_p^2/\omega]^2}\right) \tag{13b}$$

where K_0 corresponds to the ordinary wave (E vector of EM wave parallel to B_0) and is the same as in the absence of a dc magnetic field, and K_x corresponds to the extraordinary wave (H vector of EM wave parallel to B_0).

The absorptivity, reflectivity and transmissivity have been computed for a plasma slab corresponding to longitudinal propagation (electron and ion cyclotron waves) and transverse propagation (extraordinary and ordinary wave) and are shown in Figs. 5–7 (pp. 1853–1855). (The ordinary wave is not shown since it is the same as given in Section III, Fig. 2, for an isotropic plasma.) The same parameters ($d/\lambda_p = 2.5$, $\nu/\omega_p = 10^0$, 10^{-1}, 10^{-2}, 10^{-3}) as in Section III have been chosen for the plasma. The main features of these variations are the high reflectivity in the "stop-regions"[5,6] of the magneto-ionic modes, the high transmissivity outside the stop-regions and the enhanced absorptivity in the transparent regions immediately adjacent to the stop-regions. Noteworthy are the several possible enhanced frequencies of absorption (and hence of noise emission) corresponding to these different modes. The effect of increased collision frequency is to increase the absorptivity and to broaden the resonances. (Inhomogeneities of the plasma properties would be expected to have the same result.) Again, undulations due to internal reflections within the plasma slab are apparent.

Considering a randomly polarized noise signal, the total reflectivity, transmissivity or absorptivity of an anisotropic plasma slab in a direction normal to its boundaries is a combination of the reflectivities, transmissivities or absorptivities of the two possible waves in that direction. Thus, for longitudinal (relative to the dc magnetic field) propagation,

$$\theta = 0° \qquad \begin{aligned} R_\omega &= \tfrac{1}{2}(R_- + R_+) \\ T_\omega &= \tfrac{1}{2}(T_- + T_+) \\ A_\omega &= \tfrac{1}{2}(A_- + A_+) \end{aligned} \tag{14}$$


where the $-$, $+$ subscripts refer to the electron cyclotron and ion cyclotron waves, respectively. Similarly, for the magnetic field along the plasma slab, normal to the incident electromagnetic wave (transverse propagation),

$$\theta = 90° \qquad \begin{aligned} R_\omega &= \tfrac{1}{2}(R_o + R_x) \\ T_\omega &= \tfrac{1}{2}(T_o + T_x), \\ A_\omega &= \tfrac{1}{2}(A_o + A_x), \end{aligned} \tag{15}$$


where the o, x subscripts refer to the ordinary and extraordinary waves, respectively.

The total noise power available at the receiving antenna for an anisotropic plasma sheath surrounding a hypervelocity space vehicle has been evaluated for the case of the magnetic field normal to the plasma slab and parallel to the emitted noise signal (longitudinal propagation) and for the case of the magnetic field parallel to the plasma slab and perpendicular to the normally incident electromagnetic wave (transverse propagation). The same model and parameters have been assumed as in Section III; *i.e.*, the plasma sheath can be approximated by a uniform but now *anisotropic* plasma slab with sharp boundaries, the plasma is assumed to be at a temperature of 5000°K, the space vehicle at 500°K, and an external source at 300°K. The plasma parameters were taken to be $d/\lambda_p = 2.5$ and $\nu/\omega_p = 10^{-2}$. In addition, an electron gyrofrequency to plasma frequency ratio of two was assumed ($\omega_b/\omega_p = 2$). For an electron density of 4×10^{12} electrons/cm^3, this corresponds to a magnetic field of 10,000 gauss. This is an unrealistic value for practical space applications, although it could be realized in laboratory tests. It is used here to demonstrate how drastically the spectral characteristics can be altered by a magnetic field. The results [utilizing Figs. 2, 5, 6 and 7 and (14) and (15) in (9)] are shown in Fig. 8(a) and (b), (p. 1856).


The effect of the magnetic field has been to alter completely the available noise power at the receiving antenna relative to that for an isotropic plasma sheath. The noise emission for the auxiliary magnetic field along the direction of propagation is characterized by two maxima, both due to the electron cyclotron wave (the main lobe occurring at a frequency just below the electron gyrofrequency), and is followed by a pronounced minima. The effect of lower magnetic fields would be to move this maxima to lower frequencies. The ion cyclotron wave for these low collision frequencies does not make a very substantial contribution to the total noise power. There is no significance to the plasma frequency in this case. The available noise power for the auxiliary magnetic field transverse to the direction of propagation exhibits four pronounced maxima, including one at the plasma frequency (as in the isotropic case). In general, the peak emitted power is greatest for this case and occurs at a frequency just above the electron gyrofrequency.



(a)




(b)




(c)


Fig. 5—(a) Transmissivity (T_ω) of an anisotropic plasma slab as a function of RF frequency for the electron cyclotron wave ($d/\lambda_p = 2.5$, $\omega_b/\omega_p = 2$) for various electron collision frequencies. (b) Reflectivity (R_ω) of an anisotropic plasma slab as a function of RF frequency for the electron cyclotron wave ($d/\lambda_p = 2.5$, $\omega_b/\omega_p = 2$) for various electron collision frequencies. (c) Absorptivity (A_ω) of an anisotropic plasma slab as a function of RF frequency for the electron cyclotron wave ($d/\lambda_p = 2.5$, $\omega_b/\omega_p = 2$) for various electron collision frequencies.



(a)




(b)




(c)


Fig. 6—(a) Transmissivity (T_ω) of an anisotropic plasma slab as a function of RF frequency for the ion cyclotron wave ($d/\lambda_p=2.5$, $\omega_b/\omega_p=2$) for various electron collision frequencies. (b) Reflectivity (R_ω) of an anisotropic plasma slab as a function of RF frequency for the ion cyclotron wave ($d/\lambda_p=2.5$, $\omega_b/\omega_p=2$) for various electron collision frequencies. (c) Absorptivity (A_ω) of an anisotropic plasma slab as a function of RF frequency for the ion cyclotron wave ($d/\lambda_p=2.5$, $\omega_b/\omega_p=2$) for various electron collision frequencies.



(a)




(b)




(c)

Fig. 7—(a) Transmissivity (T_ω) of an anisotropic plasma slab as a function of RF frequency for the extraordinary wave ($d/\lambda_p=2.5$, $\omega_b/\omega_p=2$) for various electron collision frequencies. (b) Reflectivity (R_ω) of an anisotropic plasma slab as a function of RF frequency for the extraordinary wave ($d/\lambda_p=2.5$, $\omega_b/\omega_p=2$) for various electron collision frequencies. (c) Absorptivity (A_ω) of an anisotropic plasma slab as a function of RF frequency for the extraordinary wave ($d/\lambda_p=2.5$, $\omega_b/\omega_p=2$) for various electron collision frequencies.



(a)



(b)

Fig. 8—(a) Effective noise temperature for a hypersonic space vehicle (anisotropic plasma—longitudinal propagation with $\nu/\omega_p = 10^{-2}$, $d/\lambda_p = 2.5$, $\omega_b/\omega_p = 2$). (b) Effective noise temperature for a hypersonic space vehicle (anisotropic plasma—transverse propagation with $\nu/\omega_p = 10^{-2}$, $d/\lambda_p = 2.5$, $\omega_b/\omega_p = 2$).

VI. Conclusions

The total noise power available at a receiving antenna on a hypervelocity space vehicle has been determined by treating the engulfing plasma sheath as a uniform slab of plasma. The noise emission from the plasma can then be evaluated in terms of a boundary-value problem which for this simple model can be completely solved. The effect of high temperatures of the vehicle surface and of noise sources external to the vehicle and plasma sheath are included in the analysis.

When the plasma sheath is isotropic, the main noise power is due to emission from the vehicle surface if the RF frequency is much lower than the plasma frequency; it is due to sources outside both the vehicle and plasma for RF frequencies much greater than the plasma frequency and results from direct emission from the plasma for RF frequencies in the neighborhood of the plasma frequency. The noise power from the plasma itself is the most significant and exhibits a sharp maximum at an RF frequency just above the plasma frequency. This enhances the suggestion[8] of the value of noise emission measurements as a diagnostic tool for the exploration of the hypersonic environment of a space or re-entry vehicle.

The effects of an anisotropic plasma sheath (due to an auxiliary magnetic field) have also been investigated for the two cases of the magnetic field normal to the sheath and parallel to the sheath. The effect of the anisotropy is to alter completely the spectral characteristics of the available noise power at the receiving antenna. Several regions of both weak and intense noise emission are now possible, depending upon magnetic field strength and orientation.

Generalized Appleton-Hartree Equation for Any Degree of Ionization and Application to the Ionosphere*

I. P. SHKAROFSKY†, member, ire

Summary—**A generalized Appleton-Hartree equation is derived, applicable to any variation of electron collision frequency with electron speed and any degree of ionization. Regions of the parameters where simplification occurs are given. Results are shown for the ionosphere (60 to 320 km) and compared with experimental data. Good agreement is obtained for the *D* layer. Experimental data for the *E* layer can also be explained by assuming an electron temperature several times the gas temperature. This is consistent with rocket data and a measurement by Sputnik III. It is shown that the classic Appleton-Hartree equation should be applicable with no corrections necessary for the F_2 layer, provided the collision frequency is averaged appropriately.**

I. Introduction

Most investigations on the propagation of an electromagnetic wave in a magnetized plasma are based on the concept of a constant value for the electron collision frequency, independent of electron speed. The classic Appleton-Hartree equation, used for propagation in the ionosphere, has this inherent assumption. Because the electron elastic collision frequency with the nitrogen molecules in the atmosphere varies as the square of the electron speed,[1] a large discrepancy between classic theory and ionospheric experiments can be expected. An accurate analysis must include these effects. Several corrections to include this speed variation have appeared in the literature.[2–4] These references only account for the neutral particle effects, under the assump-

* Received by the IRE, April 6, 1961. The work reported in this paper was done under Contract GX9-998054-0001-70-Q82 to RCA, Missile and Surface Radar Div., Moorestown, N. J.

† RCA Victor Co., Ltd., Research Labs., Montreal, Canada.

[1] A. V. Phelps and J. L. Pack, "Electron collision frequencies in nitrogen and in the lower ionosphere," *Phys. Rev. Lett.*, vol. 3, pp. 340–342, October, 1959; "Drift velocities of slow electrons in helium, neon argon, hydrogen, and nitrogen," *Phys. Rev.*, vol. 121, pp. 798–806, February, 1961.

[2] R. Jancel and T. Kahn, "Théorie du couplage des ondes électromagnetiques ordinaire et extraordinarie dans un plasma inhomogène et anisotrope et conditions de reflexion. Applicàtions à l'ionosphere," *J. Phys. Radium*, vol. 16, pp. 136–145, February, 1955; "Théorie non Maxwellienne des plasmas homogènes et anisotropes," *Nuovo Cim.*, vol. 12, pp. 573–612; November, 1954.

[3] H. K. Sen and A. A. Wyller, "On the generalization of the Appleton-Hartree magnetoionic formulas," *J. Geophys. Res.*, vol. 65, pp. 3931–3950; December, 1960.

[4] A. V. Phelps, "Propagation constants for electromagnetic waves in weakly ionized dry air," *J. Appl. Phys.*, vol. 31, pp. 1723–1729; October, 1960.

tion that the gas is very slightly ionized. This may be a good approximation to conditions in the D layer, but not in the F layers of the ionosphere. In the following, a generalized Appleton-Hartree equation, valid for *any* variation of the collision frequency with electron speed and *any* degree of ionization, is derived. The results are then applied to the ionosphere. Various domains of the parameters where simplification may result are investigated.

A method for calculating the electronic conductivity for any degree of ionization has been developed.[5] In this method, the usual series expansion of Laguerre polynomials is substituted into the Fokker-Planck equation for Coulomb (electron-ion and electron-electron) collisions,[6] and into the Boltzmann equation for electron collisions with neutral particles. A Maxwellian distribution in electron velocity is assumed. For Coulomb collisions, the expressions are the same as those derived by Landshoff.[7] Collisions of electrons with neutral particles and ions, ac electric fields, as well as static magnetic fields, are treated in this analysis. In the limit of a completely ionized gas, the results agree with those of Spitzer and Harm.[8] For a slightly ionized gas, no expansion is necessary and the results are identical with those of Allis.[9] The conductivity can be calculated by using the Dingle tabulations,[10] if the electron collision frequency varies as an integral power (between -3 and 3) of velocity. This method, to be reviewed in Section II, is utilized here to yield the proper averages (or multiplying factors) for the collision frequency and multiplying factors for the angular frequency.

II. Basis of Analysis

In this analysis, existing gradients and fluctuations in the dielectric coefficient, ion motion and thermal motion of the electrons which give rise to plasma waves, are all neglected. The limit for the convergence of the theory, if thermal motions are neglected, is that the ratio of the thermal velocity of the electrons $\sqrt{kT/m}$ to the phase velocity of the wave c/n is small. That is, $n^2kT/mc^2 \ll 1$, where n is the refractive index and c is the velocity of light.

The electronic conductivity matrix $(\mathfrak{d})$ for any degree of ionization and any variation of electron-neutral particle collision frequency ν_m with electron velocity v can be represented as[5]

$$(\mathfrak{d}) = \begin{pmatrix} b+c & j(b-c) & 0 \\ -j(b-c) & b+c & 0 \\ 0 & 0 & d \end{pmatrix}, \tag{1}$$

with

$$d = \frac{Ne^2}{m} \frac{1}{\langle \nu_0 \rangle g_0 + j\omega h_0} \tag{2}$$

$$2c = \frac{Ne^2}{m} \frac{1}{\langle \nu_0 \rangle g_+ + j(\omega + \omega_b) h_+} \tag{3}$$

$$2b = \frac{Ne^2}{m} \frac{1}{\langle \nu_0 \rangle g_- + j(\omega - \omega_b) h_-} \tag{4}$$

where

N,e,m are respectively electron density, charge, and mass,

ω is the RF angular frequency,

ω_b is the cyclotron angular frequency, $\omega_b = |eB/m|$ where B is the magnitude of the dc magnetic field. The magnetic field is taken parallel to the z-axis of a Cartesian or cylindrical system of coordinates.

Also

$\langle \nu_0 \rangle$ is the averaged electron collision frequency with neutrals plus ions and will be defined below.

$g_{0,+,-}$ and $h_{0,+,-}$ are correction factors to account for the variation with velocity of the electron-neutral particle collision frequency and for electron-ion and electron-electron effects.

The averaged collision frequency is defined so as to make g and h equal to 1 at high angular frequencies. This requires[5] that

$$\langle \nu_0 \rangle = -\frac{4\pi}{3N} \int_0^\infty \frac{\partial f_0^0}{\partial v} v^3 \nu_0 dv \tag{5}$$

where

f_0^0 is the distribution function of electron velocity,

v is the electron velocity,

ν_0 is the unaveraged total electron collision frequency—a function of electron speed.

Let the contributions to ν_0 be ν_m from neutrals, whose variation with velocity depends on the constituent gases, and ν_{ei} from ions, known[6] to be of the form

$$\nu_{ei} = \frac{N_+ Y}{v^3}$$

where

$$Y = 4\pi \left(\frac{Ze^2}{4\pi\epsilon_0 m} \right)^2 \ln \Lambda, \qquad \Lambda = \frac{3(4\pi\epsilon_0 kT)^{3/2}}{2Ze^3(\pi N)^{1/2}}, \tag{6}$$

[5] I. P. Shkarofsky, "Values of the transport coefficients in a plasma for any degree of ionization based on a Maxwellian distribution," *Canad. J. Phys.*, vol. 39; November, 1961.

[6] M. P. Bachynski, I. P. Shkarofsky and T. W. Johnston, "Plasmas and the Electromagnetic Field," McGraw-Hill Book Co., Inc., New York, N. Y.; in press.

[7] R. Landshoff, "Transport phenomena in a completely ionized gas in presence of a magnetic field," *Phys. Rev.*, vol. 76, pp. 904–909; October 1, 1949.

[8] L. Spitzer and R. Harm, "Transport phenomena in a completely ionized gas," *Phys. Rev.*, vol. 89, pp. 977–981; March 1, 1953.

[9] W. P. Allis, "Motions of ions and electrons," in "Handbuch der Physik," S. Flügge, Ed., Springer-Verlag, Berlin, Ger., vol. 21; 1956.

[10] R. B. Dingle and D. Arndt, "The integrals $\mathfrak{A}p(x)$ and $\mathfrak{B}p(x)$ and their tabulation," *Appl. Sci. Res.*, vol. 6-B, no. 3, pp. 144–154, 1957; "The integrals $\mathfrak{C}p(x)$ and $\mathfrak{D}p(x)$ and their tabulation," pp. 155–164; "The integrals $\mathfrak{E}p(x)$ and $\mathfrak{F}p(x)$ and their tabulation," no. 4, pp. 245–252; 1957.

where

k is Boltzmann's constant,
T is the electron temperature,
N_+ is the ion density,
Z is the ion charge number, and
ϵ_0 is the permittivity of free space.

For the temperatures considered here, $N_+ = N$ and $Z = 1$. Thus

$$\nu_g = \nu_m(v) + \nu_{ei}(v). \tag{7}$$

Suppose that one can express ν_m as a power index of velocity, not necessarily an integer, *viz.*,

$$\nu_m = cv^r. \tag{8}$$

In most cases, this can be done over the velocity range where the largest contribution to the integral in (5) occurs. Also, if the magnitude of the electric field is sufficiently small, one can let f_0^0 be a Maxwellian distribution

$$f_0^0 = N\left(\frac{m}{2\pi kT}\right)^{3/2} \epsilon^{-mv^2/2kT}. \tag{9}$$

With these assumptions, substitution of (7) into (5) yields

$$\langle \nu_g \rangle = \langle \nu_m \rangle + \langle \nu_{ei} \rangle, \tag{10}$$

with

$$\langle \nu_{ei} \rangle = \frac{4(2\pi)^{1/2}}{3} N_+ \left(\frac{Ze^2}{4\pi\epsilon_0 kT}\right)^2 \left(\frac{kT}{m}\right)^{1/2} \ln \Lambda \tag{11}$$

and

$$\langle \nu_m \rangle = \frac{c\Gamma\left(\frac{5+r}{2}\right)}{\Gamma(5/2)} \left(\frac{2kT}{m}\right)^{r/2} \tag{12}$$

where Γ is a Gamma function.

The (g_0, h_0), (g_+, h_+) and (g_-, h_-) factors are respectively functions of $\omega/\langle \nu_g \rangle$, $(\omega+\omega_b)/\langle \nu_g \rangle$ and $(\omega-\omega_b)/\langle \nu_g \rangle$. They are also functions of $\langle \nu_m \rangle/\langle \nu_{ei} \rangle$, of Z, and depend on the variation of ν_m with velocity. These functions are tabulated in a recent article by the author[5] for $Z = 1$, power law variations of $r = -3, -2 \cdots 3$, various ratios of $\langle \nu_m \rangle/\langle \nu_{ei} \rangle$ and continuous $(\omega_\pm\omega_b)/\langle \nu_g \rangle$ values. In a slightly ionized gas, when $\langle \nu_m \rangle/\langle \nu_{ei} \rangle$ becomes quite large, the values of g and h can be obtained from simple analysis, using the tabulations of the Dingle[10] functions.

The g and h functions are monotonic; g increases from an asymptotic value less than unity at small values of $(\omega_\pm\omega_b)/\langle \nu_g \rangle$ to unity at large $(\omega_\pm\omega_b)/\langle \nu_g \rangle$ values, and h decreases from a limiting value greater than unity to unity. If the power index r in (8) is less than or equal to zero, g and h also vary monotonically as $\langle \nu_m \rangle/\langle \nu_{ei} \rangle$ increases. When r is equal to 0, g and h are identically unity at large ratios of $\langle \nu_m \rangle/\langle \nu_{ei} \rangle$, that is for the slightly ionized gas. However, when r is greater than or equal to 1, g and h vary from the values for the slightly ionized gas to approximately unity, at $\langle \nu_m \rangle/\langle \nu_{ei} \rangle$ between 1 and 10, and then g and h deviate more from unity as $\langle \nu_m \rangle/\langle \nu_{ei} \rangle$ decreases, until they approach the limits for the completely ionized gas. The explanation for this variation is the fact that ν_g, equal to $(\nu_m+\nu_{ei})$, is approximately constant[5,6] when $\langle \nu_m \rangle \approx \langle \nu_{ei} \rangle$ and when ν_m varies as a positive power of speed. In other words, since ν_{ei} decreases with electron speed as $1/v^3$ and ν_m increases as v^r, there exists a ratio, $\langle \nu_m \rangle/\langle \nu_{ei} \rangle$, for which the sum of the decreasing and increasing velocity function results in a more or less constant ν_g with respect to velocity, and when this occurs, g and h are approximately 1. Consequently, g and h shift towards 1 and then deviate from 1 as the degree of ionization in the gas increases.

III. Generalized Equation for the Refractive Index

From Maxwell's curl equation, we can write

$$\Delta x \boldsymbol{H} = [\mathfrak{d} + j\omega\epsilon_0] \cdot \boldsymbol{E} = j\omega\epsilon_0 \boldsymbol{\kappa} \cdot \boldsymbol{E} \tag{13}$$

where

$\boldsymbol{H}$ is the magnetic field vector, and
$\mathfrak{d}$ and $\boldsymbol{\kappa}$ are respectively the conductivity and dielectric coefficient matrices.

If the elements of the dielectric tensor are denoted by

$$(\kappa) = \begin{pmatrix} \epsilon_{11} & j\epsilon_{12} & 0 \\ -j\epsilon_{21} & \epsilon_{22} & 0 \\ 0 & 0 & \epsilon_{33} \end{pmatrix} \tag{14}$$

then one can write

$$\epsilon_{22} = \epsilon_{11} = 1 - \xi - \psi \tag{15}$$

$$\epsilon_{12} = \epsilon_{21} = -\xi + \psi \tag{16}$$

$$\epsilon_{33} = 1 - \gamma. \tag{17}$$

Note that the ξ, ψ, γ coefficients are equal to $(j/\omega\epsilon_0)$ times the b, c and d coefficients represented in (2) to (4). For any degree of ionization and any variation of ν_m with velocity, ξ, ψ, γ are related to the g and h functions by

$$\xi = \frac{\omega_p^2}{2\omega^2} \frac{j\omega}{\langle \nu_g \rangle g_- + j(\omega - \omega_b)h_-} = \frac{x/2}{h_- - jg_- z - h_- y} \tag{18}$$

$$\psi = \frac{\omega_p^2}{2\omega^2} \frac{j\omega}{\langle \nu_g \rangle g_+ + j(\omega + \omega_b)h_+} = \frac{x/2}{h_+ - jg_+ z + h_+ y} \tag{19}$$

$$\gamma = \frac{\omega_p^2}{\omega^2} \frac{j\omega}{\langle \nu_g \rangle g_0 + j\omega h_0} = \frac{x}{h_0 - jg_0 z} \tag{20}$$

where

$\omega_p = (Ne^2/m\epsilon_0)^{1/2}$ is the plasma frequency,
$\langle \nu_g \rangle$ is the average collision frequency of electrons

In terms of the ξ, ψ and γ coefficients, this is

$$n^2 = 1 - \frac{\dfrac{4\xi\psi}{\alpha} - \dfrac{4\xi\psi - \gamma\alpha}{\alpha(\gamma - 1)}\sin^2\theta}{1 + \dfrac{\alpha - \gamma + 4\xi\psi - \alpha\gamma}{2\alpha(\gamma - 1)}\sin^2\theta \pm \left\{\left[\dfrac{\alpha - \gamma - 4\xi\psi + \alpha\gamma}{2\alpha(\gamma - 1)}\sin^2\theta\right]^2 + \left(\dfrac{\xi - \psi}{\alpha}\right)^2\cos^2\theta\right\}^{1/2}} \tag{29}$$

with neutrals plus ions and is defined in (5) and (10), and[11]

$$x = \omega_p^2/\omega^2 \qquad y = \omega_b/\omega \qquad z = \langle\nu_g\rangle/\omega. \tag{21}$$

The following equation results[2,6] for n, the magnitude of the refractive index, from Maxwell's equations, assuming a plane-wave solution of the form $\exp(-j(\omega/c)\boldsymbol{n}\cdot\boldsymbol{r})$.

where $\alpha = \xi + \psi$. This expansion follows after considerable algebraic manipulation from (28) and after $2(A - B + C)$, $(2A - B)$ and $(B^2 - 4AC)^{\frac{1}{2}}$ have been divided by $2\alpha(\gamma - 1)$.

Let us further manipulate the equations with the values of ξ, ψ and γ given in (18) to (20). Again, after considerable algebra, one finds[12]

$$n^2 = 1 - \frac{x + \left[\dfrac{jx(z\Theta_1 + j\Theta_3)}{h_0 - x - jg_0z}\right]\sin^2\theta}{\mathcal{g}_1 - jz\mathcal{g}_2 + \left\{\left(\dfrac{-y^2\mathcal{g}_3 + z^2\Theta_5 + j\Theta_4 z - jx(z\Theta_1 + j\Theta_3)}{2(h_0 - x - jg_0z)}\right)\sin^2\theta \pm \left[\left(\dfrac{-y^2\mathcal{g}_3 + z^2\Theta_5 + j\Theta_4 z - jx(z\Theta_1 + j\Theta_3)}{2(h_0 - x - jg_0z)}\right)^2\sin^4\theta + (y\mathcal{g}_4 - jz\Theta_2)^2\cos^2\theta\right]^{1/2}\right\}} \tag{30}$$

$$n^4[\epsilon_{11}\sin^2\theta + \epsilon_{33}\cos^2\theta] - n^2[(\epsilon_{11}^2 - \epsilon_{12}^2)\sin^2\theta + \epsilon_{11}\epsilon_{33}(1 + \cos^2\theta)] + \epsilon_{33}(\epsilon_{11}^2 - \epsilon_{12}^2) = 0 \tag{22}$$

where

$$\tan^2\theta = (n_x^2 + n_y^2)/n_z^2. \tag{23}$$

That is, θ is the angle between the direction of propagation and the dc magnetic field, assumed along the z axis. Eq. (22) can be written as

$$An^4 - Bn^2 + C = 0 \tag{24}$$

where, according to (22) and (15) to (17), the coefficients are given by

$$\begin{aligned} A &= \epsilon_{11}\sin^2\theta + \epsilon_{33}\cos^2\theta \\ &= 1 - (\xi + \psi)\sin^2\theta - \gamma\cos^2\theta \qquad (25) \\ B &= (\epsilon_{11}^2 - \epsilon_{12}^2)\sin^2\theta + \epsilon_{11}\epsilon_{33}(1 + \cos^2\theta) \qquad (26) \\ &= 2 - \xi(2 + \sin^2\theta) - \psi(2 + \sin^2\theta) \\ &\quad - \gamma(1 - \xi - \psi)(2 - \sin^2\theta) + 4\xi\psi\sin^2\theta \\ C &= \epsilon_{33}(\epsilon_{11}^2 - \epsilon_{12}^2) \\ &= 1 - 2(\xi + \psi) + 4\xi\psi - \gamma[1 - 2(\xi + \psi) + 4\xi\psi]. \qquad (27) \end{aligned}$$

The solution of the quadratic equation for the square of the refractive index, is usually, in ionospheric theory, written with the square root in the denominator. That is,

$$\begin{aligned} n^2 &= \frac{B \pm \sqrt{B^2 - 4AC}}{2A} \\ &= 1 - \frac{2(A - B + C)}{2A - B \pm \sqrt{B^2 - 4AC}}. \end{aligned} \tag{28}$$

[11] In ionospheric theory, the usual notation is capital X, Y, Z instead of the lower-case letters adopted here.

where

$$x = \omega_p^2/\omega^2 \qquad y = \omega_b/\omega \qquad z = \langle\nu_g\rangle/\omega$$

$$2\Theta_1 = 2g_0 - g_- + g_+ \qquad 2\Theta_2 = g_+ - g_- \tag{31)(32}$$

$$2\Theta_3 = 2h_0 - h_- - h_+ - y(h_+ - h_-) \tag{33}$$

$$2\Theta_4 = g_0(h_- + h_+) + h_0(g_- + g_+) - 2g_-h_+ - 2g_+h_- + y(-g_0h_- + g_0h_+ - 2g_-h_+ + 2g_+h_-) \tag{34}$$

$$2\Theta_5 = g_0g_- + g_0g_+ - 2g_-g_+ \tag{35}$$

$$2\mathcal{g}_1 = h_+ + h_- + y(h_+ - h_-) \qquad 2\mathcal{g}_2 = g_+ + g_- \tag{36)(37}$$

$$2y^2\mathcal{g}_3 = h_0(h_- + h_+) - 2h_-h_+ + yh_0(h_+ - h_-) + 2h_-h_+y^2 \tag{38}$$

$$2y\mathcal{g}_4 = h_+ - h_- + y(h_+ + h_-) \tag{39}$$

and where

g_0, h_0 are the values of g and h for argument $\omega/\langle\nu_g\rangle$,
g_+, h_+ for argument $(\omega + \omega_b)/\langle\nu_g\rangle$, and
g_-, h_- for argument $|\omega - \omega_b|/\langle\nu_g\rangle$.

In (31) to (39), two sets of functions, 5Θ and $4\mathcal{g}$ functions, are defined. The Θ ones are identically zero, and the $\mathcal{g}$'s are 1, when the g and h parameters are all equal to 1 (which occurs for constant collision frequency in a slightly ionized gas).

The complicated equation can also be written as

$$n^2 = 1 - \frac{x(1 + jS)}{\mathcal{g}_1 - jz\mathcal{g}_2 - y_LR}, \tag{40}$$

[12] Since the g and h parameters are defined to be corrections in the *denominators* of ξ, ψ and γ, these correction factors combine readily in the following evaluation, and this fact justifies the original definition.

where

$$S = \frac{y_T^2}{h_0 - x - jg_0 z}\left(\frac{z\Theta_1 + j\Theta_3}{y^2}\right)$$

$$y_L = y\cos\theta \qquad y_T = y\sin\theta$$

$$R = V - jxS/2y_L \mp [(g_4 - jz\Theta_2/y)^2 + (V + jxS/2y_L)^2]^{1/2}$$

$$V = \frac{y_T^2[g_3 - (z^2\Theta_5 + j\Theta_4 z)/y^2]}{2y_L(h_0 - x - jg_0 z)}. \tag{41}$$

θ is arbitrary). Obviously, in this case $g_0 = g_+ = g_- = 1$, $h_0 = h_+ = h_- = 1$, and consequently

$$4\xi\psi = \gamma(\xi + \psi)$$

$$\Theta_i = 0 \qquad g_i = 1 \qquad S = 0 \qquad z = \nu_m/\omega$$

$$V = y_T^2/[2y_L(1 - x - jz)] \qquad R = V \mp \sqrt{1 + V^2}. \tag{46}$$

The equation for the square of the refractive index becomes the Appleton-Hartree equation, namely:

$$n^2 = 1 - \frac{x}{1 - jz - \dfrac{y_T^2}{2(1 - x - jz)} \pm \left[\dfrac{y_T^2}{4(1 - x - jz)^2} + y_L^2\right]^{1/2}}. \tag{47}$$

IV. Particular Cases

Let us now consider particular cases, when simplification results.

1) Propagation along the magnetic field, *i.e.*, $\theta = 0$:

One obtains two transverse cyclotron waves, according to the $\pm$ sign in the denominator, given by

$$n^2 = 1 - \frac{x}{h_+ - jg_+ z + h_+ y} = 1 - 2\psi = \epsilon_{11} - \epsilon_{12} \tag{42}$$

and

$$n^2 = 1 - \frac{x}{h_- - jg_- z - h_- y} = 1 - 2\xi = \epsilon_{11} + \epsilon_{12}. \tag{43}$$

The wave with h_- and g_- corresponds to the electron cyclotron wave (sometimes called the extraordinary wave for $\theta = 0$), and displays a resonance at $y = 1$ or $\omega = \omega_b$. The wave with h_+ and g_+ corresponds to the ion cyclotron wave (sometimes called the ordinary wave for $\theta = 0$). The terminology of "ion cyclotron wave" is adopted, because this wave would also display a resonance at the ion cyclotron frequency (at $\omega = eB/M_+$) if ion motions were included in the analysis.[6]

2) Propagation perpendicular to the magnetic field, *i.e.*, $\theta = 90$:

One obtains the ordinary and extraordinary waves. The ordinary wave results from choosing the minus sign in the denominator,

$$n^2 = 1 - \frac{x}{h_0 - jg_0 z} = 1 - \gamma = \epsilon_{33}, \tag{44}$$

and the extraordinary wave results from the plus sign in the denominator,

$$n^2 = \frac{(1 - 2\psi)(1 - 2\xi)}{1 - \psi - \xi} = \frac{(\epsilon_{11} - \epsilon_{12})(\epsilon_{11} + \epsilon_{12})}{\epsilon_{11}}. \tag{45}$$

3) Constant collision frequency and a slightly ionized gas:

The classic Appleton-Hartree equation, usually applied to ionospheric work, results. Note the simplification for this case, namely that the angular term in the numerator is zero and so are several factors in the denominator. (Here, and in the following cases, the angle

4) High collision frequencies, when $(\langle\nu_g\rangle) \gg \omega_b$ and $(\langle\nu_g\rangle) \gg \omega$:

In a recent article by the author[5] it is shown that $h_0 = h_+ = h_- = h(0)$ and $g_0 = g_- = g_+ = g(0)$, where $h(0)$ and $g(0)$ are the values of the functions for zero argument. Let us define an effective normalized collision frequency for this case as

$$z_1 = zg(0)/h(0) = \langle\nu_g\rangle g(0)/\omega h(0) \tag{48}$$

and a reduced plasma frequency x_1 as

$$x_1 = x/h(0) = \omega_p^2/\omega^2 h(0). \tag{49}$$

The simplification in the Θ and g functions is given in Table I, Column 2. The refractive index satisfies the Appleton-Hartree equation (47), with x_1 and z_1 defined in (48) and (49), replacing x and z. The correction factors, $g(0)$ and $h(0)$, depend on the degree of ionization and on the variation with electron speed of ν_m, the electron collision frequency with neutrals. For example,[5] in very slightly ionized nitrogen, $g(0) = 0.6$ and $h(0) = 3.0$, since in nitrogen, $\nu_m \propto v^2$.

5) High RF angular frequencies, when

$$\text{a) } \omega \gg (\langle\nu_g\rangle) \quad \text{and} \quad \text{b) } \omega \gg \omega_b$$

or

$$\text{a) } \omega \gg (\langle\nu_g\rangle) \quad \text{and} \quad \text{b) } \omega_b \gg \omega$$

or

$$\text{a) } \langle\nu_g\rangle \cong 0 \quad \text{and} \quad \text{b) } \omega \neq \omega_b.$$

As discussed in Section II, all the g and h functions approach 1, and hence, the usual Appleton-Hartree equation (47) results, with $z = \langle\nu_g\rangle/\omega$. Note, that the collision frequency to be applied is that defined in (5), and results quoted in the literature must be checked to determine whether they refer to the same average.

6) High magnetic fields, satisfying

$$\text{a) } \omega_b \gg (\langle\nu_g\rangle) \qquad \text{b) } \omega_b \gg \omega.$$

In this case, $h_+ = h_- = g_+ = g_- = 1$, but g_0 and h_0 depend on $\omega/\langle\nu_g\rangle$. If one also has $\omega \gg (\langle\nu_g\rangle)$, case 5) results. If on the other hand, $\omega \ll (\langle\nu_g\rangle)$, then $g_0 = g(0)$ and $h_0 = h(0)$.

TABLE I

SIMPLIFICATION OF THE Θ AND $\mathcal{G}$ FUNCTIONS IN THE GENERALIZED APPLETON-HARTREE EQUATION FOR PARTICULAR CASES (SEE TEXT)

Function	a) Case 3 ν_m constant and neutral dominated b) Case 5 $\omega \gg (\langle \nu_g \rangle)$ and $\omega \gg \omega_b$ c) Case 5 $\omega \gg (\langle \nu_g \rangle)$ and $\omega \ll \omega_b$ d) Case 5 $\langle \nu_g \rangle \cong 0$ and $\omega \neq \omega_b$ e) Case 8 $\nu_g = \nu_m + \nu_{ei}$ constant
$g_0, \pm$	1
$h_0, \pm$	1
$\Theta_{1,2,3,4,5}$	0
$\mathcal{G}_{1,2,3,4}$	1
S	0
V	$\dfrac{y_T^2}{2y_L(1-x-jz)}$

Function	Case 4 $(\langle \nu_g \rangle) \gg \omega_b$ and $(\langle \nu_g \rangle) \gg \omega$	Case 6 $\omega_b \gg \omega$ and $\omega_b \gg (\langle \nu_g \rangle)$	Case 7 $y=1$ and $(\langle \nu_g \rangle) \ll \omega = \omega_b$
g_0	$g(0)$	g_0	1
g_-	$g(0)$	1	$g(0)$
g_+	$g(0)$	1	1
h_0	$h(0)$	h_0	1
h_-	$h(0)$	1	$h(0)$
h_+	$h(0)$	1	1
Θ_1	0	g_0-1	$[1-g(0)]/2$
Θ_2	0	0	$[1-g(0)]/2$
Θ_3	0	h_0-1	0
Θ_4	0	g_0+h_0-2	$3[1-g(0)]/2$
Θ_5	0	g_0-1	$[1-g(0)]/2$
$\mathcal{G}_1$	$h(0)$	1	1
$\mathcal{G}_2$	$g(0)$	1	$[1+g(0)]/2$
$\mathcal{G}$	$\lvert h(0)\rvert^2$	$1+(h_0-1)/y^2 \cong 1$ since $y \gg 1$	1
$\mathcal{G}_4$	$h(0)$	1	1
S	0	$\left(\dfrac{z(g_0-1)+j(h_0-1)}{h_0-x-jg_0z}\right)\sin^2\theta$	$\dfrac{z[1-g(0)]\sin^2\theta}{2(1-x-jz)}$
V	$\dfrac{\lvert h(0)\rvert^2 y_T^2}{2y_L(h(0)-x-jg(0)z)}$	$\dfrac{\lvert h_0-1-jz(g_0-1)\rvert(1-jz)\sin^2\theta}{2(h_0-x-jg_0z)}$	$\left(\dfrac{2-jz[1-g(0)](3-jz)}{2(1-x-jz)}\right)\sin^2\theta$

The general equation for the refractive index reduces to

$$n^2 = 1 - \frac{x - x\left[-jz(g_0-1)+(h_0-1)\right]\sin^2\theta/(h_0-x-jg_0z)}{1-jz-\left\{\left(\dfrac{y^2+(1-jz+x)\left[h_0-1-jz(g_0-1)\right]}{2(h_0-x-jg_0z)}\right)\sin^2\theta \pm \left[\left(\dfrac{y^2+(1-jz-x)\left[h_0-1-jz(g_0-1)\right]}{2(h_0-x-jg_0z)}\right)^2 \sin^4\theta + y^2\cos^2\theta\right]^{1/2}\right\}}. \tag{50}$$

7) Cyclotron resonance ($y=1$) with $\omega=\omega_b \gg (\langle \nu_g \rangle)$:

We now have $g_-=g(0)$, $h_-=h(0)$ and $g_0=g_+=1$, $h_0=h_+=1$, $y=1$. The modified Appleton-Hartree equation is (see Column 4 of Table I)

$$n^2 = 1 - \frac{x + jxz(1-g(0))\sin^2\theta/\left[2(1-jz-x)\right]}{1-jz\dfrac{(1+g(0))}{2}+\left\{\left(\dfrac{jz(1-g(0))(3-jz+x)-2}{4(1-x-jz)}\right)\sin^2\theta \pm \left[\left(\dfrac{jz(1-g(0))(3-jz-x)-2}{4(1-x-jz)}\right)^2 \sin^4\theta + \left(1-jz\dfrac{(1-g(0))}{2}\right)^2\cos^2\theta\right]^{1/2}\right\}}. \tag{51}$$

Note that the results, exactly at resonance, are independent of $h(0)$.

8) Constant total collision frequency:

We consider the situation when over a reasonable velocity range, ν_g, given by (7),

$$\nu_g = \nu_m(v) + \nu_{ei}(v) = \nu_m(\nu) + \frac{4\pi N_+}{v^3}\left(\frac{Ze^2}{4\pi\epsilon_0 m}\right)^2 \ln\Lambda, \tag{52}$$

is constant with respect to velocity. If ν_m varies as v^2, then ν_g is nearly constant[5] when $\langle \nu_m \rangle / \langle \nu_{ei} \rangle$ is between 2.25 and 3.7, since in this range $0.92 \leq g \leq 1$ and $1 \leq h \leq 1.038$. If ν_m varies as v, then $0.96 \leq g \leq 1$ and $1 \leq h \leq 1.035$, when $\langle \nu_m \rangle / \langle \nu_{ei} \rangle$ is between 3 and 15. Assuming that the error in taking g and h equal to 1 is small, the relationship for n reduces to the Appleton-Hartree equation (47), with z denoting ν_g/ω.

V. Application to the Ionosphere

In general, one can plot from the calculated g and h curves, the Θ and $\mathcal{G}$ functions vs $\langle\nu_g\rangle/\omega$ for various ω_b/ω and $\langle\nu_m\rangle/\langle\nu_{ei}\rangle$. The investigation that follows is for ν_m proportional to v^2. This applies up to about 120 km in the ionosphere, where electron collisions with the nitrogen species are predominant over collisions with the oxygen atoms. The usual assumption that the atmosphere is dry (contains no water vapor) is made throughout this discussion. Typical graphs are shown in Figs. 1–9 (pp. 1864–1868) for degrees of ionization corresponding to 1) a weakly ionized gas ($\langle\nu_m\rangle/\langle\nu_{ei}\rangle\rightarrow\infty$), 2) equal frequencies of electron collisions with neutrals and ions ($\langle\nu_m\rangle/\langle\nu_{ei}\rangle\cong 1$), and 3) an ion-dominated plasma ($\langle\nu_m\rangle/\langle\nu_{ei}\rangle\rightarrow 0$). Values of ω_b/ω equal to 10^4 or 10^3, 10^2, 10, 1 or 0.999, 10^{-1}, 10^{-2}, 10^{-4} are used.

Note the following characteristics in the figures:

1) For large $\langle\nu_g\rangle/\omega$, the Θ curves approach zero and the $\mathcal{G}$ curves approach the values given in Column 2 of Table I. Also, the lower the value of ω_b/ω, the quicker the curve attains its limit.

2) For negligible $\langle\nu_g\rangle/\omega$ and $\omega\neq\omega_b$, the Θ and $\mathcal{G}$ curves are respectively equal to 0 and 1, which should be so according to Column 1 of Table I. At cyclotron resonance, the curves assume the values tabulated in the last column of Table I. Note that if $\omega_b/\omega=0.999$, deviations towards zero or 1 occur for extremely small $\langle\nu_g\rangle/\omega$.

3) In the limit of $\omega_b\gg\langle\nu_g\rangle\gg\omega$, which, for example, occurs when $\omega_b/\omega=10^4$ and $10<(\langle\nu_g\rangle/\omega)<10^3$, some curves flatten out and tend towards the values given in Column 3 of Table I. If ω_b/ω is lower than 10^4, they never actually attain these limits.

4) The largest deviations are present in the curves for the slightly ionized gas, and the least in the partially ionized gas, $\langle\nu_m\rangle\approx\langle\nu_{ei}\rangle$. As the ionization increases, the $\mathcal{G}$ curves shift towards 1 and the Θ curves towards zero, and then they deviate more when $\langle\nu_m\rangle/\langle\nu_{ei}\rangle$ becomes less than 3. Finally, the limiting values for a completely ionized gas are attained.

The graphs show that the approach to the limiting values is slow in most cases, and hence the use of equivalent collision frequencies in the Appleton-Hartree equation must be justified by investigating curves such as illustrated here.

The curves in Figs. 1–9 are not sufficiently accurate to calculate the refractive index. As an example of the difficulty, consider the magnitude of the $(-y^2\mathcal{G}_3+z^2\Theta_5)$ combination in the generalized Appleton-Hartree equation (30). In many cases, one cannot obtain reasonable values, simply because of the inaccuracy in the $\mathcal{G}_3$ and Θ_5 functions. One can conclude that the Θ and $\mathcal{G}$ functions are only useful for illustrating the physical fact that large deviations from zero and unity can occur, and for providing regions where their replacement by limiting constants can be justified.

Values for the electron collision frequency with nitrogen molecules will now be given, and applied to the D layer of the ionosphere, or in general to heights below 85 km. Basically, the formula used for nitrogen is identical to that given by Huxley.[13,14] The cross section for nitrogen, Q_{N_2}, is[15]

$$Q_{N_2} = 3.29\times 10^{-23}v \text{ cm}^2 \ (v \text{ in cm/sec}) \tag{53}$$

and 0.8 times this value for air.

$$Q_{\text{air}} = 2.63\times 10^{-23}v \text{ cm}^2. \tag{54}$$

If N_M is the number density of air molecules, the collision frequency is

$$\nu_m = N_m vQ = 2.63\times 10^{-23}v^2(\rho/\rho_0)L_0 \tag{55}$$

where

ρ is the density,
ρ_0 is the density at standard temperature and pressure, and
L_0 is Loschmidth's number
$L_0=p_0/kT_0=2.687\times 10^{19}$ molecules/atm.cm^3.

Hence for air

$$\begin{aligned}\nu_m &= 7.073\times 10^{-4}(\rho/\rho_0)v^2(v \text{ in cm/sec})\\ &= 7.073(\rho/\rho_0)v^2(v \text{ in m/sec}).\end{aligned} \tag{56}$$

The high-frequency average is calculated from (12) to be equal to

$$\begin{aligned}\langle\nu_m\rangle &= 5.359T\rho/\rho_0\times 10^8\\ &= 1.9944N_M T\times 10^{-17}(N_M \text{ in } 1/m^3).\end{aligned} \tag{57}$$

Three different average collision frequencies are currently in use in the literature, namely $\langle\nu_m\rangle$, $\overline{\nu_m}$ and ν_P, defined, for a variation of $\nu_m\propto v^2$

$$\text{respectively by } \langle\nu_m\rangle = \overline{(1/v^2)d/dv(v^3\nu_m/3)} = 5\overline{\nu_m}/3,$$

$$\nu_m = \nu_m$$

and $\nu_P=0.4\langle\nu_m\rangle$. A bar denotes the following average for a scalar quantity ϕ

$$\bar{\phi} = (1/N)\int \phi f_0 4\pi v^2 dv.$$

[13] L. G. H. Huxley, "A discussion of the motion in nitrogen of free electrons with small energies with reference to the ionosphere," *J. Atm. and Terr. Phys.*, vol. 16, pp. 46–58; October, 1959.

[14] I. P. Shkarofsky, *et al.*, "Collision frequency associated with high temperature air and scattering cross-sections of the constituents," in "Electromagnetic Effects of Re-entry," Pergamon Press, New York, N. Y.; 1961.

[15] Phelps in a recent article[4] uses values for nitrogen which are 15 per cent larger than these. In a footnote, he quotes measurements, which should read, "are 10–12 per cent smaller" than given in his paper, so that his new values are 3–5 per cent larger than given here. For consistency, the analysis here is based exclusively on the cross sections plotted in Shkarofsky.[14] Also, for simplicity, the contribution from oxygen is neglected, since the additional error introduced is less than 15 per cent.




Fig. 1—The function Θ_1. The numbers beside the curves are values of ω_b/ω.
The set ———— corresponds to $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = \infty$
—·—·— $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = 1$
— — — $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = 0$




Fig. 2—The function Θ_2. The numbers beside the curves are values of ω_b/ω.
The set ———— corresponds to $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = \infty$
—·—·— $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = 1$
— — — $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = 0$




Fig. 3—The function Θ_3. The numbers beside the curves are values of ω_b/ω.
The set ———— corresponds to $\langle\nu_m\rangle/\langle\nu_{ei}\rangle=\infty$
Take $\Theta_3=0$ for $\langle\nu_m\rangle/\langle\nu_{ei}\rangle=1$
— — — $\langle\nu_m\rangle/\langle\nu_{ei}\rangle=0$




Fig. 4—The function Θ_4. The numbers beside the curves are values of ω_b/ω.
The set ———— corresponds to $\langle\nu_m\rangle/\langle\nu_{ei}\rangle=\infty$
—·—·— $\langle\nu_m\rangle/\langle\nu_{ei}\rangle=1$
— — — $\langle\nu_m\rangle/\langle\nu_{ei}\rangle=0$




Fig. 5—The function Θ_5. The numbers beside the curves are values of ω_b/ω.
The set ———— corresponds to $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = \infty$
—·—·— $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = 1$
— — — $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = 0$




Fig. 6—The function $\mathcal{J}_1$. The numbers beside the curves are values of ω_b/ω.
The set ———— corresponds to $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = \infty$
Take $\mathcal{J}_1 = 1$ for $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = 1$
— — — $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = 0$




Fig. 7—The function $\mathcal{J}_2$. The numbers beside the curves are values of ω_b/ω.
The set ———— corresponds to $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = \infty$
—·—·— $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = 1$
— — — $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = 0$




Fig. 8—The function $\mathcal{J}_3$. The numbers beside the curves are values of ω_b/ω.
The set ———— corresponds to $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = \infty$
Take $\mathcal{J}_3 = 1$ for $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = 1$
— — — $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = 0$




Fig. 9—The function $\mathcal{G}_4$. The numbers beside the curves are values of ω_b/ω.
The set ———— corresponds to $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = \infty$
Take $\mathcal{G}_4 = 1$ for $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = 1$
— — — $\langle \nu_m \rangle / \langle \nu_{ei} \rangle = 0$

Many discrepancies between quoted values, such as those of Huxley,[13] who uses the second average, and those of Phelps and Pack[1,4] and Seddon,[16] who adopt the third average, vanish, if this point is remembered. Here, the first average $\langle \nu_m \rangle$ is adopted. As a result, *the values of the collision frequency $\langle \nu_m \rangle$ here are 2.5 times larger than those plotted by Phelps, Pack and Seddon.* Another point to note[14] is that the measurements of the collision cross section of electrons with nitrogen molecules by Huxley,[13] by Phelps, *et al.*,[17] and by Phelps and Pack,[1] using different respective methods, all practically coincide numerically.

An attempt is now made to plot for the ionosphere the quantities $\langle \nu_g \rangle$ and $\langle \nu_m \rangle / \langle \nu_{ei} \rangle$ vs altitude up to 340 km, which is above the F_2 layer. One is immediately faced with three unknowns.

1) The electron density profile depends on local time, season, solar activity and latitude.

2) Although nitrogen is the basic constituent of air below 90 km, electron collisions with oxygen atoms become important at higher altitudes and comparable to that with nitrogen molecules in the F_2 layer. The exact relative proportion of nitrogen molecules and oxygen atoms vs height is unknown.

3) The electron temperature is unknown; it may be quite different, by as much as a factor of 5, than the temperature of the neutral particles. Furthermore, the velocity distribution of the electrons may also be non-Maxwellian.

For discussion, one can assume an average daytime profile[16,18,19] of electron density, shown in Fig. 10. A plasma frequency scale is also shown. We will also adopt the 1959 ARDC model of the atmosphere,[20] which provides values for the molecular weight, as well as for the gas temperature T_g and neutral particle density N_M. Electron collisions with neutral oxygen molecules are neglected as being small compared with collisions with nitrogen molecules.

Below 90 km, effects due to oxygen atoms[20] can also be neglected, and (57) applies for $\langle \nu_m \rangle$ in air.

Above 180 km, oxygen is assumed to be completely dissociated, and air can be considered to consist only of N_2 and O. Then the relative number densities are given in terms of the molecular weight of air

$$M = (28.016 N_{N_2} + 16 N_0)/N_M \tag{58}$$

by

$$N_{N_2} = N_M(M - 16)/12.016 \text{ and } N_0 = N_M - N_{N_2} \tag{59}$$

where N_{N_2} is the number density of nitrogen, whose molecular weight is 28.016, N_O is the number density of oxygen atoms (molecular weight = 16), and N_M is the number density of air (molecular weight = M). From the tabulated data[20] for N_M and M, the quantities N_{N_2} and N_O can be obtained. Let $\langle \nu_{N_2} \rangle$ and $\langle \nu_O \rangle$ be the averaged collision frequencies for N_2 and O. Then we know (see Section II) that the averages can be added to yield

[16] J. C. Seddon, "Summary of Rocket and Sate lite Observations Related to the Ionosphere," Natl. Aeronautics and Space Admin., Goddard Space Flight Ctr., Washington, D. C., NASA Note D-667; 1961.

[17] A. V. Phelps, *et al.*, "Microwave determination of the probability of collision of slow electrons in gases," *Phys. Rev.*, vol. 84, pp. 559–562; November 1, 1951.

[18] See "The Ionosphere"—IGY issue of PROC. IRE, vol. 47, pp. 167, 169, 273, 281, 292; February, 1959.

[19] J. A. Ratcliffe, Ed., "Physics of the Upper Atmosphere," Academic Press, New York, N. Y., pp. 409–411, 442–445; 1960.

[20] R. A. Minzner, *et al.*, "The ARDC Model Atmosphere, 1959," A.F. Cambridge Research Ctr., Cambridge, Mass., Rep. AFCRC-TR-59-267; August, 1959.




Fig. 10—The ratio $\langle \nu_m \rangle / \langle \nu_{ei} \rangle$ and the total collision frequency $\langle \nu_g \rangle$, vs height for an assumed average daytime profile of electron density (N) or plasma frequency (ω_p), if the electron and neutral particle temperatures are equal. The range in value of the cyclotron frequency (ω_b) is also shown. The arrows indicate possible deviations if the electron temperature is larger than the neutral particle temperature by the amount shown.

The average collision frequency with all neutrals, $\langle \nu_m \rangle$, viz.,

$$\langle \nu_m \rangle = \langle \nu_{N_2} \rangle + \langle \nu_0 \rangle. \tag{60}$$

The value of $\langle \nu_{N_2} \rangle$ is (1/0.8) times that in (57), since $\langle \nu_m \rangle$ was assumed there to be 80 per cent that of $\langle \nu_{N_2} \rangle$. Thus,

$$\langle \nu_{N_2} \rangle = 2.492 N_{N_2} T \times 10^{-17}. \tag{61}$$

This equation applies if the electron temperature is less than about 1500°K, which would be true[20] up to 400 km, if the electron and gas temperatures are equal ($T \cong T_g$). For higher temperatures, $\langle \nu_{N_2} \rangle$ does not vary as T, since[14] ν_{N_2} is not proportional to v^2. It is known[14] that the cross section of electron collisions with oxygen atoms, based on the analyses of Klein and Brueckner,[21] is nearly constant with speed and equal to 10^{-19} m^2. The analyses of Mitra, Yamanouchi, Robinson, Hammerling, *et al.*, and Lamb and Lin, which predict large cross sections at low electron energies, have been shown[14] to be questionable. A low cross section was also found experimentally by Lin and Kivel.[22] We therefore write

$$\nu_0 = N_0 v \times 10^{-19} \tag{62}$$

and averaging according to (12) yields

$$\langle \nu_0 \rangle = 0.8282 \times 10^{-15} T^{1/2} N_0. \tag{63}$$

Adding, (60) becomes (for $T \leq 1500$°K)

$$\langle \nu_m \rangle = 0.8282 \times 10^{-15} N_0 T^{1/2} + 2.493 \times 10^{-17} N_{N_2} T. \tag{64}$$

For reference, the value of ν_m before averaging is, according to (55) and (62), given

$$\nu_m = N_0 v \times 10^{-19} + N_{N_2} v^2 3.29 \times 10^{-25} (v \text{ in } m/s). \tag{65}$$

Between 90 km and 180 km, the relative proportions of N_2, O_2 and O are quite uncertain.[23] However, it is easy to show, from the values[20] of the molecular weight of air as a function of height and from (59), that up to 180 km, the number density of atomic oxygen is certainly not greater than 10 per cent that of nitrogen. Further evidence that this is so is given by Johnson.[24] Assuming that for lower altitudes $N_{N_2} \leq 10\ N_O$, one can neglect the contribution of atomic oxygen given by (63) to the averaged collision frequency and extend the range of (57) up to 180 km, as a first approximation. The error is less than 12.5 per cent.

Most of the uncertainty in the calculation arises from a lack of knowledge of the electron temperature and electron distribution function. The results, to be shown, are based on the ideal assumptions of a Maxwellian distribution and equal electron and gas temperatures. Some calculations based on higher electron temperatures are also shown. The electron and ion densities are assumed equal, and negative ions are neglected. Ions with charge numbers greater than one are assumed to be insignificant.

In Fig. 10, $\langle \nu_g \rangle$, the sum of electron collisions with all neutrals plus ions ($\langle \nu_m \rangle + \langle \nu_{ei} \rangle$) is also plotted where $\langle \nu_m \rangle$ is given by (57) up to 180 km and by (64) above 180 km, and where $\langle \nu_{ei} \rangle$ is given by (11). In MKS units,

$$\langle \nu_{ei} \rangle = 8.375\ N \log \Lambda \times 10^{-6} / T^{3/2}$$

and

$$\Lambda = 1.24 \times 10^7 (T^3/N)^{1/2}. \tag{66}$$

The ratio $\langle \nu_m \rangle / \langle \nu_{ei} \rangle$ is also given vs height. Both are based on the assumption that the electron and gas temperatures are equal. No attempt is made to calculate the conductivity functions g and h, mainly because of the uncertainties in the atomic oxygen concentration and electron temperature, and also because it is shown below that there are regions where g and h are 1.

Several calculations obtained by assuming a higher electron temperature are shown by arrows in Fig. 10.

[21] M. M. Klein and K. A. Brueckner, "Interaction of slow electrons with atomic oxygen and atomic nitrogen," *Phys. Rev.*, vol. 111, pp. 1115–1120; August, 1958.

[22] S. C. Lin and B. Kivel, "Slow-electron scattering by atomic oxygen," *Phys. Rev.*, vol. 114, pp. 1026–1027; May 15, 1959.

[23] Ratcliffe, *op. cit.*, p. 34.

[24] C. Y. Johnson, "Aeronomic Parameters from Mass Spectrometry," presented at the Symposium on Aeronomy, Copenhagen, Denmark; July, 1960.

One point is based on measurements with Sputnik III. Krassovsky[25] reports an effective electron temperature of about 7000°K at 242 km, whereas the ARDC value[20] for the air temperature is 1415°K. As a result of $T \cong 5T_g$, the value of $\langle \nu_m \rangle / \langle \nu_{ei} \rangle$ is raised and $\langle \nu_g \rangle$ is decreased at this height. The decrease in $\langle \nu_g \rangle$ is due to the smaller value of $\langle \nu_{ei} \rangle$ which decreases faster with temperature than $\langle \nu_m \rangle$ increases. At heights below 200 km, the ratio $\langle \nu_m \rangle / \langle \nu_{ei} \rangle$ would also be larger, but $\langle \nu_g \rangle$ would be increased rather than decreased. This is because $\langle \nu_m \rangle$ is now the main term in $\langle \nu_g \rangle$ and it increases with temperature. At 200 km, there is only a small change in $\langle \nu_g \rangle$, first a decrease as $T \rightarrow 3T_g$ and then an increase as $T \rightarrow 5T_g$. This result is obtained by plotting $\nu_m = \nu_{N_2} + \nu_O$ vs velocity up to 1 ev, using the collision cross-section data in Shkarofsky, *et al.*,[14] and using the values $N_{N_2} = 7.220 \times 10^{15}$ and $N_O = 1.186 \times 10^{15}$ deduced from Minzner[20] for 200 km. Note that the exact cross-section data for nitrogen is required for these higher temperatures and that ν_{N_2} does not vary as v^2. One finds approximately that ν_m obeys the following power law,

$$\nu_m = 1.265 \times 10^{-5} v^{1.3224} \tag{67}$$

so that

$$\langle \nu_m \rangle = 1.965 T^{.6612}. \tag{68}$$

The sum of $\langle \nu_m \rangle$ and $\langle \nu_{ei} \rangle$ varies little with temperature for 200 km.

The magnetic field of the earth varies between 0.365 and 0.575 gauss, depending on latitude and height. The cyclotron frequency $\omega_b = eB/m$ is then between 6.42×10^6 and 1.01×10^7, and this is indicated in Fig. 10. We thus see that the largest corrections in the conductivity occur in the D layer (at about 70 km), since $\omega_b \cong \langle \nu_g \rangle$. Above 110 km, in the E and F layers, $\omega_b \geq (10^2 \langle \nu_g \rangle)$, even if $T \cong 5T_g$ or $\langle \nu_g \rangle$ is five times that shown at 110 km. Also, the plasma frequency $\omega_p = (Ne^2/m\epsilon_0)^{1/2}$ is indicated in the figure, and obviously, above 110 km ω_p is much greater than $\langle \nu_g \rangle$. Thus both $x = \omega_p^2/\omega^2$ and $y = \omega_b/\omega$ are much greater than $z = \langle \nu_g \rangle / \omega$. Let us look at Table I. At cyclotron resonance, the last column (case 7) applies. Otherwise, depending on whether $\omega_b \gg \omega$ or $\omega_b \ll \omega$, the third (case 6) or first column (case 5) can be used. Note that provided ω_b is not too near to ω, all the g functions can be taken as one; the Θ functions, however, do not behave as nicely. In the general equation (30), one can neglect Θ_5 since $y^2 g_3 \gg z^2 \Theta_5$.

In the region where $\omega_b \geq (6 \times 10^3 \langle \nu_g \rangle)$, which occurs in the ionosphere above 150 km if $T = T_g$, and above 190 km if $T = 5T_g$, investigation of the g and Θ curves, Figs. 1–9, indicates that it is safe to use the ordinary Appleton-Hartree equation with $\langle \nu_g \rangle$ as the collision frequency, provided the RF angular frequency ω satisfies $\omega_b/\omega \leq 0.9$ or $100 \leq (\omega_b/\omega) \leq 2$. The limit $\omega_b \geq 6 \times 10^3 \langle \nu_g \rangle$, may in fact be less, since as (67) indicates ν_m varies as a power much less than 2, whereas the g and Θ functions are for $\nu_m \propto v^2$. Thus in the F_2 layer, except at cyclotron resonance, it should always be possible to let the g and h correction functions be 1, and the ordinary Appleton-Hartree equation should be applicable.

The region where ν_g is constant with respect to speed depends on $\langle \nu_m \rangle / \langle \nu_{ei} \rangle$. This ratio is quite uncertain because T is unknown. Assuming $T \approx T_g$, the region starts in the E layer and extends to 150 km. If T is five times greater than T_g, then ν_g is constant in the F_2 layer. (See arrow in Fig. 10 and limits for constant ν_g, if $\nu_m \propto v^2$ or $\nu_m \propto v$, given in Section IV, case 8.) This fact provides another justification for letting g and h be 1 in the F_2 layer. In any case, there exists a region where no correction need be applied to the Appleton-Hartree equation, as discussed in case 8. It also seems from the single point of Krassovsky[25] that one has to go to altitudes above the F_2 layer before electron-ion collisions will dominate neutral collisions, since, above 340 km, the neutral particle density decreased more rapidly than the electron density.[26]

VI. Comparison with Experiments

The values of $\langle \nu_g \rangle$ are compared in Fig. 11 with experimental data of Kane,[27] Schlapp,[28] Whitehead[29] and Ataev.[30] Kane's data, plotted here, are those reevaluated[1,31] with the proper v^2 relation for the collision frequency. Recall that the $\langle \nu_g \rangle$ defined here is 2.5 times ν_p, the collision frequency used by Phelps.[1] The values of $\langle \nu_g \rangle$ agree very favorably with Kane's experimental results for the D layer. Ratcliffe[19] also finds good agreement with other experimental data. However, above 90 km, Ratcliffe, Schlapp and Whitehead note that the theoretical values for $\langle \nu_g \rangle$ are appreciably smaller than those obtained experimentally. Ratcliffe and Schlapp suggest that this may be due to atomic oxygen, which they neglect theoretically. In these calculations, however, it is found that the influence of atomic oxygen is small as far as values of $\langle \nu_g \rangle$ are concerned, provided the three assumptions in the analysis are true, namely:

1) atomic oxygen is less than 1/10 the nitrogen concentration below 180 km,

[25] V. I. Krassovsky, "Exploration of the upper atmosphere with the help of the third soviet sputnik," Proc. IRE, vol. 47, pp. 289–296; February, 1959.

[26] Y. L. Albert, "State of the outer ionosphere," *Priroda*, vol. 6, pp. 85–87; 1958. Translated by E. R. Hope, DRB Canada, no. T304R; September, 1958.

[27] J. A. Kane, "Arctic measurements of electron collision frequencies in the D-region of the ionosphere," *J. Geophys. Res.*, vol. 64, pp. 133–139; February, 1960.

[28] D. M. Schlapp, "Some measurements of collision frequency in the E-region of the ionosphere," *J. Atmos. Terr. Phys.*, vol. 16, pp. 340–343; November, 1959.

[29] J. D. Whitehead, "The absorption of short radio waves in the D-, E- and F-regions of the ionosphere," *J. Atmos. Terr. Phys.*, vol. 16, pp. 283–290; November, 1959.

[30] O. M. Ataev, "The determination of the number of collisions in the ionosphere," *Radio Engineering and Electronics*, (Translation of *Radiotekhnika i elektronika* by Pergamon Press, New York, N. Y.), vol. 4, no. 9, pp. 37–45; 1959.

[31] J. A. Kane, "Re-evaluation of ionospheric electron densities and collision frequencies derived from rocket measurements of refractive index and attenuation," Natl. Aeronautics and Space Admin., Goddard Space Flight Ctr., Washington, D. C., NASA TN- D-503; November, 1960.




Fig. 11—Comparison of experimental data with the theoretical total collision frequency $\langle \nu_g \rangle$ vs height, replotted from Fig. 10, when $T = T_g$ (solid curve) and T is greater than T_g (dashed curve). The experimental points indicated by vertical lines are those of Kane, by arrows are those of Ataev, by crosses are those of Schlapp and by squares are those of Whitehead.

2) the collision cross section of atomic oxygen is not much greater than that given by Klein and Brueckner[21],
3) the electron and gas temperatures are equal.

Suppose that the electron temperature is greater than the gas temperature above 110 km. Note that at 110 km the gas temperature starts to increase rapidly from about 287°K and reaches 1031°K at 150 km, after which it increases at a slower rate to 1404°K at 200 km. Assume that the electron temperature is much greater at the high temperatures. In Fig. 12, a possible variation is shown, which includes the electron temperatures of 7000°K at 242 km and 15,000°K at 795 km, given by Krassovsky.[25] The latter point has been reevaluated by Whipple[32] to be near 9000°K. If, in the E layer, the electron temperature is about three times the gas temperature (see Fig. 11), the theoretical electron collision frequencies, based on the higher temperature, agree with the experimental values of Schlapp and Ataev in the E layer. Boggess, *et al.*, report rocket data[33] of electron temperatures in the E layer, which indeed indicate a

[32] E. C. Whipple, Jr., "Ion-trap results in 'Exploration of the upper atmosphere with the help of the third Soviet Sputnik,'" Proc. IRE (Correspondence), vol. 47, pp. 2023–2025; November, 1959.

[33] R. L. Boggess, *et al.*, "Langmuir probe measurements in the ionosphere," *J. Geophys. Res.*, vol. 64, pp. 1627–1630; October, 1959.




Fig. 12—The temperature of air T_g vs height according to the 1959 ARDC model, and the assumed electron temperature T (dashed curve) vs height. The points at 242 and 795 km are those from Krassovsky. The arrow at 795 km indicates Whipple's interpretation of the Russian measurement, initially deduced to be 15,000°K. The crosses indicate values given by Boggess *et al.* The point ⊙ at 120 km is deduced from Schlapp's and Ataev's values of $\langle \nu_g \rangle$, shown in Fig. 11.

high electron temperature (see Fig. 12), but also a surprising minimum at 175 km. Recent measurements by Boggess[34] indicate that the electron temperature rises to a maximum of 2800°K and becomes isothermal near the F_2 layer (no decline in temperature observed). Whitehead's result for 190 km still remains inexplicable, since, as discussed above, a large change in electron temperature produces a small change in collision frequency at 200 km. Theoretically, the new curve for the collision frequency, shown dashed in Fig. 11, is above the original curve for heights less than 200 km and below the original curve for heights greater than 200 km. Ataev's result for the F_2 layer seems to favor the original curve based on $T = T_g$. However, measurements of collision frequency in the F_2 layer are widely scattered[30] in value and inconclusive.[19] More accurate and systematic measurements, possibly sounding by satellites from above the ionosphere, will check the hypothesis that $T > T_g$ in the F_2 layer, since the hypothesis predicts smaller collision frequency values than given by letting $T = T_g$. This effect is reversed in the E layer where higher temperatures give higher collision frequencies, and, indeed, Schlapp and Ataev find the collision frequency to be higher than expected. One may also suggest that if the hypothesis proves to be correct a measurement of electron collision frequency in the ionosphere may be a sensitive method for determining the electron temperature, especially in the E layer.[35]

Acknowledgement

It is a pleasure to thank Dr. T. W. Johnston and Dr. M. P. Bachynski for stimulating and fruitful discussions.

[34] R. L. Boggess, private communication; March 13, 1961.

[35] A similar suggestion has been made by M. Nicolet, "Collision frequency of electrons in the terrestrial atmosphere," *Phys. Fluids*, vol. 2, pp. 95–99; March–April, 1959, in connection with the electron-ion collision frequency in the F_2 layer.

The Electrical Conductivity of a Partially Ionized Gas*

DIPAK L. SENGUPTA†, MEMBER IRE

Summary—**The electrical conductivity of a low density and partially ionized gas where both electron-neutral particle and Coulomb type collisions play important roles is discussed. The effects of inelastic collisions and a steady magnetic field are not considered. We assume that the ionized gas is perturbed by a weak electric field, and obtain the velocity distribution function for the electrons by solving the Boltzmann equation; the collision between neutral and charged particles is accounted for by the hard sphere model for the particles, while the collision between the charged particles is taken care of by the Fokker-Planck terms. Explicit expressions for ac and dc conductivity are given for various cases. To the extent that the assumptions made for the collision models are valid, the expressions for conductivity given here are quite general and can be used for any degree of ionization.**

Introduction

THE purpose of this paper is to derive expressions for the electrical conductivity of a low-density and partially ionized gas where both electron-neutral particles and Coulomb type collisions between the charged particles play important roles. During the past, considerable work has been done along this line. Margenau[1] and his group published a series of papers dealing mostly with low-intensity fields and weakly ionized gases. Spitzer and his co-workers[2] on the other hand dealt with the small signal static conductivity of low density fully ionized gases. In a weakly ionized gas, Coulomb collisions between charged particles are neglected. In the fully ionized gas it is the Coulomb collisions which determine the electron velocity distribution function.

The present paper deals with an intermediate case of the interaction between a low-intensity electromagnetic field and a partially ionized gas where neither the electron-neutral particles nor the Coulomb collisions can be neglected. The effects of inelastic collisions and a steady magnetic field are neglected in the present analysis. The elastic collision between electrons and neutral particles is explained by the standard binary collision process[3,4] with a hard sphere model for the particles. The Coulomb collisions between the charged particles are accounted for by using the model derived from the Fokker-Planck equation as given by Dreicer.[5] After assuming that the interacting electromagnetic field is of low intensity, an expression for the electron velocity distribution function is derived by solving Boltzmann's equation with the above two models for the collision terms. Expressions for the ac electrical conductivity in various cases are then derived. To the extent that the assumptions for the collision models are valid, the expressions derived here for the conductivity are quite general in nature; they reduce to the well-known relations for both the limiting cases of fully and weakly ionized gases.

Basic Formulation of the Problem

In this section we shall formulate the problem in general terms. The basic parameter which has to be determined before one can obtain any information about the ionized gas is the electron velocity distribution function. Let us define the electron velocity distribution function $F(v, t)$ such that Fd^3v gives the number of electrons whose velocities lie in the element of volume d^3v situated around the point $\boldsymbol{v}$ in the velocity space. It is assumed that the macroscopic properties of the gas do not vary from point to point. Then the distribution function F satisfies Boltzmann's equation:

$$\frac{\partial F}{\partial t} + \boldsymbol{a}(t) \cdot \nabla_v F = \left(\frac{\partial F}{\partial t}\right)_{\text{coll.}}, \tag{1}$$

where

$\boldsymbol{a}(t)$ is the force per unit mass on the electrons,

∇_v is the gradient operator in velocity space,

and

$(\partial F/\partial t)_{\text{coll.}}$ is the rate of change of the distribution function due to various types of collisions. At present we assume,

$$\left(\frac{\partial F}{\partial t}\right)_{\text{coll.}} = \left(\frac{\partial F}{\partial t}\right)_{cn} + \left(\frac{\partial F}{\partial t}\right)_{cc}, \tag{2}$$

where the subscript *cn* means collision between electron and neutral particles, and *cc* means Coulomb collisions between the charged particles. Explicit expressions for the collision terms depend on the type of model one assumes for the collision process. In general there should be considered two other equations similar to (1) in order to account for the velocity distributions of the heavy

* Received by the IRE, September 5, 1961. The research reported in this paper was sponsored by the Advanced Research Projects Agency and the Air Force under ARPA Order 147-60 and Air Force Contract No. AF 19(604)-7428.

† Radiation Lab., University of Michigan, Ann Arbor.

[1] H. Margenau, "Conduction and dispersion of ionized gases at high frequencies," *Phys. Rev.*, vol. 69, pp. 508–513; May, 1946. Also, "Conductivity of plasmas to microwaves," *Phys. Rev.*, vol. 109, pp. 6–9; January, 1958.

[2] R. Cohen, L. Spitzer and P. Routly, "The electrical conductivity of an ionized gas," *Phys. Rev.*, vol. 80, pp. 230–238; October, 1950.

[3] T. Holstein, "Energy distribution of electrons in high frequency gas discharges," *Phys. Rev.*, vol. 70, pp. 367–384; February, 1946.

[4] S. Chapman and T. G. Cowling, "The Mathematical Theory of Nonuniform Gases," Cambridge University Press, Cambridge, England, ch. 18; 1939.

[5] H. Dreicer, "Electron velocity distributions in a partially ionized gas," *Phys. Rev.*, vol. 117, pp. 343–354; January, 1960.

neutral particles and positive ions. However, for simplicity of analysis it is assumed here that the heavy particles are stationary relative to the motions of the electrons.

In the present problem the acceleration of the electron is assumed to be of the form:

$$\mathbf{a}(t) = -\frac{eE_0 \cos \omega t}{m}, \tag{3}$$

where

E_0 is the amplitude of the incident electric field and polarized along the z axis,
ω is the angular frequency of the incident field,
$-e$ is the charge of an electron,
m is the mass of an electron.

The effect of the alternating magnetic field is neglected. After the distribution function F is determined from (1), the current produced in the gas may be obtained from

$$J_z = -n_0 e \bar{v}_z = -e \int F d^3v v \cos \theta, \tag{4}$$

where

J_z is the z-component of the current, assumed positive along the positive direction of the z axis,
$\bar{v}_z$ is the mean velocity of the electrons along the positive z-direction,
θ is the angle between the z axis and the velocity vector v,
n_0 is the electron density.

Discussion of the Collision Terms

As mentioned in the Introduction we shall consider only two types of elastic collisions—between electron-neutral particles and electron-heavy positive ions. If the gas is fully ionized and of high density, then collisions between charged particles of the same kind (for example electron-electron, ion-ion) should also be considered. For a low-density ionized gas the latter two collision effects may be neglected in comparison with the first two. The electron-neutral particle interaction is a short-range phenomenon and explicit expression for this is taken from the standard analysis.[3,4] Since Coulomb force is a long-range phenomenon, the cumulative effects of small deflections suffered by the electrons at large distances due to the interaction with the ions become very important,[2] and they cannot be accounted for in the same way as is done in the first case. This type of interaction is in general explained by the Fokker-Planck equation. The detailed derivation of the collision term from the Fokker-Planck equation is given by Dreicer.[5] Here, we take our collision term after applying the relevant approximations to the general Coulomb collision term given by Dreicer.

Evaluation of the Electron Distribution Function

In the analysis we shall make use of the Lorentz approximation which states that the collisions between various particles produce a spherically symmetric velocity distribution—small deviations from spherical symmetry are then explained accurately enough by the coefficient $F^1(v)$ in the spherical harmonic expansion of F:

$$F(\cos \theta, v) = \sum_{n=0}^{\infty} F^n(v) P_n(\cos \theta) \doteq F^0(v) + \cos \theta F^1(v), \tag{5}$$

where

the polar axis is chosen to be the z axis,
P_n's are the Legendre polynomials.

The approximation made in (5) is valid if $F^1 \ll F^0$. This condition physically means that the average velocity of the electron gas is small compared to the root mean square electron speed. This is a reasonable assumption if the perturbing field is small.

Using the orthogonality property of spherical harmonics the following two relations are obtained for the macroscopic quantities of the gas:

$$\text{electron concentration } n_0 = \int_0^{\infty} F^0 4\pi v^2 dv, \tag{6}$$

$$\text{electric current } J_z = -\frac{4\pi e}{3} \int_0^{\infty} F^1 v^3 dv. \tag{7}$$

After expanding the term $\mathbf{a}(t) \cdot \nabla_v F$ in (1) into its spherical harmonic components in the velocity space, substituting (5) into (1), and equating the terms independent of $\cos \theta$ and those dependent on $\cos \theta$, the following relations are obtained:

$$\frac{\partial F^0}{\partial t} - \frac{\gamma \cos \omega t}{3v^2} \frac{\partial}{\partial v} (v^2 F^1) = \left(\frac{\partial F^0}{\partial t}\right)_{cn} + \left(\frac{\partial F^0}{\partial t}\right)_{cc}, \tag{8}$$

$$\frac{\partial F^1}{\partial t} - \gamma \cos \omega t \left(\frac{\partial F^0}{\partial v}\right) = \left(\frac{\partial F^1}{\partial t}\right)_{cn} + \left(\frac{\partial F^1}{\partial t}\right)_{cc}, \tag{9}$$

where

$$\gamma = \frac{eE_0}{m}.$$

The contributions due to electron-neutral particle collisions are,[3,4]

$$\left(\frac{\partial F^0}{\partial t}\right)_{cn} = \frac{1}{v^2} \frac{m}{M} \frac{\partial}{\partial v} (v^3 F^0 \nu_e(v)) + \frac{KT}{Mv^2} \frac{\partial}{\partial v} \left(v^2 \nu_e(v) \frac{\partial F^0}{\partial v}\right), \tag{10}$$

$$\left(\frac{\partial F^1}{\partial t}\right)_{cn} = -F^1 \nu_e(v), \tag{11}$$

where

$$\nu_e(v) = 2\pi N v \int_0^{\pi} (1 - \cos\beta) \sin\beta \cdot \sigma_e(\beta, v) d\beta, \tag{12}$$

N = the number density of neutral particles,
$\sigma_e(\beta, v)$ = differential cross section for elastic scattering through the angle β,
M = the mass of the neutral particles,
T = temperature of the electron gas,
K = Boltzmann constant.

The factor $\nu_e(v)$ may be identified with the frequency of electron-neutral particle collisions. In general $\nu_e(v)$ is a function of v.

The Coulomb collision terms, subject to the Lorentz approximation and the condition $m/M \ll 1$, are given by[5]

$$\left(\frac{\partial F^1}{\partial t}\right)_{cc} = -\frac{n_0\Gamma_{ei}}{v^3}, \tag{13}$$

$$\left(\frac{\partial F^0}{\partial t}\right)_{cc} = 0, \tag{14}$$

where

$$\Gamma_{ei} = 4\pi\left(\frac{ee_i}{m}\right)^2 \ln(\lambda/p_0), \tag{13a}$$

p_0 = the average impact parameter (distance of closest approach between the two colliding particles),
e_i = charge on a heavy ion,
λ = the Debye shielding distance.

After substituting (10), (11), (13), and (14) into (8) and (9) the following two equations are obtained:

$$\left(\frac{\partial F^0}{\partial t}\right) - \frac{\gamma\cos\omega t}{3v^2}\frac{\partial}{\partial v}(v^2F^1) = \frac{1}{v^2}\frac{m}{M}\frac{\partial}{\partial v}(v^3F^0\nu_e(v)) + \frac{KT}{Mv^2}\frac{\partial}{\partial v}\left(v^2\nu_e(v)\frac{\partial F^0}{\partial v}\right), \tag{15}$$

$$\frac{\partial F^1}{\partial t} - \gamma\cos\omega t\left(\frac{\partial F^0}{\partial v}\right) = -\left[\nu_e(v) + \frac{n_0\Gamma_{ei}}{v^3}\right]F^1. \tag{16}$$

In order to solve (15) and (16), we assume that the isotropic part of the distribution function is independent of time. Thus the solution F^1 of (16) in terms of F^0 is given by the following:

$$F^1 = F^1(\text{at } t = 0)\exp -\left[\nu_e(v) + \frac{n_0\Gamma_{ei}}{v^3}\right]t + \gamma\left(\frac{\partial F^0}{\partial v}\right)\left[\frac{\omega}{\omega^2 + \left\{\nu_e(v) + \frac{n_0\Gamma_{ei}}{v^3}\right\}^2}\sin\omega t + \frac{\nu_e(v) + n_0\Gamma_{ei}/v^3}{\omega^2 + \left\{\nu_e(v) + \frac{n_0\Gamma_{ei}}{v^3}\right\}^2}\cos\omega t - \frac{\nu_e(v) + n_0\Gamma_{ei}/v^3}{\omega^2 + \left\{\nu_e(v) + \frac{n_0\Gamma_{ei}}{v^3}\right\}^2}\cdot\exp -\left\{\nu_e(v) + n_0\Gamma_{ei}/v^3\right\}t\right]. \tag{17}$$

It can be seen from (17) that the combined collision effect (electron-neutral particle and Coulomb) relaxes the perturbed distribution function F^1 to the following steady-state value:

$$F^1 = \gamma\left(\frac{\partial F^0}{\partial v}\right)\left[\frac{\omega}{\omega^2 + \left\{\nu_e(v) + \frac{n_0\Gamma_{ei}}{v^3}\right\}^2}\sin\omega t + \frac{\nu_e(v) + n_0\Gamma_{ei}/v^3}{\omega^2 + \left\{\nu_e(v) + \frac{n_0\Gamma_{ei}}{v^3}\right\}^2}\cos\omega t\right]. \tag{18}$$

After substituting (18) into (15) and taking the time average, we obtain:

$$-\frac{\gamma^2}{6v^2}\frac{\partial}{\partial v}\left[v^2\frac{\partial F^0}{\partial v}\frac{\nu_e(v) + n_0\Gamma_{ei}/v^3}{\omega^2 + \left\{\nu_e(v) + \frac{n_0\Gamma_{ei}}{v^3}\right\}^2}\right] = \frac{1}{v^2}\frac{m}{M}\frac{\partial}{\partial v}(v^3F^0\nu_e(v)) + \frac{KT}{Mv^2}\frac{\partial}{\partial v}\left(v^2\nu_e(v)\frac{\partial F^0}{\partial v}\right). \tag{19}$$

From (19), F^0 can be expressed as:

$$F^0 = A\exp -\int_0^v \frac{mvdv}{\frac{M\gamma^2}{6\nu_e(v)}\frac{\nu_e(v) + n_0\Gamma_{ei}/v^3}{\omega^2 + \left\{\nu_e(v) + \frac{n_0\Gamma_{ei}}{v^3}\right\}^2} + KT}, \tag{20}$$

where A is a constant of integration. If Coulomb collisions are neglected the distribution function (20) reduces to the one given by Margenau[1] for the constant mean free path case. If the thermal energy of the electrons is large and the electric field E_0 is sufficiently small, then the term KT in the denominator of the integrand in (20) is predominant and F^0 reduces to the Maxwellian distribution,

$$F^0 = n_0\left(\frac{m}{2\pi KT}\right)^{3/2} e^{-mv^2/KT}, \tag{21}$$

where the constant A has been determined by using (6). Eq. (20) indicates that, strictly speaking, F^0 cannot be assumed Maxwellian and independent of the field intensity E^0. As we shall see later this fact makes the electrical conductivity of the ionized gas a nonlinear function of the field intensity. We are now in a position to calculate the conductivity of the gas. This is done in the next section.

Expressions for the Electrical Conductivity

After using (7) and (18), the following relation is obtained for the electric current:

$$J_z = -\frac{4\pi e^2 E_0}{3m}\int_0^\infty\left[\frac{\omega v^3}{\omega^2 v^6+\{v^3\nu_e(v)+n_0\Gamma_{ei}\}^2}\sin\omega t + \frac{\{\nu_e(v)+n_0\Gamma_{ei}\}}{\omega^2 v^6+\{\nu_e(v)v^3+n_0\Gamma_{ei}\}^2}\cos\omega t\right]v^6\left(\frac{\partial F^0}{\partial v}\right)dv. \quad (22)$$

Defining complex conductivity as $\sigma=\sigma_r-i\sigma_i$, it can be shown that the real and imaginary parts of the electrical conductivity of a partially ionized gas are given by

$$\sigma_r = -\frac{4\pi e^2}{3m}\int_0^\infty\frac{\nu_e(v)v^3+n_0\Gamma_{ei}}{\omega^2 v^6+\{\nu_e(v)v^3+n_0\Gamma_{ei}\}^2}v^6\cdot\left(\frac{\partial F^0}{\partial v}\right)dv, \quad (23)$$

$$\sigma_i = -\frac{4\pi e^2}{3m}\int_0^\infty\frac{\omega v^3}{\omega^2 v^6+\{\nu_e(v)v^3+n_0\Gamma_{ei}\}^2}v^6\cdot\left(\frac{\partial F^0}{\partial v}\right)dv. \quad (24)$$

For the dc case $\omega=0$, $\sigma_i=0$, $\sigma_r=\sigma_{\text{D.C.}}$ If Coulomb collisions are neglected, and F^0 is assumed to be given by (21), then (23) and (24) can be written in the following forms after introducing the dimensionless parameter $x^2=mv^2/2KT$:

$$\sigma_r = \frac{4\pi e^2 n_0}{3m}\frac{2}{(\pi)^{3/2}}\int_0^\infty\frac{\nu_e(x)}{\omega^2+\nu_e^2(x)}e^{-x^2}x^4dx, \quad (25)$$

$$\sigma_i = \frac{4\pi e^2 n_0}{3m}\frac{2}{(\pi)^{3/2}}\int_0^\infty\frac{\omega}{\omega^2+\nu_e^2(x)}e^{-x^2}x^4dx. \quad (26)$$

For constant ν_e, σ_i and σ_r as given above reduce to the familiar forms.[1] In general $\nu_e(x)$ is a complicated function of x, and the integrals in (25) and (26) are not always amenable to integration in closed forms.

Conductivity of a Fully Ionized Gas

In this section we shall derive expressions for the ac conductivity of a fully ionized gas. In order to simplify the analysis it is assumed that the isotropic part of the the distribution function is Maxwellian and is given by (21). Since the gas is fully ionized, $\nu_e(v)=0$ and hence, (23) and (24) may be written as follows:

$$\sigma_r = \frac{\sigma_{\text{D.C.}}}{3}\int_0^\infty\left[1-\frac{\omega_0^3x^6}{\omega_0^3x^6+1}\right]x^7e^{-x^2}dx, \quad (27)$$

$$\sigma_i = \frac{\sigma_{\text{D.C.}}}{3n_0\Gamma_{ei}}\frac{\omega}{\omega_0^3}\int_0^\infty\frac{x^{10}e^{-x^2}}{x^6+\frac{1}{\omega_0^3}}dx, \quad (28)$$

where

$$\omega_0^3 = \frac{\omega^2\left(\frac{2KT}{m}\right)^3}{n_0^2\Gamma_{ei}^2}, \quad (29)$$

and

$$\sigma_{\text{D.C.}} = \frac{4\pi e^2}{m\Gamma_{ei}}\frac{2}{(\pi)^{3/2}}\left(\frac{2KT}{m}\right)^{3/2}. \quad (30)$$

For the dc case $\omega=0$, we obtain $\sigma_i=0$ and $\sigma_r=\sigma_{\text{D.C.}}$ since in (27)

$$\int_0^\infty x^7e^{-x^2}dx = 3.$$

The dc conductivity as given by (30) is the same as given by Spitzer.[6]

We shall now evaluate explicitly σ_r as given by (27). Let us denote the integral in (27) by I. After a change of variable $t=x^2$, I may be written as follows:

$$I = \frac{1}{2}\int_0^\infty\frac{t^6e^{-t}}{t^3+1/\omega_0^3}dt. \quad (31)$$

Using the known result

$$\int_0^\infty\frac{t^ne^{-t}}{t_1+t}dt = K_n(t_1),$$

where K_n is the usual notation for the modified Bessel function of the second kind and order n, the following is obtained for I:

$$I = \frac{\omega_0^2}{6}K_6(1/\omega_0) - \frac{\omega_0^2}{12}\left[K_6\left(\frac{e^{\pi i/3}}{\omega_0}\right)+K_6\left(\frac{e^{-\pi i/3}}{\omega_0}\right)\right] - i\frac{\sqrt{3}}{12}\omega_0^2\left[K_6\left(\frac{e^{\pi i/3}}{\omega_0}\right)-K_6\left(\frac{e^{-\pi i/3}}{\omega_0}\right)\right]. \quad (32)$$

Eq. (32) may also be written in the following form:

$$I = \frac{\omega_0^2}{6}K_6(1/\omega_0) + \frac{\omega_0^2}{12}\frac{\pi_i}{2}\left[H_6^{(1)}\left(\frac{e^{\pi i/6}}{\omega_0}\right)-H_6^{(2)}\left(\frac{e^{-\pi i/6}}{\omega_0}\right)\right] + \frac{\sqrt{3}}{12}\omega_0^2\pi/2\left[H_6^{(1)}\left(\frac{e^{\pi i/6}}{\omega_0}\right)+H_6^{(2)}\left(\frac{e^{-\pi i/6}}{\omega_0}\right)\right], \quad (33)$$

[6] L. Spitzer, "Physics of Fully Ionized Gases," Interscience Publishers, Inc., New York, N. Y., p. 63; 1956.

where $H_6^{(1)}$ and $H_6^{(2)}$ are the notations for the Hankel functions of the sixth order and of the first and second kind respectively. Using the property of the Hankel functions[7] that $H_6^{(1)}(e^{\pi i/6}/\omega_0)$ is the complex conjugate to $H_6^{(2)}(e^{-\pi i/6}/\omega_0)$, the value of the integral I as given in (33) may be written in the following form:

$$I = \frac{\omega_0^2}{6} K_6(1/\omega_0) - \frac{\omega_0^2}{12} \pi\rho \sin\phi + \frac{\sqrt{3}}{12} \omega_0^2 \pi\rho \cos\phi, \quad (34)$$

where

$$H_6^{(1)}\left(\frac{e^{\pi i/6}}{\omega_0}\right) = \rho\cos\phi + i\rho\sin\phi. \quad (35)$$

After substituting (34) in (27) the following is obtained for the real part of ac conductivity of a fully ionized gas:

$$\sigma_r = \frac{\sigma_{D.C.}}{3}\left[3 - \frac{\omega_0^2}{6}\left\{K_6(1/\omega_0) - \frac{\pi\rho}{2}\sin\phi + \frac{\sqrt{3}}{2}\pi\rho\cos\phi\right\}\right]. \quad (36)$$

The integration involved in (28) may be evaluated similarly, and we obtain formally the following expression for σ_i,

$$\sigma_i = \sigma_{D.C.}\left(\frac{\omega}{n_0\Gamma_{ei}}\right)^{1/3}\left(\frac{m}{2KT}\right) \cdot \left[\frac{K_{9/2}(1/\omega_0)}{6} - \frac{K_{9/2}\left(\frac{-e^{\pi i/3}}{\omega_0}\right) + K_{9/2}\left(\frac{-e^{-\pi i/3}}{\omega_0}\right)}{12} + i\frac{K_{9/2}\left(\frac{-e^{\pi i/3}}{\omega_0}\right) - K_{9/2}\left(\frac{-e^{-\pi i/3}}{\omega_0}\right)}{4\sqrt{3}}\right]. \quad (37)$$

It can be seen from (36) and (37) that for $\omega = 0$, $\sigma_r = \sigma_{D.C.}$ and $\sigma_i = 0$.

Eqs. (36) and (37) are analytically too complicated to discuss. They can be greatly simplified and brought into more tractable forms if one approximates the Bessel functions involved by the first terms of their corresponding asymptotic expansions. In order to obtain a simplified expression for σ_r we shall work with (32). After using the asymptotic series for the K functions, as given in Watson,[8] and making some algebraic manipulations, the following is obtained for σ_r:

$$\sigma_r = \frac{\sigma_{D.C.}}{3}\left[3 - \frac{\omega_0^2}{12}\left(\frac{\pi\omega_0}{2}\right)^{1/2} \cdot \left\{e^{-1/\omega_0} - e^{-1/2\omega_0}\cos\left(\frac{\pi}{6} - \frac{3}{2\omega_0}\right)\right\}\right]. \quad (38)$$

This expression is valid for the range of frequencies for which the values of ω_0 lie in the range $1/\omega_0 > 6$, where ω_0 is as given by (28). Similarly the asymptotic expression for σ_i is obtained in the following form:

$$\sigma_i = \sigma_{D.C.}\frac{\omega}{\omega_0}\left[\left(\frac{\pi\omega_0}{2}\right)^{1/2} e^{-1/\omega_0} + \frac{1}{3}\left(\frac{\pi\omega_0}{2}\right)^{1/2} e^{1/2\omega_0}\cos\left(\frac{\sqrt{3}}{2\omega_0}\right)\right], \quad (39)$$

which should be used for the range of frequencies for which $1/\omega_0 > 4.5$.

Using (38) and (39), the conductivity of a fully ionized gas has been computed at a few frequencies. It is assumed that the ionized gas has the following characteristics:

$$n_0 = 10^{15}/\text{cm}^3$$
$$T = 10^4 \text{ degrees Kelvin.}$$

The calculated normalized values of σ_r and σ_i are as shown below:

frequency (in kilomegacycles)	$\frac{\sigma_r}{\sigma_{D.C.}}$	$\frac{\sigma_i}{\sigma_{D.C.}} \times 10^{-10}$
1	1	—
10	0.9992	4.3
20	0.9978	18.4

For the ionized gas under consideration the real part of the ac conductivity does not change appreciably from the dc conductivity up to the frequency 1 kMc. The imaginary part of the conductivity increases with frequency. For the values of σ_r and σ_i at frequencies higher than those shown above, one should use (36) and (37).

Discussion

In the above the electrical conductivity of a partially ionized gas has been discussed in detail. It has been assumed that the gas is of low density and that the incident electrical field is very weak. The general expressions derived for the conductivity may be applied to specific cases keeping in mind the assumptions made in the analysis. For non-Maxwellian distribution for the isotropic part of the velocity distribution function and for velocity-dependent collision frequency, the conductivity expressions become very complicated and are to be evaluated by numerical methods. Depending on the type of gas and the degree of ionization, one can make some reasonable physical assumptions which will greatly simplify the calculation.

Acknowledgment

The author wishes to express his thanks to Prof. K. M. Siegel for encouragement during the course of this work, and to Dr. R. Goodrich and Dr. R. Kleinman for reading the manuscript.

[7] E. Jahnke and F. Emde, "Tables of Functions," Dover Publications, New York, N. Y., p. 134; 1945.
[8] G. N. Watson, "Theory of Bessel Functions," Cambridge University Press, Cambridge, England, p. 102; 1952.

Interaction of Microwaves in Gaseous Plasmas Immersed in Magnetic Fields*

K. V. NARASINGA RAO†, STUDENT MEMBER, IRE, J. T. VERDEYEN†, STUDENT MEMBER, IRE, AND L. GOLDSTEIN†, FELLOW, IRE

Summary—The phenomenon of radio frequency electromagnetic wave interaction in gaseous plasmas is reviewed. The application of microwave interaction to the study of plasmas immersed in magnetic fields is discussed. Attention is focused on the effects produced in such plasmas when one of the simultaneously propagating microwaves is in electron-cyclotron resonance. It is demonstrated that, for relatively modest amplitudes of the resonating wave, the kinetic energy of the electrons increases considerably, which in turn affects 1) the electron collision frequency and 2) the magnetic field control of the plasma confinement.

I. Introduction

IT is now well known that the phenomenon of wave interaction was first observed in 1933 between low-frequency radio waves which were propagated in a common region of the ionosphere [1]. Since it was possible to trace the effect to a region of the ionosphere which was strongly irradiated by the powerful waves (150–200 kw) transmitted by the Radio Station of Luxemburg, the phenomenon became known as the Luxemburg Effect.

The theory explaining this effect was first proposed in 1934 by Bailey and Martyn [2]. Later (1937) Bailey [3] extended this theory taking into account the influence of the earth's magnetic field on the propagation of the ionospheric radio waves involved. This theory predicted, in particular, that when the frequency of one of the interacting waves is in the vicinity of, or at the gyrofrequency of the electrons in the ionospheric region of interest, the wave interaction will be enhanced. These predictions have since been borne out by direct experimental observations [4].

In 1953 the simple phenomenon of radio wave interaction was extended [5] to (guided) microwaves propagated in laboratory gaseous plasmas under readily controlled conditions with a consequent generalization and close check of the (1955) theory [6]. Based on the generalized theory it was then possible to develop a method of rather detailed investigations of high RF EM wave interaction with gaseous plasmas, which in turn enabled the detailed study of the interaction processes taking place among the charged constituents as well as among the charged and neutral constituents of gaseous plasmas [7], [8].

This paper deals with an experimental investigation of the interaction of two or more electromagnetic waves guided through a magneto plasma medium. The magneto plasma referred to here is a plasma obtained in the afterglow of a pulsed gas discharge (degree of ionization less than 10^{-4}) which is immersed in an external dc magnetic field, variable from 0 to 0.3 webers/m^2. The gases used are primarily the inert gases in the pressure range 0.5 to 10.0 mm Hg. The EM waves utilized are in the frequency range 4.0 to 10.0 Gc and are guided along the external magnetic field. The general topic of investigation is the transfer of EM energy to the electron gas in the plasma and the effects of this transfer of energy on 1) the plasma parameters and 2) the associated wave propagation characteristics of the plasma. This has been investigated, in particular, when the frequency of one EM wave is at or in the vicinity of the cyclotron frequency of the electrons.

This paper is divided into six sections: In Section II, a qualitative description of the interaction of EM waves of radio frequency is given. Section III deals with a description of the plasma medium and a quantitative treatment of the wave interaction phenomenon in gaseous plasmas. The experimental apparatus used in this investigation is described in Section IV. Section V is devoted to the experimental results and Section VI contains the conclusions and the possible implications of these results.

II. Interaction of Electromagnetic Waves in a Plasma

It is known that the propagation of electromagnetic waves in material media is different from the propagation in free space because there is energy exchange between the media and the waves. A plasma, being a material medium, will alter the propagation of electromagnetic waves, and this fact has been used to determine those plasma parameters which influence electromagnetic wave propagation. Usually these techniques have been used to study the plasma in any given time-independent energy state. The probing electromagnetic wave which is used in such a study must be of sufficiently small amplitude so that it does not appreciably disturb the plasma.

If the amplitude of the electromagnetic wave propagating in a plasma does not satisfy this condition, a change in the energy state of the electron gas of the plasma results, which in turn affects the propagation of any succeeding wave packet. This means that each wave packet propagates in a slightly different plasma than the preceding one. This phenomenon is generally referred to as self-modulation or as self-distortion.

* Received by the IRE, August 7, 1961. This work is sponsored by the AFCRC, Geophysics Research Directorate, Bedford, Mass.
† Dept of Elec. Engrg., University of Illinois, Urbana, Ill.

While the change of the energy state of the electron gas thus affects wave propagation in a plasma, it also affects those processes occurring in the plasma which are dependent upon the energy state of the electron gas, such as recombination, diffusion, production rate, etc.

We have considered above the effect of only one electromagnetic wave on a plasma and the resulting reaction of the plasma on the electromagnetic wave in the two cases: 1) negligible perturbations corresponding to small-wave amplitudes and 2) significant disturbances corresponding to large-wave amplitudes. The next step is to combine the two effects by applying two electromagnetic waves to the plasma. One wave will be of sufficiently small amplitude so as to be capable of probing the plasma—hence the name *sensing wave;* the other will be of sufficient amplitude and of different frequency so as to disturb the plasma—hence the name *disturbing wave.* The effect which the disturbing wave causes on the plasma, as detected by the sensing wave, is generally referred to as wave interaction and, when modulation is involved, as cross-modulation.

Let us consider the processes by which energy is transferred from an electromagnetic wave to the electron gas of a plasma. When a high-frequency electromagnetic wave impinges upon a plasma, it causes an ordered oscillatory motion of the electrons which is superimposed onto the existing disordered thermal motion. The ordered electron velocity is 90° in time phase with respect to the driving force of the E field of the wave. The energy associated with this ordered motion, if not interfered with, is taken from the EM wave in $\frac{1}{2}$ cycle, and returned to the wave in the following $\frac{1}{2}$ cycle so that the average power transferred to the electron gas is zero. When, however, the electrons collide with other constituents of the plasma, the ordered momentum is scattered, and consequently the velocities of the electrons no longer have a definite phase relationship to the driving force. Following such collisions, the previous ordered energy of the electron gas is not returned to the electromagnetic wave and hence represents RF power transferred into the electron gas. The electron gas loses, however, a fraction of this energy to the heavy constituents of the plasma.

These momentum-transfer collisions between electrons and the heavy particles of a plasma constitute one mechanism by which EM energy is transferred into disordered thermal energy of the electrons. There exists however, under particular conditions, another mechanism of EM energy transfer to a plasma, in which the collisions, by interrupting the ordered motion of the electrons, hinder the energy transfer. Such conditions occur when resonance prevails between a proper frequency of the plasma electrons, such as their cyclotron frequency, and the particular frequency of the EM waves. In this case, an initial value problem must be considered and the solution of which indicates that the energy of an electron grows, in between collisions, as $(Et)^2$ where E is the applied electric field and t is the time elapsed since its last collision. In the study reported here we are concerned mainly with the effects of this electromagnetic energy transfer from one of the EM waves whose frequency is at or in the vicinity of the cyclotron frequency of electrons.

III. Characteristics of an Afterglow Plasma

As mentioned earlier, the plasma considered here is that obtained in the afterglow of a partially ionized rare gas whose degree of ionization is less than 10^{-4}. We shall assume that only three types of constituent gases are present in the afterglow, namely the gas of the electrons, that of the positive ions and that of the neutral molecules. The fundamental parameters of interest are essentially: 1) the number density of the charged particles, 2) the temperature of the constituent gases, and 3) the type of neutral molecules in which the plasma is formed. Upon removal of the external plasma-excitation source the constituent particles undergo mainly elastic collisions among themselves and with the walls of the reservoir, and thereby attain thermodynamic equilibrium at the temperature of the reservoir ($T_e = T_i = T_g = T_r$). This plasma tends, however, towards a neutral gas state by means of various loss mechanisms of the charged particles. These mechanisms are 1) volume recombination of electrons and ions, 2) diffusion of electrons to boundaries and 3) attachment of electrons to neutral particles. The absence of any electronegative gases in these experiments permits us to neglect the attachment process, and hence the rate of loss of the charged particles is given by

$$\frac{dn}{dt} = -\alpha n_e \cdot n_i + D\nabla^2 n, \tag{1}$$

where α = the recombination coefficient of electrons and ions whose densities are, respectively, n_e, n_i, and D = the diffusion coefficient.

If we assume that only elastic collisions of electrons with other constituents of the plasma take place in the afterglow, it is possible to define certain fundamental quantities which describe the interactions of the electrons with other constituents of the plasma. The probability of electron-molecule collision for momentum transfer, P_{em} is related to the effective cross section of molecules, Q_{em} and to the corresponding electron-molecule collision frequency ν_{em} by the equation

$$P_{em}(v)p = N_m Q_{em}(v) = \frac{\nu_{em}}{v}, \tag{2}$$

where N_m = number density of molecules, v = velocity of electrons, p = pressure (at 0°C). Analogous quantities for electron-ion collisions are

$$N_i Q_{ei} = \frac{\nu_{ei}}{v}. \tag{3}$$

If Q_{em} does not vary appreciably with electron velocity,

then the collision frequencies mentioned above may be reduced to the following functional forms:

$$\nu_{em} = AT_e^{1/2}, \tag{4}$$

$$\nu_{ei} = \frac{BN_i}{T_e^{-3/2}} \ln [CN_i^{-1/2}T_e^{1/2}], \tag{5}$$

where A, B, C are constants and T_e is electron temperature. In any case, the total effective collision frequency defined by

$$\nu_t = \nu_{em}(T_e) + \nu_{ei}(T_e) \tag{6}$$

is thus dependent upon the number density of the charged particles, pressure of the gas, kind of gas, and electron temperature. To facilitate the interpretation of the experimental results on the interaction of microwaves, a plot of N_iQ_{ei} and P_{em} as a function of electron temperature is shown in Fig. 1. It can be seen from this figure that an enhancement in electron temperature may cause either a decrease or an increase in the total electron collision frequency ν_t depending on whether *e-i* or *e-m* collisions are predominant. If we neglect the slow variation of the logarithmic term in (5), then the total collision frequency will *increase* with electron temperature provided $\nu_{em} > 3\nu_{ei}$ or *decrease* if $\nu_{ei} > \frac{1}{3}\nu_{em}$. This result is obtained by differentiating (6) with respect to T_e. In certain gases, like Xe, Kr, or Ar, an increase in electron temperature from ~300°K causes a decrease in ν_t, even without any Coulomb collisions. The variation of ν_{em} in these gases with increasing T_e is similar to the variation of ν_t in a low pressure high density neon plasma as can be inferred from Fig. 1. These aspects of the total collision frequency dependence on electronic energy have been demonstrated in this investigation using the technique of wave interaction, and are discussed in Section V.




Fig. 1—Probability of electron-molecule collision for momentum transfer P_{em} or N_iQ_{ei} vs electron temperature (°K). The dashed curves represent N_iQ_{ei} for two electron densities 10^{11}/cc and 10^{10}/cc. The solid curves represent P_{em} in neon and xenon gases. Data for solid curves is obtained from [20] and dashed curves are plotted using (5), as given by [6].

Now we shall consider briefly the dependence of the electron-loss mechanisms in a nonmagnetized, decaying, rare gas plasma upon the electron temperature It is known that the volume recombination decreases with increasing electron temperature since α, the recombination coefficient, is inversely proportional to some power (~3/2) of T_e [9]. However, if "free" diffusion of electrons occurs in a plasma, it will be enhanced when T_e increases. In a plasma of high-charge densities, interactions among the charges of opposite sign results in the ambipolarity of the diffusion. The ambipolar diffusion coefficient is given by the equation

$$D_a = D_+\left(1 + \frac{T_e}{T_i}\right), \tag{7}$$

where D_+ is the diffusion coefficient of the positive ions. It is seen that D_a increases with T_e.

The ambipolar diffusion in a magneto plasma depends upon the direction of the magnetic field. The diffusion coefficients parallel and perpendicular to the direction of the magnetic field are given [10], [11] in terms of the magnetic field intensity by

$$D_\perp = \frac{D_\parallel}{1 + \dfrac{\omega_H}{\nu_e}\cdot\dfrac{\Omega_H}{\nu_i}}, \tag{8a}$$

$$D_\parallel = D_a, \tag{8b}$$

where ω_H, and Ω_H are the cyclotron frequencies of the electrons and ions, respectively, and ν_e, ν_i are the total electron and ion collision frequencies.

It can be seen from (8a) and (8b) that in plasmas where the condition

$$\frac{\omega_H}{\nu_e}\cdot\frac{\Omega_H}{\nu_i} \gg 1$$

is satisfied, the diffusion of charged particles in the transverse direction is negligible compared to that in the parallel direction, *i.e.*, $D_\perp/D_\parallel \ll 1$. However, the absorption of EM waves under electron-cyclotron resonance conditions results in a considerable heating of the electron gas only. In the plasma considered here, it is possible to chage ν_t appreciably by this process which results in making the ratio $D_\perp/D_\parallel$ approach unity. The implication of this statement is that the transverse diffusion of the plasma can be enhanced considerably by the heating of the electron gas. In other words, the external magnetic field, which impedes the transverse diffusion of the cool electrons and thus delays plasma disintegration, loses its control over the diffusion process when the electrons become energetic.

A. Electromagnetic Description of the Plasma

A mathematical description of the influence of the electromagnetic wave upon a plasma consists of the

simultaneous solution of Maxwell's equations and Boltzmann's equation:

$$\nabla \times \boldsymbol{H} = \boldsymbol{J} + \epsilon_0 \frac{\partial \boldsymbol{E}}{\partial t}, \tag{9}$$

$$\nabla \times \boldsymbol{E} = -\mu_0 \frac{\partial \boldsymbol{H}}{\partial t}, \tag{10}$$

$$\frac{\partial f}{\partial t} + \boldsymbol{v} \cdot \nabla_r f + (\boldsymbol{E} + \boldsymbol{v} \times \boldsymbol{B}) \cdot \nabla_v f = \left.\frac{\partial f}{\partial t}\right|_{\text{coll.}}, \tag{11}$$

$$\boldsymbol{J} = -e \iiint \boldsymbol{v} f d^3 v. \tag{12}$$

However, a somewhat less rigorous but a more easily solved set of equations is the combination of Maxwell's equations with the Langevin equation:

$$\frac{\partial \boldsymbol{v}}{\partial t} + \nu \boldsymbol{v} = \frac{q}{m} (\boldsymbol{E} + \boldsymbol{v} \times \boldsymbol{B}), \tag{13}$$

$$\boldsymbol{J} = -ne\boldsymbol{v}. \tag{14}$$

In (13), ν is responsible for viscous damping and is related to the average momentum-transfer collision frequency of the electrons with the other constituents of the plasma. The restrictions and assumptions, which are inherent in the usage of (13) rather than (11), have been discussed by several authors [12], [13], [14] and will not be considered here. Suffice it to say that the use of (13) and (14) leads to an expression for the current density which is reasonably accurate for our purposes.

Eqs. (13) and (14) can be solved for the current density in terms of the plasma parameters and the electromagnetic fields.

$$\begin{bmatrix} J_x \\ J_y \\ J_z \end{bmatrix} = \begin{bmatrix} \sigma_{xx} & \sigma_{xy} & 0 \\ -\sigma_{xy} & \sigma_{yy} & 0 \\ 0 & 0 & \sigma_{zz} \end{bmatrix} \begin{bmatrix} E_x \\ E_y \\ E_z \end{bmatrix}, \tag{15}$$

where

$$\sigma_{xx} = \sigma_{yy} = \omega_p^2 \epsilon_0 \left[\frac{\nu + j\omega}{(\nu + j\omega)^2 + \omega_H^2} \right],$$

$$\sigma_{xy} = \omega_p^2 \epsilon_0 \left[\frac{\omega_H}{(\nu + j\omega)^2 + \omega_H^2} \right],$$

$$\sigma_{zz} = \omega_p^2 \epsilon_0 \left[\frac{1}{\nu + j\omega} \right],$$

$$\omega_p^2 = \frac{n_e e^2}{m\epsilon_0},$$

$$\omega_H = \frac{eB_0}{m},$$

$\boldsymbol{B} = B_0 \hat{a}_z$, the external magnetic field.

In principle we could now use (15) in conjunction with (9) and (10) to solve for the propagation constant of the electromagnetic waves in the guiding structures used for this experiment. However, this procedure leads to a transcendental equation which must be solved numerically for the propagation constant [15], and an interpretation of the experiments which follow would be difficult. In order to facilitate the interpretation of our experiments, we use Poynting's Theorem for the average power (per unit of volume) input to the plasma.

$$\langle \mathcal{P} \rangle = \tfrac{1}{2} \operatorname{Re} \sigma_{xx} [\,|E_x|^2 + |E_y|^2] + \frac{j}{2} \operatorname{Im} \sigma_{xy} [E_x^* E_y - E_x E_y^*] + \tfrac{1}{2} \operatorname{Re} \sigma_{zz} |E_z|^2, \tag{16}$$

where (*) denotes complex conjugate.

Most of the experiments which are described in this paper were performed on plasmas located in the center of a rectangular waveguide as shown in Fig. 6(b). We note that when the magnetic field is not present, then $\sigma_{xy} = 0$, hence E_y and E_z are zero for the TE_{10} mode of propagation. In addition to this fact, E_y and E_z must go to zero at the x walls even in the presence of the magnetic field. Hence the products $\sigma_{xy} E_y E_x$ and $\sigma_{zz} E_z^2$ are of second order and are neglected. Under these assumptions, (16) may be written as

$$\langle \mathcal{P} \rangle = \tfrac{1}{2} \operatorname{Re} \sigma_{xx} |E|^2. \tag{16a}$$

It is seen that the absorption is proportional to the real part of the main diagonal component of the conductivity matrix. This conductivity is plotted as a function of ω_H/ω for various values of ν/ω in Fig. 2. It is interesting to note that the absorption increases with increasing collision frequency for values of the magnetic field variable $(\omega_H/\omega) \neq 1$, whereas at cyclotron resonance $\omega_H = \omega$ the absorption decreases with increasing collision frequency. This is consistent with our earlier observation that the collisions cause the transfer of energy from an electromagnetic wave to the electron gas of the plasma in the absence of resonance conditions, and impede the energy transfer in the close vicinity of resonance.

Fig. 3 illustrates the variation of Re σ_{xx} with ν/ω, where the magnetic field is a fixed parameter. This is the case which corresponds to most of the experiments described here. It is noticed in this figure that for a fixed value of the magnetic field variable $(\omega_H/\omega) \neq 1$, σ_{xx} first increases, reaches a maximum and then decreases as the quantity (ν/ω) increases. The effect of such behavior on the absorption of an electromagnetic wave will be shown in the experimental section. If the statement can be made that the E field inside the plasma is related to the applied E field by a function which is weakly dependent upon the collision frequency, then the point at




Fig. 2—Normalized electrical conductivity, *i.e.*, real part of σ_{xx} as a function of magnetic field (ω_H/ω), with collision frequency as a parameter.




Fig. 3—Normalized electrical conductivity, *i.e.*, real part of σ_{xx} as a function of collision frequency (ν/ω), with magnetic field (ω_H/ω) as a parameter.

which the absorption reaches a maximum, as the collision frequency is varied, is the point at which σ_{xx} is a maximum. This point was used to measure the effective electron collision frequency in both disturbed and unperturbed plasmas.

So far we have only considered the attenuation of an electromagnetic wave, which is one of the two characteristic quantities in wave propagation. The other measurable quantity is the phase velocity of the electromagnetic wave in the plasma. However, the phase velocity does not lend itself to dynamic measurement as easily as the absorption. For this reason, phase velocity measurements will be presented by static point-by-point measurements.

In order to correlate attenuation and phase measurements to the plasma parameters, an analytic expression for the propagation constant γ must be obtained. It was mentioned earlier that a rigorous solution of Maxwell's equations in the guiding structures considered here leads to a transcendental equation which must be solved numerically for the propagation constant. However, in many cases, approximate techniques can be fruitfully used to obtain admittedly less rigorous, but useful, solutions.

One such approximation technique is to use an integral equation which expresses the propagation constant in terms of the fields inside the plasma. This is the approach which is used for the study of magneto plasmas located in a rectangular waveguide as illustrated in Fig. 6(b). It is shown in the Appendix that the propagation constant in this guiding system can be approximated by

$$\gamma^2 + \beta_0^2 = j\omega\mu_0\sigma_{xx}g, \tag{17}$$

where β_0 = phase constant in the structure without a plasma, g = geometrical factor. Experiments which will be described in Section V have shown that (17) is qualitatively correct, and appear to justify the assumptions which are listed in the Appendix.

Another possible approximate method of solving for the propagation constant is to assume that the plasma is unbounded and is subjected to a uniform plane wave. This approach is especially useful in discussing the experiments performed in circular waveguides. For the case when the electromagnetic wave is propagating along the direction of the magnetic field, the propagation constant for circularly polarized waves can be simply expressed by [16], [17]

$$\gamma_{c,i}^2 = -\frac{\omega^2}{c^2}\left[1 - \frac{\omega_p^2/\omega^2}{\left(1 \pm \frac{\omega_H}{\omega}\right) - j\frac{\nu}{\omega}}\right], \tag{18}$$

where $\gamma = \alpha + j\beta$, α = attenuation constant and β = phase constant.

In (18) the minus sign is associated with γ_e, the propagation constant of the extraordinary wave (which rotates in the same sense as the electrons); the positive sign is associated with γ_i, the propagation constant of the ordinary wave (which rotates in the same sense as the positive ions). The decomposition of a linearly-polarized wave into two contrarotating circular waves leads to the well-known Faraday rotation of the plane of polarization of the linear wave. The angle of rotation θ is proportional to the difference of the phase constants β_i and β_e and the length of the path

$$\frac{2\theta}{L} = \beta_i - \beta_e. \tag{19}$$

The waveguide Faraday rotation [18] in a magneto plasma does not appear to differ in the first approximation from that of the unbounded case. The angle of rotation of a linearly-polarized wave propagating in an unbounded plasma is plotted in Fig. 4. It is seen from this figure that the angle of rotation per unit length is proportional to the number density of the electrons, and is nearly independent of the collision frequency for values of ω_H/ω much different than unity.

For ω_H/ω close to 1, the rotation angle is dependent upon both n and ν. The phenomenon of Faraday rotation is used here to study the enhancement of plasma disintegration resulting from a significant rise in the electron temperature following EM-energy transfer at cyclotron resonance to the electron gas of the plasma.




Fig. 4—Normalized Faraday rotation, *i.e.*,

$$\frac{2\theta}{\beta_0 L}\cdot\frac{360}{2\pi} = \left(\frac{\beta_i}{\beta_0} - \frac{\beta_e}{\beta_0}\right)\frac{360}{2\pi}$$

dependence on magnetic field (ω_H/ω) shown for $\nu/\omega=0$ and $\nu/\omega=0.1$. These curves are plotted for the particular value of the parameter $\omega_P^2/\omega^2=0.2$.

IV. Experimental Techniques and Apparatus

The technique of interaction of guided microwaves in a nonmagnetized plasma developed in our laboratory [5] has been extended in this study to investigate the above phenomena in magneto plasmas. The main problems associated with this technique can be broadly divided into three categories: 1) production of a suitable gyromagnetic plasma, 2) propagation of microwaves of proper characteristics through the magneto plasma and 3) investigation of the mutual interaction of these waves and the plasma. In addition to the method of probing the plasma by microwave-interaction techniques the visible light intensity emitted by the afterglow was simultaneously observed, and yielded valuable information concerning the plasma behavior. The general experimental procedure can be described best by referring to the schematic diagram in Fig. 5. A pulsed discharge plasma is obtained in a cylindrical tube which is placed either in a cylindrical or a rectangular waveguide assembly. This assembly is located in the core of a solenoid which provides the external dc-magnetic field. Two pulsed microwave signals of different frequencies and amplitudes are propagated nearly simultaneously through the decaying plasma. The transmission and reflection characteristics of these two waves and their mutual interaction in the plasma is studied under varied experimental conditions, which will be described later.

For the investigation of magneto plasmas located in rectangular waveguides the experimental arrangement shown in Fig. 6 was used. Fig. 6(b) shows the waveguide assembly containing the magneto plasma. A 2.5 or 5.0 cm long pyrex glass tube, with OD 1 cm and wall thickness 0.7 mm is used as a discharge tube in which the magneto plasma is produced. This discharge tube is located at the center of a WR 137 rectangular waveguide, such that the E field of the wave is approximately uniform across the discharge tube. The waveguide assembly containing the discharge tube is in a nearly uniform magnetic field (variation 1 per cent), which can be varied from 0 to 3000 gauss. The plasma is produced in the discharge tube by a recurrent electrical discharge through the gas. The microwave apparatus is shown schematically in Fig. 6(a). Two klystrons generate microwave power at frequencies f_d and f_s. The microwave signal of frequency f_d has a peak power of 100 mw. This signal is designated as the *disturbing signal* and is in resonance with the electrons in the magneto plasma, *i.e.*, $f_d=f_H=eB/2\pi m$. The second microwave signal, $f_s>f_d$ is of sufficiently low amplitude ($\lesssim 10$ μw) and is designated as the *sensing wave*, detected by D_2; D_1 receives only the *disturbing wave* f_d. The microwave signals reflected by the 3-stub tuners are absorbed in the ferrite isolators I_1 and I_2, so as not to re-enter the plasma. Before presenting the experimental results, the sequence of events occurring in a typical experiment is described in a timing diagram shown in Fig. 7. A




Fig. 5—Schematic diagram illustrating the technique for the study of wave-interaction phenomenon in laboratory magneto plasmas.




Fig. 6—(a) Block diagram of the experimental arrangement used for the study of magneto plasmas located in rectangular waveguides. (b) A cross-sectional view of the waveguide assembly containing the discharge tube




Fig. 7—Timing diagram of the sequence of events in a typical wave-interaction experiment.

2-μsec-wide, 5-kv dc-discharge pulse, repeated at the rate of 100 pps establishes a plasma which then decays as represented by *a* and *b* of Fig. 7. The pulsed microwave signals of controllable widths are propagated at the desired times during the afterglow. The visible light intensity emitted by the afterglow as recorded by a photomultiplier is also sketched in trace *d*. The RF envelopes of the transmitted and reflected microwave signals can be displayed on a dual-beam oscilloscope.

V. Experimental Results

In order to show the general validity of the simple theory of wave interaction in gaseous plasmas and to verify the discussions given in Section III, we report here the results of experiments performed in plasmas produced in neon and xenon gases. The gas pressures are chosen so as to achieve an efficient transfer of electromagnetic energy to the electron gas under cyclotron resonance condition; hence the quantity ν/ω_d should be much smaller than unity. Xenon was chosen as a typical gas whose collision frequency exhibits the Ramsauer behavior for low-energy electrons as opposed to that of neon. The presence of electron-ion collisions in a neon plasma of appropriate charge densities results in the fact that the total collision frequency in such a plasma varies with electronic energy in a manner similar to that of ν_{em} in xenon (see Fig. 1). In the following paragraphs, the propagation characteristics of an electromagnetic wave in a low temperature isothermal (300°K) plasma is studied and this is followed by a similar study in a perturbed plasma.

A. Propagation Characteristic of Sensing Signal Guided Through a Magneto Plasma

A low-power-pulsed microwave signal $f_s = 4.566$ Gc is guided through a decaying magneto plasma obtained in neon at a pressure of 1.6 mm Hg. The experimentally measured attenuation and phase shift undergone by this sensing signal are plotted as a function of the magnetic field in Fig. 8(a). The solid curve represents the measured attentuation and the dotted curve the measured phase constant. The theoretical attenuation and phase constants, α and β, obtained from the expression given by (17) are plotted in Fig. 8(b). A comparison of the theoretical and experimental curves shows the similarity in the general shape of the curves. It is known that the fundamental parameters such as electron density and effective collision frequency can be determined from such experimental data. The technique is also applicable to the determination of these parameters in a plasma which is perturbed, for example, by another electromagnetic wave. If the two EM waves are propagated in the time sequence shown in Fig. 7, then this technique provides information on the state of the plasma prior to, during, and in the wake of the disturbance.




Fig. 8—(a) Experimental values of the normalized attenuation and phase constants as a function of (ω_H/ω). $f_s=4.96$ Gc. Peak power 150 μw. The pulsed probing signal is transmitted 1.0 msec after the termination of a 2-μsec wide, 5-kv discharge pulse through neon gas (1.6 mm Hg). (b) theoretical plot of normalized attenuation and phase constants for $\omega_P^2/\omega^2=0.1$ and $\nu/\omega=0.04$.




Fig. 9—Wave-interaction in the afterglow of a neon magneto plasma (pressure (1 mm Hg). $f_H=eB/2\pi m=f_D=4.80$ Gc. Peak power 75 mw. Pulsed disturbing signal is propagated 1.0 msec after the termination of 2-μsec wide, 5-kv discharge pulse. $\nu_{ei}>\nu_{em}$ $f_s=6.2$ Gc. Peak power 20 μw. Traces 1 and 5 are the RF envelopes of the transmitted sensing and disturbing pulses in the absence of the plasma. Trace 3 is the envelope of f_s when f_d is shut off. When f_D is incident on the plasma, traces 2 and 6 are transmitted RF envelopes of f_s and f_D, respectively. Trace 4 is the photomultiplier output representing the light intensity emitted in the afterglow. Downward deflection indicates increased light output.

B. Cross-Modulation in a Neon Afterglow

The experiments, which are described below, were performed in a decaying neon plasma under two different conditions: 1) $\nu_{ei}>\frac{1}{3}\nu_{em}$ and 2) $\nu_{em}>3\nu_{ei}$. These conditions determine whether the total collision frequency decreases with energy of the electrons as in case 1, or increases with the energy of the electrons as in case 2. In the early part of a 1 mm Hg-neon afterglow, the electron density is in the range 10^{12} to 10^{10} electrons/cc and $T_e\sim300°$K. Hence, the first condition is prevalent as can be seen from Fig. 1. Of course, as the plasma continues to decay condition 2) becomes prevalent.

Fig. 9 displays the oscilloscope traces of the transmitted microwave signals and the photo-multiplier output for a typical experiment in which condition 1) prevails. Notice that the amplitude of the transmitted sensing wave initially increases, reaching a maximum at the point denoted by t_1, even though the electron energy is increasing from $t=t_0$ to t_1. Since the absorption of the sensing signal is proportional to ν_t for this value of the magnetic field

$$\left(\omega_H=\omega_d,\ i.e.,\ B=\frac{m}{e}\omega_d\right),$$

the increased transparency indicates that the total collision frequency has decreased. At $t=t_1$, the derivative of ν_t with respect to T_e is zero, or $\nu_{ei}=\frac{1}{3}\nu_{em}$. An independent measurement of the number density of the electrons would then yield the temperature T_e. As the energy of the electron gas is further increased, the electron collisions with the neutrals predominate over those with ions so that now the absorption of the sensing wave increases.

At the point $t=t_2$, the absorption reaches a maximum despite the continued energy rise of the electron gas. This point corresponds to the maximum value of σ_{xxs} as a function of ν/ω_s as seen in Fig. 3. This interpretation is correct provided that it is assumed that the number density of the electrons does not vary appreciably in the time interval (t_2-t_0).

If this assumption is correct, then the product of the disturbing power P_d and the time interval t_2-t_0 should be a constant, provided that the rate of energy increase of the electron gas is large compared to the rate of energy loss. This is the case, even for relatively modest values of electric field, when the frequency of the disturbing wave is close to cyclotron resonance. Fig. 10 is a plot of log P_d as a function of log (t_2-t_0) and verifies that $P_d(t_2-t_0)$ is a constant whose value depends on the initial value of ν/ω_d. Hence it is reasonable to neglect the variation of n_e in the time interval t_2-t_0 and assign an energy state to the electron gas such that at $t=t_2$, ν/ω_s has the value which maximizes σ_{xxs}. For the frequencies used here, $\nu/\omega_s\sim0.2$. This is about a 100-fold rise in collision frequency.

This large rise in the collision frequency is also indicated by the amplitude of the transmitted disturbing wave itself. Since the absorption of the disturbing wave is proportional to $1/\nu_t$, this large increase of ν_t results in a decreased absorption.[1] This is the phenomenon which was referred to earlier as self-modulation.

[1] The experiment described here illustrates insertion loss only. However, reflection measurements have shown that the absorption is very closely approximated by the insertion loss.




Fig. 10—Time elapsed since the initiation of the disturbing microwave pulse to establish a constant energy state of the electron gas (*i.e.*, corresponding to $\nu/\omega_s \sim 0.2$ at $t=t_2$), as a function of the amplitude of the disturbing wave. The two curves correspond to two different values of n_e and ν_t. Neon gas 1.0 mm Hg. $f_H = eB/2\pi m = 4.86$ Gc; $f_s = 6.2$ Gc.




Fig. 11—Wave-interaction phenomena, when the amplitude of disturbing wave is constant, but whose pulse duration is varied. Neon 0.8 mm Hg. $f_H = eB/2\pi m = 4.97$ Gc. Peak power 100 mw. $f_s = 5.86$ Gc. Trace 4 represents the amplitude of the transmitted sensing signal (CW) in the absence of the pulsed disturbing signal. Trace 3 shows the duration for which the disturbing pulse is applied. The effect of the disturbing signal on the plasma "seen" by the sensing signal is represented in trace 2. Trace 1 is the photomultiplier output.

It is also noted in Fig. 9 that the amplitude of the transmitted sensing wave reaches its unattenuated value at the point $t=t_3$. In view of the above discussion, this is possible if the number density of the electrons in the plasma has decayed considerably in the time interval t_3-t_2. This will later be shown to be the case. This fact indicates that the plasma is being rapidly destroyed due to the drastic heating of the electron gas by the resonating disturbing wave. The variation of the visible light intensity, as seen in Fig. 9 also shows the effect of the disturbing wave on the plasma. Immediately after the initiation of the disturbing pulse, the light intensity decreases due to a reduction in the electron-ion recombination coefficient. This reduction in light intensity is known [19], [5] as quenching of the afterglow. Having decreased the collision frequency of the electrons, the rate of transfer of electromagnetic energy to the electrons is thus accelerated. Electrons reach energies high enough to undergo inelastic collisions with neon atoms in their ground state (~18.5 ev) or certainly with neon atoms which are in metastable states (~2 ev). Such collisions result in a net increase of light intensity following the termination of the initial quenching. The decrease in photomultiplier current after the removal of the disturbing pulse is most likely due to the decreasing number of inelastic collisions as well as the reduction in recombination light intensity which in the prevailing charge density range is approximately proportional to n^2.

We shall now describe effects produced at constant amplitude when the width of the disturbing pulse is varied. Figs. 11(a), (b), (c) show the oscilloscope traces of the transmitted microwave signals and photomultiplier current, for three different pulse widths of the disturbing wave under the condition $\nu_{em} \gg 3\nu_{ei}$. It should be noted that the sensing microwave signal is operated in this instance as a continuous wave pulsed-off for a short duration in order to obtain a reference level. In the absence of the disturbing signal, trace 4 in all these figures shows that the attenuation of the sensing signal decreases as a function of time due to the normal decay of the electron density. For a narrow pulse of the disturbing wave, only the increasing absorption of the sensing signal and immediate relaxation is seen on trace 2 of Fig. 11(a). However, for wider disturbing pulses (width $> t_2-t_0$) it is observed that the amplitude of the transmitted sensing signal reaches a value corresponding to its original unattenuated level even before the conclusion of the disturbing pulse [trace 2 of Fig. 11(b), (c)]. This is again attributed to the rapid loss of electrons from the plasma when they are subjected to resonant heating for the time intervals indicated above. One of the possible reasons for this phenomenon is that it appears necessary to keep the electrons energetic for such a time interval so that they are capable of diffusing to the walls with a very considerably enhanced diffusion coefficient. In addition to the enhanced collisional diffusion, a second possible reason for the rapid disintegration of the plasma might be due to some instability which can develop when considerable selective heating of the electron gas occurs, which is the case at cyclotron resonance. When the cross-modulation experiment was performed in neon (0.5 mm Hg), as shown in Fig. 12, a low-frequency (140 kc) amplitude modulation was observed on the amplitude of the transmitted sensing signal, during the time interval of the disturbing wave pulse. However such variations in the transmitted am-

plitude of the sensing wave were not observed at higher pressures or for lower electron densities.

The phenomena are considerably different at later times in the afterglow (Fig. 13) but are readily understood on the basis of the previous experiments. It is seen that the absorption of the sensing wave increases immediately with increasing electron energy. This is understood upon the basis of the expression of the total collision frequency $\nu_t = \nu_{ei} + \nu_{em}$. Since the electron density is much lower at these times in the afterglow, the contribution of ν_{ei} to the total collision frequency is negligible. Hence, an increase of the energy of the electrons can only increase their collision frequency as contrasted with the initial decrease which was observed in Fig. 9.

It is also seen that the increase in photomultiplier current occurs almost immediately (<1 μsec) after the start of the disturbing pulse. This occurs because the electrons are accelerated to high energies (from about 0.04 ev to at least 2 ev) within very few collision times.




Fig. 12—The low-frequency (~140 kc) amplitude modulation which was observed on the transmitted amplitude (trace 2) of the sensing signal, when plasma electrons are accelerated by the resonating disturbing wave. Trace 1 is the photomultiplier output. Neon gas 0.5 mm. Hg $f_H = eB/2\pi m = f_D = 5.1$ Gc. Peak power 100 mw; $f_s = 5.86$ Gc.




Fig. 13—Wave-interaction in the afterglow of a neon plasma for the condition $\nu_{em} \gg 3\nu_{ei}$. Neon 1.0 mm Hg. $f_D = 4.78$ Gc $= f_H$. $f_s = 6.47$ Gc. Trace 1 shows photomultiplier output. Trace 3 represents the amplitude of transmitted disturbing signal and trace 2 that of the sensing signal. Peak power of $f_D = 100$ mw.

This rapid acceleration is attributed to the fact that the power absorbed from the disturbing wave is inversely proportional to $1/\nu_t$ for $\omega_H = \omega_d$. The total collision frequency at $t = t_0$ is, of course, smaller than in the experiment described in Fig. 9, since the contribution of ν_{ei} to the total collision frequency is here insignificant. Hence the energy rise when only ν_{em} is present is more rapid than in the case when $\nu_t = \nu_{ei} + \nu_{em}$.

This rapid rise in the electronic energy is also evidenced by the self-modulation of the transmitted disturbing wave. It is seen that the transmitted disturbing wave increases more rapidly in Fig. 13 than in Fig. 9. This is consistent with the above discussion.

Additional experiments were performed to verify the fact that the point t_2 of Figs. 9, 11, and 13 is in every case the point where Re σ_{xxs} reaches its maximum. Two sensing frequencies, ω_{s1} and ω_{s2}, are used such that $\omega_{s1} > \omega_{s2} > \omega_d = \omega_H$. Thus, as predicted by Fig. 3, the point of maximum absorption (t_2) as sensed by ω_{s2} is closer to t_0 than the corresponding point sensed by ω_{s1}. This is seen in Fig. 14.

This figure also illustrates the enhanced disintegration of the plasma in the time interval $t_4 - t_2$. All other quantities being equal, the propagation of ω_{s2} is affected by a smaller electron density than that of the higher frequency ω_{s1}, because ω_{s2} is closer to cyclotron resonance than ω_{s1}. Hence the plasma becomes completely transparent to ω_{s1} at an earlier time than to ω_{s2}.

The enhanced disintegration of the plasma as a result of the rapid rise of electron energy has been studied in greater detail by using Faraday rotation [18] of guided electromagnetic waves through plasmas. In this experiment, the plasma (same dimensions as in the rectangular guide experiments) is centrally located in a circular waveguide immersed in a longitudinal magnetic field. By measuring the angle of rotation of a linearly-polarized TE_{11} pulsed sensing wave as a function of time in the late afterglow, during and in the wake of a pulsed disturbing wave, ($\omega_d = \omega_H$) information is obtained on the influence of the resonance heating of the electrons on the phase velocities of the extraordinary and ordinary sensing waves.

Fig. 15 shows typical results of such an experiment for several amplitudes of the disturbing wave. Notice that at any time $t > t_1$, the angle of rotation does not return to its unperturbed value for large amplitudes of the disturbing wave. However, for smaller amplitudes of the disturbance, the angle tends to relax towards the undisturbed value. Since the rotation angle is directly proportional to the total number of electrons in the magnetized plasma, the difference in angles at $t = t_3$ (after the plasma electron gas has relaxed to its initial temperature) represents the loss of electrons. Notice the correspondence of the experimentally obtained dependence of Faraday rotation upon collision frequency in the interval ($t_1 - t_0$) to that predicted theoretically from (18) and plotted in Fig. 16.




Fig. 14—Effect caused by the disturbing microwave signal ($f_D = 5.05$) on two sensing signals. $f_{s1} = 6.0$ Gc. $f_{s2} = 6.7$ Gc. Trace 1b and 2b represent the amplitudes of transmitted f_{s1} and f_{s2} respectively in the absence of the disturbing signal, whereas 1a and 2a represent the corresponding trace in the presence of the disturbing signal. Trace 4 shows the duration for which the pulsed signal is present. Trace 3 represents the photomultiplier output. Neon gas 0.9 mm Hg.




Fig. 15—Faraday rotation of 1 μsec wide sensing signal (f_s) as a function of time in the afterglow, during and in the wake of the pulsed disturbing signal (f_D). The Faraday rotation is shown for different amplitudes of the disturbing signal.




Fig. 16—Normalized Faraday rotation as a function of ν/ω for different values of ω_p^2/ω^2, and constant $\omega_s/\omega_H = 1.04$.

C. Cross-Modulation in a Ramsauer Gas (Xenon)

It was shown in the previous experiments that it was possible for the total collision frequency in a neon plasma to decrease with increasing electronic energy despite the fact that the cross section for momentum transfer between electrons and neon atoms is a slowly increasing function of electron temperature. The decreasing collision frequency with increasing electron energy is due to the coulomb collisions between the electrons and ions which are dominant when the degree of ionization is greater than 10^{-5} and at low electron temperatures ($\lesssim 300°K$).

As is well known, the cross section for momentum transfer of electrons with xenon atoms decreases very rapidly with increasing T_e from $\sim 300°K$ reaching a minimum and then increasing as shown in Fig. 1. In view of the large absolute values of xenon cross section for slow ($\sim 300°K$) electrons, the electron-ion collision frequency contributes little, if any, to the total collision frequency at the xenon pressure indicated, even at the maximum electron densities used in these experiments ($\sim 10^{11}$/cc). At these electron densities however, a neon (1 mm Hg, 300°K) plasma is already completely coulomb-interaction dominated, as just mentioned. Therefore, in view of the falling cross sections with increasing electron energy in both cases, the phenomena of wave interaction will be completely similar.

Fig. 17 shows the oscilloscope traces of the amplitudes of the transmitted signals obtained from the experiment performed in a xenon afterglow. These photographs [Fig. 17(a), (b), (c)] show the effects for three different amplitudes of the disturbing wave ($\omega_d = \omega_H$). It is seen that immediately after the application of the disturbing microwave signal, the absorption of the sensing signal decreases in the time interval $t_1 - t_0$. This is, of course, due to the decreasing collision frequency with increasing electron energy, as is the case in a coulomb-interaction dominated neon plasma. At the instant t_1, the electron energy corresponds to that energy for which Q_{em} and therefore ν_{em} is a minimum (Ramsauer). In the time interval t_1 to t_2 [Fig. 17(a)] the absorption of the sensing signal increases reaching a maximum at $t = t_2$ despite the increasing collision frequency. The interpretation of this point is identical with the corresponding point in the neon plasma discussed earlier and shown in Fig. 9. It is also seen in Fig. 17(c), as opposed to (a) and (b), that as a result of the relatively high level (100 mw) of the disturbing wave and immediately following its conclusion, the complete unattenuated amplitude of the sensing wave signal is transmitted. In the case of a passive plasma this could occur only as a result of a drastic loss of electron density in the short time interval observed.

The results of these experiments led to a simple method of determination of electron collision frequencies in a magneto plasma. This method will now be described.




Fig. 17—Wave-interaction phenomena in xenon. Pressure 0.4 mm Hg. Trace 1 is the transmitted amplitude of the sensing signal in the presence of a disturbing signal. Trace 2 is the transmitted amplitude of the disturbing signal. $f_s=6.1$ Gc. $f_H=eB/2\pi m=f_D=5.2$ Gc. The three photographs show the effects for three amplitudes of the disturbing pulse.

D. Cross-Modulation Technique for Determining Collision Frequency

The method is based upon the interpretation of the point $t=t_2$ in Fig. 9. At this point $\partial\sigma_{xxs}/\partial\nu=0$. If the magnetic field intensity is adjusted to a value such that

$$\left.\frac{\partial\sigma_{xxs}}{\partial\nu}\right|_{t=t_0}=0, \tag{20}$$

then the value of ν at $t=t_0$ is a solution to (20). The condition given by (20) is obtained experimentally by varying the magnetic field and observing the cross modulation as shown in Fig. 18. Notice that for both $\omega_H/\omega_s\ll 1$ and $\omega_H/\omega_s\gg 1$, the sensing wave undergoes increased absorption for increasing collision frequency. However, for $\omega_H/\omega_s=1$, the absorption decreases. It appears obvious that there are two values of the magnetic field, for which the cross modulation disappears: these fields are solutions of (20). The value of ν is given to a good approximation by

$$\nu\doteq\omega_s\left|1-\frac{\omega_H}{\omega_s}\right|, \tag{21}$$

where ω_H corresponds to these values of the magnetic field for which the cross modulation disappears.

The validity of this method is limited by the range of validity of (16a). Basically, the use of this equation requires that the electron density be small enough so that the electromagnetic fields inside the plasma can be well approximated by the applied fields. It is for this reason that the experiments were performed with very low electron-density plasmas ($n_e<10^8$/cc). Furthermore,




Fig. 18—Variation of the cross-modulation as a function of the magnetic field. Neon gas 12.0 mm Hg. $f_d=4.764$ Gc. $f_s=6.72$ Gc.

experiments have shown that only the value $\omega_H/\omega_s>1$ can be used in (21). For $\omega_H/\omega_s<1$, both α, the attenuation constant, and β, the phase constant, are dependent upon ν, whereas for $\omega_H/\omega_s>1$, β is almost independent of ν. Since attenuation is used for this measurement, the condition $\omega_H/\omega_s>1$ must be used.

This method yielded collision frequencies in good agreement with published results.

VI. Conclusion

In summary, the typical experimental results reported above illustrate adequately the general phenomenon of RF wave interaction in magneto plasmas. The theory on which these experimental results are based can be considered as a generalization of Bailey's [3] theory of interaction of radio waves in the ionosphere. It was shown here that the phenomenon of interaction of microwaves in a magneto plasma constitutes a useful method for investigating plasma behavior. This method is applied here to study some of the detailed aspects of electromagnetic energy transfer into kinetic energy of a charged constituent of the plasma. Particular emphasis was placed here on the transfer of electromagnetic energy to the electron gas of a plasma under cyclotron-resonance condition. The consequent fast rate of kinetic energy increase of the electrons is evidenced by the corresponding change in their collision frequency and also in the magnetic field control of plasma confinement.

Appendix

Derivation of (17)

In order to derive an approximate expression for the propagation constant for waves propagating as exp $(-\gamma z)$ in an anisotropic medium, let us consider Maxwell's equations with and without the plasma:

$$\nabla_t\times\boldsymbol{H}_0-\gamma_0\hat{a}_z\times\boldsymbol{H}_0=j\omega\epsilon_0\boldsymbol{E}_0, \tag{22}$$

$$\nabla_t\times\boldsymbol{E}_0-\gamma_0\hat{a}_z\times\boldsymbol{E}_0=-j\omega\mu_0\boldsymbol{H}_0, \tag{23}$$

$$\nabla_t\times\boldsymbol{H}-\gamma\,\hat{a}_z\times\boldsymbol{H}=\boldsymbol{J}+j\omega\epsilon_0\boldsymbol{E}, \tag{24}$$

$$\nabla_t\times\boldsymbol{E}-\gamma\,\hat{a}_z\times\boldsymbol{E}=-j\omega\mu_0\boldsymbol{H}, \tag{25}$$

where

$\boldsymbol{E}_0$, $\boldsymbol{H}_0$ = electromagnetic fields in the empty structure,

$\boldsymbol{E}$, $\boldsymbol{H}$ = electromagnetic fields in the structure,

$\nabla_t = \hat{a}_x(\partial/\partial_x) + \hat{a}_y(\partial/\partial_y)$,

$\hat{a}$ = unit vector,

γ, γ_0 = propagation constant of a wave with and without the plasma,

J = conduction current density as defined by (15).

The following sum is formed: $\boldsymbol{E}\cdot 22 + \boldsymbol{E}_0\cdot 24 - \boldsymbol{H}\cdot 23 - \boldsymbol{H}_0 \cdot 4$; this is integrated over the volume enclosed by the guiding structure. The application of the divergence theorem leads to the following equation:

$$\oint\!\!\oint_S (\boldsymbol{H}_0 \times \boldsymbol{E} - \boldsymbol{H} \times \boldsymbol{E}_0)\cdot d\boldsymbol{S} - (\gamma + \gamma_0) \iiint (\boldsymbol{E}\cdot \hat{a}_z \times \boldsymbol{H}_0 + \boldsymbol{E}_0 \cdot \hat{a}_z \times \boldsymbol{H}) dV = 2j\omega \iiint (\epsilon_0 \boldsymbol{E}\cdot\boldsymbol{E}_0 + \mu_0 \boldsymbol{H}\cdot\boldsymbol{H}_0) dV + \iiint \boldsymbol{E}_0 \cdot \boldsymbol{J}\cdot dV. \quad (26)$$

The first integral of (26) is zero because of the boundary conditions on E and E_0. Further simplification is possible if the fields in the absence of the plasma are TE. We can solve (23) and (25) for $\boldsymbol{H}$ and $\boldsymbol{H}_0$ and substitute this in (26):

$$\gamma + \gamma_0 = \frac{\iiint \boldsymbol{E}_0 \cdot \boldsymbol{J} dV + 2j\omega \iiint (\epsilon_0 \boldsymbol{E}\cdot\boldsymbol{E}_0 + \mu_0 \boldsymbol{H}\cdot\boldsymbol{H}_0) dV}{\frac{1}{j\omega\mu_0} \iiint (\boldsymbol{E}_0 \cdot \nabla_t E_z + (\gamma+\gamma_0)\boldsymbol{E}\cdot\boldsymbol{E}_0) dV}. \quad (27)$$

The fields which were assumed for the plasma partially filling the waveguide as shown in Fig. 6(b) were

$$\boldsymbol{E} = A \sin\left(\frac{\pi y}{a}\right)\hat{a}_x + B \sin\left(\frac{\pi x}{b}\right)\hat{a}_y + C \sin\left(\frac{\pi x}{a}\right)\sin\left(\frac{\pi y}{b}\right)\hat{a}_z. \quad (28)$$

This assumption leads to a solution for the propagation constant given by

$$\gamma^2 - \gamma_0^2 = j\omega\mu_0\sigma_{xx}\left(\frac{W}{a} + \frac{1}{2\pi}\sin\left(\frac{\pi W}{2a}\right)\right) + \frac{8}{\pi^2}\frac{B}{A}\sigma_{xy}\sin\left(\frac{\pi W}{2a}\right). \quad (29)$$

The choice of the ratio B/A was made in the following manner. The dominant mode in the waveguide is the TE_{10} mode in the limit of low electron densities; in addition, the amplitude B arises because σ_{xy} is nonzero. Hence the product of $\sigma_{xy}B$ is considered to be of second order in importance and is neglected.

Bibliography

[1] B. D. H. Tellegan, "Interaction between radio waves?" *Nature*, vol. 131, p. 840; June, 1953.

[2] V. A. Bailey and D. F. Martyn, "The influence of electric waves on the ionosphere," *Phil. Mag.*, vol. 18, pp. 369–386; August, 1934.

[3] ——, "The motions of electrons in a gas in the presence of variable electric fields and a constant magnetic field," *Phil. Mag.*, vol. 23 (suppl), pp. 774–781; April, 1937.

[4] ——, *et al.*, "Resonance in gyro-interaction of radio waves," *Nature*, vol. 169, pp. 911–913; May, 1952.

[5] L. Goldstein, *et al.*, "Interaction of microwaves propagated through a gaseous discharge plasma," *Phys. Rev.*, vol. 90, pp. 151–152, April, 1953; "Quenching of afterglow in gaseous discharge plasmas by lower power microwaves," *Phys. Rev.*, vol. 90, pp. 486–487, May, 1953.
L. Goldstein and J. M. Anderson, "Interaction of microwaves in gaseous discharge plasmas and the Ramsauer effect," in "Record of the Fourteenth Annual Conference on Physical Electronics," Res. Lab. of Electronics, Mass. Inst. Tech., Cambridge; March, 1954.

[6] J. M. Anderson and L. Goldstein, "Interaction of electromagnetic waves of radio-frequency in isothermal plasmas: Collision cross-section of helium atoms and ions for electrons," *Phys. Rev.*, vol. 100, pp. 1037–1046; November, 1955.

[7] A. A. Dougal and L. Goldstein, "Energy exchange between electron and ion gases through coulomb collisions in plasmas," *Phys. Rev.*, vol. 109, pp. 615–624; February, 1958.

[8] L. Goldstein and T. Sekiguchi, "Electron-electron interaction and heat conduction in gaseous plasmas," *Phys. Rev.*, vol. 109, pp. 625–630; February, 1958.

[9] C. L. Chen, *et al.*, "Electron temperature dependence of the recombination coefficient in pure helium," *Phys. Rev.*, vol. 121, pp. 1391–1400; March, 1961.

[10] L. Tonks, "Theory of magnetic effects in the plasma of an arc," *Phys. Rev.*, vol. 56, pp. 360–373; August, 1939.

[11] W. P. Allis and E. I. Gordon, "Microwave Gaseous Discharges," Quart. Progr. Rept. of Res. Lab. of Electronics, Mass. Inst. Tech., Cambridge; July, 1957 (unpublished).

[12] ——, "Motions of ions and electrons," in "Handbuch der Physik," S. Flugge, Ed., Springer-Verlag, Berlin, Germany, vol. 21; 1957.

[13] P. Molmud, "Langevin equation and the ac conductivity of non-Maxwellian plasmas," *Phys. Rev.*, vol. 114, pp. 29–32; April, 1959.

[14] I. P. Shkarofsky, "Values of Transport Coefficients in a Plasma for any Degree of Ionization on a Maxwellian Distribution," Res. Labs., RCA Victor, Ltd., Montreal, Canada, Res. Rept. No. 7-801; December, 1960.

[15] H. Suhl and L. R. Walker, "Topics in guided wave propagation through gyromagnetic media," *Bell Sys. Tech. J.*, vol. 33, pp. 579–659; May, 1954.

[16] E. C. Jordan, "Electromagnetic Waves and Radiating Systems," Prentice Hall, Inc., New York, N. Y.; 1950.

[17] L. Goldstein, "Electrical discharge in gases and modern electronics," in "Advances in Electronics and Electron Physics," L. Marton, Ed., Academic Press, Inc., New York, N. Y., vol. 7; 1955.

[18] ——, "Nonreciprocal electromagnetic wave propagation in ionized gaseous media," IRE Trans. on Microwave Theory and Techniques, vol. MTT-6, pp. 19–29; January, 1958.

[19] C. Kenty, "The recombination of argon ions and electrons," *Phys. Rev.*, vol. 32, pp. 624–635; October, 1928.

[20] S. C. Brown, "Basic Data on Plasma Physics," The Technology Press, John Wiley and Sons, Inc., New York, N. Y.; 1959.

Frequency Conversion in a Microwave Discharge*

J. R. BAIRD† AND P. D. COLEMAN†, MEMBER, IRE

Summary—One nonlinear property of a microwave discharge located between two closely spaced parallel plates whose dimensions are small compared to the wavelength is analyzed. This discharge geometry, with its small volume, permits the attainment of CW microwave power densities in the discharge of the order of 0.1 to 1 Mw/cm³. It is concluded that the high power density coupled with the high diffusion rate of the closely spaced parallel plates results in a modulation of the electron density at the microwave frequency. The source of this nonlinearity is postulated to be a modulation of the ionization frequency ν_i whose functional form is taken to be $\nu_i = \alpha |v_d|$ where v_d is the ordered drift velocity and α is a proportionality factor constant in time. The theoretical analysis is compared to experimental results obtained by approximating the assumed geometry in an *X*-band and *K*-band frequency multiplier and in an *X*-band mixer. Harmonics up through the seventh at *X* band and up through the fourth at *K* band have been studied. Frequency mixing of 9- and 11-kMc signals to obtain a 20-kMc signal has yielded predictable results. Parametric amplification in a discharge is briefly considered.

I. Introduction

NONLINEAR properties are known to be possessed by microwave discharges. However, few paper exist on this subject, perhaps because it is difficult to isolate or restrict the discharge conditions such that a single effect can be studied and quantitatively analyzed.

In this paper the discharge geometry chosen is that of two closely spaced parallel plates having dimensions which are small compared to the operating wavelength. This restriction reduces the description of the discharge to a one-dimensional, lumped circuit element.

The small volume condition on the discharge permits the system to be operated at large CW power densities and field strengths for very modest absolute input power. Typical volumes considered are of the order of 10^{-5} cm³. Hence with a power input of 10 watts, the power density approaches 1 Mw/cm³. Field strengths are typically of the order of 0.5 to 3 kv/cm. Thus the discharge is being driven sufficiently hard for nonlinear effects to become useful and important.

The large electron densities and close spacing of the discharge plates permit diffusion losses to become dominant. The large power densities permit ionizations at fast rates. Hence the possibility exists for generating and losing electrons in times comparable to the RF period.

For the discharge geometry in this paper, it is postulated that the ionization frequency ν_i can be appreciably modulated by the microwave drive frequency. The functional form assumed is that ν_i is proportional to the absolute value of the ordered drift velocity v_d in the direction of the applied microwave field. Since this function is even, the ionization frequency will be modulated twice during each RF cycle.

By first solving for the linear drift velocity solution v_d of the momentum transfer equation, then determining ν_i, and, third, solving the continuity equation for the electron density $n(x, t)$, the harmonic current response of the discharge can be readily computed. It has been found convenient to include along with the microwave field a dc field for diagnostic purposes.

The analysis has been experimentally verified with a 3-cm frequency multiplier and mixer, and an 8.6-mm frequency multiplier. The variation of harmonic power as a function of a dc bias field is shown experimentally to be in close agreement with theory up through the 7th harmonic in the *X*-band device. Conversion losses were also found to be accurately predictable.

The performance of the 35-kMc multiplier was checked through the 4th harmonic. Here the electron density is varying at a 70-kMc rate. Just how far in frequency one can extend this type of device has yet to be determined.

II. Description of the Nonlinearity

If the microwave discharge is assumed to have a parallel plate geometry, then all quantities will involve only one space variable x. Neglecting the ionic current, the current density $J(x, t)$ of $n(x, t)$ electrons per unit volume having an average velocity $v_d(x, t)$ is given by the scalar expression

$$J(x, t) = qn(x, t)v_d(x, t) \tag{1}$$

where $-q = e$ is the electronic charge.

If the discharge is nonlinear, then the current density $J(x, t)$ response to the application of a combined dc and microwave electric field will have harmonic current components in addition to the fundamental and dc components. This will require, as seen from (1), that the electron density $n(x, t)$ and/or the average drift velocity $v_d(x, t)$ be expressible in a Fourier series.

In the linear analysis[1] of a microwave discharge in a parallel plate geometry where a combined dc and ac electric field E_T of the form

$$E_T = E_0 + E\left[\cos \omega t - \frac{\omega}{\nu_c} \sin \omega t\right] \tag{2}$$

* Received by the IRE, August 28, 1961. The work described was performed under the sponsorship of the AEC Res. Div., Thermonuclear Branch, under Contract AT(11-1)-392 and WADD Electronic Tech. Lab., under Contract AF33(616)-7043.

† Ultramicrowave Group, University of Illinois, Urbana, Ill.

[1] E. Everhart and S. C. Brown, "The admittance of high frequency gas discharges," *Phys. Rev.*, vol. 76, pp. 839–842; September, 1949.

is applied in the x direction, the solution of the momentum transfer equation

$$\frac{\partial v_d}{\partial t} + \nu_c v_d = \frac{qE_T}{m} \tag{3}$$

for the velocity v_d is given by

$$v_d = \frac{q}{m\nu_c}[E_0 + E\cos\omega t] = \frac{qE}{m\nu_c}[\beta + \cos\omega t], \tag{4}$$

where ν_c is the collision frequency for momentum transfer, m is the electron mass, and β is defined as

$$\beta = E_0/E. \tag{5}$$

The continuity equation for the case where diffusion is the dominant loss mechanism is

$$\frac{\partial n}{\partial t} = \nu_i n + D\frac{\partial^2 n}{\partial x^2}, \tag{6}$$

where ν_i is the ionization frequency and D the diffusion constant.

A linear solution (electron density independent of time) of (6) for the condition $n(x, t)$ is zero at the metal plate boundaries located to $x = \pm l$ is

$$n(x, t) = n(x) = n_0\cos\left(\frac{\pi x}{2l}\right), \tag{7}$$

with

$$D = \left(\frac{2l}{\pi}\right)^2 \nu_i. \tag{8}$$

To account for a nonlinear effect using the momentum transfer and continuity equations, it could be assumed that the collision frequency ν_c and/or the ionization frequency ν_i are not constant in time.

Margenau and Hartman[2] have treated the case of a low power level microwave discharge wherein diffusion has been neglected and the electron density has been assumed to be constant in time. The nonlinearity of the discharge has been accounted for by having the collision frequency ν_c a function of time. This assumption leads to harmonic component terms in the average drift velocity $v_d(x, t)$.

In the discharge geometry of this paper, diffusion will be the dominant loss mechanism for electrons as opposed to attachment and recombination since the density gradient between the two closely spaced electrodes is extremely high. Also the power level (0.1 to 1 Mw/cm^3) and field strength (0.5 to 3 kv/cm) are quite large so that electrons can be generated and lost at a very rapid rate. This leads to the possibility that the ionization frequency ν_i could be a function of time and hence, the electron density $n(x, t)$ could be modulated by the microwave drive field. The problem is to find the appropriate functional form of $\nu_i(t)$ that will explain the experimental facts.

In his study of dc gas discharges, Townsend assumed that the ionization frequency ν_i was proportional to the average dc drift velocity.[3] A corresponding assumption for the microwave discharge would be to make the ionization frequency proportional to the absolute value of the ordered drift velocity since ionizations are equally probable for both positive and negative velocities;

$$\nu_i = \alpha|v_d|. \tag{9}$$

While the utility of the assumption made in (9) will have to be determined by the agreement between computed and experimental results, some intuitive arguments can be made to support this assumption.

The microwave field strengths used in the experiments described in this paper, while far in excess of the minimum required to sustain the discharge, are not sufficient to give an electron-ionizing energy in one oscillation. To provide a net transfer of energy, collisions must exist. The energy which the electrons gain is largely in the form of random thermal motion with only a small part contributed by ordered RF motion. Thus, it is expected that the electron energy or temperature is at best only slightly modulated by the RF field.

Except for high velocity electrons, the electron velocity distribution in velocity space is probably not too different from a Maxwell distribution as shown in Fig. 1(a). However, consider next the distribution of velocities in the x, y and z directions. The curves of Fig. 1(c) and (d) are close to equilibrium distributions since there are no applied fields in these directions. All velocities in the y and z directions are a result of energy gained in the x direction and scattered into the y and z directions by elastic and inelastic collisions. The most probable x component of velocity will not be zero, as indicated by Fig. 1(b), but will vary with the RF ordered velocity as shown by curves a and c.

The number of electrons Δn with velocities exceeding the ionizing velocity v_i due to the RF modulation will be given approximately by

$$\Delta n \simeq \int_{v_i}^{\infty} N\left[\frac{m}{2\pi kT}\right]^{-1/2} \cdot\left[\epsilon^{-(m/2kT)(v_x-|v_d|)^2} - \epsilon^{-(m/2kT)v_x^2}\right]dv_x. \tag{10}$$

Since $|v_d| \ll v_i$, the first exponential term can be expanded in a series wherein only the first two terms are retained, yielding

$$\Delta n \simeq |v_d| \int_{v_i}^{\infty} \frac{mv_x}{2kT} N\left(\frac{m}{2\pi kT}\right)^{-1/2} \epsilon^{-(mv_x^2/2kT)}dv_x. \tag{11}$$

Thus assuming the ionization frequency ν_i proportional to the number of electrons Δn having an x com-

[2] H. Margenau and L. M. Hartman, "Theory of high frequency gas discharges II," *Phys. Rev.*, vol. 73, pp. 309–315; February, 1948.

[3] S. C. Brown, "Basic Data of Plasma Physics," John Wiley and Sons, Inc., New York, N. Y., p. 137; 1959.




Fig. 1—Maxwell distribution of velocity components. (a) Velocity distribution. (b) Distribution of x component of velocity. (c) Distribution of y component of velocity (d) Distribution of z component of velocity.

ponent of velocity exceeding the ionization velocity v_i appears to be compatible with (9).

For the discharge geometry and power levels stated in this paper, it will be assumed that the principal source of nonlinearity arises from an RF modulation of the ionization frequency ν_i and that its functional form can be sufficiently described by the relationship given in (9).

III. Calculation of Current Density Function $J(x, t)$

The current density function $J(x, t)$ will be calculated assuming that the average drift velocity $v_d(x, t)$ in the x direction can be represented by the linear solution given by (4) and that the electron density function $n(x, t)$ contains harmonic terms because of the RF modulation of the ionization frequency ν_i. The calculation of $n(x, t)$ involves solving (6) and (9).

Substituting the linear drift velocity value given by (4) into (9), the result is

$$\nu_i = \frac{q\alpha E}{m\nu_c} \left| \beta + \cos \omega t \right|, \tag{12}$$

where α is a constant of proportionality independent of the time t.

Since ν_i is seen to be an even function of $\theta = \omega t$, it can be expanded in the following Fourier cosine series:

$$\nu_i = \frac{q\alpha E}{m\nu_c}\left[\frac{a_0}{2} + \sum_{k=1}^{\infty} a_k \cos (k\theta)\right], \tag{13}$$

where the Fourier coefficient a_k are given by

$$a_k = \frac{1}{\pi}\int_{-\pi}^{\pi} \left| \beta + \cos\theta \right| \cos (k\theta) d\theta = a_k(\beta). \tag{14}$$

The boundary condition that the electron density is zero at $x = \pm l$ will require that the space variation of $n(x, t)$ is given by the factor $\cos(\pi x/2l)$ as in the linear case. The appropriate functional form for $n(x, t)$ is

$$n(x, t) = n_0\left[1 + \sum_{s=1}^{\infty} B_s \sin (s\theta)\right] \cos\left(\frac{\pi x}{2l}\right), \tag{15}$$

where the coefficients B_s are yet to be determined. It will be observed that the expression for $n(x, t)$ as given by (15) reduces to the linear solution when the coefficients B_s are set equal to zero. Since the modulation of $n(x, t)$ is not expected to be large, all the B_s coefficients are small compared to one.

The various terms in the continuity equation, as given by (6), can now be readily computed. First, the term $\nu_i n$ is seen to be

$$v_i n \simeq \frac{\alpha q n_0 E}{m\nu_c}\left[\frac{a_0}{2} + \sum_{k=1}^{\infty} a_k \cos (k\theta)\right] \cos\left(\frac{\pi x}{2l}\right), \tag{16}$$

where the coefficients B_s have been neglected. Next, the diffusion term is approximated by

$$D\frac{\partial^2 n}{\partial x^2} \simeq -\frac{n_0 D\pi^2}{4l^2} \cos\left(\frac{\pi x}{2l}\right). \tag{17}$$

Finally, by differentiating $n(x, t)$ as given by (15), one obtains

$$\frac{\partial n}{\partial t} = n_0\omega \sum_{s=1}^{\infty} sB_s \cos(s\theta) \cos\left(\frac{\pi x}{2l}\right). \tag{18}$$

Equating coefficients of like terms in the continuity equation yields

$$B_s = \frac{\alpha qE}{m\omega\nu_c} \frac{a_s}{s}. \tag{19}$$

The current density $J(x, t)$ can now be readily computed from (4) and (15):

$$J(x, t) \simeq \frac{n_0q^2E}{m\nu_c}\left\{[\beta + \cos\omega t] + \frac{\pi q\alpha a_0E}{m\omega\nu_c}\sum_{s=2}^{\infty} A_s \sin s\omega t\right\} \cos\left(\frac{\pi x}{2l}\right), \tag{20}$$

where the small term multiplying sin ωt has been neglected, and A_s is given by

$$A_s = \frac{1}{2\pi a_0}\left[2\beta\frac{a_s}{s} + \frac{a_{s-1}}{s-1} + \frac{a_{s+1}}{s+1}\right] = A_s(\beta). \tag{21}$$

The harmonic terms in (20) are those involving the coefficients A_s. Hence the linear solution is obtained by setting A_s equal to zero.

At this point in the analysis, all the coefficients can be calculated in terms of β, the ratio of dc electric field amplitude E_0 to the RF field amplitude E; however, the proportionality constant α is still to be determined.

IV. Physical Realization of Assumed Discharge Geometry

Assuming the preceding analysis to be valid, it should be possible to predict the nonlinear behavior of any microwave discharge system in which the discharge takes place between closely spaced parallel plates whose dimensions are small compared to the wavelength. The conditions imposed are that the system can be described essentially in terms of one dimensional, lumped circuit elements as opposed to a distributive system.

A convenient way to meet the prescribed conditions in a microwave waveguide system is shown in Fig. 2. In this structure, the adjustable center conductors of two dc isolated coax lines meet in the center of a rectangular waveguide to form a small gap discharge region. If the gap spacing is small compared to the discharge post diameter, a uniform field assumption in the gap region is a good approximation. The coax lines are dc isolated by mica washers, while a vacuum seal is maintained by O rings positioned as shown.

The basic structure of Fig. 2 has been used for both a frequency multiplier and a frequency mixer. With some modification it might also be useful in a microwave discharge, parametric amplifier system.




Fig. 2—Cross-sectional view of microwave gas discharge structure.

V. Frequency Multiplication

Any nonlinear element capable of being driven at high power levels with microwave frequencies of the order of 10 to 70 kMc is of considerable interest for the possible production of low millimeter and submillimeter wave signals; therefore, the first application of the preceding analysis will be made to a microwave frequency multiplier.

To evaluate the harmonic power output of the microwave discharge system shown in Fig. 2, the current I flowing in the discharge posts due to the motion of the electrons in the discharge gap must be computed. This current is given by the well known expression

$$I = \frac{A}{2l}\int_{-l}^{l} qnv_d dx = \frac{A}{2l}\int_{-l}^{l} J dx, \tag{22}$$

where A is the area of the discharge plates.

Substituting for J from (20) and performing the integration over x, the current is found to be

$$I \simeq \frac{2n_0q^2AE}{\pi m\nu_c}\left\{[2\beta + \cos\omega t] + \frac{\pi q\alpha a_0E}{m\omega\nu_c}\sum_{s=2}^{\infty} A_s \sin(s\omega t)\right\}. \tag{23}$$

The factor 2 multiplying β has been added in the dc term in an attempt to account for the positive ion current. At microwave frequencies this positive ion current is negligible.

From (23) it is seen that the various current amplitudes are

$$I_0 \simeq \frac{4n_0q^2AE_0}{\pi m\nu_c}, \tag{24}$$

$$I_1 \simeq \frac{2n_0q^2AE}{\pi m\nu_c}, \tag{25}$$

and

$$I_s \simeq \frac{2n_0q^3\alpha a_0AE^2}{m^2\omega\nu_c^2} A_s. \tag{26}$$

The power P_s radiated by the sth harmonic current can be computed from

$$P_s = \tfrac{1}{2}I_s^2R_s, \tag{27}$$

where R_s is the radiation resistance for the sth harmonic frequency. If this harmonic power is normalized to the fundamental power P_1, a power conversion ratio can be defined as

$$\frac{P_s}{P_1} = \frac{I_s^2R_s}{I_1^2R_1} = \left[\frac{\pi\alpha qa_0E}{m\omega\nu_c}\right]^2 \frac{R_s}{R_1} A_s^2, \tag{28}$$

where R_1 is the resistance associated with the fundamental power.

This power conversion ratio can be put into a more compact form by first noting that the total number of electrons N_R produced during one RF cycle is

$$N_R = \int_A \int_{-l}^{l} \left[\int_0^{1/f} n\nu_i dt \right] dx dA = \frac{4\alpha qAEln_0a_0}{m\omega\nu_c}, \tag{29}$$

while the total number of electrons N_T in the discharge is given by

$$N_T = \int_A \int_{-l}^{l} n dx dA = \frac{4n_0Al}{\pi}. \tag{30}$$

Using the above expressions for N_R and N_T, the harmonic power conversion ratio can finally be expressed as

$$\frac{P_s}{P_1} = \left(\frac{R_s}{R_1}\right)\left(\frac{N_R}{N_T}\right)^2 A_s^2. \tag{31}$$

The above formula illustrates the importance of having a system in which the electrons can be generated and lost in times comparable to the RF period so that the ratio (N_R/N_T) is as large as possible.

VI. Experimental Investigation of Harmonic Power vs Bias Voltage

The harmonic power conversion ratio as given by (31) is in a form that is convenient to study experimentally. It is assumed that the discharge is maintained by the microwave energy and that the dc bias field does not perturb the discharge appreciably. Hence N_R and N_T are not expected to depend upon β in the range $0 \leq \beta \leq 1$ provided the bias voltage does not exceed the ionization potential of the gas. This makes it possible to study the harmonic power conversion ratio as a function of β or bias voltage, holding all other parameters of the system constant.

Eqs. (14) and (21) permit the calculation of A_s^2, which in turn is proportional to P_s/P_1 as a function of β. The results of this calculation are shown in Figs. 3–5, wherein the ratio has been normalized to one, for $S=2$, 3, 4, 5, 6, and 7.




Fig. 3—Harmonic power vs bias voltage.




Fig. 4—Harmonic power vs bias voltage.




Fig. 5—Harmonic power vs bias voltage.

The block diagram of Fig. 6 shows the experimental set-up. Here the first slotted line is used to insure that the tuned impedance of the discharge is at least close to an impedance match, while the second slotted line is used to measure the real part of the input impedance of the discharge, R_1, as introduced in (28).




Fig. 6—Block diagram of experimental set-up.

To experimentally observe this variation of harmonic power with bias voltage, a 60-cycle sweep voltage is connected directly to the two discharge posts and to the horizontal input of an oscilloscope so that the horizontal deflection of the oscilloscope trace is proportional to the bias voltage. The vertical input of the oscilloscope is fed by the output of a crystal detector used to monitor a selected harmonic power. Hence the vertical deflection of the oscilloscope trace is proportional to the harmonic power P_s. The oscilloscope traces in the top half of Figs. 3–5 show the results of this measurement made on a microwave discharge multiplier driven by an X-band signal. The input power level was in the range 20 to 40 watts CW at a frequency of 9 kMc.

Similar experiments were done using 25 watts of CW power at 35 kMc with almost identical curves being obtained for the second, third, and fourth harmonic power.

Both theory and experiment show that all even harmonic powers are zero at zero bias voltage ($\beta = 0$), while all odd harmonic powers are maximum. This assumes that both discharge posts are identical in size. If the two posts are not identical, electron diffusion to one post will exceed that to the other resulting in an "effective dc bias voltage" thereby permitting some even harmonic power to appear. It is believed that the results of Uenohara[4] on an S-band multiplier of similar geometry can be explained on the basis of this discharge post geometry effect since the two posts in his experiment were of different sizes.

VII. Absolute Value of Harmonic Power

To further investigate the harmonic power conversion ratio given in (31), the resistance ratio (R_s/R_1) and electron ratio (N_R/N_T) must be computed and/or measured.

It can be seen from (13) that the value of the ionization frequency averaged over an RF cycle can be related to (N_R/N_T) as follows:

$$\langle \nu_i \rangle = \frac{1}{2\pi} \int_0^{2\pi} \nu_i d\theta = \frac{q\alpha a_0 E}{2m\nu_c} = \frac{\omega}{2\pi} \left(\frac{N_R}{N_T} \right). \tag{32}$$

The value of $<\nu_i>$ can also be expressed as

$$\langle \nu_i \rangle = \zeta D E_m^2, \tag{33}$$

where ζ is the ac ionization coefficient,[5] D the diffusion constant, and E_m is the amplitude of the ac electric field. Thus if ζ is known for the gas used, the ratio (N_R/N_T) could be computed. Unfortunately, detailed data of this type is scarce, so it is desirable to look for another method of estimating the electron ratio.

Experimentally, N_T can be measured by applying a dc voltage $V_0 = 2lE_0$ to the discharge posts and observing the dc current given by (24). Combining (24) and (30), it is seen that

$$N_T = \frac{2ml^2\nu_c}{q^2} \left(\frac{I_0}{V_0} \right), \tag{34}$$

where all quantities on the right side of (34) are now known or measured.

Of the total power P dissipated in the microwave discharge, a certain amount (aP) will go into creating ionization. Thus, if ω is the RF angular frequency and V_i the average ionization potential for the gas, then the total number of electrons N_R produced during one RF cycle is given by

$$N_R = \frac{2\pi a P}{\omega V_i}. \tag{35}$$

As a typical example in using the above technique for determining the ratio of N_R/N_T, consider the 35 kMc gas discharge structure previously given in Fig. 2, wherein air is used for the gas. The gap spacing $2l$ in this structure is 0.010 inch, and the post diameter 0.025 inch, resulting in a gas volume of 8×10^{-5} cm^3. The input CW power P used was 25 watts; hence the power density was 300 kw/cm^3. The gas pressure was

[4] M. Uenohara, "A new high-power frequency multiplier," Proc. IRE, vol. 45, pp. 1419–1420; October, 1957.

[5] S. C. Brown, "Basic Data of Plasma Physics," John Wiley and Sons, Inc., New York, N. Y., 1959.

TABLE I

HARMONIC OUTPUT FROM 8.6-MM FREQUENCY MULTIPLIER

Harmonic Number s	β_{max}	$A_s^2(\beta_{max})$	R_1/Z_0	R_s/Z_0	N_R/N_T	Power Input (watts)	Theoretical Power (watts)	Measured Power (watts)
2	0.75	7.8×10^{-3}	0.25	0.5	0.2	25	15.5×10^{-3}	15×10^{-3}
3	0	0.57×10^{-3}	0.25	0.5	0.2	25	1.14×10^{-3}	1×10^{-3}
4	0.4	16×10^{-6}	0.25	0.5	0.2	25	32×10^{-6}	24×10^{-6}

TABLE II

HARMONIC OUTPUT FROM 3-CM FREQUENCY MULTIPLIER

Harmonic Number s	β_{max}	$A_s^2(\beta_{max})$	R_1/Z_0	R_s/Z_0	N_R/N_T	Power Input (watts)	Theoretical Power (watts)	Measured Power (watts)
2	0.75	7.8×10^{-3}	0.03	0.5	0.25	40	0.330	0.1
3	0	0.57×10^{-3}	0.03	0.5	0.25	40	24×10^{-3}	40×10^{-3}
4	0.4	16×10^{-6}	0.03	0.5	0.25	40	0.67×10^{-3}	1×10^{-3}
5	0	3.6×10^{-6}	0.03	0.5	0.25	40	0.15×10^{-3}	0.3×10^{-3}
6	0.25	0.58×10^{-6}	0.03	0.5	0.25	40	24×10^{-6}	—
7	0	0.196×10^{-6}	0.03	0.5	0.25	40	8.2×10^{-6}	—

adjusted to approximately 44 mm Hg so that the collision frequency ν_c was approximately equal to ω. The field strength was in the range 1 to 3 kv/cm. For these conditions, it is estimated[6] that the fraction a is of the order of $\frac{1}{3}$. Finally assuming an average ionization potential V_i for air of 14 electron volts, we compute the value of N_R to be 1.1×10^8. The measured value of N_T obtained from (34) was determined to be 5×10^8, giving the approximate ratio of N_R/N_T the value 0.2.

The radiation resistance R_r of a uniform filament of current of length c across the center of a rectangular waveguide of dimensions a and b has the value[7]

$$R_r = \frac{c^2}{ab} Z_0 \tag{36}$$

where Z_0 is the characteristic impedance of the guide. In the structure considered in this paper, the harmonic current on the discharge posts is not uniform but has a sinusoidal distribution. If the electrical length of the current filament exceeds 180°, as it will for high harmonics, destructive interference will result so that in general the effective length of posts is about equal to λ_s, the harmonic free-space wavelength. This nonuniform sinusoidal current distribution will reduce the value of R_r by a factor of two; hence the value of R_s appearing in (27) will be taken to be

$$R_s \simeq \frac{\lambda_s^2}{2ab} Z_0. \tag{37}$$

Using the above technique, Tables I and II for an 8.6-mm and a 3-cm frequency multiplier were compiled. The agreement between theoretically computed and experimentally measured harmonic power is considered satisfactory.

The R_1/Z_0 ratios tabulated in Tables I and II are determined from slotted line measurements taken directly at the input to the discharge device. The tuned VSWR is more commonly of the order of 2. It might be assumed that an impedance match would be desirable. However, this is not true if a stable discharge is to be maintained. Suppose an impedance match did exist. Next, suppose a slight reduction in average electron density occurs. This density reduction would necessarily cause a change in the RF impedance of the discharge and hence change the impedance match. This in turn would cause a power reflection with less power dissipated in the plasma, which would mean a further reduction in electron density and so on until the discharge disappears. Thus to sustain a discharge by microwave energy alone, some mismatch must occur, such that a reduction in plasma density improves the VSWR.

Most of the experiments performed with the multiplier used air as the gas. However, nitrogen, neon, argon, helium, xenon, and carbon dioxide were also used. As might be expected, a discharge in nitrogen was found to have almost the same behavior as a discharge in air. For other gases the input power level could not be maintained at the same value as that for air without the discharge expanding out of the gap region and into the waveguide. Hence for these cases the ratio N_R/N_T was less than that associated with air. However, when an external dc magnetic field was applied along the axis of the discharge posts to retard transverse diffusion of the plasma, the power conversion efficiency was improved to the point where argon, for example, could be made to yield superior results to air. Also, each different gas had to be used at the pressure necessary to make the collision frequency approximately equal to the drive frequency ω.

[6] S. C. Brown and W. P. Allis, "Basic Data of Electrical Discharges," Mass. Inst. Tech., Cambridge, Tech. Rept. No. 283, pp. 172–173; June 1958.

[7] J. C. Slater, "Microwave Transmission," McGraw-Hill Book Co., Inc., New York, N. Y., p. 288; 1942.

VIII. Frequency Mixing

The preceding analysis can readily be extended to include the process of frequency mixing by including a second field in (2).

Let the new applied electric field be of the form

$$E_T = E_0 + E_1\left[\cos \omega_1 t - \frac{\omega_1}{\nu_c}\sin \omega_1 t\right] + E_2\left[\cos \omega_2 t - \frac{\omega_2}{\nu_c}\sin \omega_2 t\right], \tag{38}$$

where $E_2 \ll E_1$, so that the discharge is maintained by means of the microwave power P_1 at angular frequency ω_1.

Corresponding to (4), the new linear solution to the momentum transfer equation for the drift velocity is

$$v_d(x, t) = \frac{q}{m\nu_c}\left[E_0 + E_1 \cos \omega_1 t + E_2 \cos \omega_2 t\right]. \tag{39}$$

Since it has been assumed that $E_2 \ll E_1$, the expression for $n(x, t)$ will essentially be the same as that determined previously in (15);

$$n(x, t) \simeq n_0\left[1 + \frac{\alpha q E_1}{m\omega_1\nu_c}\sum_{s=1}^{\infty}\frac{a_s}{s}\sin (s\omega_1 t)\right] \cdot \cos\left(\frac{\pi x}{2l}\right). \tag{40}$$

Following the same procedure used in obtaining (23), the new current I, flowing in the discharge posts, will contain sum and difference frequencies as indicated below:

$$I \simeq \frac{2n_0q^2A}{\pi m\nu_c}\left\{\left[2E_0 + E_1\cos \omega_1 t + E_2 \cos \omega_2 t\right] + \left[\frac{\pi q\alpha a_0 E_1^2}{m\omega_1\nu_c}\sum_{s=2}^{\infty}A_s \sin (s\omega_1 t)\right] + \frac{\alpha q E_1 E_2}{m\omega_1\nu_c}\left[\sum_{s=1}^{\infty}\frac{a_s}{2s}\left[\sin (s\omega_1 + \omega_2)t + \sin (s\omega_1 - \omega_2)t\right]\right]\right\}. \tag{41}$$

The current amplitude I_2 at frequency ω_2 is seen to be

$$I_2 = \frac{2n_0q^2AE_2}{\pi m\nu_c}, \tag{42}$$

while the current amplitude I_3 at the sum or difference freqency $\omega_3 = \omega_1 \pm \omega_2$ is

$$I_3 = \frac{n_0\alpha q^3 A E_1 E_2}{\pi m^2\nu_c^2\omega_1}a_1. \tag{43}$$

A mixer efficiency can now be defined as the ratio of the power output P_3 at frequency ω_3 to the power input P_2 at frequency ω_2; thereby we can obtain an expression similar to that given by (28).

$$\frac{P_3}{P_2} = \frac{I_3^2\Re_3}{I_2^2R_2} = \left(\frac{\alpha q a_1 E_1}{2m\omega_1\nu_c}\right)^2\left(\frac{\Re_3}{R_2}\right) = \left(\frac{\Re_3}{R_2}\right)\left(\frac{N_R}{N_T}\right)^2\left(\frac{a_1}{2\pi a_0}\right)^2; \tag{44}$$

In this ratio, $\Re_3$ is the interaction resistance at frequency ω_3, while R_2 is the resistance associated with frequency ω_2.

If $\omega_1 \simeq \omega_2$ and $\omega_3 = \omega_1 + \omega_2 \simeq 2\omega_1$, then $R_2 \simeq R_1$ and $\Re_3$ will be approximately equal to the interaction resistance of the second harmonic frequency considered in the frequency multiplier. In (21), for the case $s = 2$, a_1 will contribute the most to the value of A_2, so that


$$A_2 \simeq \frac{a_1}{2\pi a_0}. \tag{45}$$

Hence, for these conditions, the mixer conversion efficiency should be approximately the same as the second harmonic conversion efficiency. Also, the variation of P_3 with β should be similar to the variation of the second harmonic power. A comparison of the curves given in Figs. 3 and 7 shows this to be true.

To investigate experimentally the mixing properties of the plasma, the parallel-plate discharge-gap geometry was built into the crossed X-band structure shown in Fig. 8. This arrangement permits the introduction of: a 20-watt CW 9-kMc signal through one waveguide port; a sliding short tuning element in a second waveguide to adjust for maximum electron density modulation; a third waveguide containing a filter to block the 9-kMc signal but pass a 0.1-watt, 1-kc square wave modulated, 11-kMc mixing signal; and finally, a fourth waveguide which tapers down from the X-band waveguide to an RG 53/U K-band waveguide to pass the 20-kMc sum frequency. A 20-kMc band-pass filter was also included in the RG 53/U waveguide section to reject the 18-kMc, second harmonic of the 9-kMc drive frequency. This filter arrangement, plus the square wave modulation of the 11-kMc mixing frequency, makes certain that other frequencies in the system are not mistaken for the desired 20-kMc sum frequency.

The power P_3 as a function of β or bias voltage was observed by again applying a 60-cps sweep voltage to the discharge posts and to the horizontal input of an oscilloscope. The crystal detected, 20-kMc output power was fed to the vertical input of the oscilloscope to obtain the oscilloscope trace shown in the top of Fig. 7. The base line in this picture is caused by the square wave modulation of the 11-kMc signal which is not synchronized with the 60-cps sweep voltage.

A measurement of the 20-kMc sum frequency power






Fig. 7—Mixer output vs bias voltage.




Fig. 8—Gas discharge structure.

yielded a signal 28 db down from the 100-mw 11-kMc power. This conversion ratio to the sum frequency compares favorably to the value one could obtain with a crystal diode operating at the same frequencies. It is believed that if a different structural arrangement were made to observe the difference frequency rather than the sum frequency, this conversion loss could be substantially reduced especially if the difference frequency was placed at 60 Mc where $\mathcal{R}_3$ in (44) could be made quite large.

IX. Parametric Amplification

Modulation of the electron density at a microwave frequency implies that the discharge has time-varying properties which may be exploited in a parametric amplifier. It was seen in Section VIII on frequency mixing that the application of the low level, complex field

$$e_2 = E_2\left(1 + j\frac{\omega_2}{\nu_c}\right)\epsilon^{j\omega_2 t} \tag{46}$$

along with the high level pump field e_1 gave rise to a complex current,

$$i_3 = -jI_3\epsilon^{j\omega_3 t} = -j\frac{q^2N_R}{2lm\nu_c}\left(\frac{a_1}{2\pi a_0}\right)E_2\epsilon^{j\omega_3 t} \tag{47}$$

at the difference frequency $\omega_3 = \omega_1 - \omega_2$.

If the power P_3 radiated by the current i_3 is reflected back into the discharge, it will in turn produce an e_3 field to mix with the pump field e_1. This power relationship can be expressed as

$$P_3 = \tfrac{1}{2}\left|\, i_3\right|^2\mathcal{R}_3 = \tfrac{1}{2}\left|\, 2le_3\right|^2/R_3, \tag{48}$$

where $\mathcal{R}_3$ is the radiation resistance associated with the current i_3, while R_3 is the real part of the discharge impedance at frequency ω_3.

Eq. (48) will determine the magnitude of the field e_3, but not its phase. However, it will be assumed that the fields at ω_3 were reflected to make e_3 have the following complex form:

$$e_3 = E_3\left(1 + j\frac{\omega_3}{\nu_c}\right)\epsilon^{j\omega_3 t}. \tag{49}$$

This field e_3 will now combine with the pump field e_1 to produce a current Δi_2 at the signal frequency ω_2;

$$\Delta i_2 = -j\frac{q^2N_R}{2lm\nu_c}\left(\frac{a_1}{2\pi a_0}\right)E_3\epsilon^{j\omega_2 t}. \tag{50}$$

The original current i_2 produced by the field e_2 was given by (42). In complex form the expression is

$$i_2 = \frac{q^2N_T}{2lm\nu_c}E_2\epsilon^{j\omega_2 t}. \tag{51}$$

Since the discharge is a lossy element, further effects of Δi_2 will be neglected. Hence the power P_2 at the signal frequency is seen to be

$$P_2 \simeq \tfrac{1}{2}\,\mathrm{Re}\,(i_2 + \Delta i_2)(2le_2)^*$$
$$= \frac{q^2N_TE_2^2}{2m\nu_c}\left[1 - \frac{\omega_2}{\nu_c}\left(\frac{N_R}{N_T}\right)\left(\frac{E_3}{E_2}\right)\left(\frac{a_1}{2\pi a_0}\right)\right]. \tag{52}$$

The choice of the phase of e_3 in (49) is now apparent since it leads to the desired negative power term in (52). The first term in (52) is the power dissipated in the discharge at frequency ω_2.

In order to have gain in the device,

$$G = \frac{\omega_2}{\nu_c}\left(\frac{N_R}{N_T}\right)\left(\frac{E_3}{E_2}\right)\left(\frac{a_1}{2\pi a_0}\right) \tag{53}$$

must be greater than unity. This expression contains the unknown field ratio E_3/E_2.

To evaluate E_3/E_2, first note that the power dissipated in the discharge at frequency ω_2 can also be written as

$$\frac{q^2 N_T E_2^2}{2m\nu_c} = \frac{|2le_2|^2}{2R_2}, \tag{54}$$

where R_2 is the real part of the discharge impedance at ω_2.

Solving (54) for R_2, the result is

$$R_2 = \frac{4l^2 m\nu_c}{q^2 N_T}\left[1 + \left(\frac{\omega_2}{\nu_c}\right)^2\right]. \tag{55}$$

From (48), it can be shown that

$$\frac{E_3}{E_2} = \frac{q^2 N_R}{4l^2 m\nu_c}\left(\frac{a_1}{2\pi a_0}\right)\left[\frac{\Re_3 R_3}{1 + \left(\frac{\omega_3}{\nu_c}\right)^2}\right]^{1/2}. \tag{56}$$

Finally, the gain G expression becomes, with the use of R_2 from (55),

$$G = \frac{\omega_2}{\nu_c}\left(\frac{N_R}{N_T}\right)^2\left(\frac{a_1}{2\pi a_0}\right)^2\left(\frac{\Re_3 R_3}{R_2^2}\right)^{1/2} \cdot \frac{\left[1 + \left(\frac{\omega_2}{\nu_c}\right)^2\right]}{\left[1 + \left(\frac{\omega_3}{\nu_c}\right)^2\right]^{1/2}}. \tag{57}$$

This equation shows that it would be desirable to make the signal frequency ω_2 considerably greater than the collision frequency ν_c, indicating that the gas pressure should be reduced in order to make the discharge extremely reactive. This is analogous to the high Q or high "cutoff" frequency requirements for crystal diodes used as parametric amplifiers.

An important problem in the design of a possible gas discharge parametric amplifier would be achieving the desirable impedance levels to maximize the resistance ratio term in (57) while at the same time maintaining impedance matches in the microwave circuits.

Assuming that a parametric amplifier would operate in the manner described, it may have two interesting features: 1) the saturated power output could be high, perhaps the order of one watt and 2) the gain could be controlled by changing the bias voltage.

X. Conclusions

It is concluded that the nonlinear behavior of a microwave discharge located between two closely spaced parallel plates whose dimensions are small compared to the wavelength can be accurately analyzed using the assumption that the ionization frequency ν_i is proportional to the absolute value of the drift velocity v_d.

Using straightforward Fourier expansions for ν_i and the electron density $n(x, t)$, the momentum transfer and continuity equations can be solved readily for the current $J(x, t)$ response to applied microwave fields.

The discharge geometry and analysis has a somewhat universal aspect in that it can be applied with little change in form to frequency multipliers, frequency mixers, and parametric amplifiers.

Experimentally, CW power densities of the order of 0.3 Mw/cm^3 were obtained using 25 watts of 35-kMc power. Modulation of the electron density the order of 5 per cent at 70 kMc (twice the drive frequency) was believed to have been achieved.

The microwave gas discharge, with its relatively large CW and pulsed power capabilities, combined with its predictable performance at high harmonics, make it an attractive element for further study in the low millimeter wave region.

A Plasma Microwave Energy Detector*

R. L. TAYLOR† AND S. B. HERSKOVITZ†, MEMBER, IRE

Summary—**A detector of microwave energy employing a gaseous discharge is described. The principle of operation is based upon the temperature sensitivity of the electron-ion recombination rate. By photomultiplier observations of the decaying plasma afterglow, short pulses of microwave energy can be detected. At present, the minimum discernible signal strength is about one microwatt peak.**

The theory, experimental configuration, and prospects for improved sensitivity are discussed.

LARGELY overshadowed by space age and controlled fusion programs are the efforts of numerous researchers into the more prosaic area of electronic applications of the plasma state of matter. One such activity deals with the use of a gaseous discharge as the detection element in radar receivers.

The ability to detect minute amounts of microwave energy is the prime function of a radar system. To perform this task, a typical radar receiver employs an extremely sensitive semiconducting crystal rectifier as its sensing element. This very sensitivity, however, places a burden upon the user in the form of protecting the crystal rectifier from accidental exposure to incident energies of more than a few ergs. This exposure must be guarded against, not only when the rectifier is actually in operation in a radar receiver, but even while the element is being stored or transported.

For several years, various groups of investigators have explored the use of an ionized gas as a detector element to provide a means of minimizing this problem.[1–5] In this application an ionized gas possesses several noteworthy properties: namely, the element does not act as a detector until activated, and second, it can be exposed to megawatts of energy without permanent damage. These advantages, however, are not gained without a corresponding sacrifice in sensitivity.

Detectors which use ionized gases have usually been based upon changes in electrical conductivity. The detector to be described, however, is quite different from its predecessors in that it makes use of changes in the light output of a decaying plasma.

Light from a Decaying Plasma

The mechanisms involved with the emission of light from a gas during ionization and subsequent afterglow are numerous and form the subject of several phases of physics, *e.g.*, emission spectroscopy, quantum mechanics, metastable determination, etc. Of fundamental interest to the present discussion, however, is the alteration of the total light emitted from a gaseous afterglow, or decaying plasma, with the addition of microwave energy to the system.

In 1928, Kenty observed a quenching of certain spectral lines in an emission spectrum with the addition of dc energy.[6] That the light output of a gaseous afterglow could similarly be altered by microwave energy was first demonstrated and is being extensively investigated by the Goldstein group[7,8] at the University of Illinois.

If a gas is ionized by a pulse of electrical energy, a typical afterglow is observed upon removal of the pulse. The characteristic light output of a pure noble gas shows several interesting features. (See Fig. 1.) Initially, at time zero (the moment of removal of the ionizing pulse), an extremely high level of light output is observed which rapidly decreases to a minimum in perhaps 40 microseconds (μsec). The abscissa represents volts output of




Fig. 1—Light output from pulsed plasma.

* Received by the IRE, August 28, 1961.

† Air Force Cambridge Research Laboratories, Office of Aerospace Research, Electronics Research Dir., Laurence G. Hanscom Field, Bedford, Mass.

[1] D. H. White, "Microwave Detection with Gas Tubes," Fed. Telecommun. Labs., Nutley, N. J., Contract DA-36-039-SC-15512, Final Rept.; 1953.

[2] H. Farber, "Study of Microwave Detection in Gaseous Discharge Tubes," Polytech. Inst. Brooklyn, N. Y., Contract DA-36-039-SC-5670, Final Rept.; 1955.

[3] L. Gould, "Microwave Detection by a dc Gaseous Discharge," Signal Corps Engrg. Labs., Belmar, N. J., Tech. Memo No. M-1836; October, 1956.

[4] M. Mentzoni, "The Detection of Microwaves by Glow Discharges," Polytechnic Institute of Brooklyn, Brooklyn, N. Y., Contract AF 30(602)-1448; 1957.

[5] H. Farber and M. Mentzoni, "The Long Rise Times Associated with Gaseous Detection of Microwaves," Polytechnic Institute of Brooklyn, Brooklyn, N. Y., Contract AF 19(604)-4143; February, 1959.

[6] C. Kenty, "The Recombination of argon ions and electrons," *Phys. Rev.*, vol. 32, pp. 624–635; October, 1928.

[7] J. M. Anderson and L. Goldstein, "Interaction of Microwaves in Gaseous Discharge Plasmas," University of Illinois, Urbana, Contract AF 19(604)-524, Tech. Rept. No. 7; 1955.

[8] A. A. Dougal and L. Goldstein, "Energy between electrons and ion gases through coulomb collisions in plasmas," *Phys. Rev.*, vol. 109, pp. 615–624; February, 1958.

a photomultiplier viewing the total light output, and the ordinate time, in μsec. The next feature of note is a secondary build-up of light output to a maximum value at about 100 to 120 μsec. A monotonic decay of light which will be referred to as the afterglow period is then traced out. At the right, the initiation of another pulse and afterglow period occurs.

The initial intense light output is a result of energy loss by the many excited atoms. As electrons now rapidly lose energy through inelastic collision processes, fewer excited atoms are created and the light output falls. A condition is finally reached such that the electron temperature and density are appropriate for optimum electron-ion recombination. A second light output maximum is then observed. It is at this point, the inception of the characteristic afterglow, that the plasma performs as a microwave detector.

The effect of impinging microwave energy, such as a radar echo, on the afterglow luminosity is now considered. At sufficiently high frequencies, such as those commonly employed in radar systems, only the electrons, by virtue of their minute mass, are greatly affected by the alternating electric field of the radar echo. Thus incident electromagnetic energy acts almost exclusively as an energy source for the electrons in the gas. Fig. 2 represents this situation diagrammatically. The incident electromagnetic signal, represented by a circle at the center, supplies energy almost exclusively to the electrons of the plasma system. The electrons, in turn, through collisional processes, impart this energy to the ions, neutral species, and container walls.




Fig. 2—Energy distribution processes.

To postulate a simple working picture of the light-producing mechanisms germane to the detection application, the assumption is made that electron-ion recombination is the principal source of visible light emitted from the decaying discharge. This assumption ignores certain other conceivable emitting processes such as metastable decays, wall fluorescence, multibody collisions, etc. These omissions, however, do not materially alter the detection mechanism.

Despite this simplifying assumption, the electron-ion recombination phenomenon is unfortunately still beclouded by additional complexities. The recombination process may take numerous forms.[9] Certain of these are light producers; others are not. Since methods of independently determining the coefficients of various electron-ion recombination processes are rather fragmentary, the following discussion will deal with the "bulk" coefficient. This recombination coefficient, which is ordinarily measured, will be understood to be representative of the various independent light-producing mechanisms.

Many measurements of electron-ion recombination have been made.[10] The inconsistency of data from investigator to investigator leaves much to be desired. Notwithstanding the spread of experimental data, it can be stated that the recombination coefficient is a decreasing function of temperature. Representative of these values is the data of Chen, *et al.*, yielding an experimental temperature dependence of $T_e^{-3/2}$ for electron-ion recombination coefficient over a pressure range of 7–29 mm Hg in pure helium.[11] Thus, as electrons are heated, the recombination coefficient decreases. From assumptions above, this decrease also results in a lowering of the afterglow light output. This quenching of the afterglow forms the basis of the described detector.

Enhancement of Afterglow Quenching

To optimize the performance of a microwave energy detector based upon quenching of the afterglow, two general criteria must be considered: 1) the detector must be in a condition to efficiently convert incident energy, *e.g.*, a radar echo, into afterglow light quenching and 2) the incident signal must be delivered efficiently to the detector.

For optimum performance as a detector, loss of electrons by means other than recombination must be minimized. Diffusion losses can be suppressed by operation at higher gas pressures, the use of magnetic fields, and appropriate container geometry. Electron losses by attachment are eliminated by the use of noble or other gases with unfavorable attachment rates.

The remaining electron loss process, recombination, may be controlled, within bounds, to optimize the detector for specific application. The recombination rate, as previously mentioned, is a decreasing function of temperature. The rate of cooling of electrons can be affected by four parameters:

1) number density of neutral atoms (pressure),
2) collision probability,
3) mass of the neutral atom,
4) metastable atom concentration.

For a given electron density and incident signal, electrons with lower temperatures, hence greater recombination rate, will yield a greater quench in afterglow.

[9] L. B. Loeb, "Basic Processes of Gaseous Electronics," University of California Press, Berkeley, pp. 477–594; 1955.
[10] *Ibid.*, pp. 560–562.
[11] C. L. Chen, C. C. Leiby and L. Goldstein, "Electron temperature dependence of the recombination coefficient in pure helium," *Phys. Rev.*, vol. 121, pp. 1391–1400; March, 1961.

Rapid cooling of electrons can be achieved by using higher pressures of parent atoms with large collision cross sections and small atomic masses. Destruction of metastable states by the use of Penning mixtures[12] also accelerates cooling. Under these conditions, a high-sensitivity short-duration afterglow would be produced.

To extend the afterglow period, and hence increase the range of detection between pulses, it is desirable to cool the plasma electrons more slowly. This action is accompanied by a decrease in optimum sensitivity. In the particular experiments described, in order to prolong the interpulse period, electrons were cooled at a slower rate than that which would have yielded maximum sensitivity.

Techniques for insuring the efficient delivery of the incident signal to the detector are based upon common microwave techniques and physical electronics principles. Microwave techniques include such obvious expedients as maintaining low-loss transmission lines and power-multiplication approaches. Further techniques for enhancing the increase of electron energy due to an incident signal by cyclotron resonance will also enhance the detection abilities.[13,14]

Consideration of the above requirements, to a large extent, dictates the choice of parent gas and experimental configuration. Practical considerations, however, somewhat modify this idealized picture, and necessitate compromise.

Experimental Configuration

From the foregoing criteria, the general experimental configuration may be surmised. The choice of a rare gas as the parent medium is evident. For a compromise between maximum sensitivity and duration of afterglow, neon, with its moderate mass, low probability of collisions, and ease of ionization, was chosen as the parent gas. The gas is contained in a simple discharge tube, the diameter of the glass envelope being chosen so as to be as large as possible—for diffusion considerations—without imposing serious microwave mismatch problems.

The gas bottle is inserted into an *S*-band waveguide line. The plasma is established by a pulse of dc power, typically 1000 volts, and the light output monitored by a gated photomultiplier. A pulse of *S*-band energy is then introduced into the waveguide system to serve as a simulated radar echo. This simulated echo is monitored by use of a crystal probe in a slotted line. The entire system is synchronized by a master trigger generator and the output displayed on an oscilloscope. To permit variation of the gas fill, the detector tube is attached to a vacuum and gas back-fill system. Fig. 3 represents the experimental situation diagrammatically.




Fig. 3—Block diagram of plasma microwave detector.




Fig. 4—Block diagram of vacuum system.

The vacuum and gas back-fill system (see Fig. 4) is of conventional design, employing a three-stage oil diffusion pump capable of attaining vacua of 10^{-7} mm Hg. Of special interest is the use of a cataphoresis pump[15] in the form of a glass helix consisting of about 72 inches of $\frac{1}{2}$-inch outside-diameter tubing wound into 7 loops. This pump allows noble gases to be ultrapurified. A special wide-range thermocouple[16] is employed to measure gas pressures without the possibility of contamination from manometric fluids.

The plasma detector itself consists of a simple discharge tube $\frac{3}{4}$-inch outside diameter, with tungsten rod electrodes spaced about 12 inches apart. The detector is placed diagonally through the *H*-plane of a 2:1 tapered

[12] A mixture of gases in which the ionization potential of one constituent is below the metastable potential of the other. Thus, the metastable level is continuously destroyed by collisions between the two species.

[13] J. E. Etter and L. Goldstein, "Guided Wave Propagation in Gyromagnetic Gaseous Discharge Plasmas," University of Illinois, Urbana, Contract AF 19(604)-524, Tech. Rept. No. 3; 1954.

[14] L. P. McGrath, A. D. Chatterjee and J. P. Monier, "Further Studies of Resonance Phenomena at Microwave Frequencies in Gyromagnetic Gaseous Discharge Plasmas," University of Illinois, Urbana, Contract AF 19(604)-2152, Sci. Rept. No. 2; 1957.

[15] R. Riez and G. H. Dieke, "The analysis and purification of rare gases by means of electric discharges," *J. Appl. Phys.*, vol. 25, pp. 196–201; February, 1954.

[16] Consolidated Vacuum Corp. Autovac Vacuum Gauge Type LKB-3294. Ranges from 1 micron to 100 mm Hg.

section (see Fig. 5). In this configuration, the detector tube essentially fills the cross section of the microwave line. During detection the afterglow electron densities as measured by standard cavity techniques[17–19] are in the range of 1×10^{10} to 4×10^{10} electrons per cubic centimeter.

The most satisfactory performance of the plasma detector in respect to minimum detectable signal resulted from the use of pure neon gas in the pressure range of from 2 to 10 mm Hg.

In Fig. 6 the typical detection phenomenon is represented. The upper trace represents a 150-μsec portion of the light output from the decaying plasma contained within the gas tube. The photomultiplier is gated so as to protect it from the extremely high light output typical at the inception of the plasma (see Fig. 1), and thus prevents fatiguing of the photocathode. Light output is displayed as amplitude in arbitrary units on the vertical axis and time (50 μsec per major division) on the horizontal. In the lower curve, the quenching of light output due to a 5-μsec, 20-mw peak pulse at 3000 Mc is displayed.

Caution must be used in assigning a sensitivity figure to the plasma microwave detector. In semiconductor crystal detector nomenclature, sensitivity deals with a voltage output resulting from a given power input. The crystal is generally used to detect, rectify, and mix the incoming signal with the output of a local oscillator. The resultant IF frequency is then amplified, rectified, and reamplified before being measured. The plasma detector is not analogous to a crystal in this function. A crystal, however, can also be used directly to rectify microwave signals, the output being fed into a video amplifier. In this function, a closer comparison to the plasma detector may be made. The plasma detector acts essentially as an energy transducer, converting incident microwave energy into an alteration of light intensity. This function is so dissimilar to the function of a crystal detector that comparison of sensitivity by semiconductor crystal nomenclature is meaningless. More useful, therefore, is the specification of a minimum detectable signal, one which will produce an alteration of the light output curve by an amount equal to twice the value of the average noise, or thickness, of the light output curve. In this context, maximum sensitivities of the plasma detector are from 1 to 5 microwatts peak power.

Fig. 7 shows the effect of various signal strengths on the amount and character of the typical afterglow quench. Here input pulses vary from one to 128 mw in




Fig. 5—Plasma microwave detector. The diode detector is inserted into the H-plane of a tapered waveguide section. The cylindrical cavity to the right is used to determine electron densities.



Fig. 6—Typical detection phenomenon. *Upper portion*: Afterglow of 5-μsec duration pulsed discharge (1 kv, about 0.5 amp) in neon ($p=10$ mm Hg), 250 μsec after pulse. Time scale: 50 μsec per division. *Lower portion:* same discharge conditions as above. Quenching pulse is 5 μsec wide, 20 mw peak power. Photomultiplier gated RCA 6217.

[17] S. C. Brown and D. J. Rose, "Methods of measuring the properties of ionized gases at high frequencies. I—Measurements of Q," *J. Appl. Phys.*, vol. 23, pp. 711–718; July, 1952.

[18] S. C. Brown and D. J. Rose, "Methods of measuring the properties of ionized gases at high frequencies. II—Measurement of electric field," *J. Appl. Phys.*, vol. 23, pp. 719–722; July, 1952.

[19] D. J. Rose and S. C. Brown, "Methods of measuring the properties of ionized gases at high frequencies. III—Measurement of discharge admittance and electron density," *J. Appl. Phys.*, vol. 23, pp. 1028–1032; September, 1953.




Fig. 7—Variation of quench with signal strength. Input pulses of 5-μsec duration varying from 1 to 128 mw in 3-db steps. Time scale: 20 μsec per division. Discharge conditions identical to those of Fig. 6.




Fig. 8—Ionization due to large input signal. Input pulse of 5-μsec duration, 500-mw peak power. Time scale: 20 μsec per division. Discharge conditions identical to those of Fig. 6.




Fig. 9—Multiple pulse response. *Upper portion:* input pulses of 5-μsec duration, 20-mw peak power. *Lower portion:* input pulses of 5-μsec duration, 90 mw followed by 20-mw peak power. Discharge conditions identical to those of Fig. 6.

3-db steps. The stronger signals produce more profound alterations of the light output but also prolong the "recovery time," or interval before normal light output is resumed. Each major division on the horizontal scale represents 20 μsec.

By continuously increasing the microwave signal strength, a point is reached where energy input is sufficient to cause further ionization in a manner similar to the plasma originating pulse. Fig. 8 illustrates this effect with an input pulse of 500 mw. On the lower trace, an initial small decrease of light, followed by a building up to an increased value and subsequent decay is seen.

In Fig. 9, the effects of multiple input pulses are illustrated. In the upper portion, two pulses of 20 mw each cause similar decreases in light output. In the lower portion, an input signal of 90 mw followed by a signal of 20 mw results in quenches of different magnitude. It is readily apparent that the plasma detector is not a square law device.

A typical response curve of input power to light quenching in arbitrary units is illustrated in Fig. 10.

The plasma detector is inherently a broad-band device. The unit employed in these experiments operates over the entire usable range of *S*-band (2.84″×1.34″) waveguide. Fig. 11 depicts the frequency response of a typical 10-mm neon gas fill. Curves are plotted for




Fig. 10—Light output alteration as a function of input signal level.




Fig. 11—Frequency response of plasma microwave detector.

three power inputs; 20, 5, and 1 mw peak. The fine structure, particularly evident in the 20-mw curve, is related to the standing wave ratio of the microwave line. At points of poorer matching (*i.e.*, at 3000 and 3400 Mc), the incident power upon the detector is diminished, with a consequent lowering of the amount of light quenching.

The Future of the Plasma Detector

The plasma microwave detector, as it exists today, does not rival the crystal rectifier as an envelope detector. A standard crystal rectifier can detect signals with strengths in the order of 10^{-8} watts. In the present state of development, the plasma detector under optimum conditions can respond to about 10^{-6} watts of incident energy. A crystal semiconductor used as a mixer can detect microwave signals as small as 10^{-13} watts. The plasma microwave detector has not been investigated for any mixing properties.

There are, however, several approaches available to improve the present minimum detectable signal level. An obvious method of increasing the plasma detector sensitivity is to employ a dc magnetic field so as to cause the plasma electrons to execute cyclotron motion. In this condition, the electrons are more efficient absorbers of microwave energy at particular microwave frequencies, and will produce more profound quenching of light output. The relationship of magnetic field to applied microwave frequency may be related simply by $B=0.357f$, where B is the magnetic field in Gauss and f is the applied microwave frequency in Mc per second. Thus, to produce maximum signal enhancement at 3000 Mc, a 1070-Gauss magnetic field would be employed. Such operation will narrow the bandwidth of the device.

Practical difficulties may prevent full utilization of the advantages expected from operation at cyclotron resonance. These difficulties concern the compromise necessary in optimum gas pressure to satisfy the conflicting requirements of minimizing pressuring broadening effects on cyclotron resonance, maintaining a stable discharge, and minimizing unwanted electron loss through diffusion. The magnetic field required for cyclotron resonance, however, yields the advantage of restraining electron diffusion.

Methods to enhance or multiply the incident microwave signal offer other sensitivity increasing techniques. The use of "squeezed" waveguide sections, resonant cavities, and similar structures effectively multiplies the incident power density upon the detector. These manipulations also narrow the bandwidth of operation.

Finally, it should be remembered that we can measure only what we can see. The present method of display, presentation, and observation leaves much to be desired as far as determining the ultimate sensitivity of this device.

Interaction of a Modulated Electron Beam with a Plasma*

G. D. BOYD†, member, ire, R. W. GOULD‡, member, ire, and L. M. FIELD||, fellow, ire

Summary—**The results of a theoretical and experimental investigation of the high-frequency interaction of an electron beam with a plasma are reported. An electron beam, modulated at a microwave frequency, passes through a uniform region of a mercury arc discharge after which it is demodulated. Exponentially growing wave amplification along the electron beam was experimentally observed for the first time at a microwave frequency equal to the plasma frequency. Approximate theories of the effects of 1) plasma-electron collision frequencies, 2) plasma-electron thermal velocities and 3) finite beam diameter, are given.**

In a second experiment the interaction between a modulated electron beam and a slow electrostatic wave on a plasma column has been studied. A strong interaction occurs when the velocity of the electron beam is approximately equal to the velocity of the wave and the interaction is essentially the same as that which occurs in traveling-wave amplifiers, except that here the plasma colum replaces the usual helical slow-wave circuit. The theory predicting rates of growth is presented and compared with the experimental results.

* Received by the IRE, August 7, 1961. This work was supported by the Office of Naval Research, Contract NONR 220(13).

† Bell Telephone Labs., Inc., Murray Hill, N. J.
‡ California Inst. of Tech., Pasadena, Calif.
|| Microwave Tube Div., Hughes Aircraft Co., Culver City, Calif.

I. Introduction

In 1929 Tonks and Langmuir[1] reported on experiments involving electron-plasma oscillations and defined the electron-plasma oscillation frequency

$$\omega_p^2 = \frac{n_0 e^2}{m\epsilon_0} \tag{1}$$

where e is the magnitude of the electronic charge, m its mass, n_0 the density of plasma electrons per unit volume, and ϵ_0 the permittivity of free space. (MKS units are used throughout this paper.)

When the electron thermal velocities are small compared to the velocity of waves being considered, the plasma can be characterized by a dielectric constant

$$\frac{\epsilon}{\epsilon_0} = 1 - \frac{\omega_p^2}{\omega(\omega - i\nu)}, \tag{2}$$

where ω is the angular signal frequency and ν is an effective collision frequency for the plasma electrons. For the experiments described in this paper the effect of the massive positive ions may be neglected.

In 1948 Haeff[2] suggested that plasma oscillations excited by a directed beam of charged particles might be responsible for certain types of RF energy received from the sun, and he discussed the mechanism of two-stream amplification. Bohm and Gross[3] have given a more extensive discussion of the interaction of an electron beam and a thermal plasma. Complex propagation constants were found for waves whose frequency is approximately equal to the plasma frequency defined in (1). The significance of the complex propagation constant is that small disturbances are amplified as the beam drifts through the plasma. In an earlier paper Pierce[4] had noticed a similar instability when an electron beam passed through a positive ion cloud and had attempted to relate this to positive ion oscillations observed in vacuum tubes. These discoveries have stimulated a very great amount of theoretical study of instabilities in plasmas with non-Maxwellian velocity distribution. The amplification mechanism, however, is essentially that of the double-stream amplifier invented by Haeff[5] and independently by Pierce and Hebenstreit.[6] In the case of the plasma, one group of charged particles is stationary.

Several experiments have been performed in which directed electron beams are passed through the plasma region of a gas discharge. Looney and Brown's[7] early experiment is representative. A beam of high-energy electrons (several hundred volts) was injected into the plasma of a dc discharge from an auxiliary electron gun. RF signals were detected by a small wire probe placed in the beam. The probe was movable and showed the existence of standing-wave patterns of oscillatory energy. Nodes of the pattern coincided with electrodes which bound the plasma. The thickness of the ion sheaths at these electrodes determined the standing-wave pattern. The frequencies of oscillation seemed to be related to the transit time effects of the electrons between the sheaths and did not appear to verify the theory of Bohm and Gross.[3] Later Gordon[8] investigated the energy exchange mechanism which was involved and showed that the results of Looney and Brown might be understood in terms of reflex klystron oscillations due to the electron beam being reflected by the sheaths. He found that the radiation detected by the probe was due to the fields of the bunched beam and not primarily due to plasma oscillations. Wehner[9] had previously built a plasma oscillator using this klystron bunching principle.

Very recently Kofoid[10] found oscillations very similar to those of Looney and Brown when two oppositely directed electron beams were passed through the plasma. This result tends to support Gordon's conclusion.

The dispersion equation for small amplitude waves in a system consisting of a beam and a collisionless plasma has been derived by a number of investigators.

$$1 = \frac{\omega_p^2}{\omega^2} + \frac{\omega_b^2}{(\omega - \gamma v_b)^2} \tag{3}$$

where ω_p is the plasma frequency of the plasma, ω_b is the plasma frequency of the beam, and v_b is the drift velocity of the beam. A number of simplifying assumptions have been made in obtaining this result:

1) Only small sinusoidal waves have been considered.
2) The electric vector and the direction of propagation of waves have been taken parallel to the direction of the beam (longitudinal waves).
3) All quantities were independent of the coordinates

[1] L. Tonks and I. Langmuir, "Oscillations in ionized gases," *Phys. Rev.*, vol. 33, pp. 195, 990; 1929.
[2] A. V. Haeff, "Space-charge wave amplification effects," *Phys. Rev.*, vol. 74, pp. 1532–1533; 1948. Also, "On the origin of solar radio noise," *Phys. Rev.*, vol. 75, pp. 1546–1551; 1949.
[3] D. Bohm and E. P. Gross, "Theory of plasma oscillations. A. Origin of medium-like behavior," *Phys. Rev.*, vol. 75, pp. 1851–1864; 1949. Also, "Theory of plasma oscillations. B. Excitation and damping of oscillations," *Phys. Rev.*, vol. 75, pp. 1864–1876; 1949. Also, "Effects of plasma boundaries in plasma oscillations," *Phys. Rev.*, vol. 79, pp. 992–1001; 1950.
[4] J. R. Pierce, "Possible fluctuations in electron streams due to ions," *J. Appl. Phys.*, vol. 19, pp. 231–236; 1948.
[5] A. V. Haeff, "The electron-wave tube," Proc. IRE, vol. 37, pp. 4–10; January, 1949.
[6] J. R. Pierce and W. B. Hebenstreit, "New type of high-frequency amplifier," *Bell Sys. Tech. J.*, vol. 28, pp. 33–51; 1949.
[7] D. H. Looney and S. C. Brown, "The excitation of plasma oscillations," *Phys. Rev.*, vol. 93, pp. 965–969; 1954.
[8] E. I. Gordon, "Plasma Oscillations, Interactions of Electron Beams with Gas Discharge Plasmas," Ph.D. dissertation, Mass. Inst. Tech., Cambridge; 1957.
[9] G. Wehner, "Plasma oscillator," *J. Appl. Phys.*, vol. 21, pp. 62–63; 1950.
[10] M. J. Kofoid, "Experimental two-beam excitation of electron oscillations in a plasma without sheaths," *Phys. Rev. Lett.*, vol. 4, pp. 556–557; 1960.

perpendicular to the direction of the beam and the effective beam boundaries were neglected; *i.e.*, the problem was considered one-dimensional.

4) Thermal velocities and collisions of the plasma electrons were neglected.
5) The plasma and the beam were assumed spatially uniform.

One may interpret this dispersion relation as giving either the propagation constant γ of waves whose frequency is ω, or the frequency of oscillation of disturbances whose wave number is γ. It is the former interpretation which we employ in this paper.

In the absence of a secondary electron beam or alternative feedback path, we expected the system of an electron beam interacting with a plasma over a finite length to be inherently stable; that is, we did not expect spontaneous oscillations.[11] On the other hand, small perturbations in current (shot noise) or velocity of the incoming electron beam or fluctuations arising in the plasma would increase in amplitude along the electron beam. In the first[12] of the two experiments described below (Fig. 1) we deliberately introduced a modulation of the electron beam at a microwave frequency and observed the amount by which this modulation was increased after having passed through the plasma. This experiment verified some of the early predictions. Kharchenko, *et al.*,[13] examined the modulation of the beam as it emerged from the plasma when no microwave modulation had been applied initially. They found a noise modulation whose frequency spectrum was sharply peaked at the plasma frequency, presumably due to the selective amplification of wide band fluctuation noise. Finally, Bogdanov,[14] and very recently, Allen and Kino,[15] repeated our first experiment with a longitudinal magnetic field and observed several interesting new effects.

During the course of the first experiment it was shown[16] that a cylindrical plasma column was capable of supporting electrostatic waves whose velocity could be made slow compared with the velocity of light. This suggested the second experiment[17] described below (Fig. 4) in which traveling-wave interaction occurred between such a slow wave and an electron beam which passed down the axis of the plasma at a velocity about equal to the wave velocity.

II. Interaction at Plasma Resonance

The first experiment utilized devices of the type shown in Fig. 1. An electron beam was modulated by a short helix, passed along the axis of the plasma column, and then upon emerging was demodulated by a second helix. The plasma density could be varied by changing the arc current, and strong amplification was found to occur[12] only when the plasma frequency was very close to the modulation frequency.




Fig. 1—Helix modulation experiment.

A. The Effect of Thermal Velocities of the Plasma Electrons—One-Dimensional Theory

Bohm and Gross[3] have derived the dispersion equation, including the effect of the thermal distribution of velocities of the plasma electrons, for a broad electron beam passing through a stationary plasma. The effect of short-range collisions of the plasma electrons may also be included in an approximate manner through the introduction of a velocity-independent collision frequency[18] ν. We now give a discussion of the solutions of this equation for the conditions of our first experiment.

All waves were assumed to have exponential spatial and time dependence $e^{i(\omega t-\gamma z)}$, where $\gamma=\beta-i\alpha$ was the complex propagation constant and α and β were both real. A beam plasma frequency was defined in terms of the beam electron density n_b by $\omega_b^2=n_b e^2/m\epsilon_0$. The thermal distribution of velocities of the electron beam about their mean velocity v_b was neglected since their

[11] P. A. Sturrock, "Excitation of plasma oscillations," *Phys. Rev.*, vol. 117, pp. 1426–1429; 1960.

[12] G. D. Boyd, L. M. Field, and R. W. Gould, "Excitation of plasma oscillations and growing plasma waves," *Phys. Rev.*, vol. 109, pp. 1393–1394; 1958. (This article contains a preliminary account of the first experiment described here.)

[13] I. F. Kharchenko, *et al.*, "Experimental and theoretical investigation of the interaction of an electron beam with a plasma," *Proc. Conf. on Ion Phenomena in Gases*, Uppsala, Sweden, vol. II, pp. 671–680; 1959.

[14] E. V. Bogdanov, V. J. Kislov, and Z. S. Tchernov, "Interaction between an electron stream and a plasma," *Proc. Symp. on Millimeter Waves*, Polytechnic Inst. of Brooklyn, N. Y., vol. 9, pp. 57–71; April, 1959.

[15] M. A. Allen and G. S. Kino, "Interaction of an electron beam with a fully ionized plasma," *Phys. Rev. Lett.*, vol. 6, pp. 163–165; 1961.

[16] A. W. Trivelpiece, "Slow Wave Propagation in Plasma Waveguides," Ph.D. dissertation, Calif. Inst. Tech., Pasadena; 1958. Also, A. W. Trivelpiece and R. W. Gould, "Space charge waves in cylindrical plasma columnes," *J. Appl. Phys.*, vol. 30, pp. 1784–1793; 1959. Also, "Electro-mechanical modes in plasma waveguides," *Proc. IEE*, vol. 105, pt. B, pp. 516–519; 1958.

[17] G. D. Boyd and R. W. Gould, "Travelling wave interaction in plasmas," *J. Nuclear Energy*, vol. 2, pt. C, pp. 88–89; 1961. (This article contains a preliminary account of the second experiment described here.)

[18] R. W. Gould, "Plasma Oscillations and Radio Noise from the Disturbed Sun," Calif. Inst. of Tech., Pasadena, Calif., Tech. Rept. 4, Contract NONR 220 (13); September, 1955.

random energy of approximately 0.1 ev was small compared to the random energy of 4.7 ev of the plasma electrons.

With these definitions the one-dimensional dispersion relation may be written

$$1 = \omega_p^2 \frac{(\omega - i\nu)}{\omega} \int_u \frac{f_0(u)du}{(\omega - \gamma u_z - i\nu)^2} + \frac{\omega_b^2}{(\omega - \gamma v_b)^2}, \quad (4)$$

where $f_0(u)$ was the normalized unperturbed distribution function of velocities of the plasma electrons and $du = du_x du_y du_z$. We assumed a Maxwellian velocity distribution

$$f_0(u) = \left(\frac{m}{2\pi kT}\right)^{3/2} \exp\left\{-\frac{m}{2kT}(u_x^2 + u_y^2 + u_z^2)\right\}, \quad (5)$$

where T is the equivalent "temperature" of the plasma electrons, and u is their random velocity vector.

The integral which resulted when (5) was substituted into (4) may be expressed in terms of the error function of complex argument. A large-argument asymptotic expansion of this function was easily obtained by expanding the denominator of the integral in (4) in powers of $\gamma u_z/(\omega - i\nu)$ and integrating term by term. The dispersion relation became

$$1 = \frac{(\omega_p/\omega)^2}{1 - i\frac{\nu}{\omega}}\left\{1 + \frac{\Gamma^2}{R\left(1 - i\frac{\nu}{\omega}\right)^2} + \frac{5}{3}\frac{\Gamma^4}{R^2\left(1 - i\frac{\nu}{\omega}\right)^4} + \cdots\right\} + \frac{(\omega_b/\omega)^2}{(\Gamma - 1)^2}, \quad (6)$$

where

$$R = \frac{mu_b^2}{3kT}. \quad (7)$$

is the ratio of the beam energy to the mean energy of a plasma electron and

$$\Gamma = \frac{\gamma v_b}{\omega} \quad (8)$$

is a normalized propagation constant. For the first experiment $R \approx 100$ and $|\Gamma| \approx 1$.

Neglecting collisions, there was a range of frequencies for which Γ was complex and a range for which it was real. Since $R \gg 1$, only the first two terms of the above series were considered. Eq. (6) then reduced to

$$(\Gamma - 1)^2(\Gamma^2 + \Lambda) + \sigma = 0, \quad (9)$$

where

$$\sigma = R\left(\frac{\omega_b}{\omega_p}\right)^2, \qquad \Lambda = R\left(1 - \frac{\omega^2}{\omega_p^2}\right) \quad (10)$$

Fig. 2 shows the locus of the roots of this equation in the complex Γ plane with Λ and σ as parameters. The growth constant is $-\alpha = (\omega/v_b)$ Im Γ. Alternatively, the gain is -8.68α db per cm, if α has units cm^{-1}. For a growing wave α is negative. This figure reveals that the maximum growth rate α occurs when the frequency ω is within a few per cent of the plasma frequency, provided $0.003 \leq \sigma \leq 3.0$ and $R \geq 30$. Thus maximum interaction occurs close to plasma resonance. In Fig. 3 we plot the normalized growth rate vs ω_p^2/ω^2 for representative beam energies (R) and beam densities (ω_b^2/ω_p^2).




Fig. 2—Solution of (9) for the complex propagation constant

$$\Gamma = \frac{\gamma v_b}{\omega} = \frac{\beta v_b}{\omega} - i\frac{\alpha v_b}{\omega}$$

over a range of values of the parameters σ and Λ.




Fig. 3—Growth parameter $-\alpha$ vs the normalized plasma frequency squared. R is the ratio of the electron-beam energy to the average random energy of the plasma electrons. ω_b^2/ω_p^2 is the ratio of the beam-electron density to the plasma-electron density.

The effect of collisions is to reduce the growth rate, and it is convenient to evaluate this effect when $\omega = \omega_p$ ($\Lambda = 0$) since this is the condition for maximum growth rate (approximately). If it is also assumed that collisions are infrequent ($\nu \ll \omega$), (6) may be written as

$$\Gamma = 1 + i\sqrt{\frac{\sigma}{\Gamma^2 + iR\frac{\nu}{\omega}}}. \quad (11)$$

This equation is easily solved by iteration, taking Γ^2 equal to unity on the right-hand side as the first step. (Results are given in Tables I and II of Sections V and VI.)

B. The Effect of Finite Electron-Beam Diameter

In the Appendix we derive the dispersion equation for waves which can exist upon an electron beam of radius b passing through an infinite plasma. Thermal velocities and collisions of the plasma electrons are neglected. It is shown that the effect of the finite beam diameter is to introduce a beam-plasma reduction factor into (3), so that it can be written as

$$1 = \frac{\omega_p^2}{\omega^2} + \frac{(\omega_b')^2}{(\omega - \gamma v_b)^2} \tag{12}$$

where

$$\left(\frac{\omega_b'}{\omega_b}\right)^2 = \frac{1}{1 + \dfrac{I_0(\gamma b)K_1(\gamma b)}{I_1(\gamma b)K_0(\gamma b)}} . \tag{13}$$

In the thin beam limit ($\gamma b \to 0$), the above becomes

$$\left(\frac{\omega_b'}{\omega_b}\right)^2 \simeq \frac{1}{2}(\gamma b)^2(0.11593 - \ln \gamma b) \qquad \gamma b \ll 1, \tag{14}$$

which is similar to that obtained by Sturrock.[11]

We note from (13) that, if γ is real, the effect of finite beam size is simply to reduce the effective beam density and hence the rate of growth. When the growth per wavelength is small ($-\alpha \ll \beta$), it is sufficient to evaluate (13) by setting $\gamma = \omega/v_b$. Fig. 3 shows that this is not always a good approximation, and a complete discussion of the solutions of (12) and (13) has not been given. The solutions of the corresponding dispersion equation which results when the beam and plasma are subjected to a very strong axial magnetic field is given in Bogdanov, *et al.*[14]

III. Slow-Wave Interaction

During the course of the first experiment (Fig. 1), an interaction of the electron beam with the plasma was obtained when the plasma frequency was several times the modulation frequency imposed on the beam.

In this case the electron beam interacts with one of the slow space-charge waves which propagates along the plasma column. These propagating waves are electromechanical in nature and result from the interplay of kinetic energy of the plasma electrons and the energy stored in the electric field. In the special case of no axial magnetic field these waves are surface waves. They have been studied in detail by Trivelpiece and Gould.[16] Synchronism between an electron beam and such a slow wave results in familiar traveling-wave interaction. (See Pierce and Field[19] for a physical description of traveling-wave interaction.)

The second experiment described in this paper was designed to investigate more completely this traveling-wave interaction. A different configuration, shown in Fig. 4, was employed. In order to enhance the traveling-wave interaction, the diameter of the plasma column was made smaller than in the first experiment, and the electron-beam diameter was made larger. Modulation and demodulation of the electron beam was accomplished with cavity resonators (at a fixed frequency) so as to allow a variable beam velocity.




Fig. 4—Cavity-modulation experiment.

A. Slow-Wave Mode of Propagation

We now give a short theoretical discussion of the electrostatic waves which propagate along a nondrifting plasma column of radius a which fills a glass tube whose outer radius is c. Two cases will be considered: 1) a perfectly-conducting surface at radius c, and 2) the glass tube in free space. Thermal velocities and collisions of the plasma electrons will be neglected.

The electric fields of these modes are derivable from a potential if their phase velocity is small compared to the velocity of light.[16] In this approximation the potential satisfies the Laplace equation. First let there be a conducting surface at radius c. Field are assumed to vary as $e^{i(\omega t - n\theta - \beta z)}$. In the absence of the electron beam and neglecting collisions, the propagation constant is real, so β is used for the propagation constant instead of $\gamma(\alpha = 0)$.

The time-varying potential in each region is given by

$$\phi_1 = \frac{I_n(\beta r)}{I_n(\beta a)} e^{i(\omega t - n\theta - \beta z)} \qquad r \leq a$$

$$\phi_1 = \frac{I_n(\beta r)K_n(\beta c) - I_n(\beta c)K_n(\beta r)}{I_n(\beta a)K_n(\beta c) - I_n(\beta c)K_n(\beta a)} e^{i(\omega t - n\theta - \beta z)}$$

$$a \leq r \leq c. \tag{15}$$

Matching tangential electric field and normal displacement at $r = a$, and using (2) for the plasma dielectric permittivity and κ as the relative dielectric constant of the glass, one obtains the dispersion equation

$$\left(1 - \frac{\omega_p^2}{\omega^2}\right)\frac{1}{\kappa} = \frac{I_n(\beta a)}{I_n'(\beta a)}\left\{\frac{I_n'(\beta a)K_n(\beta c) - I_n(\beta c)K_n'(\beta a)}{I_n(\beta a)K_n(\beta c) - I_n(\beta c)K_n(\beta a)}\right\}, \tag{16}$$

where the primes denote derivatives of the Bessel functions with respect to the argument. In the limit of

[19] J. R. Pierce and L. M. Field, "Traveling-wave tubes," Proc. IRE, vol. 35, pp. 108–111; February, 1947.

large βa the asymptotic frequency of propagation is

$$\frac{\omega}{\omega_p} = \frac{1}{\sqrt{1+\kappa}}. \tag{17}$$

The solution of this equation for the circularly symmetrical mode ($n=0$) is shown in Fig. 5 by the lower dashed curve, where we plot ω/ω_p vs βa. The phase and group velocities are given by ω/β and $\partial\omega/\partial\beta$, respectively. Angular dependent modes are not of particular interest in the second experiment since their fields vanish on the axis where the electron beam passes and, in addition, the excitation cavities are cylindrically symmetric.




Fig. 5—Frequency vs propagation constant βa for the surface-wave mode of propagation on a plasma-glass column in free space (solid curve), and when covered with a conducting surface (dashed curve). In the latter case, the upper dashed curve represents the $n=1$ mode, and the lower dashed curve represents the $n=0$ mode. The ○, ● and △ correspond to measurements on the plasma-glass column in free space, and should lie on the theoretical solid curve. The × data was obtained with the glass coated with a conducting layer, and such points should lie on the lower dashed curve.

Where the glass tube is in free space rather than being surrounded by a metallic conductor, expressions for the potential in three separate regions—1) plasma $r \leq a$, 2) glass $a \leq r \leq c$, 3) free space $c \leq r < \infty$—must be joined so that the tangential field and normal displacement are continuous. This leads to a dispersion equation for the circularly symmetric mode ($n=0$)

$$\left(1 - \frac{\omega_p^2}{\omega^2}\right)\frac{I_1(\beta a)}{I_0(\beta a)} = \frac{-\kappa}{be\coth(\beta c, \beta a)} \cdot \frac{\kappa + \dfrac{K_1(\beta c)}{K_0(\beta c)}\dfrac{1}{be\tanh(\beta c, \beta a)}}{\kappa + \dfrac{K_1(\beta c)}{K_0(\beta c)}Be\tanh(\beta c, \beta a)}, \tag{18}$$

where the functions

$$be\coth(\beta c, \beta a) = \frac{I_1(\beta c)K_0(\beta a) + I_0(\beta a)K_1(\beta c)}{I_1(\beta c)K_1(\beta a) - I_1(\beta a)K_1(\beta c)}$$

$$be\tanh(\beta c, \beta a) = \frac{I_1(\beta c)K_1(\beta a) - I_1(\beta a)K_1(\beta c)}{I_0(\beta c)K_1(\beta a) + I_1(\beta a)K_0(\beta c)}$$

$$Be\tanh(\beta c, \beta a) = \frac{I_0(\beta c)K_0(\beta a) - I_0(\beta a)K_0(\beta c)}{I_1(\beta c)K_0(\beta a) + I_0(\beta a)K_1(\beta c)} \tag{19}$$

are defined and tabulated by Birdsall.[20] Solution of this equation is depicted by the solid line in Fig. 5. The horizontal line in Fig. 5 at $\omega/\omega_p = 1$ corresponds to plasma oscillations which are independent of the wavelength of the disturbance.

The vertical lines labeled 800, 400, 200, and 100 volts correspond to constant phase velocity lines when the frequency is fixed and the plasma density is varied. The intersection of these curves with any of the propagation constant curves specifies the operating point at which the electron beam velocity is synchronous with the phase velocity of the surface wave.

B. Interaction Impedance

An electron beam traveling in synchronism with the slow surface wave will interact with the axial electric field of the wave. Under these conditions a spatially growing wave will result (the propagation constant becomes complex), so that the RF energy traveling along the plasma column increases with distance. This energy is supplied by the conversion of the beam kinetic energy.

Pierce[21] has shown that an approximate value of the growth constant in a traveling-wave amplifier can be expressed in terms of an *interaction impedance*, which is proportional to the square of the axial electric field at the position of the beam per unit power flow in the slow wave. Calculations[22] of this impedance for the circularly symmetric mode of the plasma-glass column in free space (ω-β diagram is given by the solid curve of Fig. 5) are approimately 800 ohms in the range $0.5 < \beta a < 1.5$.

IV. Characteristics of the Plasma and the Electron Beam

A. Mercury Arc Discharge

The positive column of an arc discharge in mercury vapor was the plasma. The mercury gas pressure was regulated by maintaining the temperature of the mercury "well" at 300 ± 0.1°K. The vapor pressure at this temperature was 2.1×10^{-3} mm Hg (2.1 microns), and the density of mercury atoms was 6.8×10^{13} per cm^3. The electron density n_0, corresponding to an electron plasma frequency of 3000 Mc, was 1.12×10^{11} per cm^3. The random energy of the plasma electrons was characterized by an equivalent temperature T_e. Measurements of T_e by Langmuir probes gave $T_e = 35{,}000$°K, or 4.7 electron volts. The energy corresponding to the axial drift velocity which is necessary to carry the discharge current was about 0.2 ev and was therefore small compared with the random energy. The collision

[20] C. K. Birdsall, "Memorandum for File ETL-12," Hughes Aircraft Co., Malibu, Calif.; July 1, 1953.

[21] J. R. Pierce, "Traveling Wave Tubes," D. Van Nostrand Co., New York, N. Y.; 1950.

[22] G. D. Boyd, "Experiments on the Interaction of a Modulated Electron Beam with a Plasma," Ph.D. dissertation, Calif. Inst. Tech., Pasadena; 1959. Also, "Power Flow and Gap Coupling to Slow Wave Plasma Modes," Electron Tube and Microwave Lab., Calif. Inst. Tech., Pasadena, Tech. Rept. 12, NONR 220 (13); June, 1959.

frequency of plasma electrons with the sheath at the tube wall was approximately 129×10^6 sec^{-1} for a plasma column diameter of 1.04 cm (as in the first experiment). The collision frequency of electrons with un-ionized mercury atoms was 37×10^6 sec^{-1} corresponding to a mean-free path of the plasma electrons through mercury atoms of approximately 3.5 cm, which was somewhat greater than the tube diameter.

The mean-free path for beam electrons of 100 to 1000 volts in the plasma ranged from about 26 to about 65 cm at the vapor pressure used throughout these experiments.

B. Electron Beam

The electron-beam gun was of the conventional type used in traveling-wave tubes. Beam focusing was possible with an electron lens (focusing cylinder, Figs. 1 and 4) and ion space-charge forces. *L* cathodes were found to be the most satisfactory in resisting the adverse effects of mercury ion bombardment. Arcing between gun electrodes due to the presence of ions did not seem to occur in the voltage range employed. The cathode button diameters were 0.045 and 0.090 inch in the helix modulation tube of Fig. 1 and in the cavity modulation tube of Fig. 4, respectively.

V. Helix Modulation Experiment

A. Interaction at Plasma Resonance

A schematic of the helix modulation tube is shown in Fig. 1. The plasma interaction length between helices was about 5 cm. The inner radius of the glass tube was 0.52 cm. The *S*-band coupling waveguides were tapered to 1 cm in height. The input and output helices were each 3 cm long. The helix-synchronous voltage was 400 volts.

In the operation of the experiment the electron beam was modulated with a microwave frequency between 2.2 and 4.0 kMc, and the output signal from the demodulation helix was observed as the arc current was swept. The plasma density, and thus the square of the plasma frequency, is approximately proportional to arc current in low-pressure arc discharges.[23] According to the theory presented in Section II, the output signal level should be a maximum when the arc current is such that plasma frequency ω_p equals the modulation frequency ω. This value of arc current for maximum interaction should change as the input frequency is changed. For convenience, the arc current was swept at a 60-cps rate, so that the result could be displayed on an oscilloscope.

The output signal level was displayed on the *y* axis of the oscilloscope, while a signal proportional to the discharge current was used to drive the *x* axis. Fig. 6 shows the resulting display for six different modulating frequencies. The arc current zero line is the heavy vertical line on the extreme left. From these and similar traces the current for maximum interaction was obtained, and the result is shown in Fig. 7.




Fig. 6—Detected output signal vs arc current as obtained from the helix-modulation tube. Horizontal calibration: 20 divisions equal 0.40 ampere.




Fig. 7—G_1 and G_2 give the axial plasma frequency squared as obtained from Fig. 6. The circles represent measurements of the average plasma frequency squared over the plasma interaction region as obtained by the cavity perturbation method.

The observation that points G_1 and G_2 lie on relatively straight lines passing nearly through the origin is strong evidence that the interaction observed corresponds to plasma resonance. Approximate equality of the modulation frequency and the plasma frequency must be ascertained from an independent measurement of plasma density. The fact that the straight lines when extrapolated to zero frequency do not pass exactly through the origin may be explained in terms of part of the plasma being produced by beam collisions. Differences in beam focusing probably accounts for the difference between the intercepts of curves G_1 and G_2, taken with different electrode potentials.

To obtain a measurement of electron density by an independent method, the cavity-perturbation tech-

[23] B. Klarfeld, "Characteristics of the positive column of gaseous discharge," *J. Phys. USSR*, vol. 5, pp. 155–175; 1941.

nique[24–26] which measured the average plasma electron density over the cross section, was applied to the plasma interaction region of the helix tube. The average square of plasma frequency was also plotted vs arc current in Fig. 7. The difference in slopes (a factor of 1.4) between the cavity data and G_1 or G_2 may be explained by the fact that electron density on the axis, where interaction occurs, is higher than the average density for a specific current. Assuming a parabolic dependence of density on radius,[27] it was estimated from the ratio of the slopes that the edge plasma density was about 0.4 of the plasma density on the axis, which was in reasonable accord with Klarfeld.[23]

B. Rate of Growth

Table I presents theoretical growth constants in db per cm for different values of the electron-beam current. All rates of growth are for 3000 Mc, assume a 400-volt beam, include a beam-reduction factor of 0.4 [from (25)], a beam diameter of 3 mm, and a value of $R=100$. The first column gives the maximum rate of growth (such as that taken from the peak of the curves in Fig. 3) and neglects collisions. The second column also neglects collisions and gives the growth at the plasma frequency $\omega=\omega_p$. The remaining columns are also for $\omega=\omega_p$, but include collision frequencies ν of 30, 100, and 300 Mc, respectively.

TABLE I

Theoretical Growth Constants at Plasma Resonance for the Helix Modulation Tube

I_b	Max G db per cm	G at $\omega=\omega_p$ db per cm			
ma	$\nu=0$	$\nu=0$	$\nu=30\times10^6$	$\nu=100\times10^6$	$\nu=300\times10^6$
0.25	17.2	11.1	10.74	9.68	6.95
0.5	22.05	15.5	14.93	13.4	9.71
1.0	27.55	21.4	20.55	18.38	13.5
2.0	34.0	29.2	27.9	24.96	18.68

Experimentally, the maximum net gain observed between the input and output waveguides was about +25 db. Under this condition the cathode current was 2.0 ma, and the current reaching the beam collector was 0.48 ma. When the arc was turned off but the beam left on, the net loss between waveguides was as little as 10 db if the beam remained well focused. This implies an electronic gain of 35 db in the 5-cm interaction length or a growth constant of 7 db per cm. The theoretical prediction, assuming a beam current of 0.5 ma and a collision frequency of 100 Mc (Table I), was about 13.4 db per cm. On many occasions the helix modulation tube showed a net *loss* of 10 db or so. Adjusting electrode potentials of the device so as to show net gain was sometimes difficult.

The theoretical bandwidth of this amplification device is less than 1 per cent. The experimentally observed bandwidths of 25 per cent or so seen in Fig. 6, together with the reduced gains, are likely to be explained by the variations in the plasma density *along* the path of the beam. When the plasma frequency varies along the path of the electron beam, it can be shown that the effect is to reduce the gain at any one frequency and to increase the range of frequencies over which amplification is possible. The density is probably lowest where the beam enters and where it emerges because of diffusion losses.

It is difficult, for two reasons, to observe the growing waves at plasma resonance by moving an antenna along the outside of the glass column. First, the fields decay exponentially away from the surface of the beam and the decay factor is large, since $\beta a=8.2$ for the helix tube at 3000 Mc and 400 volts. Secondly, as may be seen from the following argument, plasma oscillations ($\omega=\omega_p$) produce very little field outside the plasma column. The dielectric constant (2) is zero in the plasma, and hence the normal component of the displacement vector vanishes at the edge of the plasma. Therefore, the normal component of the electric field vanishes outside the plasma column. Of course this argument neglects the effect of random energy of the plasma electrons, but it does serve to indicate that the field outside should be small. The first argument does not apply to the cavity modulation tube to be discussed in Section VI, since βa is approximately unity and the electron beam passes closer to the edge of the plasma column in that tube. The growing wave at plasma resonance *was* detectable in the cavity modulation tube using a traveling probe.

C. Slow-Wave Interaction

When the electron beam was defocused so badly that it filled most of the plasma column, being reflected from the sheath from the edge of the plasma column and then partially collected at the second helix, an interaction was observed when the plasma frequency was greater than the modulation frequency. Fig. 8 shows the detected output signal vs arc current. The arc current increases from left to right and is zero at the heavy vertical line at the far left. Two interactions may be seen, the one at lower current occurring when

[24] M. A. Biondi and S. C. Brown, "Measurements of ambipolar diffusion in helium," *Phys. Rev.*, vol. 75, pp. 1700–1705; 1949.
[25] K. B. Persson, "Limitations of the microwave cavity method of measuring electron densities in a plasma," *Phys. Rev.*, vol. 106, pp. 191–195; 1957.
[26] S. J. Buchsbaum and S. C. Brown, "Microwave measurements of high electron densities," *Phys. Rev.*, vol. 106, pp. 196–199; 1957.
[27] R. M. Howe, "Probe studies of energy distributions and radial potential variations in a low pressure mercury arc," *J. Appl. Phys.*, vol. 24, pp. 881–894; 1953.




Fig. 8—Detected output signal vs arc current as obtained from the helix tube. Calibration as in Fig. 6. The interaction peak at the larger current is with the surface wave mode of propagation. NF is with the output unfiltered.




Fig. 9—Detected output signal vs arc current as obtained from the cavity-modulation tube. Horizontal calibration: 20 divisions equal 0.050 ampere. The beam is interacting with the angularly independent surface-wave mode of propagation.

$\omega_p = \omega$, and the one at higher current presumably due to the axially symmetric surface wave mode of propagation. The subsidiary maxima in Fig. 2 of the preliminary report[12] were probably also due to the surface-wave interaction. If the beam were not deliberately defocused, interaction with the surface wave could not be observed since the fields are strong only at the surface of the plasma column.

Also shown in Fig. 8 are two photographs at the same frequency taken with the detected output signal both filtered and nonfiltered (NF). Appreciable noise is present in both interactions, some of which may be associated with moving striations.[28]

In Figs. 6, 8 and 9 hysteresis is evident. This may be due to space-charge buildup and decay or to nonequilibrium heating effects. The hysteresis phenomena is not completely understood.

VI. Cavity Modulation Experiment

A. Slow-Wave Interaction

A larger beam and smaller plasma column were necessary to obtain strong interaction with the surface-wave mode of propagation, thus the device shown in Fig. 4 was constructed. By varying the beam voltage (approximately 1000 to 100 volts) βa could be made to fall between 0.5 and 1.5. By operating with a significantly smaller value of βa than in the helix tube, the surface-wave fields are much stronger near the axis where the electron beam passes. By employing an axial magnetic field it would be possible to have the fields on the axis stronger than at the surface.[16]

The detected output signal 490 Mc is shown in Fig. 9 vs arc current at six different electron-beam voltages. The zero of current is the numbered heavy line at the far left. As the beam velocity increases, the phase velocity of the slow surface wave must also increase to fulfill the synchronism condition. From Fig. 5 it is seen that βa and f/f_p decrease as the velocity increases. Thus as the beam velocity increases the plasma frequency must increase if synchronism is to be maintained. Fig. 9 shows that, indeed, as the beam voltage is increased, the arc current for maximum gain increases.

The electron density in the plasma column of the cavity-modulation tube was measured by the cavity-perturbation technique.[24–26] as a function of arc current. From the arc current corresponding to the peak interaction in Fig. 9 one may obtain the *experimental* ω-β diagram as shown by the data points in Fig. 5. The result is seen to correspond well to the theoretical curves. Any errors in the cavity measurements of plasma density would tend to shift the vertical scale.

Interaction was also observed at the plasma resonance with the cavity tube. This interaction occurred near the value of the current at which the arc extinguished, and stable operation was difficult. Nevertheless, the values of the interaction-arc current at which this interaction occurred were used to determine the plasma frequency $f_p = \omega_p/2\pi$, and the results (f/f_p) are plotted in Fig. 5 near the horizontal line at $f/f_p = 1$.

B. Growing Surface Waves

The surface-wave fields are strongest at the surface of the plasma column. A traveling probe at the surface of the glass column was used to detect a growing standing-wave pattern (Fig. 10). The standing-wave pattern is a result of the interference between the growing surface wave and the wave which is reflected by the output cavity resonator. From the standing-wave pattern one may measure the electronic wavelength on the plasma column. This is in agreement with the value predicted from the beam voltage.

[28] L. Pekarek, "Theory of moving striations," *Phys. Rev.*, vol. 108, pp. 1371–1372; 1957.




Fig. 10—Growing wave strength vs distance as obtained by a traveling probe at the surface of the glass column of the cavity-modulation tube.

The 250-volt case in Fig. 10 is of particular interest. The lower curve was taken with the beam current greatly reduced by lowering the cathode temperature. The signal then decayed along most of the interaction region because of collisional attenuation in the surface-wave propagation. The upper curve is with a normal beam current and shows a growing wave.

Theory[21] predicts a growth constant of 2.75 db per cm when an interaction impedance of 800 ohms (Section III-B) and a 200-volt beam at 1-ma current are assumed, and when space charge in the beam, plasma random energy, and collisions are neglected. A representative experimental value at 1 ma and 200 volts is about 0.8 db per cm. The discrepancy between the theoretical and experimental growth constants may be due possibly to the neglect of loss along the plasma column in the theoretical calculation.

C. *Interaction at Plasma Resonance*

Because of the smaller value of βa (approximately 1) for the cavity tube (as compared with $\beta a \approx 8$ in the helix tube), it was found that a growing standing-wave pattern could be observed with a traveling probe outside the plasma column (see Fig. 10). A representative growth constant was found to be 1 db per cm at 1-ma beam current.

Measurements on the growing standing-wave pattern indicated that the interfering wave had a large phase velocity compared to the forward-beam velocity, and thus the standing-wave pattern was probably due to stray radiation in free space from the signal source. The standing-wave pattern could not have been a result of the reflected surface wave since the latter does not propagate when $f=f_p$.

Table II gives theoretical growth constants in db per cm, assuming a 200-volt beam, a beam reduction factor of 0.21 from (25) a beam diameter of 4.8 mm, and a value of $R=200/4.7=42.6$. The presentation of the data is similar to that in Table I.

TABLE II

Theoretical Growth Constants at Plasma Resonance for the Cavity-Modulation Tube

I_b	Max G db per cm	G at $\omega=\omega_p$ db per cm			
ma	$\nu=0$	$\nu=0$	$\nu=30\times10^6$	$\nu=100\times10^6$	$\nu=300\times10^6$
0.25	6.61	5.32	4.72	3.58	2.11
0.5	8.27	7.23	6.38	4.92	2.96
1.0	10.32	9.62	8.52	6.70	4.16
2.0	12.72	12.52	11.20	9.05	5.78

The experimentally measured growth rate of 1 db per cm was considerably less than the theoretical value of about 6.7 db per cm (assuming 100-Mc collision frequency), and this discrepancy is most likely due to variations of the axial plasma density or to an incorrect estimate of the beam diameter in the plasma.

VII. Summary and Conclusions

Experiments have been performed substantiating two types of interaction between a modulated electron beam and a plasma. In one case the plasma acts as a resonant, nonpropagating medium and in the other as a slow traveling-wave structure with which synchronism between it and the electron beam is observed.

Exponential growth constants along the beam were measured with a traveling probe for both interactions. The experimental rates of growth were considerably less than that predicted theoretically. For the traveling-wave interaction, the neglect of loss and the random energy of the plasma electrons in the theory are probably of most importance.

Trivelpiece and Gould[16] have shown that immersing the plasma column in an axial magnetic field converts the nonpropagating plasma resonance into a backward-wave propagating mode (phase and group velocities in opposite directions) with which backward-wave interaction (and thus oscillation) is possible. Recently Targ and Levine[29] have observed such backward-wave oscillations. Structureless slow-wave propagating circuits are intriguing and deserve further investigation.

Appendix

Three-Dimensional Theory Neglecting the Random Energy of the Plasma Electrons

If in a plasma the wavelength of the disturbance is small compared to the free-space wavelength at that frequency, the magnetic field associated with plasma oscillations may be neglected. Under this quasi-static approximation the time-varying potential and charge

[29] R. Targ and L. P. Levine, "Backward-wave microwave oscillations in a system composed of an electron beam and a hydrogen gas plasma," *J. Appl. Phys.*, vol. 32, pp. 731–737; 1961.

density are related by Poisson's equation

$$\nabla^2\phi_1 = -\rho_1/\epsilon_0. \tag{20}$$

In the one-dimensional case analyzed in Section II-A the quasi-static *approximation* is unnecessary since the time-varying magnetic field vanishes identically ($\nabla\times\boldsymbol{E}_1 = -\gamma\mathbf{e}_z\times\boldsymbol{E}_1 = 0$).

The three-dimensional problem considered here consists of an electron beam of finite radius b passing through a nondrifting infinite cold plasma. To obtain the dispersion equation for growing waves, one computes the sum of the ac charge densities of the beam and of the plasma from the linearized small-signal continuity and force equations. Substituting this sum into (20) and rewriting slightly, one obtains

$$\nabla\cdot\left\{1 - \frac{\omega_p^2}{\omega^2} - \frac{\omega_b^2}{(\omega-\gamma v_b)^2}\right\}\nabla\phi_1 = 0, \tag{21}$$

where a z dependence of $e^{-i\gamma z}$ has been assumed. This is the appropriate differential equation for the beam and plasma together. In the region outside the beam the same equation can be used by setting $\omega_b = 0$.

Note that (21) is written in the form $\nabla\cdot\boldsymbol{D}_1 = 0$, where $\boldsymbol{D}_1$ is the displacement vector. In this form the boundary condition at the interface between the region containing plasma alone and that containing plasma plus beam is evident: the normal component of the quantity $\boldsymbol{D}_1$ is continuous between regions. The potential must also be continuous.

The solutions to (21) are either

$$1 = \frac{\omega_p^2}{\omega^2} + \frac{\omega_b^2}{(\omega-\gamma v_b)^2} \qquad r \le b, \tag{22}$$

or

$$\nabla^2\phi_1 = 0 \qquad 0 \le r \le \infty. \tag{23}$$

Eq. (22) is identical to (3). This represents the one-dimensional solution and is independent of beam radius. Eq. (22) was derived by Pierce,[4] except that he was considering the interaction of beam electrons with ions. The solution of this equation is plotted in Fig. 3 under the designation of $R = \infty$.

For the three-dimensional case the solutions are obtained from (23). Note that (23) implies that $\rho_{1b} + \rho_{1p} = 0$, and therefore that the system consisting of the electron beam and the plasma has no density modulation; only a "rippled boundary" form of modulation at $r = b$ which is the interface between the two regions.

Circularly symmetric solutions of (23) contain modified Bessel functions and are, respectively, $I_0(\gamma r)e^{-i\gamma z}$ and $K_0(\gamma r)e^{-i\gamma z}$ for the radius less than or greater than the beam radius. The potential has been taken to be finite at the origin and zero at infinity. Matching the above boundary conditions results in

$$1 = \frac{\omega_p^2}{\omega^2} + \frac{(\omega_b')^2}{(\omega-\gamma v_b)^2}, \tag{24}$$

where

$$\left(\frac{\omega_b'}{\omega_b}\right)^2 = \frac{1}{1 + \dfrac{I_0(\gamma b)K_1(\gamma b)}{I_1(\gamma b)K_0(\gamma b)}}. \tag{25}$$

The only quantitative effect in (24) compared to (3), which neglects the random energy of the plasma electrons, is to replace the electron-beam plasma frequency by a *reduced*-beam plasma frequency ω_b'. This is a result of the difference between *rippled boundary* modulation and density modulation.

Inclusion of the effects of the random energy of the plasma electrons into the finite geometry problem is more difficult due to the complexity of the boundary conditions. As an approximation to the three-dimensional problem it is assumed that one may take the one-dimensional dispersion relation (6) and replace the beam plasma frequency by the reduced-beam plasma frequency of (25). This results in an approximate dispersion relation, including the random energy and collisions of the plasma electrons, for a finite diameter beam in an infinite plasma.

If the electron beam were immersed in a finite axial magnetic field both rippled boundary and density modulation would occur.

Acknowledgement

A great deal of credit for the success of these experiments is attributable to A. F. Carpenter, whose skill and patience in the fabrication of the glass tubes is gratefully acknowledged. Fruitful discussions were enjoyed with Dr. A. W. Trivelpiece.

The continuing support of the Office of Naval Research is very gratefully acknowledged.

A Method of Measurement of Flame Attenuation at 200 Mc*

ALBERT W. BIGGS†, MEMBER, IRE

Summary—**This paper presents a simple method for the determination of the attenuation encountered by a VHF signal as it passes through a flame or the exhaust trail produced by a flame. The measurements are made of the VSWR and the shift of the minimum electric field as the ionized gases pass between two parallel plates of a short-circuited, two-bar transmission line. The relative dielectric constant and the conductivity of an ionized gas are plotted for several electron densities and collision frequencies for a frequency of 200 Mc. Another set of curves is derived from these for attenuation and minimum shift due to ionized gases in a predetermined length of transmission line. Characteristic impedance curves are also plotted. Simple Smith chart techniques are used to determine the VSWR and minimum shift when ionized gases pass through a length of shorted transmission line. The length corresponds to a half wavelength of the wave in the line with no ionized gases present. Calibration was accomplished with the use of distilled water.**

Introduction

SEVERAL methods are available[1] for the measurements of attenuation in a radio signal when it passes through an ionized gas. The selection of 200 Mc as the frequency for attenuation measurements precluded the use of microwave horns[2] or helix antennas[3] because of their large physical size. The transmission line proved to be the simplest mechanism. When it has a short-circuited load, the VSWR is high (infinitely when losses in the system are absent, but this is impossible). The minimum is also quite sharply defined.

When a slightly ionized gas passes between the two conductors of a short-circuited transmission line, the wave is attenuated as it passes to and from the short circuit. The VSWR is reduced with the increase of electron density and the increase of collision frequency. The wavelength of the wave is also increased in the ionized plasma region. Both of these can be measured with a slotted line and a standing wave detector.

Analytical Determination of VSWR and Minimum Shift

The relative dielectric constant K of an ionized gas is a function of the collision frequency ν of electrons with gas molecules, the plasma frequency ω_p, and the frequency ω of the radio signal passing through the medium. It is given by

$$K = 1 - \frac{1}{(\nu/\omega_p)^2 + (\omega/\omega_p)^2}, \tag{1}$$

with the plasma frequency equal to

$$\omega_p = e\sqrt{\frac{n}{\epsilon_0 m}} \times 10^3, \tag{2}$$

where n is the electron density in electrons per cubic centimeter, e is the electron charge, m is the electron mass, and ϵ_0 is the dielectric constant of free space (MKS units). This is shown in Fig. 1 for a frequency of 200 Mc. The range of collision frequencies is selected because it is typical[4] for flames.

The conductivity σ is given by the expression

$$\sigma = \epsilon_0 \nu \frac{1}{(\nu/\omega_p)^2 + (\omega/\omega_p)^2}. \tag{3}$$

This is shown in Fig. 2 for a 200 Mc signal.

The attenuation α and phase constant β are derived from K and σ in terms of collision frequency and electron density from[5]

$$\alpha = \frac{\omega}{c}\sqrt{K}\sqrt{\sqrt{1+\left(\frac{\omega\sigma}{K\epsilon_0}\right)^2} - 1} \tag{4}$$

$$\beta = \frac{\omega}{c}\sqrt{K}\sqrt{\sqrt{1+\left(\frac{\omega\sigma}{K\epsilon_0}\right)^2} + 1} \tag{5}$$

The curve for α is shown in Fig. 3.

* Received by the IRE, August 21, 1961.

† Aero-Space Div., Boeing Co., Seattle, Wash.

[1] A. G. Gaydon and H. G. Wolfhard, "Flames—Their Structure, Radiation, and Temperature," Chapman & Hall, Ltd., London, Eng.; 1953.

E. Sanger, P. Goercke and I. Bredt, "Ionization and Luminescence in Flames," NACA Tech. Memo 1305; April, 1951.

H. Belcher and T. M. Sugden, "Studies on the ionization produced by metallic salts in flames. I. The determination of the collision frequency of electrons in coal-gas/air flames," *Proc. Roy. Soc. (London) A*, vol. 201, pp. 480–488; May, 1950.

T. M. Sugden and B. A. Thrush, "A cavity resonator method for electron concentration in flames," *Nature*, vol. 158, pp. 703–704; October, 1951.

H. Smith and T. M. Sugden, "Ionization produced in metallic salts in flames. I. Ionic equilibrium in hydrogen/air flames containing alkali metal salts," *Proc. Roy. Soc. (London) A*, vol. 211, pp. 31–58; February, 1952.

T. M. Sugden, "The use of microwaves in the study of ionic and chemical equilibrium at high temperature," *Discussion, Faraday Soc.*, vol. 19, pp. 68–76; January, 1955.

F. P. Adler, "Measurement of the conductivity of a jet flame," *J. Appl. Phys.*, vol. 25, pp. 903–906; July, 1954.

[2] W. C. King and W. Gordy, "One-to-one millimeter wave spectroscopy. IV. Experimental methods and results for OCS CH_3F, and H_2O," *Phys. Rev.*, vol. 93, pp. 407–412; February, 1954.

K. E. Shuler and J. Weber, "A microwave investigation of the ionization of hydrogen-oxygen and acetylene-oxygen flames," *J. Chem. Phys.*, vol. 22, pp. 491–502; February, 1954.

[3] A. Dauguet, "Etude de l'ionisation des gaz de propulseurs a reaction," *Ann. Télécommun.*, vol. 12, pp. 234–244; June, 1957.

[4] J. Schneider and F. W. Hofmann, "Absorption and dispersion of microwaves in flames," *Phys. Rev.*, vol. 116, pp. 244–249; October, 1959.

[5] E. C. Jordan, "Electromagnetic Waves and Radiating Systems," Prentice-Hall, Inc., New York, N. Y., p. 672; 1955.




Fig. 1—Relative dielectric constant in an ionized gas for different electron densities.




Fig. 2—Conductivity of an ionized gas for different electron densities.




Fig. 3—Attenuation in an ionized gas for different electron densities.




Fig. 4—Characteristic impedance of an ionized gas for different electron densities.




Fig. 5—VSWR with lossless coaxial cable in an ionized gas for different electron densities.




Fig. 6—VSWR and shift of minimum for 25 ft PF RG87A coaxial cable in an ionized gas for different electron densities.

In terms of σ and K, the characteristic impedance Z_1 is

$$Z_1 = Z_1' - jZ_1'' \tag{6}$$

with

$$Z_1' = \frac{0.707Z_0}{\sqrt{K[1 + (\omega\sigma/K\epsilon_0)^2]}} \sqrt{\sqrt{1 + (\omega\sigma/K\epsilon_0)^2} + 1} \tag{7}$$

$$Z_1'' = \frac{0.707Z_0}{\sqrt{K[1 + (\omega\sigma/K\epsilon_0)^2]}} \sqrt{\sqrt{1 + (\omega\sigma/K\epsilon_0)^2} - 1.} \tag{8}$$

These are shown in Fig. 4. The characteristic impedance Z_0 is that for a two-bar transmission line with air dielectric:[6]

$$Z_0 = 120\pi \frac{a}{b}, \tag{9}$$

where a is the separation between plates and b is the width of the plates.

The VSWR for a transmission line with no losses is given in Fig. 5. The actual installation uses 25 feet of RG87A coaxial cable. The attenuation of this cable and 56 in of brass two-bar line is 0.012 neper per meter. The attenuation lowers the VSWR to those shown in Fig. 6. Also shown is the shift in the minimum electric field measured from the load. A shorter length of cable would yield higher VSWR readings.

Interpretation of VSWR and Minimum Shift

At high values of electron density, for n greater than 10^8, the minimum shift and the VSWR yield both electron density and collision frequency. For low values of electron density, two possibilities exist for collision frequency. More sensitive measurements are needed, but the attenuation can be determined with the aid of Fig. 6 and Fig. 3.

[6] S. Ramo, and J. R. Whinnery, "Fields and Waves in Modern Radio," John Wiley and Sons, Inc., New York, N. Y., p. 364; 1953.




Fig. 7—Block diagram of measurement equipment.

Calibration

Distilled water was used to calibrate the two-bar transmission line. A block diagram showing the instrumentation is in Fig. 7.

The two-bar line was constructed with two waveguides so that cooling water could flow in the line when hot ionized gases passed between the bars. One end of the line was short-circuited. The other end was matched to a coaxial cable by a quarter wavelength balun. The line was immersed in distilled water at depths measured in wavelengths of the wave in water. The VSWR with three-quarter wavelengths of line in water was 1.04. For a half wavelength, it was 26. The corresponding conductivity was 3×10^{-2} mhos per meter, while the relative dielectric constant was 82. This compares with 10^{-2} and 78 from Von Hippel.[7] A one molar solution of sodium chloride gave a VSWR of 13 for all depths of liquid in the two-bar line. The attenuation for a one molar solution of salt water is so large for six or more inches of liquid that the wave is lost. The solution takes on the character of a metallic surface. Eqs. (6) and (7) reduce to

$$Z_1' = Z_1'' = 0.707Z_0\left(\frac{\epsilon_0}{\omega\sigma}\right). \tag{10}$$

The conductivity is readily obtained with the help of a Smith chart. The shift in the minimum can also be used with liquids of conductivities greater than that of distilled water.

[7] A. Von Hippel, "Dielectric Materials and Applications," John Wiley and Sons, Inc., New York, N. Y., p. 361; 1954.

Electrical Characteristics of a Penning Discharge*

J. C. HELMER† AND R. L. JEPSEN†, SENIOR MEMBER, IRE

Summary—The uniform-space-charge theory of the high-vacuum, Penning discharge has been tested and supported in two experiments. In one experiment a measurement of ion energies verifies the existence of a large space-charge depression of potential along the axis of the anode cylinder. In another, the frequency of body rotation of the electron cloud is verified by allowing the cloud to interact with the structure of a split-anode magnetron. Spontaneous oscillation is obtained. The avalanche theory of the cold-cathode discharge is tested by a measurement of the noise spectrum of the discharge current. Partial confirmation is obtained, although it is finally concluded that the discharge may be dominated by other processes, such as plasma instabilities. Evidence for plasma instabilities is presented in the form of star-shaped, ion-sputtering patterns. Three possible instability mechanisms are discussed, by means of which such sputtering patterns could be formed. A useful by-product of this investigation is the discovery that a Penning "ion-gun" produces a naturally collimated, intense ion beam of sharply defined energy.

I. Introduction

PENNING discharges have been used for ion sources, vacuum gauges, and small vacuum pumps. More recently it has been possible to construct high-speed, high-vacuum pumps containing thousands of small Penning discharge cells operating in parallel. In this respect the state of the art has reached a high degree of refinement,[1] although the electronic characteristics of the discharge itself are not too well defined. The purpose of this paper is to describe some recent experiments on the Penning discharge and to discuss the results in relation to existing theories of the discharge.

It is important to note that many different types of discharges can exist in the Penning cell, depending on the operating pressure. Much of the available literature on this discharge is concerned with a low-voltage, glow-type discharge which is observed at relatively high pressures. In the following discussion we will be concerned only with a high-voltage, high-impedance discharge which is characteristic of the cell for all pressures *below* approximately 10^{-4} mm Hg. Operation in this region is distinguished by the fact that there is little or no trapping of positive ions in the discharge so that the body of the discharge consists of a dense, negative cloud of electrons.

II. Physical Principles of the Penning Discharge

The electrode configuration for a Penning cell is shown in Fig. 1. A cylindrical anode is mounted between two cathodes and immersed in a magnetic field parallel to the axis of the cylinder. It is most easy to visualize the operation of the cell by supposing that the anode contains a cloud of electrons in perfect vacuum. The electrons are supposed to have energy less than the applied potential, so they cannot reach the cathodes. In addition the magnetic field is supposed to be so strong that the cycloidal electron orbits in the transverse plane are much smaller in diameter than the anode. Then the electrons cannot reach the anode. Consequently, the electron cloud is contained without losses, except for radiation which we neglect.




Fig. 1—Configuration of a Penning discharge.

Now suppose that a neutral molecule enters the system. This molecule will eventually be ionized by the energetic electron cloud. The ionizing electron will recover the energy it has lost by moving closer to the anode, while the ion is driven into one of the cathodes by a strong electric field, giving rise to secondary emission of electrons. In steady state, the process is described by a Townsend avalanche equation. If the mechanism of trapping secondaries is independent of pressure, then we may predict the following measurable behavior:

1) The current drawn by the cell is proportional to pressure.
2) The pumping speed of the cell in liters per second is independent of pressure.

The second conclusion really depends on another assumption, *i.e.*, that the pumping speed in molecules per second is proportional to the current. In any case these predictions have been verified over the pressure range 10^{-5} to 10^{-8} mm Hg for a cell of approximately the following dimensions and operating conditions:[1]

* Received by the IRE, August 21, 1961.
† Varian Associates, Palo Alto, Calif.
[1] R. L. Jepsen, "Important characteristics of a new type Getter-ion pump," *Le Vide*, vol. 80, pp. 80–94; March-April, 1959.

anode diameter	$\frac{1}{2}$ in
anode length	$\frac{7}{8}$ in
cathode spacing	$1\frac{1}{4}$ in
magnetic field	1200 gauss
anode voltage	3000 v.

Thus it is reasonable to state that the principal feature of the discharge is a trapped cloud of electrons whose charge is approximately constant and independent of pressure. By virtue of its motion this cloud sweeps out the volume of the system at a constant rate, in a manner analogous to the rotor of a mechanical forepump, disposing of the molecules by ionization. To consider what happens to the molecules after ionization would involve the description of pumping mechanisms which are described elsewhere and are outside the scope of this article.[2]

An additional confirmation of this viewpoint is that for different gasses at the same pressure, the current drawn is approximately proportional to the ionization cross section. Thus the charge of the electron cloud is substantially independent of gas type, as well as of pressure.

In order to account for the current drawn at a given pressure, in a given gas, one of the authors has shown that the number of trapped electrons must be such as to cause a space-charge depression of potential along the axis of the anode cylinder that is a substantial fraction of the applied voltage.[3] The maximum number of trapped electrons is determined by the condition that the potential depression on the axis of the anode shall not exceed the applied voltage, otherwise electrons will drain to the cathodes. In the absence of a detailed knowledge of the potential profile within the anode, we may assume the existence of uniform charge density. For this case the maximum amount of negative charge Q that may be trapped in a cylindrical anode at a voltage V relative to the cathodes is given by

$$Q = 1.11V \times 10^{-12} \tag{1}$$

coulombs per centimeter of anode length. This charge is independent of the anode diameter. The value of the magnetic field depends on the anode diameter, since the condition for constant cycloidal orbit energy is $V/Bd = \text{constant}$, where V is the anode voltage, d is the anode diameter, and B is the magnetic field strength. On the other hand, the number of ionizations required for an electron to reach the anode remains invariant only if V and Bd are separately held constant. This is the condition for invariance of the Townsend avalanche equation.

The large space-charge depression of potential along the axis of the Penning cell results in strong radial electric fields within the anode which are transverse to the dc magnetic field. Consequently, the device has many of the characteristics of a crossed-field, smooth-bore magnetron. Furthermore, experiments by the authors on magnetron geometries have disclosed that magnetron cells and Penning cells have very similar characteristics. Therefore, in the interests of simplicity, it is reasonable to approach the theory of the Penning cell by way of the theory of the cold-cathode magnetron which has a simple, two-dimensional field configuration. Theories for the striking potentials of cold-cathode magnetrons have been developed by Haefer[4] and by Redhead,[5] but no theory exists for the current-voltage characteristic of a cold-cathode magnetron discharge under space-charge dominated conditions. This is the case of interest to us.

The difficulty in analyzing the space-charge limited discharge is illustrated by a discussion of the planar magnetron, shown in Fig. 2. Two planes are separated in the x direction by an amount a. The planes lie in the yz plane and are immersed in a magnetic field in the z direction. Across the planes is applied a potential V. The charge distribution is assumed to be a function of x alone. An avalanche, starting from one secondary electron at the cathode, works its way towards the anode so that the charge of electrons in an avalanche at position x is given by

$$q = e \exp \int_0^x \alpha(E)dx, \tag{2}$$




Fig. 2—Discharge in a planar magnetron.

which defines $\alpha(E)$. Multiplying this by the number of avalanches per second initiated at the cathode gives the average current at position x. The average charge density is obtained by dividing the average current by the drift velocity $v(e)$ in the x direction. Thus for the divergence equation $\nabla \cdot E = \rho/\epsilon$ we get

$$\frac{dE}{dx} = \frac{i_0}{\epsilon v(E)} \exp \int_0^x \alpha(E)dx, \tag{3}$$

[2] S. L. Rutherford, *et al.*, "On pumping mechanisms in Getter-ion pumps employing cold-cathode gas discharges at low pressures," in "Vacuum Symposium Transactions," Pergamon Press, London, Eng., p. 380; 1960.

[3] R. L. Jepsen, "Magnetically confined cold-cathode gas discharges at low pressures," submitted to *J. Appl. Phys.*

[4] R. Haefer, "Die Strom-Spannungscharakteristiken einer selbstandigen Gasentladung im transversalen Magnetfeld," *Acta Phys. Austriaca*, vol. 8, pp. 213–224; 1954.

[5] P. A. Redhead, "The Townsend discharge in a coaxial diode with axial magnetic field," *Canad. J. Phys.*, vol. 36, pp. 255–270; March, 1958.

where i_0 is the current at the cathode ($x=0$). The solution of this equation is constrained by the condition

$$\int_0^a Edx = V = \text{constant}. \tag{4}$$

In addition we must satisfy the Townsend avalanche equation

$$\Gamma(P)\left[\exp \int_0^a \alpha(E)dx - 1\right] = 1, \tag{5}$$

where $\Gamma(P)$, a function of the pressure P, is the average probability per ion of generating a secondary electron at the cathode *which succeeds in getting away from the cathode by collision with a neutral molecule.* We may expect in (3) that for every value of E at the cathode E_0 there is an i_0 such that (4) is satisfied. However, there is only one combination E_0, i_0 such that (5) is satisfied also. The solutions to (3)–(5) may be obtained with a computer if the functions $\alpha(E)$, $v(E)$, and $\Gamma(P)$ are known. The trouble is that these functions are not well known. If an electron has neither much greater nor much less than ionizing energy, then $v(E)$ is approximately the radius of the cycloidal electron orbit divided by the time between collisions, while $\alpha(E)$ is the inverse of the radius of the cycloid orbit. In our case this approximation is *not* valid, since the electric field at the cathode may be very weak due to space-charge depression. Then electrons in traversing the space between cathode and anode pass through a wide range in energy, beginning with elastic collisions and progressing through the energy required for excitation, ionizing, and multiple ionizing collisions. An additional limitation to this approach is that we have neglected cooperative phenomena, such as plasma oscillations and instabilities, which in the past have played a major role in the explanation of current drawn by magnetrons under below cutoff conditions.

In the absence of an analytic solution for the potential distribution in the interior of the magnetron or the Penning cell, we have found it convenient to assume a uniform charge distribution, leading in the case of Penning cells to a parabolic potential well in the radial direction. The radial electric field E_r gives rise to an azimuthal drift velocity equal to E_r/B such that a parabolic potential well produces a uniform rotation of the electron cloud. The measurements to be described bear in part on the assumption of uniform charge distribution. In addition we will consider the effects produced by avalanche noise and plasma instabilities.

III. The Energies of Ions Produced in a Penning Cell

If a hole is drilled in a cathode on the axis of a Penning cell, the ions that are normally incident on the area of the hole emerge and form a useful ion beam. The ion energies and the beam definition may be analyzed by collecting the beam in a Faraday cup preceded by a small aperture for exploring the transverse dimensions of the beam. When a positive voltage is applied to the Faraday collector, some of the ions may not be energetic enough to overcome the potential barrier and are turned away. Thus, the current-voltage characteristic of the collector serves to measure the energy distribution of the ion beam. Experiments of this type have produced the following results:

1) Ion Energies: The ion energy is sharply defined, with a spread of less than 10 per cent of the mean ion energy. In a standard cell, such as that described in Section II, with an anode voltage of 3000 volts, the mean ion energy is about 1000 electron volts. These ions originate along the axis of the cell and, consequently, their energy is a measure of the potential along the axis. In this case we have a space-charge depression of potential of 2000 volts, thus confirming the earlier prediction of the magnitude and importance of this depression. A typical current-voltage collector characteristic is shown in Fig. 3. The depression of the curve below the zero current axis is caused by the collection of secondary electrons which are present in copious numbers.




Fig. 3—Measurement of ion energy.

2) Beamwidth: The beamwidth, which was not aperture limited, generally lies between 5 and 10° as determined by the angle subtended by the half-intensity points at the beam aperture. This measurement was made in a plane about 2 in from a $\frac{1}{8}$-in diameter beam aperture. The unusual degree of self-collimation may be caused in part by beam neutralization from secondary electrons produced on the edges of the beam aperture.

3) Voltage Dependence of Ion Energies: Below an anode voltage of 4000 volts the ion energy dependence is complicated, as shown in Fig. 4. In this region the space charge is approaching the theoretical maximum given by (1). Above an anode voltage of 4000 volts the ion energy increases linearly with voltage so that relation to (1) is violated. This violation must occur since there is a limit to the space charge that can be contained by a given magnetic field strength. The condition for containment, derived from orbit analysis, is simply that

$$\frac{\omega_p^2}{\omega_c^2} \ll 1, \tag{6}$$

where ω_p is the plasma frequency and ω_c is the cyclotron frequency of the electrons. Thus, as the anode voltage increases, the axial potential depression adjusts itself so that (6) is always satisfied. This measurement points up a unique feature of the Penning discharge, *i.e.*, that as a magnetron it is able to adjust the potential of its virtual axial cathode to whatever value is best suited to the needs of the discharge.




Fig. 4—Voltage and pressure dependence of ion energy.

Allis has shown that (6) is just the ratio of the mc^2 energy density of the electrons to the energy density of the magnetic field.[6]

4) Pressure Dependence of Ion Energies: It is shown in Fig. 4 that at constant anode voltage, a decrease in pressure is accompanied by an increase in ion energy, perhaps reflecting a reduction in space charge. This brings up the interesting question of whether there is some low pressure at which the discharge will go out. It is well known, for example, that Penning structures employing ring anodes tend to go out at pressures in the neighborhood of 10^{-6} mm Hg. The explanation of this behavior may be that at low pressures too many secondary electrons are recaptured at the cathodes before making the ionizing collisions which allow them to be trapped in the cloud. This is the origin of the pressure dependence of (5). On the other hand, the cylindrical anode Penning cell we have described is known to maintain a discharge to pressures as low as 10^{-12} mm Hg.[7] Our electrode configuration may be especially favorable for the generation of two-stream instabilities between the secondary electron streams and the trapped electron cloud.[8,9] Such an instability would be an efficient mechanism for the trapping of secondary electrons. In our case the instability would occur near the plasma frequency of the electron cloud, and the condition for instability is that the secondary electrons shall oscillate between the cathodes at approximately the same frequency. This condition may be met with an electron cloud of high density, such as we obtain, but perhaps not with a cloud of lower density.

5) Ion Current: A $\frac{1}{8}$-in diameter hole in a $\frac{1}{2}$-in diameter cell occupies 1/16 of the cross-sectional area of the cell. It is found, however, that the ion beam contains $\frac{1}{5}$ of the total ion current to the cathode from which it emerges. This shows that the ion current is most intense at the center of the cathode, which may be deduced easily by visual examination of the cathode sputtering pattern. Through some mechanism, about which we can only speculate, many of the ions produced throughout the volume of the cell ultimately emerge along the axis of the cell with axially directed velocities, thereby producing a narrow beam of very high intensity and well-defined energy. At a pressure of 10^{-6} mm Hg a beam current of about 1 microamp is obtained.

IV. Rotation of the Electron Cloud

A distinguishing feature of uniform charge distribution is that the electron cloud within the anode rotates with uniform angular velocity. If the space-charge depression of potential along the axis, relative to the anode potential, is equal to V_0 then the shape of the parabolic potential well is given by $V' = V_0(r/a)^2$, where a is the anode radius. Consequently, the radial electric field E_r and the angular frequency of rotation ω_r are given by

$$E_r = 2V_0 r/a^2, \qquad \omega_r = E_r/rB = 2V_0/Ba^2. \tag{7}$$

On the other hand the plasma and cyclotron angular frequencies are given respectively by

$$\omega_p^2 = 4eV_0/ma^2, \qquad \omega_c^2 = \left(\frac{eB}{m}\right)^2, \tag{8}$$

and we note that there is a simple relation among the three angular frequencies, given by

$$\omega_p^2 = 2\omega_c\omega_r. \tag{9}$$

On the basis of this uniform space-charge theory we estimate that in our standard cell, described in Section II, we have a plasma frequency of about 1000 Mc, a cyclotron frequency of 3300 Mc, and a rotational frequency of 150 Mc.

The frequency of rotation of the electron cloud was measured by splitting the anode lengthwise into two halves to form the plates of a split anode magnetron, as shown in Fig. 5. To these two plates was connected a Lecher wire resonator. Spontaneous oscillation was observed in the neighborhood of 150 Mc, and the frequency of oscillation varied in approximate proportion to V/B, where V is the anode voltage and B is the applied magnetic field, as one would predict from (7). Therefore this measurement verifies the predictions of the uniform space-charge theory.

A unique feature of this oscillator is that the electron

[6] W. P. Allis, "Motion of Ions and Electrons," *Handbuch der Physik*, Springer-Verlag, Berlin, Gottingen, Heidelberg, Germany, vol. 21, p. 386; 1956.

[7] A. Klopfer, "Die Erzeugung Von Hockstvakua mit Getter-Ionenpumpen und das Messen von sehr tiefen Drucken," *Vakuum-Tech.*, vol. 10, pp. 113–118; May, 1961.

[8] J. R. Pierce, "Increasing space charge waves," *J. Appl. Phys.*, vol. 20, pp. 1060–1066; November, 1949.

[9] A. V. Haeff, "The electron-wave tube—a novel method of generation and amplification of microwave energy," Proc. IRE, vol. 37, pp. 4–10; January, 1949.

supply is produced by ionization, the rate of which is proportional to pressure. Starting current is obtained by raising the pressure until oscillation starts in the region of 10^{-6}–10^{-5} mm Hg. The power output does not exceed a few milliwatts and further increases in pressure destroy the oscillation by collision broadening. The linewidth of the oscillation is a few megacycles.




Fig. 5—Gas discharge, split-anode magnetron.

V. Avalanche Noise

If the current drawn by the Penning cell is due to the random formation of electron avalanches, as described in Section II, then this process will give rise to a Schrot noise. In the cell current a fluctuation ΔI will be observed, whose magnitude is given by the following equation

$$\Delta I/I = \sqrt{2qf/I}, \tag{10}$$

where I is the cell current, q is the charge in each avalanche, and f is the bandwidth of the noise. Furthermore, the noise spectrum will have a high-frequency cutoff given by

$$f_c \simeq 1/2\pi\tau, \tag{11}$$

where τ is roughly the width of an avalanche in time. In one set of measurements, noise of this type was found. These measurements indicated that on the average there were 10^6 electrons in each avalanche and that over the pressure range 10^{-8}–10^{-6} mm Hg the time width τ of the avalanche was given by the equation

$$\tau = 10^{-10}/P_{mm} \text{ seconds}, \tag{12}$$

where P_{mm} is the pressure in mm Hg. Eq. (12) is exactly what one would expect, since the radial rate of electron diffusion is proportional to pressure.

Unfortunately, additional work has shown that noise of this type is generally obscured by other processes, and avalanche noise seems to be an incidental rather than a characteristic feature of the discharge.



Fig. 6—Cathode sputtering pattern produced by 9 cells.

VI. Instabilities

Observation of the ion sputtering patterns on the cathodes of a Penning cell frequently show the existence of crossed or star-shaped sputtering patterns, particularly if the anode is not cylindrical. In Fig. 6 is shown a photograph of a cathode that has been bombarded by a set of nine $\frac{1}{2}$-inch-square anodes in a parallel array. An eight pointed star is sputtered out of the cathode opposite each cell with the center of the star on the cell axis. The sharp lines of the star are well-defined indentations formed by the removal of cathode material. Cylindrical cells produce only a pit in the center of the cathode, as noted in Section III, 5). If, however, a slightly elliptical cell is used, a cross is formed in the cathode such that the lines of the cross coincide with the major and minor axes of the ellipse. Visual observation has shown that these sputtering patterns are, in fact, images of an identical pattern appearing in the discharge itself. In Fig. 7 is shown a photograph of the discharge as it appears in a 2-in-square anode. This shows a pattern identical in form with the sputtering pattern from a $\frac{1}{2}$-in-square anode in Fig. 6. The luminous lines of the discharge lie in radial planes containing the axis and can be observed only by looking through a transparent screen cathode directly along the axis of the cell.

These remarkable patterns are believed to arise from an instability of the discharge which occurs in the pressure range 10^{-5}–10^{-4} mm Hg. We may speculate on the mechanism of such an instability.

Instabilities may arise from electrostatic oscillations of the electron cloud of the form discussed by Trivelpiece and Gould.[10] In this case the Penning anode will act as an open-circuited section of waveguide containing an electron cloud. Oscillations may be set up with a sinusoidal variation in amplitude along the longitudinal axis and a distribution of radial nodes not unlike those formed in a vibrating plate. The frequencies of such oscillations will lie somewhat below the plasma frequency. The star-shaped sputtering patterns may be the images of such radial nodes, where the image itself is formed by RF gradient focusing of the ions. In general, the function of anode asymmetry is to lock the azimuthal position of the instability to the laboratory coordinates.



Fig. 7—Appearance of the discharge as viewed along the axis of a 2-in-square anode. Pressure $\simeq 10^{-4}$ mm Hg.

Another form of instability which arises in crossed field devices has been discussed by Bunemann,[11] and by MacFarlane and Hay.[12] This instability gives rise to the formation of radial spokes in the discharge which may or may not be rotating. If, as in our case, the spokes are not rotating, the instability condition is approximately that the electron cloud rotates through these spokes at a rate such that the frequency of perturbation in the frame of reference of the electron is equal to the local plasma frequency.

Pease[13] discussed a third form of instability, giving rise to radial spokes of oscillating amplitude. In one form of his instability the radial-oscillation frequency is equal to the cyclotron frequency/$\sqrt{2}$ and the resulting spokes would produce a cross-shaped sputtering pattern such as we observe in elliptical cells. At this time, however, the true mechanism for our instability is unknown.

VII. Conclusions

The large space-charge depression of potential on the axis of a Penning discharge has been measured. This measurement verifies the prediction that the anode traps a very dense cloud of electrons and that space-charge fields play a dominant role in the behavior of the discharge. The theory of uniform distribution of space charge has been supported by a measurement of the angular drift frequency of the electron cloud. A Schrot type of avalanche noise may occur in Penning discharges, but it is not essential to the existence of the discharge. Therefore the operation of the discharge cannot be explained by simple diffusion theory alone. Radial instabilities of unknown origin appear in the high-pressure end of the high-vacuum discharge region. These are responsible for the star-shaped sputtering patterns that have been observed on the cathodes of the discharge cell. The high-vacuum Penning discharge may be used as an ion gun, in which case it produces a naturally collimated, very intense ion beam of well-defined energy.

VIII. Acknowledgment

The authors are particularly indebted to S. L. Rutherford, S. L. Mercer, and E. Hodges for their assistance in the completion of this work.

[10] A. W. Trivelpiece and R. W. Gould, "Space charge waves in cylindrical plasma columns," *J. Appl. Phys.*, vol. 30, pp. 1784–1793; November, 1959.

[11] O. Bunemann, "A small amplitude theory for magnetrons," *J. Electronics and Control*, vol. 3, pp. 1–50; July, 1957.

[12] G. G. MacFarlane and H. G. Hay, "Wave propagation in a slipping stream of electrons," *Proc. Phys. Soc. (London) B*, vol. 63, pp. 409–427; May, 1950.

[13] M. C. Pease, "Time dependent electron flow," *J. Appl. Phys.*, vol. 31, pp. 70–76; January, 1960.

Generation and Application of Highly Ionized Quiescent Cesium Plasma in Steady State*

J. Y. WADA†, MEMBER, IRE, AND R. C. KNECHTLI†, MEMBER, IRE

Summary—**A method of generating highly ionized quiescent plasmas in steady state is presented. Plasma densities in excess of 4×10^{12} ions/cm^3 at greater than 90 per cent ionization have been obtained. The validity of double probe measurements of plasma density and temperature in the presence of a dc magnetic field up to about 1500 gauss has been established. The recombination coefficient α of highly ionized cesium plasmas up to densities exceeding 4×10^{12} ions/cm^3 has been found to be equal to or less than 3×10^{-11} cm^3/sec, at least an order of magnitude smaller than the lowest value published to date. A valuable technique for basic as well as applied plasma research has thus been developed and directly applicable results obtained.**

I. Introduction

THE most commonly used method of generating a laboratory plasma is by means of electrical discharges. Typical characteristics of such plasmas are low percentage ionization, instabilities, and oscillations. Furthermore, a thermal equilibrium condition of the electrons and ions is not normally obtained in steady-state operation. For these reasons, a need for a new method of generating highly ionized quiescent plasmas of useful density in steady state has long been recognized. The possibility of generating a quiescent plasma by means of thermionic electron emission combined with resonance ionization (contact ionization) of cesium vapor was reported a number of years ago.[1] The plasma produced by this new method overcomes the aforementioned difficulties encountered with electrical discharges; such a plasma then makes possible a systematic and conclusive investigation of the properties of fully ionized quiescent plasmas. More recently, the results of experimental investigations of such a cesium plasma at a number of laboratories have been reported.[2–5] A brief account of the experimental results obtained at our laboratory was published earlier.[6] The purpose of the present paper is to give a more extensive and detailed description of the apparatus and of those experimental results obtained since the earlier publication.

* Received by the IRE, September 5, 1961. Part of this work was supported by the Office of Naval Research and by the Advanced Project Research Agency.

† Hughes Research Labs., Malibu, Calif.

[1] R. C. Knechtli and W. Knauer, "Low-temperature high-density plasmas," *Bull. Am. Phys.*, ser. 2, vol. 3, p. 81; January, 1958.

[2] R. C. Knechtli and J. Y. Wada, "Generation and measurement of highly ionized quiescent plasmas in steady state," *Bull. Am. Phys.*, ser. 2, vol. 5, p. 366; June, 1960.

[3] R. B. Hall and G. Bekefi, "Cesium plasma," *Bull. Am. Phys.* ser. 2, vol. 5, p. 314; April, 1960.

[4] G. S. Kino, "Thermal Generation of a Fully Ionized Plasma," LMSD Fifth Annual Symp.; December 16–17, 1960.

[5] N. Rynn and N. D'Angelo, "Device for generating a low temperature highly ionized cesium plasma," *Rev. Sci. Instr.*, vol. 31, pp. 1326–1333; December, 1960.

[6] R. C. Knechtli and J. Y. Wada, "Generation and measurement of highly ionized quiescent plasmas in steady state," *Phys. Rev. Letters*, vol. 6, pp. 215–217; March, 1961.

II. Generation of Highly Ionized Quiescent Plasma

A quiescent highly ionized cesium plasma is generated and maintained in steady state in the apparatus sketched in Fig. 1. This apparatus consists of two plasma emitters facing one another and immersed in a homogeneous axial uniform magnetic field as shown by B_0 in Fig. 1. Each plasma emitter consists of a tantalum disk heated to thermionic emission temperature by electron bombardment from an auxiliary cathode. In order to ensure an electric field free plasma region, the auxiliary cathode is completely isolated from the plasma. The whole device, including the hot tantalum plates, is placed in a vacuum tight enclosure and thoroughly outgassed at an elevated temperature. The pressure of background gases other than cesium vapor is kept at all times on the order of 10^{-7} mm Hg or less in order to keep the effect of these gases negligible. Such a condition is maintained with the use of a vac-ion pump attached to the apparatus. Although this vac-ion pump is operated only when the cesium vapor pressure is lowered by cooling the enclosure wall to subzero temperatures, and though it is turned off during experiments to avoid pumping of cesium, the background gas pressure does not exceed the order of 10^{-7} mm of Hg at any time. The cesium vapor pressure is controlled by admitting an excess of cesium metal into the apparatus after a thorough outgassing, and by accurately controlling the temperature of the enclosure walls. A direct measurement of the cesium vapor pressure is made during the operation by measuring the saturation Cs^+ ion emission from a hot tungsten filament installed in the enclosure.

In the apparatus of Fig. 1, ions are emitted by contact ionization of the cesium on the hot tantalum disks; simultaneously, electrons are emitted thermionically from the same disk. Thus, plasma is continuously generated at both ends of the plasma column at a rate controlled by the neutral cesium vapor pressure. Since these hot tantalum disks facing each other act as plasma emitters, there is no loss of plasma at either end of the plasma column. Further, a relatively modest dc magnetic field (of the order of a few hundred gauss) is sufficient to make plasma diffusion in the radial direction negligible. This technique results in a well-defined quiescent plasma column, as indicated in Fig. 1.




Fig. 1.




Fig. 2.

Langmuir probes were used to measure the plasma characteristics (ion density, electron temperature) because of the inherent simplicity of the probe technique. These probes were used as double probes, in order to minimize the perturbation introduced by them in the plasma; their dimensions also were kept relatively small. Such double probes were installed at the midplane between the two emitters. Each set consists of two 0.025-mm-diameter tungsten wires spaced approximately 3 mm apart and connected with small springs to the tungsten pins sealed on through the glass envelope. One set is placed near the axis of the plasma column; the other set is located a short distance away from the main plasma column. Because of the presence of a dc magnetic field, the validity and interpretation of this double probe method of measurement could be subject to question. Our experimental results described in Section IV did, however, substantiate our theoretical expectation that double probe measurements, even in the presence of a dc magnetic field up to at least 1500 gauss, are reliable under the conditions of our measurements (probe dimensions, spacing, and sheath thickness—all smaller than the ion cyclotron radius).

Using these probes, the characteristics of the emitter and some properties of the cesium plasma generated in this apparatus have been investigated. The results are summarized below.

A. Radial Density Distribution

For a first-order evaluation of the radial density distribution of the plasma column generated in the apparatus shown in Fig. 1, this apparatus was used with one plasma emitter operating, the other being kept cold. The angle of the dc magnetic field with respect to the axis of the tube was then continuously changed so as to sweep the plasma column across the probes (three fixed probes at different radial positions were used in this experiment). The probe measurements of plasma density as a function of magnetic field orientation yielded the profile shown in Fig. 2. Typically, the plasma density at the radial distance beyond $1.4R_0$ (R_0 is the radius of the emitter) is smaller than one-tenth the density near the center of the plasma column.

B. Effect of Emitter Temperature on Stability of Plasma

In Fig. 3 the effect of the emitter temperature on the plasma density is shown for a fixed neutral cesium vapor pressure. At sufficiently high emitter temperatures, the rate of the thermionic electron emission exceeds the rate of ion generation; then the plasma density is dependent only on the cesium vapor pressure and is nearly independent of the emitter temperature. On the other hand, if the emitter temperature is made lower, so that the rate of ion generation is greater than the thermionic emission rate, then the rate of plasma generation will be limited by the rate of electron emission. This is borne out by the measurement of plasma density vs emitter temperature shown in Fig. 3. This measurement indeed indicates that for $J_- < J_+$ (*i.e.*, $T < 2000°K$ in Fig. 3),

$$n_+ = n_- = \frac{2J_-}{ev_+},$$

where J_+ and J_- are respectively the electron saturation current density[7] and ion saturation current density available at each plasma emitter. (The factor two arises from the fact that two plasma emitters are operating.)

At relatively low temperatures, a positive space-charge sheath on the thermionic emitter surface is formed as a result of excess ion generation. Then the thermionic electrons are accelerated across the positive ion space-charge sheath and are therefore expected to gain energy. This excess energy may manifest itself either in form of noise, fluctuations, oscillations, excess electron velocity, or excess electron temperature. In our experiments, fluctuations of the potential of a floating

[7] H. A. Jones and I. Langmuir, "The characteristics of tungsten filament as functions of temperature," *GE Rev.*, vol. 30, Part I, pp. 310–319; June, 1927; Part II, pp. 354–361, July, 1927; Part III, pp. 408–412, August, 1927.

The experimental data given in Section II-B has been obtained with a tungsten plasma emitter. The general discussion and conclusion of this section, however, also do apply to tantalum emitters with an appropriate translation of the temperature scale by approximately 120°K towards lower temperatures.





Fig. 3.






Fig. 4.

probe were actually observed when an ion sheath was present at the plasma emitters (excess ion emission; $T<1900°$K in Fig. 3). These fluctuations were observed with a high frequency and sensitive oscilloscope connected to the probe. They occurred at frequencies approximately in the range of 10 to 100 kc with an amplitude on the order of 0.04 v, decreasing as the temperature increased. These fluctuations disappeared when the emitter temperature was raised to the point where no more ion sheath was formed at the emitter ($J_{-\text{sat}} > J_{+\text{sat}}$; $T>1900°$K in Fig. 3).

C. Measurement of Degree of Ionization

The results of a typical set of measurements of cesium plasma density and neutral cesium density are shown in Fig. 4. The corresponding values of the degree of ionization ν of the plasma are shown on the same figure. It may be observed that up to a density higher than $n_+ = 10^{12}$ ions/cm³, a plasma with a degree of ionization $\nu \approx 90$ per cent has been obtained. It is interesting to point out that the value $\nu = 90$ per cent corresponds approximately to the degree of ionization expected by taking into account the plasma loss on the probes as long as the volume recombination is negligible. At higher densities volume recombination should be more pronounced and reduce the degree of ionization of the plasma with increasing plasma density. In fact, by the measurement of the percentage ionization, the value of the recombination coefficient may be determined experimentally. The discussion of this experiment and the results obtained will constitute the next section.

It should be noted that a highly ionized quiescent plasma can easily be generated with the technique described here. Such a plasma in steady state constitutes a valuable experimental tool to the investigation of the properties of highly ionized plasma in basic as well as applied plasma research. In the following sections, two of many possible applications of such quiescent cesium plasmas are considered in some detail.

III. Measurement of Recombination Coefficients

An immediate application of our highly ionized quiescent cesium plasma is the measurement of the recombination properties of ionized cesium ions, *viz.*, the coefficient of recombination. As was mentioned earlier, the plasma diffusion in the radial direction may be made negligible with the application of a dc magnetic field. Thus, in the presence of an axial dc magnetic field, the first-order cause for plasma loss in this plasma column is volume recombination, together with plasma losses on the small probes used to measure the plasma density and temperature. The plasma loss on the probes is readily taken into account, and its effect on the degree of ionization of the plasma is, to a first-order approximation, independent of plasma density. The degree of ionization of the plasma then is determined by the condition that the rate of cesium ion generation on the plasma emitters be equal to the rate of cesium ion loss by volume recombination and by surface recombination on the probes. Since the rate of volume recombination is proportional to the recombination coefficient, the latter is found directly from the measurement of the degree of ionization as a function of plasma density. More specifically, we can write the rates of plasma generation and plasma surface and volume recombinations in the following manner:

$$\left(\frac{\partial N_+}{\partial t}\right)_{\text{gen}}$$

$$= (2A_e)\left(\frac{\bar{v}_0}{4}\right)n_0 \text{ (rate of plasma generation)}$$

$$\left(\frac{\partial N_+}{\partial t}\right)_{\text{probe}}$$

$$= (A_p)\left(\frac{\bar{v}_+}{4}\right)n_+ \text{ (rate of plasma losses to probes)}$$

$$\left(\frac{\partial N_+}{\partial t}\right)_{\text{volume}}$$

$$= \alpha n_- n_+ A_e L$$

$$= \alpha n_+^2 A_e L \text{ (total volume recombination),}$$

where

$n_- = n_+ =$ plasma density
$n_0 =$ cesium neutral density
$2A_e =$ total combined area of two emitters (A_e is approximately equal to the plasma column cross-sectional area)
$A_p =$ total effective area of probes (including the ion sheath effects)
$\bar{v}_0/4 =$ average thermal velocity of neutral cesium directed toward the plasma emitter surface
$\bar{v}_+/4 =$ average thermal velocity of the positive cesium ion directed toward the effective probe surface
$L =$ distance between two plasma emitters.

Equating the rate of cesium ion generation on the emitter to the rate of cesium ion losses by volume recombination and on the probes, the recombination coefficient can be obtained explicitly in terms of measurable quantities,

$$\alpha = \frac{\bar{v}_0}{2Ln_+}\left[\frac{1-\nu}{\nu} - \frac{A_p\bar{v}_+}{2A_e\bar{v}_0}\right],$$

where $\nu = n_+/(n_+ + n_0)$ is the measured degree of ionization.

In an apparatus of the type sketched in Fig. 1, a plasma column with density up to about 4×10^{12} ions/cm^3 has been generated and sustained between two hot tantalum emitters which are spaced 10 cm apart. The corresponding degree of ionization (as shown in Fig. 4) at the density of 4×10^{12} ions/cm^3 yielded with the above relation an upper limit for the volume recombination coefficient α of

$$\alpha \leq 3\times10^{-11}\frac{\text{cm}^3}{\text{sec}}.$$

To evaluate the significance of this result, it is appropriate to compare it with the measured values of a reported to date in the literature[8,9] and with the values which may theoretically be expected.

The values published to date[8,9] for α all are larger than our measured limit $\alpha \leq 3\times10^{-11}$ cm^3 sec^{-1}. (The lowest reported value is that of 3×10^{-10} cm^3 sec^{-1} given by Mohler.[8]) Insofar as dissociative recombination was invoked in the published experiments[8,9] to explain these relatively high values of α, the fact that our experiment leads to lower values of α is not too surprising. In our experiment, the high degree of ionization and low prevalent neutral density should greatly reduce the probability of formation of molecular ions and, therefore, of dissociative recombination.

The minimum value of a α to be theoretically expected corresponds to pure radiative recombination and is about equal to 10^{-12} cm^3 sec^{-1} at an electron temperature of 2000°K. This is not inconsistent with the result of our measurements.

Finally, considering the collision of two electrons with one ion in a highly ionized plasma leads to the recombination theory recently proposed by D'Angelo.[10] This should apply to our experimental conditions; for an electron temperature $T = 2000$°K and an electron density of $n_- = 4\times10^{12}$ cm^{-3}, this theory predicts $\alpha \cong 10^{-11}$ cm^3 sec^{-1}, a value which is also consistent with our measurements so far.

To gain a better understanding of recombination in a highly or fully ionized plasma, a measurement of the actual value of α rather than a determination of an upper limit still is called for. This means a modification of our apparatus for measurements at higher plasma densities and cesium vapor pressures. These modifications are presently being undertaken. At the same time, because of the apparently very low value of α, the generation of a highly ionized quiescent plasma in steady state up to densities of the order of 10^{14} cm^{-3} in large volumes may be expected with the type of apparatus shown in Fig. 1. Even higher densities may be feasible in smaller volumes.

IV. Validity of Double Probe Measurements in a DC Magnetic Field

Because double probes are convenient to use with the quiescent cesium plasmas considered here, it was found desirable to verify the validity of double probe measurements in presence of a dc magnetic field. Indeed, while the double probe methods of plasma density and temperature measurements in the absence of magnetic

[8] F. L. Mohler, "Recombination of ions in the afterglow of a cesium discharge," *J. Res. NBS*, vol. 19, pp. 447–456; 1937.
[9] P. Dandurand and R. B. Holt, "Electron density and light intensity decay in cesium afterglows," *Phys. Rev.*, vol. 82, pp. 278–279; April, 1951.
[10] N. D'Angelo, "Recombination of ions and electrons," *Phys. Rev.*, vol. 121, pp. 505–507; January, 1961.

field are commonly accepted,[11] their interpretation in the presence of a dc magnetic field has been subject to question.[12] It is reasonable to assume, however, that as long as the ion cyclotron radius is larger than sheath thicknesses and probe dimensions, the effect of the magnetic field on double probe characteristics may be neglected in a double probe measurement. This statement is based upon the following consideration. As long as the ion cyclotron radius is relatively large, neither the shape of the ion sheath around the floating double probes, nor the ion saturation current to these probes should be greatly affected by the magnetic field; hence, the plasma (ion) density measurements should, to first order, remain unaffected. The rate of electron collection in the retarding field of the floating probes should not be greatly affected by the magnetic field either; even though the electron cyclotron radius may be small, one degree of freedom (in the direction of the magnetic field) remains unperturbed for the electron motion. Hence, the double probe measurement of electron temperature (obtained from the rate of electron collection) should not be greatly affected by the magnetic field. The experimental results presented here substantiate these assumptions.

In the present measurements, plasma density and temperature are measured by means of double probes and interpreted according to classical double probe theory[11] as if no dc magnetic field were present. The plasma density thus obtained from the double probes is then compared with that obtained from a microwave cavity (resonant frequency shift) measurement; the electron temperature from the probes is compared with the pyrometrically measured temperature of the plasma emitter. The prior comparison of the plasma electron temperatures with the plasma emitter temperature by measurements of the mean cyclotron radius had shown these two temperatures to be the same within measuring accuracy for the conditions of the experiment described below.[13]

The cesium plasma used in the present measurements was generated in the apparatus sketched in Fig. 5. A drifting cesium plasma column was formed which extended through the length of a tubular glass envelope up to an end plate. The latter was used mainly to properly align the dc magnetic field. Two sets of double probes are mounted on the glass envelope. The distance between the two sets of probes is sufficient for insertion of an appropriate microwave cavity between them; however, this distance is small compared with the total length of the plasma column in order to a have uniform




Fig. 5.

density over the measured region. Since the plasma considered was well defined and in steady state, the instrumentation was very simple. For the microwave density measurements, as shown in Fig. 5, an *S*-band microwave cylindrical cavity with a proper TM_{010} resonant mode was placed in between the two sets of double probes, over the glass envelope which contained the steady-state plasma column. Since the TM_{010} mode contained only axial and no radial electrical fields (except for the fringe field due to the holes on the cavity end plates), the microwave plasma density measurement would be essentially independent of the applied magnetic field strength.

Each set of double probes consisted of two 0.025-mm-diameter tungsten wires spaced approximately 3 mm apart and welded on to the tungsten pins sealed on through the glass envelope. Two sets of probes were used to determine whether an axial density gradient existed in the plasma column along the cavity interaction region. The double probe plots obtained from these two sets of probes are practically identical for magnetic fields above 300 gauss, thus showing, as expected, negligible plasma density gradient along the microwave cavity.

The measurements were made over the range of magnetic field extending from 300 gauss to 1500 gauss with a plasma emitter temperature (pyrometrically measured temperature of hot tantalum disk) at about 2100°K and with plasma densities between 10^{10} and 10^{11} electrons /cm^3. The emitter temperature was made sufficiently high so that 1) the rate of thermionic electron emission would exceed the rate of ion emission; 2) the possible formation of a positive ion-space charge is eliminated; and 3) the temperature of electrons in the plasma is essentially equal to the emitter temperature. Under these conditions, and with the probe dimensions and spacings given above, sheath thickness, probe dimensions, and probe spacings were small compared with ion cyclotron radius. Double probe characteristics were recorded on an *x-y* recorder; a typical characteristic is shown in Fig. 6. These probe characteristics were interpreted according to the classical theory of double

[11] E. O. Johnson and L. Malter, "A floating double probe method for measurements in gas discharges," *Phys. Rev.*, vol. 80, pp. 58–68; October, 1950.

[12] A. Gutherie and R. K. Wakerling, "The Characteristics of Electrical Discharges in Magnetic Fields," McGraw-Hill Book Co., Inc., New York, N. Y., p. 30; 1949.

[13] W. Knauer, private communication.




Fig. 6.




Fig. 7.

probes in absence of magnetic fields.[11] Because of the small probe diameter, the effect of sheath thickness had to be taken into account;[11] this was also done under the assumption that the effect of magnetic field on sheath thickness was negligible, the sheath being an ion sheath controlled by ion current flow over a distance small compared with ion cyclotron radius. The radius of the plasma column was assumed to be the same as the emitter radius.

The plasma density measurements performed simultaneously with the double probes and with the microwave technique are compared in Fig. 7. Agreement within 30 per cent is shown throughout the entire range of magnetic field used in the experiment. The fact that the discrepancy of 30 per cent between the two measurements is independent of magnetic field indicates a systematic rather than magnetic field dependent error.

The electron temperature of the plasma obtained from the probe measurements was compared with simultaneous pyrometric measurements of the plasma emitter temperature (hot tantalum disk), the latter having already been found equal to the electron temperature of the plasma. The result is given in Table I and shows agreement within 10 to 20 per cent.

The results shown in Fig. 7 and Table I lead to the conclusion that double probe measurements of plasma density and temperature are reliable and are not noticeably affected by the presence of a dc magnetic field, at least under the conditions of the experiments reported above where sheath thickness, probe dimensions, and probe spacing were small compared with ion cyclotron radius.

TABLE I

Plasma Temperature Measurements

Magnetic Field	Plasma Temperature, °K	
B_0, gauss	Double Probe	Pyrometric
300	2450	2100
375	2300	2100
525	2450	2100
675	2300	2100
1050	2360	2100
1350	2170	2020
1350	2250	2120
1500	2450	2100

V. Conclusion

In conclusion it may be stated that the usefulness of a simple technique for generating highly ionized quiescent plasmas of reasonably high density in steady state has been demonstrated, that the validity of double probe measurements in the presence of dc magnetic fields up to at least 1500 gauss has been verified, that a novel and direct technique for the measurement of the recombination coefficient of cesium plasmas has been developed, and that this coefficient has been found so far to be $\leq 3 \times 10^{-11}$ cm^3 sec^{-1} up to plasma densities on the order of 4×10^{12} ions/cm^3.

VI. Acknowledgment

The writers wish to thank W. Bernstein, Drs. A. Fafarman and W. Knauer for helpful discussions, and Dr. A. Fafarman for his contribution to the earlier part of this work. Acknowledgment is extended also to A. W. Robertson for his able assistance in the construction and operation of the experimental apparatus.

A New Approach to Thermionic Energy Conversion: Space Charge Neutralization by an Auxiliary Discharge*

W. BERNSTEIN† AND R. C. KNECHTLI†, MEMBER, IRE

Summary—**The characteristics of an auxiliary discharge thermionic energy converter are derived and compared with experimental results. It is shown that the power expended in the auxiliary discharge can be as low as 10 per cent of the power generated by the converter. Thus, efficiencies of about 25 per cent and power output densities as high as 10 w/cm² can be obtained at temperatures of about 1500°K provided that low work function anodes are developed. The specific advantages of the auxiliary discharge technique over the conventional cesium converters are discussed.**

Introduction

THE development of practical thermionic converters is under active investigation at many laboratories. Desirable requirements for a useful converter include a conversion efficiency of at least 20 per cent, a power output of at least 5 w/cm², a life of at least 1000 hours, and operation in a temperature range consistent with the intended heat source. The usual heat sources include combustion, solar, nuclear, and radioisotope; therefore, a reasonable upper limit to the operating temperature appears to be about 1800°K. In this paper, it will first be shown that it should be possible to realize the desired efficiency and power output density requirements at cathode temperatures of about 1500°K; secondly, that the techniques which have been most intensively investigated do not appear capable of satisfying all the converter requirements; finally, a new technique will be presented which appears to represent a solution to many of these problems.

Simplified expressions for the efficiency and power output density of a converter are given by

$$\eta = \frac{\phi_c - \phi_A - J_0\rho d}{\phi_c + \dfrac{A_r}{A_e}\sigma\dfrac{\epsilon T^4}{J_0}} \qquad P_0 = J_0(\phi_c - \phi_A - J_0\rho d),$$

where

ϕ_c and ϕ_A = the cathode and anode work functions, respectively,
J_0 = collected current density in a/cm²,
ρ = plasma resistivity, if a plasma is present in the interelectrode space,
d = interelectrode spacing in cm,
A_r/A_e = ratio of radiating to emitting areas,
ϵ = emissivity of the cathode, given by

$$1\Big/\left(\frac{1}{\epsilon_c} - \frac{1}{\epsilon_a} - 1\right),$$

σ = Stefan-Boltzmann constant,
T = absolute temperature.

In this expression we have obviously neglected losses associated with the heat conductivity and electrical resistance of the leads, and have assumed that the total current per diode is sufficiently small so that effects of the self-magnetic field can be ignored.

The plasma resistivity arises from interaction of the emitted electrons with ions and neutral particles in the interelectrode space. The charged particle resistivity can be evaluated from the equation derived by Spitzer,[1]

$$\rho_1 = \frac{6.53 \times 10^3 \ln \Lambda}{T^{3/2}}\ \Omega\ \text{cm},$$

and can be reduced only by an increase in the electron temperature. The resistivity due to electron-neutral collisions is evaluated, in the temperature range, by

$$\rho_2 = \frac{(1.3 \times 10^{11})\sigma_c\ \Omega\ \text{cm}}{f},$$

where

σ_c = electron-neutral cross section,
f = fractional ionization,

and can be reduced significantly by an increase in the fractional ionization and an increase in the electron temperature for certain gases.

In order to conveniently determine the optimum performance of a thermionic converter, the equations for efficiency and power output density have been evaluated as functions of cathode temperature in Figs. 1 and 2 for anode work functions of 1.0 and 1.8 ev respectively, under the following assumptions:

1) The output current density is 10 a/cm² at all temperatures and is equal to the temperature limited (saturation) emission current density of the cathode.

* Received by the IRE, August 16, 1961.
† Hughes Research Labs., Malibu, Calif.

[1] L. Spitzer, Jr., "Physics of Fully Ionized Gases," Interscience Publishers, Inc., New York, N. Y.; 1956.




Fig. 1—Converter efficiency as a function of cathode temperature for 1.0- and 1.8-ev anode work functions.




Fig. 2—Converter power output density as a function of cathode temperature for 1.0- and 1.8-ev anode work functions.

2) The cathode thermionic emission obeys the Richardson equation $J = 120T^2 \exp(-e\phi_c/\kappa T)$.
3) Therefore, the value of cathode work function is that which gives 10 a/cm² at the specified temperature.
4) The plasma resistivity is taken to be 0.2 Ω cm; at an interelectrode spacing of 0.2 cm, this corresponds to 0.04 Ω, and a resistive drop of 0.4 volt at 10 a/cm².
5) A conservative value of 0.3 is taken for the effective cathode emissivity.
6) The ratio A_r/A_e is taken to be unity.

As can be seen from Figs. 1 and 2, the desired efficiencies and power output densities are easily obtained at temperatures between 1500 and 1800°K, provided low work function anodes can be developed. The use of higher work function anodes obviously requires a shift toward higher temperature for comparable characteristics. It should be pointed out that this analysis is based on the use of the theoretical emission constant of 120 a/cm² in the Richardson equation. Since almost all materials have experimentally determined emission constants smaller than this value, it is necessary to shift all the curves to slightly higher temperatures.

At present, two approaches to the development of a practical converter have been extensively investigated. In the vacuum converter,[2] which is a low temperature device, the effects of the electron space charge are reduced by the use of very small (0.0005 inch) interelectrode spacings; even at these small spacings the current densities are only about 1 a/cm², and thus the power output density is limited to at most 1 w/cm². The second approach utilizes a plasma in the interelectrode space to eliminate the effects of the electron space charge; the plasma is produced by contact ionization of cesium vapor at the hot cathode.[3] Since the ionization efficiency of cesium vapor at a hot surface falls rapidly for values of surface work function below the cesium ionization potential (3.9 volts), the amount of cesium vapor must be increased in order to maintain the desired plasma density. This leads to a high plasma resistivity, since cesium has a large electron-neutral cross section (3×10^{-14} cm²) at these temperatures; thus, very small interelectrode spacings are required. Under certain conditions, volume ionization related to the current flow in a cesium diode has been observed to far exceed contact ionization, thus significantly reducing this resistance and the small electrode spacing requirement. The mechanism of this "arc mode" is as yet not well understood. No measurements have been published yet to indicate that this process of space charge neutralization could be acceptably economic to permit efficient converter operation at low cathode temperature. At high cesium pressures, cathodes produced by formation of partial cesium monolayers on tungsten appear to represent a solution to the cathode problem. However, the anode is then completely covered with cesium; control of the anode temperature may yield a reduction in anode work function to 1.6 ev, but further reduction appears difficult.

The use of a cesium plasma triode in which the plasma is produced by contact ionization of cesium vapor at a third high work function electrode has been described by Hernqvist.[4] Here, operation at cathode temperatures of about 1500°K at lower cesium pressures and reasonable interelectrode spacings appears possible; however

[2] H. F. Webster, "Calculation of the performance of a high-vacuum thermionic energy converter," *J. Appl. Phys.*, vol. 30, pp. 488–492; April, 1959.

[3] R. L. Hirsh, "Effect of interelectrode spacing on cesium thermionic converter performance," *J. Appl. Phys.*, vol. 31, p. 2064; November, 1960.

[4] K. G. Hernqvist, "Plasma synthesis and its application to thermionic power conversion," *RCA Rev.*, vol. 22, pp. 7–20; March, 1961.

anode work functions less than 1.6 ev do not appear possible. In all cesium devices the problem of containment of high cesium pressures at high temperatures still remains serious and may lead to a significant limitation to the life of converters.

Theoretical Discussion

To escape the difficulties and limitations associated with contact ionization of cesium vapor, we have considered other methods for the production of the plasma in the interelectrode space. The use of an auxiliary discharge appears to represent an attractive method for the production of the required high density plasmas.[5] It will be shown that, in the proposed device, the power required in the auxiliary discharge to maintain the plasma represents only a small fraction of the output power of the converter. Thus, this technique offers many advantages over the cesium techniques, particularly in the temperature range below 2000°K. These advantages include: 1) that both the cathode and anode materials may be independently selected for optimum performance, 2) that the plasma resistivity is low and very small interelectrode spacings are not required, 3) that the problems associated with cesium containment are eliminated, and 4) that standard tube construction techniques can be used throughout. Consequently, the major research effort at this laboratory has been directed toward the development of auxiliary discharge thermionic converters.

One particular auxiliary discharge thermionic converter is shown schematically in Fig. 3; other configurations are obviously possible.[6] Electrons are thermionically emitted from the wires, are accelerated by the applied voltage and ionize the gas in the interelectrode space. As the plasma density increases, a positive ion sheath forms about each wire the thickness of the sheath decreases as the plasma density increases. Since the entire applied voltage appears across the sheath, which is thin at high plasma densities, the electrons are accelerated in passage through the sheath without any interactions, and enter the gas region as a monoenergetic stream. Only those positive ions which randomly strike the ion sheath will be collected to the wires; the remaining ions diffuse to both anode and cathode of the converter. The detailed analysis of this mode of discharge




Fig. 3—Schematic of an auxiliary discharge thermionic converter.

(Langmuir mode) will be found in Langmuir and Jones.[7]

Langmuir has shown that the electron current density emitted from a surface which can be neutralized by a positive-ion current to that surface is given by

$$J_0 = \sqrt{\frac{\overline{M_+}}{m_e}}\, J_+.$$

In the present configuration, the positive-ion current density at the cathode, neglecting recombination losses, is given by $J_+ = (\gamma/2) I_-$, where

γ = ionization efficiency,
I_- = wire emission current/cm² of cathode area.

The neutralized current density possible in the converter is therefore

$$J_0 = \gamma/2 \sqrt{\frac{\overline{M_+}}{m_e}}\, I_-,$$

and the power required to maintain the discharge is

$$P_a = V_a I_-,$$

where

V_a = auxiliary discharge voltage.

[5] The technique of neutralizing large electron currents by an auxiliary discharge produced plasma was first investigated by I. Langmuir (I. Langmuir, "The interaction of electron and positive ion space charges in cathode sheaths," *Phys. Rev.*, vol. 33, pp. 954–989; June, 1929) and later practically demonstrated by Johnson and Webster in the Plasmatron (E. O. Johnson and W. M. Webster, "The Plasmatron, a continuously controllable gas-discharge developmental tube," Proc. IRE, vol. 40, pp. 645–659; June, 1952). Since the requirements for low-power consumption in an auxiliary discharge thermionic converter are far more stringent than in a Plasmatron, it remains necessary to use a mode of auxiliary discharge and a geometry leading to more efficient operation.

[6] While this work was in progress, an auxiliary discharge thermionic converter was described by D. Gabor, "A new thermionic generator," *Nature*, vol. 189, pp. 868–872; March 18, 1961. Although the general concepts and predicted results are similar to those described in this paper, it should be emphasized that the discharge geometry and conditions are quite different.

[7] I. Langmuir and H. A. Jones, "Collisions between electrons and gas molecules," *Phys. Rev.*, vol. 31, pp. 357–404; March, 1928.

In order to conserve the power spent in the auxiliary discharge, a high ionization efficiency, heavy ion, low operating voltage, and low recombination rate are desirable. Each of these parameters will now be discussed in detail.

It appears difficult to obtain a high ionization efficiency in pure noble gases, at electron energies only slightly above the ionization threshold. At these energies, the excitation cross section is about three times as large as the ionization cross section.[8] Since those electrons which produce excitations no longer have sufficient energy to produce ionization, only 25 per cent of the emitted electrons are available for production of the plasma. The probability of cumulative ionization appears small at the electron temperatures expected in these discharges. Thus, at pressures where the mean free path for ionization is comparable to the average path length of the electrons in the device, values of the ratio J_0/I_- of 35 for argon and 70 for xenon may be expected.

The ionization thresholds for the noble gases are 15.7 volt, 13.3 volts and 11.5 volts for argon, krypton, and xenon, respectively. It is, therefore, obvious that higher ratios of J_0/I_- can be obtained at lower voltages for Xe than for A. It should be pointed out, that at applied voltages in excess of about 25 volts, sputtering of the wires by the positive ions, which randomly strike the sheath, will occur.

Recombination may result in a serious plasma loss at high plasma densities. If the recombination process is entirely radiative, the recombination coefficients are sufficiently small that no significant loss can occur. However, dissociative recombination with large recombination coefficients has been observed to occur for all noble gases at pressures of 1 mm Hg in discharge afterglows.[9] Since the electron temperature was only about 300°K and the electron density only about $10^9/cm^3$ in these measurements, it is uncertain whether this process will occur under the present discharge conditions.

The use of mixtures which demonstrate the Penning effect,[10] such as Ne—0.1 per cent A and A—0.1 per cent Hg, appears to represent a method for improving the ionization efficiency and eliminating the possibility of dissociative recombination. In these mixtures, the energy lost in excitation is available for ionization of the contaminant gas; this can result in a significant improvement in the ionization efficiency at electron energies corresponding to the energy required for excitation of the metastable state (11.6 volts in argon). On the other hand, the total pressure of the contaminant gas is sufficiently low that the probability of formation of the molecular ion, required for dissociative recombination, is small and therefore radiative recombination should be the only important recombination process.[9] Thus, in A—0.1 per cent Hg, the ratio J_0/I_- should be about 300, at an applied voltage at 12 volts.

[8] H. S. W. Massey and E. H. S. Burhop, "Electronic and Ionic Impact Phenomena," Oxford University Press, London, Eng.; 1956.
[9] S. C. Brown, "Basic Data of Plasma Physics," John Wiley and Sons, Inc., New York, N. Y.; 1959.
[10] M. J. Druyvesteyn and F. M. Penning, "The mechanism of electrical discharges in gases of low pressure," *Rev. Moden Phys.*, vol. 12, pp. 87–174; April, 1940.

Experiments and Results

A series of experiments was performed to demonstrate the validity of these concepts and specifically to determine the value of J_0/I_- at low voltages and the value of plasma resistance at reasonably high density. An auxiliary discharge converter was constructed using 1 cm^2 Phillips Type B dispenser cathodes as both cathode and anode. The interelectrode spacing is 0.3 cm. For most measurements, the anode is not heated except by radiation from the hot cathode. Three 0.0008-inch tungsten wires, spaced about 0.2 cm apart, are centered in the interelectrode space and are heated by a battery. The measurements are made at a pressure of about 1 mm Hg of A; the base pressure with the cathode at operating temperature is about 2×10^{-7} mm Hg.

A typical current voltage characteristic is shown in Fig. 4. Ratios of J_0/I_- of about 100 and as high as 120 are usually observed at about 1 mm Hg, for J_0 values up to 5 a/cm^2. The ratio decreases at both higher and lower pressures presumably because of a decrease in the ionization efficiency. 500-kc oscillations, which have not been studied in detail, are sometimes observed in the saturation current region.




Fig. 4—Current-voltage characteristic of auxiliary discharge thermionic converter.

The current-voltage characteristic is obviously dominated by resistance; the work function difference appears to be about 0.5 volt. The contribution of the plasma resistance is determined in the following manner: It has been shown that the resistance is inversely proportional to the fractional ionization and consequently to the wire emission current. Therefore, the resistance, determined from the slope of the current-voltage characteristic, is plotted against the reciprocal of the emission current in Fig. 5. An intercept, corresponding to a fixed resistance of 0.43 Ω is found; subsequent measurements showed that 0.3 Ω is present in the leads and 0.1 Ω can easily be attributed to poor contacts in the cathode and anode structures. Under these conditions, the plasma resistance at a wire emission current of 100 ma (which should yield a density sufficient to neutralize




Fig. 5—Total auxiliary discharge converter resistance as a function of the reciprocal of the wire emission current. Saturation current is 3 a/cm², pressure about 1 mm Hg argon, and the auxiliary discharge voltage is 20 volts.

10 a/cm²) is only about 0.04 Ω, an entirely acceptable value. It should, of course, be pointed out that since the plasma resistance is determined by the wire emission current, the resistive drop $J_0\rho d$ is constant for all values of cathode saturation current if J_0/I_- is held constant. It is thus desirable to use as high cathode current densities as possible.

It is not clear, at present, how ratios J_0/I_- as high as 120 are possible in pure argon. It is possible that ions may be reflected from both the cathode and anode with relatively high probability, thus yielding higher plasma densities than expected. Also, the formation of the molecular ion will result in an increase of $\sqrt{2}$ in the ratio; at these densities, dissociative recombination will not introduce a serious loss for argon. It is also possible that the electron temperature may be sufficiently higher than expected so that cumulative ionization is possible. A more detailed study of the discharge processes is in progress.

It should be pointed out that the plasma density is probably not uniform across the cathode surface. The use of rectangular rather than circular cathodes will result in a more efficient use of the wire emission current and will probably lead to even larger ratios of J_0/I_-.

It is obvious that large amounts of power are required to heat the tungsten wires to the temperature required for the emission of 100 ma. However, it is believed that suitable low work function materials may be used to permit emission of this current at temperatures comparable to that provided by radiation and conduction from the hot surface of the main cathode. Direct generation of ac, at any frequency up to 10 kc, is achieved by pulsing the accelerating voltage; no change in the converter characteristics is observed in this mode of operation.

In summary, neutralized currents of 5 a/cm² have been attained at an expenditure of about 1 watt in the auxiliary discharge. If a cathode with a work function of about 2.3 ev is used in conjunction with a 1.0 ev work function anode, then an output power of 4 w/cm² at an over-all efficiency of about 25 per cent is possible at a temperature of about 1500°K. Further reduction of the power consumption in the auxiliary discharge and improvement of over-all efficiency still are possible by selecting a gas mixture more favorable than argon. In conclusion, because high efficiencies seem attainable and because the necessity for cesium vapor is obviated, it is believed that this approach represents an attractive solution to the development of long-life, efficient and practical thermionic converters capable of operating at relatively low temperatures, and capable of direct generation of ac.


Acknowledgment

The authors have had many interesting discussions with W. Knauer. The devices were constructed by E. J. Haag and E. L. Nezgoda.

Correspondence

Stability Criteria for a Tunnel-Diode Amplifier*

It is often necessary when designing tunnel-diode amplifiers to keep the generator and load isolated from direct currents. This can be accomplished with the circuit of Fig. 1 which employs the blocking capacitor C_B to isolate the simulated generator and load R_L from the bias supply. The bias supply is isolated from the tunnel diode by the inductance L_B. If L_B is large there will exist some critical value of C_B below which the circuit becomes unstable. This circuit is suited to amplification at frequencies where L_B has a high impedance. Hines[1] has treated the stability of a similar circuit at high and low frequencies. The criteria developed here are general for all frequencies.



$-R$: negative resistance of tunnel diode
C: tunnel-diode junction capacitance
R_S: tunnel-diode series resistance
$L=L_d+L_p$: tunnel-diode lead inductance plus external "peaking inductance" of the shorted length of line used in the amplifier
C_B: coupling capacitance (dc blocking condenser)
L_B: bias T inductance (RF choke)
R_B: battery circuit resistance
V: bias voltage
R_L: load resistance seen by tunnel diode
$\mathcal{L}$: inductance in the load circuit

Fig. 1—Equivalent circuit of bias circuit, tunnel diode, and generator/load.

The differential equations for i, i_1, i_2, i_3 as a function of time are (see Fig. 1):

$$-Ri_1 = \frac{q_2}{C} \quad \text{or} \quad -R\frac{di_1}{dt} = \frac{i_2}{C}, \tag{1}$$

$$-Ri_1 + R_S(i_1+i_2) + L\frac{d}{dt}(i_1+i_2) = V - R_B i - L_B\frac{di}{dt}, \tag{2}$$

$$\mathcal{L}\frac{di_3}{dt} + R_L i_3 + \frac{q_3}{C_B} = V - R_B i - L_B\frac{di}{dt}, \tag{3}$$

$$i_1 + i_2 + i_3 = i. \tag{4}$$

We try solutions in which the currents i, i_3, and i_1 vary as $ae^{\lambda t}$, $be^{\lambda t}$, and $ce^{\lambda t}$, respectively. Stability is achieved if the real part of λ is negative, instability if the real part of λ is positive. We then find from (1)–(3)

$$i_1 = \frac{R_B\lambda + L_B\lambda^2}{(R_S-R)\lambda + (L - RR_SC)\lambda^2 - LRC\lambda^3}\cdot i$$

$$i_2 = -RC\frac{di_1}{dt} = \frac{RC(R_B\lambda + L_B\lambda^2)\lambda}{(R_S-R)\lambda + (L-RR_SC)\lambda^2 - LRC\lambda^3}\cdot i$$

$$i_3 = \frac{-R_B\lambda + L_B\lambda^2}{\mathcal{L}\lambda^2 + R_L\lambda + \dfrac{1}{C_B}}\cdot i. \tag{5}$$

When (5) is used in (4) we find

$$a_4\lambda^4 + a_3\lambda^3 + a_2\lambda^2 + a_1\lambda + a_0 = 0, \tag{6}$$

where

$$\begin{aligned}
a_4 &= RC[L_B(\mathcal{L}+L) + L\mathcal{L}]\\
a_3 &= RC[L_BR_L + \mathcal{L}R_B + L(R_B+R_L)]\\
&\quad - L_B\mathcal{L} - (L - RR_SC)(L_B+\mathcal{L})\\
a_2 &= RC\left[R_BR_L + \frac{L_B+L}{C_B}\right] + (L_B+\mathcal{L})\\
&\quad\cdot(R-R_S) - L_BR_L - R_B\mathcal{L}\\
&\quad - (L - RR_SC)(R_B+R_L)\\
a_1 &= \frac{1}{C_B}[(R_B+R_S)RC - (L+L_B)]\\
&\quad + (R-R_S)(R_B+R_L) - R_BR_L\\
a_0 &= \frac{1}{C_B}[R - R_S - R_B].
\end{aligned} \tag{7}$$

The Routh-Hurwitz criteria that the solutions λ of (6) all have their real parts less than zero are the following:[2]

$$a_0, a_1, a_2, a_3, a_4 > 0 \tag{8a}$$

$$a_1a_2 - a_3a_0 > 0 \tag{8b}$$

$$a_1(a_3a_2 - a_4a_1) - a_0a_3^2 > 0. \tag{8c}$$

Thus, for example, one can see that $a_1<0$ if

$$C_B < C_B^* = \frac{L + L_B - RC(R_S+R_B)}{(R-R_S)(R_B+R_L) - R_BR_L} \tag{9}$$

and that $a_3<0$ if

$$R < R^* = \frac{L_B(L+\mathcal{L}) + L\mathcal{L}}{R_SC(L_B+\mathcal{L}) + C[L_BR_L + (L+\mathcal{L})R_B + LR_L]}. \tag{10}$$

Thus if either C_B or R is less than C_B^* and R^*, respectively, instability results. Eqs. (9) or (10) are sufficient, but not necessary, conditions for instability.

In experimental test of these stability criteria, the following circuit parameters were chosen: $R_B=10\ \Omega$, $L_B=0.3\times10^{-6}$ henries, $R=100\ \Omega$, $C=7\times10^{-12}$ farads, $L=3\times10^{-9}$ henries, $\mathcal{L}=3\times10^{-9}$ henries, $R_S=2\ \Omega$, $R_L=50\ \Omega$ (the tunnel diode used was the GE IN2939). For these circuit values, the quantities a_4, a_3, a_2 and a_0 are all >0 for all values of C_B. The quantities a_1, $a_1a_2-a_3a_0$, and $a_1(a_3a_2-a_4a_1)-a_0a_3^2$ are plotted as functions of C_B in Fig. 2. We see there that instability will result if $C_B<66$ $\mu\mu$f. It was observed experimentally that stability occurred for $C_B=90$ $\mu\mu$f and instability for $C_B=25$ $\mu\mu$f.




Fig. 2—Plot of left sides of (8a)–(8c) vs C_B. Values of circuit elements used in this example are given in the text.

The stability calculation could be performed with respect to any other circuit parameter.

The circuit analyzed here must be considered only as a laboratory model. In a real system R_L is replaced by $Z(\omega)$ depending on the actual generator and load used. A similar analysis will then have to be carried out for a differential equation which is at least one degree higher and possibly also nonlinear.

The authors would like to thank Dr. I. Gerst (State University of New York) for several cogent remarks concerning the Analysis.

H. Boyet
D. Fleri
C. A. Renton
Defense Electronic Products
RCA
New York, N. Y.

* Received by the IRE, October 10, 1961. This work was performed for the Rome Air Dev. Center under Contract No. AF 30(602) 2184.

[1] M. E. Hines, "High-frequency negative resistance circuit principles for Esaki diode applications," *Bell Sys. Tech. J.*, vol. 39, pp. 477–513; May, 1960.

[2] E. A. Guillemin, "The Mathematics of Circuit Analysis," John Wiley and Sons, Inc., New York, N. Y., ch. 6; 1949.

Discussion of a Deflection System for a Flat Television Picture Tube*

Ramberg[1] has given a very interesting analysis of a novel focusing scheme originally proposed by Aiken for a flat television picture tube. The computation of the electron trajectories is based on formulas for the potential distribution given in the Appendix for a basic electrode configuration. The potential distribution in the actual horizontal and vertical deflection systems can then be obtained by superposition from this basic solution.

It is the purpose of this note to give some alternate solutions for the basic configuration of Fig. 15 in Ramberg's paper which appear to have certain computational advantages over that given in the paper. For convenience, the relevant figure is reproduced below as Fig. 1.

Ramberg obtains his basic solution by adding four partial results: a constant, two Fourier integrals which converge rather rapidly for small values of $|z|$, and a closed-form expression. The last part is somewhat complex and requires the solution of a transcendental equation, evaluation of a number of constants and four series. An alternate solution for this part is

$$\frac{1-x}{2}-\frac{1}{\pi}\sum_{m=1}^{\infty}\frac{\cosh m\pi y}{m\cosh m\pi b}\sin m\pi x. \quad (1)$$

It is easily seen that this solution reduces to $\frac{1}{2}$ at $x=0$ and to zero at $x=1$. The coefficients in the series are chosen to make the solution vanish at $y=|b|$ also. For aspect ratios b considered by Ramberg ($b\geqq 1$), the above series converge extremely rapidly. In the central plane ($y=0$), two or three terms of the series are sufficient for the computation of ϕ and the electric field components.

In spite of their rapid convergence, the other terms in Ramberg's expression are also rather cumbersome. In or near the central plane ($y=0$), we can obtain an approximate solution by conformal transformations. The result can then be made accurate by the addition of small correction terms.

For $b\to\infty$, the problem reduces to a two-dimensional one in the xz plane (see Fig. 2) which can be solved by two transformations of the Schwarz-Christoffel type. The result is

$$\phi_\infty = 1-\frac{1}{\pi}\cot^{-1}\left(\frac{e^{-\pi z}+\cos\pi x}{\sin\pi x}\right). \quad (2)$$

If we replace the last part of Ramberg's expression by (1) and then let $y=0$ and $b\to\infty$, we obtain

$$\phi_z = 1-\frac{x}{2}-\frac{1}{\pi}\int_0^\infty \frac{\sinh lx}{\sinh l}\frac{\sin lz}{l}\,dl \quad (3)$$

which must be identical with the closed-form expression given by (2). Making use of this identity, we find that for any aspect ratio b,

$$\phi = 1-\sum_{m=1}^{\infty}\sum_{n=0}^{\infty}A_{mn}\sin m\pi x \cdot\cos[2n+1)\pi y/2b]e^{k_{mn}z} \quad (5)$$

for $z\leqq 0$, and

$$\phi = 1-x-\frac{2}{\pi}\sum_{1}^{\infty}\frac{\cosh m\pi y}{m\cosh m\pi b}\sin m\pi x + \sum_{m=1}^{\infty}\sum_{n=0}^{\infty}B_{mn}\sin m\pi x \cdot\cos[(2n+1)\pi y/2b]e^{-k_{mn}z} \quad (6)$$

for $z\geqq 0$. Here,

$$k_{mn}^2=(m\pi)^2+[(2n+1)\pi/2b]^2. \quad (7)$$

$$\phi(x,0,z)=1-\frac{1}{\pi}\cot^{-1}\left(\frac{e^{-\pi z}+\cos\pi x}{\sin\pi x}\right)-\frac{1}{\pi}\sum_{1}^{\infty}\frac{\sin m\pi x}{m\cosh m\pi b}-\frac{4}{\pi^2}\int_0^\infty\sum_{0}^{\infty}\cdot\frac{\sin(2n+1)\pi x}{(2n+1)\cosh\{b\sqrt{l^2+(2n+1)^2\pi^2}\}}\cdot\frac{\sin lz}{l}\,dl$$

$$+\frac{1}{\pi}\int_0^\infty\left\{\frac{\sinh lx}{\sinh l}-\frac{4}{\pi}\sum_{n=0}^{\infty}\frac{(-1)^n}{2n+1}\frac{\sinh x\sqrt{l^2+[(2n+1)\pi/2b]^2}}{\sinh\sqrt{l^2+[(2n+1]\pi/2b]^2}}\right\}\frac{\sin lz}{l}\,dl \quad (4)$$




Fig. 1.




Fig. 2.

Again, for aspect ratios $b\geqq 1$, the series converge very rapidly so that one or two terms will suffice in most computations. In fact, it is easily estimated that all correction terms account for less than five per cent of the solution. Additional correction terms can be introduced when $y\neq 0$. The closed-form expression in (2) can also be used for the vertical deflection system.

Alternate series expressions for ϕ, that converge rapidly for $|z|>0$, can also be given. We note that ϕ must tend to unity for large negative values of z. For large positive values of z, the potential must approach the distribution given in (1). This suggests the solutions

Matching ϕ and $\partial\phi/\partial z$ at $x=0$, we obtain

$$A_{mn}=B_{mn}=\frac{-4(-1)^{m+n}}{\pi^2 m(2n+1)}\cdot\left\{1-\frac{(-1)^m(2n+1)^2}{(2n+1)^2+(2mb)^2}\right\}. \quad (8)$$

These series are very good for the computation of ϕ as long as $|z|$ is not too small, but even at $z=0$ the convergence is quite satisfactory because of the sign alternations. For the computation of the electric field components, however, this solution is not very satisfactory near $z=0$.

Harry Gruenberg
Syracuse University
Syracuse, N. Y.

Author's Comment[2]

Unquestionably, Gruenberg's series expression (1) for my closed-form elliptic-function expression as well as his closed-form expression (2) for the series corresponding to $b=\infty$[3] can contribute materially to the ease of computation. I had omitted the series representation with respect to z, given by his (5)–(8), since the contribution of the series at values of z sufficiently large to make this representation preferable in the calculation of the field components is of smaller importance.

Edward G. Ramberg
Institut für theoretische Physik
Technische Hochschule Darmstadt
Germany

* Received by the IRE, February 13, 1961.

[1] E. G. Ramberg, "Electron-optical properties of a flat television picture tube," Proc. IRE, vol. 48, pp. 1952–1960; December, 1960.

[2] Received by the IRE, March 16, 1961.

[3] In the corresponding expression for the vertical deflection field given by Ramberg at the bottom left of page 1959, an additive term $(1-y)$ has been omitted on the right side.

A Resonant Slot Parametric Amplifier*

A *C*-band degenerate parametric amplifier has been constructed in which the varactor diode is incorporated as an integral part of a resonant slot or iris. The present configuration is shown in Fig. 1 and uses a Microwave Associates 4254X varactor diode mounted in an end-plate resonant iris. The diode used is self-resonant above the operating frequency and, therefore, inductive irises were employed to resonate the residual capacitance of the diode. Capacitive irises could be used for operating frequencies above the self-resonant frequency of the diode, and in fact, the dam[1] structure is one variation of such a configuration. While the present structure employs an end-plate iris, similar operation could be achieved with guide wall slots as might be applicable in iterative array antennas.




Fig. 1—*C*-band resonant slot amplifier (biasing arrangement not shown).




Fig. 2—Tuning range of resonant slot amplifier.

Current results are quoted on the device operating in a reflecting mode with pump power incident on the opposite face. Different pump arrangements would make possible the operation of this device in the transmission mode. Passive measurements on the device clearly show that its equivalent circuit is essentially the same when the iris is radiating into space as it is when connected to *X*-band waveguide.

The operating or resonant frequency of the iris is dependent, of course, on the parameters of the particular diode in use. The operating frequency, however, can be tuned by either adjusting the slot width (and hence equivalent parallel inductance) or the diode bias (and hence capacitance of the junction). The former adjustment covers a broader range of frequencies, but requires mechanical tuning; the latter is a simple electrical adjustment which may, however, affect operating bandwidth and noise figure if carried too far. In Fig. 2 are plotted resonant frequencies of the structure as a function of bias voltage with slot width as the parameter. It can be seen that either adjustment can effectively control the resonant frequency over a small range of frequencies, and in any practical case the particular application and accessibility of the amplifier would determine the tuning method employed.

Operating in the frequency range of 4.3 to 4.9 kMc, the device has been made to operate at stable gains of up to 20 db. Gain-bandwidth products over this frequency range varied with slot width from 50 to greater than 250 Mc. The values given are for the device operated as a single tuned structure, and additional irises or tuning screws can be used to broaden the response.

By proper diode bias adjustment, the elements can be made to oscillate with the same pump power used in the amplifying mode. In an antenna array, the elements could thus serve dual transmit-receiver functions controlled through diode programming.

The device reported in this letter is similar in concept to a tunnel-diode[2] amplifier recently reported as the result of an independent study.

J. W. Amoss
G. P. Rodrigue
Sperry Microwave Electronics Co.
Clearwater, Fla.

* Received by the IRE, October 13, 1961.

[1] B. C. DeLoach, "Waveguide parametric amplifiers," presented at the Internatl. Solid-State Circuits Conf., Philadelphia, Pa., February 15–17, 1961; *Digest of Technical Papers*, pp. 24–25, February, 1961.

[2] M. E. Pedinoff, "A tunnel-diode slot transmission amplifier," Proc. IRE (Correspondence), vol. 49, p. 1315; August, 1961.

Low-Frequency Noise in Backward Diodes*

The noise temperature of backward diodes was measured over the frequency range from 300 cps to 20 kc. For bias voltages much less than the valley voltage,[1] the noise temperature exhibits the familiar $1/f$ characteristic at frequencies below 1 kc, and is substantially constant at frequencies above 1 kc. Using these devices, a 100-Mc balanced mixer, converting to 5 kc, has exhibited a double-channel noise figure of less than 7 db. This is a 30-db improvement over what would be expected from present day mixers using point contact devices.

Noise Temperature Measurement

Measurements were made using matched pairs of wire wound precision resistors as noise sources. The hot noise source was operated at room temperature (290°K), and the cold noise source at liquid nitrogen temperature (77°K).

The noise temperature of the device under test was obtained in the following manner:

1) The noise output with the 290°K noise source, E_h, was recorded over the desired frequency range.

2) The noise output with the 77°K noise source, E_c, was recorded over the desired frequency range.

3) The operating point of the diode was adjusted so that its dynamic resistance was equal to the hot (and cold) resistance. For this operating point, the noise output of the diode, E_d, was plotted over the desired frequency range.

4) The noise temperature, $\bar{t}$, was calculated from the following expression:

$$\bar{t} = \left(1 + \frac{T_c}{T_h}\right)\left[\frac{\left(\frac{E_d}{E_h}\right)^2 - 1}{1 - \left(\frac{E_c}{E_h}\right)^2}\right],$$

where T_c and T_h are the cold and hot temperatures in degrees Kelvin respectively.

These tests indicate that at bias voltages much less than the valley voltage, the backward diode has no appreciable $1/f$ noise above 1 kc.

Applications and Experimental Results

Comparison of the noise temperature of backward diodes and point contact diodes[2,3] indicates that the backward diode will provide superior performance in mixing applications requiring a low IF frequency, or in detector applications requiring a video output. Although standard junction diodes may have low noise figures at low frequencies, they are not suitable for microwave applications. Their limitations in this area are due to storage time, and due to the parasitic losses associated with the series resistance, r_s. The backward diode has no storage effects, since it operates on the principle of quantum mechanical tunneling, which is a majority carrier phenomenon. In addition, the series resistance associated with it is much smaller than that obtained with normal junction devices, since extremely low resistivity semiconductor material is used in its fabrication.

In order to test the performance of the backward diode in an operational circuit, a 100 Mc mixer was designed for direct down-conversion to 5 kc. A balanced structure was chosen in order to suppress any local oscillator noise that would otherwise degrade the mixer performance. Using a temperature-limited noise diode, a double-channel noise figure of under 7 db was obtained. A similar mixer, using point contact devices, will normally result in a 30–40-db noise figure.

The effect of operation with a high-input frequency was evaluated in a single diode mixer. This circuit was chosen for its simplicity of construction and ease of adjustment. A 30-Mc IF was chosen in order to considerably simplify the measurement of noise figure, and avoid the effects of local

* Received by the IRE, August 18, 1961; revised manuscript received, August 31, 1961.

[1] L. Esaki and T. Yajima, "Excess noise in narrow germanium *p-n* junctions," *J. Phys. Soc.*, (Japan), vol. 13, p. 1281; November, 1958.

[2] B. G. Bosch *et al.*, "Excess noise in microwave mixer crystals," Proc. IRE (Correspondence), vol. 19, pp. 1226–1227; July, 1961.

[3] I. L. Newberg, "Video Frequency Noise Measurements on Microwave Crystal Mixers," Radar Res. Group Electronic Sys. Lab., Dept. Elec. Engrg. M.I.T., Cambridge, Mass., No. 7848-TM-3 and 7848-TM-6, Contract AF 33(616)-5489, Task 50688; May, 1959 and November, 1959.

oscillator noise. The results obtained with this IF frequency should be comparable to those obtained with an audio IF frequency, since both frequencies are beyond the range where $1/f$ noise is important.

A coaxial noise source and double-stub tuner were used from 500 Mc to 2 kMc. Measurements were taken at 8.9 kMc using a waveguide noise source and a sliding probe tuner, coupled to the diode through a waveguide to coaxial transition.

Double-channel noise figures were obtained, ranging from 5 db at 500 Mc, to 14 db at 8.9 kMc. These noise figure measurements were about 2 db lower than anticipated because of the increased local oscillator drive used during this test.

The results of these experiments have indicated that it is possible to operate backward diodes as low noise mixers up to approximately one-tenth the cutoff frequency associated with the valley capacitance and the parasitic series resistance. The experimental data was taken on backward diodes with a cutoff frequency of approximately 20 kMc. With present fabrication techniques, it is feasible to extend the cutoff frequency of these devices to a value in excess of 100 kMc. Indeed, tunnel diodes with cutoff frequencies of twice this value have been reported[4] in the literature.

In conclusion, it should be noted that whereas the performance of the backward diode in this application can be duplicated by the tunnel diode,[5] a backward diode mixer is unconditionally stable for all values of source and load conductances. In addition, the device is less susceptiable to damage from accidental mechanical or electrical overloads than the point contact diode. The combination of these advantages makes the device near-ideal for applications of the type discussed in this note.

The author wishes to thank Dr. S. K. Ghandi and Dr. S. T. Fisher for their helpful suggestions and comments in preparing this material.

W. C. Follmer
Philco Research Center
Blue Bell, Pa.

[4] C. A. Burrus, "Millimeter wave Esaki diode oscillators," Proc. IRE (Correspondence), vol. 48, p. 2024; December, 1960.
[5] M. D. Montgomery, "The tunnel diode as a highly sensitive microwave detector," Proc. IRE (Correspondence), vol. 49, pp. 826–827; April, 1961.

An Extremely Wideband Tunable S-Band Parametric Amplifier*

An S-band nondegenerate parametric amplifier has been developed that can be tuned continuously across a 1000-Mc band from 2100 to 3100 Mc by mechanically tuning the pump circuit, and frequency shifting the pump source. The amplifier can be electronically tuned over a 260-Mc band from 2470 to 2730 Mc by frequency shifting the pump source only.

* Received by the IRE, October 9, 1961.




Fig. 1—Circuit diagram of a parametric amplifier.




Fig. 2—Signal gain vs signal frequency.




Fig. 3—Pump frequency vs signal frequency.

The amplifier uses two commercially available varactors in a balanced circuit configuration similar to that used by Kliphuis[1] (see Fig. 1). The zero bias capacitances of the two varactors were matched to within 10 per cent. At the signal frequency the two varactors appear in parallel, and the inductance Ls is chosen to resonate with the total diode capacitance. The signal circuit bandwidth is very wide, due to the stagger tuning effect of the two diodes in parallel. The self-resonant frequency of the two diodes in series is chosen as the idler frequency. Since there is very little external loading, the idler circuit bandwidth is determined by the Q of the varactors at the idler frequency. Because of the low ratio of idler to signal bandwidth, the voltage gain bandwidth product ($G^{1/2}BW$) is relatively low. With the availability of better varactors that have a higher self-resonant frequency (*e.g.*, "Sharpless Varactors") one will be able to get greater idler bandwidths thereby increasing the $G^{1/2}BW$ product. The wideband transformer T_1 is adjusted to give the desired gain. The use of a fixed tuned idler circuit requires that the pump frequency be varied to tune the signal frequency across the specified signal band. The pump power is introduced through a low Q resonant slot that can be mechanically tuned over 1600 Mc at X band.

Fig. 2 shows the measured midband gain as function of signal frequency, with the pump optimized. The minimum gain across the 1000 Mc tuning range was 15 db. The instantaneous gain bandwidth product was 130 Mc minimum, and was as high as 240 Mc at parts of the signal band. The noise figure of the amplifier was 2.8 db at 2400 Mc and 3.0 db at 2900 Mc. Fig. 3 is the plot of the pump frequency for optimum operation vs signal frequency.

The amplifier may also be electronically tuned for signal frequencies between 2470 Mc and 2730 Mc by varying the pump frequency only. The minimum gain was 18.5 db and the instantaneous $G^{1/2}BW$ was 100 Mc minimum. Such an amplifier can be rapidly tuned across the specified band by using a backward wave oscillator as the pump tube. The total pump power necessary for operation was approximately 50 mw. The diodes were operated with a negative bias of 0.4 volt.

Further work is presently in progress to extend this type of operation to higher frequencies.

Martin Grace
Airtron
Div. of Litton Industries
Morris Plains, N. J.

[1] J. Kliphuis, "C-band nondegenerate parametric amplifier with 500-Mc bandwidth," Proc. IRE (Correspondence), vol. 49, p. 961; May, 1961.

A Tunnel-Diode Frequency Multiplier with Gain*

A frequency multiplier which exhibits a voltage gain for the second and third harmonics has been constructed using the nonlinear negative resistance characteristics of a tunnel diode.

The possibility of using a nonlinear negative resistor to generate harmonics has been discussed by R. H. Pantell.[1] He arrives at an expression for the power gain in the mth harmonic of the form

$$\frac{W_m}{W_0} = \frac{1}{m^2}\left[\frac{h_m}{W_0} - 1\right], \qquad (1)$$

where W_0 = power input from the source, W_m = power output at the mth harmonic.

$$h_m = \frac{1}{4\pi^2}\int_0^{2\pi} dy \int_0^{2\pi} dx \frac{\partial i}{\partial v}\left(\frac{\partial v}{\partial x}\right)^2, \qquad (2)$$

i is the instantaneous current, v is the instantaneous voltage, $x = \omega_m t$ and $y = \omega_0 t$, ω_0 is the source frequency in radians, ω_m is the harmonic frequency in radians, and t is the time.

From (1) it can be seen that when h_m is negative, the right-hand side of (1) may have a magnitude greater than one, and harmonic generation is achieved with a

* Received by the IRE, October 2, 1961.
[1] R. H. Pantell, "General power relationships for positive and negative resistors," Proc. IRE (Correspondence), vol. 46, p. 1958; December, 1958.

power gain. Eq. (2) shows that h_m is negative only when $\partial i/dv$ is negative.

The tunnel-diode characteristic in Fig. 1 exhibits an appropriately large nonlinear negative conductance region. Using the circuit in Fig. 2 we observed second harmonic generation with a voltage gain of 3.7. Both source and second harmonic voltages were measured across the tunnel diode and the corresponding waveforms are shown in Fig. 3.

With a circuit of this type the best results are obtained with a low amplitude drive when the circuit is biased just beyond the region of self oscillation. Additionally, a small value of $\sqrt{L/C}$ improves the waveform.[2]

Although much work remains to be done on reliability and cascading circuits, it appears that a tunnel-diode frequency multiplier could be a reasonable means for translating stable signals from a quartz crystal oscillator from 1 kc up into the 100 kMc region. A frequency translator of this type may have the advantages of working at a constant low signal level and being all solid state.

The authors appreciate the financial support of the University Council on Research and Creative Work.

F. S. Barnes
L. Morris
Elec. Engrg. Dept.
University of Colorado
Boulder, Colo.




Fig. 1—A typical characteristic curve for a tunnel diode.




Fig. 2—The circuit diagram for a second harmonic frequency multiplier.




Fig. 3—The fundamental and second harmonic waveforms as viewed across the tunnel diode.

[2] W. A. Edson, "Vacuum Tube Oscillators," John Wiley and Sons, Inc., New York, N. Y., pp. 42–63; 1953.

Generation of Microwave Harmonics in an Electrodeless Discharge at Low Pressure*

The possibility of RF harmonic power being produced in an ionized gas was considered more than a decade ago [1], [2]. In these studies it was shown that, under special conditions, appreciable harmonic power may be generated in the ionosphere. An early attempt to produce RF harmonics in ionized gases was made by Hanley and Ruhlig [3]. With primary power at 200 Mc they achieved a conversion efficiency of 23 per cent for the second harmonic; however, to the author's knowledge, their technique has not been attempted at microwave frequencies. The main feature of their device appears to be that the coaxial discharge geometry used results in large electric field gradients.

Several workers have produced harmonics using a microwave discharge in a gap in a waveguide post [4]–[7]. Baird [8] has found that these results can be explained by electron density modulation during the RF cycle.

Whitmer [9], [10] and Hill and Tetenbaum [11] have investigated harmonic generation in cyclotron resonant plasmas at microwave frequencies. In the latter case a 15-db conversion loss was obtained for the second harmonic. Conversion to higher harmonics was very inefficient.

In the U. K. harmonics have been produced with arcs in high pressure gas [12]. In recent work using argon at 100 atmospheres, Froome [13] has produced submillimeter harmonics having power of the order of one microwatt. About 3 watts of fundamental power at 35 Gc were used in this experiment.

* Received by the IRE, August 16, 1961.

Bierrum and Walsh [14], also in the U. K., have used a point to plane geometry with pulsed power at 10 cm. Although poor efficiencies were obtained, this group has conclusively established that the harmonic output power is coherent [15].

It seems that several different mechanisms may be operating in these various experiments. The discouraging fact is that all the experiments at microwave frequencies have had very high conversion losses, at best comparable to that obtainable with low power nonlinear resistance diodes. This note reports another approach by which the author has obtained an order of magnitude improvement in efficiency for 10 cm fundamental power. This efficiency equals that achieved by Hanley and Ruhlig [3] at UHF.

The most successful arrangement is shown in Fig. 1 where the discharge vessel is either cylindrical or spherical. For generating the second harmonic the conventional cross-guide arrangement was used with coaxial coupling. A coaxial choke prevented the harmonic power from radiating into the fundamental guide. A sliding short and a tuner were used to match the second harmonic power into the harmonic waveguide. A similar arrangement was used to generate the fourth harmonic using an *X*-band guide. A choke was used to prevent the fourth harmonic from radiating into the *S*-band guide. Other harmonics, however, could radiate into the *S*-band guide. Tuning was provided for these harmonics by the arrangement shown in Fig. 2. The narrow branch of the shunt Tee does not propagate the fundamental, hence movement of the sliding short provides tuning only at harmonics other than the fourth. By this adjustment the fourth harmonic power could be improved by 3 to 4 db.




Fig. 1—Hamonic generator. 1) *S*-band guide, 2) *C*-band guide, 3) quartz discharge vessel, 4) brass post, 5) coaxial choke, and 6) adjustable waveguide short.




Fig. 2—Waveguide arrangement for harmonic generator. 1) *S*-band isolator, 2) directional coupler, 3) *E*/*H* tuner, 4) adjustable tee, 5) harmonic generator (Fig. 1), and 6) harmonic guide tuner.

The experimental conditions are summarized:

Fundamental Power:	10–50 watts CW at 2.9 Gc
Gas used:	air at 0.1 to 0.3 mm of Hg.
Discharge Vessel:	fused quartz, inside diameter 8 mm
Post Diameter:	0.10 to 0.15 inch.

The following conversion efficiencies were observed:

Harmonic:	Conversion Efficiency:
2	− 6.4 db
3	−13.2 db
4	−16.6 db.

All powers were measured with an FXR temperature compensated power meter using Weinschel attenuators. No allowance was made for losses in the fundamental and harmonic tuners.

By studying the effect on the fourth harmonic power it became evident that the best adjustment of the sliding short on the cutoff branch of the shunt Tee probably was one that satisfactorily terminated both the second and third harmonics (*i.e.* reduced the radiation of these harmonics down the fundamental guide).

A special interaction region was not made for the third harmonic. The third harmonic power was measured using each of the second and fourth harmonic generators with an appropriate band-pass filter. Similar results were obtained for both arrangements.

It is noteworthy that the pressures used are considerably below that for optimum breakdown. It is thought that these low pressures reduce the efficiency of the ionizing process and the resulting lower electron density is consistent with a higher electric field strength for a given fundamental power. Too low a pressure results in an unstable discharge and difficult tuning. Preliminary tests with Argon, which is more easily ionized than air, indicate that the most efficient operation occurs in the pressure range 30 to 40 microns of mercury. Further measurements have yet to be completed. In all cases it is important to have a very small capillary in the discharge tube. Capillaries larger than one-half mm in diameter resulted in a jet of plasma extending a few cm up the neck of the discharge tube. The efficiency of conversion under such conditions is reduced.

The operating mechanism in these experiments is not fully understood. It is believed that the very large electric field gradients result in a nonsinusoidal motion for the electrons. A preliminary analysis shows that the energy can be coupled from the fundamental fields to the harmonic fields by this process. It is interesting that such a process, which requires collisions only for the maintenance of the discharge, would be essentially that of a nonlinear reactance. The conversion efficiency consequently is not restricted by the $1/n^2$ limit for the nonlinear resistance.

In these experiments appreciable power may have been absorbed by the tuners. The efficiency of the discharge itself in generating the second harmonic may well have been better than 6 db, the theoretical limit for the nonlinear resistance.

This research is being continued in an attempt to gain a better understanding of the process, and to test the usefulness of this process at higher frequencies.

The author is grateful to Prof. J. L. Yen, who supervised this research and to the National Research Council of Canada for financial assistance.

C. B. Swan
University of Toronto
Toronto, Canada

References

[1] J. Feinstein, "Higher order approximations in ionospheric wave propagation," *J. Geophys. Res.*, vol. 55, pp. 161–170; June, 1950.
[2] K. Försterling and H. O. Wüster, "Über die Entstehung vor oberwellen in der Ionospäre," *J. Atmospheric and Terrest. Phys.*, vol. 2, pp. 22–31; 1951.
[3] T. E. Hanley and A. J. Ruhlig "Harmonic Power from an RF Discharge," Naval Res. Lab., Wash., D. C., NRL Progress Rept.; November, 1953.
[4] M. Uenohara, *et al.*, "*A new high-power frequency multiplier.*" Proc. IRE, vol. 45, pp. 1419–1420; October, 1957.
[5] K. Inada, M. Uenohara, and T. Masutani, "On the harmonics radiating from microwave discharge in air," *Proc. of the 4th Internatl. Conf. on Ionization Phenomena in Gases*, North Holland, vol. 2, pp. 768–773; 1960.
[6] J. R. Baird and P. D. Coleman, "High power gas discharge frequency multiplier," *Proc. of the Symp. on Millimeter Waves*, New York, N. Y., April, 1959, Polytechnic Press, Brooklyn, N. Y.; 19.0.
[7] G. S. Kino, *et al.*, "Millimeter Wave Generation and Amplification in Plasmas," W. W. Hansen Physics Lab., Stanford Univ., Stanford, Calif., Sci. Rept. No. 6, Contract No. AF 19 (604)-5226; December, 1959.
[8] J. R. Baird, "Frequency Conversion in a Plasma," source, University of Illinois, Urbana, Ill. Tech. Rept. No. 6, AEC Contract No. AT 11-1-392; June, 1961.
[9] R. F. Whitmer, "The nonlinear interaction of an electromagnetic wave with an anisotropic plasma," *Proc. of the Symp. on Electronic Wave-Guides*, New York, N. Y., April, 1958, Polytechnic Press, Brooklyn, N. Y.; 1958.
[10] R. F. Whitmer and E. B. Barrett, "Nonlinear interaction of an electromagnetic wave with a plasma layer in the presence of a static magnetic field. I—Theory of harmonic generation," *Phys. Rev.*, vol. 121, pp. 661–668; February 1, 1961.
[11] R. M. Hill and S. J. Tetenbaum, "Harmonic generation in a cyclotron resonant plasma," *J. Appl. Phys.*, vol. 30, pp. 1610–1611; October, 1959.
[12] K. D. Froome, "An 8-volt cold cathode mercury arc emitting microwaves," *Nature*, vol. 179, pp. 267–268, February, 1957; "A new microwave hormonic generator," *Nature*, vol. 184, p. 808, September, 1959; "Millimeter waves from mercury arc harmonic generator," *Nature*, vol. 186, p. 959, June, 1960; "Sub millimeter waves by harmonic generation from cold cathode arcs," *Nature*, vol. 188, p. 43, October, 1960.
[13] K. D. Froome, private communication.
[14] N. R. Bierrum and D. Walsh. "Harmonics from a microwave gas discharge," *J. of Electronics and Control*, vol. 8, pp. 81–90; February, 1960.
[15] N. R. Bierrum, D. Walsh, and J. C. Vokes, "Coherence and bandwidth of a gas discharge harmonic generator," *Nature*, vol. 186, pp. 626–626; May 21, 1960.

A Ruby Laser Exhibiting Periodic Relaxation Oscillations*

A ruby optical maser, with confocal ends[1,2] and an optical axis oriented 90 degrees to the cylinder axis, has been constructed by the Orlando Division of The Martin Company. This maser demonstrates some interesting properties applicable to optical radars.

A ruby measuring 2 inches in length and $\frac{1}{4}$ inch in diameter, was centered in a GE FT-524 flash tube within a magnesium oxide reflector. Threshold energy required was 1350 joules as opposed to 2030 joules required for a zero-degree oriented ruby with flat ends[3] under the same conditions. Total pulse duration realized was approximately 700 μsec. The pulse, exhibiting an initial rise time of less than 0.2 μsec, is depicted in Fig. 1. As would be expected, the output of the 90 degree oriented ruby crystal is linearly polarized. Because of the spherical ends, the half power beamwidth is 7.6 degrees. It should be noted, however, that collimation may be obtained by means of a simple lens system. These measurements were obtained with one of the faces 2 per cent transmitting and the other heavily silvered.

An important and interesting property of this optical maser is reflected in the nature of the relaxation oscillations generated. Part of an output pulse, displayed on an expanded time scale, is shown in Fig. 2. The periodic structure of the output is evident when compared with a similar sampling of the output of a zero-degree oriented ruby on the same time scale, as indicated in Fig. 3. The pulse period, referring again to Fig. 2, varied from 3.5 μsec at 3200 joules input power to 10 μsec just above threshold.




Fig. 1—Envelope of output pulse from 90° oriented ruby with confocal ends.




Fig. 2—Relaxation oscillations of 90° confocal ruby.




Fig. 3—Relaxation oscillations of 0° ruby with flat ends.

* Received by the IRE, September 25, 1961.

[1] G. D. Boyd and J. P. Gordon, "Confocal multinode resonator for millimeter through optical wavelength masers," *Bell Sys. Tech. J.*, vol. 40, pp. 489–508; March, 1961.

[2] A. G. Fox and T. Li, "Resonant modes in a maser interferometer," *Bell Sys. Tech. J.*, vol. 40, pp. 453–488; March, 1961.

[3] T. H. Maiman, "Optical maser action in ruby," *British Commun. and Electronics*, vol. 7, pp. 674; September, 1960. An optical maser using a zero-degree oriented ruby with flat ends was first reported in this article.

This periodic characteristic of the output pulse should greatly enhance the usefulness of an optical maser in an optical ranging application using correlation techniques. In addition, possible application in Doppler ranging, using a ruby laser, is suggested.

R. E. Johnson
W. H. McMahan
F. J. Oharek
A. P. Sheppard
Microwave Laboratory
The Martin Co.
Orlando, Fla.

Broad-Band S-Band Parametric Amplifier*

A nondegenerate S-band parametric amplifier has been constructed that has a 400-Mc bandwidth and a 2.1-db noise figure. Peak gain of the amplifier, as shown in Fig. 1, is 13 db with a 3-db ripple in the band-pass.




Fig. 1—13-db gain, 425 Mc, per cent $G^{1/2}B = 64$ per cent.




Fig. 2—Parametric amplifier equivalent circuit.




Fig. 3—16-db gain, 202 Mc, per cent $G^{1/2}B = 44.2$ per cent.

* Received by the IRE, October 9, 1961. This work was performed for the Bureau of Naval Weapons, Washington, D. C., Contract No. NOw 61-0283-d.

The amplifier utilizes a gallium arsenide pill varactor with a 0.4-pf capacitance.

The equivalent circuit for the amplifier is shown in Fig. 2. The values of L' and C' were chosen so that the idler frequency occurred at essentially the diode self-resonant frequency, and so that a triple-tuned response was achieved. By use of tuning screws appropriately placed on the line, the bandwidth can be shaped to obtain the type of response desired. Two typical responses are shown in Figs. 1 and 3; pump frequency in these instances was about 14.8 Gc. Two hundred milliwatts pump power was used to reverse bias the diode to -3.5 volts. This gave rise to a large value of C_1/C_0, which was necessary to obtain the broad bandwidth.

The author is indebted to B. Vincent for his interesting discussions and helpful suggestions.

Kenneth M. Johnson
Apparatus Div.
Texas Instruments, Inc.
Dallas, Tex.

Magnetoresistive Effect as a Possible Memory Device*

The change of resistance of a material in a magnetic field (Gauss effect) has been utilized primarily as a means of measuring magnetic fields. However, this effect in ferromagnetic materials might be applied in computer storage devices. Characteristics of these devices would be fast switching times and nondestructive readout.

The mechanism of the magnetoresistive effect is an extremely complex one, involving changes in the mean free path.[1] From a phenomenological standpoint, in the ferromagnetic materials, this involves an increase in the resistance when the current and magnetization are in the same direction, and a decrease when they are perpendicular to each other. The potential difference between these two states is then

$$\Delta V = IR_0 \cdot (\delta_1 + \delta_2),$$

where R_0 is the resistance in the demagnetized state and

$$\delta_i = \frac{\Delta R_i}{R_0}.$$

Values of δ_i as high as 0.16 have been reported.[2]

In our work, no attempt was made to optimize our materials; most samples were evaporated films of iron or nickel-iron, approximately one inch long by 0.050 inch wide.

Fig. 1 shows the dependence of magnetoresistive output on the magnetic field for a typical iron film approximately 5000 Å thick. Note the critical field necessary before the film begins to switch. Fig. 2 is a plot of response time vs potential difference for a typical film. This was obtained by calculating the decay time of the discharge network used to switch the film. Care was taken to ensure that the maximum field was always sufficient to saturate the material. The curve (Fig. 2) was plotted as the time constant of the discharge circuit was varied. Note that in both curves, the potential difference is in arbitrary units since it is directly dependent on the current and the resistance.




Fig. 1 -Voltage difference vs field intensity for a typical iron film.




Fig. 2—Response time vs potential difference for a typical thin film.

The feasibility of the magnetoresistive effect memory application was successfully demonstrated by evaporating a nine-element test array. Writing was accomplished by pulse drive lines. Readout was in a cyclic mode at a 10-kc rate.

One additional advantage of a magnetoresistive storage device over other thin film memories might be expected. The most

* Received by the IRE, October 13, 1961.

[1] E. N. Adams and T. D. Holstein, Jr., *J. Phys. Chem. Solids*, vol. 10, p. 254; 1959.

[2] Y. Shirakawa, Tohoku Imperial University, Sci. Rept. No. 27, 532.

critical parameter in an array of this type would be its resistance which is easier to control than the magnetic properties of other thin films.

C. Pettus
T. Young
General Products Div.
Development Lab.
IBM Corp.
Endicott, N. Y.

A Generalized Hildebrand's Method for Nonuniform Transmission Lines*

Second-order ordinary linear differential equations (LDE) with variable coefficients are, in general, solved approximately. However, there is an exact technique to convert the above-mentioned LDE into an LDE having constant coefficients originally developed by Hildebrand,[1] requiring a certain interrelationship among variable coefficients. This communication outlines his method and generalizes it so that the interrelationship among variable coefficients is completely eliminated.

The propagating voltage $V(x)$ of the nonuniform transmission line, having known arbitrary and continuous functions of x for impedance $Z(x)$ and admittance $Y(x)$, gives the following LDE:

$$V''(x) - (Z'/Z)V'(x) - YZV(x) = 0, \quad (1)$$

where the primes are used for derivatives with respect to x in this communication. Introduce a new independent variable w in place of x such that

$$w = f(x), \quad (2)$$

where the precise form of $f(x)$ is to be determined later. Combine (1) and (2),

$$f'^2\ddot{V}(w) + [f'' - (Z'/Z)f']\dot{V}(w) - YZV(w) = 0, \quad (3)$$

where the dots over the symbol represent the derivatives with respect to the newly introduced independent variable w.

Hildebrand's idea is to convert (3) into an LDE with constant coefficients,

$$\ddot{V}(w) + a\dot{V}(w) + bV(w) = 0, \quad (4)$$

where a and b are arbitrary constants. A comparison of (3) and (4) reveals that the coefficients of $\dot{V}(w)$ give a Bernoulli's nonlinear differential equation (NDE) for $f'(x)$, while the coefficients of $V(w)$ give another equation for $f'(x)$. These two $f'(x)$'s must be the same. In order to realize this identity, $Y(x)$ and $Z(x)$ must be interrelated through

$$Y(x) = -bZ(x) \Big/ \left[c + a\int Z(x)dx\right]^2, \quad (5)$$

where c is any constant and $Z(x)$ is arbitrary. The undetermined $f(x)$ becomes

$$f(x) = \int Z(x)\left[d - (a/b)\int Y(x)dx\right]dx, \quad (6)$$

where d is also any constant. The voltage $V(x)$ is given by

$$V(x) = A_1 \exp\left[\left(-\frac{a}{2} + \frac{\sqrt{a^2 - 4b}}{2}\right)\int f(x)dx\right] + A_2 \exp\left[\left(-\frac{a}{2} - \frac{\sqrt{a^2 - 4b}}{2}\right)\int f(x)dx\right], \quad (7)$$

where constants A_1 and A_2 are to be specified uniquely by the imposed boundary conditions on $V(x)$.

The preceding method lacks in generality as $Y(x)$ and $Z(x)$ are interrelated. Past exact analyses[2-5] of nonuniform transmission lines required similar interrelationships between $Y(x)$ and $Z(x)$. In this respect, the approximate method[4] seems to relax the interrelationship between $Y(x)$ and $Z(x)$.

Using the well-known Cayley's factorization technique[6] (3) can be rewritten as

$$[D + p(w)][D + q(w)]V(w) = 0, \quad (8)$$

where the differential operator D is used for (d/dw), and $p(w)$ and $q(w)$ are two undetermined functions of w. The comparison between (3) and (8) gives

$$f'^2(p + q) = f'' - (Z'/Z)f', \quad (9)$$

$$f'^2(\dot{q} + pq) = -YZ. \quad (10)$$

Eliminate p from (9) and (10) so that a generalized Riccati's NDE for q is obtained, and

$$f'q'(x) + q(x)[f'' - (Z'/Z)f'] - f'^2q^2(x) = -YZ, \quad (11)$$

where (12) has been used,

$$\dot{q} = \frac{dq(w)}{dw} = \frac{dq(x)}{dx}\frac{dx}{dw} = \frac{q'(x)}{f'(x)}. \quad (12)$$

A curious thing is that (11) is also a Riccati's NDE for $f'(x)$. This peculiarity happens to be a mere coincidence.[7] The recent communication[3] has shown how to solve (11) if variable coefficients are properly interrelated. Using the form of $(P_1/R_1)' = Q_1$, the following equation is derived easily:

$$f'' - (Z'/Z)f' = +(f + B_1)YZ, \quad (13)$$

where B_1 is a constant of integration.

If $f(x)$ is to be determined from (13), this becomes an impossible problem for variable and independent $Y(x)$ and $Z(x)$. It is proposed to use (13) in a different fashion. If $Z(x)$ and $f(x)$ are independent functions, $Y(x)$ should be given by (13). The remaining task to retrieve the propagating voltage $V(x)$ is a mechanical routine, and it is omitted here.

It is interesting to observe a simple example for which $Z(x) = 1$ (const.) and $Y(x) = x$. This *assumed* nonuniform line gives a nonhomogeneous Airy's differential equation,

$$f'' - xf = xB_1. \quad (14)$$

Using Airy's functions, $Ai(x)$ and $Bi(x)$, (14) is readily solved. This example was chosen intentionally for using an Airy's equation. However, in practical situtations for tapered lines or matchings, $f(x)$ will not be solved with ease for given independent $Z(x)$ and $Y(x)$. It would be of value if $f(x)$ and $Z(x)$ were systematically varied so that the minimum reflection coefficient would be realized for a given taper length. A substitution of (13) into (1) provides

$$V''(x) - \frac{Z'}{Z}V'(x) - \left[\frac{\frac{Z'}{Z}f' - f''}{f + B_1}\right]V(x) = 0. \quad (15)$$

The end result has shown that (15) is solved exactly for arbitrary $Z(x)$ and $f(x)$ which are independent of each other, provided $f'(x)$ is not zero.

The author wishes to express his deep gratitude to Prof. F. B. Hildebrand, Dept. of Math, M.I.T., for the help received in the literature search of the mathematical method involved in this note.

Iwao Sugai
ITT Federal Labs.
Nutley, N. J.

* Received by the IRE, June 16, 1961; revised manuscript received, August 10, 1961.

[1] F. B. Hildebrand, "Advanced Calculus for Engineers," Prentice-Hall Inc., New York, N. Y., p. 50; 1948.

[2] I. Sugai, "The solutions for nonuniform transmission line problems," Proc. IRE (Correspondence), vol. 48, pp. 1489–1490; August, 1960.

[3] I. Sugai, "A new exact method of nonuniform transmission lines," Proc. IRE (Correspondence), vol. 49, pp. 627–628; March, 1961.

[4] I. Sugai, "D'Alembert's method for nonuniform transmission lines," Proc. IRE (Correspondence), vol. 49, pp. 823–824; April, 1961.

[5] I. Sugai, "Riccati's and Bernoulli's equations for nonuniform transmission lines," IRE Trans. on Circuit Theory (Correspondence), vol. CT-8, September, 1961.

[6] E. L. Ince, "Ordinary Differential Equations," Dover Publications Inc., New York, N. Y., pp. 128–129; 1956.

[7] I. Sugai, "A class of solved Riccati's equations," *Elec. Commun.*, vol. 37, pp. 56–60; May, 1961.

The Radar Cross Section of the Moon*

Our theory[1,2] on the scattering from the moon's surface has been criticized in many places.[3,4] We were interested in determining

* Received by the IRE, September 18, 1961.

[1] T. B. A. Senior and K. M. Siegel, "A theory of radar scattering by the moon," *J. Res. NBS*, vol. 64D, pp. 217–229; May–June, 1960.

[2] K. M. Siegel, "Radio Characteristics of Lunar Surface Materials," presented at 12th Internatl. Astronautical Congress, Washington, D. C.; October 4, 1961.

[3] V. A. Hughes, "Roughness of the moon as a radar reflector," *Nature*, vol. 186, pp. 873–874; June 11, 1960.

[4] H. S. Hayre, "Radar scattering cross section—applied to moon return," Proc. IRE (Correspondence), p. 1433; September, 1961.

the electromagnetic constants and the thermal constants of the lunar surface. We were not interested in determining, unless it could be determined easily, the topography of the lunar surface. We recognized that under various propagation conditions the moon's return faded and, in fact, looked like something which was very difficult to analyze on a point-by-point basis or on a slip-of-film-by slip-of-film basis. We recognized very early that significant efforts could be made by radar to map the surface of the moon. Pettingill has made an excellent start in this direction. It was not our concern when analyzing the early lunar radar data to pick out any scattering centers on the surface of the moon, but simply to state that the key scattering centers could be found and to point out that the data we had analyzed suggested that they were approximately 5–10, which number was later increased to "of order 30." We stated that by using the experimental results of modulation loss as determined by Trexler and Youmans and by analyzing the experiments of Aarons, we could predict the maximum radar returns under good propagation conditions at all wavelengths between 100 and 10,000 Mc, and at all pulse lengths. We have been successful,[1,2] in showing that all radar data of the lunar surface were, in fact, in agreement with our predictions as far as this maximum return under optimum propagation conditions is concerned.

Apparently our operational definition of smooth as opposed to rough has not been well understood, and it would appear that the criticisms of our work (for example, by Hughes[3] and Hayre[4]) have been mainly because of this. We were interested in finding out if there was a significant number of perturbations the order of magnitude of a wavelength contributing to the returns from the key scattering centers on the surface of the moon, and we pointed out that a direct measure of the roughness effect could be obtained from a comparison of orthogonal polarizations. We stated that if the differences between orthogonal polarizations were large (10–40 db), then there could not be a significant number of such perturbations dominating the return; we also stated that if the returns from the key scattering centers showed differences of this magnitude, there could be no significant returns from perturbations the order of a wavelength for all radar wavelengths, *e.g.*, 100 Mc to 10,000 Mc, and as a result the moon could be considered a quasi-smooth surface in those regions. We went on to determine the electromagnetic constants for the first key scattering center, and later work showed these values to be in reasonable agreement with the average values obtained for the total lunar surface by radiation data.[5,6] Authors have used other definitions of rough and smooth to criticize our results which, in fact, we feel are not comparable. For example, at long pulse lengths under usual propagation conditions, if there are many scattering centers in the beam, one would expect a good approximation of the return to come from the random phase addition of these many scatterers. If, then, one analyzes the addition function and finds the phase variation is such as to agree with what one could have derived from random phase conditions from earth, then one has a tendency in this phase sense to state that if there are many scatterers present the surface is "rough." Under our definition the surface polarization-wise could still be smooth. For long pulse length returns we would expect to obtain, under normal propagation conditions, typical maximum cross sections which would be associated with the random phase additions from 30 scattering centers, for example. We therefor feel that the statistical evidence presented[3,4,7,8] does not bear on our definition for quasi-smooth. In other words, 30 smooth scattering areas which were in the beam simultaneously and whose phase was such as to vary in a random fashion with height, could agree with the definitions of rough as given[3,4,7,8] but simultaneously would be smooth under our definition. We hope this may clear up some of the arguments that have existed in this field, particularly those arguments which are more concerned with nomenclature than with physics.

T. B. A. Senior
K. M. Siegel
The University of Michigan
Ann Arbor, Mich.

[5] A. E. Salomonovich presented at IAU Symp. No. 14, Leningrad, USSR; December 9, 1960. (To be published by Cambridge University Press, Cambridge, England.)

[6] V. S. Troitskii, presented at IAU Symp. No. 14, Leningrad, USSR December 9, 1960. (To be published by Cambridge University Press, Cambridge, England.)

[7] W. E. Brown, "A lunar and planetary echo theory," *J. Geophys. Res.*, vol. 65, pp. 3087–3095; October, 1960.

[8] F. B. Daniels, "A theory of radar reflection from the moon and planets," *J. Geophys. Res.*, vol. 66, pp. 1781–1788; June, 1961.

WWV and WWVH Standard Frequency and Time Transmissions*

The frequencies of the National Bureau of Standards radio stations WWV and WWVH are kept in agreement with respect to each other and have been maintained as constant as possible with respect to an improved United States Frequency Standard (USFS) since December 1, 1957.

The nominal broadcast frequencies should for the purpose of highly accurate scientific measurements, or of establishing high uniformity among frequencies, or for removing unavoidable variations in the broadcast frequencies, be corrected to the value of the USFS, as indicated in the table below. The corrections reported have been arrived at by means of improved measurement methods based on LF and VLF transmissions.

The characteristics of the USFS, and its relation to time scales such as ET and UT2, have been described in a previous issue,[1] to which the reader is referred for a complete discussion.

The WWV and WWVH time signals are also kept in agreement with each other. Also they are locked to the nominal frequency of the transmissions and consequently may depart continuously from UT2. Corrections are determined and published by the U. S. Naval Observatory. The broadcast signals are maintained in close agreement with UT2 by properly offsetting the broadcast frequency from the USFS at the beginning of each year when necessary. This new system was commenced on January 1, 1960. A retardation time adjustment of 20 msec was made on December 16, 1959; another retardation adjustment of 5 msec was made at 0000 UT on January 1, 1961; and a time advancement of 50 msec was made at 0000 UT on August 1, 1961.

WWV Frequency
With Respect to U. S. Frequency Standard

1961 September	Parts in 10^{10}†
1	−152.0
2	−152.1
3	−152.1
4	−152.0
5‡	−151.9
6	−150.6
7	−150.5
8	−150.5
9	−150.5
10	−150.6
11	−150.6
12	−150.5
13	−150.5
14	−150.5
15	−150.3
16	−150.3
17	−150.4
18	−150.3
19	−150.2
20	−150.3
21	−150.2
22	−150.1
23	−150.0
24	−150.0
25	−149.9
26	−149.8
27	−149.7
28	−149.6
29	−149.5
30	−149.5

† A minus sign indicates that the broadcast frequency was low. The uncertainty associated with these values is $\pm 5 \times 10^{-11}$.
‡ Frequency adjusted $+1 \times 10^{-10}$ on September 5.

National Bureau of Standards
Boulder, Colo.

[1] Refer to "National Standards of Time and Frequency in the United States," Proc. IRE (Correspondence), vol. 48, pp. 105–106; January, 1960.

Notice of Frequency Adjustment WWV/WWVH

During 1960 and 1961 the nominal frequency of WWV was offset from the U. S. Frequency Standard by −150 parts in 10^{10} in order to establish a unit in close agreement with the value of the unit of UT2.

In 1962 the nominal frequency offset will be −130 parts in 10^{10} for the same reason. The frequency of WWV and WWVH will be higher by 20 parts in 10^{10} beginning at 0000 UT, January 1, 1962.

National Bureau of Standards
Boulder, Colo.

* Received by the IRE, October 26, 1961.

Received by the IRE, November 17, 1961.

Rebuttal to "A Note on Sugai's Class of Solutions to Riccati's Equation"*

The author would like to express his sincere appreciation for Dr. Stickler's interest[1] in his letter.[2] His work is undoubtedly a worthy contribution. However, there are a few interesting items which he did not consider. The purpose of this letter is to mention them briefly and also to discuss the aspect of "generalization" which he seems to have claimed.

Besides the required condition of $Q_1+Q_4=0$, there are four cases of interest as follows:

1) If Q_1 alone is zero, (3)[3] gives a quadratic expression

$$Q_4h^2 + Q_3h + Q_2 = 0,$$

where $h=v'/v$. This says that the condition $Q_1=0$ requires that $c_i(i=1, 2, 3, 4)$ must satisfy the above quadratic expression in order to provide a particular solution for Riccati's equation. Stickler says that Q_1 is not zero but he does not give a reason.

2) If Q_2 alone is zero, (3) yields a solvable Bernoulli's equation,

$$h'Q_1 - Q_1h^2 = Q_3h.$$

3) If Q_3 alone is zero, (3) results in another equation of Riccati:

$$h'Q_1 - Q_1h^2 = Q_2.$$

This has essentially two variable coefficients, as both sides can be divided by Q_1. Fourteen transforms which convert such Riccati equations into first-order linear differential equations are reported.[4] At this point an excellent work by Murphy[5] should be cited, which solved many Riccati and other nonlinear differential equations.

4) If Q_4 alone is zero, (3) gives a first-order linear differential equation,

$$h'Q_1 - Q_3h = Q_2.$$

All of these four cases also require "interrelated" variable coefficients since Q's are related to seven independent variable functions (except Q_1, which is related to four variable functions). It is possible to generate a much more complicated transform in place of (2) such that many combinations of exponential, trigonometric and polynomial functions are included. Yet such a complicated transform of the dependent variable introduces much more complicated interrelationships among variable coefficients with much decreased practical applications.

The basis of Dr. Stickler's generalization seems to have originated from the author's two transforms,[2] $r(x)=R_1s(x)/[s'(x)+P_1s(x)]$ and $r(x)=[s'(x)-P_1s(x)]/[Q_1s(x)]$. On the other hand, they had been derived from two transforms,[6] $y(x)=f(x)g(x)$ and $y(x)=1/[f(x)g(x)]$, where $f(x)$ and $g(x)$ were arbitrary functions of x. It was unfortunate that this background of the two transforms was not mentioned in the previous note,[2] and also that the paper[6] which derived them in detail was not published until May, 1961. These circumstances might have given the impression to readers that those two new transforms were generated by the so-called mathematicians' trick.

The fact that at least two functions $f(x)$ and $g(x)$ are needed, as they are to be related to each other, should be pointed out. Therefore, it is not possible to replace $y(x)$ by $z(x)$ as in $y(x)=z(x)$, which is not a transform but a change of symbols. It is also impossible to replace $y(x)$ by $f(x)\pm g(x)$, for such an expression yields Riccati's equations for $f(x)$ and $g(x)$. The key point is to obtain a solvable equation (linear or nonlinear) by using properly the products of two of the four following variables: $f(x)$, $f'(x)$, $g(x)$, and $g'(x)$, developed by $y'(x)$ and $y^2(x)$. The most compact form of transformations in nonlinear fashions that can be considered is a product or a division of two functions $f(x)$ and $g(x)$. Stickler uses five functions; four of $c_i(x)$'s and $v(x)$. In this respect it should be noted that almost all available books published in the past have mentioned the transform of the type $y(x)=f(x)/g(x)$. These books develop elegant theorems for the general solutions of Riccati's equations after their particular solutions are *somehow* obtained, and they do not mention how these particular solutions can be obtained. In contrast, my other paper[6] was motivated to secure these particular solutions exactly by using the three above-mentioned elementary and compact transforms.

A similar idea to Stickler's for converting Riccati's equations directly into Bernoulli's equations with the requirement of interrelated variable coefficients has been published[7] for the exact solutions of nonuniform transmission lines.

All these works have the common denominator, inter-relationship among variable coefficients. Therefore, any step forward which dispenses with this common denominator is a more "general" method. A small improvement has been published.[8] It combines the original method of Hildebrand, the Cayley factorization technique, and the new transform.[2]

The author would like to explain this slight improvement by taking an example of a practical problem of nonuniform transmission lines. The past exact solutions rigidly interrelated $Z(x)$ and $Y(x)$, even though these line parameters were "arbitrary." What the latest note[8] seems to have proved is that, if the independent variable x (the length of the nonuniform line) is changed to a newly-introduced independent variable w through $w=f(x)$, where $f(x)$ is arbitrary, we can have three arbitrary functions in one equation such as

$$f''(x) - [Z'(x)/Z(x)]f'(x) = [f(x) + B_1]Y(x)Z(x),$$

where B_1 is any constant. The author proposed, in general, *not* to solve for $f(x)$ when $Z(x)$ and $Y(x)$ are given independently and arbitrarily. What he proposed was to assign two independent functions such as $f(x)$ and $Z(x)$ to specify $Y(x)$, or $f(x)$ and $Y(x)$ to determine $Z(x)$, from the above equation, in order to realize the optimum performance of nonuniform lines in terms of its reflection coefficient or its minimum length. To the best knowledge of the author, this approach of having two independent variable parameters for nonuniform lines seems never to have been cited in the literature. This is a slight generalization of Hildebrand's method. For this reason the title "A Generalized Hildebrand's Method for Nonuniform Transmission Lines" was used.

Iwao Sugai
ITT Federal Laboratories
Nutley, N. J.

* Received by the IRE, August 23, 1961.

[1] D. C. Stickler, "A note on Sugai's class of solutions to Riccati's equation," Proc. IRE (Correspondence), vol. 49, p. 1320; August, 1961.

[2] I. Sugai, "A new exact method of nonuniform transmission lines," Proc. IRE (Correspondence), vol. 49, pp. 627–628; March, 1961.

[3] All equation numbers refer to Stickler.[1] All equations in this article are unnumbered, in order to avoid confusion.

[4] I. Sugai, "A class of solved Riccati's equations," *Elec. Comm.*, vol. 37, pp. 56–60; May, 1961.

[5] G. M. Murphy, "Ordinary Differential Equations and Their Solutions," D. Van Nostrand Co., Inc., Princeton, N. J.; 1960.

[6] I. Sugai, "Exact solutions for ordinary nonlinear differential equations," *Elec. Commun.*, vol. 37, pp. 47–55; May, 1961.

[7] I. Sugai, "Riccati's and Bernoulli's equations for nonuniform transmission lines," IRE Trans. on Circuit Theory (Correspondence), vol. CT-8; September, 1961.

[8] I. Sugai, "A generalized Hildebrand's method for nonuniform transmission lines," Proc. IRE (Correspondence), vol. 49, p. 1945; December, 1961.

On the Hues Seen in Fox-Color Images*

Kallmann[1] has described his observations on a two-color system. The authors have worked in the same field,[2] and would like to draw attention to the following point.

The contrast γ of color separation slides is of crucial importance for obtaining satisfactory tri-color projection. It is therefore very probable that it is important for two-color projection too. E. H. Land used slides with $\gamma=1$ and so did we. H. E. Kallmann does not mention the value of γ of his slides. The contrast of black and white film is generally not equal for different colors. One usually corrects this by choosing different developing times for the green and red separation slides. The exact procedure we used is described in our article.[3] If one does not adjust the developing times to the desired value of γ, one is very likely to get red and green separation slides of unequal contrast and $\gamma\neq 1$. Pictures such as these, combined with additional blue separation slides, yield unsatisfactory tri-color projection.

Although we do not think that this point changes H. E. Kallmann's observations substantially, it might well change the quality judgment of an observer.

C. Burckhardt
M. J. O. Strutt
Swiss Federal Inst. Tech.
Zürich, Switz.

* Received by the IRE, September 18, 1961.

[1] H. E. Kallmann, "On the hues seen in fox-color images," Proc. IRE, vol. 49, pp. 1228–1229; July, 1961.

[2] C. Burckhardt and M. J. O. Strutt, "Experiments with E. H. Land's two-color projection," IRE Trans. on Broadcast and Television Receivers, vol. BTR-7, pp. 34–40; April, 1961.

[3] C. Burckhardt and M. J. O. Strutt, "Versuche mit Landscher Zweifarbenprojektion," *Scientia Electrica*, vol. 7, pp. 66–76; June, 1961.

A Stability Test for Linear Discrete Systems in Table Form*

In this note a simple stability test[1,2] similar to Routh's table is being introduced for linear discrete systems. The proof, discussions, and extension of this method will be presented in detail in the future.[3] This test is an alternate to the stability criterion recently developed by Jury[4,5], and it shows that these two criteria are identically equal.[3]

A necessary and sufficient condition for the roots of

$$F(z) = a_0 + a_1 z + a_2 z^2 + \cdots + a_k z^k + \cdots + a_n z^n, \quad \text{with} \quad a_n > 0$$

to have all its roots inside the unit circle in the $z = e^{Ts}$ plane, or equivalently, for the linear discrete system to be stable is obtained as follows.

1) Form the following table: [It should be noted that the elements of row $2k+2$ consist of the coefficients of the row $2k+1$ written in reverse order ($k = 0, 1, 2, \cdots$).]

"Stability Test Table"

Row	z^0	z^1	z^2	$\cdots\cdots$	z^{n-k}	$\cdots$	z^{n-1}	z^n
1	a_0	a_1	a_2	$\cdots\cdots$	a_{n-k}	$\cdots$	a_{n-1}	a_n
2	a_n	a_{n-1}	a_{n-2}	$\cdots\cdots$	a_k	$\cdots$	a_1	a_0
3	b_0	b_1	b_2	$\cdots\cdots$	$\cdots$	$\cdots$	b_{n-1}	
4	b_{n-1}	b_{n-2}	b_{n-3}	$\cdots\cdots$	$\cdots$	$\cdots$	b_0	
5	c_0	c_1	c_2	$\cdots\cdots$	$\cdots$	c_{n-2}		
6	c_{n-2}	c_{n-3}	c_{n-4}	$\cdots\cdots$	$\cdots$	c_0		
$\vdots$	$\vdots$	$\vdots$	$\vdots$	$\vdots$		$\vdots$		
$2n-5$	s_0	s_1	s_2	s_3				
$2n-4$	s_3	s_2	s_1	s_0				
$2n-3$	r_0	r_1	r_2					

where,

$$b_k = \begin{vmatrix} a_0 & a_{n-k} \\ a_n & a_k \end{vmatrix} \qquad d_k = \begin{vmatrix} c_0 & c_{n-2-k} \\ c_{n-2} & c_k \end{vmatrix}$$

$$\vdots \qquad \vdots \qquad \vdots$$

$$c_k = \begin{vmatrix} b_0 & b_{n-1-k} \\ b_{n-1} & b_k \end{vmatrix} \qquad r_0 = \begin{vmatrix} s_0 & s_3 \\ s_3 & s_0 \end{vmatrix}$$

$$r_2 = \begin{vmatrix} s_0 & s_1 \\ s_3 & s_2 \end{vmatrix}.$$

2) Check for the constraints inequalities by noting the elements of the first column and the following:

$$F(1) > 0, \qquad F(-1) \begin{matrix} > 0 \ n \text{ even} \\ < n \text{ odd} \end{matrix}$$

$$\left.\begin{array}{l} |a_0| < a_n \\ |b_0| > |b_{n-1}| \\ |c_0| > |c_{n-2}| \\ |d_0| > |d_{n-3}| \\ \vdots \\ |r_0| > |r_2| \end{array}\right\} (n-1) \text{ constraints.}$$

The above constraints constitute the necessary and sufficient conditions for stability of any order linear discrete systems.

It is noticed from the table that a certain computation involved in dotted entry in in row $2n-3$ becomes redundant. Therefore, the corresponding second-order determinant to be calculated in entries $2n-4$, and $2n-5$ is also redundant.

Examples

1) $F(z) = 3 - 2z - \frac{3}{2}z^2 + z^3, \qquad n = 3.$

By applying the first constraints, we notice $F(1)>0$, $F(-1)>0$, and, since $n=3$, the system is unstable and the test could be discontinued. However, for the sake of illustration we form the table for this case as follows:

Row	z^0	z^1	z^2	z^3
1	3	-2	$-\frac{3}{2}$	1
2	1	$-\frac{3}{2}$	-2	3
3	8	$\frac{9}{2}$	$\frac{5}{2}$	

For the remainder of the stability constraints,

$$3 > 1, \qquad |a_0| < a_n,$$

violated

$$8 > \frac{5}{2}, \qquad |b_0| > |b_{n-1}|.$$

Therefore, the system is unstable. It should be added that by certain combinations of variation of signs one can obtain information on the number of roots inside the unit circle.[3] In this case, all the roots are outside the unit circle and no root is inside the unit circle.

2) $F(z) = 0.0025 + 0.08z + 0.4126z^2 - 1.368z^3 + z^4, \quad n = 4.$

Row	z^0	z^1	z^2	z^3	z^4
1	0.0025	0.08	0.4126	-1.368	1
2	1	-1.368	0.4126	0.08	0.0025
3	$\simeq -1$	1.368	-0.4116	-0.0834	
4	-0.0834	-0.4116	1.368	-1	
5	0.9936	-1.402	0.5256		

* Received by the IRE, August 21, 1961.

[1] M. Marden, "The geometry of the zeros of a polynomial in a complex variable," *Am. Math. Soc.*, pp. 148–161; 1949.

[2] Y. Tyspkin, "Theory of Pulse Systems," State Press for Physics and Mathematical Literature, Moscow, USSR, pp. 423–427; 1958. (In Russian.)

[3] E. I. Jury and J. Blanchard, "On the roots of a real polynomial inside the unit circle and a stability criterion for linear discrete systems," to be published in *Trans. AIEE.*

[4] E. I. Jury, "A Simplified Stability Criterion for Linear Discrete Systems," University of California, Berkeley, ERL Rept. No. 373; June, 1961.

[5] E. I. Jury, "Discussion on 'The stability of sampled-data systems,' by Van J. Tschauer," *Regelungstechnik*, Münich, Germany, RT8, pp. 42–46; 1960.

Stability test:

$$F(1) = 0.1271 > 0, \quad F(-1) = 2.703 > 0$$
$$0.0025 < 1, \quad |a_0| < a_n$$
$$1 > 0.0834, \quad |b_0| > |b_{n-1}|$$
$$0.9936 > 0.5256, \quad |c_0| > |c_{n-2}|$$

The system is stable.

In conclusion, this criterion is particularly useful if the coefficients of $F(z)$ are given in numbers, for in this case the stability computation involves only second-order determinants which is very simple for hand computations.

E. I. Jury
J. Blanchard
Dept. of Elec. Engrg.
University of California
Berkeley, Calif.

A Stability Test for Linear Discrete Systems Using a Simple Division*

In a preceding note [1] a stability test has been presented for linear discrete systems using table form. In this discussion an alternate procedure for the table form is indicated in which the test involves simple division of polynomials.

The stability test will be presented first and its validity second, shown by using the preceding criterion [1].

A necessary and sufficient condition for the polynomial

$$F(z) = a_0 + a_1 z + a_2 z^2 + \cdots + a_k z^k + \cdots + a_n z^n, \quad \text{with} \quad a_n > 0 \tag{1}$$

to have all its roots inside the unit circle in the $z = e^{Ts}$ plane, or equivalently, for the linear discrete system to be stable, is obtained as follows:

1) Form the inverse polynomial of $F(z)$ as follows:

$$F^*(z) = z^n F(1/z) = a_n + a_{n-1} z + a_{n-2} z^2 + \cdots + a_{n-k} z^k + \cdots + a_0 z^n. \tag{2}$$

2) Obtain the stability constraints α_k by simple division as shown

$$\frac{F(z)}{F^*(z)} \to \alpha_0 + \frac{F_1(z)}{F_1^*(z)} \to \alpha_0 + \alpha_1 + \frac{F_2(z)}{F_2^*(z)} \to \alpha_0 + \alpha_1 + \alpha_2 + \frac{F_3(z)}{F_3^*(z)} + \cdots \to \alpha_0 + \alpha_1 + \alpha_2 + \cdots + \alpha_{n-2} + \frac{F_{n-1}(z)}{F_{n-1}^*(z)}, \tag{3}$$

where $F_1(z)$, $F_2(z)$ $\cdots$ are the remainder polynomials obtained from the division and $F_1^*(z)$, $F_2^*(z)$ $\cdots$ are their inverses, as defined in (2).

* Received by the IRE, August 31, 1961.

$$\frac{F(z)}{F^*(z)} \to \frac{a_0}{a_3} + \frac{\frac{a_1a_3 - a_0a_2}{a_3} z + \frac{a_2a_3 - a_0a_1}{a_3} z^2 + \frac{a_3^2 - a_0^2}{a_3} z^3}{\frac{a_3^2 - a_0^2}{a_3} z + \frac{a_1a_3 - a_0a_1}{a_3} z^2 + \frac{a_1a_3 - a_0a_2}{a_3} z^3} \to \frac{a_0}{a_3} + \frac{a_1a_3 - a_0a_2}{a_3^2 - a_0^2} + \cdots.$$

3) Satisfy the following constraints for the stability test:

$$F(1) > 0, \quad F(-1) \begin{matrix} > 0, & n \text{ even} \\ < 0, & n \text{ odd} \end{matrix}, \quad |\alpha_k| < 1, \quad k = 0, 1, 2, \cdots, n-2. \tag{4}$$

The proof of the above test lies in the use of the preceding stability criterion, for it can be easily established that the identity of α_k's and the stability constants, a_0, b_0, c_0, $\cdots$, are as follows [1]:

$$\alpha_0 = \frac{a_0}{a_n}, \quad \alpha_1 = \frac{b_{n-1}}{b_0}, \quad \alpha_2 = \frac{c_{n-2}}{c_0}, \quad \cdots, \quad \alpha_{n-2} = \frac{r_2}{r_0}.$$

In this case it is only necessary to obtain α_0 and α_1.

Thus

$$\alpha_0 = \frac{a_0}{a_3}, \quad \alpha_1 = \frac{a_1a_3 - a_0a_2}{a_3^2 - a_0^2}.$$

The stability constraints are

$$F(1) > 0, \quad F(-1) < 0, \quad \frac{|a_0|}{a_3} < 1, \quad \left|\frac{a_1a_3 - a_0a_2}{a_3^2 - a_0^2}\right| < 1.$$

3) $F(z) = 0.0025 + 0.08z + 0.4126z^2 - 1.368z^3 + z^4$
$F^*(z) = 1 - 1.368z + 0.4126z^2 + 0.08z^3 + 0.0025z^4.$

In this case we need obtain α_0, α_1, α_2 as follows:

$$1 - 1.368z + 0.4126z^2 + 0.08z^3 + 0.0025z^4 \overline{)\, 0.0025 + 0.08z + 0.4126z^2 - 1.368z^3 + z^4 \,(\, 0.0025}$$
$$0.0025 - 0.0034z + 0.001z^2 - 0.002z^3 + \simeq 0z^4$$
$$z - 1.368z^2 + 0.4116z^3 + 0.0834z^4 \overline{)\, 0.0834z + 0.4116z^2 - \sim 1.368z^3 + z^4 \,(\, 0.0834}$$
$$0.0834z - 0.114z^2 + 0.0342z^3 + 0.007z^4$$
$$0.993z^2 - 1.4022z^3 + 0.5256z^4 \overline{)\, 0.5256z^2 - 1.4022z^3 + 0.993z^4 \,(\, 0.53}$$

From the stability constraints imposed previously on the a's, b's, $\cdots$, the constraints to be imposed on the α_k's are readily established, as explained in (4).

Examples

To illustrate the procedure to be followed, we establish the constraints in general terms for $n = 2$, $n = 3$, and provide a stability test for $n = 4$ when the coefficients of the latter polynomial are given in numbers:

1) $F(z) = a_0 + a_1 z + a_2 z^2, \quad a_2 > 0.$

In this case $F^*(z)$ is given as

$$F^*(z) = a_2 + a_1 z + a_0 z^2.$$

α_0 is obtained from

$$\frac{F(z)}{F^*(z)} \to \alpha_0 + \cdots, \quad \alpha_0 = \frac{a_0}{a_2}.$$

The stability contraints are

$$a_0 + a_1 + a_2 > 0, \quad a_0 - a_1 + a_2 > 0, \quad |\alpha_0| < 1, \quad \frac{|a_0|}{a_2} < 1.$$

2) $F(z) = a_0 + a_1 z + a_2 z^2 + a_3 z^3, \quad a_3 > 0$

$$F^*(z) = a_3 + a_2 z + a_1 z^2 + a_0 z^3.$$

It should be noted that in obtaining α_0, α_1, and α_2, the terms encircled in dotted lines as above need not be calculated. Similarly, such simplification could also be obtained from the previous examples.

In this case,

$$\alpha_0 = 0.0025, \quad \alpha_1 = 0.0834, \quad \alpha_2 = 0.53.$$

For stability constraints:

$$F(1) = 0.1271 > 0 \quad F(-1) = 2.703 > 0, \quad 0.0025 < 1, \quad 0.0834 < 1, \quad 0.53 < 1.$$

The system is stable as also shown in the preceding note[1].

In conclusion, one may notice that this test is similar to the preceding test, except that it is written in a different form. The advantages of this procedure are twofold: 1) This form is easier to remember. 2) One may not need knowledge of determinants; this form also provides a minor simplification. This procedure is equivalent to the continued fraction expansion method used for stability test of linear continuous systems.

ACKNOWLEDGMENT

The author would like to thank Dr. M. A. Pai for a discussion which was helpful in writing this note.

E. I. JURY
University of California
Berkeley, Calif.

REFERENCES

[1] E. I. Jury and J. Blanchard, "A stability test for linear discrete system in table form," PROC. IRE, vol. 49, pp. 1947–1948; December, 1961.
[2] E. I. Jury, "Additions to 'Notes on the stability criterion for linear discrete systems'," IRE TRANS. ON AUTOMATIC CONTROL, vol. AC-6 pp. 342–343; September, 1961.
[3] E. I. Jury, "A Simplified Stability Criterion for Linear Discrete Systems," University of California, Berkeley, ERL Rept. No. 373; June, 1961.

Duality of Planar Networks*

A recent communication[1] describes a method of forming the dual of a planar network which contains transformers. In this note I would like to describe a slightly different approach to duality and show how it clarifies certain controversial issues. In this respect it is suggested that this new approach may be more fundamental and may, in fact, be the basic law governing the duality of networks.

SIGNIFICANCE OF EIGENVALUES

The dual of a planar network is usually acquired by dualizing each term of the mesh or nodal equations, or by operating on the network matrices as described in the literature.[2] For instance, if (Z_1) is the Z matrix of a network, then $(1/r^2)(Z_1)$ is the Y matrix, and $r^2(Z_1)^{-1}$ is the Z matrix of the dual network. Thus, dual networks can be formed by matrix inversion. It follows, therefore, that the product of the Z (or Y) matrices of two mutually dual networks is equal to the unity matrix I, multiplied by a scalar factor r^2 (or $1/r^2$ in the case of Y matrices)

$$(Z_1)(Z_1)^{-1} = I = (Z_1)^{-1}(Z_1)$$
$$r^2(Z_1)(Z_1)^{-1} = r^2 I = (Z_1)r^2(Z_1)^{-1}$$

Therefore, if (Z_1) and (Z_2) are the Z matrices of two dual networks,

$$(Z_1)(Z_2) = r^2 I \qquad (1)$$
$$\left| (Z_1)(Z_2) - r^2 I \right| = 0. \qquad (2)$$

Eq. (1) resembles the usual definition of dual impedances z_1 and z_2, where $z_1 z_2 = r^2$ and r^2 is a frequency independent positive constant with the dimensions of resistance squared. Since (2) is the characteristic equation of the product (Z_1) (Z_2), the following definition of duality is prompted.

Two networks are dual if the characteristic equation of the matrix product of their Z (or Y) matrices has equal, positive eigenvalues whose dimensions are those of resistance (or conductance) squared.

Before applying this definition, it is instructive to consider the simplest dual networks with one element as shown in Fig. 1. Obviously, the inverse matrix method breaks down in this simple case, while the well-used mesh and nodal operation does not. The reason is very clear; the Z matrix of network 1 and the Y matrix of network 2 do not describe the single impedance element in any way. Therefore, when using the inverse matrix method, it is a necessary condition that the matrices fully describe the networks concerned.





Fig. 1—Simple dual networks.



(a)

(b)

Fig. 2—(a) Ideal transformer. (b) Network and an ideal transformer.

A. The Transformer

Consider the ideal transformer with descriptive matrices as in Fig. 2(a). Apart from the fact that a dual is not indicated by taking inverse matrices, the matrix elements are dimensionless and therefore, any solution to the characteristic equation previously mentioned cannot have the dimensions of resistance squared. This requirement of the eigenvalues would indicate that there is no dual network for an ideal transformer, thus explaining much past controversy. Since a transformer operates on networks, it seems natural to absorb a transformer into the Z or Y matrix of an accompanying network before attempting to find the dual of the network. Any transformers in the dual network can then be extracted. As an example of this procedure consider a practical transformer with leakage inductance z_1 and magnetizing inductance z_2 as shown in Fig. 2(b) (where these effects have been separated from the ideal transformer $1:n$). The details in Fig. 2(b) substantiate the findings in the literature[1] and indicate how an ideal or a practical transformer may be treated.

B. The Gyrator

The fictitious circuit element called a gyrator has found great use in duality studies[3] and apparently, unlike the transformer, has presented no controversy. It is easily shown that gyrators fulfill the eigenvalue requirements.

C. Transistors and Vacuum Tubes

The synthesis[4,5] of active devices suggests the existence of their duals. The duality between present-day active devices will now be dealt with. This subject has been discussed in the literature,[2,3] where the arguments have been mainly descriptive. It has been stated that the junction transistor (common-emitter) is the dual of the vacuum-tube triode (common cathode). Yet it is an undisputable fact that junction transistor circuitry is analogous, and not dual, to its vacuum-tube counterpart. In fact, most vacuum-tube circuits can be transistorized by simply lowering the impedance levels of interconnecting networks.

Let (Y_{ij}) and (y_{ij}) be the Y matrices of the junction transistor (common-emitter) and triode (common-cathode), respectively. To test for duality, (3) is inspected.

$$\left| \begin{pmatrix} Y_{11} & Y_{12} \\ Y_{21} & Y_{22} \end{pmatrix} \begin{pmatrix} y_{11} & y_{12} \\ y_{21} & y_{22} \end{pmatrix} - \frac{1}{r^2} \cdot I \right| = 0. \qquad (3)$$

On substituting practical values in (3), it is very obvious that duality between these devices is most unlikely. For instance, at low frequencies it is usual to take y_{11}, y_{12} and Y_{12} as zero, in which case (3) becomes (4).

$$\frac{1}{r^2}\left(\frac{1}{r^2} - y_{22} Y_{22} \right) = 0. \qquad (4)$$

The eigenvalues are 0 and $y_{22}Y_{22}$; therefore, the proposed conditions for duality are not fulfilled.

In searching for duality among active devices it is interesting to note that it is most strongly exhibited within the configurations of one type of device. For instance, let (Y_{ij}') and (y_{ij}') be the Y matrices of a junction transistor in the common-base and common-collector configurations, respectively. The characteristic equation is (5)

$$\left| \begin{pmatrix} Y_{11}' & Y_{12}' \\ Y_{21}' & Y_{22}' \end{pmatrix} \begin{pmatrix} y_{11}' & y_{22}' \\ y_{21}' & y_{22}' \end{pmatrix} - \frac{1}{r^2} \cdot I \right| = 0. \qquad (5)$$

At low frequencies it is valid to put $Y_{12}' = y_{12}' = 0$; for identical bias conditions Y_{11}', Y_{21}', y_{22}' and $-y_{21}'$ are all approximately equal to gm, the forward transconductance. Eq. (5) becomes (6):

$$\left(y_{11}' g_m - \frac{1}{r^2} \right)\left(Y_{22}' g_m - \frac{1}{r^2} \right) = 0. \qquad (6)$$

In practice, y_{11}' and Y_{22}' are very small and of similar order, thus yielding eigenvalues $y_{11}'g_m$ and $Y_{22}'g_m$ which are approximately equal, positive, and of the dimensions conductance squared. It could be said,

* Received by the IRE, August 21, 1961.
[1] P. G. Griffith, "Duality as applied to transformers," PROC. IRE (Correspondence), vol. 49, pp. 816–817; April, 1961.
[2] R. F. Shea, "Principles of Transistor Circuits," John Wiley and Sons, Inc., New York, N. Y.; 1954.
[3] R. L. Wallace, Jr., and G. Raisbeck, "Duality as a guide in transistor circuit design," *Bell Sys. Tech. J.*, vol. 30, pp. 381–417; April, 1951.
[4] J. Shekel, "The gyrator as a three-terminal element," PROC. IRE, vol. 42, pp. 1014–1016; August, 1953.
[5] H. J. Carlin, "Theory and Application of Gyrator Networks," Polytechnic Inst. of Brooklyn, N. Y., Res. Rept. 289; March, 1954.

then, that these two basic configurations of a transistor tend to be dual. (Similar results apply to the two vacuum-tube configurations, common-grid and common-anode.) The existence of this approximate duality is certainly suggested by the details of Fig. 3, where the networks of (a) are dual to those in (b) and the impedance levels are consistent with the transistor configurations.




Fig. 3—(a) Common-collector amplifier. (b) Common-base amplifier.

Conclusion

The above examples suggest that consideration of the eigenvalues gives a deeper insight into the existence of duality. In this light the duality of networks could be defined as follows:

Definition: Let (Z_1) and (Z_2) be the Z matrices which fully describe two active or passive networks Z_1 and Z_2. Then Z_1 and Z_2 are dual if the characteristic equation of $(Z_1)(Z_2)$ has eigenvalues which are positive, equal, and have the dimensions of resistance squared (or conductance squared in the case of Y matrices).

J. R. James
Radar and Telecommun. Branch
Royal Military College of Science
Swindon, Eng.

Schwarz's Lemma and Linear Passive Systems*

The physical interpretation of some basic mathematical theorems often leads to equally interesting results concerning the performance of a class of physical systems. Sometimes the situation is the other way around, that is, a relatively sophisticated mathematical fact has a physically trivial counterpart.

The subject of this note is to derive a physical interpretation of one of the fundamental theorems of Function Theory known as Schwarz's lemma. It turns out that this lemma suggests a basic inequality between active and reactive power of a linear passive one-port. The inequality is far from being trivial.

Schwarz's lemma is one of the basic theorems of Function Theory which has been subjected to many generalizations and ramifications for more than half a century. It appears as though the lemma comprises some fundamental thought which is not to be disposed of by the mode du jour. The statement of the lemma in its simplest form is given below.

Schwarz's lemma: Let $f(z)$ be a function analytic in the region $|z|<1$ and let

i) $|f(z)| \leq 1$ for $|z| < 1$

ii) $f(0) = 0$.

Then,

$$|f(z)| \leq |z| \quad \text{in} \quad |z| < 1. \tag{1}$$

and the inequality can hold only when $f(s)=e^{j\alpha}z$, α being a real constant. In geometric language, the lemma states that the euclidean distances to the origin are not increased by this very general class of analytic mapping functions. (See Fig. 1.)




Fig. 1.

Schwarz's basic lemma, as expected, has penetrated in numerous branches of physical sciences. When the function describing a physical problem is properly normalized in the reference frame of the unit disk, one can infer from the lemma a fundamental upper limit for the performance of the associated linear system. Furthermore, with the proper mathematical manipulations, one may derive more informative bounds at the price of being confined to a more restrictive family of linear systems.

The electrical engineering profession has had its own share of benefit in the use of this lemma. The theorem appears, I believe, since 1930 in the literature of the circuit theory. The reader interested in some of the applications of this theorem to Network Synthesis may wish to refer to one of several existing books on the subject or to the literature.[1-5]

As an example of the use of Schwarz's lemma, we apply the theorem to $Z(s)$ the driving-point impedance or admittance function of a bilateral linear passive network. For the complex frequency $s=\alpha+j\beta$, the active and reactive powers under the above steady-state regime are, respectively,

$$U(\alpha,\beta) = \operatorname{Re} Z(\alpha+j\beta),$$
$$V(\alpha,\beta) = \operatorname{Im} Z(\alpha+j\beta). \tag{2}$$

In order to apply the lemma, one may use a well known linear transformation of the frequency and the impedance function, that is,

$$\frac{Z(s)-Z(s_0)}{Z(s)+\overline{Z(s_0)}}; \qquad \frac{s-s_0}{s+\bar{s}_0} \qquad \operatorname{Re} s_0 > 0. \tag{3}$$

Since the conditions of the lemma are now satisfied, one can derive a suitable generalization of (1) for driving-point impedance or admittance functions. (These functions are generally referred to as Positive Real Functions, or PRF in abbreviated form.)

Theorem: For any PRF we have

$$\left|\frac{Z(s)-Z(s_0)}{Z(s)+\overline{Z(s_0)}}\right| \leq \left|\frac{s-s_0}{s+\bar{s}_0}\right|$$
$$\operatorname{Re} s > 0, \ \operatorname{Re} s_0 > 0. \tag{4}$$

A geometric interpretation of this inequality is rather interesting. Fig. 2 suggests that for a physically realizable one-port we have

$$\frac{A'B'}{A'C'} \leq \frac{AB}{AC}. \tag{4a}$$




Fig. 2.

We note with interest that the ratio of two euclidean distances appears in our calculation. (There are other forms of the theorem expounding on noneuclidean distances. See for instance G. Pick's theorem in Caratheodory[6] which has been employed in the well-known paper of O. Brune. See also Bolinder.[4])

To translate this inequality in physical language, we let

$$Z(s_0) = Z(\alpha+j\beta) = U_0 + jV_0,$$

and write

$$\left|\frac{(U-U_0)+j(V-V_0)}{(U+U_0)+j(V-V_0)}\right| \leq \left|\frac{(\alpha-\alpha_0)+j(\beta-\beta_0)}{(\alpha+\alpha_0)+j(\beta-\beta_0)}\right| \tag{5}$$

$$\frac{(U-U_0)^2+(V-V_0)^2}{(U+U_0)^2+(V-V_0)^2} \leq \frac{(\alpha-\alpha_0)^2+(\beta-\beta_0)^2}{(\alpha+\alpha_0)^2+(\beta-\beta_0)^2}. \tag{6}$$

This is a general inequality which illustrates the Schwarz's lemma for PRF.[7] The inequal-

* Received by the IRE, August 30, 1961. This work was partially supported by the Rome AF Dev. Center.

[1] P. I. Richards, "A special class of functions with positive real parts in a half-plane," *Duke Math. J.*, vol. 14, pp. 777–786; month, 1947.

[2] A. Fialkow and I. Gerst, "Impedance synthesis without minimization," *J. Math. Phys.*, vol. 34, pp. 160–168; October, 1955.

[3] N. Balabanian, "Network Synthesis," Prentice-Hall, Englewood Cliffs, N. J.; 1958.

[4] E. F. Bolinder, "Impedance and Power Transformations by the Isometric Circle Method and Non-Euclidean Hyperbolic Geometry," Res. Lab. of Electronics, Mass. Inst. Tech., Cambridge, Tech. Rept. No. 312; June 24, 1957.

[5] F. M. Reza, "A supplement to the Brune synthesis," *Trans. AIEE*, vol. 74, pp. 85–90; March, 1955.

[6] C. Caratheodory, "Theory of Functions of a Complex Variable," Chelsea Publishing Co., New York, N. Y., vol. 2, ch. 1; 1959.

[7] The reader is assumed to be familiar with the physical meaning of applying an excitation with $s=\alpha+j\beta$ which requires the introduction of resistors along with all inductors and capacitors.

ity (4) can be further employed for obtaining more specialized results if desired so. For example, if we let $s_0=a>0$, we find as a corollary for any PRF

$$\frac{Z(s)}{s} \leq \frac{Z(a)}{a} \qquad s > a > 0. \tag{7}$$

(7) is one of many results which can be derived from (4). Other results and interpretation of other forms of this lemma such as Jensen's theorem have been derived by the author. The latter being perhaps of more interest to the professional circuit theorists will be given elsewhere.

F. M. Reza
Dept. of Elec. Engrg.
Syracuse University
Syracuse, N. Y.

Discussion of "Forward Scattering by Coated Objects Illuminated by Short Wavelength Radar"*

In the course of a theoretical study on bistatic scattering measurements, I came across what appears to be an experimental error published in Proceedings.[1] As shown in Fig. 6 of the article by Hiatt, Siegel, and Weil, forward-scatter cross sections are measured by placing the test target between transmitting and receiving horns in a transmission path which has been nulled out via a secondary circuit. This interpretation is verified by the "Experimental Procedures" sec- of the article.

The fallacy of this procedure can be seen by measuring the forward-scattering characteristics of:

1) a matched termination or attenuator,
2) a short circuiting wall between horns, or
3) a matched phase shifter.

In each case a substantial scattering cross section dependent on transmitting antenna gain will be measured where, in fact, none exists at all.

In a more recent article,[2] another experimenter displays a similar arrangement of equipment in Fig. 21 for the same purpose. However, since the latter paper conspicuously avoids any measurements in the region of 180° direct forward scatter, it may be assumed that the error was not repeated. It must be recognized that forward scattering cannot be rigorously defined or measured at a bistatic angle of 180°.

J. Fisch
20 Elmwood Lane
Syosset, N. Y.

* Received by the IRE, July 20, 1961.
[1] R. E. Hiatt, K. M. Siegel, and H. Weil, "Forward scattering by coated objects illuminated by short wavelength radar," Proc. IRE, vol. 48, pp. 1630–1635; September, 1960.
[2] R. J. Garbacz and D. L. Moffatt, "An experimental study of bistatic scattering from some small, absorber coated, metal shapes," Proc. IRE, vol. 49, pp. 1184–1192; July, 1961.

Authors' Comment[3]

Fisch states that it is an utter fallacy to measure the forward-scattering characteristics of an object by the method used by the authors,[1] where the test target is placed between the transmitting and receiving horns in a transmission path which has been nulled out via a secondary circuit. We are at a loss to understand his defense of this position. Fisch proposes to disprove our procedure by measuring the forward-scattering characteristics of certain transmission line components, *i.e.*, a matched termination. He has stated that "a substantial scattering cross section dependent on transmitting antenna gain will be measured where, in fact, no forward-scattering cross section exists." This statement is untrue in two ways. First, the measured scattering cross section will not depend on antenna gain (it is assumed that the target is placed in a region of plain wave illumination); it will depend only on the degree to which the field incident on the receiving horn is changed by the energy absorbed and scattered by the test target. It is common practice to determine the amount of change by introducing a known scatterer such as a sphere. Second, Fisch is wrong when he states that his proposed test targets have no (forward) scattering cross section. This statement hardly warrants a rebuttal. Any object that changes the incident energy, whether it be a perfect piece of radar absorbing material, a matched antenna or one of Fisch's test targets will have a forward-scattering cross section. We[1] have shown by an approximate method, and Logan[4] has shown by consideration of the exact sphere solution, that the leading term in the asymptotic expansion of the forward-scattering cross section for high frequencies is precisely $4\pi A^2/\lambda^2$, where A is the area outlined by the boundary between the lit region and the shadow region of the target. The close agreement between our experimental results, our theoretical results, and Logan's theoretical results, shown in Fig. 1 of reference 1, should have convinced Fisch that no glaring experimental error had been committed. The method we use, and for which we take full responsibility, is very similar to that used by Hamren[5] in measuring forward-scatter cross-section areas. The block diagram describing his method is almost indentical to our block diagram. Hamren's method and other methods are described by King and Wu.[4]

It is almost amusing to hear "that forward scattering cannot be rigorously defined or measured at a bistatic angle of 180°." In saying this Fisch has discarded much of theoretical diffraction theory in electromagnetics and most of nuclear scattering theory, as the optics theorem relates the total cross section to the imaginary part of the forward-scattering amplitude. Since according to Fisch the forward-scattering amplitude is beyond definition, then by the above theorem so is the total cross section; again working backwards Fisch has "shown" that we can't define conservation of energy for all scattering systems in all branches of physics. Luckily for those of us working in physics Fisch is wrong, and most of our physical laws will last a good deal longer. Apparently, more work should be published explaining the bright line behind the penny, so that forward-scattering answers will be no longer the mystery some people now believe them.

We would like to take this opportunity to point out the good agreement between the experimental results of Garbacz and Moffatt[2] and the theoretical predictions in reference 1. We are happy to see this agreement in the resonance region.

K. M. Siegel
R. E. Hiatt
Radiation Laboratory
University of Michigan
Ann Arbor, Mich.

[3] Received by the IRE, August 9, 1961.
[4] R. W. P. King and T. T. Wu, "Scattering and Diffraction of Radio Waves" (Appendix for Logan's work), and pp. 192–194 of Hamren's work (see reference 5 below), Harvard University Press, Cambridge, Mass.; 1959.
[5] S. D. Hamren, "Scattering from Spheres," Elec. Engrg. Dept., University of California, Berkeley, Rept. 171; June 15, 1950.

Inductive Probability as a Criterion for Pattern Recognition*

Consider a sequence of length n composed of elements from the set $\{A_j\}$. Then the inductive probability that the next member of the sequence will be A_p is

$$P^*(A_p) = \frac{n_p + \omega_p}{n + \sum_p \omega_p}, \tag{1}$$

where n_p is the number of times A_p appears in the sequence, and ω_p is the logical width of A_p.[1] If there are m elements and the logical widths are the same, this reduces to

$$P^*(A_p) = \frac{n_p + 1}{n + m}. \tag{2}$$

To extend this measure to pattern recognition consider, as an example, the case in which there are only two elements A_1 and A_2. Suppose, for example, the sequence is

$$A_1A_2A_1A_2A_1A_2A_1A_2.$$

The inductive probability that the next element of the sequence will be A_1 is given by relation 2, in which

$$\left.\begin{aligned} n &= 8 \\ n_p &= 4 \\ m &= 2 \end{aligned}\right\} \quad \therefore P^*(A_1) = 1/2.$$

The probability that the next elements will A_1A_2 is given by

$$\left.\begin{aligned} n &= 4 \\ n_p &= 4 \\ m &= 4 \end{aligned}\right\} \quad \therefore P^*(A_1A_2) = 5/8.$$

* Received by the IRE, August 14, 1961.
[1] R. Carnap, "Logical Foundations of Probability," University of Chicago Press, Chicago, Ill.; 1950.

In this case, the pairs (A_1A_1), (A_1A_2), (A_2A_1) and (A_2A_2) are considered as the basic blocks. Similarly,

$$P^*(A_1A_2A_1A_2) = \frac{2+1}{2+16} = \frac{3}{18}$$

$$P^*(A_1A_2.1_1A_2.1_1A_2) = \frac{1+1}{1+64} = \frac{2}{65}.$$

Note that the prediction (A_1A_2) has the largest measure. This is because not only does it match the pattern, but it does so with the fewest possible elements. The extension to nonbinary cases is obvious.

However, there is an objection to this application of inductive probability. What can be done if the sample sequence is not composed of complete period? In the above example, how do we test for repetitions over three elements?

BERNARD HARRIS
College of Engrg.
New York University
New York, N. Y.

Law for Noise Loading of Multivoice-Channel FD Systems*

The concept of using a white noise signal with uniform power density over the baseband for the analysis and testing of multivoice-channel systems using FD multiplex has now become well-established in the art.

The rms level of this signal is made to correspond to the level expected of the complex baseband signal when voice traffic is actually present. Normally the level is that which is not expected to be exceeded for more than 1 per cent of the busy hour, based on the classic work of Holbrook and Dixon.[1] Curve A, of Fig. 1, is scaled from their Fig. 6, Curve B, which is usually used for this purpose.

In pursuance of this approach, the CCIR has suggested the rms level of the white noise signal should be

$$[-15 + 10 \log N] \text{ dbm } 0, \qquad N > 240$$
$$[-\ 1 + \ 4 \log N] \text{ dbm } 0, \qquad 240 > N > 60.$$

These relations are shown by Curves *B* and *C* respectively.

The Holbrook and Dixon curve did not include the effect of normal channel limiting, allowance for this being applied to their "instantaneous load capacity" data. As shown by Jacobsen,[2] this factor introduces a significant discrepancy. For this reason, it was suggested by the writer[3] that the rms level could be approximated with sufficient accuracy for design purposes by a law of the form




Fig. 1.

$$T_c = XN^{\alpha}, \tag{1}$$

where

T_c = rms power level of complex signal relative to single-channel test tone.
N = number of busy channels.
X, α = constants depending on the busy hour statistics.

Subrizi[4] later indicated that speech volumes had tended to decrease since Holbrook and Dixon carried out their work, thereby reducing the composite rms level. On the other hand, some allowance must be made in the operative system for carrier leak, dialing impulses, and the like.

Taking these into account, the writer[5] subsequently suggested the rms level for the "1 per cent of the busy hour" criterion, could be expressed satisfactorily by the relation

$$T_c = 0.315N^{0.67} \tag{2}$$

or in db,

$$(-5 + 6.7 \log N)1000 > N > 3.$$

This is shown as our Curve *D*. As can be seen, this is a closer fit to the original data than the CCIR values over most of the range.

The concept of a single law to represent rms loading is particularly valuable in comparative studies of systems, in terms of both performance and economics.

The number of teletype channels used varies considerably from system to system. Consider, however, a typical case of one voice channel in eight used for this purpose. On the basis of 18 FSK telegraph channels per voice channel and CCIR levels, the average power per voice channel so allocated will be -7.5 dbm0.

The composite N channel system level will then be

$$T_c' = X\left(\frac{7N}{8}\right)^{\alpha} + \left(\frac{N}{8}\right)\frac{1}{5.7}. \tag{3}$$

(Similar equations can of course be derived for other telegraph channel densities.)

The ratio γ between this power and that obtained from (2) (assuming all channels are used for voice) is

$$\delta = (0.875)^{\alpha} + \frac{N^{(1-\alpha)}}{14.5}.$$

Thus, there is only a small error in using (1) to represent the loading for voice plus telegraph channel densities up to the value indicated.

A further factor to be considered is that all the curves shown here are based on N busy channels. When the data are applied to an N channel capacity system, it is implied that all channels are "busy"; *i.e.*, the trunk occupancy is unity, a condition which never applies in sound engineering design. For small numbers of channels this may be as low as 0.4, or less, so that an rms level based on N channels rather than that expected from the trunk occupancy, tends to be somewhat conservative. On the other hand, this further supports the use of (2), for nominal ratios of voice-to-telegraph channels, since the increased loading due to the latter tends to be offset by the reduced occupancy.

C. A. PARRY
Page Communications Engineers, Inc.
Washington, D. C.

Reliability Factors in Thermoelectric Generator Design*

A multitude of semiconductor thermocouple elements are required in large-scale thermoelectric generators. Ideally the thermocouples may be series-paralleled in any manner to achieve the required load voltage and current. However, from a practical standpoint, the mean-time-to-failure of a thermocouple will place limits on the permissible series-parallel arrangement.

Consider the schematic generator circuit of Fig. 1; a total of S subsystems, each with n thermocouples in series, are operating in parallel. Assuming identical operating conditions and performance for each thermocouple, the line current, I_L, is simply SI_e, where I_e is the current through any single thermocouple. Failure of an individual thermocouple (failure is considered to be an open circuit) will interrupt the output of an entire subsystem with a consequent reduction in power delivered to the load. It may be desirable to maintain n as high as possible since the load voltage will vary directly as n; however, it is not desirable that a large number of thermocouples be eliminated as effective generators by a single failure. What then is the tolerable number of thermocouples in a subsystem?

If the failure process obeys what is sometimes described in the physical literature as a "chance" breakdown mechanism (*i.e.*, if the instantaneous probability of failure at

* Received by the IRE, July 28, 1961; revised manuscript received, August 11, 1961.

[1] B. D. Holbrook and J. T. Dixon, "Load rating theory for multichannel amplifiers," *Bell Sys. Tech. J.*, vol. 18, pp. 624–644; October, 1939.

[2] B. B. Jacobsen, "The effect of nonlinear distortion in multichannel amplifiers," *Elec. Commun.*, vol. 19, pp. 29–54; 1940.

[3] C. A. Parry, "Design factors for the optimization of multichannel radio systems," *Trans. AIEE, (Commun and Electronics)*, no. 233, pp. 606–620; November, 1957.

[4] V. Subrizi, "A speech volume survey on telephone message circuits," *Bell Labs. Rec.*, pp. 292–295; August, 1953.

[5] C. A. Parry, "A formalized procedure for the prediction and analysis of multichannel tropospheric scatter circuits," IRE TRANS. ON COMMUNICATIONS SYSTEMS, vol. CS-7, pp. 211–221; September, 1959.

* Received by the IRE, July 24, 1961; revised manuscript received, September 5, 1961. The work reported in this letter was supported in part by Alco Products, Inc.




Fig. 1—Schematic thermoelectric generator circuit.

time τ, conditional upon nonfailure prior to time τ, is constant), then the fraction f, of the original number of thermocouples which are intact after an operating period τ is

$$f = \exp(-\tau/M), \tag{1}$$

where M is the mean-time-to-failure of the subsystem. For n identical thermocouples in series, we have $1/M = n/m$, where m is the mean-time-to-failure of an individual thermocouple. Thus the probability that a subsystem of n thermocouples is in operation after time τ is

$$f = \exp(-n\tau/m). \tag{2}$$

The most probable line current I_L can be determined with the aid of the binomial distribution

$$b = \frac{S!}{k!(S-k)!} f^k (1-f)^{S-k}, \tag{3}$$

where b is the probability that in S repeated independent trials with probability f for success and $(1-f)$ for failure there will occur k successes and $(S-k)$ failures $(0 \le k \le S)$ For the generator under consideration, S, the number of parallel subsystems, represent the number of independent trials. "Successes" imply the subsystem is still intact and contributing to the line current. It is interesting to note that by using two or more subsystems in parallel we are decreasing the probability that the line current is 100 per cent of its rated value

$$b_{100\%} = f^S(1-f)^0 = f^S. \tag{4}$$

Since $f < 1$, f^S is largest when $S = 1$. However, the addition of parallel subsystems also decreases the probability that the line current is zero.

It is a property of the binominal distribution that the mean or expected number of successes[1] is $E(r_s) = fS$, where r_s is a random variable representing the number of successes observed among S trials. Thus, the mean or expected fraction of the initial line current from S subsystems which remains after τ is simply $f = E(r_s)/S$. Since the load voltage is constant, the mean or expected remaining fraction of the original power is also f, as given in (2).

Consider a thermoelectric generator with power rating P, which is to be operated unattended for a specified period. There is no provision for automatic switching or replacement of open-circuited thermocouples. In the most simple analysis under matched load conditions the load voltage V is

$$V = ne\Delta T/2 = P/I_L, \tag{5}$$

where

e = thermoelectric power of a thermocouple, volts/°C
ΔT = operating temperature interval, °C.

Combining (2) and (5), we have

$$I_L = \frac{2P}{ne\Delta T} = \frac{-2P\tau}{e\Delta T m \ln(f)} = \frac{P}{V}. \tag{6}$$

As an example, see Table I where some series-parallel combinations for a 100 kw generator required to operate 10,000 hours are presented. The resistance of a thermocouple has been arbitrarily taken as 0.01 ohm, corresponding to $I_e = 5$ amperes. Carbon composition resistors under stabilized operating conditions can have a mean failure time of the order of 10^8 hours. In the absence of quantitative data on thermocouple reliability, the assumption of a mean failure time longer than 10^8 hours is hardly justified. Thus, this simplified analysis serves to partially indicate the role reliability factors must play in thermoelectric generator design. As systems of progressively larger capacity are envisioned without comparable improvement in material figure of merit, greater emphasis must be placed upon reliability and associated problems of power distribution from low voltage-high current sources.

TABLE I

Series-Parallel Combinations for Two Choices of Mean-Failure-Time

(Power output 10^5 watts, operating period 10^4 hours, $e\Delta T = 0.1$ v, thermocouple resistance $= 0.01\ \Omega$)

Permissible Fraction of Original Power After 10,000 hrs, f	Allowed Number of Series Thermocouples, n	Load Current I_L, amps	Required Number of Parallel Subsystems $S = I_L/5$	Load Voltage V, volts
		$m = 10^6$ *hours**		
0.95	5	3.9×10^5	7.8×10^4	0.25
0.80	22	$9.0 = 10^4$	1.8×10^4	1.1
0.50	70	2.9×10^4	5.8×10^3	3.5
		$m = 10^5$ *hours*		
0.95	510	3.9×10^3	$7.8 = 10^2$	25.5
0.80	2230	9.0×10^2	1.8×10^2	111
0.50	6930	2.9×10^2	5.8×10^1	346

* Mean time for thermocouple failure (open circuit).

The authors are indebted to Dr. Arthur E. Mace for helpful interpretations and constructive criticisms of the text.

M. R. Seiler
T. S. Shilliday
Battelle Memorial Inst.
Columbus, Ohio

[1] See, for example, W. Feller, "An Introduction to Probability Theory and Its Applications," John Wiley and Sons, Inc., New York, N. Y., pp. 104–110, 173–174; 1950.

A Proposed Test of the Constancy of the Velocity of Light*

The experiment recently suggested by Rapier,[1] interesting and ingenious though it is, cannot demonstrate the isotropy of space to light propagation. The fallacy results from the impossibility of *empirically* establishing the absolute synchronization of clocks located in different regions of space. This is closely allied to the impossibility of empirically establishing the absolute simultaneity of events occurring in separate locations in space. The results follow from the assumption of a finite upper bound on the velocity of signal propagation.

Suppose one wished to establish the absolute simultaneity of a pair of events occurring in two different locations such as a flash of light in the distance and the reading of a clock *here* at that time. Presumably, knowing the distance separating the clock from the flash and the velocity of propagation of light, the transit time may be subtracted from the present clock reading to find the time at which the flash occurred. The temptation is to conclude that the hands of the clock stood at a certain reading simultaneously with the occurrence of the flash. Unfortunately, this *cannot be verified experimentally*. How is the velocity of light, used for the above "correction," determined? Simply by dividing the distance separating the occurrence of a flash by the time elapsed between that occurrence and an observer's reception of it. In other words, the velocity determination necessitates a *second* clock, one located at the site of the flash. Moreover, if the time interval (of transit) is to be meaningful, then the two clocks, at the two locations, must be synchronized. That is, we must know that the hands of the one clock simultaneously read the same as the hands of the other clock. In short, the establishment of the simultaneity of two events in two different regions of space requires the synchronization of a pair of clocks at these locations, and the synchronization of the clocks at these locations of space presupposes that it has been established that their hands occupy the same positions at the same time, *i.e.*, simultaneously.

It should be emphasized that the logical difficulties inherent in this and allied *Gedanken* experiments can *not* be circumvented by synchronizing a pair of clocks together and then transporting one of them to a new location. This obviously begs the question. Furthermore, it presupposes that the time indication of a clock is independent of its path and velocity. In other words, it presupposes some such proposition to the effect that two clocks in synchrony at one place will still be in synchrony when brought to different places along different paths with different speeds. Aside from the impossibility of ever empirically verifying such a proposition, even were it true (whatever that may mean, in the light of our never being able to verify it), it is a proposition that is specifically denied by relativity.

It may not be inapposite to point out

* Received by the IRE, August 25, 1961; revised manusript received, September 5, 1961.

[1] P. M. Rapier, Proc. IRE (Correspondence), vol. 49, p. 1322; August, 1961.

that time measurement in general is fraught with dilemmas. Problems arise in the case of clocks in the same region of space and even in the case of individual clocks. When two clocks are in the same region of space we can, of course, synchronize them. That is, we can arrange matters so that the hand of one clock will be at position A simultaneous with the hand of another clock being at position A', and so that the hand of one is at B, C, and so on, simultaneously with the other clock's hand being at B', C', and so on. But we have no way of ascertaining whether a particular clock is measuring off equal time *intervals*, *i.e.*, we cannot verify empirically that the interval A–B is the same as the interval B–C, nor that the interval A'–B' is the same as the interval B'–C'. In the case of an individual clock, how do we know it is accurate? By an appeal to astronomical observations and the laws of mechanics, of course. But the accurate verification of these laws and facts presupposes the existence of accurate clocks to begin with.

C. K. Gordon, Jr.
Applied Science Div.
Litton Systems, Inc.
Woodland Hills, Calif.

Narrow-Band and Wide-Band Noise Figures*

Introduction

There are at present two generally used methods of specifying transistor low-frequency noise figure (NF): a wide-band and a narrow-band method. The wide-band method[1,2] averages noise over a wide audio range in a carefully controlled roll-off amplifier, while the narrow-band method[3] measures noise over a very narrow band at a spot frequency, usually 1 kc. In the hope of removing some of the confusion regarding the relative merits of each measurement, they will both be very briefly discussed.

Discussion

A transistor noise spectrum is shown in Fig. 1. For a high-gain planar transistor f_1 may be in the region of 200–500 cps, while for a more conventional type it may lie in the region of a few kc. The upper frequency f_2 occurs above audio frequencies[4] and will not be discussed here. The average ("wide-band") NF is also shown plotted in Fig. 1. An examination will clearly indicate whether a spot NF or a wide-band NF will be higher at a certain frequency.




Fig. 1—Transistor noise spectrum.

Generally, a planar transistor is about out of the $1/f$ region at 1 kc; therefore, a 1-kc NF will generally be lower than the wide-band NF. Other transistors are generally in the $1/f$ region at 1 kc, and therefore the 1-kc NF will generally be higher than the wideband NF. A 1-kc NF will indicate the degree that the transistor is in or out of the $1/f$ region and is therefore an excellent indication of its quality; a wide-band NF, while still useful, does not indicate directly the f_1 of a transistor. A complete specification would have both, but if only one is to be chosen, the 1 kc NF is very much the more desirable. This is particularly true when its ease of measurement is considered.

Paul J. Bénéteau
Fairchild Semiconductor Corp.
Mountain View, Calif.

* Received by the IRE, August 25, 1961.

[1] J. J. Davidson, "Transistor noise factor tester," *Semiconductor Products*, vol. 2, pp. 15–20; February, 1959.

[2] P. J. Bénéteau and L. Blaser, "The Measurement of Noise Figures of Transistors," Fairchild Semiconductor Corp., Mountain View, Calif., APP-13.

[3] L. Blaser, "1 kc Narrow-Band Automatic Transistor Noise Figure Test," Fairchild Semiconductor Corp., Mountain View, Calif., APP-29.

[4] H. F. Cooke, "Transistor upper noise corner frequency," Proc. IRE (Correspondence), vol. 49, p. 648; March, 1961.

Design of a Helium-Neon Gaseous Optical Maser*

A gaseous optical maser[1] has been designed and built at Raytheon. The aim of this communication is to provide construction information concerning this version of the gaseous optical maser.

This device, which is shown in Fig. 1, was operated successfully for the first time on June 26, 1961. The main frame consists of four Invar rods joined by stainless steel rings at each end. The Fabry-Perot mirrors, which are made of quartz, are so placed that their outermost surfaces are in the same plane as the ends of the Invar rods (see Fig. 2). By using stainless steel for all connecting parts, this placement of the quartz mirror plates assures that their innermost faces, which bear the reflecting coatings, remain a relatively constant distance (one micron per degree centigrade) apart during moderate variations in ambient temperature.

* Received by the IRE, August 18, 1961; revised manuscript received, September 1, 1961.

[1] A. Javan, W. R. Bennett, Jr. and D. R. Herriott, *Phys. Rev. Lett.*, vol. 6, pp. 106; 1961.




Fig. 1—Photograph of gaseous optical maser.




Fig. 2—Raytheon gaseous optical maser. (Details of copper gaskets and loading springs for vernier adjustment of parallelism not shown.)

The movement of the stainless steel end plates which carry the Fabry-Perot mirrors is controlled by differential screws threaded into the end plates and the end rings. Vernier adjustment is obtained by varying the spring pressure tending to squeeze the end plates and end rings together. This spring loading also takes up backlash in the threads of the differential screws. Hinge action is accomplished by deforming two studs in the hinge line at each end. These studs are stainless rods milled so that they will flex about one preferred axis. These uniaxial flexible studs have no backlash and cannot become frozen by corrosion if bakeout is required. The differential screws are thinned down in the portion between the two threaded sections to accommodate misalignment as the end plates are swung through a small arc.

The various sections of the optical maser are vacuum sealed with thin annealed copper gaskets. As the flange bolts are tightened at each joint, sharp cornered shoulders bite into the soft copper to accomplish the seal. A commercial quartz optical flat is sealed in this manner to provide an output window. A shoulder structure suitable for standard Varian Pyrex windows is also provided.

The Pyrex glass discharge tube is sealed to Kovar sleeves on the ends of the bellows assemblies. Only one bellows is required at each end.

The RF discharge is maintained by connecting a simple "ham" transmitter to three sheet brass electrodes wrapped around the discharge tube. The end electrodes are grounded and the center electrode goes to a pi section matching circuit in the transmitter. A rating of 60 watts is more than adequate to sustain maser action.

The quartz Fabry-Perot mirrors are made from 1/20 wavelength optical flats available from a precision gauge manufac-

turer. Dr. Turner of Bausch and Lomb, Inc., coated these plates with 13-layer dielectric coatings with maximum reflectivity peaked at approximately 1.2 microns.

After the maser was put into operation, a group of concentric rings was observed in the output from each end. Subsequent examination of quartz flats similar to the ones installed within the maser revealed a concentric ring pattern intrinsic in the quartz itself. Fringes formed by pressing two such flats together show that the ring pattern is not due to the surfaces. The Schlieren technique shows that the rings are due to regular optical density variations. A coarse granular structure is superimposed on the ring pattern. Since the maser resonator is actually formed between the coatings on the innermost surfaces of the flats, these density variations do not affect the optical maser operation of the device. They act only as filters inserted between the maser and the detector. These variations are the result of the way the quartz manufacturer accomplishes the fusion operation. Not all quartz blanks have the rings, and in the future an attempt will be made to pick ring-free optical flats.

Although the optical maser was designed to withstand a moderate bakeout, this operation has not been necessary. Internal clean-up was accomplished by ion bombardment within the maser filled with the correct gas mixture (0.1 mm. Hg of neon and 1.0 mm of helium obtained from commercial lecture bottles). Three evacuation and refill cycles were required before the scouring action of the gas discharge cleaned up practically all of the residual contaminants so that the maser could be operated continuously for long periods of time.

When either end plate is tilted slightly from perfect parallelism, the observed beam spot breaks up into two areas separated by a dark band. Further tilting produces a more complex pattern. The nature of these patterns is being investigated by means of interference experiments. The position of the dark nodal bands is constant throughout the maser as indicated by simultaneous examination of the outputs from the two ends.

A study in progress at Raytheon has indicated that the $2s_2$ neon level should be excited very much more strongly than the other $2s$ levels because the $2s_2$ level lies closest to the ^3S level in helium. The transition probabilities of the $2s \rightarrow 2p$ transitions have been calculated by Koster and Statz.[2] The transition having the highest probability which originates with a $2s_2$ level is the $2s_2 \rightarrow 2p_4$ transition which has a wavelength of 1.15259 microns. The $2p_4$ level has a large transition probability to the $1s_2$ level. Since the $1s_2$ level is not metastable, there should be relatively little blockage in the return of the atoms to the ground state via this route. Our only observed output to date, measured with a Perkin-Elmer 98G monochromator, has a wavelength of 1.153 microns. Javan and his co-workers also report that the 1.153 micron line is the strongest.[1]

Now that the practical details of operation have been solved, an extensive program of research is contemplated. Experimental observations on the transient effects of switching the excitation on and off, the effects of a magnetic field, and several interesting interference phenomena will be reported shortly.

C. F. Luck
R. A. Paananen
H. Statz
Research Division
Raytheon Company
Waltham, Mass.

[2] G. Koster and H. Statz, *J. Appl. Phys.*, vol. 32, p. 2054; 1961.

A Critical Note on "Steady-State Analysis of Circuits Containing a Periodically Operated Switch"*

In the above paper,[1] Fettweis obtains the frequency components of the current in and the voltage across a periodic ideal switch in series with an arbitrary time-dependent impedance and a cisoidal voltage source. He further shows that if any parameter in a circuit is switched periodically between two finite nonzero values, the problem can be treated by means of an equivalent series circuit incorporating an ideal switch. Now, in practice, 1) "switches" are seldom if ever ideal, *i.e.*, they generally have a noninfinite impedance when open and a nonzero impedance when closed (*e.g.*, a rectifier bridge in a series or shunt modulator); and 2) stepwise variation of reactive elements is seldom desired, let alone achieved, since it demands impulse functions of power unless synchronized with the instants of zero stored energy. It follows that the main practical interest in step-wise variation of parameters lies in resistance variation.

It is the purpose of this note to show that a direct approach to the problem of a circuit containing a resistance varying step-wise between finite nonzero values, (which may always be reduced to a simple series circuit by Thévenin's theorem) has the following advantages over Fettweis' suggested equivalent circuit approach: 1) no equivalent circuit is required; 2) as a result the current and voltage analysed are directly those in and across the periodic resistance and not in and across a mythical ideal switch; 3) no impulse functions occur, whatever the nature of the impedance in series with the periodic resistance; and 4) the tendency to impulse functions, which are solely due to idealising the switching process (*i.e.*, making the upper resistance value tend to infinity or the lower tend to zero), emerges clearly from the general analysis.

In Fig. 1, r varies step-wise between r_1 in the ranges $(N-\frac{1}{2})T<t<NT$ and r_2 in the ranges $NT<t<(N+\frac{1}{2})T$ (N=any integer, $0<r_2<r_1<\infty$). The equivalent series circuit containing an ideal switch is shown in Fig. 2. Attention is drawn to the following relations between the two circuits:

$$Z(s) = \frac{r_1^2}{r_1 - r_2} \cdot \frac{r_2 + Z'(s)}{r_1 + Z'(s)}, \tag{1}$$

$$i = I + \frac{V}{r_1}, \qquad v = V + \frac{r_1 r_2}{r_1 - r_2} i. \tag{2}$$




Fig. 1.




Fig. 2.

Considering the current I as the sum of steady-state and transient terms, we postulate

$$I = \frac{1}{r_1 + Z'(j\omega)} \left\{ e^{j\omega t} + \sum_1^m c_k e^{\gamma_k t} \right\},$$

$$V = -r_1 I, \quad -\frac{T}{2} < t < 0, \tag{3}$$

$$I = \frac{1}{r_2 + Z'(j\omega)} \left\{ e^{j\omega t} + \sum_1^m d_k e^{\delta_k t} \right\},$$

$$V = -r_2 I, \quad 0 < t < \frac{T}{2}, \tag{4}$$

in which the γ_k and δ_k are the finite zeros of $r_1+Z'(s)$ and $r_2+Z'(s)$, respectively. The number of these is clearly the same (m), being either the number of zeros or poles of $Z'(s)$, whichever is the greater.

The known periodicity of $Ve^{-j\omega t}$ and $Ie^{-j\omega t}$ with period $T \equiv 2\pi/\Omega$ justifies

$$V = e^{j\omega t} \sum_{-\infty}^{\infty} V_n e^{jn\Omega t},$$

$$I = e^{j\omega t} \sum_{-\infty}^{\infty} I_n e^{jn\Omega t}, \tag{5}$$

* Received by the IRE, August 21, 1961; revised manuscript received, September 11, 1961.

[1] A. Fettweis, IRE Trans. on Circuit Theory, vol. CT-6, pp. 252–260; September, 1959.

where

$$V_n = \frac{1}{T}\int_{-T/2}^{T/2} V e^{-j(\omega+n\Omega)t}dt,$$

$$I_n = \frac{1}{T}\int_{-T/2}^{T/2} I e^{-j(\omega+n\Omega)t}dt. \qquad (6)$$

Finally the circuit ohmic equation, from Fig. 1, gives

$$V_n = I_n Z'\{j(\omega + n\Omega)\}, \quad n \neq 0$$

but

$$V_0 = I_0 Z'(j\omega) + 1. \qquad (7)$$

Substituting the values of V and I from (3) and (4) in (6), and carrying out the integrations and substituting the resulting values of V_n and I_n in (7) gives the infinite set of equations

$$\frac{r_2 + Z_0'}{r_1 + Z_0'}\sum_1^m c_k \frac{1-(-1)^n e^{-X_k}}{X_k - jn\pi} + \frac{r_2 + Z_n'}{r_1 + Z_n'}\sum_1^m d_k \frac{(-1)^n e^{Y_k} - 1}{Y_k - jn\pi} = \frac{1-(-1)^n}{jn\pi}\left\{\frac{r_2 + Z_0'}{r_1 + Z_0'} - \frac{r_2 + Z_n'}{r_1 + Z_n'}\right\} \qquad (8)$$

in which

$$X_k \equiv \frac{T}{2}(\gamma_k - j\omega), \qquad Y_k \equiv \frac{T}{2}(\delta_k - j\omega),$$

$$Z_n' \equiv Z'\{j(\omega + n\Omega)\}, \qquad (9)$$

(8) being valid for all integral n, the RHS vanishing with n.

It may be noted that, if (8) is multiplied by $r_1^2/r_1 - r_2$, and (1) is used, (8) is *identical* with Fettweis' (16). Indeed it is clear from (1) that the zeros of $r_1 + Z'(s)$ are the poles of $Z(s)$ and the zeros of $r_2 + Z'(s)$ are the zeros of $Z(s)$, *i.e.*, that the γ and δ in (8) are identical with Fettweis' α and β. It then follows that the c and d in (8) are identical with Fettweis' a and b.

Any $2m$ independent equations of the infinite set (8) suffice the find the unknown c_k's and d_k's. Following Fettweis, however, (8) may be manipulated to give two sets of m equations for the c_k and d_k separately:

$$\left.\sum_{l=1}^m c_l \frac{1 - e^{-(X_l + Y_k)}}{X_l - Y_k} = \frac{1 - e^{Y_k}}{Y_k}\right\} k = 1,2,\cdots,m. \qquad (10)$$

$$\left.\sum_{l=1}^m d_l \frac{1 - e^{X_k + Y_l}}{X_k - Y_l} = \frac{e^{X_k} - 1}{X_k}\right\} \qquad (11)$$

A knowledge of the c_k and d_k at once allows V_n, I_n to be computed. Note that no restrictions have been applied to $Z'(s)$.

Impulse Functions in I and V

Let p', z', be the number of finite poles and zeros of $Z'(s)$. *If* $r_1 \to \infty$, the zeros of $r_1 + Z'(s)$ approximate to the poles of $Z'(s)$, p' in number, whereas if r_1 is finite and non-zero, the zeros of $r_1 + Z'(s)$ are p' or z' in number, whichever is the greater. Further, if Z' is passive, p' and z' cannot differ by more than unity. It follows that if Z' is passive and if $z' = p' + 1$, making $r_1 \to \infty$ reduces the number of finite zeros of $r_1 + Z'(s)$ from z' to $p' = z' - 1$, *i.e.*, one of these zeros moves to infinity, necessarily along the negative real axis since $r_1 + Z'(s)$ is also passive, *i.e.*, one of the γ_k, say γ_1, $\to -\infty$, *i.e.*, from (9), $RX_1 \to -\infty$. The terms involving c_1 in (10) become $-c_1 e^{-X_1 - Y_k}/X_1$, the other terms remaining finite. Hence $-c_1 e^{-X_1}/X_1$ tends to some finite limit C_1, which, with coefficient e^{-Y_k} replaces c_1 as the unknown in these equations. The contribution to V in the interval $-T/2 < t < 0$ is, from (3),

$$-\frac{r_1 c_1 e^{\gamma_1 t}}{r_1 + Z_0'} \to C_1 X_1 e^{X_1} e^{\gamma_1 t}$$

$$\to \frac{C_1 T}{2}\gamma_1 e^{\gamma_1(t+T/2)} e^{-j\omega T/2}$$

$$\to -\frac{C_1 T}{2} e^{-j\omega T/2}\delta\left(t + \frac{T}{2}\right),$$

namely an impulse function at $t = -T/2$ of amplitude $-C_1 T/2$ times the applied voltage at that instant. There is no corresponding impulse in I since $I = -V/r_1$ in the relevant interval.

The effect on (11) is trivial, the equation for the case $k = 1$ degenerating to

$$1 + \sum_1^m d_l = 0,$$

which, using (4), shows that when $t \to 0$ in the range $0 < t < T/2$, $V \to 0$ and I also $\to 0$ unless $r_2 = 0$.

A similar analysis shows that *if* $r_2 \to 0$ and Z' is passive with $p' = z' + 1$ then one of the δ_k, say δ_1, $\to -\infty$, *i.e.*, $RY_1 \to -\infty$. The terms involving d_1 in (11) approximate to $-d_1/Y_1$ for all k. Thus $-d_1/Y_1$ tends to some finite limit D_1 which, with coefficient unity, replaces d_1 as the unknown. The relevant contribution to I in the interval $0 < t < T/2$ is, from (4),

$$\frac{d_1 e^{\delta_1 t}}{r_2 + Z_0'} \to -\frac{D_1 T}{2Z_0'}\delta_1 e^{\delta_1 t} \to \frac{D_1 T}{2Z_0'}\delta(t),$$

an impulse at $t = 0+$ of amplitude $D_1 T/2Z_0'$ times the applied voltage at this instant. This is not reflected in the voltage since $V = -r_2 I$ in the relevant interval. The effect on (10) is trivial: the case $k = 1$ degenerates to

$$\sum_{l=1}^m c_l e^{-X_l} + 1 = 0,$$

i.e.

$$\sum_{l=1}^m c_l e^{-\gamma_l T/2} + e^{-j\omega T/2} = 0$$

showing, by comparison with (3), that $I = 0$ when $t \to -T/2$ in the range $-T/2 < t < 0$ and V also $\to 0$ unless $r_1 \to \infty$.

J. M. Layton
Elec. Engrg. Dept.
Univ. of Birmingham
Birmingham, Eng.

Cyclic Codes and Transition Coding*

Data transmission systems often operate by making a binary decision at each bit time on the state of the signal during the previous interval. That is, the receiver decides which of two voltage levels, frequencies, phases, or amplitudes (depending on the modulation used) was representative of the signal during the interval under consideration.

After the decisions concerning the successive states of the line have been made, it remains only to recover the binary data. There are two ways in which this is usually done.

In the first system, a 1 is identified with one state and a 0 with the other. For example, in an FM system, f_1 could represent a 1 and f_2 a 0. Such a system could be called "state" coding (it has also been called NRZ coding). The recovery of the binary data from the succession of states on the line in this case is a trivial operation.

Alternatively, a 1 can be identified with a change of state and a 0 with no change of state. Such a system has been called "transition" coding (it has also been called NRZI and NRZ1 coding). The interpretation to be used, "state" or "transition," depends, of course, on the technique used to encode the data.

It is interesting to compare the resulting error patterns with the two interpretations. If $E_s(x)$ is the error polynomial with state coding, then, with a few assumptions, the error polynomial with transition coding, $E_T(x)$, can be shown to be

$$E_T(x) = (1 + x)E_s(x). \qquad (1)$$

The following are the required assumptions:

1) The polynomials are obtained by forming the sum

$$\sum_{i=0}^{n-1} A_i x^i, \qquad (2)$$

where n is the number of bits in the message, and $A_i = 0$ if the $(i+1)$th bit of the message is received correctly and 1 if that bit is in error.

2) End-effects are negligible for a reasonably long message. This can be stated in many ways. One of these is to say that an error in the decision on the last state is impossible and that there exists a state known without error before the first state considered as a bit of information in "state" coding. The latter is justified in most practical cases and implies that the jth "transition" bit is between the states that represent $(j-1)$th and jth "state" bits.

If one chooses to change (2) to the form

$$\sum_{i=0}^{n-1} A_i x^{n-1-i}, \qquad (3)$$

then (1) becomes

$$E_T(x) = (1 + x)E_s(x)x^{-1}. \qquad (4)$$

This does not change materially the discussion at hand.

* Received by the IRE, September 5, 1961.

Let us suppose that the same cyclic code is being used for detection with the "transition" interpretation and with the "state" interpretation. From (1) and the work of Peterson and Brown,[1] it is evident that $E_T(x)$ is undetected if, and only if, $E_s(x)$ is undetected, providing only that the characteristic polynomial $P(x)$ of the cyclic code does not contain $(1+x)$ as a factor.

Furthermore, if $(1+x)$ is a factor of $P(x)$ and $P(x)$ is used in the "state" case and $(1+x)P(x)$ in the "transition" case, one can state that $E_T(x)$ is undetected if, and only if, $E_s(x)$ is undetected.

The foregoing does not apply to those cases where "transition" coding is used and the decision for each bit is made in the receiver by examining two consecutive states of the received signal simultaneously. It applies only where the decision for each state is made separately.

FRANCIS CORR
Compagnie IBM France
Nice, France

[1] W. W. Peterson and D. T. Brown, "Cyclic codes for error detection," PROC IRE, vol. 49, pp. 228–235; January, 1961.

A Transistor Equivalent Circuit*

Brunn[1] has developed an equivalent circuit for use in the design of video amplifiers which proves to be very useful. The devices of concern were alloy-fused so that no electric field was present in the base region. With the use of diffusion process and development of various graded base structures, the frequency range of the transistors was extended to hundreds of Mc ranges. But the electric field present in the base region introduced excess-phase shifts, which are especially effective in the common emitter configuration. Therefore, it will be useful to have an equivalent circuit which includes the excess-phase shift associated with the diffused base structures. It can be shown that if the impurity in the base region is exponential in form, a constant electric field exists in the base region. Under this condition, the transport factor of the device can be approximated by

$$\text{T.F.} = \frac{\alpha_0 e^{-jm\omega/\omega_\alpha}}{1 + j\omega/\omega_\alpha}, \qquad (1)$$

which is approximately equal to α (common-base short-circuit-current gain). In this expression m is the excess-phase shift at the 3-db point (radians in excess of 45°). The input impedance of a transistor, neglecting for the moment r_b', is given by

$$Z_{\text{in}} = \frac{r_e}{1-\alpha}. \qquad (2)$$

Substituting (1) into (2) we have

$$Z_{\text{in}} = \frac{r_e}{1 - \alpha_0 + j\omega/\omega_\alpha[1+\alpha_0 m]}, \qquad (3)$$

assuming $\omega \ll \omega_\alpha$.

Eq. (3) can be written as

$$Z_{\text{in}} = \frac{r_e/1-\alpha_0}{1 + j\omega/\omega_\alpha\left(\frac{1+\alpha_0 m}{1-\alpha_0}\right)}. \qquad (4)$$

Eq. (4) can be used to realize the hybrid equivalent circuit shown in Fig. 1. Here the current source has been represented in terms of V_1, which is valid for frequencies $\omega \ll \omega_T$ where ω_T is given by $\beta_0\omega_\beta$, the gain bandwidth product of the common emitter configuration. Now r_b' and C_c have to be added as extrinsic circuit parameters. As in vacuum tubes, C_c can be treated as the Miller effect capacitance, in which case its effect to the input is given by

$$C_c' = C_c\left(1 + \frac{R_L}{r_e}\right), \qquad (5)$$

where R_L/r_e is the low-frequency voltage gain (V_L/V_1).




Fig. 1.




Fig. 2.

The final equivalent circuit is shown in Fig. 2. With m over one in the present mesa and planar structures, its effect is evident from Fig. 2. Further, under the condition

$$\omega \ll \omega_T,$$

all effects are lumped into one pole which simplifies considerably the circuit design.

VASIL UZUNOGLU
Solid State Lab.
Westinghouse Electric Corp.
Baltimore, Md.

* Received by the IRE, June 19, 1961; revised manuscript received, September 8, 1961.

[1] G. Brunn, "Common-emitter transistor Video amplifiers," PROC. IRE, vol. 44, pp. 1561–1572; November, 1956.
See also D. O. Pederson and R. S. Pepper, "An evaluation of transistor low pass broadbanding technique," 1959 IRE WESCON CONVENTION RECORD, pt. 2, pp. 111–126.

A DC Pumped Amplifier with a Two-Dimensional Field Structure*

A number of structures exist for amplifying cyclotron waves on electron beams by interaction with periodic electrostatic or magnetic fields. These include the electrostatic quadrupole structure[1] and the magnetic ring structure,[2] both of which have field components which vary spatially in three dimensions.

Amplification is also possible in periodic structures of the type shown in Fig. 1 whose fields vary in two dimensions only (see also Gould and Johnson[3]). These structures would be particularly suited to use with strip beams in conjunction with Cuccia couplers and may have advantages for high power amplification. The potential distribution in the structure is given by




Fig. 1

$$V_s = V + \sum A_n V_E \frac{\cosh \beta_n x}{\cosh \beta_n a} \sin \beta_n z. \qquad (1)$$

$|V_E|$ is the electrode potential, A_n is an amplitude coefficient and $\beta_n = 2\pi(2m+1)/L$. Considering only the fundamental in the structure β_1, the equations of motion for a paraxial electron are

$$\frac{d^2x}{d\theta^2} + \frac{dy}{d\theta} - \mu x \sin \beta_1 z = 0 \qquad (2a)$$

$$\frac{d^2y}{d\theta^2} - \frac{dx}{d\theta} = 0 \qquad (2b)$$

$$\frac{d^2z}{d\theta^2} - \frac{\mu}{\beta_1}\cos \beta_1 z = 0. \qquad (2c)$$

$$\theta = \frac{B_z t}{\eta} = \omega_c t \quad \text{and} \quad \mu = \frac{\beta_1^2 A_1 V_E}{B_z^2 \eta \cosh \beta_1 a}.$$

For amplification, electrons must traverse a structure period in half an electron cyclotron period. Hence for small pump strengths $\sin \beta_1 z = \sin 2\theta$ in (2a) and (2b). Integrating (2b) and substituting for $dy/d\theta$ in (2a) gives an unstable Mathieu equation in x. This may be solved to give the subsequent dis-

* Received by the IRE, September 14, 1961.

[1] E. I. Gordon, "A transverse-field traveling-wave tube," PROC. IRE (Correspondence), vol. 48, p. 1158; June, 1960.
[2] T. Wessel-Berg and K. Blötekjaer, "Some Aspects of Cyclotron Wave Interaction in Time Periodic and Space Periodic Fields," presented at Internatl. Conf. on Microwave Tubes, Munich, Ger.; June 7–11, 1960.
[3] R. W. Gould and C. C. Johnson, "Coupled mode theory of electron-beam parametric amplification," *J. Appl. Phys.*, vol. 32, pp. 248–258; February, 1961.

placement of an electron in an input fast or slow wave entering the structure at (r, ϕ) as

$$x = r\left[\cosh\frac{\mu\theta}{4}\cos(\theta+\phi) - \sinh\frac{\mu\theta}{4}\cos(\theta-\phi)\right], \quad (3a)$$

$$y = r\left[\cosh\frac{\mu\theta}{4}\sin(\theta+\phi) - \sinh\frac{\mu\theta}{4}\sin(\theta-\phi)\right]. \quad (3b)$$

These equations show that its motion is that of an electron in the input fast or slow wave growing as $\cosh \mu\theta/4$ coupled with that in a slow or fast wave growing as $\sinh \mu\theta/4$.

The wave-coupling characteristics of this device are therefore the same as that of the dc quadrupole amplifier. The gain in decibels is given by

$$20 \log_{10} \cosh\left[\frac{A_1 V_E N\pi}{4V_0 \cosh \beta_1 a}\right];$$

N is the number of sections in the structure and V_0 the synchronous beam voltage for zero structure voltage.

Since there is a periodic electric field along the axis, electrons entering the structure at a velocity $u_0 = L\omega_c/\pi$ will have their average velocity over a structure period reduced and so synchronism will be lost. The velocity u (voltage V) required to maintain synchronism is found by integration of (1c) as

$$\frac{2u_0}{\pi} K\left[\frac{\pi}{2}, \sqrt{\frac{2A_1V_E}{A_1V_E + V\cosh\beta a}}\right] \cdot\left[1+\frac{A_1V_E}{V\cosh\beta a}\right]^{-1/2};$$

K is a complete elliptic integral. This expression increases with increasing $|V_E|$.

Like the dc quadrupole amplifier, synchronous waves are to a first order unaffected in the structure, and hence beam spread effects are small. In this tube they will be governed by the beam thickness, and so for a given beam this effect can be minimized by making it as thin and wide as possible.

The condition where the transit time over a structure period is a full cyclotron period can be investigated by writing $\sin\theta$ for $\sin 2\theta$ in (2a). It is then found that wave growth of order μ^2 may take place. This is generally negligible. The experimental results were obtained in a tube operating at 1100 Mc incorporating Cuccia couplers and a structure with 16 pairs of electrodes whose synchronous voltage was 450 v. A strip beam was used. Gain curves for various beam voltages in this range are shown in Fig. 2 together with the theoretical structure curve. Beam interception on the structure produced the turnover of the gain curves. For beam velocities corresponding to the ω_c-pumping region, both small gain ($\sim$3 db) and attenuation effects can be produced by increasing the pumping electrode voltages. The precise effect seems to depend on beam velocity and may be due to coupling between the fast cyclotron wave and the longitudinal space-charge waves produced by the axial fields in the structure.




Fig. 2

The author wishes to thank Dr. T. E. Allibone, Director of this Laboratory, for permission to publish this letter and P. Jeffree for tube construction and the experimental work.

J. C. Bass
Research Laboratory
Associated Electrical Industries,
Aldermaston Court, Berkshire England

Miniaturized *S*-Band Isolator*

As earlier reported,[1] the use of a different concept in strip transmission-line isolators resulted in a compact isolator for the VHF and UHF range. It is also possible to utilize a similar-type structure at the higher frequencies with the expected large improvement in physical size and weight of such devices. This note reports some results of an isolator in the *S*-band frequency region. The evident size advantage can be seen in Fig. 1. The dimensions were $2\frac{1}{2}\times\frac{7}{8}\times 1$ inch and the weight is 3 ounces.

A cross-sectional view of the isolator is shown in the inset of Fig. 2. Here, as in the UHF version, the ferromagnetic material is placed asymmetrically on the center conductor and magnetized perpendicular to the direction of propagation.

The same general characteristics noted in the low-frequency isolators were also observed at frequencies up to *C* band. The most useful characteristic was that for a particular ferrite geometry, the operating frequency could be lowered by a sizeable amount by sliding the ferrite slabs to a more symmetrical position on the center strip. This is evidenced in Fig. 2. Curve 2 represents the results with the ferrite slabs in one position and curve 1 shows the results of the ferrite being moved 0.030 inch to a more symmetrical position. Thus the operating frequency was conveniently shifted downward by approximately 400 Mc.




Fig. 1—Miniaturized isolator.




Fig. 2—Electrical characteristics of isolator.

The electrical results were notable; better than 10-to-1-db isolation-to-insertion-loss ratio was achieved from 2.8 to 3.4 Gc or a bandwidth of approximately 20 per cent. As curve 2 in Fig. 2 shows, the same nonreciprocal ratio was obtained from 3.2 to 3.7 Gc. The input VSWR was low in both cases.

The material used in this case was a common magnesium manganese ferrite. For greater power-handling capacity, it is possible to use a temperature-compensated material such as yttrium-gadolinium garnet.[2]

Acknowledgment

The author wishes to thank M. Liberman for his aid in the construction of this device.

D. Bruce Swartz
Applied Physics Sec.
Sperry Microwave Electronics Co.
Clearwater, Fla.

* Received by the IRE, September 11, 1961.

[1] D. B. Swartz, "Compact UHF isolator," *J. Appl. Phys.*, vol. 32, pp. 319–320; March, 1961.

[2] G. R. Harrison and L. R. Hodges, "Microwave properties of polycrystalline hybrid garnets," *Microwave J.*, vol. 4, pp. 53–65; June, 1961.

Pole-Zero Sensitivity Relationships*

Several interesting and useful relationships between the sensitivities of critical frequencies to element variations can be derived from the well-known relationships for frequency and magnitude scaling of network functions.[1] Thus, if s_0 is a critical frequency (either a pole or a zero) of a network containing l inductors, r resistors, and c capacitors:

$$\frac{ds_0}{s_0} = \sum_{i=1}^{l} S_{L_i}^{s_0} \frac{dL_i}{L_i} + \sum_{i=1}^{r} S_{R_i}^{s_0} \frac{dR_i}{R_i} + \sum_{i=1}^{c} S_{C_i}^{s_0} \frac{dC_i}{C_i}, \quad (1)$$

where

$$S_x^{s_0} \equiv \frac{x}{s_0} \cdot \frac{\partial s_0}{\partial x}.$$

If all elements of a kind vary together, (1) may be written in the form

$$\frac{ds_0}{s_0} = \frac{dL}{L} \sum_{i=1}^{l} S_{L_i}^{s_0} + \frac{dR}{R} \sum_{i=1}^{r} S_{R_i}^{s_0} + \frac{dC}{C} \sum_{i=1}^{c} S_{C_i}^{s_0}. \quad (2)$$

To accomplish frequency scaling such that $s_0 = as_0'$, the elements are varied according to: $L=(1/a)L'$, $C=(1/a)C'$, $R=R'$. Therefore,

$$\frac{ds_0}{s_0} = \frac{da}{a} = -\frac{dL}{L} = -\frac{dC}{C} \quad \text{and} \quad \frac{dR}{R} = 0. \quad (3)$$

Substituting (3) into (2) gives

$$\sum_{i=1}^{l} S_{L_i}^{s_0} + \sum_{i=1}^{c} S_{C_i}^{s_0} = -1. \quad (4)$$

To scale the magnitude of a network impedance by a factor b:

$$L = bL', \quad C = \frac{1}{b} C', \quad R = bR' \text{ while } s_0 = s_0'.$$

Therefore,

$$\frac{dL}{L} = \frac{db}{b} = -\frac{dC}{C} = \frac{dR}{R} \quad \text{and} \quad \frac{ds_0}{s_0} = 0. \quad (5)$$

Substituting (5) into (2) gives

$$\sum_{i=1}^{l} S_{L_i}^{s_0} + \sum_{i=1}^{r} S_{R_i}^{s_0} - \sum_{i=1}^{c} S_{C_i}^{s_0} = 0. \quad (6)$$

Since the sensitivities are phasors which depend on the network configuration and element values but *not* on the particular type of element variation, (4) and (6) give relationships which are valid for any kind of variation. However, unless the variation of all elements of a kind is uniform, (2) is not valid and the more general form, (1), must be used.

Often RC circuits containing no inductance are of interest, in which case $S_{L_i}^{s_0} = 0$, and (4) and (6) may be combined to yield

$$\sum_{i=1}^{r} S_{R_i}^{s_0} = \sum_{i=1}^{c} S_{C_i}^{s_0} = -1. \quad (7)$$

As an example of the application of (7), consider a parallel-T null circuit which is built into a functional electronic block so that environmental effects (temperature, etc.) cause a uniform variation on all elements of a kind. Then from (2) and (7),

$$\frac{ds_0}{s_0} = -\left(\frac{dR}{R} + \frac{dC}{C}\right). \quad (8)$$

Since the value given by (8) is real, the variation of the transmission zero will take place in a radial direction in the s plane. Therefore the null frequency will shift, but the Q of the null will remain unaffected. It can then be concluded that the Q is changed only when individual elements of a kind vary by different amounts. Eq. (8) also emphasizes the well-known fact that if the resistances and capacitances can be so compensated as to vary by equal amounts in opposite directions, the critical frequencies are unaffected. Eq. (7) serves as a useful check on the accuracy of calculated sensitivities, and also shows that regardless of the circuit configuration or the number of elements, the combined sensitivities remain constant. Therefore it would be fruitless to attempt to devise passive circuits with low sensitivities to the uniform type of variation that has been assumed. As pointed out, however, the uniform variation of one type of element can be made to compensate for the uniform variation of another type of element.

W. E. Newell
Semiconductors Devices Sec.
Electronics Dept.
Westinghouse Res. Labs.
Pittsburgh, Pa.

* Received by the IRE, September 25, 1961.

[1] M. E. Van Valkenburg, "Introduction to Modern Network Synthesis," John Wiley and Sons, Inc., New York, N. Y., Sec. 2.5; 1960.

A Waveguide In-Line Ferrite Rotary Joint*

Most waveguide rotary joints utilize the principle of converting the RF energy either to the TEM mode in coaxial or the TM_{01} mode in cylindrical line. The object of the conversion is to obtain a circularly symmetric transmission mode which is not effected by the physical orientation of the transmission line about the axis of propagation. A technique has been developed which essentially removes the effect of the transmission line altogether by means of confining the propagation in a circular mode within a rod of ferrite placed axially in the waveguide. The orientation of the waveguide walls then have little effect on the transmission, and one section of waveguide can be axially rotated with respect to a succeeding section. The VSWR and insertion loss can be made quite small and, although the device uses ferromagnetic principles, it is completely reciprocal.

* Received by the IRE, September 1, 1961.




Fig. 1—Experimental ferrite rotary joint.




Fig. 2—Plot of insertion loss and VSWR vs rotation. Field = 90 oe.

An experimental X-band model of the rotary joint is shown in Fig. 1. A quarter-inch diameter rod of R-151 ferrite is supported axially in RG-52 waveguide with polystyrene supports. The rod is 3 in long with $\frac{3}{8}$ in tapers at each end for matching. Experimental electromagnets are around the waveguide for application of a longitudinal magnetic field.

A plot of the measured VSWR and insertion loss is shown in Fig. 2. It is seen that the VSWR is less than 1.4 and the insertion loss less than 0.5 db for all angles of rotation. It should be noted that no particular attempt was made in this model to optimize the VSWR or insertion loss other than placing the simple taper at each end; nor was an optimum length chosen other than which gave reasonably low VSWR and insertion loss as shown. The purpose of the model was mainly to prove the concept of the rotary joint.

The reciprocity of the joint was checked by reversing the input and output connections. Also, the direction of the magnetic field was reversed by changing the polarity of the magnetizing current. In both cases the values of VSWR and insertion loss were the same.

The principle of operation of the device is the conversion of the dominant mode linearly-polarized field in the rectangular guide into a circularly-polarized field contained primarily within the ferrite rod and reconversion into linear polarization past the junction of the rotating sections. In order to effect these polarization changes, two ferromagnetic principles are utilized. One is the

usual Faraday rotation effect and the other a "variable dielectric waveguide" effect. The latter effect[1] is brought about by the change in the permeability of the ferrite due to the applied magnetic field. As the permeability increases, larger portions of the RF field in the waveguide will be contained within the ferrite rod. The high dielectric constant of the ferrite causes large phase shifts. At the same time, the field which enters the rod is Faraday rotated in polarization such that the field is now in two orthogonal components, one parallel to the broad wall and the second parallel to the narrow wall of the waveguide. In the absence of the ferrite rod, the parallel component would not propagate at frequencies below the cutoff as determined by the narrow wall dimension (for RG-52, below 14.75 Gc). However, since most of the field is within the ferrite, cutoff is at a much lower frequency. In the limiting case, where all the RF field is within the rod, cutoff would be determined by the propagation of the circular TE_{11} mode in a rod of dielectric constant ϵ and diameter d. This frequency is

$$f_c = \frac{c}{\lambda_c} = \frac{1.841c}{\pi d\sqrt{\epsilon}} \cong 8 \text{ Gc}.$$

If we assume that the major portion of the field is contained within the ferrite, the actual cutoff is somewhere close to, but slightly above, 8 Gc.

Because of the rectangular geometry, the phase velocities of the two orthogonal components will differ, and at some point along the rod, they will be in quadrature. This will give rise to an elliptically-polarized field, or if the field magnitudes are equal, to circular polarization. At this point along the rod, the walls of the waveguide have little or no effect on the propagation and the joint can be effectively placed here. Beyond this joint, a reverse process as described above takes place, reconverting the field back to the dominant linear mode in the waveguide.

In order to support the above, a test was performed to prove the circularity of the field at the junction. This consisted of measuring the circularity of the radiated field of the second half of the rod unbounded by the waveguide. A circular field with an ellipticity of only 1.4 db was measured.

In its final form, this joint will offer a convenient means for the embodiment of an end-on rotary joint in a very short length. With the electromagnets replaced with small permanent magnets, the length of the joint proper should be of the order of 2 to $2\frac{1}{2}$ in. The complexity of the mechanics of the joint is reduced since no choking is required as with usual joints and the bearing mechanism can be quite simple. In addition, this technique offers a simple means of transforming from linear to circular polarization which could be useful in many other component or antenna applications.

H. Saltzman
Douglas Research Corp.
Mount Vernon, N.Y.
A. Rossero
GPL Div.
General Precision, Inc.
Pleasantville, N. Y.

[1] J. A. Weiss, "A phenomenological theory of the Reggia Spencer phase shifter," Proc. IRE, vol. 47, pp. 1130–1137; June, 1959.

Signal-to-Noise Ratios in Photoelectric Mixing*

Quantum mechanical analyses[1] have shown that even an ideal linear amplifier has an inherent noise of $h\nu$ watts/cps referred to the input, *i.e.*, the total noise power spectral density $\psi(\nu)$ is given by

$$\psi = \frac{h\nu}{\exp(h\nu/kT) - 1} + h\nu. \qquad (1)$$

The first term is the thermal noise (one-dimensional black-body radiation) from the source at temperature T. The second term represents the minimum additional noise due to quantum effects, and is usually ascribed entirely to spontaneous emission in the amplifying medium.

For $h\nu \gg kT$, thermal noise virtually disappears, and $\psi \to h\nu$. Thus if an ideal amplifier has a pass band B cps wide centered at a frequency $\nu \gg kT/h$, and if the input signal power is $\bar{P}_s$, the output signal-to-noise ratio (SNR) will be

$$\frac{S}{N} = \frac{P_s}{\int_{\nu-B/2}^{\nu+B/2} \psi(\nu)d\nu} = \frac{\bar{P}_s}{h\nu B}. \qquad (2)$$

The SNR does not become infinite in the absence of thermal noise: instead the familiar kT is replaced by $h\nu$. At room temperature and optical frequencies $h\nu/kT \approx 90$, so that (2) applies and gives the performance of an ideal coherent light amplifier.

A photocell is a perfect square-law device in the sense that the current is proportional to the incident light power. If two similarly polarized coherent, coincident beams of light of slightly different frequency fall on a photocell, the power, and hence the photocurrent, will vary at the difference frequency. Photocells can thus be used as mixers having conversion gain, and it is interesting to compare their signal-to-noise performance with that of the ideal amplifier.

Fig. 1 shows a balanced mixer consisting of two photocells and a half-reflecting half-transmitting mirror, $M/2$, which serves as a hybrid junction. For such a mirror, the reflection and transmission coefficients are $e^{i\pi/4}/\sqrt{2}$ and $e^{-i\pi/4}/\sqrt{2}$, respectively, and so if we write the instantaneous signal power as

$$P_s = [A_s \cos(\omega_s t + \pi/4)]^2$$

and the instantaneous local oscillator power as

$$P_0 = [A_0 \cos(\omega_0 t - \pi/4)]^2$$

we find

$$P_1 = \tfrac{1}{2}(A_0 \cos\omega_0 t + A_s \cos\omega_s t)^2,$$
$$P_2 = \tfrac{1}{2}(A_0 \sin\omega_0 t - A_s \sin\omega_s t)^2. \qquad (3)$$

(We have complicated the expressions for P_s and P_0 to simplify those for P_1 and P_2. The relative phase of signal and local oscillator is significant only when $\omega_0 = \omega_s$.)

Now, if η is the quantum efficiency of a photocell, *i.e.*, the average number of electrons produced per photon absorbed, then the photocurrent is given by $i = \eta q P/h\nu$, where q is the charge on the electron. Thus we find, ignoring any frequency components higher than $\delta \equiv \omega_s - \omega_0$, that

$$i_1 + i_2 = \frac{\eta q}{2h\nu}(A_0^2 + A_s^2), \qquad (4)$$

while the signal current i_s is given by

$$i_s = i_1 - i_2 = \frac{\eta q}{h\nu} A_0 A_s \cos\delta t, \qquad (5)$$

and has the mean-square value

$$\overline{i_s^2} = \left(\frac{\eta q}{h\nu}\right)^2 \frac{A_0^2 A_s^2}{2}. \qquad (6)$$

If the bandwidth of the circuits following the mixer is B cps, the mean-square shot noise affecting the output will be

$$\overline{i_n^2} = 2qB(i_1 + i_2) = \frac{\eta q^2 B}{h\nu}(A_0^2 + A_s^2). \qquad (7)$$

Taking the ratio of (6) to (7), we have

$$\frac{S}{N} = \frac{\eta}{2h\nu B} \frac{A_0^2 A_s^2}{A_0^2 + A_s^2}. \qquad (8)$$

As A_0 is increased, both the signal current (5) and the SNR (8) increase, the former without limit, the latter approaching the value

$$\left.\frac{S}{N}\right|_{\max} = \frac{\eta}{h\nu B} \frac{A_s^2}{2} = \eta \frac{\bar{P}_s}{h\nu B}, \qquad (9)$$

where $\bar{P}_s$ is the average value of P_s.

Comparing this result with (2), we see that if the quantum efficiency were unity, the photoelectric heterodyne converter would have the same signal-to-noise performance as the ideal amplifier, which is perhaps not too surprising.

But now let us consider the performance of the device as a homodyne converter, or synchronous detector. To do this we merely set $\omega_0 = \omega_s$ so that $\delta = 0$, and we now find from (5) that i_s has a mean-square value twice as great as before, cos δt having been replaced by unity. The output noise in the band from 0 to B cps will still be given by (7). As a result, we now find in the limit, as $(A_0/A_s) \to \infty$:

$$\left.\frac{S}{N}\right|_{\max} = \eta \frac{\bar{P}_s}{\left(\frac{h\nu}{2}\right)B}. \qquad (10)$$

With unity quantum efficiency the perform-




Fig. 1—A balanced photoelectric mixer.

* Received by the IRE, August 10, 1961; revised manuscript received September 19, 1961.

[1] See, *e.g.*, M. W. P. Strandberg, "Inherent noise of quantum-mechanical amplifiers," *Phys. Rev.*, vol. 106, pp. 617–620; May 15, 1957.

ance is now twice as good as that of an *ideal* amplifier, which does seem surprising.

The two-fold improvement with homodyne as against heterodyne mixing occurs because the signal conversion gain is doubled while the noise (which arises after mixing) is unaffected. This improvement is not found in the usual RF mixer where the noise enters with the signal and changes in conversion gain affect both equally.

It should be noted that the result (10) *cannot* be obtained by later synchronous detection of the IF resulting from an initial optical heterodyne mixing. In order to obtain the base-band B as in (10), the IF band would have to extend from $\delta - B$ to $\delta + B$ and so have twice the width assumed in (7). This doubles the total IF noise power, but only half of this total, *i.e.*, the amount given by (7), is demodulated along with the signal to produce base-band power. Thus the ratio (9) is again obtained.

The results (9) and (10) include only the usual Poisson distributed shot noise of the photocurrent. If one assumes a noise power of $h\nu/2$ watts/cps associated with the input signal due to the zero-point energy of the electromagnetic field, then (10) becomes

$$\left.\frac{S}{N}\right|_{\max} = \frac{\overline{P}_s}{\left(1+\frac{1}{\eta}\right)\left(\frac{h\nu}{2}\right)B} \qquad (11)$$

which for $\eta = 1$ agrees with the SNR for an ideal linear amplifier. However, one must then assume this same $h\nu/2$ noise to be present in the input to any linear amplifier which leaves only $h\nu/2$ for additional noise due to spontaneous emission.

Additional noise might also result from statistical fluctuations in η, but this component, if it exists, should vanish as $\eta \to 1$. The quantum efficiency of good silicon photodiodes is probably close enough to unity to test experimentally whether (10) or (11) holds.

In any event, photoelectric mixing appears very promising as a means for linear amplification and frequency conversion of coherent optical signals.

B. M. Oliver
Hewlett-Packard Co.
Palo Alto, Calif.

Efficiency of Frequency Multipliers Using Charge-Storage Effect*

The disadvantage of the basic circuit for harmonic generation using the charge-storage effect of a p-n junction, treated by Leenov and Uhlir,[1] is that unwanted power is dissipated in both load and generator resistors. The basic circuit is shown in Fig. 1(a). By referring to the ideal current waveform shown in Fig. 2, it is seen that if both the input and output are resonated to allow only sinusoids at two frequencies to exist across the junction, no discontinuity and hence no harmonic generation, can occur due to the charge-storage effect; the circuit is as shown in Fig. 1(d).




Fig. 1—Practical circuits.
(a) S_1 and S_2 open—untuned case.
(b) S_1 open, S_2 closed—tuned output.
(c) S_1 closed, S_2 open—tuned input.
(d) S_1 and S_2 closed—tuned input and output (basic circuit for multiplication using depletion-layer effect).




Fig. 2—Current waveforms for untuned cases.

In contrast to the untuned case treated by Leenov and Uhlir, that of the output load being resonant at $n\omega_1$ has been analysed; the circuit is as shown in Fig. 1(b). The results for a $\times 2$ and a $\times 10$ generator are shown in Fig. 3(a) and (b), respectively. It is seen that there is a value of R_n/R_g which gives a minimum loss for a given angle of forward drive. To illustrate the behavior, an angle of 120° was chosen for the calculation; in fact, this angle is not the optimum one and a slight improvement can be obtained by increasing the conduction angle to about 140° (approximately 1 db for the $\times 2$ circuit and 4 db for the $\times 10$ circuit). The important point to note is that the efficiency is inherently limited by the nature of the nonlinearity being utilized. From the curves it is seen that the theoretical limiting value of power loss for the $\times 2$ multiplier is 7.2 db and for the $\times 10$ multiplier 25 db, giving an improvement in each case of about 3 db over the untuned circuit. The discrepancy between these values obtained theoretically and the measured results may be accounted for by the deterioration in waveform due to the slow recovery time of the diode used (collector-base junction of OC44, input at 350 kc). The actual waveform obtained is shown in Fig. 2.

The alternative to resonating the load is to prevent harmonic currents from flowing in the generator resistance. In this case, if the generator is matched to the input impedance of the multiplier, theory predicts




Fig. 3—Results for tuned output circuit.
(a) $\times 2$ circuit. (b) $\times 10$ circuit.

that an over-all improvement of 5.0 db may be obtained compared with the untuned circuit for $\phi = 120°$. The arrangement used is shown in Fig. 1(c) and measurements on this circuit closely confirmed the theoretical figure of 5.0 db. The matching conditions for this circuit can be obtained from the Fourier coefficients for the fundamental frequency and yield the result $R_n \doteq \frac{1}{3} R_g$ for $\phi = 120°$ (see Fig. 2).

To give some idea of the relative merits of an optimized charge-storage type multiplier compared with a depletion layer nonlinearity multiplier, consider each type when multiplying by 10. The charge-storage type has a limiting efficiency of -23 db (tuned and matched input, $\phi = 120°$). For a similar loss, theoretical calculations indicate that using depletion layer nonlinearity, the circuit being as shown in Fig. 1(d), a diode with a Q factor $\doteq 100$ at the fundamental frequency is required, (estimated for the case of $V_1 = 0.95\ V_b$, where V_1 is the peak applied voltage and V_b is the bias voltage, assuming $\gamma = \frac{1}{2}$, *i.e.*, abrupt junction).[2] It should be noted that if three $\times 2$ stages using the depletion-layer effect are cascaded (giving approximately the same order of multiplication, *i.e.*, $\times 8$ compared with $\times 10$), an over-all efficiency of about -5 db should be obtained, if a diode of similar Q is available, (*i.e.*, $Q = 100/n$ at the output frequency $n\omega_1$).

It may thus be concluded that, in general, the highest efficiency may be obtained by cascading lower order (*e.g.*, $\times 2$) multipliers using the depletion-layer effect. For high order single-stage multipliers (having the obvious advantage of simplicity) it may be advantageous to use the charge-storage effect, depending upon whether or not a high Q diode is available. The important point to note is that the efficiency of the

* Received by the IRE, July 24, 1961; revised manuscript received, September 25, 1961.

[1] D. Leenov and A. Uhlir, "Generation of harmonics and subharmonics at microwave frequencies with p-n junction diodes," Proc. IRE, vol. 47, pp. 1724–1729; October, 1959.

[2] The optimum value of V_1/V_b, and hence the value of Q factor, depends critically upon the forward conduction characteristics of the diode.

charge-storage type multiplier is inherently limited. It may also be relevant in practical applications that the power handling capabilities of this type of multiplier are considerably greater than those of the depletion-layer type. It should also be borne in mind that in practical circuits it is of course possible that harmonic generation may occur due to a combination of the two mechanisms, (as in the simple two frequency depletion-layer multiplier, with finite loss resistance).

The author gratefully acknowledges the many helpful discussions he had with Dr. A. R. Boothroyd and Dr. D. F. Page.

D. J. Roulston
Dept. of Elec. Engrg.
Imperial College of Science and Tech.
London, England

Transistor Storage Time in Circuits with Speed-Up Capacitors*

Base speed-up capacitors have been treated in connection with storage time primarily to calculate τ_s.[1] Presented here are expressions which have been obtained for storage time using arbitrary values of speed-up capacitance C for the circuit shown in Fig. 1.




Fig. 1—Experimental circuit and associated waveforms.

When the transistor is saturated and when τ_s, an effective minority carrier lifetime, is used in place of the usual τ, the continuity equation can be integrated once in a field-free base region. Use of the divergence theorem then leads to the following first-order differential equation:

$$I_{Bs} - i_b(t) = K_s p_c(t) + k_s \frac{dp_c(t)}{dt}, \qquad (1)$$

where

I_{Bs} = base current at saturation threshold,
K_s = proportionality factor between p_c and saturated base current,
k_s = proportionality factor between charge stored and p_c for the diode with emitter and collector tied together,




Fig. 2.




Fig. 3.

$i_b(t)$ = instantaneous base current,
$p_c(t)$ = instantaneous minority carrier density in base at the collector junction.

Eq. (1) is valid for storage-time calculations only because it relates the excess current necessary to maintain the excess charge, Q_{Bx} (*i.e.*, the additional charge over and above that required for the threshold of saturation) in the base. By using the initial condition

$$p_c(0) = \frac{1}{K_s}\{I_{Bs} - I_{B1}\}, \qquad (2)$$

(1) can be integrated recalling that p_c is zero at time t_s. Thus,

$$I_{Bs} = e^{-t_s/\tau_s}\left[\frac{1}{\tau_s}\int_0^{t_s} i_b(t)e^{t/\tau_s}dt + I_{B1}\right], \qquad (3)$$

where

I_{B1} = final equilibrium "on" base current with device in saturation.

For a step voltage V_g, (3) yields for storage time

$$t_s = \tau_s \ln\left[\frac{(I_{B1} - I_{B2})\left(1 + \frac{R}{R_s}\frac{t_0}{t_0 - \tau_s}\right)}{I_{Bs} - I_{B2} + \frac{R}{R_s}\left(\frac{t_0}{t_0 - \tau_s}\right)(I_{B1} - I_{B2})e^{-t_s/t_0}}\right], \qquad (4)$$

where

I_{B2} = "off" generator voltage divided by the total series resistance $(R + R_s)$,

and

$$t_0 \equiv \frac{RR_sC}{R + R_s}. \qquad (5)$$

When C and, hence, t_0, is set equal to zero, (4) degenerates to the frequently used expression for storage time.[1-3] Eq. (4) is plotted in Fig. 2.

An approximation to (4) also appears in Fig. 2. This approximation is valid when $t_s \gg t_0$, and is described by

$$t_s = \tau_s \ln\frac{(I_{B1} - I_{B2})\left(1 + \frac{R}{R_s}\frac{t_0}{t_0 - \tau_s}\right)}{I_{Bs} - I_{B2}}. \qquad (6)$$

Because of practical experimental limitations, the experimental value of τ_s determined may correspond to the value predicted by (6). In view of this, τ_s may be calculated from (6) under the condition $t_0 \ll \tau_s$. For the experimental procedure outlined by Sparkes and Beaufoy (*i.e.*, $I_{B2}=0$, $R_s \ll R$), (6) simplifies to

$$\tau_s = \frac{RC}{1 - \frac{I_{Bs}}{I_{B1}}}. \qquad (7)$$

Fig. 3 is a plot of (7) and the experimental data (i_c=3 ma) from Fig. 11 of Sparkes.[4] Note that (7) describes the initial variation of τ_s with excess base current. At large values of I_{Bx}, the deviation of experimentally observed data may be explained by effects due to high injection levels. Fig. 3 is similar to Fig. 11 of Sparkes.[4] The explanation given in this reference for the initial variation in τ_s (the change in charge due to collector depletion region narrowing) is a contributing factor. However, it is believed that an important contributing factor to this variation is given by (7).

Expressions for t_s have also been derived for ramp and exponential forms of the generator V_g output. It is anticipated that the work described here will be published in detail in the near future.

R. P. Nanavati
Syracuse Univ.
Syracuse, N. Y.
R. J. Wilfinger
General Products Div.
Development Lab.
IBM Corp.
Endicott, N. Y.

* Received by the IRE, September 7, 1961; revised manuscript received, September 15, 1961.

[1] R. Beaufoy and J. J. Sparkes, "The junction transistor as a charge controlled device," *ATE J.*, vol. 13, pp. 310–327; October, 1957.

[2] J. J. Ebers and J. L. Moll, "Large signal behavior of junction transistors," Proc. IRE, vol. 42, pp. 1761–1772; December, 1954.

[3] J. A. Ekiss and C. D. Simmons, "Junction transistor response characterization," *Solid State J.*, vol. 2, pp. 17–24; January, 1961.

[4] J. J. Sparkes, "A study of the charge control parameters of transistors," Proc. IRE, vol. 48, pp. 1696–1705; October, 1960.

Improvement in the Performance of an Automatic Noise Figure Meter with a Liquid-Nitrogen-Cooled Termination*

NOMENCLATURE

B = amplifier bandwidth
F = noise figure meter reading
F' = actual noise figure of amplifier
G = amplifier gain
k = Boltzmann's constant (1.38×10^{-23} watt-sec/°K)
L = directional coupler insertion loss
N = available noise power from amplifier when noise generator is off
N^* = available noise power from amplifier when noise generator is on
t_1 = coupling power coefficient of directional coupler
t_2 = resistive power transmission coefficient of the direct path through coupler
T = termination temperature
T_0 = defined ambient temperature (290°K)
T_0' = actual ambient temperature
T_e = rated excess noise of noise generator
T_e' = actual excess noise of noise generator
T_R = excess-noise temperature of amplifier.

In the measurement of the noise figure of low-noise (less than 6-db) amplifiers, it is difficult to obtain an accurate scale reading on standard automatic noise figure meters. One method of expanding the scale and increasing the measurement accuracy employs a directional coupler and cooled termination,[1] as shown in Fig. 1.

The definition of noise figure[2] is the ratio of the available noise power from the amplifier to the available noise power from an ideal amplifier, both with input termination temperature T_0. In the case of the normal automatic noise figure meter where a noise source is connected directly to the amplifier input, the available output noise power with the noise source not turned on is

$$N = kT_0BGT. \tag{1}$$

The available output noise power with the noise generator on is

$$N^* = kT_0BGF + kT_eBG. \tag{2}$$

The noise power ratio is

$$\frac{N^*}{N} = 1 + \frac{T_e}{FT_0}. \tag{3}$$

The noise power ratio for the amplifier under evaluation (Fig. 1) is




Fig. 1.




Fig. 2.




Fig. 3.

Setting (3) and (4) equal to each other and substituting $t_2(1-t_1)=1/L$ gives

$$T_R = FT_0t_1\frac{T_e'}{T_e} - T_0' + \frac{T_0'-T}{L}. \tag{5}$$

Noise figure is related to receiver noise temperature by

$$F' = 1 + \frac{T_R}{T_0}. \tag{6}$$

Eq. (5) is plotted on the right-hand side of Fig. 2 for a typical example.

The following parameters were measured at 2388 Mc using a Narda directional coupler Model 3003–30 and a Bendix noise tube Model TD-40:

$$L = 1.026(0.11\text{ db})$$
$$t_1 = 0.0107(-19.70\text{ db})$$
$$T_e'/T_e = 0.794(-1\text{ db})$$
$$T_0 = T_0' = 290°\text{K}$$
$$T = 77.5°\text{K}.$$

$$\frac{N^*}{N} = \frac{T_R + (T_0' + T_e')t_1 + [T_0'(1-t_2) + Tt_2](1-t_1)}{T_R + T_0't_1 + [T_0'(1-t_2) + Tt_2](1-t_1)}. \tag{4}$$

For comparison, a plot of noise figure (as conventionally measured) vs receiver temperature is shown on the left-hand side of Fig. 2. Reading accuracy is better with the new technique, particularly in the measurement of low noise temperatures. Values of L and t_1 were obtained with the Weinschel dual-channel insertion test set (accurate to 0.02 db), and T_e'/T_e was evaluated with a 2388-Mc mixer and recorder system calibrated to about 1 per cent using a liquid-nitrogen-cooled termination, room-temperature termination, and AIL precision attenuator.

The coupling value for the directional coupler is best chosen to give a noise figure reading on the meter near the center of the scale (the most accurate portion of the scale). A noise figure meter reading of 18 db for the above example is obtained with an amplifier noise temperature of 72°K.

This improved measurement technique also slightly reduces the sensitivity to excess-noise temperature error.[3]

Fig. 3 shows a typical liquid-nitrogen-cooled termination, 50-ohm transmission line, and container as used in the method described. The container and transmission line are constructed from stainless steel to reduce thermal heat loss. The Stoddart Aircraft Company termination has a special insert selected to have a VSWR of less than 1.05 at the operating frequency when cooled to the temperature of liquid nitrogen (77.5°K).

This technique of noise figure measurement extends the range of an automatic noise figure meter for use with low-noise amplifiers, increases the accuracy, and is relatively simple to implement.

C. T. STELZRIED
Jet Propulsion Lab.
California Inst. Tech.
Pasadena, Calif.

* Received by the IRE, August 7, 1961; revised manuscript received, September 18, 1961. This paper presents the results of one phase of research carried out at the Jet Propulsion Lab., California Institute of Technology, under Contract No. NASw-6, sponsored by NASA.

[1] M. Negrete, "Additional conveniences for noise figure measurements," *Hewlett Packard J.*, vol. 10; February–March, 1959.

[2] H. T. Friis, "Noise figures of radio receivers," PROC. IRE, vol. 32, pp. 419–422; July, 1944.

[3] *Research Summary No. 36-7*, Jet Propulsion Lab., Calif. Inst. Tech., Pasadena, Calif., vol. 1, p. 85; February 5, 1961.

A Tunnel-Diode Wide-Band Frequency Doubling Circuit*

A typical tunnel-diode volt-ampere characteristic shows a marked similarity to a parabola in the region of its peak current operating point. If a sinusoidal voltage is applied to a diode biased at its maximum current point, the diode current variations will be at twice the frequency as the applied voltage. See Fig. 1. If the selected region of the diode provides a transfer function of Ke^2 and $e=\sin\omega t$; then

$$i = K\sin^2\omega t = K\frac{(1-\cos 2\omega t)}{2}.$$

The steady-state component is removed by ac coupling.

* Received by the IRE, September 25, 1961.




Fig. 1.




Fig. 2.

The waveforms from the circuit of Fig. 1 show a 2-kc voltage variation being derived from a 1-kc signal source. See Fig. 2. The sweep speed in Fig. 2 is 50 μsec/cm and the vertical sensitivity is 50 mv/cm.

Frank D. Neu
Lawrence Radiation Lab.
University of California
Berkeley, Calif.

A Note on Antenna Breakdown*

Introduction

The fact that the breakdown potential for an antenna varies with pressure and that the recovery potential is somewhat lower than the breakdown potential is well treated in the literature. The general shape of the curves are shown in Fig. 1.

The temptation is to devote primary attention to the breakdown curve. The researcher concentrates on determining and improving the breakdown curve. The designer concentrates on providing an antenna that operates below the breakdown curve. The recovery curve is, for the most part, ignored. This reasoning makes an apparently logical assumption that there is no need to be concerned with antenna recovery characteristics if the antenna does not break down. There are some circumstances, however, that cause antenna breakdown from an external stimulus, and then the antenna will remain in this condition as long as the antenna operating point is above the recovery curve.




Fig. 1.

Discussion

An excellent example of the breakdown stimulus is missile staging, which was demonstrated during the Titan missile program. Some Titan missiles that successfully staged suffered breakdown of the telemetry antenna, operating at about 200 Mc, while Titan missiles that had not staged passed through the identical altitude region without incurring breakdown. The antenna breakdown began at the time of missile staging.

An explanation for this series of events can be deduced by reviewing a few simple factors associated with the staging of the Titan. The first stage is jettisoned, and the second stage is ignited while the two stages are close to each other. The highly ionized exhaust from the second stage is deflected from the first stage. Some of this plasma finds its way to the telemetry antenna. Curves similar to Fig. 1 exist for the antenna operating in the plasma. However, the curves are at a much lower voltage level than those for antenna operation in air. If the plasma breakdown voltage drops below the antenna operating point, breakdown occurs. The antenna operates in the plasma for a short period of time as the missile accelerates away from the first stage. The change from antenna operation in plasma to operation in air is a continuous time function. As the effect of the plasma decreases, the breakdown and recovery curves once more return to the original values. But if the antenna has broken down, it will stay in that condition until the operating point goes below the recovery curve. Now the performance of the Titan telemetry antenna can be explained. When the Titan did not stage, there was no stimulus and thus no breakdown. Some of the missiles that staged did not incur antenna breakdown. For these missiles, the plasma breakdown voltage did not drop below the antenna operating point. In the case of the remaining missiles, the plasma breakdown voltage dropped below the operating point causing breakdown in the presence of the plasma. This momentary breakdown became sustained breakdown because the operating point was above the recovery curve.

An additional example is afforded by an analysis of the performance of the telemetry antenna on a nose cone that was used on the Atlas and Thor missiles. Antenna breakdown during powered flight was more common on the Atlas than on the Thor. For our purposes, there are two major differences between the powered flight of the Atlas and Thor missiles: the Atlas achieves higher velocities than the Thor, and the Atlas stages whereas the Thor does not. There has been speculation that some of the Atlas nose-cone antenna breakdown was caused by shock ionization due to the higher velocity. A comparison of the Atlas and Thor velocities through the critical altitude region, 150,000 to 300,000 feet for the frequencies involved, rule out shock ionization. There is no evidence that the Atlas nose cone is subjected to shock ionization during powered flight. An examination of the records reveals that on a substantial percentage of tests, breakdown of the antenna begins at staging. This evidence indicates strongly that on some Atlas test flights, breakdown of the nose-cone telemetry antenna was caused by plasma in the vicinity of the antenna, which in turn was the result of staging.

Conclusion and Recommendations

Much work has been done to improve the antenna characteristics represented by the breakdown curve. The results of this work will certainly be useful on vehicles that do not encounter a stimulus to cause momentary breakdown.

However, antenna performance can be governed by the recovery curve and not the breakdown curve when an external stimulus, such as staging, is encountered. Those engaged in antenna breakdown research should give more consideration to recovery characteristics of antennas.

The antenna designer who is concerned with breakdown must decide whether the breakdown or recovery curve governs for his application. In these cases where the recovery curve governs, he must be extremely careful when he tries to apply theory or experimental data that deals only with the breakdown curve, since some of the techniques developed to improve the breakdown characteristics may have little effect on the recovery characteristics.

E. L. Tarca
Space Systems Technology Group
Siegler Corp.
Inglewood, Calif.

* Received by the IRE, September 25, 1961.

Contributors



M. P. Bachynski

Morrel P. Bachynski was born in Bienfait, Saskatchewan, Can., on July 19, 1930. He received the B.E. degree in engineering physics in 1952, and the M.Sc. degree in 1953, both from the University of Saskatchewan, Saskatoon, Can., and the Ph.D. degree from McGill University, Montreal, Can., in 1955.

Until October 1955, as a member of the staff of the Eaton Electronics Research Laboratory (McGill University), he was engaged in investigations of aberrations in microwave lens systems. Since that time he has been with the RCA Victor Research Laboratories, Montreal, Can., concerned primarily with short-wave propagation and plasma physics problems, where he is now Director of the Microwave Physics Laboratory. In addition, he is connected with the Graduate School of McGill University, teaching classes in antenna and electromagnetic theory in the Extension Department.

Dr. Bachynski is a member of the Canadian Association of Physicists and Commission VI of the Canadian National Committee of URSI.

❖




J. R. Baird

Jack R. Baird (S'60) was born in Colchester, Ill., on May 1, 1931. He received the B.S. and M.S. degrees in electrical engineering in 1958 and 1959, respectively, from the University of Illinois, Urbana, where he is presently working on the Ph.D. degree.

From 1951 through 1954 he served in the U. S. Air Force as an Instructor in the radar school at Lowry Air Force Base, Denver, Colo. He joined the Ultramicrowave Group, at the University of Illinois, in 1956 as an undergraduate technician designing and constructing high-power modulators, waveform generators, and special power supplies for low millimeter wavetubes. He is currently a Graduate Research Assistant. His research interests have included problems in field emission, nonlinear microwave plasmas, megavolt electronics, and submillimeter waves.

Mr. Baird is a member of Tau Beta Pi.

❖



W. Bernstein

W. Bernstein received the B.S. degree from New York University, N. Y., in 1944. From 1946 to 1948 he did graduate work at the University of Chicago, Ill., and the University of Wisconsin, Madison.

He is a physicist in the Electron Dynamics Department of the Hughes Research Laboratory, Malibu, Calif. Prior to joining Hughes, he was at Project Materhorn, Princeton University, N. J., and at Brookhaven National Laboratory. His fields of specialization are plasma physics and low-energy nuclear physics.

❖




A. W. Biggs

Albert W. Biggs (S'56–M'59) was born in Toledo, Ohio, on October 4, 1926. He received the B.S. degree in electrical engineering from Washington University, St. Louis, Mo., in 1948, and the M.B.A. degree from Stanford University, Stanford, Calif., in 1950. He is currently completing his dissertation for the Ph.D. degree in electrical engineering at the University of Washington.

From 1955 to 1957, he was at the University of Washington as an Instructor in Electrical Engineering. Since 1957, he has been with the Boeing Company, Seattle, where he has been engaged in research on microwave and low-frequency propagation.

Mr. Biggs is a member of the American Physical Society.

❖



G. D. Boyd

Gary D. Boyd (S'53–M'60) was born in Los Angeles, Calif., on September 14, 1932. He received the B.S., M.S., and Ph.D. degrees in 1954, 1955, and 1959, respectively, from the California Institute of Technology, Pasadena, where he was engaged in plasma physics research.

He is presently engaged in research on optical masers at the Bell Telephone Laboratories, Inc., Murray Hill, N. J.

Dr. Boyd is a member of the American Institute of Physics.



G. R. Brewer

George R. Brewer was born in New Albany, Ind., on September 10, 1922. He received the B.E.E. degree in electrical engineering in 1943 from the University of Louisville, Ky., and the M.S.E. degree in electrical engineering in 1948, the M.S. degree in physics in 1949, and the Ph.D. degree in electrical engineering in 1951, all from the University of Michigan, Ann Arbor.

From 1943–1944 he worked with the M.I.T. Radiation Laboratory, Cambridge, Mass., where he was concerned with magnetron development. In 1944 he joined the Naval Research Laboratory, where he did research and development on microwave electron tubes and in 1947 he began research on magnetrons, space charge, and associated subjects at the Engineering Research Institute of the University of Michigan. He joined Hughes Research Laboratories, Malibu, Calif., in 1951, where he has worked with traveling-wave tubes, electron guns, electron beam focusing systems, and more recently with ion propulsion. He is currently Head of the Electron Dynamics Department.

Dr. Brewer is a member of the American Rocket Society, the American Physical Society, Sigma Xi, RESA, and Phi Kappa Phi.

❖



G. C. Cloutier

Gilles G. Cloutier was born in Quebec City, Canada, on June 27, 1928. He received the B.A. degree in 1949 and the B.Sc. degree in physics in 1953, both from Laval University, Quebec. He was employed in the Research Laboratories of the Defense Research Board of Canada from 1953–1954. He received the M.Sc. and Ph.D. degrees from McGill University, in 1956 and 1959, respectively


In 1959 he joined the Research Laboratories of the RCA Victor Company, Montreal, where he is carrying out research in the field of microwave physics, plasmas and ionic propulsion.

Dr. Cloutier is a member of the Canadian Association of Physicists, the American Rocket Society and Sigma Xi.

❖

Paul D. Coleman (A'45–M'55) was born in Stoystown, Pa., on June 4, 1918. He received the B.A. degree from Susquehanna

University, Selinsgropve, Pa., in 1940, the M.S. degree in physics from Pennsylvania State University, University Park, in 1942, and the Ph.D. degee in physics from the Massachusetts Institute of Technology, Cambridge, in 1951.



P. D. Coleman

He was employed as a physicist with the U. S. Signal Corps and subsequently with the U. S. Air Force at Wright Air Development Center, Dayton, Ohio, from 1942 to 1946. During this period, he was engaged in work on electromagnetic theory, and received the Army Air Force Meritorious Civilian Award in 1946 for his contribution to aircraft antenna theory.

From 1946 to 1951, he was a physicist with the U. S. Air Force at the Cambridge Air Research Center, Mass., and later a Research Associate in physics at the Research Laboratory of Electronics, at M.I.T., where he was concerned with the generation of submillimeter waves.

In 1951, he became an Associate Professor in Electrical Engineering at the University of Illinois, Urbana, where he established the Ultramicrowave Group in the Electrical Engineering Research Laboratory. He is presently a Professor on the graduate electrical engineering staff, teaching and directing research on submillimeter wave generation, detection, and propagation. In 1959, he became a member of the Board of Technological Counselors of FXR, Inc., Woodside, N. Y., and in 1960 was elected Chairman.

He is a member of Sigma Xi, the American Physical Society, and Pi Mu Epsilon.

❖

Frederick W. Crawford was born in Birmingham, England, on July 28, 1931. After four years in industry, during which he obtained the B.Sc. degree in engineering from London University, London, England, he spent four years at Liverpool University, Liverpool, obtaining the Ph.D. degree for research on arc discharges in 1955, and the Diploma in Education in 1956. He obtained the M.Sc. degree in Mathematics from London University in 1958.




F. W. Crawford

During 1956–1957, he worked on electronic instrumentation as a scientist with the Research Department of the National Coal Board. The next two years were spent as a Senior Lecturer in Electrical Engineering at the College of Advanced Technology, Birmingham, England. Since the end of 1959, he has been working on plasma instabilities as a Research Associate at the Microwave Laboratory, Stanford University, Stanford, Calif. He is presently on a temporary leave to study at the Centre des Etudes Nucléaires de Saclay, France.

Dr. Crawford is a member of Sigma Xi, an associate member of the IEE, and an associate of the Institute of Physics of Great Britain.

❖

Malcolm R. Currie (S'52–A'55–SM'58) was born in Spokane, Wash., on March 13, 1927. He received the B.A. degree in physics in 1949, the M.S. degree in 1952, and the Ph.D. degree in 1954, all from the University of California, Berkeley.



M. R. Currie

From 1944 to 1947 he served in the U. S. Navy Air Corps. He was associated with the Microwave Laboratory at the University of California from 1949 to 1951. From 1952 to 1954 he was a Research Assistant in the Electronics Research Laboratory. He was an Instructor in the Department of Electrical Engineering during 1953–1954. Since 1954 he has been associated with the Research Laboratories of the Hughes Aircraft Company, Malibu, Calif., where he has been concerned primarily with problems in microwave and millimeter wave tubes, plasma physics, optical masers and ion propulsion. From 1957 to 1959 he was Manager of the Electron Dynamics Department. In 1960 he became Director of the Physics Laboratory, and he is now Associate Director of the Research Laboratories.

Dr. Currie received the Eta Kappa Nu Award (outstanding young electrical engineer) for 1958. He is a member of the American Physical Society, the American Rocket Society, Sigma Xi, RESA, and Phi Beta Kappa.

❖

Daniel G. Dow (S'53–M'57) was born in Ann Arbor, Mich. on April 26, 1930. He received the B.S. degree in engineering physics in 1952 and the M.S.E.E. degree in 1953, both from the University of Michigan, Ann Arbor, and the Ph.D. degree from Stanford University, Stanford, Calif., in 1958.



D. G. Dow

From 1953 to 1955 he was a Project Officer in the Electron Tube Branch at Wright Air Development Center, Dayton, Ohio, responsible for research and development in microwave tubes. From 1955 to 1958, he was a Research Assistant at Stanford and holder of Fellowships from the Sylvania Electric Corporation and the Bell Telephone Laboratories. From 1958 to 1961 he was a member of the faculty of electrical engineering at the California Institute of Technology, Pasadena, and a Consultant to the Physics Laboratory of the Hughes Research Laboratories, Culver City, Calif. In July of 1961 he joined the Central Research Laboratories of Varian Associates, Palo Alto, Calif., where he is currently conducting research in the fields of plasma physics and physical electronics.

Dr. Dow is a member of the American Physical Society and Sigma Xi.

❖

Lester M. Field (M'48–F'52) was born in Chicago, Ill., on February 9, 1918. He received the B.S. degree from Purdue University, Lafayette, Ind., in 1939, and the Ph.D. degree from Stanford University, Calif., in 1943.



L. M. Field

Upon receiving his Ph.D. degree, he joined the Electron Dynamics Group of the Bell Telephone Laboratories. After early work in electron optics and magnetrons, he collaborated with Dr. J. R. Pierce to become co-developer of the first stable traveling-wave tubes. This device introduced new principles into the art of microwave amplification which served as the opening wedge to a whole new realm of types of amplifiers and new interaction processes. In 1946 he returned to Stanford University where he was one of the originators of their Electron Tube Laboratory. During this period he invented many modern forms of traveling-wave tube propagating structures, the velocity-jump amplifier (and noise de-amplifier), scanning search-receivers, transverse current amplifiers, and many others. He became Stanford University's youngest full Professor at 32. In 1953 he became a full Professor at the California Institute of Technology, Pasadena, and there established a tube research activity which expanded into a group studying plasma physics and microwave interaction with matter. Here he invented several forms of beam-plasma amplifiers and studied fundamental plasma behavior. During this period he also became the Associate Director of the Hughes Research Laboratories, Los Angeles, Calif., and became Head of its Physics Laboratory in 1955. As Head of the Physics Laboratory, he participated in establishing programs in plasma studies, fusion power, ion propulsion and masers, as well as maintaining a continuing interest in microwave tubes through patents on new forms of high-power tube structures, such as the stub-supported contrawound helix and folded waveguide circuit. In recent years, he has been concerned with monitoring and welding together research, development,

production and business groups to make an over-all microwave tube enterprise.

Dr. Field is a member of Sigma Xi, and the American Physical Society. He is a Wilbur Scholar of Tau Beta Pi, and recipient of the 1949 Eta Kappa Nu Outstanding Young American Engineer Award.

❖

Ian P. French was born in Cuenca, Ecuador, on April 22, 1935. He received the B.Sc. (Hons.) degree in applied physics from St. Andrews University, Scotland, in 1958. He is continuing his studies under the auspices of the Extension Department of McGill University.



I. P. French

He joined Canadair, where he was engaged in radome design and test in 1958. In 1959 he joined the RCA Victor Research Laboratories, Montreal, Can., where he has spent some time on millimeter-wave studies. Since then he has been engaged in investigations of the electromagnetic properties of plasmas, and is presently associated with experiments on microwave propagation through plasmas and aerospace communication studies.

❖

Ladislas Goldstein (SM'55–F'56) was born in Dombrad, Hungary, on February 6, 1906. He received the B.S. degree in physics from the College of the City of Nagyvarad, and the M.S. degree from the University of Paris, France, in 1928, where he was a Fellow from 1929 to 1934, receiving the D.Sc. degree in nuclear physics in 1937.



L. Goldstein

From 1934 to 1937 he was an Assistant Instructor at the University of Paris, and from 1937 to 1940 he was a Research Associate and a Fellow of the National Center Research of France. From 1940 to 1942 he was a Research Associate at the Institute of Atomic Physics. He was the Director of the laboratories at the Canadian Radium and Uranium Corporation from 1942 to 1944, and from 1944 to 1945 he was a research worker with the Admiralty Research Laboratories, Teddington, England. From 1945 to 1951 he was a Research Physicist with the Federal Telecommunication Laboratory, and in 1951 he became a Professor of Electrical Engineering at the University of Illinois, Urbana.

He has concentrated his efforts in the field of nuclear physics. He has worked on the use of gas-discharge phenomena in microwave physics, microwave propagation through media containing free electrons, infrared radiation detection, and the application of ionizing radiations of radioactive substances.

Dr. Goldstein is a member of the Physical Society.

❖

Roy W. Gould (S'48–A'51–M'56) was born in Los Angeles, Calif., on April 25, 1927. He received the B.S.E.E. degree from the California Institute of Technology, Pasadena, in 1949, and the M.S. degree from Stanford University, Stanford, Calif., in 1950. He completed the requirements for the Ph.D. degree in physics at the California Institute of Technology in 1955. During his graduate study, he held a National Science Foundation Fellowship and a Howard Hughes Fellowship.




R. W. Gould

In 1951 and 1952, he was employed at the Caltech Jet Propulsion Laboratory as a Research Engineer and worked on the guidance system of the Corporal missile. Since 1955, he has been on the staff of the California Institute of Technology, where he now an Associate Professor of Electrical Engineering and Physics, teaching and conducting research in the field of plasma physics.

Dr. Gould is a member of Tau Beta Pi, Sigma Xi, and the American Physical Society.

❖

Theodore P. Harley (S'58–M'59) was born in New York, N. Y., on July 25, 1925. He received the B.S.E.E. degree in 1948 from the College of the City of New York, and the M.S.E.E. degree from Colorado University, Boulder, in 1953. He has also completed additional graduate studies at the University of Washington, Seattle, leading to a Ph.D. degree and has taught a course in electronics.



T. P. Harley

From 1948 to 1953, he was employed by the Bureau of Reclamation, Denver, Col. In 1953 he joined the staff of the Boeing Company, Seattle, Wash., as an Associate Research Engineer. Currently, he is working in the Aero-Space Division of this company doing work in propagation through plasmas.

❖

John C. Helmer, for a photograph and biography, please see pages 1588–1589, of the October, 1961, issue of these Proceedings.

Edward W. Herold was born in New York, N. Y., in 1907. He received the B.Sc. degree in physics from the University of Virginia, Charlottesville, in 1930, the M.Sc. degree from the Polytechnic Institute of Brooklyn in 1942, and an honorary D.Sc. degree, also from the Polytechnic Institute of Brooklyn, in 1961.



E. W. Herold

From 1924 to 1926 he worked at Bell Telephone Laboratories, and from 1927 to 1929 with E. T. Cunningham, Inc. He was with RCA at Harrison, N. J., from 1930 to 1942 and from 1942 to 1959 at RCA Laboratories, Princeton, N. J., where he became Director, Electronic Research Laboratory. In 1959, he joined Varian Associates, Palo Alto, Calif. as Vice President, Research. He has made his career in research and development, specializing in electron tubes, semiconductor physics and devices, signal-to-noise problems, and plasma physics.

He is a member of Phi Beta Kappa and Sigma Xi, and has been active in IRE affairs including membership on the Board of Directors from 1956 to 1958.

❖

Sheldon B. Herskovitz (S'55–M'56) was born in Brooklyn, N. Y., on March 13, 1930. He received the B.S. degree in chemistry in 1951 from the Massachusetts Institute of Technology, Cambridge. He served in the Air Force for two years with the Vacuum Tubes Group of the Air Force Cambridge Research Center, Cambridge, Mass., and then returned to Harvard University, Cambridge, where he received the M.A. degree in chemistry in 1955. During graduate work, he was employed as an engineer in the Research and Development Group of Microwave Associates, then in Boston, Mass. Since 1955, he has been employed at the Air Force Cambridge Research Laboratories, where he has been concerned primarily with an experimental research program involving the interaction of ionized gases and microwave energy.



S. B. Herskovitz

Mr. Herskovitz is a member of the American Physical Society, the American Vacuum Society, and the Scientific Research Society of America.

❖

Henri Hodara was born in Paris, France, on January 8, 1926. He received the B.S.E.E. degree from the Massachusetts Institute of

Technology, Cambridge, in 1947; the M.S.E.E. degree from Stanford University, Calif., in 1949; and is presently completing his Doctoral dissertation at the Illinois Institute of Technology, Chicago.



H. Hodara

From 1949 to 1956 he was primarily active as a Management Consultant, in both the U.S.A. and abroad. He was a Project Engineer for Cook Research Laboratories from 1956 to 1960. While at Cook, he designed a UHF subminiature transmitter for a recovery package, airborne ferret equipment, and object locators. In 1960 he joined The Hallicrafters Company, Chicago, Ill., as Head of Space Communications and has since then become Associate Director of the Research and Development Division. His work is primarily in the field of communications; he has published extensively on wave propagation in anisotropic plasmas, re-entry blackout, and communications. He is a Hallicrafters' Consultant to the Physical Science Laboratory of the New Mexico State University and Bell Telephone Laboratories on plasma propagation for Nike-Zeus. He has also acted as a Consultant to the Army Corps of Engineers, Fort Belvoir, Va., on various problems of weak signal detection and electromagnetic theory and has taught evening graduate school in the Electrical Engineering Department of the Illinois Institute of Technology.

❖

Robert L. Jepsen (A'52–SM'57) was born in Valley, Wash., on June 16, 1920. He received the B.S. degree in electrical engineering from Washington State College, Pullman, in 1944 and the Ph.D. degree in physics from Columbia University, New York, N. Y., in 1951.




R. L. Jepsen

He was employed by the Radio Corporation of America, Lancaster, Pa., from 1944 to 1946 as a magnetron research and development engineer. Between 1946 and 1951, he was a Research Associate at the Columbia Radiation Laboratory where he was engaged in research on magnetrons. He joined Varian Associates, Palo Alto, Calif., as a Research Physicist in 1951, and served as Director of the microwave tube research until 1957. He was awarded the first Varian Associates Advanced Study Grant and spent the 1957–1958 academic year at Harvard University, Cambridge, as a Research Fellow working in the fields of ferrites and ferromagnetic insulators. Upon returning to Varian Associates, he worked as a Research Physicist in the areas of plasma physics and vacuum physics. He is presently Manager of Research and Development for the Vacuum Products Division.

Dr. Jepsen is a member of Tau Beta Pi and Sigma Xi.

❖

Gordon S. Kino (S'52–A'54) was born in Melbourne, Australia, on June 15, 1928. He received the B.S. and M.S. degrees in mathematics in 1948 and 1950, respectively, from London University, London, England. In 1955 he received the Ph.D. degree in electrical engineering from Stanford University, Stanford, Calif.



G. S. Kino

He joined the Mullard Radio Valve Company, Salfords, Surrey, England, in 1947, where he did research on microwave triodes, traveling-wave tubes, and klystrons. From 1951 to 1955 he was employed as a Research Assistant at the Electron cs Laboratory of Stanford University, where he carried out research on traveling-wave tubes and electromagnetic theory. He became a member of the technical staff of the Bell Telephone Laboratories, Murray Hill, N. J., in 1955, where he was associated with the Electron Tube Development Department and did research on magnetrons. He returned to the Stanford Microwave Laboratory in 1957, and is now an Associate Professor in the Electrical Engineering Department. He is in charge of a plasma physics group at Stanford.

Dr. Kino is a member of Sigma Xi, the American Physical Society, and the American Rocket Society.

❖

Ronald C. Knechtli (M'45) was born in Geneva, Switzerland, on August 14, 1927. He received the Diploma in electrical engineering in 1950 and the Ph.D. degree in 1955 from the Swiss Federal Institute of Technology, Zurich.




R. C. Knechtli

From 1951 to 1953 he was a Research Engineer at Brown Boveri, Baden, Switzerland, in the field of microwave tubes and then a Research Assistant at the Massachusetts Institute of Technology, Cambridge. From 1953 to 1958 he worked on low-noise microwave tubes and plasma physics at the RCA Laboratories, Princeton, N. J.; in 1958 he joined the Hughes Research Laboratories, Malibu, Calif., where he now heads the Plasma Research Section.

Dr. Knechtli is a member of the American Physical Society, Sigma Xi, and RESA.

K. V. Narasinga Rao (S'55) was born in Vizagapatam, India, on June 27, 1933. He received the B.Sc. (Hons) degree in physics from Andhra University, Waltair, India, in 1952, and the diploma (D.I.I.Sc.) in electrical technology from the Indian Institute of Science, Bangalore, in 1955.




K. V. Narasinga Rao

He joined the Andhra Electricity Department, Madras, India, as a junior electrical engineer for a short period in 1955. In 1957 he received the M.S. degree in electrical engineering from the University of Illinois, Urbana, where he is currently a Research Assistant in the Gaseous Electronics Laboratory, and where he is finishing his Ph.D. requirements.

Mr. Narasinga Rao is a student member of the American Geophysical Union.

❖

Dipak L. Sengupta (S'55–M'59) was born in Bengal, India, on January 16, 1931. He received the B.Sc. degree in physics and the M.Sc. degree in radiophysics, both from Calcutta University, Calcutta, India, in 1950 and 1952, respectively. He received the Ph.D. degree in electrical engineering from the University of Toronto, Toronto, Ontario, in 1958.



D. L. Sengupta


Until 1954 he worked as a Government of India Senior Research Scholar at the Bengal Engineering College of Calcutta University. At the University of Toronto, he was a part-time Research Assistant in electrical engineering; there he designed and developed the antenna assembly of the University's radio-telescope. During the year of 1959 he worked in the Gordon McKay Laboratory of Harvard University, Cambridge, Mass., as a Research Fellow in electronics in the Division of Applied Physics and Engineering. At present, he is an Associate Research physicist at the Radiation Laboratory of the University of Michigan, Ann Arbor.

Dr. Sengupta is a member of Sigma Xi and the American Physical Society.

❖

Issie P. Shkarofsky (M'58) was born in Montreal, Canada, on July 4, 1931. He graduated in 1952 from McGill University, Montreal, with the B.Sc. degree and first-class honors in physics and mathematics. In the following year, 1953, he obtained the

M.Sc. degree, conducting his research at the Eaton Electronics Research Laboratory, McGill University, in the fields of microwave optics and antennas.



I. P. Shkarofsky

He then joined the microwave tube and noise group at the Eaton Electronics Research Laboratory, McGill, and received the Ph.D. degree in 1957 with a dissertation on modulated electron beams in space-charge-wave tubes and klystrons.

After graduation, he joined the Microwave Research Laboratory, RCA Victor Co., Ltd., Montreal, where he has participated in research on microwave diffraction and millimeter waves. He is presently engaged in research on electromagnetic wave interaction with plasmas, plasma kinetics and plasma stability.

Dr. Shkarofsky is an associate member of the Canadian Association of Physicists.

❖

Leonard S. Taylor (A'54–M'56) was born in New York, N. Y., on December 28, 1928. He received the A.B. degree in Physics from Harvard University, Cambridge, Mass., in 1951, and the M.S. and Ph.D. degrees in Physics from New Mexico State University, University Park, in 1956 and 1960, respectively.



L. S. Taylor

From 1951 to 1954 he was employed by the Raytheon Manufacturing Company, where he worked in microwave component development and guided missile flight test analyses. From 1955 to 1959 he was at White Sands Missile Range, N. Mex., where he was engaged in the development of special microwave telemetry equipment and communications systems analysis. Since August, 1960, he has been with the Advanced Aerodynamics Operation of the General Electric Space Sciences Laboratory, Valley Forge, Pa., where he has been engaged in research on the interaction of electromagnetic waves and plasmas.

Dr. Taylor is a member of the American Physical Society and Sigma Pi Sigma.

❖

Richard L. Taylor was born in Milford, N. H., on September 22, 1931. He received the B.S.E.E. degree from the University of New Hampshire, Durham, in 1954.

He was then employed by the Air Force Cambridge Research Center, Cambridge, Mass., where he worked on radar devices. He entered active service with the Army in 1955, during which time he again was connected with radar systems. He returned to the Air Force Cambridge Research Laboratories in 1957, where he is presently employed as an Electronic Engineer in the Gaseous Electronics Section. His present work deals with the measurement of plasma properties by the use of microwave techniques.



R. L. Taylor

❖

George Tyras (S'54–M'57) was born in Czestochowa, Poland, on November 26, 1920. He received the B.S.E.E. degree from Newark College of Engineering, N. J., in 1954 and the M.S.E.E. degree from the University of Washington, Seattle, in 1957.



G. Tyras

From 1952 to 1954, he was affiliated with Charles Engelhard, Inc., Newark, N. J., where he was engaged in research and development of industrial instruments. In 1954 he joined the Boeing Company, Seattle, Wash., where he was engaged in the analysis of fire control systems and radar detection. Later he became involved in analysis of electromagnetic propagation through anisotropic ferrites. Presently he is engaged in research on radio-frequency propagation through ionized gases. He is also doing further graduate work in electrical engineering at the University of Washington under the Boeing Graduate Study Program.

❖

Joseph T. Verdeyen (S'59) was born in Terre Haute, Ind., on August 15, 1932. He received the B.S.E.E. degree from Rose Polytechnic Institute, Terre Haute, in 1954.



J. T. Verdeyen

He then participated in the Communication Development Training Program at Bell Telephone Laboratories, Murray Hill, N. J., until 1955, at which time he entered the Signal Corps for two years. During this time, he participated in the evening graduate program of Rutgers University, Fort Monmouth, N. J. In September, 1957, he became an Assistant Instructor in Electrical Engineering at Rutgers, where he received the M.S.E.E. degree in 1958. He then joined the staff of the University of Illinois, Urbana, as an Instructor in Electrical Engineering, and began work towards the Ph.D. degree. He is currently engaged in research in plasma physics.

Mr. Verdeyen is a member of Tau Beta Pi and Blue Key.

❖

Jim Y. Wada (S'56–M'57) was born in Lomita, Calif., on May 15, 1934. He received the B.S. degree in engineering from the University of California at Los Angeles in 1956, and the M.S.E.E. degree from the University of Southern California, Los Angeles, in 1958. Currently he is studying at U.S.C. on a part-time basis for the Ph.D. degree.



J. Y. Wada

In 1956 he joined the technical staff of Hughes Aircraft Company, Malibu, Calif., where he participated in the research and development of radar transmitters and low-noise microwave tubes. Since 1959 he has been engaged in plasma physics research.

Mr. Wada is a member of the American Physical Society and Tau Beta Pi. He was a recipient of the Hughes M.S. Fellowship.

❖

James S. Yee (M'59) was born in Canton, China, on October 24, 1927. He received the B.S. degree in physics and the M.S. degree in electrical engineering in 1952 and 1956, from the University of Washington, Seattle. He has taken graduate courses on electromagnetic theory at the University of Southern California, Los Angeles, and is continuing graduate work on microwave networks and electromagnetic theory at the University of Washington.



J. S. Yee

From 1952 to 1953 he was with the U. S. Geological Survey, Sacramento, Calif. From 1953 to 1954 he was a Research Fellow at the Electrical Engineering Department, University of Washington. He was with the Boeing Company, Seattle, where he worked on radar-tracking error problems from 1954 to 1955, and from 1955 to 1957 he was at the Hughes Research Laboratories, Culver City, Calif., where he conducted research on linear and two-dimensional slot array designs, surface wave antennas and electromagnetic diffraction problems, especially those related to radar cross section of simple and complex shapes. Presently, he is a Research Specialist with the Antennas and Radomes Unit, Boeing, conducting research work on antennas operating in a hypersonic environment, and on microwave and plasma interactions.

Mr. Yee is a member of Phi Beta Kappa, and an associate member of Sigma Xi.

Books

Satellite Environment Handbook, Francis S. Johnson, Ed.

Published (1961) by Stanford University Press, Stanford, Calif. 144 pages+3 index pages+xii pages +references by chapter+5 appendix pages. Illus. 7×10. $5.50.

Although there has not yet been a spate of books on the upper atmosphere, their numbers are certainly beginning to respond to the greatly increased scientific and technological activity in this field. This book, written by authors at the Space Physics Research Group of the Missiles and Space Division of the Lockheed Aircraft Corp., Palo Alto, Calif., is a concise and up-to-date compendium of information "compiled principally in response to numerous questions from engineering projects directed to the Space Physics Research organization."

The editor says: "Many of the phenomena described in this book were not known or even suspected three years ago. Some of our present ideas will undoubtedly have to be altered in varying degrees within the next year or two. It is probable that there are still some major surprises in store for us."

The chapters and authors are:

1) Structure of the upper atmosphere (16 pages): F. S. Johnson
2) Structure of the ionosphere (20 pages): W. B. Hanson
3) Penetrating radiation (26 pages): A. J. Dessler
4) Solar radiation (11 pages): F. S. Johnson
5) Micrometeorites (10 pages): J. F. Vedder
6) Radio noise (6 pages): O. K. Garriott
7) Thermal radiation from the earth (6 pages): F. S. Johnson
8) Geomagnetism (26 pages): A. J. Dessler

The first two chapters describe the upper atmosphere. They are accurate and reasonably adequate except that the chapter on the ionosphere does not contain a section on the propagation of radio waves. Because of the existence in the ionosphere of free electrons, of vertical gradients in the electron concentration, of the pervading magnetic field of the Earth, and of the collisions with other constituents, this is a very complicated matter which certainly is one of the most important aspects of satellite environment. Nearly all of our knowledge of the ionosphere has been obtained from its effect on radio wave propagation. Consequently, there are necessarily numerous references to these effects in this chapter but they require a prior knowledge on the part of the reader for understanding. The chapter should also include such classical things as the Chapman theory of layer formation, and the close relationship of the *E*-region ionization with solar zenith angle, in contrast to the large role of geomagnetic control in *F*-region ionization. Also, some mention should have been made of field-aligned ionization and of estimates and observations of integrated electron content from which it is concluded that there is something like four times as much ionization above hmF2 as there is below it.

The second two chapters describe the particle and electromagnetic radiation environment to which the atmosphere is exposed from without. These chapters are especially interesting because they contain so much new information. As is true with the first two chapters as well, they cannot fail to give even the specialist new perspective and stimulation. The chapter on penetrating radiation treats particles trapped in the Earth's magnetic field, solar flare radiation, and cosmic radiation. The motion of trapped particles and the way in which the motion is controlled by the field, are described very clearly. Although the book does not use the term, it should be mentioned that the geocentric region bove hmF2 in which charged particles move under control of the Earth's magnetic field and essentially without collisions, is now being called the *magnetosphere* (after the suggestion of T. Gold). The chapter on solar radiation includes the latest measurements made from space vehicles and presents a complete picture of what is known of the spectrum of solar radiation incident upon the atmosphere.

The flux of "meteoroids" past the Earth can be estimated from radar and visual data, from the mass-accretion by the Earth as obtained by analyses of deep-sea sediments and dust collected in remote regions, from the zodiacal light, and by direct measurement with space vehicles. The answers obtained from the various methods are spread by a factor of 10^4 so that there is still much to be learned about this feature of the Earth's environment. This problem is presented in the fifth chapter with the same conciseness and clarity which characterizes those on the atmosphere and radiation.

The short chapter on radio noise is useful but it is very brief and has been presented mainly from the point of view of a ground-based observer.

The chapter on thermal radiation from the Earth is also short but will be interesting to nearly all readers because most will not know anything about it although the principal reference is to work published 25 years ago. A one-page description of the airglow is included in this chapter.

Geomagnetism is, of course, of great importance to satellite environment. Although the editor has chosen to place this chapter last, the reader might well be advised to read it first because the magnetic field exercises so much control over the ionized atmosphere and the charged particles which enter it from without. The inclusion of the integral invariant to describe the field, and of hydromagnetic waves to explain sudden perturbations, insures that even the experienced geomagnetician will enjoy reading the chapter. He will note the omission, though, of direct measurements by space vehicles, and of measurements made by the double refraction of radio waves and the possibility of extending these with "top-side sounders."

If you are interested in the upper atmosphere and near planetary-space, this book should be on your shelf beside Mitra and Ratcliffe.[1] Because it is so very concise, it is not the same kind of book that they are. But for that reason, it can accomplish what a 600–700 page, exhaustive treatment cannot: 1) For the expert from another field, it can give a short but advanced and correct introduction; 2) For the upper atmospherici st, it can give a new perspective. For the latter, it is an experience like flying across the United States in clear weather in a jet aircraft for the first time, after crossing it many times since childhood by automobile. One misses a lot of detail but he gains a perspective the automobile could never give him. At the same time, he hates to see a visitor, in making his first trip, do it by jet; but that's how it is these days more often than not.

M. G. Morgan
Dartmouth College
Hanover, N. H.

[1] See review, Proc. IRE, Vol. 48, p. 2045, December, 1960.

Handbook of Thermophysical Properties of Solid Materials, Vol. IV, A. Goldsmith, T. E. Waterman, and H. J. Hirschhorn, Eds.

Published (1961) by the Macmillan Company, 60 Fifth Ave., New York 11, N. Y. 798 pages+vi pages. Illus. 8¼×11¼. $90.00 set of 5 vols.

The stated purpose of this five volume work is to compile, evaluate, and consolidate all original text data on thermophysical properties of solid material published during the period 1940 to 1957 inclusive. The materials contained in these volumes are those which may find application in the design of aircraft, missiles, space vehicles, conventional or nuclear power plants, or allied equipment. A further restriction is that only materials melting above 1000°F are included: exceptions are limited to the categories of plastics or composite materials.

The handbook was prepared by the Heat Transfer Section of the Armour Research Foundation and was based on technical goals and requirements set forth by the Thermophysical Branch, Material Center, Wright Air Development Division.

The properties considered, presented as functions of temperature when applicable, are: density, melting point, latent heat of fusion, latent heat of vaporization, latent heat of sublimation, specific heat at constant pressure, thermal conductivity, thermal diffusivity, emissivity, reflectivity, linear thermal expansion, vapor pressure, and electrical resistivity.

The properties are arranged in a materials index. Volume I covers elements melting above 1000°F and includes 13 different forms of carbon data. Volume II covers alloys and includes the following subsections:

iron-base alloys, copper-base alloys, nickel-base, cobalt-base, and refractory metal-base alloys, light metal alloys including titanium alloys, and other metal alloys. Volume III covers ceramics including glasses. Volume IV, the only volume presented for review, covers cermets, intermetallics, polymeric material including plastics and composite materials. Volume V contains the complete list of references, the alphabetic author index, and the alphabetic list of materials.

The data are presented in graphical form utilizing the absolute temperature scales. A single page contains, on one side, a graph displaying the data and, on the other side, pertinent reference material. The properties, organized by materials, are presented individually under each material section. The readability of the text is, in general, quite adequate; however, in cases where a great deal of data is available concerning a certain property, the identification symbols can be confusing to recognize.

Due to the relatively new surge of interest in materials shown by electronics people, these volumes can be a valuable addition to a reference library. They appear to be most useful to two general types of readers. The first would be those interested in surveying general classes of materials for specific useful properties. The volumes contain a wealth of general knowledge which would be very useful in a survey of this kind. In this light, one feature of the compilation of data is noticeable by its absence. There are no summary graphs comparing the same property for general groups of materials. This type of summary graph would be exceptionally useful to the reader interested in comparing a particular property within a group of materials. The second type of reader for whom the book would be most useful is the preliminary design engineer. Once a material is decided upon for a specific application, many of the important design parameters can be obtained in these volumes. Due to the fact, however, that the volumes include data through 1957 only, it will be necessary for the design engineer further to augment the present information with more recent data. This is particularly true of Volume IV which covers cermets, intermetallics, polymerics, and composite materials in which interest has grown rapidly during the past four years.

There is one example of an outstanding lack of understanding concerning the applicability of some of the data. Presented in Volume IV are electrical resistivity values for some intermetallic semiconducting compounds such as indium antimonide. It is well known that the electrical resistivity depends on the carrier concentration in semiconductors; but, in the section on indium antimonide showing the electrical resistivity, no information is given which details the specific carrier concentration at which the electrical resistivity measurements were made. This type of information is extremely limited in its usefulness.

Two drawbacks to the method of presentation are noted. The first is the organization of the information by the use of a materials index which could be expansible. The idea is an excellent one; however, the binding of the material in book form makes it very inconvenient to insert additional pages into the volumes. Perhaps a presentation in binder form into which additional pages could be easily placed would be more acceptable. The second drawback is the inclusion of all references in the fifth volume. In the reviewer's case, not having been supplied with the reference volume, it was impossible to check the references cited for accuracy. This severely limits the worker who may be interested in the information contained in one volume rather than the whole set.

While it is relatively easy to find fault in an undertaking of this magnitude, these volumes are definitely worthy of inclusion in a library of reference materials and are a vast improvement over existing works of similar nature. They will be particularly useful to the technical person at the survey or preliminary design stage.

James G. Harper
Texas Instruments Inc.
Dallas, Tex.

Static Relays for Electronic Circuits, Richard F. Blake, Ed.

Published (1961) by Engineering Publishers, Div. of The AC Book Co., Inc., Elizabeth, N. J. 198 pages +viii pages. Illus. 6¼×9¼. $7.50.

The material in this book was based on the Static Relays Symposium sponsored by the Electronic Components Research Department of the U. S. Army Signal Research and Development Laboratory. There are 18 chapters prepared by various authors covering the general state of the art. The first three are devoted to a statement of the general concept, a useful review of regenerative switching in semiconductors and desirable specifications for static relays.

This book will be particularly interesting to the practicing engineer already in the field of semiconductors who has not kept abreast of developments in static switching. Many new circuits and ideas are presented leading toward a surprisingly wide range of applications where replacement of mechanical contacts with an operationally equivalent static semiconductor device is feasible.

R. P. Burr
Circuit Research Co.
Glen Cove, N. Y.

Thermoelectricity: Science and Engineering, by R. R. Heikes and R. W. Ure.

Published (1961) by Interscience Publishers, Inc., 250 Fifth Ave., New York 1, N. Y. 569 pages +6 index pages +xi pages. Illus. 6¼×9¼. $18.50.

The purpose of this book is to provide a systematic treatment of thermoelectricity, and to cover various topics in chemistry physics, and engineering. Many of these topics in themselves could constitute an entire volume and sufficient references are given to prior literature. The key results are presented with clarity. The book also contains some original contributions to the theory of thermoelectric materials and thermoelectric device design.

The first two chapters cover basic definitions and the thermodynamics of thermoelectric phenomena. Next are two chapters on transport processes in semiconductors, semimetals, narrow-band semiconductors, ionic crystals and liquids. The effects of high energy radiation and diffusion are then presented. These subjects are followed by chemical preparation and experimental measurement of material properties.

Following these fundamental topics is a chapter on the relationship between the thermoelectric figure of merit and microscopic properties of various types of materials. It is here that the question of optimum choice of material parameters, such as doping level, is considered. Next, the additional effects which occur at low temperatures, such as the phonon drag effect, are considered. Known thermoelectric materials are then surveyed and their electric, thermal, and chemical properties given in several tables and graphs.

The final four chapters of the book are concerned with devices. The basic principles of thermionic conversion are treated, followed by thermoelectric devices. The subject matter covered includes: approximate and exact calculations of device performance; staged and simple thermocouple designs; heat transfer problems and their effect on device design; technology problems, such as contacts to thermoelectric materials.

This book is a good reference work in the area of thermoelectricity; both the basic principles and advanced topics have been adequately covered. The book is recommended to all those engaged either in basic thermoelectric research or engineering. Particularly, it will serve as an excellent introduction to the field.

W. H. Clingman
Texas Instruments Inc
Dallas, Tex

Recent Books

Davis, Sidney A. and Ledgerwood, Byron, K. *Electromechanical Components for Servomechanisms.* McGraw-Hill Book Co., Inc., 330 W. 42 St., New York 36, N. Y. $11.50. A book designed to give practical aid in the selection, specification and application of rotating components. Various components are discussed and their design features analyzed.

Langmuir, D. B., Stuhlinger, E., and Sellen, J. M., Jr., Eds. *Electrostatic Propulsion,* Vol. 5 in *Progress in Astronautics and Rocketry,* M. Summerfield, Series Ed. Academic Press, Inc., 111 Fifth Ave., New York 3, N. Y. $5.75.

Martin, W. T. and Reissner, E. *Elementary Differential Equations.* Addison-Wesley Publishing Co., Inc., Reading, Mass. $6.75. A textbook of differential equations with applications to physical science and engineering, intended primarily for a one-semester course.

Parratt, Lyman G. *Probability and Experimental Errors in Science: An Elementary Survey.* John Wiley and Sons, Inc., 440 Park Ave. S., New York 16, N. Y. $7.25. A book designed to introduce the undergraduate student to the unifying concepts of probability and statistics as they apply in science.

Proceedings of the Second International Conference on Operational Research. John Wiley and Sons, Inc., 440 Park Ave. S., New York 16, N. Y. $15.00.

Scanning the Transactions

Words are essential for communication and even for thought. English-speaking peoples need not be limited in their communicating and thinking by a dearth of words; the new unabridged Webster's contains the forbidding number of 450,000. Of these, approximately 100,000 are claimed to be new additions, words that were not in previous editions of this tome. It is a certainty that the field of electronics has made a not insignificant contribution here, although it would be demanding too much to require lexicographers to be absolutely current in the dynamic electronics vocabulary. Even those most intimately concerned with it have their problems in keeping pace. More difficult than learning accepted terminology is the problem of manufacturing and sorting new terms for new ideas, devices, and requirements. Tunnel diodes are no exception. There is an impressive amount of work in progress on these devices, but discussion is hampered by a lack of standard terminology and definitions. Now a paper has been published which puts forth the important tunnel-diode parameters and includes definitions, symbology, and measurement methods. (C. D. Todd, "Tunnel-Diode Parameters," IRE TRANS. ON INSTRUMENTATION, September, 1961.)

Underwater television is not an entirely new concept. In fact, television "underwater" is occasionally brought rather dramatically to our attention with TV commercials showing that, if we should care to, we can use this pen for writing or that razor for shaving while immersed in the universal solvent. Sometimes the net result of such commercials is an urge to submerge the TV set itself. This is done, but in a much more scientific way, as described in a recent paper on the role of television in underwater weapons testing. Closed-circuit television systems have been used by the Navy to instantaneously obtain valuable data on Polaris Missile launchings and other underwater tests. (O. R. Metzler, "Television in Underwater Weapons Testing," IRE TRANS. ON MILITARY ELECTRONICS, October, 1961.)

Education will continue evolving as long as the subject matter with which it is concerned is undergoing evolution. Nowhere is this more apparent than in engineering education. The trend can be towards more specialization as the subjects become increasingly complex, or the emphasis can be on fundamentals and a broader approach. A plea not for more humanities but for different humanities has been made. The thesis is that a reappraisal of the extent, task, and presentation of the humanities is mandatory. (W. W. Harmon, "The Humanities in an Age of Science," IRE TRANS. ON EDUCATION, September, 1961.) One educator has presented some very cogent arguments for a complete renovation of the engineering curriculum and the awarding of a nonprofessional degree. He maintains that specialized professional training is the proper function of the graduate schools only. (N. Balabanian, "A Case for a Liberal Engineering Education and a Nonprofessional Degree," IRE TRANS. ON EDUCATION, September, 1961.)

Family, genus, and species were categories created by the naturalist Linnaeus to bring order to the near chaos in biological classification. Although not a problem of comparable magnitude, engineers are for convenience usually classified by means of their special interests. Without some of us realizing it, a new "breed" has quite recently joined our ranks: the bio-medical engineer. This interdisciplinary title would have sounded almost absurd not too many years ago, but now the bio-medical engineer is very much—and very appropriately—with us. His appearance has been attended by some unique and challenging problems in education (Symposium on Educational Frontiers in Bio-Medical Engineering, IRE TRANS. ON BIO-MEDICAL ELECTRONICS, October, 1961.)

Radio-electronics originally was concerned with communications and little else, but now each year reveals it ramifying into new and sometimes unexpected areas. Measurements in many fields have been revolutionized in the age of electronics. Two novel applications have recently been discussed. Measurement of the atmospheric temperature field by electromagnetic means is possible. (D. Fryberger and E. Uretz, "Some Considerations Concerning the Measurement of the Atmospheric Temperature Field by Electromagnetic Means," IRE TRANS. ON MILITARY ELECTRONICS, October, 1961.) The atmosphere comes under additional electronic surveillance, this time chemical, with a device for measuring ozone content. (C. R. McCully, *et al.*, "An Instrument for Continuous Analysis of Atmospheric Ozone," IRE TRANS. ON INSTRUMENTATION, September, 1961.)

Round Shoulders on humans are not considered as particular signs of strength. Not so for waveguides. "Round shoulders"—or more exactly, rounded corners—are known to be useful in many high-power microwave components in eliminating breakdown by reducing electric-field concentrations. Conditions in microwave high-power filters are considered in detail in a recent paper. A number of rounded-corner geometries important in microwave-filter structures were analyzed by conformal mapping. The optimum shape is not necessarily an approximation to a circular arc but rather a geometry for uniform field strength over the rounded portion. Smoothness is much more important for evacuated than for pressurized filter structures. Formulas and graphs are presented for use by the designer. (S. B. Cohn, "Rounded Corners in Microwave High-Power Filters and Other Components," IRE TRANS. ON MICROWAVE THEORY AND TECHNIQUES, September, 1961.)

Abstracts of IRE Transactions

The following issues of TRANSACTIONS have recently been published, and are now available from The Institute of Radio Engineers, Inc., 1 East 79 Street, New York 21, N. Y., at the following prices. The contents of each issue and, where available, abstracts of technical papers are given below.

Sponsoring Group	Publication	IRE Members	Libraries and Colleges	Non-Members
Aerospace and Navigational Electronics	ANE-8, No. 3	$2.25	$3.25	$4.50
Bio-Medical Electronics	BME-8, No. 4	2.25	3.25	4.50
Education	E-4, No. 3	2.25	3.25	4.50
Electron Devices	ED-8, No. 5	2.25	3.25	4.50
Engineering Management	EM-8, No. 3	2.25	3.25	4.50
Instrumentation	I-10, No. 2	2.25	3.25	4.50
Microwave Theory and Techniques	MTT-9, No. 5	2.25	3.25	4.50
Military Electronics	MIL-5, No. 4	2.25	3.25	4.50

Aerospace and Navigational Electronics

VOL. ANE-8, NO. 3, SEPTEMBER, 1961

The Evaluation of Error Standard Deviation in the Accuracy Evaluation of the Doppler Navigator—N. Marchand (p. 91)

The standard error deviation for the Doppler navigator is theoretically derived for the general case of both random and systematic errors. It is demonstrated that both the along-course error deviation and across-course error deviation, when expressed on a per unit basis, consist of two terms. One term is independent of the distance traveled and the other is dependent upon the distance traveled. There is a possibility that results of statistical analysis of experimental data, as given in the literarure, may be incomplete since the term in the error standard deviation, per unit distance traveled, which is independent of distance traveled is not included. It is demonstrated how this omission may come about by neglecting the mean errors in the subsets of the population of observations.

Identification and Evaluation of Magnetic-Field Sources of Magnetic Airborne Detector Equipped Aircraft—P. Leliak (p. 95)

A general method for identifying and evaluating magnetic sources associated with the magnetic airborne detector-equipped aircraft is described. It is derived for the compensation of magnetic noise related to the maneuvers of the aircraft. Mathematical formulas are included with a uniform engineering method, that is independent of the type of magnetic source encountered, for analyzing magnetic airborne detector records. A method for calibrating magnetic sources while in flight is also offered.

Correction to "Post-War Developments in Continuous-Wave and Frequency-Modulated Radar"—W. K. Saunders (p. 105)

A Basic Control Equation for Rendezvous Terminal Guidance—L. A. Irish (p. 106)

A basic rendezvous homing control equation, which adjusts the magnitude and direction of the acceleration of an interceptor vehicle in response to sensed interceptor-target relationships, is derived, and the selection of system gain parameters to give a desired dynamic behavior is described. Modifications to the basic control equation for the following system variations are discussed:

1) Rendezvous at a preset relative position or velocity,
2) Landing on the moon (or other extra-terrestrial body),
3) Operation with a propulsion unit having a limited range of thrust variation,
4) Operation with a fixed-thrust pulsed propulsion unit.

Abstracts (p. 114)
Book Reviews (p. 115)
PGANE News (p. 116)

Bio-Medical Electronics

VOL. BME-8, NO. 4, OCTOBER, 1961

Papers from Symposium on Educational Frontiers in Bio-Medical Engineering, University of Vermont; May 5–6, 1960

New Frontiers in Bio-Medical Engineering Education—G. C. Riggle (p. 208)

Biology in Bio-Medical Engineering—R. W. Stacy (p. 209)

Physiology in Bio-Medical Engineering—F. J. Sichel (p. 211)

The Role of the Engineer in Bio-Medical Science—S. A. Talbot (p. 212)

Specialized Courses Required in Bio-Medical Engineering Science—S. A. Talbot (p. 216)

Bio-Medical Engineering Program at Johns Hopkins, Pennsylvania, Rochester and Yale—H. P. Schwan (p. 219)

The Bio-Medical Engineer—J. W. Dow (p. 223)

Informal Training Program in Bio-Medical Engineering at Brooklyn Polytechnic Institute and the Rockefeller Institute—R. L. Schoenfeld (p. 225)

Bio-Medical Engineering Program at Drexel Institute of Technology—D. H. Le Croissette (p. 227)

Medical Electronics at the University of Vermont—H. M. Smith, Jr. (p. 228)

Medically- and Engineering-Oriented Facilities, Instruction and Research in Bio-Medical Electronics—V. W. Bolie, M. J. Swenson, W. B. Boast, and R. Getty (p. 229)

Bio-Medical Electronics—Past and Present—H. P. Schwan (p. 234)

A brief review of the development of the field of bio-medical electronics and its present status is presented. Topics include development, description of the field, industry education and future outlook.

Influence of Light Atmospheric Ions on Human Visual Reaction Time—M. Knoll, J. Rheinstein, G. F. Leonard, and P. F. Highberg (p. 239)

An automatic electronic visual-reaction-time meter has been developed which includes a random-pulse generator controlled by nuclear radiation for starting the subject's light pulse. With this instrument (using radioactive ion generators) several hundred subjects have been investigated in over 12,900 tests. An influence of light atmospheric ions on the human reaction time has been found for ion currents between 10^6 and 10^9 inhaled ions per second or ion densities of about 10^3 to 10^6 ions/cm^3. Inhaling positive or negative ions may increase or decrease the reaction time of different people or even of the same person after several hours. In this respect the influence of ions resembles the effect of many drugs on the human system. The effect disappears when the subject is breathing through the nose instead of the mouth.

Electrical Analog Simulation of Temperature Regulation in Man—R. J. Crosbie, J. D. Hardy, and E. Fessenden (p. 245)

Using the basic equations for heat balance which have been developed to take into account heat losses by radiation, convection and evaporation, an electrical analog has been constructed to simulate the physiological responses to heat and cold in the nude man. As has been previously shown, physiologic temperature regulation involves three of the basic types of control modes, namely, proportional control, rate control, and some of the characteristics of on-off control. The rate and proportionality constants have been determined experimentally on the assumption that the regulated temperature is the average body temperature. Time constants for the various thermal changes can be determined from the thermal constants of tissue and the response times of the physiological variables of sweating, vasomotor activity and change in metabolic rate. The simulator predicts steady-state situations of rectal temperature, skin temperature, metabolic rate, vasomotor state and evaporative heat loss under both resting conditions and exercise. Dynamic responses to sudden shifts in environmental temperature, air velocity, relative humidity and metabolic rate can be simulated to a considerable extent using equations based on the controls outlined above.

Transistorized Pacemaker for Remote Stimulation of the Heart by Radio-Frequency Transmission—L. Eisenberg, A. Mauro, and W. W. L. Glenn (p. 253)

Diverse techniques have been developed for controlling the cardiac rate by external means when normal physiological processes fail to maintain a stable rate. These techniques are presented in a brief summary.

The factors underlying the choice of the radio frequency transmission technique are presented and evaluated, taking into account

control of the stimulus, avoidance of infection, and minimizing the number of electrical components within the body. A set of design specifications is then evolved based upon the physiological needs of the patient, utilizing the philosophy of the RF transmission approach. The design of two transistorized, battery-operated pacemakers is then presented in detail with a description of the constructed units and an evaluation of performance. These units have now been used successfully on five patients.

A Portable Miniature Transistorized Radio-Frequency Coupled Cardiac Pacemaker—D. M. Hickman, L. A. Geddes, H. E. Hoff, M. Hinds, A. G. Moore, C. K. Francis, and T. Engen (p. 258)

A miniature, transistorized radio-frequency-coupled cardiac pacemaker was developed to eliminate wires penetrating the skin when electrodes are placed on the heart to drive it. The design also eliminates the need for totally implanting a pacemaker with its batteries.

The stimulating impulse is transmitted via amplitude modulation to a tuned circuit and detector assembly implanted below the skin. The output of the detector is connected to electrodes directly on the heart, making external control of the heart rate possible.

In operation, the pacemaker transmitter is placed on the surface of the body above the receiver implant. The size of the unit is $4 \times 1\frac{3}{4} \times 1\frac{1}{2}$ inches. It weighs three ounces.

Correction to "The Center for Vital Studies—A New Laboratory for the Study of Bodily Functions in Man"—W. A. Spencer, L. A. Geddes, and H. E. Hoff (p. 262)

Letters to the Editor (p. 263)

Abstracts of Current Bio-Medical Electronic Research Projects (p. 265)

Notices (p. 267)

PGBME Affiliates (p. 268)

Proceedings of the Third International Conference on Medical Electronics (p. 296)

Education

Vol. E-4, No. 3, September, 1961

Acknowledgment—W. R. LePage (p. 83)

Editorial—H. E. Koenig (p. 84)

A Case for a Liberal Engineering Education and a Nonprofessional Degree—N. Balabanian (p. 86)

The traditional four-year engineering program gives neither an adequate professional training nor a liberal education. It is proposed that a four-year program of "liberal engineering" be instituted which synthesizes traditionally compartmentalized disciplines and concentrates on the intellectual components of the profession. Specialized professional training should be the proper function of the graduate school.

The Technology of Information Systems—Another Challenge for Engineering Education—L. E. Saline (p. 91)

The proper functioning of the world in which we live is becoming more and more dependent on information and how we use it. With methodologies and machines that are becoming available to information systems technology, we are, indeed, entering the Age of Information—an age of promise in business, in government, and in the military that can have as profound an effect on the world as the harnessing of the atom, the development of electric power, or the Industrial Revolution of the Nineteenth Century. The purpose of this paper is to delineate the broad technology of information systems in order to provide a basis for estimating the impact of this technology on future engineering education. Suggestions for modifying undergraduate engineering curriculums are made in order that future engineering graduates will be prepared to contribute to the continuing development of the technology and to utilize the technology in performing other engineering work. This paper discusses such topics as: What is an Information System?; Functions of a Generic Information System; Men in Information Systems; Machines in Information Systems; Methods in Information Systems; How Information Systems Are Created; Major Problems Facing Information Systems Technology; and The Challenge for Engineering Education.

Dis-service Courses—T. L. Martin, Jr. (p. 98)

For many years the traditional engineering physics course was the pivotal subject in the engineering curriculum. It provided an adequate basis in macrophysics to support traditional engineering. The course is still offered, virtually unchanged for the past forty years except in minor details; the evolution of microphysics, structural chemistry, and physical metallurgy has made little impact upon this course. Engineering physics is now a sacred cow—a dis-service course.

This course has been cancelled at the University of Arizona and classical macrophysics is taught by the engineering departments in the various and usual subdivisions of mechanics, thermodynamics, electric and magnetic fields, and electric circuits. A new course, at the junior level, has been introduced by the Physics Department to cover Microphysics. It is offered under the title of "Structure of Matter" and covers electrons, atoms, chemical bonds, crystals, the energy band theory of crystals, and other topics from wave, statistical, and quantum mechanics. The course has been offered for three years. While it is under constant revision there is little doubt now that this represents a positive solution to a part of the problem posed to engineering educators by recent advances in contemporary science.

System Theory in a Unified Curriculum—H. K. Kesavan and B. R. Myers (p. 102)

The incessant search for unifying concepts in engineering education has, in recent times, stepped up its pace to match the tempo of our scientific and technological progress. Although a single unified curriculum for all engineering problems would indeed be a utopia, there is hope, nevertheless, that certain apparently diverse areas of engineering can be regrouped with emphasis on the basic disciplines underlying them. System theory, which is briefly exposed here, is one such fundamental discipline with its mainsprings in the mathematical model of linear-graph theory. The chief assertion of this paper is that system theory could very well serve as a basis for unifying the areas of 1) circuit theory, 2) circuit aspects of electronics, 3) rotating machinery, 4) elementary statics and dynamics, and 5) system analysis. The ideas presented here are sufficiently supported by the authors' classroom experiences. In the light of the curriculum proposed, certain of the inevitable implications for Canadian electrical engineering are discussed.

On Some Mathematical Aspects of Magnetohydro- and Plasma-Dynamics—M. Z. V. Krzywoblock (p. 111)

The author presents a review of some mathematical aspects of magnetohydrodynamics and plasma-dynamics, and the fields of mathematics required and used in those domains are briefly discussed. The last section is devoted to the discussion of adjusting the mathematical program of a university, from the point of view of engineering, physics and mathematics, so that a greater number of students in those disciplines will be prepared for graduate courses in magnetohydrodynamics and plasma-dynamics.

The Humanities in an Age of Science—W. W. Harman (p. 118)

Many persons today question the meaningfulness of the traditional formulations of some of the basic questions which have been asked in the humanities, and also the validity of the introspective means by which answers have been sought. These challengers often appear to have behind them the great weight of the scientific progress of recent centuries. The basic issue on which the behavioral scientist and the scientific humanist appear to differ so from the poet, the artist, or the religious philosopher has to do with the physical and the spiritual aspects of reality. Predominately, the scientist tends to operate on the implicit assumption that only the physical or sense-perceived world has reality; the poet and the mystic live in both worlds. The behavioral scientist tends to see values as culturally generated and acquired, the poet, as inherent in the structure of things.

Questions about the nature of reality are not to be decided by disputation among ourselves, but by conducting such experiments as will enable us to discern what that nature really is. The nature of such experiments and suggestions for the possible resolution of this basic issue form the subject matter of this paper.

Correction to "Today's Dilemma in Engineering Education"—G. S. Brown (p. 126)

Correspondence (p. 127)

Contributors (p. 128)

Electron Devices

Vol. ED-8, No. 3, September, 1961

Editorial—E. L. Steele (p. 345)

New Editorial Board (p. 346)

An Integrated Semiconductor Shift Register—J. T. Wallmark and S. M. Marcus (p. 350)

Transition Region Properties of Reverse-Biased Diffused *p-n* Junctions—J. Cohen (p. 362)

Poisson's equation is solved for two common types of diffused p-n junctions in a manner similar to that of previous authors. By a suitable transformation, the field in the junction and capacitance-voltage relation for all junctions are shown to be presentable as a single family of curves with no approximation other than the assumption of negligible drift field. The abrupt and graded regions are discussed in detail. The zero-bias potential and capacitance are also discussed.

Alloy Diffused Variable Capacitance Diode with Large Figure-of-Merit—A. Shimizu and J. Nishizawa (p. 370)

The product of the cut-off frequency and the capacitance-voltage sensitivity is proposed as a figure-of-merit of the variable capacitance diode.

It is expected from the theoretical results that the high-voltage sensitivity, $(\partial C/\partial V)/C$ of the capacitance is obtained by the "hyper-abrupt" junction in which the impurity concentration decreases with the distance from the p-n boundary. Assuming the exponential decrease of the impurity concentration, the theoretical expression is derived for the capacitance-voltage characteristic of the "hyper-abrupt" junction diode, and is compared with the experiment.

"Hyper-abrupt" structure is easily obtained by the alloy-diffusion technique. The experimental capacitance-voltage characteristics of the germanium alloy-diffused diode agree fairly well with the theoretical results. Diodes changing the capacitance in proportion to the -3 power of the applied voltage have been made, with the tuning ratio to about 100. To date, a diode with the maximum cut-off frequency of 30 kMc and with the figure-of-merit

$F\gamma$ of 5.5 kMc/v, has been made. Further increase of these quantities, however, will be obtained by the reduction of the thickness of the base layer, which is about 15 microns in the above diode.

A Treatment of Diffusion Errors Affecting Junction Depth—J. E. Reynolds (p. 377)

An error treatment of the diffusion variables of time t, temperature T, and starting resistivity ρ, has been made in regard to their effects upon junction depth. An analytical equation has been derived for engineering usage in determining the per cent error in junction depth x:

$$\text{Per cent error in junction depth} = 100\sqrt{\frac{\Delta t^2}{2t} + \frac{Q\Delta T^2}{2RT^2} + \frac{\sqrt{\pi Dt}}{\mu\pi\sigma^2 N x}\Delta\rho \exp\,(x^2/4Dt)^2}$$

A sample calculation using the above equation is presented along with a method of estimating errors in junction depth due to heating and cooling in the diffusion cycle.

Diode Oscillation in High-Voltage Klystrons—K. Tomiyasu and M. P. Forrer (p. 381)

Diode oscillations at frequencies between 1350 and 3700 Mc sometimes occurred in a particular high-voltage pulsed klystron. These frequencies agree closely with those calculated for an inverted spherical diode. The oscillations are often delayed a few microseconds after the electron beam is turned on. Experimental techniques revealed that two of the modes, TE_{41} and TE_{61}, with Q's of about 1000 had their highest electric fields in a region of the electron gun remote from the beam.

Proposed Method for Controlling and Minimizing Reflections from a Surface—R. H. Mattson (p. 386)

This paper proposes a method whereby the reflection of an electromagnetic wave from a surface can be controlled. The idea is to use a p-n junction as the controlling device. The device is made in such a way that the junction is parallel to the surface upon which the electromagnetic radiation is impinging. If the p region is very narrow the wave will penetrate through it into the depletion region. If the n region is hi conductivity, the wave is reflected from it. Then if the depletion layer width is right for the frequency considered, the reflected wave will interact with the impinging wave to give the desired effect. By changing the bias applied to the junction a tuning effect can be obtained.

Detailed analysis of the proposed device is covered in the paper. There are some practical limitations to creating the device described, but the idea and the method of analysis could be useful to individuals interested in creating microwave tuning and control components.

Ceramic Metalizing Tape for Reliable Metal-Ceramic Seals—H. D. Doolittle, K. Ettre, R. F. Spurck, and P. F. Varadi (p. 390)

A ceramic-metalizing method was developed which increases the reliability of hard-soldered metal-ceramic seals and makes production automation possible. The new technique utilizes a "metalizing tape" consisting of a self-supporting plastic tape which contains the metalizing powders and a suitable binder (methacrylic-type). This tape can be manufactured with extremely uniform thickness, density and surface smoothness, all of which qualities can be controlled on the prefabricated tape prior to its usage. The application of the prefabricated metalizing tape to the ceramic surface can be accomplished in a very simple way: by using a suitable solvent to form a bond between the metalizing tape and the ceramic, or by thermal sealing. The materials and the methods used for the preparation of the metalizing tape are described, as well as the methods of application.

The resulting extremely uniform metal coating on the ceramic makes it possible to investigate the effect of metalizing thickness and of different materials on the bond strength and on the vacuum qualities of metal-ceramic butt seals.

Tunnel-Diode Converter Analysis—C. S. Kim (p. 394)

An analysis of tunnel-diode converters is presented for two different conditions of operation. In the first, the converter is self-oscillating; in the second, the local oscillator (LO) voltage is provided from an external source. Two classes of self-oscillating converters are presented. The first operates on the fundamental of the oscillation frequency and the other operates on the second harmonic.

Assuming the dynamic conductance of a tunnel diode changes only as a function of the local oscillator voltage, and expressing this conductance in a Fourier series, a 3×3 conductance matrix is obtained. Utilizing this matrix, expressions for gain, bandwidth, and noise figure are obtained. The analysis includes the image frequency termination. In the expressions for noise figure, the cross-correlation terms, produced by the amplitude change of the dc equivalent shot-noise current due to the LO voltage, are also included.

Correction to "Bridge Measurement of Tunnel-Diode Parameter"—W. H. Card (p. 405)

The Videograph Tube—A New Component for High-Speed Printing—R. W. Crews and P. Rice (p. 406)

A cathode-ray tube having a faceplate penetrated by an array of many fine wires, has been developed for high-speed printing applications. Charge patterns are deposited on moving paper in response to a modulated electron beam which scans the inner ends of the wires in the CRT. The pattern on the paper is dusted with an electroscopic powder to make it visible. Copy having a resolution of 10^4 picture elements/inch^2 can be produced at a rate of 2 feet^2/second.

The tube is being used in high-speed facsimile equipment and in a computer output printer which prints magazine address labels at a speed of 130,000 labels per hour from digital information stored on tape. Television pictures have been reproduced field-by-field at standard rates. The tube has wide application in systems where high-speed, remote print-out or local reproduction of copy is required. The cost of the recording paper is about one-tenth that of light-sensitive materials.

Influence of Velocity Spread on Gain and Efficiency of Klystrons—H. G. Kosmahl (p. 414)

This paper presents the calculation of the effect of velocity spread in electron streams on the gain and efficiency in klystrons. Using the density-function method and assuming a half-Maxwellian velocity distribution, a small-signal theory of a klystron tube was developed. The form of the solution is a power series whose coefficients contain even powers of $\omega q/\omega$. The effect of losses in the cavity has also been included. The results are presented as plots of the ratios of the ac component of the bunched current with velocity spread vs a dimensionless parameter that is a measure of the velocity spread. The plots contain $\omega q/\omega$, the lengths of the drift tube and of the gaps as important design parameters.

Solid-State Device Research Conference (p. 420)

Contributors (p. 431)

Engineering Management

Vol. EM-8, No. 3, September, 1961

About This Issue—The Editor (p. 119)

Decision Making, Growth, and Failure—S. B. Alpert and H. Weitz (p. 120)

A case study is presented of the changes in the ratio of "administrative" to "productive" personnel in the aircraft engine division of a large industrial firm. The ratio is traced over an eight year period through growth and decline stages. Some contributing factors and consequences of the A/P index are examined.

Designing the Corporate Structure to Combine Small-Company Vitality with Large-Company Strength—A. W. Tyler and A. D. Ehrenfried (p. 125)

The early leaders in corporate organization are found to be the giants of industry today. Following the move of the past decade to corporate decentralization is a new trend toward the recentralizing of management planning and specialized service. The result is a new form of corporate structure toward which both large corporations and groups of small companies can evolve. This structure appears to combine the better features of both the large and the small organization. It is made necessary by the complexity of present-day business management, and is made possible by the new technologies of electronic data processing, business communications, and high-speed transportation.

The Institutional Location of the Scientist and His Scientific Values—R. G. Krohn (p. 133)

Several writers on the history of science have argued that changes in the institutional location of science will be accompanied by several major changes in scientific attitudes and values. A sample of approximately 30 per cent of the working scientists in several disciplines was interviewed in the Minneapolis-St. Paul area. Those interviewed worked in government, industrial, and university laboratories. A number of indicators of scientific attitudes and values were examined.

Special Section on Services for R, D, and E

Development of a Technical Services Department for IBM—F. H. Welsh, Jr. (p. 139)

To develop the highly complex products required of industry today, it is necessary to provide the research and engineering personnel developing these products with an array of highly specialized supporting services. Since these supporting skills are not required by any one engineering group 100 per cent of the time, economics dictates that these services be centralized. Thus, a Technical Services Department is born. The supporting skills provided by such an organization may vary, for example, from the analytical ability of highly-specialized Ph.D.s, to the manipulative ability of highly trained tool and die makers.

IBM has a particular need for such specialized services because of the number of engineering groups which it has working simultaneously on different projects. In this article, it is not possible to cover the development of Technical Services in all the IBM Laboratories. Therefore, the discussion is limited to the IBM General Products Division Development Laboratory at Endicott, N. Y. This is appropriate, as Endicott is typical of other IBM Commercial Laboratories.

A Systematic Procedure for Preparing Specifications on Electronic Instrumentation and Control Systems—H. Olken (p. 143)

This is a report on the development of a systematic procedure for preparing specifications for electronic instrumentation or control systems. This procedure aids in the preparation

of specifications which: 1) make it possible to find any particular specification requirement quickly, and 2) insure that no important requirement has been omitted. Details of this procedure and a discussion of advantages gained through its use are presented. Also discussed is a technique for specification review and revision that helps to improve the proficiency of engineers at specification writing.

The Industrial Engineer's Role in New Product Development—D. W. Karger (p. 155)

Two examples are presented of the kind of contribution industrial or production or methods engineers can make to new product development. The first is a 1.2 volt mercuric oxide battery. The second is a tantalum capacitor. Contributions to analyses of costs and tolerances are cited.

Technical and Management Notes

An Approach to Probabilistic Forecasting of Engineering Manpower Requirements—L. B. Wadel and C. M. Bush (p. 158)

A statistical technique is presented for estimating probable future manpower requirements in the face of uncertainty about the success of outstanding bids.

A Visual Method of Program Balance and Evaluation—L. B. C. Fong (p. 160)

A visual method is presented for providing an overview of the entire program of the Diamond Ordnance Fuze Laboratories. The display indicates relative emphasis of effort at the various levels in the laboratories and permits comparison between fields and specialities.

About the Authors (p. 164)

Affiliated Societies—IRE Professional Group on Engineering Management (p. 166)

Information for Authors (Inside Back Cover)

Instrumentation

Vol. I-10, No. 2, September, 1961

Abstracts (p. 56)

Tunnel Diode Parameters—C. D. Todd (p. 57)

Engineers and technicians concerned with the use of, or the testing of tunnel diodes need to understand the symbology and basic definitions of the various parameters involved. In many cases, a knowledge of simplified measuring techniques is also necessary. It is the purpose of this paper to fulfill these basic needs.

Separation of Magnetic Losses in UHF Ferrites—A. Brastins and E. M. Williams (p. 63)

The Asymmetrical Bridge—A. B. Kaufman (p. 68)

A Display Simulator for Computer-Aided Systems—R. H. Prager (p. 71)

A Stable, Scannable, Magnet Current Regulator—N. W. Bell and R. H. Small (p. 75)

Analysis of a Time-Varying Pulse System with Random Inputs—T. S. George (p. 78)

A Nanosecond Time Base for Traveling-Wave Deflection Cathode-Ray Tubes—G. J. Frye, J. D. Bruce, and N. S. Nahman (p. 85)

An Instrument for Continuous Analysis of Atmospheric Ozone—C. R. McCully, J. F. Roesler, E. S. Gordon, J. N. Van Scoyoc, and R. A. Carrigan (p. 89)

Contributors (p. 94)

Microwave Theory and Techniques

Vol. MTT-9, No. 5, September, 1961

Microwaves—A Review of Progress in Great Britain During 1960—A. E. Karbowiak (p. 374)

The fields covered by the review are: Electromagnetic theory as applicable to wave propagation, theory of waveguides and components, microwaves in fundamental measurements (such as time and atomic constants), designs of components, measurements, solid-state devices and a summary of utilization. Future trends are also indicated. The review (with some exceptions) does not cover the following fields: Antennas, propagation and microwave tubes. In reviewing technical publications, preference is given to such aspects of work which are novel, fundamental or are of controversial nature or are likely to influence future trends; where appropriate, criticism of the work is given.

A New Type of Circular Polarizer Using Crossed Dipoles—M. F. Bolster (p. 385)

A method of obtaining a circularly-polarized wave by use of two orthogonal dipoles driven in parallel by a common transmission line is shown. The lengths of the dipoles are so chosen that the real part of their input admittances are equal and the angle of the input admittances differ by 90°. When these two conditions are met the resulting radiated wave in a normal direction will be circularly polarized.

The method is applicable both to a circularly-polarized radiating antenna and to the problem of producing a circularly-polarized wave of the TE_{11} mode in a round waveguide. For the first case, an analysis and a method of design are shown, and for the second case an experimentally developed example is given. The second case employs monopoles rather than dipoles for convenience in energizing from a coaxial line.

Rounded Corners in Microwave High-Power Filters and Other Components—S. B. Cohn (p. 389)

Microwave high-power filters must be operated with internal air pressures of at least one atmosphere, or with a good vacuum. Pressures between these extremes result in reduced power-handling ability. The breakdown processes for both high air pressure and vacuum are discussed, and it is made clear that any sharp corner on which the electric field would concentrate must be rounded if high-power operation is to be achieved. For good results in vacuum operation, the surfaces must be especially smooth and free of contamination, while in high-pressure operation, minor irregularities are less important.

Various high-power filter configurations of importance are described, and the structural corners at which electric-field concentrations occur are pointed out. A number of simplified geometries are then shown that can represent the essential portions of the practical structures with sufficient accuracy for ordinary purposes. Formulas and graphs for these simplified geometries are presented that give the ratio of the maximum electric field strength on the boundary to a uniform reference field strength at a point sufficiently removed from the corner. In some cases, the boundary curve is an approximation to a circular arc, while in other cases a boundary shape is derived such that the electric field strength along the curve is constant. These constant-field-strength boundaries are optimum shapes from the standpoint of power-handling ability.

A Periodic Structure of Cylindrical Posts in a Rectangular Waveguide—E. E. Altshuler (p. 398)

The propagation characteristics of a rectangular waveguide loaded with uniformly spaced cylindrical posts (periodic structure) are investigated at a frequency of 2840 Mc. A qualitative discussion on the expected behavior of the effective guide wavelength of this type of periodic structure is presented, and it is shown that the presence of the posts reduces the guide wavelength of the waveguide. The guide wavelength is then measured as a function of post diameter, post depth, and post spacing; and curves enabling one to design periodic structures which have guide wavelengths in the region of the free space wavelength are presented.

Modes in Rectangular Guides Loaded with a Transversely Magnetized Slab of Ferrite Away from the Side Walls—G. Barzilai and G. Gerosa (p. 403)

The characteristic equation describing the general modal spectrum for a rectangular guide partially filled with a slab of ferrite transversely magnetized and situated away from the side walls is derived. This equation is numerically solved for particular cases and for modes of zero and first order with respect to the dependence along the direction of the dc magnetic field. Some experiments to verify the theoretical results are presented and show good agreement with the theory.

Higher-Order Evaluation of Electromaggetic Diffraction by Circular Disks—W. H. Eggimann (p. 408)

The problem of the diffraction of an arbitrary electromagnetic field by a circular perfectly-conducting disk has been solved by using a series representation in powers of $k=2\pi/\lambda$ and the rectangular disk coordinates. The surface current density is given in terms of the field and its derivatives at the center of the disk. General expressions for the electric- and magnetic-dipole moments, the far-field and the scattering coefficient for the case of a plane wave at arbitrary incidence are presented. The calculations agree with results published by other authors. A bibliography of the most recent publications on this problem is included.

Low-Noise Properties of Microwave Backward Diodes—S. T. Eng (p. 419)

This paper describes, for what is believed to be the first time, the low-noise properties of backward tunnel diodes in microwave applications. The physics of the diodes is reviewed together with some of the characteristics and equivalent circuit parameters. The diodes are then considered as mixer diodes with IF in the audio range and also the standard 30-Mc IF. Another promising application considered is the use of the backward diodes in low-level detection.

The results show that the noise figure at 13.5 kMc with a 1-kc IF is around 15 db better than any commercially available mixer diodes. Using 30-Mc IF, the noise figure of backward diode mixers is without special optimum design, comparable to the best mixer diodes on the market. Of great importance, especially in microminiaturization, is the fact that these diodes may be used with a very low local oscillator power (50 μw or less). The high nonlinearity of the I-V characteristic at the origin and the low 1/f noise properties of these diodes are also of benefit in crystal video receivers and other low-level detector applications.

Design Theory of Up-Converters for Use as Electronically-Tunable Filters—G. L. Matthaei (p. 425)

The up-converters discussed use a single diode, a wide-band impedance matching filter at their signal input, a moderately wide-band impedance matching filter at their pump input, and a narrow-band filter at their sideband output. With a narrow-band filter at the sideband output, the frequency which will be accepted by the amplifier can be controlled by varying the pump frequency. Analysis of the impedance matching problem involved shows that tuning ranges of the order of a half-octave to an octave are possible. Theory is presented for both the lower-sideband and upper-sideband types of tunable up-converters and for the design of the required impedance-matching networks. It is shown that, because of the pump input bandwidth required, it will generally be necessary to accept some mismatch at the pump input. But, by use of a properly designed impedance-matching filter, the reflection loss can be kept nearly constant across the pump band, and the incident pump power required is not unreasonable. It is seen that properly designed devices

of this type using voltage-tunable pump oscillators should have wide tuning range, fast tuning capability, a useful amount of gain, no image response, and a low noise figure.

Anisotropic Properties of Strip-Type Artificial Dielectric—N. J. Kolettis and R. E. Collin (p. 436)

Theoretical formulas for the propagation phase constant of a two-dimensional strip medium are presented for general directions of propagation. In addition a number of experimental results are included that verify the validity of the theory. Some of the difficulties encountered in defining equivalent dielectric constants for this medium are also pointed out.

Optimization of Waveguide Tapers Capable of Multimode Propagation C. C. H. Tang (p. 442)

By converting Maxwell's equations, the general case of mode conversion in tapered waveguides is treated by matrix formulation in terms of an infinite set of coupled differential equations with nonuniform coupling coefficients and varying phase constants. An "orthogonalization" or "diagonalization" process is introduced through a nonlinear matrix transformation which is a function of taper length. The general matrix solution of the problem is obtained through a perturbation method in the form of an integral equation of the Volterra type, and the integral equation is solved by an iteration method. In view of the difficulties in finding eigenvalues, the problem is then reduced to the two-mode case, and the mode conversion is obtained in an explicit form revealing certain information which characterizes the choice of "mode-conversion distribution function." Optimization is first obtained through proper choice of the mode-conversion distribution function. In an attempt to approximate a Tchebycheff mode-conversion response, further optimization is realized by creating "new zeros" and thereby changing the density of the distribution of zeros in the vicinity of the origin of the mode-conversion curve and the nature of the optimization procedure essentially becomes that of synthesis. Through using the optimized distribution function, a total reduction of about 50 per cent in taper length is realized (when compared with the cosine-squared distribution) for the case of 50-db prescribed-mode discrimination in a taper connecting a $\frac{7}{8}$-in ID waveguide to a 2-in ID waveguide operating in the circular electric mode up to 75 kmc.

Correspondence (p. 452)

Contributors (p. 455)

Military Electronics

Vol. MIL-5, No. 4, October, 1961

A. G. Waggoner (p. 264)

Guest Editorial—A. G. Waggoner (p. 265)

Microwave Telemetry at U. S. Missile Ranges—G. F. Bigelow, T. B. Jackson, and R. T. Merriam (p. 266)

An orderly plan has been prepared covering the implementation of UHF radio telemetry on the country's missile ranges. Requirements have been drafted for UHF systems to be developed by 1970. Programs have been launched to transfer the requirements into equipment. Preliminary standards have been established.

Today, UHF telemetry links are utilized for a limited number of projects. Currently a high-performance UHF link is expensive, large in size, and complex. One must use a transmitter that may weigh 12 to 50 pounds, that has a volume of 250 to 1000 cu in, and that has an over-all power efficiency of 2 per cent for an 8 to 10 watt output. Its cost may be 10 times that of a 5-watt VHF transmitter. Automatic tracking systems are required but are not generally available. Special preamplifier-converters are also necessary. Because of these factors, UHF telemetry is used, at present, only by a few missile projects.

Obviously, we must continue to advance the state-of-the-art until a spectrum of microwave devices is available to fill the needs of the majority of telemetry users. Economy, as well as technical capability and flexibility, will be the mark of these developments.

Information Bandwidth Problems in Instrumentation of Missile Flight Tests W. E. Mimmack (p. 272)

The operation of missile flight-test instrumentation systems at minimum bandwidth is an important economic consideration. Design of instrumentation systems may become difficult or impossible unless intelligently chosen bandwidth parameters are specified. Since nearly all missile flight-test instrumentation systems operate as sampled data devices, the bandwidth parameter shows up as a sampling rate requirement.

It can be shown, under fairly general conditions involving no highly restrictive assumptions, that the rate of information acquisition of a sampled-data instrumentation system, when considered as a function of sampling interval, has a maximum. This can be readily appreciated intuitively. For a position-measurement system, for instance, if the sampling interval is made very short, the amount of information gained with each subsequent sample is very small because of the large amount of prior information about the position of the object being measured. No information would be gained if a sample were taken an infinitesimally small time after an initial measurement. Also, a very long time interval between samples would permit considerable growth of ignorance about the object's position, but the logarithmic information-gain function would grow slowly compared with t^{-1}; so the information rate for long sampling intervals would also be a small number. Somewhere between these two cases lies at least one maximum in information rate.

The selection of a sampling rate corresponding to the maximum information rate is recommended as a good choice for many types of missile test instrumentation systems. General sampling-rate formulas are developed, as well as specific formulas for certain important types of instrumentation problems.

Some Considerations Concerning the Measurement of the Atmospheric Temperature Field by Electromagnetic Means—D. Fryberger and E. F. Uretz (p. 279)

A system for determining atmospheric temperature structure by using an electromagnetic radiometer probe is described. The relationship between the electromagnetic sensor reading and atmospheric conditions is developed for both the microwave and infrared sensor utilizing a unified approach for the two cases. It is shown that, with the assumption of horizontal homogeneity, several alternate procedures for inversion of sensor readings to yield the spacial-temperature field are possible. One of these procedures which was used to invert theoretical radiometer readings from an assumed atmospheric structure is described in detail. The results of the inversion which was accomplished with the aid of a UNIVAC 1105 computer are included.

Improvement in Tracking Accuracy of Pulse Radar by Coherent Techniques—S. Kazel and J. N. Faraone (p. 286)

The theory of optimum linear prediction and filtering is applied to determine the optimum system response of pulse (noncoherent) and pulse-Doppler (coherent) radars for target motions consisting of 1) random steps of velocity, and 2) random steps of acceleration. The rms error in velocity data is calculated for each system, and the improvement factor of pulse-Doppler over pulse radar is obtained. The improvement factor is considerably greater in the case of random steps of acceleration, demonstrating that the relative accuracy of the two systems depends on the nature of the target motion, as well as on the radar parameters. Although the errors in both systems are reduced somewhat by allowing large delays in output data, the relative accuracy is found to be unchanged.

Integrated Missile Flight Safety System at Vandenberg/Point Arguello—K. E. Bailey and J. K. Moller (p. 294)

The background for the present safety system is outlined in a review of the original Air Force plans and installations and subsequent Navy-Air Force agreements for the coordinated use of the Pacific Missile Range, considering the expanded scope of operations in the area.

A description is given of the ground stations in the unified acquisition and tracking system for range safety as well as the auxiliary equipment for missile monitoring during early parts of its flight trajectory. A review is made of the associated data transmission and processing equipment including operational direct voice circuits. The corresponding safety equipment in different types of missiles is discussed in connection with both command, tracking, and telemetry functions. The implementation of the flight termination command requirements is outlined in the main transmitting station and missile checkout apparatus. The support areas of status reporting, telemetry, timing, and communications are discussed in detail. Finally, new requirements for precise downrange impact prediction and vehicle thrust termination are described.

The Digital Data Processor for the Skytop Static Test Facility—K. M. Roehr and R. D. Coleman (p. 300)

The Digital Data Processor implements a new data-acquisition concept which permits self-adaptive, accurate, real-time digitizing and editing of a large number of high-frequency data channels. The system was designed to meet the constantly changing requirements of a high-energy propulsion engine research and development program.

The centrally located processor basically samples 127 channels of analog information from any one of several 1-million-pound static test stands, and produces a digital tape. Before a new test the sampling scheme of the data channels is quickly set for any desired selection sequence that will best fit the new test situation. During a test the data processor can monitor preselected channels. Based on their performance, sampling priority can be shifted from one channel group to another, thus automatically optimizing the data-acquisition process. Immediate digitizing of the multiplexed analog data preserves its original accuracy. Record lengths on the output tape are programmable, and the tape format is compatible with the IBM 7090 computer.

Determination of Satellite Trajectories from Track-While-Scan Radar Measurements—R. B. Barrar and R. Deutsch (p. 306)

Classical methods for determining satellite orbits were limited to the use of angle information and only rough estimates of distance. With radar, it is possible to obtain good range information, but poor angular accuracy. Three approximate schemes are described which are ideally suited to track-while-scan radar observations. The accuracy obtained with these techniques has been demonstrated by the numerical evaluation of some typical cases.

Infrared Automatic Acquisition and Tracking System—R. C. Barbera (p. 312)

A technique for accumulating airborne visible and infrared spectroradiometric data from missile plumes and re-entry objects establishes the requirements for a precision tracking front surface mirror. The processing of target radiation, reflected by the tracking mirror into an infrared tracker telescope, to derive target coordinate information, is described. The deri-

vation of transformed target error signals to command the motion of the hydraulically driven tracking mirror is outlined. A description of the servo-electronics system, with selected circuitry, is given. The dynamic characteristics of the system, as determined from preliminary field tests, indicate that the system has a tracking rate capability of 10°/sec with an accuracy better than 60 seconds of arc. The detection sensitivity of the infrared tracker telescope is 1.6×10^{-10} w/cm² in the 2- to 6-μ region, and is sufficient to provide 10-mile tracking ranges against a jet target in a sunlit cumulus cloud background.

In a typical installation, aiming of the tracking mirror is provided by a 7×35, 10° field of view sighting telescope which is automatically slaved by the tracking mirror when acquisition and target tracking occurs, thereby providing continuous observation of the target. As an alternative to visual aiming, an automatic search program is generated by an accurate electro-mechanical programmer, which is described.

Target acquisition, in an automatic mode of operation, is accomplished through the use of a simple logic circuit which provides electronic background discrimination by virtue of signal pulse width.

High Precision Angle Determination by Means of Radar in a Search Mode—E. C. Watters, F. L. Rees, and R. A. Enstrom (p. 317)

One of the more difficult requirements to meet in the design of radars is that of accurate angular measurement. In tracking radars the azimuth and elevation of a target can be measured to a high degree of accuracy by a nulling method. Two of the most practical methods for obtaining angular accuracy in search radars are discussed in this paper. The first method is an interferometer technique employing either two receiving antennas for each dimension of angular measurement with two frequencies of transmission for the resolution of ambiguities, or three receiving antennas positioned relative to one another so that the equivalent effect is achieved with only one-frequency transmission. The second method is a combination amplitude comparison and interferometer technique in which the ambiguities are resolved by the amplitude comparison system. An analysis of each of these systems has been made using a statistical approach in which equations are developed relating the probability of error for a specified angular accuracy to SNR power in the receiver. Curves are presented which show this relationship for a 100 to 1 beam-splitting ratio.

An automatic TV Tracking Theodolite for Range Instrumentation—R. Wisnieff (p. 326)

The factors affecting the design of a gated Automatic TV Tracking System are discussed, and a system mechanization to achieve the design objectives is outlined. Only the composite video of a closed-circuit TV system is required as an input. A study of the dynamic performance of typical targets indicates that the unpredictable target motion in a frame period of 1/30 sec must be an extremely small fraction of the field of view required for initial target acquisition. This permits the use of a small tracking gate in the larger acquisition field, since the target coordinates of the previous frame may be used to position the gate. This small gate permits a signal-to-noise enhancement and effectively rejects extraneous targets outside the tracking gate.

The tracking is effected by subdividing the tracking area into equal early and late video gates in each coordinate. The differential video between these gates is applied to an electronic integrator in such a manner that the integrator output voltage, which is also the reference for the generation of the early-to-late gate transition, changes to place this gate transition on the target. The integrator voltages are, therefore, a measure of the target coordinates in the TV field.

The operation of an experimental system fabricated to determine the feasibility of applying this technique to a range-instrumentation system has produced tracking accuracies of better than 0.05 milliradian in an acquisition field of 10×10 milliradians. Current developments and additional applications of the technique are discussed briefly.

The Future of Pulse Radar for Missile and Space Range Instrumentation—D. K. Barton (p. 330)

An account of instrumentation radar development is given, and advantages and disadvantages of radar as compared to other instruments are discussed. Capabilities of present monopulse radars are described, based upon actual test data from the AN/FPS-16. This radar has a range of 200 miles on echo targets of one-square-meter cross section and can track to an accuracy of 0.1 mil in angle and 5 yards in range. The next generation in instrumentation radar is represented by the AN/FPQ-6, now under development, which will extend accurate tracking to ranges in excess of 500 miles on echo targets and will track existing beacons beyond the moon. An important capability not yet exploited in pulsed-instrumentation radars is the coherent pulsed-Doppler velocity-measurement channel which will equal the accuracy of microwave CW systems in radial-velocity data. Provisions for adding this fourth tracking channel to both AN/FPS-16 and AN/FPQ-6 are being made, and suitable beacons are being designed. An important advantage of pulsed-Doppler radar is the ability to share a single coherent beacon in multiple-station operation, providing highly accurate, three-coordinate velocity and position data without special interstation communication links over ground paths.

Beyond the immediate developments of the AN/FPQ-6, there are three major areas of improvement which will greatly extend radar performance. Solid-state maser preamplifiers will increase sensitivity of microwave radars by a factor of nearly one hundred within one or two years. Microwave antennas are already under construction in the 100- and 300-ft diameter class. Multiple-tube transmitters will make available ten to one hundred times the presently used average power, and signal-processing techniques are available to code the transmissions for accurate measurement of range and velocity. As a result of these developments, the improvement in radar performance should proceed at a more rapid pace even than that of the past ten years.

The unique ability of radar in acquiring and tracking uncooperative objects has been appreciated for some years, and examples of actual tracks are presented to show some of the interesting data which can be extracted from satellite echo signals.

Effects of Atmospheric Turbulence on Optical Instrumentation—R. A. Becker (p. 352)

The results of research on optical turbulence at White Sands Missile Range are presented. It has been shown that elevating camera stations 33 feet above ground level can yield nearly a threefold increase in optical resolution during periods of atmospheric turbulence. Early research postulated the existence of thermal-induced air lenses as the cause of optical-turbulence effects. Recent research has shown that air lenses can account for most of the observed effects. The "prism" concept of turbulence appears to be unnecessary for explaining tubulence-induced image motion.

The dependence of the optical effects of turbulence upon exposure time and aperture size are discussed qualitatively. The source of optical turbulence in the atmosphere and a method of measuring the turbulence-generating potential of various terrain surfaces are described on the basis of micrometeorology.

This research has been limited to an investigation of optical turbulence during the period from sunrise to sunset. However, many of the results apply to the nighttime turbulence encountered by astronomers.

Television in Underwater Weapons Testing—A. R. Metzler (p. 357)

At the Naval Ordnance Test Station sea ranges at San Clemente Island, closed-circuit television is used both over and under water for certain phases of underwater weapons testing. The functions of this instrumentation are to provide: real-time data, engineering surveillance, monitoring, underwater launcher positioning, range surveillance, time-event data, trajectory data, and to assist in underwater search and recovery.

At present, 17 closed-circuit systems are in use above and below the surface of the ocean, and more systems are being built. The new systems include an Image Orthicon camera for underwater search and a Vidicon-type system for operations at a depth of 6000 feet.

Programmed Search in Adaptive Systems—N. S. Potter (p. 362)

An investigation is conducted of the programming of search by discrete data systems over a space volume. The distribution of search effort which leads to the greatest attainable information rate on a contact, or probability of its retention by maximizing the probability of a positive interrogation within some designated time interval is determined. An estimate of p, the relative frequency of positive interrogations of an individual contact, is utilized as a basis for adjustment of the sampling rate in accordance with results of the search program optimization study. It is shown that in the case of Rayleigh signal sources, the rate of convergence to a stable estimate of p is greatest if a search program characterized by a rapid sampling rate and a consequent low probability of detection on the individual trial is employed.

If, following a sequence of observations, the statistical distribution of the position of the contact may be ascertained with some confidence, a suitably restricted space volume may be used in the allocation of search. It is shown that, if an extremal exists, the uniformly interrogated search field, which is optimal in the sense that the product of the containment and detection probabilities is greatest, is defined by an equiprobability density of location contour. Further, if a nonuniformly distributed search program is pursued and the errors are determined to be binormally, circularly distributed, the greatest effort should be allocated to the region in the vicinity of the center of the positional distribution, with a parabolic decline to zero in dwell time as the periphery of a bounding, circular region, whose radius is a function of the standard deviation, is approached.

The Design of a CW Passive Missile Trajectory Measuring System—R. A. Voss (p. 370)

Several tests have provided data sufficient to demonstrate the feasibility of tracking missiles with a CW passive Doppler system. Initial experiments utilized a local television station as a target illuminator; later tests examined the capability of such a system as a terminal trajectory measuring device. These latter tests showed that the system could be designed to have a multiple-target capability.

An interim high-power system is being installed to determine if the techniques established for a low-power system can be extended to provide reliable coverage of White Sands Missile Range (WSMR). Some improvement of these techniques is anticipated, and, in addition, certain tests will employ spaced receivers operated as radio interferometers.

Contributors (p. 375)

Abstracts and References

Compiled by the Radio Research Organization of the Department of Scientific and Industrial Research, London, England, and Published by Arrangement with that Department and *Electronic Technology*, Dorset House, Stamford St., London S.E. 1, England

NOTE: The Institute of Radio Engineers does not have available copies of the publications mentioned in these pages, nor does it have reprints of the articles abstracted. Correspondence regarding these articles and requests for their procurement should be addressed to the individual publications, not to the IRE

Acoustics and Audio Frequencies..... 1979
Antennas and Transmission Lines..... 1980
Automatic Computers..... 1981
Circuits and Circuit Elements..... 1981
General Physics..... 1983
Geophysical and Extraterrestrial Phenomena..... 1984
Location and Aids to Navigation..... 1986
Materials and Subsidiary Techniques.. 1987
Mathematics..... 1990
Measurements and Test Gear..... 1990
Other Applications of Radio and Electronics..... 1990
Propagation of Waves..... 1990
Reception..... 1991
Stations and Communication Systems.. 1991
Subsidiary Apparatus..... 1992
Television and Phototelegraphy..... 1992
Transmission..... 1992
Tubes and Thermionics..... 1992

The number in heavy type at the upper left of each Abstract is its Universal Decimal Classification number. The number in heavy type at the top right is the serial number of the Abstract. DC numbers marked with a dagger (:) must be regarded as provisional.

UDC NUMBERS

Certain changes and extensions in UDC numbers, as published in PE Notes up to and including PE 666, will be introduced in this and subsequent issues. The main changes are:

Artificial satellites:	551.507.362.2	(PE 657)
Semiconductor devices:	621.382	(PE 657)
Velocity-control tubes, klystrons, etc.:	621.385.6	(PE 634)
Quality of received signal, propagation conditions, etc.:	621.391.8	(PE 651)
Color television:	621.397.132	(PE 650)

The "Extensions and Corrections to the UDC" Ser. 3, No. 6, August, 1959, contains details of PE Notes 598–658. This and other UDC publications, including individual PE Notes, are obtainable from The International Federation for Documentation, Willem Witsenplein 6, The Hague, Netherlands, or from The British Standards Institution, 2 Park Street, London, W.1., England.

A list of organizations which have available English translations of Russian journals in the electronics and allied fields appears each June and December at the end of the Abstracts and References' section.

The Index to the Abstracts and References published in the PROC. IRE from February, 1960 through January, 1961 is published by the PROC. IRE, May, 1961, Part II. It is also published by *Electronic Technology* and appears in the March, 1961, issue of that Journal. Included with the Index is a selected list of journals scanned for abstracting with publishers' addresses.

ACOUSTICS AND AUDIO FREQUENCIES

534.152 3603

Optical Calibration of Vibration Pickups at Small Amplitudes—V. A. Schmidt, S. Edelman, E. R. Smith and E. Jones. (*J. Acoust. Soc. Am.*, vol. 33, pp. 748–751; June, 1961.) A photometric device based on a Fizeau-type interferometer and capable of measuring sinusoidal variations ranging from 72 to 4400 A in amplitude is described.

534.2:534.88 3604

Horizontal Refraction in a Three-Dimensional Medium of Variable Stratification—D. E. Weston. [*Proc. Phys. Soc. (London)*, vol. 78, pp. 46–52; July, 1, 1961.] The bending of rays caused by reflection at an inclined boundary is discussed, with reference to underwater propagation of sound. See also 2204 of 1959.

534.2–14 3605

The Propagation of Tone Signals in a Plane Water Layer with Agitated Surface—L. N. Zakharov. (*Akust. Z.*, vol. 6, no. 4, pp. 454–461; 1960.) Investigation of the effect of surface agitation on signal amplitude and phase difference. Quantitative correlations are obtained between the fluctuation of the acoustic signal and height of the surface wave.

534.2–14 3606

The Fluctuations of Underwater Acoustic Signals Reflected from a Rough Sea Surface—G. E. Smirnov and O. S. Tonakanov. (*Akust. Z.*, vol. 6, no. 4, pp. 482–490; 1960.) Experiments were carried out in natural conditions and in a model tank at frequencies of 5–25 kc and 70–200 kc respectively. A factor is derived for the amplitude variation and the magnitude of fluctuation of the phase difference of reflected signals corresponding to different values of the roughness coefficient of the water surface.

534.21 3607

Experimental Study of the Influence of Surface Finish on Attenuation of Surface Waves—N. S. Bykov and Yu. G. Shneider. (*Akust. Z.*, vol. 6, no. 4, pp. 501–503; 1960.)

534.232 3608

Computation of Axial Concentration Coefficient of Certain Discrete Receiving-Radiating Groups—R. V. Belyakov. (*Akust. Z.*, vol. 6, no. 4, pp. 499–501; 1960.)

534.232:538.652 3609

Utilization of Magnetostrictive Materials in Generating Intense Sound—R. R. Whymark. (*J. Acoust. Soc. Am.*, vol. 33, pp. 725–732; June, 1961.) The calculating and theoretical sound outputs of a laminated bar of annealed Ni at its resonance frequency agree within ±10 per cent. The bar, resonant longitudinally at 20 kc, gave a measured maximum sound intensity of 167 w/cm².

534.232:621.316.825 3610

Thermoelectric Ultrasonic Pickup with a Semiconductor Thermistor—É. K. Labartkava (*Akust. Z.*, vol. 6, no. 4, pp. 468–471; 1960.) A brief description is given of a point-type transducer consisting of a microthermoresistor with a plexiglas thermosensitizer.

534.232.089.6 3611

Acoustic Measurements under Transient Temperature Conditions—W. L. Paine. (*J. Acoust. Soc. Am.*, vol. 33, p. 816; June, 1961.) A transducer to be calibrated is precooled or warmed to the temperature extreme of interest and its performance is then monitored as it returns to the ambient temperature of the water in an anechoic test tank.

534.283–8:537.311.31 3612

Dynamical Theory of Ultrasonic Attenuation in Metals—N. Takimoto. (*Progr. Theor. Phys.*, vol. 25, pp. 327–352; March, 1961.) A detailed investigation of the ultrasonic attenuation governed by the dynamic properties of conduction electrons.

534.522.1 3613

Optical Measurement of Ultrasonic Fields—R. F. Weeks (*J. Acoust. Soc. Am.*, vol. 33, pp. 741–747; June, 1961.) Passage of an ultrasonic wave train through a transparent solid produces a periodic birefringence within the solid. A photomultiplier scans the transmitted light mechanically to determine sound energy flow in the solid.

534.62 3614

Acoustic Properties of Anechoic Chamber—N. Olson. (*J. Acoust. Soc. Am.*, vol. 33, pp. 767–770; June, 1961.) Results of measurements made in a chamber built for the National Research Council of Canada are given in graphical form.

534.88:621.396.965.4 3615

Multiplicative Receiving Arrays: the Angular Resolution of Targets in a Sonar System with Electronic Scanning—V. G. Welsby. (*J. Brit. IRE*, vol. 22, pp. 5–12; July, 1961.) A theoretical analysis of the effect of cross-product terms on the performance of a multiplicative system is given. Results of practical trials confirm that the system can give an angular resolution approximately twice as good as that of the same array used additively.

621.395.625.3:681.84.083.84 3616

The Modulation Noise of Magnetic Recording Tape—P. A. Mann. (*Arch. elekt. Übertragung*, vol. 15, pp. 18–24; January, 1961.) With reference to earlier investigations on unused and erased tape (3385 of 1957) the effect of modulation on tape noise is calculated for sinusoidal and pulse modulation. The spectral

distribution of noise power is found to be independent of signal frequency.

681.828.5 3617
Electronic Generation of Sounds using the Principle of Light-Spot Scanning of Stencils—G. Holoch. (*Nachrtech. Z.*, vol. 14, pp. 1–6; January, 1961.) Method and equipment are described for the production of pure and mixed sounds with dynamic structure of almost any desired rate of variation.

ANTENNAS AND TRANSMISSION LINES

621.315.212 3618
Temperature Variation of Primary and Secondary Parameters of 2.6/9.5 mm Coaxial Pairs—A. Payant. [*Câbles & Trans. (Paris)*, vol. 15, pp. 130–147; April, 1961.] A theoretical and experimental study with reference to the experimental Corbeil-Versailles link.

621.315.212:621.372.51 3619
Physically Short High-Power Balun is Continuously Variable—J. T. Coleman. (*Electronics*, vol. 34, pp. 50–52; July 28, 1961.) A coaxial-line capacitively loaded balun for 5 Mw at 10–30 Mc having a physical length $<\lambda°/20$ and using vacuum variable capacitors is described.

621.372.2:621.371 3620
Transmission-Line Model—J. D. Wallace. (PROC. IRE, vol. 49, p. 1324; August, 1961.) A hypothetical infinitely long coaxial line with zero-loss conductors having a ratio between the inner diameter of the outer conductor and the outer diameter of the inner conductor equal to $e^{2\pi}$, when used in a vacuum, can be shown to have the same properties as free space. The line formulas enable various propagation problems to be simulated. Examples are given.

621.372.2:[621.372.51+621.372.814 3621
The Design of n-Step Line Transformers—H. Schreiber. (*Arch. elekt. Übertragung*, vol. 15, pp. 84–90; February, 1961.) Design formulas are derived for noncompensated matching transformers consisting of n sections of homogeneous transmission line. Design methods are compared.

621.372.2:621.372.512 3622
High-Speed Microwave Switch—L. L. Oh and C. D. Lunden. (*Electronics*, vol. 34, p. 60; July 7, 1961.) A noncontacting rotary switch using straight-line and circular-line codirectional couplers for sampling the power in a 24-element linear antenna array is described. It scans at rates up to 5000 rev/min and has a power-coupling efficiency of 80 per cent at 430 Mc.

621.372.2:621.372.512 3623
Zigzag-Line Couplers transfer Microwave Power—L. L. Oh and C. D. Lunden. (*Electronics*, vol. 34, pp. 58–59; July 14, 1961.) Brief details are given of several UHF switches using a zigzag line as the coupling element. An almost constant input impedance is maintained during switching and several advantages, due to the absence of arcing and mechanical contacts, are obtained over conventional switching devices.

621.372.8:537.56 3624
Propagation of Centimetre Waves through Waveguides Filled with Plasma of the Positive Column of a Discharge: Part 1—V. E. Golant, A. P. Zhilinskiĭ, M. V. Krivosheev, and G. P. Nekrutkina. (*Zh. Tekh. Fiz.*, vol. 31, pp. 55–62; January, 1961.) Results of an experimental investigation are compared with theoretical data.

621.372.8:537.56 3625
Propagation of Centimetre Waves through Waveguides Filled with Plasma of the Positive Column of a Discharge: Part 2—V. E. Golant, A. P. Zhilinskiĭ, M. V. Krivosheev, and L. I. Chernova. (*Zh. Tekh. Fiz.*, vol. 31, pp. 63–70; January, 1961.) Results are given of an experimental investigation of the dependence of the wave propagation constant on the high-frequency field strength, for regions in which nonlinear effects occur. Part 1: 3624 above.

621.372.8.09 3626
The Influence of Parasitic Parameters of an Electrical Waveguide Model on the Accuracy of the Solution of the Problem of Field Distribution—N. I. Shteĭn. (*Radiotekh. Elektron.*, vol. 5, pp. 1417–1425; September, 1960.)

621.372.81 3627
Wave Parameters and Wave Matrices Particularly for Microwave Networks with Multimode Waveguide—H. Brand. (*Arch. elekt. Übertragung*, vol. 15, pp. 48–60; January, 1961.) The relation between vector field quantities and the scalar wave parameters in waveguide networks is analyzed for several types of mode. The use of scattering and transmission matrices for calculations on multimode waveguide systems is described with examples.

621.372.829:621.372.853.2 3628
Propagation of Electromagnetic Waves in Waveguides of Complex Cross-Section with a Cross-Magnetized Ferrite Plate—N. M. Kovtun. (*Radiotekh. Elektron.*, vol. 5, pp. 1426–1430 September, 1960.) Equations are derived defining the propagation constants of a ferrite-loaded waveguide of H-shape cross section and variants of this.

621.372.832 3629
Electromagnetic Waves in Multiterminal Couplings of Rectangular Waveguide—H. Kaden. (*Arch. elekt. Übertragung*, vol. 15, pp. 61–70; February, 1961.) The distribution of H_{01}-mode power at a transition from two parallel waveguides to a single waveguide of double width is considered, and the problem is formulated mathematically by an infinite set of linear equations which are solved approximately by computer. The coupling between two parallel rectangular waveguides coupled by a slot of arbitrary length is calculated and the special case of equal distribution of power in the two waveguide sections is discussed.

621.372.837.1 3630
Waveguide Switch for Microwave Radiometers—M. J. B. Scanlan. (*Electronic Tech.*, vol. 38, pp. 337–339; September, 1961.) The switch, especially useful for large waveguides, is based on the short-slot or Riblet coupler and operates in the range 1–2 Gc. A vane, rotating at half the switching frequency, opens and closes the waveguides joining the two couplers.

621.372.852:621.318.134 3631
Low-Level Garnet Limiters—F. R. Arams, M. Grace, and S. Okwit. (PROC. IRE, vol. 49, pp. 1308–1313; August, 1961.) S- and L-band low-level passive limiters using polished single crystals of narrow-line-width Y-Fe garnet have been developed. Performance data are given. The operation of three novel types of limiter—electronically tunable preselectors and cavity-type and comb-type filters—is described.

621.396.67 3632
The Antenna Constructed by Parallel Wires—K. Nagai, R. Sato, and H. Uchida. (*Sci. Repts. Res. Insts. Tohoku Univ., Ser. B.*, vol. 12, no. 2, pp. 73–96; 1960.) The interchange between normal-phase modes and the zero-phase modes in the case of two asymmetrical or discontinuous parallel wires is considered. The theory developed is applied to radiating systems.

621.396.67:621.397.62 3633
The Permissible Mismatch in Aerial Installations for Television Reception—Fiebranz. (See 3955.)

621.396.67.095 3634
Current Waves in a Thin Cylindrical Conductor: Part 3—Variational Method and its Application to the Theory of an Ideal Conductor and a Conductor with Impedance—L. A. Vaĭnshteĭn. (*Zh. Tekh. Fiz.*, vol. 31, pp. 29–44; January, 1961.) A method of successive approximations is described based on the variational principle. This technique permits a derivation of an expression for waves in thin conductors. An approximate expression is also obtained for the scattering characteristic of a plane EM wave on a semi-infinite conductor. Part 2: 4104 of 1960.

621.396.67.095 3635
Current Waves in a Thin Cylindrical Conductor: Part 4—Input Impedance of an Oscillator and the Accuracy of Formulae—L. A. Vaĭnshteĭn. (*Zh. Tekh. Fiz.*, vol. 31, pp. 45–50; January, 1961.) Values of the complex variable determining the input impedance of an infinite conductor are tabulated, and the significance of this parameter in calculating the impedance of a straight conductor of finite length is clarified. Part 3: 3634 above.

621.396.674.3 3636
The Electromagnetic Fields of a Horizontal Dipole in the Presence of a Conducting Half-Space—J. R. Wait. (*Canad. J. Phys.*, vol. 39, pp. 1017–1028; July, 1961.) Fairly simple expressions for the fields are obtained by three methods and adequately cover all distances.

621.396.676:551.507.362.2 3637
Reconnaisance Satellite Antennas—R. B. MacAskill. (*Electronic Ind.*, vol. 20, pp. 108–115; April, 1961.) Design problems relating to gain, bandwidth and directivity requirements are discussed. Signal resolving techniques and possible types of antenna are outlined.

621.396.677 3638
Circular Aerial Arrays for Radio Astronomy—J. P. Wild. [*Proc. Roy. Soc. (London) A*, vol. 262, pp. 84–99; June 13, 1961.] A theoretical analysis shows that a circular array has a number of advantages over the Mills cross: 1) the length of transmission line between each element and receiver is halved; 2) for the same information, the number of elements required is reduced in the ratio $4:\pi$; 3) the beam possesses circular or elliptical symmetry, and 4) the system can be calibrated directly for phase and amplitude using a transmitter on a central tower.

621.396.677:621–526 3639
Project Echo: Antenna Steering System—Klahn, Norton, and Githens. (See 3937.)

621.396.677.091.22 3640
Maximum Antenna Gain of Shaped Beams—D. Levine. (*J. Franklin Inst.*, vol. 271, pp. 184–191; March, 1961.) The maximum gain of narrow beams can be evaluated within 1 db if it is assumed that 60 per cent of the transmitted energy lies outside the 3-db power contour. If the computed gain exceeds the measured value by more than 1 db, it is probable that the design can be improved.

621.396.677.3 3641
The Theory of a Single-Ring Circular Antenna Array—C. E. Hickman, H. P. Neff, and J. D. Tillman. (*Commun. and Electronics*, no. 54, pp. 110–115; May, 1961.) An examination is made of the currents possible in a circular array, the pattern which results from them and means of producing a specific radiation pattern.

621.396.677.3 3642
Resolution Characteristics of Correlation Arrays—I. W. Linder. (*J. Res. N. Bur. S.*, vol. 65D, pp. 245–252; May/June, 1961.) Analysis of resolution capabilities of correlation arrays shows a marked change in performance in the presence of two or more signal sources. These effects are analyzed for single-frequency signal sources and for randomly varying signal sources. Under optimum conditions a correlation array has twice the directivity of a linear array of the same length.

621.396.677.73 3643
A Method of Determining Phase Centres and its Application to Electromagnetic Horns—Y. Y. Hu. (*J. Franklin Inst.*, vol. 271, pp. 31–39; January, 1961.) The center of a radiating system may be located from the expression for the radiating field. The method is applied to EM horns of different dimensions and flare angles.

621.396.677.833 3644
The Radiation of a Reflector Aerial in the Shadow Region—V. L. Tandit and L. B. Tartakovskiĭ. (*Radiotekh. Elektron.*, vol. 5, pp. 1398–1406; September, 1960.) The radiation field in the shadow region of an infinitely thin, ideally conducting reflector irradiated by a small wide-beam exciter is calculated, taking into account diffraction corrections for the near field of the exciter, the curvature of the reflector, and fringe effects.

621.396.677.833.2 3645
The Condition of Shadowing and the Diffraction Correction to Current Distribution—B. E. Kinber. (*Radiotekh. Elektron.*, vol. 5, pp. 1407–1416; September, 1960.) Theoretical treatment relating to the diffraction field of a paraboloidal radiator.

621.396.677.833.2 3646
Project Echo: A Horn-Reflector Antenna for Space Communication—A. B. Crawford, D. C. Hogg, and L. E. Hunt. (*Bell Syst. Tech. J.*, vol. 40, pp. 1095–1116; July, 1961.) The mechanical construction and electrical properties are described. Gain and pattern measurements at 2390 Mc agree well with the theoretical characteristics.

621.396.677.833.2:621.396.965 3647
Design of Line Feed for World's Largest Aperture Antenna—A. F. Kay. (*Electronics*, vol. 34, pp. 46–47; July 7, 1961.) A description of the design of the feed system for the 1000 ft spherical dish antenna being erected at Arecibo, Puerto Rico.

AUTOMATIC COMPUTERS

681.142 3648
Digital Computers.—K. Mierzowski. (*VDI Z.*, vol. 103, pp. 767–775; June 11, 1961. 4 tables.) Annual review of developments in computer design with descriptions of recent installations and tabulated performance data. 76 references. For previous review see 3381 of 1960 (Schuff).

681.142 3649
Notes on the Structure of Logic Nets—R. M. Stewart. (Proc. IRE, vol. 49, pp. 1322–1323; August, 1961.) An elementary approach to a theory of the role of structure in logic nets.

681.142 3650
The Main Store of a Digital Differential Analyzer—P. L. Owen, M. F. Partridge, and T. R. H. Sizer. (*Electronic Engrg*, vol. 33, pp. 514–520; August, 1961.) A description of the performance and circuits of the main store of CORSAIR.

681.142:621.3.029.6 3651
A Potential Microwave Computer Element—R. W. Couch, A. F. Rashid, and R. Spence. (Proc. IRE, vol. 49, pp. 1338–1339; August, 1961.) A bistable-oscillator frequency-script system is described which uses a tunnel diode as the active element. A switching time of the order of 10 cycles is required for resonance frequencies of 600/735 kc. Operation at 250/375 Mc has been demonstrated, and operation at 10 Gc is suggested.

CIRCUITS AND CIRCUIT ELEMENTS

621.316.825 3652
New, Thermally Variable Bead Resistor—V. J. Tennery and R. G. West. (*J. Appl. Phys.*, vol. 32, p. 1402; July, 1961.) The unique I/V characteristic of ion-doped $BaTiO_3$ is illustrated. A bead 0.075 inch in diameter dissipated 1.5 w in still air.

621.318.4:621.3.011.4 3653
Equivalent Circuits of Coils with Distributed Capacitances—A. Fettweis. (*Rev. HF, Brussels*, vol. 5, no. 2, pp. 19–25; 1961.) The equivalent circuit comprises an ideal coil, a certain number of positive capacitances (two in the case of a coil with one winding) and an additional capacitance which can be either positive or negative depending on the relative magnitude and the exact distribution of the various parasitic capacitances.

621.318.4.042:621.375.3 3654
On the Core Gain of the Magnetic Amplifier Cores—K. Murakami and T. Kikuchi. (*Sci. Repts. Res. Insts. Tohoku Univ., Ser. B*, vol. 12, no. 2, pp. 135–144; 1960.) New definitions, specific core gain and core gain, are suggested and the relation of these to the power gain of an amplifier is discussed.

621.318.435 3655
An Experimental Study on the Ampere-Turn Gain of Ordinary Saturable Reactors—W. A. Geyger. (*Commun. and Electronics*, no. 54, pp. 173–178; May, 1961.) Measurements show the great improvements in performance of dc instrument transformers can be obtained by slightly increasing the effective ratio of primary to secondary turns and applying a properly rated ac bias circuit.

621.318.57:537.312.62 3656
On the Linear Circuit Aspects of Cryotrons—P. M. Chirlian and V. A. Marsocci. (Proc. IRE, vol. 49, p. 1326; August, 1961.) An expression is derived for the gate resistance of a cryotron in the transition region.

621.318.57:621.317.6 3657
Variable-Conductance Sampling Switch—J. E. Taylor. (*Rev. Sci. Instr.*, vol. 32, pp. 754–755; June, 1961.) Weighted sums are produced of discrete samples from continuous voltage waveforms, by varying the rate at which the integrating capacitor can charge. The switch has been operated randomly and cyclically at rates between 20 and 50000/sec.

621.318.57:621.382.23 3658
The Silicon Cryosar—H. Izumi. (Proc. IRE, vol. 49, pp. 1313–1314; August, 1961.) The main difference from the Ge cryosar [3211 of 1959 (McWhorter and Rediker)] is that negative-resistance characteristics are obtained using crystals with uncompensated impurities. As a computer element the device has been switched in about 50 nsec and has a maximum/minimum voltage ratio as high as 7.

621.319.4:621.372.44:621.382 (083.7) 3659
IRE Standards on Solid-State Devices: Definitions of Terms for Nonlinear Capacitors, 1961—(Proc. IRE, vol. 49, pp. 1279–1280; August, 1961.) Standard 61 IRE 28.S1.

621.372.44:621.373 3660
On Some Aspects of Matrix Calculus applied to Local Oscillation in Nonlinear Circuits—F. Bertein. (*J. Phys. Radium*, vol. 21, suppl., *Phys. Appl.*, pp. 137A–148A; November, 1960.) The application of matrix methods to the analysis of oscillating circuits with an impressed signal of low amplitude is considered. The representation of amplitude and phase modulation in coordinate form is illustrated, and examples are given of the use of these methods in problems of oscillator stabilization.

621.372.5:517.7 3661
Elliptic Functions in Network Synthesis—S. D. Bedrosian. (*J. Franklin Inst.*, vol. 271, pp. 12–30; January, 1961.) The Jacobian elliptic functions are used to solve the approximation problem of network synthesis. A unified design chart for image parameter filters, elliptic-function filters and 90°-phase-difference networks is shown and tabular and graphical data emphasizing extreme parameter values are given.

621.372.5:621.3.049.75 3662
Shaping of Distributed *RC* Networks—B. L. H. Wilson and R. B. Wilson. (Proc. IRE, vol. 49, pp. 1330–1331; August, 1961.) An improvement in the attenuation factor of a 180°-phase-shift network from 29 to 7 appears to be possible if the conventional untapered 3-section network is replaced by a tapered distributed network.

621.372.54 3663
Graphical Procedures for Solving the Approximation Problem of Electrical Filters—R. Rubini. (*Alta Frequenza*, vol. 30, pp. 135–155; February, 1961.) Three graphical methods of synthesizing filter response characteristics as the sum and difference of functions of similar geometric form are explained. The methods are theoretically equivalent but have different fields of application. For English version see *ibid.*, vol. 30, pp. 198 215; March, 1961.

621.372.54:621.372.412 3664
Optimum Matching of Symmetrical Low-Pass and High-Pass Filters: Application to Low-Pass and High-Pass Ladder Filters using Piezoelectric Crystals—J. E. Colin and P. Allemandou. [*Câbles & Trans.* (*Paris*), vol. 15, pp. 99–114; April, 1961.] A filter structure is suggested which is especially suitable for use with crystal elements. Advantages and disadvantages of this and similar structures are discussed.

621.372.543.2 3665
Tunable Rejection Filters—L. A. Moxon. (*Electronic Tech.*, vol. 38, pp. 327–330; September, 1961.) An analysis of the requirements for a rejection filter is used in the design of some practical circuits, tunable over half an octave and covering the HF band.

621.372.55:621.396.4:621.376 3666
V.H.F. Broad-Band Variable Group-Delay Equalizers—R. Hamer and R. G. Wilkinson. (*Electronic Engrg*, vol. 33, pp. 506–510; August, 1961.) The two designs described are for links using 1) 960 telephony channels or 405-line subcarrier color television, and 2) 1800 telephony channels or 625-line subcarrier color television.

621.372.6 3667
Application of Graph Theory to the Analysis of Active and Mutually Coupled Networks—W. H. Kim. (*J. Franklin Inst.*, vol. 271, pp. 200–221; March, 1961.) A unified graphical ap-

proach applying the concept of the mathematically equivalent circuit [52 of 1956 (Percival)] as it relates to the indefinite admittance matrix of a multipole.

621.372.632:621.382.23 3668
Stable Low-Noise Tunnel-Diode Frequency Converter—F. Sterzer and A. Presser. (PROC. IRE, vol. 49, p. 1318; August, 1961.) An initial wide-band converter with local-oscillator frequency 780 Mc and intermediate frequency 30 Mc had unity conversion gain and a radiometer noise figure of 2.5 db.

621.373:621.372.2:621.372.44 3669
Self-Oscillation in a Transmission Line with a Tunnel Diode—J. Nagumo and M. Shimura. (PROC. IRE, vol. 49, pp. 1281–1291; August, 1961.) A theoretical analysis of the circuit is given together with experimental results. The self-oscillation can be explained as a periodic solution of the linear wave equation with a nonlinear boundary condition.

621.373:621.391.822 3670
Broadening of the Spectrum of an Oscillator due to Noise—J. Loeb. (*Ann. Télécommun.*, vol. 14, pp. 151–152; May/June, 1959.) A formula is derived for the frequency broadening due to random thermal noise in a nonlinear circuit.

621.373.4 3671
Pulling Phenomena in Valve Oscillators—S. Spiess. (*Nachrtech.*, vol. 10, pp. 452–457 and 540–546; October and December, 1960.) A general theory of pulling effects is derived on the basis of band-filter theory. These effects are calculated as a function of detuning and degree of coupling between similar and dissimilar oscillator circuits. A mechanical analogue of a "pulled" oscillating system is described.

621.373.4.029.4:621.316.86 3672
Varistor Network controls Voltage-Tuned Oscillator—M. Uno. (*Electronics*, vol. 34, pp. 44–47; July 28, 1961.) An AF phase-shift oscillator, with SiC varistors as the variable elements has almost constant output over a range of 10:1 and low harmonic distortion.

621.373.421.11 3673
Locking of a Two-Circuit Oscillator—G. D. Shemanaev and E. N. Ivanova. (*Radiotekh. Elektron.*, vol. 5, pp. 1387–1397; September, 1960.) The addition of a second tuned circuit improves the amplitude/frequency and phase /frequency characteristics of a locked oscillator. The effect of coupling conditions on stability is discussed.

621.373.421.13 3674
Recent Development of Quartz Crystal Units for Telecommunication—K. Takahara. (*Rev. Elec. Commun. Lab., Japan*, vol. 9, pp. 165–206; March/April, 1961.) A new method and equipment devised for manufacture and development of crystal units in the range 1 kc–100 Mc, and associated apparatus are described.

621.373.43:621.382.23 3675
Tunnel-Diode One-Shot and Triggered Oscillator—T. W. Flowerday and D. D. McKibbin. (PROC. IRE, vol. 49, p. 1315; August, 1961.) The one-tunnel-diode flip-flop described by Kaenel (1761 of July) which requires a bidirectional pulse can be made to operate as a triggered oscillator by the addition of an identical circuit with modified bias.

621.373.43:621.382.3 3676
The Switching Mechanism of the Schmitt Trigger Circuit using Transistors—K. Leberwurst. (*Nachrtech.*, vol. 10, pp. 519–524; December, 1960.) Equivalent circuits and characteristic curves are derived; results of measurements are given for comparison.

621.373.431.1:621.382.23 3677
The Tunnel-Diode Pair—D. J. Hamilton and M. J. Morgan. (*Semiconductor Prod.*, vol. 4, pp. 17–23; July, 1961.) The composite V/I characteristic of the twin circuit is considered and its application in the design of astable, monostable and bistable multivibrators is illustrated; trigger requirements and effects of loading can also be determined.

621.374 3678
A Low-Level Linear Rundown Circuit for Pulse Height to Pulse Width Conversion—D. L. Endsley, W. W. Grannemann, and T. Summers. (*Commun. and Electronics*, no. 54, pp. 150–152; May, 1961.) A two-transistor device consisting of a constant-current generator and an emitter follower circuit is described. Experimental and theoretical analysis of the circuit are in good agreement.

621.374:621.382.23 3679
Tunnel-Diode Fast-Step Generator produces Positive or Negative Steps—R. Carlson. (*Electronics*, vol. 34, pp. 48–49; July 28, 1961.) The generator produces pulses of about 2 μsec duration having a rise time of 0.5 nsec at recurrence frequencies up to 100 kc.

621.374:621.382.333 3680
The Collector-Coupled Complementary Pair—V. Spány. (*Electronic Engrg*, vol. 33, pp. 526–527; August, 1961.) The astable mode gives phantastron-type waveforms with peak-to-peak voltages almost equaling the supply voltage. The bistable mode gives thyratron-type characteristics.

621.374.3:621.382.3 3681
Fast Coincidence Circuits using Avalanche Transistors—J. C. Artiges and J. C. Brun. (*J. Phys. Radium*, vol. 22, suppl., *Phys. Appl.*, pp. 53A–58A; February, 1961.) The circuit described has a resolution time of 2 nsec and an efficiency of 90 per cent. Results of tests made with 1) a pulse generator, and 2) a pair of photomultipliers are reported.

621.374.32:621.382.3 3682
An Automatic Self-Checking Transistor Counter with Digital Display—H. I. Messer and W. H. P. Leslie. (*Electronic Engrg*, vol. 33, pp. 484–489; August, 1961.)

621.374.32:681.142 3683
A Fast Binary Counter—E. Taranto. (*J. Brit. IRE*, vol. 22, pp. 31–32; July, 1961.) "A transistor binary counter employing seven flip-flops is described. Its operation is dependent only on the switching time of one flip-flop which may be ~100 nsec."

621.374.4:621.372.44 3684
A Tripler Circuit using a Capacitance Diode—D. Lohrmann and W. Marks. (*Frequenz*, vol. 15, pp. 9–12; January, 1961.) Mathematical analysis of a frequency tripler circuit and deviation of an equivalent circuit. The results of an analysis and of measurements on a practical circuit are compared.

621.374.5 3685
The Pulse Response of a Delay Line—P. Poincelot. [*Câbles & Trans.* (*Paris*), vol. 15, pp. 93–98; April, 1961.] An expression is developed for each element of the network and a solution is obtained in the form of a convergent Neumann series.

621.375.018.756:621.382.23 3686
Zener Diode creates Logarithmic Pulse Amplifier—D. Ophir and U. Galil. (*Electronics*, vol. 34, pp. 68–70; July 14, 1961.) Amplification over three decades is achieved by using as the logarithmic device a Zener diode to which a small resistance has been added to straighten the characteristic curve.

621.375.221 3687
Note on the Series Correction of Wide-Band Amplifiers—A. V. J. Martin. (*Onde élect.*, vol. 41, pp. 258–262; March, 1961.) A variation of the series-inductance correction circuit is considered in which the load resistance is connected across the output, and the circuit designed for either maximally flat transfer impedance or maximally flat input impedance. Inconvenient ratios of input to output capacitance can be avoided by using a cathode-follower stage.

621.375.3 3688
A New Magnetic-Controlled Rectifier Power Amplifier with a Saturable Reactor Controlling 'On' Time—R. E. Morgan. (*Commun. and Electronics*, no. 54, pp. 152–155; May, 1961.)

621.375.4 3689
Problems relating to Transistor Power Amplifiers—G. B. Debiasi. (*Alta Frequenza*, vol. 30, pp. 114–121; February, 1961.) The design of transformerless AF output amplifiers is considered, and a graphical method for determining transistor thermal stability is given.

621.375.4.024 3690
A Circuit for the Compensation of Voltage Drift in the Input Stage of a Direct-Coupled Transistor D.C. Amplifier—U. Hölken. (*Nachrtech. Z.*, vol. 14, pp. 32–36; January, 1961.) In the circuit given the temperature drift of the base/emitter voltage has been compensated almost to the theoretical limit.

621.375.4.024:621.398 3691
Differential Amplifier with Regulator Achieves High Stability, Low Drift—R. D. Middlebrook and A. D. Taylor. (*Electronics*, vol. 34, pp. 56–59; July 28, 1961.) A transistor dc amplifier suitable for missile telemetry systems is described.

621.375.426 3692
Narrow-Band Amplification with Transistors—E. R. Hauri and H. Beneking. (*Nachrtech. Z.*, vol. 14, pp. 37–39; January, 1961.) Contribution to 4149 of 1960 with author's reply.

621.375.9:538.569.4 3693
Field-Swept Maser Oscillation—J. C. Kemp. (*Phys. Rev. Lett.*, vol. 7, pp. 21–23; July 1, 1961.) The application by Singer and Wang (2897 of October) of their analysis of maser oscillations to experimental results of the author is criticized. They attribute the oscillations to energy exchange between cavity and emitting sample. The radiation envelope is, however, largely determined by the Zeeman field sweep rate, due to a different mechanism.

621.375.9:538.569.4:538.222 3694
Paramagnetic Maser Oscillator Analysis—S. Wang and J. R. Singer. (*J. Appl. Phys.*, vol. 32, pp. 1371–1376; July, 1961.) An equation for the output waveform is derived and numerical solutions obtained using a computer. Good agreement with experiment is given for steady-state and field-swept oscillators.

621.375.9:538.569.4:621.396.43 3695
Project Echo: The Dual-Channel 2390-Mc/s Travelling-Wave Maser—R. W. De Grasse, J. J. Kostelnick, and H. E. D. Scovil. (*Bell Syst. Tech. J.*, vol. 40, pp. 1117–1127; July, 1961.) Details of the ruby material isolator and amplifier package construction are given. An instantaneous bandwidth of 13 Mc and effective noise temperature of 8°K were obtained and the gain (>33db) was sufficient to override the noise of the following stage.

621.375.9:621.372.44 3696
Parametric Amplifiers—G. B. Stracca. (*Alta Frequenza*, vol. 30, pp. 98–113; February, 1961.) Theoretical comparison of gain, bandwidth, noise and stability of the negative-resistance amplifier and upper- or lower-sideband converts. Experimental results are also reported. For English version see *ibid.*, vol. 30, pp. 244–254; March, 1961.

621.375.9:621.372.44 3697
The Wide Tuning Range of Backward Travelling-Wave Parametric Amplifiers—H. Hsu and S. Wanuga. (PROC. IRE, vol. 49, pp. 1339–1340; August, 1961.) A method is indicated of increasing the range beyond that suggested by Straus. (IRE TRANS. ON MICROWAVE THEORY AND TECHNIQUES, vol. MTT-9, p. 95; January, 1961.)

621.375.9:621.372.44:621.382.2 3698
Theory of Nonreciprocal Circuits with Equal Input and Output Frequency using Nonlinear Semiconductor Elements—R. Maurer and K. H. Löcherer. (*Arch. elekt. Übertragung*, vol. 15, pp. 71–83; February, 1961.) The quadripole equations and transfer gain are derived for nonreciprocal amplifiers which consist of tunnel-diode or parametric-diode converter stages in cascade connection [see also 93 of February (Maurer *et al.*)]. Matching and decoupling problems are considered for various circuit configurations.

621.375.9:621.372.44:621.382.23 3699
Signal and Noise Characteristics of Diode-Reactance Amplifiers for the U.H.F. Region—R. Maurer. (*Radio Mentor*, vol. 27, pp. 110–113; February, 1961.) Examples are given of mixer circuits, straight amplifiers, and a traveling-wave amplifier using parametric-amplifier techniques. The problem of matching by means of nonreciprocal elements or by bridge circuit is also dealt with.

621.375.9:621.372.44:621.391.822 3700
Noise Figure and Stability of Negative-Conductance Amplifiers—A. C. MacPherson. (PROC. IRE, vol. 49, pp. 1314–1315; August, 1961.) Calculations of lowest noise-figure attainable from stability considerations are in agreement with results of an earlier analysis [2277 of 1960 (Van der Ziel and Tamiya)], but the lowest possible noise figure is obtained at the expense of stability.

621.375.9:621.372.44:621.396.969.3 3701
Project Echo: 961-Mc/s Lower-Sideband Up-Converter for Satellite-Tracking Radar—M. Uenohara and H. Seidel. (*Bell Syst. Tech. J.*, vol. 40, pp. 1183–1205; July, 1961.) The amplifier is pumped at 11.7 Gc and although regenerative it has been made unconditionally stable by careful mechanical and electrical design. The over-all noise figure is 1.6 db, gain 22 db and bandwidth 20 Mc.

621.375.9:621.382.23 3702
A Tunnel-Diode Slot Transmission Amplifier—M. E. Pedinoff. (PROC. IRE, vol. 49, pp. 1315–1316; August, 1961.) A negative-conductance waveguide transmission-type amplifier consisting of a tunnel-diode mounted within an S-band waveguide end-plate slot has been built operating at a frequency of 2.7 Gc with a bandwidth of 21 Mc and 16 db gain. No measurements have yet been made of noise figure.

621.376:621.372.54 3703
The Matching Problem of the Ring-Type and Double Push-Pull Modulator with Filter Termination at Both Ends.—H. Bauch. *Arch. elekt. Übertragung*, vol. 15, pp. 1–17; January 1961.) Detailed discussion of an impedance matching method for obtaining optimum frequency response and minimum attenuation.

621.376.22 3704
A Ring Modulator with Integrated Filters—J. Salzmann. [*Câbles & Trans.*, vol. 15, pp. 148–159; April, 1961.] A lossless four/terminal frequency-translating network is proposed which avoids using a transformer between rectifiers and filters.

GENERAL PHYSICS

535.215 3705
Theory of Phototexcitation in Solids—A. Messen. (*J. Phys. Radium.*, vol. 22, pp. 135–141; March, 1961.) The theory of optical absorption by photoexcitation is reviewed and further investigated. A distinction is made between "oblique" and "vertical" transitions.

537.311.1 3706
Tunnelling from an Independent-Particle Point of View—W. A. Harrison. (*Phys. Rev.*, vol. 123, pp. 85–89; July 1, 1961.) Calculation of wave functions for tunnelling problems, with applications.

537.52:538.63 3707
Radio-Frequency Breakdown Controlled by Drift of Electrons in an Inhomogeneous Magnetic Field—L. T. Shepherd and H. M. Skarsgard. (*Canad. J. Phys.*, vol. 39, pp. 983–992; July, 1961.) Measurements of breakdown RF electron field versus magnetic field were made at pressures between 1.25 and 6×10^{-3} mm in H and He. The breakdown RF field varied as the inverse square root of the magnetic field as predicted by theory.

537.525 3708
Experimental Evidence for Beam-Plasma Interaction in a Low-Pressure Argon Discharge—L. H. Putnam, H. D. Collins, and N. L. Oleson. (*Phys. Rev. Lett.*, vol. 7, pp. 77–79; August 1, 1961.)

537.533 3709
Broadening of a Beam of Electrons by the Space Charge—M. Boivin. (*J. Phys. Radium*, vol. 21, suppl., *Phys. Appl.*, pp. 171A-172A; November, 1960.) A recurrence formula is developed for computing the broadening of the beam.

537.56 3710
Filamentary Structure Produced by an Electric Current in a Plasma—H. Alfvén. (*Ark. Fys.*, vol. 19, pp. 375–378; June 8, 1961.) An electric field parallel to a magnetic field in a plasma at low pressure produces a current which is confined to a filament. Simple formulas are given for the cross-section of the filament and the current in it.

537.56 3711
Space Dispersive Properties of Plasma—J. Neufeld. (*Phys. Rev.*, vol. 123, pp. 1–10; July 1, 1961.)

537.56:537.533 3712
Interaction of Fast Electron Beams with Longitudinal Plasma Waves—Ya. A. Romanov and G. F. Filippov. (*Zh. Eksp. Teor. Fiz.*, vol. 40, pp. 123–132; January, 1961.) Equations are derived for the variation with time of the plasma-wave spectral density and the fast-electron distribution function, for arbitrary velocity distributions.

537.56:538.56 3713
Waves in a Rarefied Ionized Gas Propagated Transverse to an External Magnetic Field—T. Watanabe. (*Canad. J. Phys.*, vol. 39, pp. 1044 1057; July, 1961.) Three modes of plane waves, in which the perturbed magnetic field is parallel to the external magnetic field, can be propagated transverse to the external magnetic field in a collision-free and fully ionized gas. In the HF limit the three modes behave respectively as electromagnetic, electron sound, and ion sound waves.

537.56:538.566:535.43 3714
Concerning the Disturbances Produced by a Body Moving in a Plasma—L. P. Pitaevskiĭ and V. Z. Kresin. (*Zh. Eksp. Teor. Fiz.*, vol. 40, pp. 271–281; January, 1961.) Formulas derived for the disturbance of electron density are used to calculate the effective cross-section for the scattering of electromagnetic waves at this disturbance in particular cases.

537.56:538.6 3715
Electrohydromagnetic Waves in a Fully Ionized Gas: Part 2—K. D. Cole. (*Planet. Space Sci.*, vol. 5, pp. 292–298; August, 1961.) The Appleton-Hartree dispersion formula for magneto ionics is generalized to include the effect of heavy ions. The ratio of particle energy to magnetic field energy in a wave of arbitrary frequency is determined. A band of frequencies around the plasma frequency is found for which waves are attenuated. Location of these bands would enable the interplanetary magnetic field and electron density to be estimated. Part 1: 2305 of 1960.

537.56:538.63 3716
The Statistical Mechanics, Dynamics and Magnetohydrodynamics of Plasmas—R. Jancel and T. Kahan. (*Cah. Phys.*, vol. 15, pp. 57–101; February, 1961.) A system of equations is established in particular to denote the movement, the current and the compression tensor of an ionized gas. These are applied to partially and completely ionized gases and used to obtain the general equations of magnetohydrodynamics. Propagation modes of different types of waves are determined.

537.56:538.63 3717
On Plasma Oscillations with Special Emphasis on the Landau Damping and the Gross Gaps in the Frequency Spectrum—A. Kildal. (*Nuovo Cim.*, vol. 20, pp. 104–122; April 1, 1961. In English.) A linear theory of oscillations of the form $\exp[i(\boldsymbol{k}.\boldsymbol{r}-\omega\, t)]$ in a collision-free electron plasma in an external magnetic field is given.

537.56:538.63 3718
Collective Motions in a Plasma due to Magnetic Interaction—G. Kalman. (*Nuovo Cim.*, vol. 20, pp. 198–200; April 1, 1961.) The existence of collective modes due to the static magnetic interaction between the current elements represented by the moving electrons has been investigated.

537.56:538.63 3719
Plasma Density Fluctuations in a Magnetic Field—E. E. Salpeter. (*Phys. Rev.*, vol. 122, pp. 1663–1674; June 15, 1961.) A continuation of earlier work (*ibid.*, vol. 120, pp. 1528–1535; December 1, 1960) in which the frequency spectrum was derived for the spatial Fourier transform of the electron charge density fluctuations in a plasma. The effects of a constant magnetic field in an arbitrary direction are considered. A theoretical basis is provided for analyzing back-scatter experiments, and intensities are derived as a function of the real frequency variable for the case of thermodynamic equilibrium.

538.311:621.318.3 3720
Hydromagnet: a Self-Generating Liquid-Conductor Electromagnet—H. H. Kolm and O. K. Mawardi. (*J. Appl. Phys.*, vol. 32, pp. 1296–1304; July, 1961.) The exciting current is generated by forcing a liquid conductor radially inwards across an axial magnetic field. The tangential current thus generated adds to the initial applied field.

538.561:537.122 3721
Emergence into Vacuum of the Cherenkov Radiation produced by Longitudinal Waves in a Medium—B. L. Zhelnov. (*Zh. Eksp. Teor. Fiz.*, vol. 40 pp. 170–177; January 1961.) The EM radiation of an electron moving into a vacuum from a medium with spatial dispersion is considered. Under certain conditions, in addition to the transition radiation there is Cherenkov radiation from longitudinal waves in the medium. At large distances from the interface this radiation is a spherical wave confined to a narrow range of frequencies near the plasma frequency.

538.561.029.65:537.533 3722
Coherent Generation of Microwave Power by Annihilation Radiation of a Prebunched Beam—B. W. Hakki and H. J. Krumme. (PROC. IRE, vol. 49, p. 1334; August, 1961.) Millimeter-wave radiation at the 100 mw level has been produced by the creation and annihilation of a tightly bunched 0.8 Mev electron beam. A proposed extension of the method, based on optical techniques, is intended to produce power in the submillimeter region.

538.566:535.42 3723
The Problem of Diffraction of Electromagnetic Waves as a Perfectly Conducting Plane Ring—G. A. Grinberg and É. N. Kolesnikova. (*Zh. Tekh. Fiz.*, vol. 31, pp. 13–17; January, 1961.) Theoretical treatment of the diffraction of plane electromagnetic waves assuming a ring of internal radius and width much greater than the wavelength. Integral equations for the "shadow" currents are given, from which the total current flowing in the screen is determined.

538.566:535.42 3724
Diffraction of a Plane Wave by a Unidirectionally Conducting Half-Plane—S. R. Seshadri. [*Proc. Nat. Inst. Sci.* (*India*) *Part A*, vol. 27, pp. 1–10; January 26, 1961.] The problem is formulated in terms of an integral equation specifying the screen function, whose solution is obtained by the standard Wiener-Hopf procedure. Expressions for the fields and the current induced on the half-plane are given.

538.566:535.42 3725
A Note on the Diffraction of a Scalar Wave by a Small Circular Aperture—R. A. Hurd. (*Canad. J. Phys.*, vol. 39, pp. 1065–1070; July, 1961.)

538.566:537.56 3726
Kinetic Theory of Reflection of Electromagnetic Waves from a Moving Plasma—V. I. Kurilko. (*Zh. Tekh. Fiz.*, vol. 31, pp. 71–77; January, 1961.) Mathematical analysis of the reflection of electromagnetic waves from a plasma moving in a space in which the phase velocity of the waves is less than the velocity of light.

538.566.029.6:535.43:537.56 3727
Scattering of Microwaves from a Cylindrical Plasma in the Born Approximation: Part 1—Y. Midzuno. (*J. Phys. Soc. Japan*, vol. 16, pp. 971–980; May, 1961.) Formulas are derived for the angular distribution function and the effect of special distributions is considered.

538.569.4 3728
Some Properties of Resonance Line-Shape Functions—D. G. Hughes and D. K. C. MacDonald. [*Proc. Phys. Soc.* (*London*), vol. 78, pp. 75–80; July 1, 1961.] Mathematical discussion of the broadening of spectral lines.

538.569.4:537.228.5 3729
Shift of Nuclear Quadrupole Resonance Frequency by Electric Field—T. Kushida and K. Saiki. (*Phys. Rev. Lett.*, vol. 7, pp. 9–10; July 1, 1961.) A linear shift in the Br^{81} line in $NaBrO_3$ is observed when a field of several kv/cm is applied parallel to the (111) crystal axis. The line shape becomes asymmetric, and is attributed to unresolved line splitting.

538.569.4:537.228.5 3730
Linear Effect of Applied Electric Field on Nuclear Quadruple Resonance—J. Armstrong, N. Bloembergen, and D. Gill. (*Phys. Rev. Lett.*, vol. 7, pp. 11–14; July 1, 1961.) A linear Stark effect is observed in the Cl^{35} line in $KClO_3$ and $NaClO_3$ crystalline powders, as predicted theoretically.

538.569.4:537.29 3731
Linear Effect of Applied Electric Field on Magnetic Hyperfine Interaction—N. Bloembergen. (*Phys. Rev. Lett.*, vol. 7, pp. 90–92; August 1, 1961.)

538.569.4:621.375.9 3732
Angular Variation of Axial Spin-Hamiltonian Eigenvalues in Strong Magnetic Field—H. A. Buckmaster. (*Canad. J. Phys.*, vol. 39, pp. 1073–1079; July, 1961.) The expressions for the energies of transitions between levels with strong field quantum numbers M and $M-m$ are given for $m=1, 2, 3$. The tables give the values of the coefficients containing S and M for a range of values of these parameters.

538.569.4:621.375.9:535.61-1/2 3733
A Proposal for a Tunable Source of Radiation for the Far Infrared using Beats between Optical Masers—D. C. Lainé. (*Nature*, vol. 191, pp. 795–796; August 19, 1961.)

538.569.4:621.375.9:535.61-2 3734
Theory of Quantum Oscillators in a Multimode Cavity—W. G. Wagner and G. Birnbaum. (*J. Appl. Phys.*, vol. 32, pp. 1185–1194; July, 1961.) The distribution of power in the various modes in the steady-state operation of an optical maser is studied.

538.569.4:621.375.9:535.61-2 3735
Proposed Technique for Modulation of Coherent Light—A. K. Kamal and S. D. Sims. (PROC. IRE, vol. 49, p. 1331; August, 1961.) A frequency shift of the coherent-light output proportional to the strength of an electric field applied to a ruby laser provides a system for FM of the output.

GEOPHYSICAL AND EXTRATERRESTRIAL PHENOMENA

523.164 3736
Studies in Cosmic Radio Noise at Bangalore—S. Bhagavantum, M. Krishnamurthi and S. Ramakrishna. (*J. Indian Inst. Sci.*, vol. 43, pp. 97–103; April, 1961. The techniques in use at Bangalore for a radio survey of the sky and the disturbed sun at 28.6 Mc and 62 Mc are described.

523.164.3:551.507.362.2 3737
Interpretation of Cosmic-Noise Measurements at 3.8 Mc/s from Satellite 1960 η1—J. H. Chapman and A. R. Molozzi. (*Nature*, vol. 191, p. 480; July 29, 1961.) The analysis given is based on the assumption that observed variations in signal strength were due to three causes: 1) variation of radiation resistance of the antenna with the dielectric constant of the surrounding ionosphere, 2) restriction of the angular aperture at the antenna due to ionospheric refraction and polarization, and 3) variation of cosmic-noise power over the sky.

523.164.32:551.510.535 3738
Oscillations in the Refraction of Radio Waves Emitted by the Sun—B. M. Chikhachev. (*Radiotekh. Elektron.*, vol. 5, pp. 1359–1369; September, 1960.) Radio astronomy observations at sunrise in November and December, 1949, at wavelengths of 1.5 and 2 m showed a periodic variation of ionospheric refraction with uniform change of zenith distance of the sun. This variation is analyzed in terms of sunspot activity and the motion of "cellular" waves in the ionosphere [see 1680 of 1950 (Martyn)].

523.164.34 3739
Lunar Temperature Measurements at 3200 Mc/s—W. J. Medd and N. W. Broten. (*Planet. Space Sci.*, vol. 5, pp. 307–313; August, 1961.)

523.164.4 3740
Distribution of Brightness in Extragalactic Radio Sources—A. T. Moffet and P. Maltby. (*Nature*, vol. 191, pp. 453–454; July 29, 1961.) Measurements have been made at 31.3 cm λ both on N-S and E-W base lines with a resolution of about 1.5′. Interpretations are given of the asymmetry observed in 88 sources.

523.164.4 3741
The Radio Source Hercules *A*—P. J. S. Williams, D. W. Dewhirst, and P. R. R. Leslie. (*Observatory*, vol. 81, pp. 64–68 plate; April, 1961.) Interferometer observations were made at 178 Mc on the two components of the intense source. The separation in declination is $0'.32 \pm 0'.60$.

523.164.4 3742
Central Component of the Radio Source Centaurus *A*—P. Maltby. (*Nature*, vol. 191, pp. 793–794; August 19, 1961.) Observations made with a variable-spacing interferometer at 21.6 and 31.3 cm show that the radiation originates outside the wide dust band.

523.165 3743
Flux and Energy Spectra of the Protons in the Inner Van Allen Belt—J. E. Naugle and D. A. Kniffen. (*Phys. Rev. Lett.*, vol. 7, pp. 3–6; July 1, 1961.)

523.165 3744
Energy Spectrum of Electrons Trapped in the Geomagnetic Field—M. Walt and W. M. MacDonald. (*J. Geophys. Res.*, vol. 66, pp. 2047–2052; July, 1961.) Solutions of the Fokker-Planck equation for the electron distribution function are obtained by reducing the equation to an eigenvalue problem. The spectrum obtained with a source of decaying albedo neutrons is at variance with the observed result.

523.165:551.507.362.2 3745
Characteristics of the Van Allen Radiation Zones as Measured by the Scintillation Counter on Explorer VI—A. Rosen and T. A. Farley. (*J. Geophys. Res.*, vol. 66, pp. 2013–2028; July, 1961.) Results were obtained over a period of four weeks from a counter recording fluxes of electrons above 200 kev and protons above 2 Mev. A geomagnetic storm which occurred about a week after launching the satellite produced an immediate increase in the counting rate; large fluctuations in particle intensity were observed at the edge of the outer Vay Allen belt during the storm, which were closely related to simultaneous geomagnetic activity.

523.5 3746
On Meteor Ablation in the Atmosphere—F. Verniani. (*Nuovo Cim.*, vol. 19, pp. 415–442; February, 1961.) Improvements to the usually adopted theory are given and approximate expression suggested for the fundamental equation of ablation of low-velocity meteors.

523.5:621.396.96 3747
Reduction of Meteor Velocities from Continuous-Wave Radio Records—D. W. R. McKinley and E. L. R. Webb. (*Monthly*

Notices Roy. Astron. Soc., vol. 122, no. 3, pp. 255–262; 1961.) An analysis of the reduction technique used at Ottawa shows that in velocity measurements any statistical bias was positive and less than 1 per cent.

550.385.37 3748
Some Studies of Geomagnetic Micropulsations—R. A. Duncan. (*J. Geophys. Res.*, vol. 66, pp. 2087–2094; July, 1961.) Recordings made at four stations in Australia are analyzed. The period of the continuous type of oscillation (*Pc*) increases with latitude, and also varies diurnally. The damped trains of oscillations (*Pt*), occurring mainly near midnight, are followed by magnetic bays with an average delay of about 15 minutes. Effects observed during magnetic storms are discussed.

550.385.4 3749
Some Features of Magnetic Storms in High Latitudes—D. G. Knapp. (*J. Geophys. Res.*, vol. 66, pp. 2053–2085; July, 1961.) Ionospheric currents in high latitudes during magnetic disturbances are deduced from magnetic data. Lists of disturbances, during and prior to the I.G.Y., are given.

551.507.362:523.3/.4 3750
The National Program for Lunar and Planetary Exploration—A. R. Hibbs. (*J. Geophys. Res.*, vol. 66, pp. 2003–2012; July, 1961.) An illustrated description of the "Ranger" and other planned spacecraft.

551.507.362:537.56 3751
Excitation of Plasma Waves by Bodies Moving in Ionized Atmosphere—K. P. Chopra. (*Planet. Space Sci.*, 1961, vol. 5, pp. 288–291; August, 1961.) An ionized cloud, formed in front of a rapidly moving body, excites waves by interaction with the ambient plasma. Extraordinary electromagnetic waves are generated in the presence of a suitable week magnetic field.

551.507.362.1:550.380.8 3752
On the Interplanetary Magnetic Storm: Pioneer V—P. J. Coleman, Jr, C. P. Sonett, and L. Davis, Jr. (*J. Geophys. Res.*, vol. 66, pp. 2043–2046; July, 1961.) A magnetic field of 20 to 50 γ was detected by Pioneer V perpendicular to the sun-earth line during periods of intense solar activity between March 26 and April 6, 1960. Quiet-time fields of 2.7 γ were observed on other occasions.

551.507.362.1:550.385.4:523.14 3753
Magnetic Storms in Interplanetary Space as Observed by Pioneer V—E. W. Greenstadt. (*Nature*, vol. 191, pp. 329–331; July 22, 1961.) A positive correlation is found between the interpanetary field measured at the satellite and the planetary magnetic index a_p during the flight of Pioneer V from launch on March 11, 1960 to the end of April. Magnetic storms at the satellite occur at the same time as earth storms although there is a slight delay towards the end of the period of telemetry.

551.507.362.2 3754
Satellite Flashing-Light System—R. Freed and L. S. Klivans. (*Electronic Ind.*, vol. 20, pp. 94–98; April, 1961.) To provide increased accuracy of the determination of the position of a satellite, a coded flashing-light system could be carried. Design details are given.

551.507.362.2 3755
Effect of an Oblate Rotating Atmosphere on the Orientation of a Satellite Orbit—G. E. Cook. [*Proc. Roy. Soc.* (*London*) *A*, vol. 261, pp. 246–258; April 25, 1961.] For inclinations of 60°–70° in particular, significant rotation of the major axis in the orbital plane occurs due to the atmosphere.

551.507.362.2 3756
Atmospheric Phenomena noted in Simultaneous Observations of 1958 δ2 (Sputnik III)—J. Aarons, H. E. Whitney, R. S. Roger, J. Thomson, J. Bournazel, E. Vassy, H. A. Hess, K. Rawer, N. Carrara, P. Checcacci, B. Landmark, J. Troim, B. Hultqvist and L. Liszka. (*Planet. Space Sci.*, vol. 5, pp. 169–184; July, 1961.) Events occurring in three typical revolutions of Sputnik III are described; measurements were made on the 20 Mc transmissions. Signal drop-outs due to transmitter failure were noted and another type of signal decrease was attributed to localized absorbing regions. Regions of the ionosphere causing scintillation were also identified; they have an extent in the horizontal plane of several hundred km.

551.507.362.2 3757
Methods of Calculating Atmospheric Densities from Satellite Orbit Data—G. V. Groves. (*Planet. Space Sci.*, vol. 5, pp. 314–320; August, 1961. In French.) Formulas relating atmospheric density to the rate of change of period of a satellite as obtained by various workers are reviewed, and are shown to be in sufficient agreement to meet practical needs.

551.507.362.2:523.164:621.391.812 3758
Ray Paths from a Cosmic Radio Source to a Satellite in Orbit—C. B. Haselgrove, J. Haselgrove, and R. C. Jennison. [*Proc. Roy. Soc.* (*London*) *A*, vol. 261, pp. 423–434; May 16, 1961.] A satellite above the F_2 maximum can receive radiation on frequencies that are totally reflected by the ionosphere. Two effects of reflection in the upper part of the ionosphere are discussed: 1) focusing, and 2) interference. Both occur particularly when a satellite enters or leaves a region in which it can receive radiation from a point source in space.

551.507.362.2:523.72 3759
Measurement of Solar X-Radiation—K. A. Pounds. (*J. Brit. IRE*, vol. 22, pp. 171–175; August, 1961.) The X-ray emission measuring equipment to be carried in Skylark rockets and the satellite U.K. 1 is described. Both X-ray flux and spectral shape are to be investigated.

551.507.362.2:551.510.535 3760
Local Electron Densities deduced from the Faraday Fading of Satellite Transmissions using Measurements during Two Consecutive Transits—L. Liszka. (*Planet. Space Sci.*, vol. 5, pp. 213–219; July, 1961.) In the analysis it is assumed that during the period of revolution of the satellite the relative gradients of the local electron density are constant at the same altitudes and the changes in density above the F_2 maximum are the same as those within the F_2 layer. Daytime observations of 1958 δ2 in September, 1959, have been analyzed.

551.507.362.2:621.391.812.63 3761
Scintillations and the Latitude Distribution of Ionospheric Irregularities—D. G. Singleton. (*Nature*, vol. 191, pp. 482–483; July 29, 1961.) Evidence is given in support of Kent's interpretation of the rapid fading of earth-satellite signals (488 of 1960). Mawdsley's alternative explanation of scattering by field-aligned irregularities (4215 of 1960) is not confirmed by experiment.

551.507.362.2:621.396.9 3762
Radio Tracking of Artificial Earth Satellites—Pressey. (See 3784.)

551.507.362.2:621.396.963.3 3763
Tracking and Display of Earth Satellites—Van Golder, Jr. (See 3798.)

551.510.53 3764
Charged Particles in the Upper Atmosphere—A. Dalgarno. (*Ann. Géophys.*, vol. 17, pp. 16–49; January–March, 1961. In English.) A comprehensive review of collision processes involving charged particles in the upper atmosphere. 225 references.

551.510.53 3765
Structure, Variations and Measurements of the Earth's Ionosphere and Exosphere—C. Altman. (*Bull. Res. Counc. Israel*, vol. 90, pp. 39–48; February, 1961.) A survey of present knowledge and work being conducted at the Technion, Israel Institute of Technology, Haifa.

551.510.53 3766
The Distribution of Minor Ions in Electrostatic Equilibrium in the High Atmosphere—P. Mange. (*J. Geophys. Res.*, vol. 65, pp. 3833–3834; November, 1960.) A simple discussion of the factors which govern the distribution of ions in diffusive equilibrium. The scale height of the predominant ion is twice that of the corresponding neutral constituent, and the concentration of a minor light ion can increase with altitude.

551.510.53 3767
Comments on Tidal Winds in the High Atmosphere—B. Haurwitz. (*Planet. Space Sci.*, vol. 5, pp. 196–201; July, 1961.) The accuracy of published data on tidal wind variations are discussed on the basis of computations of the indices of the probable-error circle: variations with seasons and elevation are real although their magnitudes may be unreliable.

551.510.535 3768
Diffusion in the Ionosphere: A Review of some Recent Work—V. C. A. Ferraro. (*Ann. Géophys.*, vol. 17, pp. 82 89; January–March, 1961. In English.) Work by Gliddon and Kendall (2738 of 1960) shows considerable support for the hypothesis that F_1 and F_2 regions are produced by the same source of ionization.

551.510.535 3769
The Lunar Variation of the Virtual Height of the Normal Ionospheric E layer above Fribourg—P. Rougerie. (*Ann. Géophys.*, vol. 17, pp. 145–146; January–March, 1961. In English.) A semidiurnal lunar variation of 0.1 km has been detected with a maximum at 0830 lunar time.

551.510.535 3770
Theory of Overhead Nonblanketing Sporadic E—J. Renau. (*J. Geophys. Res.*, vol. 66, pp. 2121–2128; July, 1961.) Sequences of $h'(f)$ curves are calculated for an E layer in which a horizontal stratum of irregularities 1–2 km thick is slowly descending. The results are very similar to recorded sequences of ionograms showing sporadic E.

551.510.535 3771
Observations on the Ionospheric F Layer at Night: Part 2—The Law of Electron Loss in the F layer—C. S. G. K. Setty. (*J. Inst. Telecommun. Engrs., India*, vol. 7, pp. 65–77; March, 1961.) At night, electrons in the F layer are lost by attachment-like processes. The loss coefficients are of the form $K = K_0 \exp [h_0 - h)/H_k]$ where h_0 is the height at which $K_1 = K_0$ and H_k is the scale height of the loss coefficient. Assuming the loss coefficients are attributable to loss rates in chemical processes, H_k values correspond to those of molecular oxygen and nitrogen. Part 1: 3395 of November.

551.510.535 3772
Equatorial Spread-F in Relation to Post-Sunset Height Changes and Magnetic Activity—M. S. V. G. Rao and B. R. Rao. (*J. Geophys. Res.*, vol. 66, pp. 2113–2120; July, 1961.) The seasonal dependence of the correla-

tions is found, and the data are considered in relation to Martyn's theory of the formation of spread F (see 1555 of 1959).

551.510.535:550.385.4 3773
On the Relation between Magnetic Storm and Ionospheric Disturbances that Occurred on Sept. 13th 1957—Y. Hakura, M. Nagai, and Y. Sano. (*J. Radio Res. Labs., Japan*, vol. 8, pp. 81–95; March, 1961.) The patterns of dense E_s, blackouts and F_2-layer disturbance in the northern hemisphere are compared with the current systems of geomagnetic disturbance at different stages of the storm. With the development of polar-cap blackout, several hours before the sudden commencement of the storm, a current system was produced in the polar cap region. During the main phase, blackouts and E_s coincide with strong currents at auroral latitudes.

551.510.535:551.507.362.1 3774
Upper Atmospheric Turbulence near the 100 km Level—J. E. Blamont and C. de Jager. (*Ann. Géophys.*, vol. 17, pp. 134–144; January–March, 1961. In English.) An examination of observations of a sodium trail produced by a Véronique rocket in the upper atmosphere.

551.510.536 3775
Hydrogen Atoms and Ions in the Thermosphere and Exosphere—D. R. Bates and T. N. L. Patterson. (*Planet. Space Sci.*, vol. 5, pp. 257–273; August, 1961.) The structure of the atmosphere between 100 km and 500 km is discussed in terms of various models. For a further note on the temperature in the exosphere see *ibid.*, p. 328.

551.510.536:551.507.362.2 3776
Variable Conditions of the Terrestrial Exosphere—H. K. Paetzold and H. Zschörner. (*Astronautica Acta*, vol. 6, no. 6, pp. 373–381; 1960.) The well-known features of atmospheric density variations as deduced from satellite observations are discussed. Data for at least ten satellites show evidence of an annual variation in atmospheric density with a minimum in July, the amplitude of the variation increasing with altitude.

551.510.536:551.594.6 3777
Exospheric Electron Density Variations deduced from Whistlers—R. A. Helliwell. (*Ann. Géophys.*, vol. 17, pp. 76–81; January–March, 1961. In English.) New data on electron density are presented. Density is approximately proportional to the strength of the earth's magnetic field. An unexplained annual variation, in which the December value is nearly twice that in June, is reported.

551.593 3778
Altitudes of the Night Airglow Radiations—D. M. Packer. (*Ann. Géophys.*, vol. 17, pp. 67–75; January–March, 1961. In English.) Observational methods for obtaining the layer heights of air-glow emission are briefly reviewed and results derived from ground measurements, rocket flights and kinetic temperatures are discussed.

551.593.551.507.362.1 3779
Attempt to Measure Night Helium Glow—Evidence for Metastable Molecules in the Night Ionosphere—E. T. Byram, T. Å. Chubb, and H. Friedman. (*J. Geophys. Res.*, vol. 66, pp. 2095–2100; July, 1961.) A rocket experiment, intended to measure the intensity of night-time He glow (wavelengths 584 Å and 304 Å) gave negative results, but provided some evidence for the existence of metastable molecules above 100 km.

551.594.5 3780
Some Auroral Observations inside the Southern Auroral Zone—J. V. Denholm. (*J. Geophys. Res.*, vol. 66, pp. 2105–2111; July, 1961.)

551.594.6 3781
Guiding of Whistlers by the Magnetic Field—R. Gendrin. (*Planet. Space Sci.*, vol. 5, pp. 274–282; August, 1961. In French.) A mechanism is proposed which explains the wideband noise observed during whistler reception. A particle moving with velocity $cf_H/2f_0$, where f_H is gyrofrequency and f_0 is plasma frequency, causes a wave to be propagated along the earth's magnetic field; all frequency components of the wave travel with the same velocity. See 201 of February (Smith).

551.594.6 3782
The Dispersion of Whistlers Compared with the Geomagnetic Latitudes of their Sources—H. Norinder and E. Knudsen. (*Planet. Space Sci.*, vol. 5, pp. 326–328; August, 1961. In French.) Observational results are presented which indicate that the geomagnetic latitude of lightning discharges is a factor determining the dispersion constant of the related whistlers.

LOCATION AND AIDS TO NAVIGATION

621.396.9 3783
Development Trends of Modern Location Techniques: Correlation Location Methods—F. H. Lange. (*Nachrtech.*, vol. 11, pp. 2–7; January, 1961.) The application of the principles of "correlation electronics" (3630 of 1958) to radiolocation systems is discussed.

621.396.9:551.507.362.2 3784
Radio Tracking of Artificial Earth Satellites—B. G. Pressey. (*J. Brit. IRE*, vol. 22, pp. 97–107; August, 1961.) The three principal methods using 1) radar, 2) Doppler frequency shift, and 3) interferometer are outlined. The construction, operation and performance of the interferometer system used in the U. S. Minitrack network are described.

621.396.933.2 3785
Controlled (h/d) Flight Path System for Use during Climb and Descent—R. D. Ryan. (*J. Inst. Nav.*, vol. 14, pp. 195–201; April, 1961.) Any of a number of accurate straight or curved flight paths may be selected in an attachment for the Australian DME system.

621.396.933.2 3786
Phase Difference Observations at Spaced Aerials and their Application to Direction Finding—W. C. Bain. (*J. Res. NBS*, vol. 65D, pp. 229–232; May/June, 1961.) Measurements on frequencies near 6 Mc are shown to give results indicating that the performance of a wide-aperture direction finder should not fall seriously below theoretical expectation.

621.396.933.2 3787
Research at the National Bureau of Standards applicable to Long-Distance Location and Direclon- Finding Problems—R. Silberstein. (*J. Res. NBS*, vol. 65D, pp. 233–235; May/June, 1961.) A general account of work undertaken since 1941 including references to the development of a technique for determining polarization error, the development of Loran-C, a rapid-scan directional aerial, and the study of non-great-circle bearings.

621.396.933.2 3788
Instrumentation for Propagation and Direction-Finding Measurements—E. C. Hayden. (*J. Res. NBS*, vol. 65D, p. 253; May/June, 1961.) Summary of a conference paper in which the limitations imposed on radio DF systems are discussed and two specific systems for use with wide-aperture arrays are proposed.

621.396.933.2 3789
Brooke Variance Classification System for D.F. Bearings—E. M. L. Beale. (*J. Res. NBS*, vol. 65D, pp. 255–261; May/June, 1961.)

621.396.933.2 3790
Estimation of Variances of Position Lines from Fixes with Unknown Target Positions—E. M. L. Beale. (*J. Res. NBS*, vol. 65D, pp. 263–273; May/June, 1961.) See also 3789 above.

621.396.933.2:621.391.812.63 3791
Influence of Ionospheric Conditions on the Accuracy of High-Frequency Direction Finding—P. J. D. Gething. (*J. Res. NBS*, vol. 65D, pp. 225–228; May/June, 1961.) During ionospheric storms bearing accuracy is reduced when fixes result from signals propagated via the F_2 layer.

621.396.933.2:621.396.663 3792
Design for Spinning-Goniometer Automatic Direction Finding—W. J. Lindsay and D. S. Heim. (*J. Res. NBS*, vol. 65D, pp. 237–243; May/June, 1961.) The construction of an automatic sensing unit and of a bearing read-out computer is considered. The advantages of narrow-band synchronous post-detection filtering are discussed.

621.396.96 3793
Secondary Surveillance Radar—D. H. R. Archer. (*Electronic Engr.*, vol. 33, pp. 414–420 and 490–494; July and August, 1961.) System design problems are discussed, in particular methods of suppressing sidelobe effects. The application of a secondary-radar system for data transmission is considered.

621.396.962.3 3794
Superregenerative Pulse Radar—F. H. Shepard, Jr. (*Proc. Radio Club Amer.*, vol. 37, Winter, 1960/1961.) For pulse reception, where broad bandwidths are used, the SNR is equal to that of other receiving systems. The basic circuit of a superregenerative radar transmitter-receiver is shown and a double-pulse technique for an A-scope display is outlined.

621.396.962.3 3795
A Monopulse Instrumentation System—F. P. Storke, Jr. (PROC. IRE, vol. 49, pp. 1328–1329; August, 1961.) The tracking error relative to the beam width is expressed in terms of the differential phase shifts before and after the comparing hybrid. The importance of the latter is shown and a system is described which is insensitive to phase shifts in the IF amplifier since reference and error signals undergo the same phase shift in it. See 1240 of 1960 (Rhodes).

621.396.962.33 3796
Detection Range Predictions for Pulse Doppler Radar—S. A. Meltzer and S. Thaler. (PROC. IRE, vol. 49, pp. 1299–1307; August, 1961.) A mathematical model is constructed. It is applicable to situations where thermal noise and sidelobe clutter limit detection range, and allows for variation of most of the important radar parameters.

621.396.963.3 3797
C.R.T. Display of Alphanumeric Information Applied to Radar Data Handling—J. S. Johnston. (*J. Brit. IRE*, vol. 22, pp. 139–143; August, 1961.) The problem of extracting and displaying in alpha-numeric form the information presented by long-range radar is discussed. A writing speed of 3×10^4 characters/sec is possible.

621.396.963.3:551.507.362.2 3798
Tracking and Display of Earth Satellites—A. Van Gelder, Jr. (PROC. IRE, vol. 49, pp.

1332–1333; August, 1961.) Comment on 2393 of 1960 (Slack and Sandberg). Several errors are corrected and certain steps in the derivation are questioned.

621.396.969.3:551.507.362.2 3799
Project Echo: Satellite-Tracking Radar—O. E. De Lange. (*Bell. Syst. Tech. J.*, vol. 40, pp. 1157–1182; July, 1961.) A 961-Mc system with 60-ft and 18-ft paraboloids as transmitting and receiving antennas respectively is described. The transmitting system is shared with the "Echo" communications channel, 2.5 kw being then available for radar. The 18-ft paraboloid is conically scanned and feeds a receiver incorporating a parametric amplifier with a sensitivity of −150 dbm in a 100-cps bandwidth. Radar and optical pointing were found usually to agree to within a few tenths of a degree, but computed orbital azimuth data were in error by up to 1.2°.

MATERIALS AND SUBSIDIARY TECHNIQUES

535.215 3800
Temperature-Dependent Bismuth-Cesium Photosurfaces—R. J. Zollweg and C. R. Taylor. (*J. Appl. Phys.*, vol. 32, pp. 1316–1319; July, 1961.) The sensitivity variation with temperature depends on the presence of oxygen and upon the size of the aggregates in the photosurface.

535.215:546.48'221 3801
Photosensitivity and Speed of Response in Cadmium Sulphide—D. Shaw. (*Brit. J. Appl. Phys.*, vol. 12, pp. 337–341; July, 1961.) Photoconductivity and photocurrent decay times have been measured for a large number of crystals of widely varying photosensitivity over an illumination range 0.007–875 ft candles.

535.215:546.48'221 3802
***p*-Type Photoconductivity and Infrared Quenching in Electron-Bombarded CdS**—B. A. Kulp and R. H. Kelley. (*J. Appl. Phys.*, vol. 32, pp. 1290–1292; July, 1961.)

535.215:546.48'221 3803
Analysis of Photojunctions Formed by Diffusing Copper into Insulating Cadmium Sulphide Crystals—R. R. Bockemuehl, J. E. Kauppila, and D. S. Eddy. (*J. Appl. Phys.*, vol. 32, pp. 1324–1330; July, 1961.)

535.37 3804
Lead- and Manganese-Activated Calcium Cadmium Silicate Phosphors—Y. Uehara, Y. Kobuke, I. Masuda, and T. Kushida. (*J. Electrochem. Soc.*, vol. 108, pp. 235–238; March, 1961.)

535.376:546.681'18 3805
Electroluminescence at *p-n* Junctions in Gallium Phosphide—M. Gershenzon and R. M. Mikulyak. (*J. Appl. Phys.*, vol. 32, pp. 1338–1348; July, 1961.)

537.226:538.566.2.029.6 3806
Dispersion of the Permeability and Permittivity of Artificial Dielectrics in the Frequency Range 500–35000 Mc/s I. A. Deryugin and M. A. Sigal. (*Zh. Tekh. Fiz.*, vol. 31, pp. 100–108; January, 1961.) A report of measurements of the frequency dependence of the properties of Cu powders in paraffin.

537.226:546.814–31 3807
Dielectric Properties of SnO_2—L. V. Deshpande and V. G. Bhide. (*Nuovo Cim.*, vol. 19, pp. 816–817; February 16, 1961.) Samples of SnO_2 in ceramic and compressed powder form have a dielectric constant of the order of 10^5 and show ferroelectric properties.

537.227:546.42'824–31 3808
Nonlinearity and Microwave Losses in Cubic Strontium-Titanate—G. Rupprecht, R. O. Bell, and B. D. Silverman. (*Phys. Rev.*, vol. 123, pp. 97–98; July, 1961.) A summary and interpretation of results of measurements made on single crystals, at temperatures from 90°K to 230°K and frequencies from 1 to 36 Gc.

537.227:546.431'824–31 3809
Perfectness of Macrodomains of $BaTiO_3$ Crystals—K. Aizu and O. Nakada. (*J. Phys. Soc. Japan*, vol. 16, pp. 923–927; May, 1961.) A statistical investigation based on thermodynamics shows that a plate thicker than 2×10^{-6} cm contains practically no reversely polarized microdomains.

537.227:546.431'824–31 3810
Surface Layers on Barium Titanate Single Crystals above the Curie Point—H. Schlosser and M. E. Drougard. (*J. Appl. Phys.*, vol. 32, pp. 1227–1231; July, 1961.) Dielectric dispersion measurements have been carried out on $BaTiO_3$ single crystals of different thickness at temperatures above the Curie point up to 180°C.

537.227:546.431'824–31 3811
Investigation of Rare-Earth-Doped Barium Titanate—V. J. Tennery and R. L. Cook. (*J. Amer. Ceram. Soc.*, vol. 44, pp. 187–193; April 1, 1961.) The effect of additions of rare-earth oxides on the dc resistivity of $BaTiO_3$ is investigated.

537.227:546.431'824–31 3812
Effect of WO_3 on Dielectric Properties of $BaTiO_3$ Ceramics—V. Ern and R. E. Newnham. (*J. Amer. Ceram. Soc.*, vol. 44, p. 199; April 1, 1961.)

537.227:546.431'824–31 3813
Dielectric Properties of $BaTiO_3$ Single Crystals in the Paraelectric State from 1 kc/s to 2000 Mc/s—E. Stern and M. Lurio. (*Phys. Rev.*, vol. 123, pp. 117–123; July 1, 1961.)

537.227:621.372.44 3814
Antiferroelectric Ceramics with Field-Enforced Transitions: a New Nonlinear Circuit Element—B. Jaffe. (PROC. IRE, vol. 49, pp. 1264–1267; August, 1961.) Ceramic dielectrics have been prepared which undergo field-enforced antiferroelectric-to-ferroelectric transitions from below −60°C to over 100°C. The transition is indicated by a D/E hysteresis figure with a linear central region and loops showing saturation on either end. Capacitance nonlinearity, energy storage and transducer properties are described.

537.228.1/.2:547.476.3 3815
The Piezoelectricity and Electrostriction of Rochelle Salt—G. Schmidt. (*Z. Phys.*, vol. 161, pp. 579–603; February 14, 1961.) Detailed report of measurements and discussion of results with particular reference to the ferroelectric anomaly of Rochelle salt.

537.228.1:549.514.41 3816
Piezoelectricity of Quartz for Finite Strain—S. Machlup and M. E. Christopher. (*J. Appl. Phys.*, vol. 32, pp. 1387–1391; July, 1961.) Calculation of the principal piezoelectric coefficient using a hard-sphere, rigid-ion model.

537.311.33 3817
Behaviour of Hot Electrons in Microwave Fields—B. V. Paranjape. (*Phys. Rev.*, vol. 122, pp. 1372–1375; June 1, 1961.) A theoretical investigation is made of the currents produced by hot electrons when a weak microwave field is superimposed on a strong steady electric field, and also the effect of a strong microwave field alone. An alternating current at the same frequency as the applied field and leading it in phase is produced.

537.311.33 3818
Electron-Electron Scattering and Transport Phenomena in Nonpolar Semiconductors—J. Appel. (*Phys. Rev.*, vol. 122, pp. 1760–1772; June 15, 1961.) Electron-electron scattering causes electrical conductivity to be reduced less than the electronic heat conductivity. Its influence on electrical conductivity, heat conductivity and the Seebeck coefficient is calculated as a function of temperature, and its effect on transport phenomena is briefly considered.

537.311.33 3819
Alternative Approach to the Solution of Added Carrier Transport Problems in Semiconductors—J. P. McKelvey, R. L. Longini, and T. P. Brody. (*Phys. Rev.*, vol. 123, pp. 51–57; July 1, 1961.) A method is described for computing carrier fluxes by solving the continuity equation in terms of a Green's function.

537.311.33 3820
Mechanism of Impurity Conduction in Semiconductors—J. Mycielski. (*Phys. Rev.*, vol. 123, pp. 99–103; July 1, 1961.) The conductivity of impurities at low temperatures is discussed in terms of jumps over the Coulomb potential barrier between empty and occupied impurity centres. Calculations relating to anomalies of activation energy are made.

537.311.33 3821
Current-Carrier Transport with Space Charge in Semiconductors—W. Van Roosbroeck. (*Phys. Rev.*, vol. 123, pp. 474–490; July 15, 1961.) A theory is developed for one-dimensional drift of carriers, taking into account the space charge which can develop in high-resistance materials. The theory is exact for small-signal field variations.

537.311.33 3822
The Scattering of Phonons by Bound Electrons in a Semiconductor—I. C. Pyle. (*Phil. Mag.*, vol. 6, pp. 609–616; May, 1961.)

537.311.33:534.28 3823
Interaction of Electrons and Holes with Acoustic Waves in Intrinsic Semiconductors—N. Mikoshiba. (*J. Phys. Soc. Japan*, vol. 16, pp. 895–905; May, 1961.) A self-consistent theory is produced which shows that the acoustoelectromotive force is too small to be detected by experiment.

537.311.33:535.215 3824
On the Study of Volume Recombination of Excess Charge Carriers in Semiconductors with the Aid of Photoconductance—B. H. Schultz. (*Philips Res. Rep.*, vol. 16, pp. 175–181; April, 1961.) By measuring amplitude and phase of photoconductance in different ambients, it is possible in some cases to determine the surface effects, and reliable volume-recombination times can be deduced.

537.311.33:535.34–15 3825
Contribution of Lattice Scattering between Nonequivalent Valleys to Free-Carrier Infrared Absorption in Semiconductors—H. Risken and H. J. G. Meyer. (*Phys. Rev.*, vol. 123, pp. 416–419; July 15, 1961.)

537.311.33:538.614 3826
The Faraday Effect in Nondegenerate Semiconductors—B. Donovan and J. Webster. [*Proc. Phys. Soc.* (*London*), vol. 78, pp. 120–132; July 1, 1961.] The theory of the Faraday effect, in relation to microwave and infrared propagation in semiconductors is developed. Frequency and temperature dependence are investigated for *n*-type Ge.

537.311.33:538.63 3827
The Theory of Electrical Conductivity of Semiconductors in a Magnetic Field: Part 1—V. L. Gurevich and Yu. A. Firsov. (*Zh. Eksp. Teor. Fiz.*, vol. 40, pp. 199–213; January, 1961.) A quantum theory of the transverse conductivity of semiconductors in a strong magnetic field is developed, taking account of inelastic scattering of electrons.

537.311.33:538.63 3828
Galvanomagnetic Effects in Semiconductors at High Electric Fields—E. M. Conwell. (*Phys. Rev.*, vol. 123, pp. 454–463; July 15, 1961.) A theory of magnetoconductivity for general energy-band structure is evolved in a form convenient for the calculation of Hall coefficients and other galvanomagnetic effects for either low or high electric field strengths.

537.311.33:538.63 3829
Measurements of the Frequency Dependence of the Gauss Effect in Various Semiconductors up to 2000 Mc/s—M. J. O. Strutt and F. K. von Willisen. (*Arch. elekt. Übertragung*, vol. 15, pp. 25–32; January, 1961.) The Gauss effect in Corbino disks of Ge, InSb and InAs was measured in the frequency range 0–2 Gc as a function of temperature in the range 140°–270°K for flux densities up to 30 Mc. For earlier measurements of this galvanomagnetic effect see 2804 of 1957 (Ramer *et al.*).

537.311.33:539.23 3830
Field-Enhanced Donor Diffusion in Degenerate Semiconductor Layers—W. Shockley. (*J. Appl. Phys.*, vol. 32, pp. 1402–1403; July, 1961.) An expression for the effective diffusion constant is given.

537.311.33:[546.28+546.289]:535.215 3831
Photovoltages in Silicon and Germanium Layers—H. Kallmann, B. Kramer, E. Haidemanakis, W. J. McAleer, H. Barkemeyer, and P. I. Pollak. (*J. Electrochem. Soc.*, vol. 108, pp. 247–251; March, 1961.) Photovoltages of several thousand volts are observed between electrodes 1 cm apart when the layers are maintained at liquid-nitrogen temperatures and strongly illuminated. At room temperature, only a few hundred volts were produced. A possible explanation of this effect is suggested.

537.311.33:[546.28+546.289]:621.317.3(083.7) 3832
IRE Standards on Solid State Devices: Measurement of Minority-Carrier Lifetime in Germanium and Silicon by the Method of Photoconductive Decay—(PROC. IRE, vol. 49, pp. 1292–1299; August, 1961.) Standard 61 IRE 28.S2.

537.311.33:546.28 3833
The Formation of Dislocation-Free Silicon Single Crystals—G. Ziegler. (*Z. Naturforsch.*, vol. 16a, p. 219; February, 1961.) The configuration of dislocations in thin Si rods is investigated to obtain insight into the mechanism of dislocation reduction.

537.311.33:546.28 3834
Low-Frequency Conductivity due to Hopping Processes in Silicon—M. Pollak and T. H. Geballe. (*Phys. Rev.*, vol. 122, pp. 1742–1753; June 15, 1961.) The complex conductivity has been measured in n-type Si with various kinds of impurities at frequencies between 100 cps and 10 kc in the temperature range 1–20° K. In most cases it is several orders of magnitude higher than the measured dc conductivity; this is attributed to polarization caused by hopping processes. A simple theory is derived which is in good agreement with the observed variation of conductivity with frequency and concentration.

537.311.33:546.28 3835
Hot-Electron Emission from Silicon p-n Junctions Parallel to the Surface—J. L. Moll, N. I. Meyer, and D. J. Bartelink. (*Phys. Rev. Lett.*, vol. 7, pp. 87–90; August 1, 1961.) Experimental results are presented and compared with theoretical expressions which take into account the important types of interaction between the hot electrons and the crystal lattice.

537.311.33:546.28 3836
Forward Characteristics of Si p-π-n-Junctions—M. Tokunaga and K. Shono. (*J. Phys. Soc. Japan*, vol. 16, pp. 1029–1030; May, 1961.) A series of junctions were prepared in p-type Si crystals of resistivity 2–5 Ωcm, by diffusing B from one side and P from the other side of the crystal. I/V characteristics of junctions with π-regions of different width are shown and discussed.

537.311.33:546.289 3837
Electronic Effect in the Elastic Constants of Germanium—L. J. Bruner and R. W. Keyes. (*Phys. Rev. Lett.*, vol. 7, pp. 55–56; July 15, 1961.) A measured change in one of the elastic constants (C_{44}) of Ge when heavily doped with As is reported.

537.311.33:546.289 3838
Electric-Field-Induced Modulation of the Absorption due to Interband Transitions of Free Holes in Germanium—M. A. C. S. Brown and E. G. S. Paige. (*Phys. Rev. Lett.*, vol. 7, pp. 84–86; August 1, 1961.) Observations were made of the change in absorption due to a change in the distribution function of the free holes. Experimental data are given and discussed.

537.311.33:546.289 3839
Anodic Oxidation of Germanium—T. Gabor. (*J. Appl. Phys.*, vol. 32, pp. 1361–1363; July, 1961.) "On anodic polarization of etched samples of n-type or near-intrinsic p-type germanium, striations are formed. The periodic depletion of holes is advanced as a tentative explanation of the phenomenon."

537.311.33:546.289 3840
A Study of Growth Processes in Germanium Dendrites using Pulse Electroplating Techniques—R. C. Smith. (*J. Electrochem. Soc.*, vol. 108, pp. 238–241; March, 1961.) Separate mechanisms for axial and lateral growth have been identified. The observed resistivity boundary lines are due to the lateral growth mechanism.

537.311.33:546.289 3841
Influence of Wet and Dry Ambients on Fast Surface States of Germanium—Y. Margoninski and H. E. Farnsworth. (*Phys. Rev.*, vol. 123, pp. 135–140; July 1, 1961.) A specimen of n-type Ge was subjected to different gaseous environments. The effects of N_2, O_2 and water vapor on the surface states can be discussed separately.

537.311.33:546.289 3842
Determination of the Coefficient of Diffusion of Arsenic in Germanium by Measurement of the Thermoelectric Voltage—E. Batifol and G. Duraffourg. (*J. Phys. Radium*, vol. 21, Suppl., *Phys. Appl.*, pp. 207A–216A; November, 1960.) The surface concentration of As is obtained by measurement of 1) thermoelectric power, 2) sheet resistance. The mean value of the diffusion coefficient at 800° C is 1.3×10^{-11} cm²/sec.

537.311.33:546.289 3843
Recombination at Copper and at Nickel Centres in p-Type Germanium—B. H. Schultz. (*Philips Res. Repts.*, vol. 16, pp. 182–186; April, 1961.) An explanation is given for the different temperature dependence of recombination rates at Cu centers for partly compensated and noncompensated crystals. No solution could be found for the discrepancies which occur with Ni.

537.311.33:546.289 3844
Effect of Temperature and Doping on the Reflectivity of Germanium in the Fundamental Absorption Region—M. Cardona and H. S. Sommers, Jr. (*Phys. Rev.*, vol. 122, pp. 1382–1388; June, 1961.)

537.311.33:546.289:538.63 3845
Longitudinal Magnetoresistance in n-Type Germanium: Experimental—W. F. Love and W. F. Wei. (*Phys. Rev.*, vol. 123, pp. 67–73; July 1, 1961.) Curves showing the variation of the magnetoresistance ratio with magnetic field and temperature, in fields up to 300 kg and temperature from 20°K to 300°K, are presented and discussed.

537.311.33:546.289:538.63 3846
Longitudinal Magnetoresistance in n-Type Germanium: Theoretical—S. C. Miller and M. A. Omar. (*Phys. Rev.*, vol. 123, pp. 74–80; July 1, 1961.) Calculations of acoustic scattering give satisfactory agreement with the experimental results at high field strengths (3845 above).

537.311.33:546.289:621.391.822 3847
Slow Decay of Reverse Current and Noise in Field Effect on Ge p†-n Junction—H. Edagawa, Y. Morita, S. Maekawa, and Y. Inuishi. (*J. Phys. Soc. Japan*, vol. 16, pp. 1041–1042; May, 1961.) Current and noise measurements were made simultaneously at the junctions; results are presented in graphical form.

537.311.33:546.289:621.391.822 3848
Recombination Noise of Germanium Single Crystals in the Range of Defect Semiconduction—M. Pilkuhn. (*Z. Naturforsch.*, vol. 16a, pp. 173–182; February, 1961.) The frequency dependence of recombination noise was investigated in the range 100 cps–500 kc for various contact arrangements and specimen surfaces. Also investigated were the temperature characteristics of noise in the range 6–15°K, and the dependence on field strength of the spectral distribution function of noise.

537.311.33:546.289:621.391.822 3849
Fluctuation Phenomena in the Formation of Impact Ionization Avalanches in Ge Single Crystals between 5° and 10° K—M. Pilkuhn. (*Z. Naturforsch.*, vol. 16a, pp. 182–187; February, 1961.) The increase of noise observed during low-temperature breakdown in Ge is shown to be due to recombination effects. See also 3848 above.

537.311.33:546.47'241 3850
The Electrical Properties of Zinc Telluride—H. Tubota, H. Suzuki, and K. Hirakawa. (*J. Phys. Soc. Japan*, vol. 16, pp. 1038–1039; May, 1961.) The electrical resistivities and Hall coefficients of stoichiometric and Sb- or In-doped samples are given in graphical form.

537.311.33:546.681'18 3851
The Preparation and Floating-Zone Processing of Gallium Phosphide—C. J. Frosch and L. Derick. (*J. Electrochem. Soc.*, vol. 108, pp. 251–257; March, 1961.)

537.311.33:[546.682'19+546.682'18 3852
Infrared Cyclotron Resonance in n-Type InAs and InP—E. D. Palik and R. F. Wallis. (*Phys. Rev.*, vol. 123, pp. 131–134; July 1, 1961.)

537.311.33:546.682'86 3853
Anisotropic Segregation in InSb—W. P. Allred and R. T. Bate. (*J. Electrochem. Soc.*, vol. 108, pp. 258–261; March, 1961.)

537.311.33:546.682.86 3854
Pinch Effect in Indium Antimonide—A. G. Chynoweth and A. A. Murray. (*Phys. Rev.*, vol. 123, pp. 515–520; July 15, 1961.) A critical current of 4–5 a for the occurrence of pinch effect in InSb was measured by three different experimental methods.

537.311.33:546.682'86:535.215 3855
Properties and Applications of Indium Antimonide—R. E. J. King and B. E. Bartlett. (*Philips Tech. Rev.*, vol. 22, pp. 217–255; April 5, 1961.) The preparation of InSb crystals and the construction and performance of photocells based on InSb are described.

537.311.33:546.682'86:535.215 3856
Oscillatory Photoconductivity in InSb—W. Engeler, H. Levinstein and C. Stannard, Jr. (*Phys. Rev. Lett.*, vol. 7, pp. 62–63; July 15, 1961.) Cu, Ag, Au and Ni were added to InSb, and an oscillating curve was obtained for the photoconductive response as a function of incident wavelength at liquid-helium temperatures. The oscillations are attributed to the emission of successive longitudinal optical phonons.

537.311.33:546.682'86:538.632 3857
Corbino-Disk Magnetoresistivity Measurements on InSb—M. Green. (*J. Appl. Phys.*, vol. 32, pp. 1286–1289; July, 1961.)

537.311.33:546.811–17:538.63 3858
Magnetoresistance of Oriented Gray Tin Single Crystals—O. N. Tufte and A. W. Ewald. (*Phys. Rev.*, vol. 122, pp. 1431–1436; June 1, 1961.) The low-field magnetoresistance coefficients were evaluated from measurements on *n*- and *p*- type crystals at 77, 195 and 273°K. An explanation is given of the anisotropy observed in *n*-type crystals at 195 and 273°K.

537.311.33:546.824–31 3859
Nonohmic Behaviour in Near-Stoichiometric Rutile (TiO_2)—E. H. Greener and D. H. Whitmore. (*J. Appl. Phys.*, vol. 32, pp. 1320–1324; July, 1961.) Increase in ambient specimen temperature requires a higher field for the transition from ohmic to nonohmic behavior. At 908°C only ohmic currents are exhibited at the highest field-strength used (10 v/cm).

537.311.33:546.824–31:537.323 3860
Thermoelectric Behaviour of Rutile—K. Sakata. (*J. Phys. Soc. Japan*, vol. 16, p. 1026; May, 1961.) Thermo-EMF and conductivity have been measured as functions of temperature for samples sintered in O_2 at different pressures.

537.311.33:621.317.33 3861
Contactless Resistivity Meter for Semiconductors—J. C. Brice and P. Moore. (*J. Sci. Instrum.*, vol. 38, p. 307; July, 1961.) Resistivity is determined as a function of the eddy currents induced in the specimen by a 10-Mc oscillator. Resultant amplitude changes in the oscillator output are measured with a valve voltmeter.

537.311.33:669:061.3 3862
New Techniques for Producing Ultrapure Semiconductors—T. Maguire. (*Electronics*, vol. 34, pp. 41–45; July 7, 1961.) A review is given of the papers presented at the conference on ultrapurification of semiconductor materials, held at Boston, Mass.

537.312.62 3863
Magnetic Properties of Thin Superconducting Tin and Indium Films—B. K. Sevast'yanov. (*Zh. Eksp. Teor. Fiz.*, vol. 40, pp. 52–63; January, 1961.) The conditions for the absence of the normal phase in a superconducting film of finite size arranged at a small angle to a uniform magnetic field are determined. The dependence of the transverse component of the magnetic moment M on the temperature and thickness is determined for tin and indium films of thickness 4×10^{-3}–2×10^{-6} cm.

537.312.62:538.222 3864
Differential Paramagnetic Effect in Superconductors—R. A. Hein and R. L. Falge, Jr. (*Phys. Rev.*, vol. 123, pp. 407–415; July 15, 1961.)

537.312.62:539.23 3865
Size Effects in Thin Superconducting Indium Films—A. M. Toxen. (*Phys. Rev.*, vol. 123, pp. 442–446; July 15, 1961.)

538.221 3866
Distribution of the Magnetization in a Ferromagnet—M. W. Muller. (*Phys. Rev.*, vol. 122, pp. 1485–1489; June 1, 1961.) Analysis provides evidence that a stable nonuniform distribution is produced in a thick ferromagnetic slab in a large applied field, and that domains can appear if the anisotropy field is smaller than the demagnetizing field.

538.221 3867
Change of Thermal and Electrical Conductivity of Ferromagnetic Materials in a Magnetic Field—H. Papadimitraki. (*Z. Naturforsch.*, vol. 16a, p. 217; February, 1961.) Summary of experimental results obtained with Ni; the Lorentz number is plotted as a function of field strength over the range 0–4000 oersteds. Effects in Fe are too small to obtain quantitative results.

538.221 3868
Weak Field Behaviour of the ΔE Effect in Ferromagnetic Cubic-Solid-Solution Alloys—M. Yamamoto and S. Taniguchi. (*J. Phys. Soc. Japan*, vol. 16, pp. 1035–1036; May, 1961.)

538.221 3869
Magnetic Properties of Sintered Iron—H. Dietrich. (*Z. Metallkde*, vol. 52, pp. 232–235; April, 1951.) Magnetic data of unalloyed sintered iron are tabulated and the dependence of the characteristics on the manufacturing process and heat treatment is illustrated.

538.221 3870
On the Influence of the Formation of Subgrain Structures on the Magnetic Properties of Pure Iron—G. Montalenti and C. Sari. (*Nuovo Cim.*, vol. 19, pp. 605–608; February 1, 1961.) The formation of extremely stable subgrain structures which cannot be removed by further heat treatment, reduces considerably the permeability of iron specimens.

538.221 3871
Ferromagnetism in Solid Solutions of Scandium and Indium—B. T. Matthias, A. N. Clogston, H. J. Williams, E. Corenzwit, and R. C. Sherwood. (*Phys. Rev. Lett.*, vol. 7, pp. 7–9; July, 1961.)

538.221 3872
Magnetic Anisotropy and Rotational Hysteresis in Single Crystals of Magnetite Below the Transition Temperature—R. F. Pearson and R. Cooper. [*Proc. Phys. Soc.* (*London*), vol. 78, pp. 17–24; July 1, 1961.] Results of torque measurements, with some theoretical discussion.

538.221 3873
Magnetization of Nickel Single Crystals—L. Tterlikkis and A. W. Jenkins, Jr, (*J. Appl. Phys.*, vol. 32, pp. 1293–1296; July, 1961.) Anisotropy coefficients are calculated from experimental curves. A possible method of measuring internal strain energy is suggested.

538.221 3874
Magnetic Anisotropy of Heusler Single Crystal—K. Aoyagi and M. Sugihara. (*J. Phys. Soc. Japan*, vol. 16, p. 1027; May, 1961.) Experimental details of the growth and ferromagnetic properties of a crystal of Cu_2 Mn-Al.

538.221:537.533.72 3875
An Electron-Optical Method for the Measurement of the State of Magnetization of Ferromagnetic Specimens—C. Schwink. (*Z. Phys.*, vol. 161, pp. 560–578; February 14, 1961.) The feasibility of electron-optical measurements of magnetization is investigated theoretically for a cylinder with gap system [see also 1256 of May (Murrmann and Schwink)].

538.221:539.23 3876
The Preparation of Continuous Single-Crystal Thin Films of Nickel and Nickel-Iron Alloys—O. S. Heavens, F. F. Miller, G. L. Moss, and J. C. Anderson. [*Proc. Phys. Soc.* (*London*), vol. 78, pp. 33–37; July 1, 1961.]

538.221:539.23 3877
Magnetic Anisotropy in Single-Crystal Nickel Films—J. C. Anderson. [*Proc. Phys. Soc.* (*London*), vol. 78, pp. 25–32; July 1, 1961.]

538.221:539.23 3878
Field-Induced and Angle-of-Incidence Anisotropy in Nickel-Iron Films—E. Feldtkeller. (*Z. angew. Phys.*, vol. 13, pp. 74–76; February, 1961.) The magneto-optical Faraday effect is used to determine the contours of anisotropy orientation and field strength and of the wall coercivity.

538.221:539.23:538.61 3879
The Kerr Hysteresis Effect: a Phenomenon of Surface Magnetization—J. Kranz and B. Passon. (*Z. Phys.*, vol. 161, pp. 525–538; February 14, 1961.) Surface-magnetization curves for Fe-Si single crystals are obtained with the aid of the Kerr effect. See also 1281 of 1959 (Kranz and Drechsel).

538.221:539.23:538.614 3880
Observations of Cross-Tie Domain Walls by the Faraday Effect—A. L. Houde. (*J. Appl. Phys.*, vol. 32, pp. 1234–1237; July, 1961.) An apparatus for observation of the microscopic Faraday effect is described. The fine structure of the domain configurations in thin permalloy films has been observed.

538.221:539.23:621.385.833 3881
Transmission-Electron-Microscope Observations of Magnetic Domain Walls—J. T. Michalak and R. C. Glenn. (*J. Appl. Phys.*, vol. 32, pp. 1261–1265; July, 1961.) This technique for domain studies complements other techniques and is especially valuable for investigating magnetic films.

538.221:621.318.134 3882
The Theory of the High-Frequency Magnetic Susceptibility of Ferrodielectrics at Low Temperatures—I. A. Akhiezer, V. G. Bar'yakhtar, and S. V. Peletminsky. (*Zh. Eksp. Teor. Fiz.*, vol. 40, pp. 365–374; January, 1961.) The transverse components of the susceptibility tensor of a ferrite are calculated using methods of quantum field theory and taking both exchange and relativistic interactions between spin waves into account, and the ferromagnetic resonance line width is determined.

538.221:621.318.134 3883
A Note on the Electron Diffusion and the Wall Relaxation in Ferrites—H. Sekizawa. (*J. Phys. Soc. Japan*, vol. 16, pp. 1034–1035; May, 1961.) The distinction between the relaxation times due to the motion of electrons and wall relaxation is established.

538.221:621.318.134:538.652 3884
Theory of Magnetostriction in Cobalt-Manganese Ferrite—J. C. Slonczewski. (*Phys. Rev.*, vol. 122, pp. 1367–1372; June 1, 1961.)

538.221:621.318.4.042.1:534.2–8 3885
Studies of Magnetization Processes of Magnetic Cores by Supersonic Methods—K. Nishiguchi and H. Sawabe. (*Rev. Elec. Commun. Lab., Japan*, vol. 9, pp. 207–213; March/April, 1961.) When an ultrasonic vibration is applied to a magnetic core, the voltage output induced in a winding on the core is proportional to the remanent flux. This principle is applied to nondestructive investigation of the inner structure of magnetic cores.

538.221:621.318.57 3886
Two-Phase Permalloy for High-Speed Switching—E. A. Nesbitt and E. M. Gyorgy. (*J. Appl. Phys.*, vol. 32, pp. 1305–1308; July, 1961.) Gold added to permalloy makes precipitation of a second phase possible; coercive force and the threshold of rotational flux reversal can thus be controlled. Switching cores of such material are four times faster than standard cores.

538.22 3887
Abrupt Magnetic Transition in $MnSn_2$—J. S. Kouvel and C. C. Hartelius. (*Phys. Rev.*, vol. 123, pp. 124–125; July 1, 1961.)

539.2:538.569.4 3888
Spin-Lattice Relaxation in Imperfect Cubic Crystals and in Noncubic Crystals—E. R. Andrew and D. P. Tunstall. [*Proc. Phys. Soc. (London)*, vol. 78, pp. 1–11; July 1, 1961.]

548.5:535.215 3889
Vapour-Phrase Growth of Single Crystals of II–VI Compounds—W. W. Piper and S. J. Polich. (*J. Appl. Phys.*, vol. 32, pp. 1278–1279; July, 1961.)

669.018.5:537.311.33 3890
Capillary Alloying: an Improved Alloying Method—K. Lehovec, K. Busen, J. Casey, C. Pochop, and A. Webb. (*J. Electrochem. Soc.*, vol. 108, pp. 241–247; March, 1961.) Extremely flat, uniformly alloyed metal/semiconductor junctions can be produced with a separation from the wafer surface of less than 0.25 μ. Advantages of the technique over pellet alloying are the high degree of purity of the liquid alloy surface before alloying, and the possibility of comparing alloy compositions conveniently.

MATHEMATICS

512:621.318.57:681.142 3891
Symbolic Logic—B. R. Wilkins. (*Electronic Tech.*, vol. 38, pp. 317–324; September, 1961.) Elements of Boolean algebra and Venn diagrams are explained and their applications to verbal statements and to switching and computer circuits are considered.

517.941 3892
Six 'Natural' Normalizations of the Characteristic Equation of Third Degree—E. Schwartz. (*Arch. elekt. Übertragung*, vol. 15, pp. 94–100; February, 1961.) With the aid of the normalized equations and diagrams derived, the location of the roots in the complex plane can be determined; this leads to the solution of the linear homogeneous differential equation of third order on which the characteristic equation is based.

517.942.82 3893
A Theorem of the Laplace Transformation—G. Fodor. (*Period. Polyt., Bp., Elect. Engrg*, vol. 5, pp. 41–56; 1961. In German.) The problem of dealing with the Laplace transform of the derivative of a discontinuous function is considered. The method of solution proposed simplifies practical application.

517.942.82 3894
The Solution of Ordinary and Partial Differential Equations by means of the One- and Multi-dimensional Laplace Transformation for Limited Ranges—A. Käch. (*Arch. elekt. Übertragung*, vol. 15, pp. 33–47; January, 1961.)

MEASUREMENTS AND TEST YEAR

529.78:621.317.755 3895
Precise Measurement of a Time Interval of the Order of One Microsecond—J. Bourguignon. (*J. Phys. Radium*, vol. 21, Suppl., *Phys. Appl.*, pp. 217A–218A; November, 1960.) A simple modification of normal oscillographic technique is described, giving a triangular-waveform display with marker traces. Accuracy of the order of 5 nsec is obtained.

621.3.018.41(083.74) 3896
A Magnetic Shield for Beam Frequency Standards—F. S. Barnes, (PROC. IRE, vol. 49, p. 1328; August, 1961.) To reduce the frequency uncertainty of caesium-beam frequency standards, caused by stray electromagnetic fields, a magnetic shield of superconducting material is proposed instead of the more usual mumetal.

621.317(083.74) 3897
Measurement and Standardization—J. Cassassolles. (*Rev. gén. Élect.*, vol. 70, pp. 201–207; April, 1961.) A review of the work done by the Union Technique de l'Électricité (U.T.E.) on standardization of methods of measurement, measuring equipment and different reference standards.

621.317.029.6:[541.135+621.318.134 3898
New Methods of Studying Concentrated Electrolytes and Ferromagnetic Oxides at Very Short Wavelengths—J. C. Lestrade. (*Rev. gén. Élect.*, vol. 70, pp. 99–122; February, 1961.) Techniques of measurement at frequencies up to 4 Gc are described and results of measurements of the permittivity of several concentrated electrolytic solutions and the gyromagnetic resonance of γ-Fe_2O_3 and Fe_3O_4 are presented. An interpretation of observed phenomena is given. 62 references.

621.317.081.6(083.74) 3899
The Origin of International Electrical Units and their Present Situation—R. Hérou. (*Rev. gén. Élect.*, vol. 70, pp. 222L–236L; March, 1961.) A brief history is given of the development of electrical standards and the definitions of the standard ohm, volt, and ampere adopted by international committees from 1881 to 1948 are tabulated.

621.317.332.6.029.6 3900
Measurement of Low Reflection Coefficients at High Frequencies—K. Kohler. (*Frequenz*, vol. 15, pp. 12–17; January, 1961.) The principle of the method which is applicable to coaxial systems and waveguides is described. A commercial-type directional coupler with a quadripole tuned by stubs is used. See also 3567 of 1958 (Linnebach).

621.317.373:621.3.018.783 3901
The Effect of Nonlinear Distortion on Errors in Measuring the Phase Shift between Two Voltages—B. G. Kaduk. (*Izmer. Tekh.*, no. 6, pp. 44–45; June, 1961.) Formulas applicable to the measurement of phase difference are derived.

621.317:4.538.221:539.23 3902
Method for Measuring the Anisotropy Function of Thin Magnetic Films—T. D. Rossing and R. Stolen. (*Rev. Sci. Instr.*, vol. 32, pp. 752–753; June, 1961.) A simple apparatus is described in which the ac field coil and pick-up coil can be rotated together. The method gives a more accurate value for the anisotropy field than the usual hysteresis method.

621.317.725.029.5/.6 3903
Measuring Low-Level R.F. Voltage with Servo Feedback Techniques—T. C. Anderson. (*Electronics*, vol. 34, pp. 63–65; July 14, 1961.) A millivoltmeter is described which has seven voltage ranges, covering 10 mv to 10 v rms, and operates over the frequency range 500 kc–1 Gc.

621.317.733.011.22 3904
A Precision Conductance Bridge of New Design—G. J. Janz and J. D. E. McIntyre. (*J. Electrochem. Soc.*, vol. 108, pp. 272–276; March, 1961.) The bridge is designed for construction from standard commercially available components. The "four-leads" cell technique eliminates lead effects in remote conductance measurements.

621.317.738 3905
Measurements of the Dielectric Properties of Lossy Materials—E. Groubert and P. Caillon. (*J. Phys. Radium*, vol. 21, suppl., *Phys. Appl.*, pp. 155A–160A; November, 1960.) Apparatus for determining the dielectric properties of insulating materials at HF is described. Measurement is based on the variation of the width of the resonance curve of a tuned circuit when an impedance is placed across it.

621.317.77 3906
Construction of a High-Frequency Phase Meter—D. Boussard. (*J. Phys. Radium*, vol. 22, supple., *Phys. Appl.*, pp. 69A–71A; February, 1961.) The meter was designed to measure accurately the phase difference between two points on a conductor system in a linear accelerator. It has a range $+60°$ to $-15°$ and an accuracy within 0.5°.

OTHER APPLICATIONS OF RADIO AND ELECTRONICS

535.376:681.142 3907
The Electroluminescent Matrix for Pattern Display and Recording—D. C. Jeffreys and G. R. Hoffman. (*J. Brit. IRE*, vol. 22, pp. 53–64; July, 1961.) The photographic etching technique and vacuum deposition method of forming the matrix are described and a method of extending the lifetime of electroluminescent layers is noted. Selection problems in this type of matrix system are considered.

621.385.833 3908
The Resolving Power of Spherically Corrected Electrostatic Electron Microscopes—W. E. Meyer. (*Optik, Stuttgart*, vol. 18, no. 2, pp. 69–91; 1961.) The theoretical limit of resolution is calculated and methods of reducing aberration due to misalignments are given.

PROPAGATION OF WAVES

621.391.812.61.029.65 3909
Effect of Polarization on the Attenuation by Rain at Millimetre Wavelength—S. Okamura, K. Funakawa, H. Uda, J. Kato, and T. Oguchi (*J. Radio Res. Labs., Japan*, vol. 8, pp. 73–80; March, 1961.) The attenuation of vertically and horizontally polarized waves is compared using a method for rapidly switching the polarization. It is shown that the attenuation is generally larger for horizontally polarized waves. The measurements are in reasonable agreement with the theoretical calculations of Oguchi (1977 of July).

621.391.812.624.029.64 3910
Antenna Siting Tests at 3480 and 9640 Mc/s on a 173-Mile Tropospheric Scatter Path—N. D. La Frenais and W. J. Lucas. (PROC. IRE, vol. 49, pp. 1325–1326; August, 1961.) Signal recordings made at a favorable and an unfavorable receiving site are compared. Analysis shows how the difference in signal levels measured at the two sites varied as a

function of the system transmission loss. The figures for the dependence on the angular path distances show a dependence of θ^{-3} instead of the normally accepted θ^{-5}. See 683 of March (Geiger *et al.*).

621.391.812.63 3911
Simple Graphical Procedure for Calculating Sky-Wave Field Intensities—K. C. Chadha. (*J. Inst. Telecommun. Engrs. India*, vol. 7, pp. 89–102; March, 1961.) A series of graphical methods of applying the procedures S.P.I.M. [see 199 of 1953 (Rawar)] and RPU-9 (*U. S. Army Signal Corps Report*, No. 9) considerably reduce the labor involved but maintain the accuracy of the systems.

621.391.812.63 3912
Diversity Effects in Long-Distance High-Frequency Radio Pulse Propagation—S. A. Bowhill. (*J. Res. NBS*, vol. 65D, pp. 213–223; May/June, 1961.) Description of spaced-antenna measurements on an 8600-km path between Ceylon and England using pulsed radio signals. Interpretation of results in terms of E- and F-region multiple reflections gives good correlation with observed delay on the echoes received. The results also indicated that most of the diversity arises through phase incoherence between various orders of reflection.

621.391.812.63 3913
Space Analysis of Radio Signals—J. B. Smyth. (*J. Res. NBS*, vol. 65D, pp. 293–297; May/June, 1961.) An antenna is represented as a space-frequency filter. The RF field generated by it is distorted in passing into the ionosphere, generating new space frequencies which are the information contained in the field at the receiving antenna.

621.391.812.63 3914
Transequatorial Back-Scatter Observations of Magnetically Controlled Ionization—J. A. Thomas. (*Nature*, vol. 191, p. 792; August 19, 1961.) Very-long-range transequatorial echoes have been observed at Brisbane with a 16-Mc narrow-beam rotating-antenna back-scatter equipment [3371 of 1960 (Thomas and McNicol)]. They occur on 95 per cent of afternoons and are attributed to the ionospheric-tilt chordal-hop mechanism proposed by Villard *et al.* (244 of 1958).

621.391.812.63:621.396.663. 3915
Propagation Studies Using Direction-Finding Techniques—E. C. Hayden. (*J. Res. Nat. B. S.*, vol. 65D, pp. 197–212; May/June, 1961.) Two methods are described for the study of direction of arrival of individual components of multipath signals, resolution being undertaken by "time of arrival" separation for pulse transmissions or by "direction of arrival" separation using a highly directional antenna system. Some results obtained in studies of reception on 5.155 Mc over a path of 450 km and on 10 Mc over a path of 1000 km are presented.

621.391.812.63.029.4/.5 3916
Comparison between Mode Theory and Ray Theory of V.L.F. Propagation—H. Volland (*J. Res. NBS*, vol. 65D, pp. 357–361; July/August, 1961.) Values of field strength according to mode theory and ray theory in the VLF band are derivable from the same expression of the original vector potential, the result of one theory being the analytic continuation of the other one in another range of convergence. Both theories give the same result between distances of 3000 km and 2000 km. The relation to lightning discharges is considered.

621.391.812.63.029.45 3917
Statistics of a Radio Wave Diffracted by a Random Ionosphere—S. A. Bowhill.) *J. Res. NBS.*, vol. 65D, pp. 275–292; May/June, 1961.) Mathematical methods for evaluating the statistical properties of a random signal diffracted in free space are applied to the random structure of the lower ionosphere at very low frequencies. Allowance is made for sphericity, and anisotropy in the signal variations is permitted.

621.391.812.63.029.45 3918
Excitation of V.L.F. and E.L.F. Radio Waves by a Horizontal Magnetic Dipole—J. Galejs. (*J. Res. NBS*, vol. 65D, pp. 305–311; May/June, 1961.) The VLF and ELF modes excited by a horizontal magnetic dipole in the shell between a finitely conducting earth and an isotropic ionosphere are shown to have an almost transverse magnetic character. Response of the zero-order mode of the magnetic dipole has been calculated.

621.391.812.63.029.53 3919
Characteristics of Ionospherec Waves in the M.F. Band Measured at Night by the Vertical-Incidence Method—S. Hasegawa and T. Kobayashi. (*J. Radio Res. Labs., Japan*, vol. 8, pp. 127–136; March, 1961.) Observations of virtual heights and field intensities on frequencies of 540, 1040 and 1440 kc are described. During summer the one-hop-E mode is predominant over the full frequency range, while in autumn and winter the one-hop-F mode is more important above 1 Mc.

621.391.812.63.029.62 3920
Effect of E_s on V.H.F. Pulse Wave Propagation—K. Aida, T. Koseki, and K. Uchikura. (*J. Radio Res. Labs, Japan*, vol. 8, pp. 117–126; March, 1961.) Observations of VHF propagation over a path of 960 km and vertical soundings near the path midpoint show that during the day, propagation occurs via the E_s layer but during the night, reflection from meteoric dust is more important.

621.391.812.63.029.62 3921
Influence of Types of E_s Layer on E_s-Layer Propagated Waves—A. Sakurazawa. (*J. Radio Res. Labs, Japan*, vol. 8, pp. 97–116; March, 1961.) The factors governing E_s-layer propagation are examined by comparing VHF observations over a 1100-km path with those of E_s at the path midpoint. The analysis shows that the reflecting efficiency of the E_s layer depends on the values of f_0E_s over an area about the midpoint. The attenuation due to the D region is negligible while that due to the E region is most noticeable for propagation via the "h" type E_s.

RECEPTION

621.376.33:621.396.43 3922
Project Echo: F.M. Demodulators with Negative Feedback—C. L. Ruthroff. (*Bell Syst. Tech. J.*, vol. 40, pp. 1149–1156; July, 1961.) The performance of a FM receiver is described in which the beating oscillator is made to follow the instantaneous frequency of the signal. A smaller IF bandwidth can then be used which results in a better SNR than can be obtained with a conventional FM receiver or with SSB techniques.

621.391.82 3923
On the Theory of Amplitude Distribution of Impulsive Random Noise—K. Furutsu and T. Ishida. (*J. Appl. Phys.*, vol. 32, pp. 1206–1221; July, 1961.) Two models are considered and treated mathematically, one for Poisson noise (*e.g.*, electronic noise) and the other for Poisson-Poisson noise (*e.g.*, atmospheric noise). Theoretical distributions are compared with actual atmospheric noise.

621.391.82(545.5) 3924
Measurements of Radio Noise in the Delhi Area: Part I—N. B. Bhatt, M. K. Gupta, and Y. S. N. Murty. (*Def. Sci. J.*, vol. 11, pp. 23–33; January, 1961.) Noise levels measured in and near Delhi in the frequency range 150 kc–21 Mc show little correlation with the CCIR predictions. The diurnal variation was much smaller than expected.

621.391.821:621.396.62 3925
Effect of Receiver Bandwidth on the Amplitude Distribution of V.L.F. Atmospheric Noise—F. F. Fulton, Jr. (*J. Res. NBS*, vol. 65D, pp. 299–304; May/June, 1961.) For an assumed three-term parametric-exponential equation relating cumulative amplitude probability to field-strength threshold, expressions are derived indicating parameter variation as a function of bandwidth.

621.396.62:621.396.43 3926
Project Echo: Receiving System—E. A. Ohm. (*Bell Syst. Tech. J.*, vol. 40, pp. 1065–1094; July, 1961.) An over-all system noise temperature of about 20°K was obtained at 2390 Mc by combining a horn-reflector antenna maser preamplifier and special FM demodulator.

621.396.62:621.396.43 3927
Project Echo: Standby Receiver System—L. U. Kibler. (*Bell Syst. Tech. J.*, vol. 40, pp. 1129–1147; July, 1961.)

621.396.621 3928
Receivers with Zero Intermediate Frequency—M. D. Rubin. (Proc. IRE, vol. 49, pp. 1327–1328; August 1961.) An outline of the advantages and disadvantages of using a zero intermediate frequency. See, *e.g.*, 1677 of 1959 (Greene and Lyons) and 2767 of September (Casey).

621.396.621.072.6:621.391.82 3929
The Effect of Interference on an Automatic Frequency Control System: Part 1—V. I. Kaganov and N. S. Nemirovskiĭ. (*Radiotekh. Elektron.*, vol. 5, pp. 1380–1386; September, 1960.) An analysis of the effect of noise on an AFC system comprising an ideal discriminator, the mean frequency of which is not zero, operating with and without an IF filter.

STATIONS AND COMMUNICATION SYSTEMS

621.391.621.372.54 3930
Prediction of Signals by means of a Simple *RC* Network—A. Schief. (*Arch. elekt. Übertragung*, vol. 15, pp. 91–93; February, 1961.) A linear *RC* filter network for the statistical prediction of signals in noise is designed and experimental results are given.

621.391:621.376.23 3931
Multiple-Burst Detection—F. Corr. (Proc. IRE, vol. 49, p. 1337; August, 1961.) A class of cyclic codes exist which can correct any t bursts of minimum length b in a block of $(2^k-1)b$ bits. A proof is given that this code can alternatively be used to detect any $2t$ bursts of length b in a similar block. bkt check digits will be required.

621.396.2 3932
Spectrum Representation for Vestigial-Sideband Transmission in the Light of Transmission Possibilities between Single- and Double-Sideband Transmission—N. Berger. (*Nachrtech.*, vol. 11, pp. 31–35; January, 1961.)

621.396.43:551.507.362.2 3933
Satellites as Passive Relay Stations for Communications over Long Distances—W. Mansfeld. (*Frequenz*, vol. 15, pp. 1–9; January, 1961.) Conditions for the use of satellites as reflectors are examined. System design features

discussed include the shape and dimensions of the reflectors, transmitter output and antenna diameters.

621.396.43:551.507.362.2 3934
Participation of Bell Telephone Laboratories in Project Echo and Experimental Results—W. C. Jakes, Jr. (*Bell Syst. Tech. J.*, vol. 40, pp. 975–1028; July, 1961.) Two-way voice communication by reflection from a 100-ft diameter spherical balloon satellite orbiting at a height of 1000 miles was demonstrated over a coast-to-coast path in the U.S.A. Modulation tests using carrier frequencies of 960 and 2390 Mc showed FM to be superior to other forms. Measured transmission-path loss agreed closely with theory.

621.396.43:551.507.362.2 3935
Project Echo: System Calculations—C. L. Ruthroff and W. C. Jakes, Jr. (*Bell Syst. Tech. J.*, vol. 40, pp. 1029–1039; July, 1961.)

621.396.934:621.391.822 3936
Overall System Requirements for Low-Noise Performance—C. R. Ditchfield. (*J. Brit. IRE*, vol. 22, pp. 123–127; August, 1961.) The practical limitations of a microwave system for communication with and between satellites are discussed. The limit of performance will probably be determined by ambient noise background rather than receiver noise.

SUBSIDIARY APPARATUS

621–526:621.396.677 3937
Project Echo: Antenna Steering System—R. Klahn, J. A. Norton, and J. A. Githens. (*Bell Syst. Tech. J.*, vol. 40, pp. 1207–1225; July, 1961.) The use of basic orbital information to generate antenna steering instructions for project Echo is discussed. A digital method is described in which predicted pointing data is transmitted by teletype to the antenna site, then stored, and subsequently used when required in real time to control the antenna drive mechanism.

621–526:621.396.677:778.53 3938
Project Echo: Boresight Cameras—L. K. Warthman. (*Bell Syst. Tech. J.*, vol. 40, pp. 1227–1233; July, 1961.) Cameras are attached to the project Echo transmitting and receiving antennas at Holmdel for recording the position of the satellite. An exposure of 1/30 sec at *f*/3.5 was used at 4 frames/sec.

621.3.087.4:621.395.625.3 3939
An Analytical Expression for Describing the Write Process in Magnetic Recording—T. C. Ku. (PROC. IRE, vol. 49, pp. 1337–1338; August, 1961.)

621.3.087.4:621.397 3940
Video-Tape Analyzer—A. A. Goldberg and M. R. Nannah. (*J. Soc. Mot. Pict. Telev. Engrs.*, vol. 70, pp. 85–89; February, 1961.) Tape frequency response, noise contribution, drop-outs and rate of wear are determined and an assessment is made of the decline in picture quality due to repeated playback.

621.311.69:621.383.5 3941
Spectral Response of Solar Cells—B. Dale and F. P. Smith. (*J. Appl. Phys.*, vol. 32, pp. 1377–1381; July, 1961.) Theoretical response curves are derived by an analysis including the effects of carrier diffusion and drift due to the electric field in the surface region.

621.311.69:621.383.5:551.507.362.2 3942
Solar Cells for Communication Satellites in the Van Allen Belt—F. M. Smits, K. D. Smith, and W. L. Brown. (*J. Brit. IRE*, vol. 22, pp. 161–169; August, 1961.) The power output of solar cells on satellites is degraded by radiation damage on passing through the Van Allen belts. Methods of overcoming this are discussed.

621.311.69:629.19 3943
Power Supplies for Space Vehicles—N. W. Snyder. (*Astronautica Acta*, vol. 6, no. 6, pp. 271–310; 1960.) A comprehensive review of types of power systems, energy sources and power converters and an examination of the problems associated with their development as power supplies for space vehicles.

621.314.63 3944
Communication and Destructive Oscillation in Diode Circuits—I. Somos. (*Commun. and Electronics*, no. 54, pp. 162–172; May, 1961. Discussion.) An investigation of these phenomena in Si rectifiers and a study of how commutation may cause destruction of unprotected cells.

621.314.63 3945
A Fatigue-Free Silicon Device Structure—W. B. Green. (*Commun. and Electronics*, no. 54, pp. 186–191; May, 1961. Discussion.) By using hard solder instead of soft solder to make joints in the device, ruptures are no longer produced by cyclic thermal stress.

621.316.72 3946
Passive Voltage and Current Stabilizers using a Bridge Network—A. Caravel. (*J. Phys. Radium*, vol. 21, suppl., *Phys. Appl.*, pp. 187A-190A; November, 1960.) The residual voltage variation, which occurs when a Zener diode is used as a stabilizer, is removed by using a Wheatstone bridge network.

621.316.721.078.3:621.318.3 3947
Transistorized Current Stabilizers for Electromagnets of Medium Power (1 to 10 kW)—M. Sauzade. (*J. Phys. Radium*, vol. 21, Suppl. *Phys. Appl.*, pp. 161A–170A; November, 1960.) Methods of computing the characteristics and determining the stability are given.

621.316.722.1 078 3948
Cathode-Coupled Cascode Stabilizer Circuit—S. G. Jones and R. S. McClean. (*Electronic Engrg.*, vol. 33, pp. 503–505; August, 1961.) In a negative h.v. power supply (−6.8 kv nominal), the peak-to-peak ripple was less than 1.5 v and a ±10 per cent change in line voltage gave less than 1 v change in output.

TELEVISION AND PHOTOTELEGRAPHY

621.397.12 3949
A High-Speed Facsimile System with Electronic Scanning—K. Kubota, K. Kobayashi, Y. Okajima, and S. Nanbo. (*Rev. Elect. Commun. Lab., Japan*, vol. 9, pp. 214–219; March/April, 1961.)

621.397.331.2 3950
The Problem of Signal/Noise Ratio in Television Camera Tubes—H. Fix and A. Kaufmann. (*Radio Mentor*, vol. 27, pp. 114–116; February, 1961.) Reassessment of the relative merits of various types of camera tube with regard to SNR. This is in closer agreement with subjective assessments and is based on measurements of the spectral composition of statistical fluctuations in camera installations (1326 of June).

621.397.331.22 3951
Image-Orthicon Tubes with Field Mesh—K. Frank. (*Electronische Rundschau*, vol. 15, pp. 66–68; February, 1961.) The picture defects which can be minimized by the use of a field mesh are summarized [see also 2926 of 1957 (Theile and Pilz)]. The disadvantages, such as moiré effects, of this system are discussed and design improvements are suggested.

621.397.331.222 3952
Photoconductive Camera Tubes: the C.F.T.H. Vidicons—M. Blamoutier. (*Onde élect.*, vol. 41, pp. 229–238; March, 1961.)

621.397.331.222 3953
On the Possibility of using Germanium Sulphide Photoresistors as Targets in Television Camera Tubes—V. I. Perevodchikov and E. P. Kuznetsov. (*Radiotekh. Elektron.*, vol. 5, pp. 1478–1483; September, 1960.) A method of preparing high-resistivity GeS photo sensitive layers is described and their main characteristics are given. The basic parameters of a vidicon-type camera tube with a GeS target are discussed.

621.397.331.24 3954
The Reflected-Beam Picture Tube—a Further Step towards a Flat Tube of Large Image Size—P. Neidhardt. (*Nachrtech.*, vol. 11, pp. 27–30; January, 1961.) The principle of operation, design problems and practical possibilities for this type of picture tube are reviewed. See also 4043 of 1960 (Law and Ramberg).

621.397.62:621.396.67 3955
The Permissible Mismatch in Aerial Installations for Television Reception—A. Fiebranz. (*Nachrtech. Z.*, vol. 14, pp. 25–31; January, 1961.) The receiver input voltage is determined for mismatch conditions. Frequency-independent voltage components are found to depend on voltage SWR only, for low-order terms. The effects of mismatch on television picture quality are discussed.

621.397.74 3956
The Technique of the Television Transmissions (Session of the Federal Parliament')—H. Probst. (*Tech. Mitt. PTT.*, vol. 39, pp. 39–44; February, 1961.) Description of studio arrangements camera equipment, mobile and fixed control installations and the transmission system used for relaying interviews from the Parliament Building in Berne.

TRANSMISSION

621.396.61:621.396.43 3957
Project Echo: 960-Mc/s, 10-kW Transmitter—J. P. Schafer and R. H. Brandt. (*Bell Syst. Tech. J.*, vol. 40, pp. 1041–1064; July, 1961.) Driver-modulator units for FM, ph.m, SSB and pulse are described. The main output amplifier consists of a four-stage water-cooled klystron.

TUBES AND THERMIONICS

621.382.2:621.318.7:621.317.3 3958
Measuring Recovery Time of Ultra-Fast Diodes—G. C. Messenger. (*Electronic Ind.*, vol. 20, pp. 99–100; April, 1961.) An indirect method which gives accurate results below 1 nsec is described. Results have been obtained down to 0.05 nsec.

621.382.22:621.376.23.029.64 3959
High-Level Microwave Detector using Avalanche Injection—H. M. Day and A. C. MacPherson. (PROC. IRE, vol. 49, pp. 1333–1334; August, 1961.) An avalanche injection microwave diode has been constructed which has useful properties as a large-signal detector. At 9350 Mc, rectified voltages up to 12v across 200 Ω have been obtained with input power varying from 1 to 3 w.

621.382.23 3960
A Method for Determining the Base Voltage and Contact Resistance of a Conductivity-Modulated Diode—J. M. Swartz and H. C. Gorton. (PROC. IRE, vol. 49, pp. 1326–1327; August, 1961.) The contact resistance is measured from the dynamic change in voltage with current at high levels of carrier injection.

621.382.23:539.12.04 3961
Electron-Bombardment Damage in Silicon Esaki Diodes—R. A. Logan, W. M. Augustyniak, and J. F. Gilbert. (*J. Appl. Phys.*, vol. 32, pp. 1201–1205; July, 1961.) The excess current

in Si Esaki diodes has been shown to be a sensitive indicator of the density and distribution of states introduced into the forbidden gap by electron bombardment. The effects of bombardment and the annealing properties of the radiation damage depend on the specific donor in the n-type region.

621.382.23:621.372.44 3962
Large-Signal Circuit Theory for Negative-Resistance Diodes, in particular Tunnel Diodes—M. Schuller and W. W. Gärtner. (Proc. IRE, vol. 49, pp. 1268–1278; August, 1961.) The device and its external circuit are characterized by a system of accurate nonlinear differential equations, and solutions are obtained by an electronic computer. Results agree with measurements.

621.382.23:621.373.431.1 3963
The Tunnel-Diode Pair—Hamilton and Morgan. (See 3677.)

621.382.3:621.317.3 3964
Measurement of Transistor Quadripole Parameters—R. Paul. (*Nachrtech.*, vol. 11, pp. 8–12; January, 1961.) Measuring circuits are given and the accuracy of measurement is estimated. See also *ibid.*, vol. 10, pp. 56–61; February, 1960.)

621.382.3:621.317.7 3965
Transistor Current Gain at U.H.F.—B. N. Harden. (*Electronic Tech.*, vol. 38, pp. 312–316; September, 1961.) "A coaxial-line system and a twin-channel comparator are used to determine amplitude and phase variations of current gain. Results in the frequency range 300–800 Mc are compared with values obtained by a bridge method." See 3426 of 1959 (Smith and Hyde).

621.382.3:621.391.822 3966
Investigation of the Noise of Semiconductors—I. P. Valkó. (*Period. polyt., Bp., Elect. Engrg*, vol. 5, no. 1, pp. 57–73; 1961. In German.) Results of investigations of low-frequency transistor noise are reviewed. Details are given of test equipment for the direct indication of noise amplitude and spectral distribution.

621.382.32 3967
Graphical Analysis of the Operation of the Tecnetron: Parts 1 and 2—A. V. J. Martin and J. Le Mée. (*J. Phys. Radium*, vol. 22, suppl. *Phys. Appl.*, pp. 1A–12A and 83A–90A; February and June, 1961.) The operation of the device in the subcritical field region, where the carrier mobility is considered to be constant, is analyzed graphically and a set of universal curves of the main characteristics is derived. A detailed comparison is made between analytical and graphical approximations. See also 1959 IRE Convention Record, vol. 7, pt. 3, pp. 9–17; also, 1341 of 1961 (Martin).

621.382.333 3968
Characteristic Transistor Properties for Communications Applications and their Interrelation—W. Benz. (*Frequenz*, vol. 15, pp. 17–29; January, 1961.) Detailed consideration of the operation of a transistor as an amplifier including a discussion of dc conditions and dependence on temperature, frequency and working point. Transistor noise and nonlinear distortion, and the application of the transistor as a switching device are also mentioned. 52 references.

621.382.333 3969
A Method of Determining the Impurity-Doping Profile of a Transistor from Measurements of Certain of its Electrical Characteristics—J. P. Biet. (*J. Phys. Radium*, vol. 22, suppl., *Phys. Appl.*, pp. 59A–63A; February, 1961.) By measuring the hybrid-π parameters as a function of collector voltage and current, values can be obtained for the resistivity of the base and of the collector region, and the shape of the junction and base width can be ascertained.

621.382.333.33:621.372.632 3970
On Parametric Amplification in Transistors—J. Lindmayer and C. Wrigley; V. W. Vodicka and R. Zuleeg. (Proc. IRE, vol. 49, pp. 1335–1337; August, 1961.) Comment on 4420 of 1960 and 369 of February, and authors' reply.

621.382.333.34 3971
***p-n-p-n* Structures and a Solid-State Silicon Thyratron**—M. Sassier. (*Onde élect.*, vol. 41, pp. 239–246; March, 1961.) The theoretical relations governing the operation of *p-n-p-n* triodes are considered and applied to an analysis of the characteristics of a Si thyratron. Methods of manufacture are outlined.

621.383:535.376 3972
Infrared Detectors based on Phosphors—R. Groth. (*Z. Naturforsch*, vol. 16a, pp. 169–172; February, 1961.) The principle of a detector using infrared-sensitive phosphors is described and experimental results are given which were obtained with a SrS-Ce-Sm phosphor. A sensitivity of 6×10^{-11} was achieved near $\lambda=1\mu$.

621.383.49 3973
Reduction of Optical Reflection by Blooming without Increasing the Surface Recombination in Germanium Photoresistors—F. R. Kessler. (*Z. angew. Phys.*, vol. 13, pp. 72–74; February, 1961.) Comparison of results obtained with vapor-deposited $PbCl_2$ and Se; in the latter case the surface recombination remains unchanged but the sensitivity of the photoresistor is considerably increased.

621.383.51 3974
Germanium Bicrystals and their Application in Grain-Boundary Photocells—H. F. Mataré. (*Elektronische Rundschau*, vol. 15, pp. 57–60 and 207–211; February and May, 1961.) The mechanical and chemical structure of the grain boundary is considered and a model derived. The effect of impurities and the electrical properties of the bicrystal interface are discussed. Practical applications of this type of cell are mentioned. 27 references.

621.383.8 3975
Large-Field Image Intensifier Tubes for Visual, Ultraviolet and Infrared Ranges—L. F. Guyot. (*Onde élect.*, vol. 41, pp. 220–228; March, 1961.) A series of four tubes with 100-mm object field and luminance gain up to 6000 is described.

621.385.032.213.23 3976
Measurement of Oxide-Cathode Evaporation in Thermionic Valves with Radioactive Isotopes—C. Röszler. (*Nachrtech.*, vol. 11, pp. 13–16; January, 1961.) Results of experimental investigations on various types of tube are summarized.

621.385.032.213.23 3977
Suppression of Emission from Portions of Barium-Activated Tungsten Dispenser Cathodes and Adjoining Electrodes—R. Levi and E. S. Rittner. (Proc. IRE, vol. 49, pp. 1323–1324; August, 1961.) A technique for carburizing portions of a Ba-activated cathode to suppress the electron emission from areas where it is undesirable. Reductions in emission of two orders of magnitude are possible.

621.385.032.269.1 3978
The Matching of Pierce Guns to Tunnels—C. J. Milner and K. J. Ausburn. (*Brit. J. Appl. Phys.*, vol. 12, pp. 346–347; July, 1961.) All Pierce guns which shoot the maximum electron current through two identical apertures collinear with the axis of the gun have a unique ratio of cathode to anode radius. The value of this unique ratio is given for four important cases. A simple design procedure and relevant numerical data are given.

621.385.3+621.385.5 3979
A Method of Stabilizing the Gain of Triodes and Pentodes—H. Lorenz. (*Nachrtech.*, vol. 10, pp. 534–536; December, 1960.) The stabilization is effected by using a cathode resistance appropriate to the working point of the tube. The resistance tube is determined by measurement.

621.385.6 3980
Three Interpretations of Space-Charge Waves in Electron Beams—H. Groendijk. (*Tijdschr. ned. Radiogenoot.*, vol. 26, pp. 51–64; July 31, 1961.) The phenomenon is interpreted as 1) a single moving wave with phase velocity equal to the beam velocity and amplitude varying sinusoidally with position, 2) two moving waves of constant amplitude with different phase velocities, and 3) a stream of independent oscillators.


621.385.6:537.533 3981
Propagation in Periodic Electron Beams—W. M. Mueller. (*J. Appl. Phys.*, vol. 32, pp. 1349–1360; July, 1961.) A small-signal analysis of smooth electron beams with preiodic variations in their dc parameters reveals the existence of infinite sets of space harmonics of the fast and slow space-charge waves. Various effects and the possible uses of the periodicity in beams are mentioned.

621.385.6:621.372.8 3982
Electromagnetic Radiation from a Beam of Charged Particles Passing near a Waveguide with an Infinite Flange—Yu. N. Dnestrovskiĭ and D. P. Kostomarov. (*Radiotekh. Elektron.*, vol. 5, pp. 1431–1441; September, 1960.) A two-dimensional analysis of the EM radiation from a modulated electron beam passing the flange of a planar waveguide. The problem is reduced to a set of algebraic solutions which are solved analytically for a range of electron velocities.

Translations of Russian Technical Literature

Listed below is information on Russian technical literature in electronics and allied fields which is available in the U. S. in the English language. Further inquiries should be directed to the sources listed. In addition, general information on translation programs in the U. S. may be obtained from the Office of Science Information Service, National Science Foundation, Washington 25, D. C., and from the Office of Technical Services, U. S. Department of Commerce, Washington 25, D. C.

PUBLICATION	FREQUENCY	DESCRIPTION	SPONSOR	ORDER FROM:
Acoustics Journal (Akusticheskii Zhurnal)	Quarterly	Complete journal	National Science Foundation—AIP	American Institute of Physics 335 E. 45 St., New York 17, N. Y.
Automation and Remote Control (Avtomatika i Telemekhanika)	Monthly	Complete journal	National Science Foundation—MIT	Instrument Society of America 313 Sixth Ave., Pittsburgh 22, Pa.
	Monthly	Abstracts only		Office of Technical Services U. S. Dept of Commerce Washington 25, D. C.
Journal of Abstracts, Electrical Engineering (Reserativnyy Zhurnal: Electronika)	Monthly	Abstracts of Russian and non-Russian literature		Office of Technical Services U. S. Dept. of Commerce Washington 25, D. C.
Journal of Experimental and Theoretical Physics (Zhurnal Eksperimentalnoi i Teoreticheskoi Fiziki)	Monthly	Complete journal	National Science Foundation—AIP	American Institute of Physics 335 E. 45 St., New York 17, N. Y.
Journal of Technical Physics (Zhurnal Tekhnicheskoi Fiziki)	Monthly	Complete journal	National Science Foundation—AIP	American Institute of Physics 335 E. 45 St., New York 17, N. Y.
Proceedings of the USSR Academy of Sciences: Applied Physics Section (Doklady Akademii Nauk SSSR: Otdel Prikladnoi Fiziki)	Bimonthly	Complete journal		Consultants Bureau, Inc. 227 W. 17 St., New York 22, N. Y.
Radio Engineering (Radiotekhnika)	Monthly	Complete journal	National Science Foundation—AIEE	Royer & Roger, Inc. 41 E. 28 St., New York 16, N. Y.
	Monthly	Abstracts only		Office of Technical Services U. S. Dept. of Commerce Washington 25, D. C.
Radio Engineering and Electronics (Radiotekhnika i Elektronika)	Monthly	Complete journal	National Science Foundation—AIEE	Royer & Roger, Inc. 41 E. 28 St., New York 16, N. Y.
	Monthly	Abstracts only		Office of Technical Services U. S. Dept. of Commerce Washington 25, D. C.
Solid-State Physics (Fizika Tverdogo Tela)	Monthly	Complete journal	National Science Foundation—AIP	American Institute of Physics 335 E. 45 St., New York 17, N. Y.
Telecommunications (Elektrosviaz')	Monthly	Complete journal	National Science Foundation—AIEE	Royer & Roger, Inc. 41 E. 28 St., New York 16, N. Y.
	Monthly	Abstracts only		Office of Technical Services U. S. Dept. of Commerce Washington 25, D. C.
Automation Express	10/year	A digest: abstracts, summaries, annotations of various journals		International Physical Index, Inc. 1909 Park Ave., New York 35, N. Y.
Electronics Express	10/year	A digest: abstracts, summaries, annotations of various journals		International Physical Index, Inc. 1909 Park Ave., New York, 35, N. Y.
Physics Express	10/year	A digest: abstracts, summaries, annotations of various journals		International Physical Index, Inc. 1909 Park Ave., New York 35, N. Y.
Express Contents of Soviet Journals Currently being Translated into English	Monthly	Advance tables of contents of translated journals		Consultants Bureau, Inc. 227 W. 17 St., New York 22, N. Y.
Technical Translations	Twice a month	Central directory in the U. S. of translations available from all major sources in the U. S.	OTS and Special Libraries Assoc.	Superintendent of Documents U. S. Gov't Printing Office Washington 25, D. C.



A WORLD WIDE STANDARD POLARAD FIELD INTENSITY RECEIVERS

MODEL FIM-2
1,000 to 10,000 mc.

Hundreds of Polarad Calibrated Field Intensity Receivers are in use today throughout the world. **Why?**

...because the FIM series, in production since 1956, offers ±1db accuracy because of its self-contained signal generator.

...because the Model FIM-2 is the only single unit microwave system capable of measuring rf interference and susceptibility. It has been designed for measurements in accordance with all military RFI specifications.

...because the FIM-2 is an integration of two instruments in one, it is always available in your laboratory as either a sensitive microwave receiver or an accurate signal generator.

...because UNIDIAL® tunes both the receiver and signal generator simultaneously; and, the front-panel meter indicates average, peak, slide-back peak or quasi-peak value of rf signals, the Polarad of FIM-2 is the most convenient instrument in use today.

MODEL FIM-2 FEATURES

MAIL THIS COUPON

FREQUENCY RANGE: 1 gc to 10 gc in 4 tuning units; 2 more tuning units under development will extend frequency to 20 gc.
FREQUENCY DIAL ACCURACY: ±1%
SENSITIVITY: 20 microvolts
MAXIMUM RF INPUT: 3 volts
IMPULSE BANDWIDTH: 5 mc
IMAGE AND SPURIOUS RESPONSE REJECTION: 60 db
OUTPUTS: Video, audio, recorder
SIGNAL GENERATOR OUTPUT POWER: 0.223 volts to 5 microvolts (for susceptibility measurements)
SIGNAL ATTENUATION: 0 to 80 db in 1 db steps

FREE LIFETIME SERVICE

POLARAD ®PEC
ELECTRONICS CORPORATION
43-20 34th Street, Long Island City 1, N.Y.

Representatives in Principal Cities (See your yellow pages)

POLARAD ELECTRONICS CORPORATION:
43-20 34th St., Long Island City 1, N. Y.

Please send me information and specifications on:

- ☐ Model FIM-2 Calibrated Microwave Field Intensity Receiver
- ☐ Notes on Microwave Measurements

POLARAD

My application is _____

Name _____

Title _____ Mail Station _____ Dept. _____

Company _____

Address _____

City _____ Zone _____ State _____



ELECTROPLATED WIRES

Production equipment, designed and built in our own plant, assures precise, continuous plating of wire. . . . Our electroplates are consistently uniform and well bonded to the base wire. . . . Several metals may be plated one over the other, or two metals may be deposited simultaneously as an alloy. . . . A desirable application is the Gold plating of Copper wire. This combines the conductivity of Copper with the solderability and corrosion-resistance of Gold. Many other combinations are possible.

Send us details of your specific requirements

SIGMUND COHN
Manufacturing Co., Inc.
SINCE 1901
121 South Columbus Ave.
Mount Vernon, New York

THE BATTERY THAT'S USED IN GUIDED MISSILES NOW RELEASED AS GOVERNMENT SURPLUS



For Photography, Aircraft, Models, Searchlights, Radios, etc. **$1.95** ea. Postpaid

Sintered-plate Nickel-Cadmium alkaline storage batteries designed for "Nike" Missile and now surplus due to design change. A lifetime battery with no known limit of service (over 5000 recharges on test without loss of capacity). Other features: Virtually indestructible, compact & lightweight, withstands heavy shock and vibration. Flat voltage curve during discharge, retains charge year or more, high discharge rate up to 50 amps. for this cell, no corrosive fumes to harm clothing or equipment, spill-proof construction, discharge in any position, indefinite storage without deterioration, operates in temperatures —60° F to +200° F. Each cell is approx. 4 ampere hour capacity, nominal voltage per cell is 1.2 volts. (A 6 V. battery requires 5 cells.) Cell size 6″ H. × 2″ W. × ½″ T. Wt. 6 oz. ea. Uses Potassium-Hydroxide (30%) electrolyte. Negligible loss during lifetime service. Add only distilled water once a year. A fraction of Government cost.

Used Test Cells .....$1.95 ea. Postpaid
Brand New Cells ..... 2.95 ea. Postpaid

6 Ampere Hour Cells size 4½″ H. × 2⅜″ W. × ¾″ T.

Used test cells .....$2.95 **New Cells** .....$3.95 ea.

All cells guaranteed to your satisfaction or money refunded (less Postage).

ESSE RADIO COMPANY, Dept. IRE

42 W. South Street Indianapolis 25, Indiana

STANDARD WORKS of REFERENCE from PERGAMON

PLASMA PHYSICS and the PROBLEMS of CONTROLLED THERMONUCLEAR RESEARCH

Editor: Academician M. A. Leontovich; *Translation Editor:* Prof. J. Turkevich, *Princeton*

The first English translation of a large and authoritative selection of articles by leading Soviet scientists, these four volumes of recently declassified material reveal the research carried out between 1951 and 1958 at the USSR Institute of Atomic Energy. **4 vol. set, $80.00**

PLASMA PHYSICS and THERMONUCLEAR RESEARCH *Vol. 1, Series XI, Progress in Nuclear Energy*

Editors: C. Longmire, James L. Tuck, W. B. Thompson

This volume contains the edited Proceedings of the 2nd International Conference on the Peaceful Uses of Atomic Energy, Geneva, 1958. Part I offers a general survey of progress made; Part 2 is devoted to particular devices, such as the Stellarator, the Magnetic Mirror, the Plane Shock and the Pinched Discharge. 625 pp., *illustrated* **$15.00**

All books available for 14 days' free examination.

PERGAMON PRESS, INC. Dept. IR4 122 E. 55th St., New York 22, N. Y.
Publishers of ENCYCLOPAEDIC DICTIONARY OF PHYSICS

(Continued from page 64A)


ceived the honorary degree of Doctor of Science from Union College in 1944, from Hamilton College in 1946, from Drexel Institute in 1955, and from Marquette University in 1949. In 1950 he received the honorary degree of Doctor of Engineering from Rensselaer Polytechnic Institute.

He is a member of the National Academy of Sciences and American Philosophical Society, and a fellow of the American Institute of Electrical Engineers and the American Association for the Advancement of Science.

In 1956, Dr. Suits was named as a vice president of the American Management Association and served as chairman of the Association's new Research and Development Division from 1956 to 1958. The 1962 Industrial Research Institute Medal will be presented to Dr. Suits next spring at the annual meeting of the Institute.

✣

Rolf D. Weglein (S'52–A'55–SM'58) has been appointed head of product development for Hughes Aircraft Company's microwave tube division. He will direct the development of new products in the manufacturing area and will be responsible for the continual improvement of tubes currently in production. He has had ten years' experience in research and development of microwave tubes and components. Before joining the microwave tube division, he directed exploratory work in solid state low noise parametric amplifiers for the Hughes Research Laboratories in Malibu, Calif. He holds a master's degree in electrical engineering from the California Institute of Technology and is a member of Tau Beta Pi, Sigma Xi, ARS and the American Physical Society.



R. D. WEGLEIN

✣

James R. White (S'50–A'52–M'56–SM'58) was recently named to manage the Satellite Integration Facility recently established by Electro-Mechanical Research, Inc., in College Park, Md., it was announced recently. He will direct satellite integration programs which EMR has established to provide engineering, checkout and prelaunch satellite system integration for the National Aeronautics and Space Ad-



J. R. WHITE

(Continued on page 68A)

1962 1963 1964 1965 1966


All

LAMBDA

Power Supplies guaranteed for 5 years

Every Lambda power supply carries a written guarantee that it will perform to specifications for five full years. You can install power supplies now with complete assurance that they will still perform to design standards in 1966. *Lambda's guarantee, which covers workmanship and materials (except for tubes and fuses), has been in effect on all power supplies sold since 1953.* It is your strongest assurance of power supply performance in installations where dependability is an absolute necessity for round-the-clock, heavy-duty service.

SEND FOR NEW LAMBDA CATALOG 61





ALL-TRANSISTORIZED
LA SERIES

Nine Models Available
Voltages up to 330 VDC—Currents up to 20 Amp
Convection Cooled—Short Circuit Proof

LAMBDA ELECTRONICS CORP.

515 BROAD HOLLOW ROAD • HUNTINGTON, L.I., NEW YORK • 516 MYRTLE 4-4200

Western Regional Office: 230 North Lake Avenue, Pasadena, California • Phone: Code 213, MUrray 1-2544
New England Regional Office: 275 Boston Post Road, Marlboro, Massachusetts • Phone: Code 617, HUntley 5-7122
Middle Atlantic District Office: 515 Broad Hollow Road, Huntington, L. I., New York • Phone: Code 516, MYrtle 4-4200



WESGO—*Quality leader in vacuum tube ceramics and brazing alloys!*

High alumina ceramics for vacuum tube envelopes, internal spacers, rf windows, heat sinks, high-voltage insulators ...*your* specific electronic application.

Ultra pure low vapor pressure brazing alloys—a complete range of melting points and wetting characteristics for any vacuum requirement; wire, ribbon, sheet, powder, preforms...

AND THE NEW WESGO FLEXIBRAZE

...a money-saving new form for brazing alloys. Obviates the waste in stamping, gives you totally new versatility, bends to the form you need. Valuable for R&D work, introduces new production-line economies.

"VX" Super Refractory, Wesgo ceramics with uniquely high resistance to thermal shock. Ideally suited for use in furnace brazing, available in boats, slabs, special brazing fixtures.

devoted to the manufacture of products of unparalleled quality... to meet the exacting requirements of the vacuum tube industry!

Dept. P-12

WESTERN GOLD & PLATINUM COMPANY

525 Harbor Boulevard • Belmont, California • LYtell 3-3121

6777

IRE People

(Continued from page 66A)

ministration. The present contract which the facility is handling is the NASA S-3 satellite integration.

Mr. White is a graduate of Virginia Polytechnic Institute with a B.S. degree in Electrical Engineering. He has worked for Avco-Radiation Laboratories as Section Chief of Advanced Communications. Before joining EMR, he was employed at NACA, Langley Field, Va., as a Senior Aeronautical Scientist.

He is a member of the Tau Beta Pi, Eta Kappa Nu, and the Phi Kappa Phi honor societies. He is a Registered Professional Engineer in the State of Massachusetts.

❖

Membership

The following transfers and admissions have been approved and are now effective:

Transfer to Senior Member

Barclay, C., Boulder, Colo.
Cooper, J. I., Hawthorne, Calif.
Dertinger, E. F., Acton, Mass.
Farris, H. W., Ann Arbor, Mich.
Fitzmorris, M. J., Jr., Concord, Mass.
Grabowski, S. J., Fayetteville, N. Y.
Gulihur, D. L., Jackson, Miss.
Haynes, M. K., Chappaqua, N. Y.
Heydt, H. L., Ithaca, N. Y.
Kleppinger, R. E., Raritan, N. J.
Koehler, L. K., Los Alto, Calif.
Kosso, E. V., Reno, Nev.
Ksienski, A. A., Los Angeles, Calif.
Lingelbach, D. D., Stillwater, Okla.
Mahmoud, M. A., Kuwait, Arabia
May, H. A., Baltimore, Md.
Nachman, M. W., Levittown, Pa.
Oettinger, A. G., Cambridge, Mass.
Pulliam, P. E., Chula Vista, Calif.
Rezek, R. M., Centerport, L. I., N. Y.
Sachs, B. K., Huntington, L. I., N. Y.
Tallmadge, G. E., Palo Alto, Calif.
Thibodeau, D. L., Pointe Claire, Que. Canada
Tudor, J. R., Columbia, Mo.
Webb, M. L., Northfield, Vt.
Welsted, I. G., Mount Holly, N. J.
Wetmore, G. C., Kensington, Md.
Woodka, C. J., Scottsdale, Ariz.

Admission to Senior Member

Barker, J. L., East Norwalk, Conn.
Bigelow, J. E., Hales Corners, Wis.
Clingman, W. H., Jr., Dallas, Tex.
Clurman, S. P., Trenton, N. J.
Cox, C. W., Rapid City, S. D.
Culver, H. E., Arlington, Va.
Duinker, S., Eindhoven, Netherlands
Felling, W. E., Wellesley Hills, Mass.
Gatti, E. C., Milano, Italy
Gureckis, P. V., Washington, D. C.
Haimson, J., Palo Alto, Calif.
Hooten, B. P., Towson, Md.
Jenkins, L. B., Jr., Louisville, Ky.
Johnson, T. H., Boston, Mass.
Kramar, E., Stuttgart, Wurttemberg, Germany
Levine, P., Philadelphia, Pa.
MacDonald, D. N., Pasadena, Calif.
Maloney, E. S., Arlington, Va.
Meinke, H. H., Gauting, Bayern, Germany
Miller, C. E., Cambridge, Ohio
Milsum, J. H., Montreal, P.Q., Canada
Morgan, W. A., Baytown, Tex.
Riggs, J. R., New York, N. Y.
Steffens, C., Menlo Park, Calif.
Taylor, D. E., Westport, Conn.
Towle, H. C., Huntington, L. I., N. Y.
Trolander, H. W., Yellow Springs, Ohio
Turner, R. D., Ithaca, N. Y.
Viles, F. M., Framingham Center, Mass.
Watt, L. A. K., Seattle, Wash.

Transfer to Member

Ausec, R. C., Orlando, Fla.
Boyko, L. L., Oneida, N. Y.
Brown, P. L., Dallas, Tex.
Hale, G. K., III, Winston-Salem, N. C.
Hawley, M. M., St. Louis, Mo.
Ho, Y-C, Cambridge, Mass.
Leach, R. E., Spartanburg, S. C.
Lurie, A. B., Syracuse, N. Y.
Mann, C. W., Carlisle, Pa.
McConnell, V. I., Severna Park, Md.
Rajagopal, E. S., Oxford, England
Rowe, H. S., Limassol, Cyprus
Scian, H., Staten Island, N. Y.
Swanson, K. T., Washington, D. C.
Vogt, A. R., Park Forest, Ill.
Weissman, D., New London, Conn.

Admission to Member

Anderson, L. V., Downers Grove, Ill.
Andrews, J. C., Winchester, Tenn.
Arienzo, M. C., New York, N. Y.
Baganoff, F., St. Ann, Mo.
Ballou, R. G., York, Pa.
Balser, D. J., Melbourne, Fla.
Bauman, H. J., Hackensack, N. J.

(Continued on page 70A)

A Technical Inventory of the Professional Groups

On June 2, 1948, one of the most startling developments in engineering society history came to fruition: the formation of the first Professional Group of the IRE. Just how important this development was, and is, can be convincingly demonstrated by a brief inventory of the Professional Group activities.

As of September 30, 93,016 IRE members had joined 28 Professional Groups. They joined because these Groups were able to provide them with specialized technical services and information they could not afford to miss.

One of the services they could not afford to miss was the Professional Group Transactions. In 1960 alone, Group members were flooded with 99 issues of Transactions totaling 8616 pages of valuable technical material. This was 3½ times as many editorial pages as were published in the Proceedings. And this wealth of technical information could be had by paying only the small assessment fees levied by the various Groups.

Another service which 93,000 Group members found extremely important was the many meetings, sessions, and symposia held all over the country by the Groups. In fact during 1961 the Groups participated in over 40 major conferences and conventions, thus making available to their members, in still another way, the latest information on important new developments in their field.

The extensive national activities of the Groups were greatly supplemented by the activities of local Group Chapters in all parts of the country. A total of 287 Chapters have been organized in 57 local IRE Sections and have been holding meetings regularly.

The members of each Group have been introduced to one other important commodity—each other. Through local and national meetings and committees, thousands of engineers have had an invaluable opportunity to meet and exchange ideas with other engineers who are interested in exactly the same technical problems.

The inventory shows that if you have not yet joined a Professional Group, you are not getting the most out of your IRE membership.

Ernst Weber

Chairman, Professional Groups Committee



At least one of your interests is now served by one of IRE's 28 Professional Groups

Each group publishes its own specialized papers in its *Transactions*, some annually, and some bi-monthly. The larger groups have organized local Chapters, and they also sponsor technical sessions at IRE Conventions.

Aerospace and Navigational Electronics (G 11)	Fee $3
Antennas and Propagation (G 3)	Fee $6
Audio (G 1)	Fee $2
Automatic Control (G 23)	Fee $3
Bio-Medical Electronics (G 18)	Fee $3
Broadcast & Television Receivers (G 8)	Fee $4
Broadcasting (G 2)	Fee $2
Circuit Theory (G 4)	Fee $4
Communication Systems (G 19)	Fee $2
Component Parts (G 21)	Fee $3
Education (G 25)	Fee $3
Electron Devices (G 15)	Fee $3
Electronic Computers (G 16)	Fee $4
Engineering Management (G 14)	Fee $3
Engineering Writing and Speech (G 26)	Fee $3
Geoscience Electronics (G 29)	
Human Factors in Electronics (G 28)	Fee $2
Industrial Electronics (G 13)	Fee $3
Information Theory (G 12)	Fee $4
Instrumentation (G 9)	Fee $3
Microwave Theory and Techniques (G 17)	Fee $3
Military Electronics (G 24)	Fee $2
Nuclear Science (G 5)	Fee $3
Product Engineering and Production (G 22)	Fee $2
Radio Frequency Interference (G 27)	Fee $2
Reliability and Quality Control (G 7)	Fee $3
Space Electronics and Telemetry (G 10)	Fee $3
Ultrasonics Engineering (G 20)	Fee $2
Vehicular Communications (G 6)	Fee $3

IRE Professional Groups are only open to those who are already members of the IRE. Copies of Professional Group Transactions are available to non-members at twice the cost-price to IRE members.

The Institute of Radio Engineers
1 East 79th Street, New York 21, N.Y.

USE THIS COUPON

PG-12-61

Miss Emily Sirjane
IRE—1 East 79th St., New York 21, N.Y.

Please enroll me for these IRE Professional Groups

..... $.....
..... $.....

Name .....
Address .....
Place .....

Please enclose remittance with this order.

Academic Press
NEW YORK and LONDON

The Plasma Dispersion Function
The Hilbert Transform of the Gaussian

By BURTON D. FRIED, *Ramo-Wooldridge, Canoga Park, California, and* SAMUEL D. CONTE, *Space Technology Laboratories, Inc., Los Angeles*

November 1961, 419 pp., $12.00

These tables (pp. 17-419), will be useful in the analysis of a large class of plasma physics problems involving linearized wave motions, oscillations, and instabilities in a very hot plasma. Explicit formulae for all components of the "dielectric constant" or "conductivity" tensors of a uniform plasma in a constant magnetic field are given in terms of Z and Z'.

Physics of the Aurora and Airglow

By JOSEPH W. CHAMBERLAIN, *Yerkes Observatory, University of Chicago*

July 1961, 704 pp., $16.50

The author has included previously unpublished research on the theory of hydrogen emission in aurora, resonance scattering by atmospheric sodium, and excitation of the oxygen red lines in the airglow. In addition, he presents an extensive altas of the auroral spectrum. The summary of radio studies of the aurora is written from the point of view of physical processes. Auroral theory is treated with an emphasis on developments since the discovery of the Van Allen radiation belts during the IGY.

Physics of the Upper Atmosphere

Edited by J. A. RATCLIFFE, *Cavendish Laboratory, Cambridge*

1960 (Second printing, 1961), 586 pp., $14.50

Review:

". . . the book constitutes a most useful and up-to-date compendium on upper atmosphere physics. It is a must for the specialist, but is written so that the non-specialist or student can inform himself authoritatively of the state of this important subject." —*Science*

Wave Propagation and Group Velocity

By LÉON BRILLOUIN, *Member of the National Academy of Sciences*

with a contribution by A. SOMMERFELD

1960 (Second printing, 1961), 154 pp., $6.00

Review:

"The author is to be congratulated for bringing forth in book form these interesting and important contributions on wave propagation in dispersive media."

—*Physics Today*

Rarefied Gas Dynamics

Edited by L. TALBOT

November 1961, 748 pp., $19.00

November advertisement gave incorrect price

Detailed literature available upon request

111 Fifth Avenue, New York 3, New York
17 Old Queen Street, London, S. W. 1

Membership

(Continued from page 68A)


Beach, K. M., Jr., Palo Alto, Calif.
Beatty, J. F., Westwood, Mass.
Beery, W. M., Boulder, Colo.
Belcourt, F. J., White Bear Lake, Minn.
Bitsko, L. P., Offutt AFB, Neb.
Black, T. A., Austin, Tex.
Bowne, G. D., Marblehead, Mass.
Broadway, W. S., Melbourne, Fla.
Broll, O. J., Lynn, Mass.
Brown, D. A., Pittsburgh, Pa.
Brown, E. S., New Hartford, N. Y.
Brown, H. J., Washington, D. C.
Brown, T. B., Elmhurst, Ill.
Bruce, J. D., Lawrence, Kan.
Bruins, R. W., Schiedam, Netherlands
Cagnon, R. R., Canoga Park, Calif.
Calhoun, F. L., Los Angeles, Calif.
Campbell, W. E., Fort Huachuca, Ariz.
Cappa, M. B., Sepulveda, Calif.
Carpenter, M. E., San Diego, Calif.
Cater, I. B. R., Montreal, Que., Canada
Chambers, D. S., Riverton, N. J.
Chang, T. H., Philadelphia, Pa.
Charbel, M. S., Bogota, D.E. 2, Colombia
Charko, J. P., Ottawa, Ont., Canada
Chen, C-F., Memphis, Tenn.
Chin, L. A., Vancouver, B. C., Canada
Chwedchuk, L., Ottawa, Ont., Canada
Clark, L. F., Thousand Oaks, Calif.
Clodfelter, J. P., Baltimore, Md.
Collin, A. R. G., Brussel, Belgium
Conklin, H., Moses Lake, Wash.
Coogan, F. C., Mystic, Conn.
Coulbourn, C. B., Jr., Redondo Beach, Calif.
Cramer, M. L., Anaheim, Calif.
Curcie, S. C., San Francisco, Calif.
Dal Santo, W. R., Titusville, Fla.
Dando, K. R., Hagerstown, Md.
Daniel, J. T., Houston, Tex.
Dascher, A. J., Albuquerque, N. M.
Davo, R. R., Succasunna, N. J.
Desch, R. F., Boulder, Colo.
Duncan, J. J., Marietta, Ga.
Eaker, N., Richardson, Tex.
Echikawa, K., Kitakawachi, Osaka, Japan
Eden, H. D., Ventura, Calif.
Edgar, W. J., Ithaca, N. Y.
Ellis, R. A., Aberdeen Proving Ground, Md.
Essex, J. W., Waterloo, Ont., Canada
Evelsizer, G. E., Hillsboro, Ore.
Feeney, L. W., West Palm Beach, Fla.
Ferguson, G. D., Jr., Clearwater, Fla.
Flack, F. S., Washington, D. C.
Ganzel, J. R., Elmwood Park, Ill.
Gardner, R. B., Dayton, Ohio
Garey, J. R., Lansdowne, Pa.
Gentry, C. T., Dover, N. J.
Gibb, D. W., New York, N. Y.
Gironda, A. J., Sr., Norton AFB, Calif.
Glenn, M. S., Richardson, Tex.
Goldway, M., Ramatgan, Israel
Gorman, S. J., Arlington, Va.
Grover, C. S., Bedford, Mass.
Gulatsi, R. L., Devon, Pa.
Gullette, P. L., Riverton, N. J.
Hadley, H. N., Needham Heights, Mass.
Hall, J. H., North Chicago, Ill.
Hampton, G. H., Sr., Baltimore, Md.
Hansen, M., Glenside, Pa.
Harris, F. S., Jr., Salt Lake City, Utah
Harty, J. F., West Orange, N. J.
Haskins, E. R., Lockport, Ill.
Heierle, J. J., Bern, Switzerland
Heller, J., Bayside, L. I., N. Y.
Hellman, H., Little Falls, N. J.
Hemmer, N. H., Jr., Rockville, Md.
Hess, R. J., San Pedro, Calif.
Hibbits, F. G., San Diego, Calif.
Hill, J. W., Lynchburg, Tenn.
Hinkle, W. P., Thomasville, N. C.
Holzapfel, E. C., Flushing, L. I., N. Y.
Hull, D. E., Eau Gallie, Fla.
Isaman, F. E., Northridge, Calif.
Jain, N. C., Poona 5, India
Janardhanam, G., Bangalore-1, South India
Jenssen, H. F., Carle Place, L. I., N. Y.
Johnson, J. F., Jr., Dayton, Ohio
Joseph, R. D., Costa Mesa, Calif.
Kain, L. A., North Weymouth, Mass.
Kaufman, R. A., Silver Spring, Md.
Kearney, T. J., Endicott, N. Y.
Keene, F. R., Laureldale, Pa.
Kelly, M. J., Ithaca, N. Y.
Kirkpatrick, F. J., Austin, Tex.
Kirstukas, E. M., Baltimore, Md.
Klein, R. J., Chicago, Ill.
Kleker, J. H., Jr., Wheaton, Ill.
Knapp, C. F., Burbank, Calif.
Komatz, R. P., Panama City, Fla.
Korman, H. P., Chicago, Ill.
Kronenbitter, R. E., Willow Grove, Pa.
Kuehl, J. W., Florissant, Mo.
Kushida, A. H., Los Angeles, Calif.
LaFond, C. D., Washington, D. C.
Lamb, R. C., Boulder, Colo.
Lambert, T., Saxonville, Mass.
Lathey, C. E., Bethesda, Md.
Learoyd, J. A., Los Angeles, Calif.
Leccese, F. M., Ithaca, N. Y.
Ledbetter, H. D., Washington, D. C.
Leong, H., Franklin Park, N. J.
Lineback, C. D., Mansfield, Ohio
Lippman, G., New York, N. Y.
Lohr, B. F., Bethesda, Md.
Luhan, F. C., New York, N. Y.
Lupish, W., Ringoes, N. J.
Mahler, H. W., Danbury, Conn.
Maisner, L., San Pedro, Calif.
Mann, H. E., San Antonio, Tex.
Martin, J. W., Overland Park, Kan.
Mason, G. F., Jr., Fort Worth, Tex.
Mayr, H., Milano, Italy
McCallum, F. A., Mobile, Ala.
McCarthy, T. F., Southboro, Mass.
McMahan, W. H., Orlando, Fla.
Mellinger, F. J., Glendora, Calif.
Mendelson, H., Forest Hills, L. I., N. Y.
Meyer, R. K., Indianapolis, Ind.
Michelson, G. P., Santa Barbara, Calif.
Middleton, W., New York, N. Y.
Miller, R. J., Ithaca, N. Y.
Millett, R. E., Smithtown, N. Y.
Moore, W. H., Farmington, Mich.
Morgan, R. L., Raytown, Mo.
Morin, H. J., Framingham, Mass.
Morris, W. A., Plymouth, Devon, England
Munson, G. M., Scottsdale, Ariz.
Murray, J. P., Rome, N. Y.
Nagle, R. E., Glendora, N. J.
Netzel, L. J., Canoga Park, Calif.
Nezgoda, E. L., Hawthorne, Calif.
Ng, W. K., Los Angeles, Calif.
Norris, C. S., Ithaca, N. Y.
Nose, K., Lihue, Kauai, Hawaii
November, G. S., Marblehead, Mass.
O'Hara, W. P., Medford, Mass.
Opgaard, I., Stamford, Conn.
Palmer, G. L., Dallas, Tex.
Pearce, R. B., Jr., Fullerton, Calif.
Peterson, R., Fairfax, Va.
Pethe, V. A., Trombay, Bombay, India
Puris, O., Chicago, Ill.
Ramachandran, V., Bangalore, India
Ramsdale, C. F., Topeka AFS, Kan.
Rayfield, G. A., Tullahoma, Tenn.
Redding, R. R., Houston, Tex.
Robertson, R. E., Anaheim, Calif.
Rodgers, J. A., Vienna, Va.
Sabin, W. E., Lynchburg, Va.
Sgro, T. R., Brooklyn, N. Y.
Shaw, R. H., Ivyland, Pa.
Shiffer, C., Towson, Md.
Shum, E. K-s., Washington, D. C.
Sloop, R. B., Ithaca, N. Y.
Slusarek, Z. M., Philadelphia, Pa.
Smart, R. G., New South Wales, Australia
Smith, E. J., Schenectady, N. Y.

(Continued on page 72A)





*GREAT NEBULA OF ANDROMEDA, COURTESY BETTMAN ARCHIVES



Amperex® DX-151
4mm Reflex Klystron

Now manufactured in the United States

Immediately available from stock

WIDE TUNING RANGE
67 to 73kMc minimum

HIGH POWER
Guaranteed 100mw midband

LONG LIFE
Warranteed 250 hours


APPLICATIONS ■ Microwave communications ■ Microwave spectroscopy ■ Radiometry ■ Plasma diagnostics ■ Pumping for parametric amplifier ■ Local Oscillator for Radar ■ Components testing

Ask Amperex about millimeter-wave tubes for your specific applications

AMPEREX ELECTRONIC CORPORATION, 230 Duffy Avenue, Hicksville, L. I., N. Y.
In Canada: Philips Electronics Industries, Ltd., Tube, Semiconductor and Components Departments, 116 Vanderhoof Avenue, Toronto 17, Ontario

SENSITIVE RESEARCH

MAGNETIC MEASUREMENTS




FLUXMETERS

Portable, .5% accurate DC fluxmeters provide a simplified method for the rapid measurement of magnetic flux density (B) and magnetic field strength (H).

The fluxmeter is a zero torque movement with indications based on flux linkage changes in an external search coil. Deflection is proportional to total quantity of charge moved through coil and the instrument may therefore be applied as an integrator. Basic sensitivity is 10,000 maxwells per division for a 1 turn search coil. Sensitivity is proportional to number of turns on the search coil.

Model FM (Ranges: x1/x3/x10/x30/x100) Price $310.00

Model FS (Single range) Price $215.00



TEST SETS

Model MAT does magnetic testing in conformance with methods prescribed by the ASTM. Specifically designed for 1) the determination of magnetization curves and hysteresis loops; 2) measurement of core loss using Epstein specimens, ring cores or E and I cores; 3) measurement of DC flux density or magnetic field strength; 4) measurement of AC permeability. Price $2,775.00

Model COL provides the user with a high accuracy method of measuring AC core loss and exciting current. Price $1,675.00

SENSITIVE RESEARCH INSTRUMENT CORPORATION
NEW ROCHELLE, N.Y.

Membership

(Continued from page 70A)

Smith, H. W., Pomona, Calif.
Smith, J. P., Blue Bell, Pa.
Smith, J. L., Jr., Richardson, Tex.
Sproch, A., E. Palo Alto, Calif.
Stanfield, W. V., Philadelphia, Pa.
Stetson, R. B., Milford, N. H.
Stewart, G. H., Jr., Haddonfield, N. J.
Stiegler, R. W., Jr., Dallas, Tex.
Stowell, P. A., Paoli, Pa.
Sudbury, N. D., Nr. Marlborough, Wiltshire, England
Salas C., J. F., Caracas, Venezuela, S. A.
Sinha, O. P., Ranchi (Bihar), India
Szkutnicki, Z. R., London, S. W. 12, England
Thompson, E. L., Chicago, Ill.
Thomson, R. B., Columbus, Ind.
Unger, R. H., Ames, Iowa
Vicari, A. O., Plainfield, N. J.
Vollmer, R. L., Rockville, Md.
Wallace, C. W., Watertown, Mass.
Wallen, J., Jr., Falls Church, Va.
Wallingford, E. E., Kingston, Ont., Canada
Walston, D. H., Indianapolis, Ind.
Weaver, W. T., Dallas, Tex.
Weighart, F. G., Brookfield, Conn.
Wettstein, E. C., Wakefield, Mass.
Wheeler, R. R., Palo Alto, Calif.
Williams, J. L., Annandale, Va.
Wilson, D. L., Bellflower, Calif.
Wise, J. D., Dickinson, Tex.
Young, G. O., Anchorage, Alaska

Admission to Associate

Alexander, A., New York, N. Y.
Bangham, H. C., Annapolis, Md.
Barron, R. C., Mountain View, Calif.
Brown, R. C., Santa Clara, Calif.
Carroll, J. M., Larson AFB, Washington
Cavella, J. J., Philadelphia, Pa.
Colbert, M. R., Jersey City, N. J.
Conca, R. E., Los Angeles, Calif.
Cote, M., Drummondville, P. Q., Canada
Cox, W. R., Utica, N. Y.
English, J. W., Victoria, B. C., Canada
Ewen, J. J., Nashwauk, Minn.
Gest, B., Philadelphia, Pa.
Giacobbe, J. R., East Natick, Mass.
Glassie, D. C., Jr., Washington, D. C.
Godfrey, E. H., Alexandria, Va.
Goffin, P. V., Buenos Aires, Argentina
Gorner, C., St. Johns, Nfld., Canada
Grabowsky, W. P., Jenkintown, Pa.
Haight, A. K., New York, N. Y.
Jaenisch, J. E., San Gabriel, Calif.
Jeffrey, C. F., Maracaibo, Venezuela
Johnson, C. K., Kensington, Md.
Kahn, M. H., East Meadow, L. I., N. Y.
Kirschner, A. J., Floral Park, L. I., N. Y.
Lang, P. C., San Jose, Calif.
Lashock, J. J., Kennewick, Wash.
Lathrop, L. L., Chicago, Ill.
Lodge, G. A., New York, N. Y.
Ludlow, D. L., Milpitas, Calif.
McTigue, R. T., River Forest, Ill.
Meginniss, S. M., II, Baltimore, Md.
Mintz, S., Winnipeg, Man., Canada
Moody, M. E., Arlington, Va.
Pfeiffer, C. D., Buffalo, N. Y.
Polin, J., Elkins Park, Pa.
Potter, H. S., Norristown, Pa.
Pusateri, T. L., Pittsburgh, Pa.
Samuel, C. H., Portland, Ore.
Sim, S. M., Singapore 9
Taylor, G. S., Mountain View, Calif.
Thornton, J. P., Victoria, B. C., Canada
Timmer, H. G., Big Rapids, Mich.
Vega-Velasco, R. E., Bogota, Colombia, S. A.
Watson, W. D., Beverly Hills, Calif.
Werner, P-A., Stockholm K, Sweden
Wilks, R. C., Silver Spring, Md.
Winter, L. F., Poughkeepsie, N. Y.
Young, R. E., Jr., Falls Church, Va.
Zudell, J., Lorain, Ohio

Section Meetings

AKRON

"Horizon Sensors for Vertical Stabilization of Satellites & Space Vehicles," M. H. Arck, Barnes Engineering Co. 6/20/61.

ALAMOGORDO-HOLLOMAN

"High & Low Resolution Shaft Position Encoding Techniques," D. Griffin & N. Bartle, United Aircraft. 9/19/61.

BALTIMORE

"Stereo FM—How it Works," R. M. Linz, General Elec. Co. 10/9/61.

BEAUMONT-PT. ARTHUR

"How Complex Is a Jupiter IRBM?," B. Cunningham. 9/12/61.

CEDAR RAPIDS

Annual Picnic. 6/24/61.

CENTRAL FLORIDA

"Transit Satellite Navigational System," D. W. Rabenhorst, Johns Hopkins University. 9/12/61.

CHICAGO

"Power Transmission by Microwave Beam," W. C. Brown, Raytheon Co. 10/13/61.

DALLAS

"Solid-State Electronics for the 60's," R. L. Petritz, Texas Instruments. 9/26/61.

EGYPT

"Recent Developments in Video Tape Recorders," Y. Hamalainen, R.C.A. Geneva. 8/9/61.

ELMIRA-CORNING

"Recent Advances in High Power Microwave Switching," G. I. Klein, Westinghouse Electric Corp. 9/25/61.

EL PASO

Tour of Radio Station XELO. 8/31/61.
"Automatic Dispatching Systems for Power Plants," R. D. Wood, General Electric Co.; Joint meeting with AIEE El Paso Section. 10/5/61.

EMPORIUM

"Scientific Aids to Crime Detection," A. J. Baker, F.B.I. 10/17/61.

EVANSVILLE-OWENSBORO

"Ion Pumping and Its Place in the Field of High Vacuum," R. A. Gray, Ultek Corp. 10/11/61.

FLORIDA WEST COAST

"Electronic Applications in Vehicle Design and Operation," J. B. Bidwell, General Motors Research Labs. 9/20/61.

FORT HUACHUCA

"Automation in Hotels," E. Lewis, Fair, Isaac & Co. 9/25/61.

FORT WAYNE

"Noise Figure and Noise Figure Measurements," J. L. Minck, Hewlett-Packard Co.; "The Formation of Ferromagnetic Domains," Film Strip. 9/21/61.

GAINESVILLE

"Natural and Artificial Lightning Atmospherics," M. M. Newman, Lightning & Transients Research Institute. 10/11/61.

GENEVA

"The Diminishing High Frequency Radio Spectrum and its Effects upon Future Telecommunication Planning," G. Jacobs, Frequency Div., U.S.I.S. (VOA). 9/29/61.

HUNTSVILLE

"Microwave Tubes," A. B. Sutherland, Sperry Rand Corp. 9/28/61.

INDIANAPOLIS

Films—"Missiles and Radar Systems," F. H. Sauerteig, Indianapolis Power & Light Co. 9/28/61.
"What Is NEC?," J. J. Gershon, National Elec. Conference. 10/10/61.

ITHACA

Election of Officers. 5/18/61.
"Recent Physics Developments and Their Potentialities to Electronics," A. G. Tweet, General Electric Co. 10/12/61.

KANSAS CITY

"Communications Equipment Manufacture at the Western Electric Company's New Lee's Summit Works," E. D. Lander, Western Electric Co. 9/12/61.

KITCHENER-WATERLOO

Tour of CHCH T.V. Studio. 9/18/61.

LITTLE ROCK

"Strategic Air Command World-Wide Communications," C. Hinkle, Jr., Little Rock Air Base. 9/18/61.

LONDON

Tour of Northern Electric Co.—London Works. 9/20/61.
"Telemetry Systems for Small Satellites," R. W. Rochelle, Goddard Space Flight Center. 10/16/61.

LONG ISLAND

"Microwave Radiometry in Space," H. I. Ewen, Ewen Knight Corp. 10/10/61.

LOS ANGELES

"Where in the World Is WESCON Going?," B. S. Angwin, General Electric Co.; "WESCON Viewed Inside Out," W. E. Peterson, Automation Develop. Corp. 9/22/61.

NEW YORK

Panel Discussion—"Communications Satellites," J. R. Pierce, Bell Telephone Labs., R. R. Abrams, IT&T, W. E. Fromm, Airborne Instrument Labs. 10/4/61.

NORTHERN NEW JERSEY

"Early Plans for the Exploration of the Moon and Near Planets," A. Hyatt, NASA. 9/13/61.

OKLAHOMA CITY

"Active Communication Satellites," J. Jennings, Southwestern Bell. 9/11/61.

OMAHA-LINCOLN

"The Nebraska Research Institute and the Electronics Industry In Neb.," J. T. Vosoba, Nebraska Legislature; "A Wide Range Temperature Controller for Industry"—demonstration, J. Matejka, Omtronics Mfg., Inc.; joint with AIEE Neb. Section Comm. & Elect. Tech. Gps. 10/6/61.

OTTAWA

"A New Theory of the Aurorae and Related Phenomena," C. O. Hines, Dept. of National Defense; "International Aspects of IRE," J. T. Henderson, Natl. Research Council of Canada. 10/12/61.

(Continued on page 74A)

Solve Breadboard Needs Now

24 Hour SERVO Delivery!

- Wright 400 Cycle Motors, Motor Tachs, Inertia Damped Motors
- Advanced Designs, Including Very High Acceleration
- Full Production Quality Meeting All MIL Specs
- All Have Pinion Shafts .437" Long

This NEW service on quantities up to 10 pieces per item. Shipments made 24 hours after receipt of order - no spec. modifications. Normal fast delivery on larger quantities.

SERVO MOTORS	FRAME SIZE	VOLTS Ø1	VOLTS Ø2	STALL TORQUE	SPEED RPM	STALL PWR/Ø	ACCEL. RAD/SEC^2
20D633-2C	8	26	26	.22 OZ. IN.	6200	2.5W	106,000
20D633-4C	8	26	36 CT	.22 OZ. IN.	6200	2.5W	106,000
20D632-4C	8	26	36 CT	.35 OZ. IN.	6200	3.1W	99,800
20D627-2C	8	115	115/57	.33 OZ. IN.	6200	3.5W	98,000
20D603-2C	11	115	115/57	.60 OZ. IN.	6200	3.5W	43,300
20D603-4C	11	115	36 CT	.60 OZ. IN.	6200	3.5W	43,300
20D590-2A	15	115	115/57	1.3 OZ. IN.	4800	6.2W	27,800
20D612-2C	18	115	115/57	2.3 OZ. IN.	4800	9.1W	31,000

MOTOR TACHS	FRAME SIZE	VOLTS Ø1	VOLTS Ø2	TACH. VOLTS	STALL TORQUE	SPEED RPM	V/1000 RPM	TOTAL NULL	ACCEL. RAD/SEC^2
20D628-2C	8	115	115/57	26	.33 OZ. IN.	6200	.20	.019V	75,800
20D631-4C	8	26	36 CT	26	.35 OZ. IN.	6200	.20	.019V	80,500
20D634-2C	8	26	26	26	.22 OZ. IN.	6200	.20	.019V	75,000
20D634-4C	8	26	36 CT	26	.22 OZ. IN.	6200	.20	.019V	75,000
20D604-2F	11	115	115/57	115	.60 OZ. IN.	6200	.500	.019V	32,600
20D604-4F	11	115	36 CT	115	.60 OZ. IN.	6200	.500	.019V	32,600
20D593-2A	15	115	115/57	115	1 3 OZ. IN.	4800	3.1	.019V	17,500
20D614-2C	18	115	115/57	115	2.3 OZ. IN.	4800	3.1	.019V	25,900

INERTIA DAMPED	FRAME SIZE	VOLTS Ø1	VOLTS Ø2	STALL TORQUE	STALL POWER	SPEED RPM	DAMPING
20D618-2B	8	115	40/20	.30 OZ. IN.	3.5W	6200	40 DYNE CM
20D605-2D	11	115	115/57	.60 OZ. IN.	3.5W	6200	100 DYNE CM
20D613-2C	18	115	115/57	2.3 OZ. IN.	9.1W	4800	750 DYNE CM

WRIGHT / DIVISION OF SPERRY RAND
Durham, North Carolina
Tel. 682-8161

"Servos For New Horizons"

PUBLI-SERVICE PARIS



IN PARIS
PORTE DE VERSAILLES
FROM 16th TO 20th
FEBRUARY 1962

5th INTERNATIONAL EXHIBITION OF ELECTRONIC COMPONENTS

The greatest world meeting
in the field of electronics

FÉDÉRATION NATIONALE
DES INDUSTRIES
ÉLECTRONIQUES

23 rue de Lübeck, Paris 16e
phone: PASsy 01.16

Section Meetings

(Continued from page 73A)

PHILADELPHIA

"Keeping an Eye on the Weather," G. Corrington, RCA. 10/4/61.

PITTSBURGH

"Cryogenics Applied to Super Conducting Electromagnets," J. K. Hulm, Westinghouse Electric Corp. 10/9/61.

PRINCETON

"Principles of Ground Effect Machines, and Their Future," T. E. Sweeney, Princeton University. 10/10/61.

RIO DE JANEIRO

"Electric Computing Machines—Their Applications," C. A. G. Cordovil, IBM do Brazil. 7/12 61.

"Electronic Computing Machines Part II," C. A. G. Cordovil. IBM do Brazil. 8/9 61.

ROCHESTER

"Patent Law for the Engineers," T. L. Styner, General Dynamics Elect.; Election of Officers. 5/18/61.

ROME-UTICA

"Problems In System Engineering," R. Chipp, Rodd Chipp Assoc.; Joint with PGEM. 9/12/61.

7th National Communications Symposium. 10/2–3–4/61.

SAN DIEGO

"Limitations to Radio Communications in Noise," J. C. Webster, Navy Electronics Labs. 9/6/61.

Demonstration of Navy ASW Operations, W. G. Reifenrath, narrator. 10/4/61.

SCHENECTADY

"Digital Applications of Thermoplastic Recording," R. G. Reeves, Gen. Elect. Co. 10/10/61.

TOLEDO

Du Pont color-sound movie: Installation of Officers. 9/18/61.

TORONTO

"State of Art of Solid State Microwave Transmitters," W. Maciag, Sylvania Electronic Systems. 9/25/61.

Canadian Electronics Conference. 10 2 3 4/61.

TULSA

"The Ampex Video Tape Recorder," J. Bushnell, KVOO TV; Tour of Facilities. 9/21/61.

TWIN CITIES

"Missiles and Their Development," M. E. Griffith, U. S. Air Force; Joint with American Rocket Society. 9/15/61.

Tour of IBM Plant. 10 3/61.

VIRGINIA

"Estimation of the Physical Constants of the Moon Surface," K. M. Siegel, University of Michigan. 10/6/61.

WASHINGTON

Panel discussion—"Space Communications," Panel members—J. Pierce, Bell Tel. Labs., E. LaPorte, Radio Corp. of America; H. Trotter, Gen. Tel. & Elect. Labs., Inc.; R. P. Gifford, G.E. Co. 9/11/61.

"Electronics & Investments," T. W. Folger, Kidder, Peabody & Co. 10/16/61.

WESTERN MICHIGAN

Field Trip—Keller Tool Co. Plant. 6/14/61.
"Theory of Beam Antennas," C. Schecter, Electronic Dist. 9/13/61.

WINNIPEG

Tour of Minto Armouries. 10/6/61.
"What's New in Tubes, Semiconductors, Components & Educational Aids?," D. S. Simkins, Philips Electronics Industries Ltd. 10/16/61.

SUBSECTIONS

BUENAVENTURA

Tour of Pacific Missile Range, "PMR Instrumentation Ships," LCDR Janiec & L. Rose. 9/13/61.

CATSKILL

"Some Recent Developments in Lasers," J. W. Crowe, IBM Corp. 9/27/61.

CRESCENT BAY

"Systems Engineering in an Engineering Education Program," L. M. K. Boelter, UCLA. 6/22/61.
"Reorganization of Air Force Ballistic Systems Division and Space Systems Division," P. S. Walker, USAF. 9/18/61.

FAIRFIELD COUNTY

"Engineering Consideration in Design of Business Machines," J. Conklin, Pitney-Bowes. 6/22/61.

LEHIGH VALLEY

"Theory and Application of Speech, Production & Coding," E. E. David, Bell Telephone Labs. 5/24/61.

MEMPHIS

Demonstration on the IBM Computers: 705. 1401, C. Bovaird, IBM Corp. 9/29/61.

MERRIMACK VALLEY

"Electromechanical Teaching Machines," G. J. Rath, Raytheon Co. 9/25/61.
"Millimicrosecond Photographic and Electro-Optical Techniques," J. A. Hull, AVCO. 10/16/61.

MONMOUTH

"Survey of Microwave Parametric Amplifiers," G. Wade, Raytheon Co. 9/20/61.

NORTHERN VERMONT

Tour of G.E. Plant, narrator—Mr. Wolfe, G.E. Co. 9/18/61.
"Progress in Space Technology during Past Three Years," J. Bohuslaw, G.E. Co.; Film on Astronomy. 10/16/61.

PASADENA

"Communications—Challenge of Today," C. D. Barcus, Pacific Telephone. 9/20/61.

READING

"The Use and Service Techniques of Commercial Computers," A. Peters & W. Acker, IBM. 10/4/61.

SANTA ANA

"Don't Write Off the Electronics Industry," R. T. Silberman, Elect. Capital Corp. 9/12/61.

WESTCHESTER

Panel discussion—"Ways to Security and Status for the Engineer," Louis Yagoda, moderator; Panel members—J. T. Dollard, N.Y. State Society of Professional Engineers, C. N. Hull, Sperry Gyroscope Co. 9/27/61.


WESTERN NORTH CAROLINA

Tour of FAA Radar Facilities, W. B. Daniel. U.S. Gov. 9/29/61.

Special Customer Service On

MicroMatch®

DIRECTIONAL COUPLERS DC and RF OUTPUT



Unusual manufacturing flexibility combined with thirteen years of experience as specialists in the field of RF Power Measuring Equipment have enabled us to provide industry and the government agencies with over 4000 different models of MicroMatch directional couplers.

A typical example of special customer service is an RF output coupler with provisions for extracting or injecting up to 1000 watts of RF power. Couplers of this type are produced for use with both air and solid dielectric transmission lines.


To learn how readily and inexpensively your most exacting requirements can be satisfied, please write outlining your specifications in terms of frequency range, power level and type of connectors.

For more information on RF Loads, Directional Couplers, Tuners, and RF Wattmeters, write us at 185 N. Main Street, Bristol, Conn.

M. C. Jones Electronics Co., Inc.

SUBSIDIARY OF THE Bendix CORPORATION

Designed for M Application



MINIATURE INDUCTANCES FOR PRINTED WIRING

22 to 10,000 microhenries ± 5%. Maximum d.c. current rating 1210 to 60 milliamperes. Low d.c. resistance. Wound with high temperature wire and encapsulated in epoxy for −55°C to +125°C ambient temperature. Approximately the size of a transistor. Leads spaced 0.2 inch.

JAMES MILLEN MFG. CO., INC.

MALDEN

MASSACHUSETTS

Professional Group Meetings

Antennas and Propagation

Albuquerque-Los Alamos—June 20

"Precision Reflectometer Measurements," W. Little, Sandia Corp.

Boston—September 27

"Multiplate Antennas," A. C. Schell, Air Force Cambridge Res. Labs., Bedford, Mass.

"Extremely Low Frequency Terrestrial Noise as a Propagation Research Tool," H. R. Reamer, Sylvania Electronics Systems, Waltham, Mass.

Audio

Chicago—September 20

"Techniques for High-Speed Testing of Audio Amplifiers in Production," E. E. Bockenfeld, Hammond Organ Co.

Automatic Control

Chicago—September 26

"Terman and Automatic Control"—A Panel Discussion, R. W. Bull, Coleman Instruments; A. A. Gerlach, Cook Technological Center; R. B. Liepold, Automatic Electric Co.; Prof. G. J. Murphy, Northwestern University.

Los Angeles—September 12

"Unified Analysis of Linear Feedback Systems," D. McRuer, Systems Technology, Inc., Inglewood, Calif.

Bio-Medical Electronics

North Carolina—September 15

"Electronics in Obstetrical Research," Dr. F. C. Greiss, Bowman Gray School of Medicine, Winston-Salem, N. C.

"Basis of Phono Cardiographic Interpretation," Dr. M. P. Spencer, Bowman Gray School of Medicine.

"The Electronic Monitoring in Intensive Care of Patients," Dr. J. H. Meredith, Bowman Gray School of Medicine.

Broadcasting

Omaha-Lincoln—September 7–8

"Solid State Short Course for Radio-TV Engineers II," N. M. Bashara, R. G. Combs, C. M. Hyde, J. Kohl, E. A. Pearlstein, W. C. Robison, University of Nebraska.

San Francisco—August 22

"FM Broadcasting Allocations, Stereophonic FM Transmission, New Proposed FM Rules," H. L. Kassens, FCC; J. Barr, FCC; D. von Recklinghausen, H. H. Scott, Inc., Maynard, Mass.

Circuit Theory

Chicago—September 12

"Application of Topology to Electrical Networks," (Panel Discussion) Dr. S. L. Hakimi, Dr. A. I. Weinzweig, Northwestern University.

Los Angeles—September 19

"Venus Radar Experiments," R. Goldstein, Jet Propulsion Lab., Pasadena.

Communications Systems

Oklahoma City—September 25

"Video Recording and Transmission Equipment," C. Deal, Oklahoma City Board of Education.

Coffee and Tour of the Broadcast Centers TV PFM Studios and Transmitter Facilities KOKH TV.

San Francisco—September 20

"The Videograph Process—A New Approach to High Speed Printout and Display," W. B. Evans, A. B. Dick Res. and Dev. Lab., Palo Alto.


Plant tour and demonstration of electronic printout from a monoscope tube.

Component Parts

Chicago—September 12

"Stacked Wafer Module Design Concepts," R. E. Bauer, Paktron Div. of Illinois Tool Works, Alexandria, Va.

(Continued on page 78A)



Engineering hints from Carborundum

How to Join KOVAR® Alloy to Other Metals

KOVAR, the original iron-nickel-cobalt alloy, has a thermal expansion curve which matches almost perfectly that of several hard glasses. It is a widely accepted answer to the problem of producing vacuum and pressure tight glass-to-metal seals.

Most applications involve joining Kovar Alloy by either welding, brazing or soldering to other metals. Ordinary joining methods require variations and refinements to meet special characteristics or conditions—with such considerations as these:

1. KOVAR ALLOY has a considerably lower expansivity than most other metals.
2. WELDED AND BRAZED JOINTS WITH KOVAR ALLOY are frequently made in close proximity to a glass seal.
3. FOR HIGH VACUUM APPLICATIONS it is essential that no brazing alloy is used which contains a high vapor pressure constituent, such as cadmium, zinc or lead.

For example, to avoid stress corrosion on silver brazed Kovar joints we advise the following precautions:

1. BRAZING SURFACE to be free of longitudinal scratches.
2. ANNEAL KOVAR PARTS before brazing.
3. PLATE THE BRAZING SURFACE with copper or nickel.
4. DESIGN THE JOINT to avoid tensional stressing of the Kovar Alloy during the brazing operation. If the higher expansion member is on the inside, allow sufficient clearance between the parts.
5. USE A EUTECTIC BRAZING ALLOY, such as 72% silver, 28% copper.
6. THE BRAZING TEMPERATURE should be applied uniformly, such as in an atmosphere controlled furnace or high frequency induction heating.

New Technical Bulletin 100EB2A, available on request, gives additional information on welding, brazing, and soldering of Kovar Alloy to other metals. Individual engineering reports are also furnished on specific customer problems on Kovar Alloy joints.


Kovar Alloy, either oxide bonded to hard glass, or brazed to metallized ceramic insulators, makes a rugged permanent seal . . . even under the most severe conditions of temperature, vibration and handling. Technical service is available to help you solve processing and application problems. Contact the Carborundum Company, Refractories Division, Dept. P-121, Latrobe Plant, Latrobe, Pa.

THERE IS NO TRUE SUBSTITUTE FOR KOVAR® ALLOY
***. . . supplied only by* CARBORUNDUM**

KOVAR's superiority in making all types of glass-to-metal and ceramic-to-metal seals — and its ability to be easily formed, welded, soldered and brazed — is the result of a stringently controlled manufacturing process based on over 25 years continuous production experience. KOVAR is an alloy of unique and rigidly maintained characteristics. Stock and custom forms, together with complete technological advisory service, are available only through Carborundum.

CARBORUNDUM®

measures
.002 microvolts!



KEITHLEY
MILLI-MICROVOLTMETER

The Keithley Model 149 is the most sensitive electronic voltmeter available today, having a signal-to-noise ratio that approaches the theoretical limit. Recommended for use with thermocouples or thermopiles, the Model 149 is also ideal in cryogenics investigations and Hall Effect studies.

Zero suppression up to 100 times full scale adds versatility for the user. Line-operated, the Model 149 can accommodate either a floating or ground-referenced input. Output is 5 v or 5 ma on all ranges. Brief specifications:

- **range:** 0.1 microvolt to 100 millivolts in 13 overlapping 1x and 3x steps.
- **noise:** less than 6 x 10^{-10} v rms with shorted input.
- **input impedance:** 10K ohms on 0.1 μv range rising to 10 megohms on 100 μv scale.
- **stability:** within 0.01 μv per hour.
- **speed of response:** to 90% fs in .5 seconds on most ranges.
- **accuracy:** 2% fs on all ranges.
- **price:** $895.00

Other MICROVOLTMETERS:

Model 150A	1 μv sensitivity	$750.00
Model 151	100 μv sensitivity	$420.00

full details in latest catalog . . .

KEITHLEY
INSTRUMENTS

12415 EUCLID AVENUE
CLEVELAND 6, OHIO

Professional Group Meetings

(Continued from page 76A)

Component Parts
Electron Devices

Omaha-Lincoln—October 6

"Manufacture of Temperature Controllers, and Precision Resistors," J. Matejka, Omtronics Mfg., Inc., Omaha.

"Components Distribution Aids, such as IRE Proceedings and Convention Shows," R. H. Engstrom, Omtronics.

Electron Devices
Microwave Theory and Techniques

San Francisco—September 20

"Microwave Research in Europe," Prof. H. Heffner, Stanford University, Stanford, Calif.

Electronic Computers

Akron—March 22

"Some New Concepts in Information Retrieval," J. E. Belzer, Western Reserve University, Cleveland.

Engineering Management

Los Angeles—September 26

"Engineering Education—What to do about it," Dr. A. Rosenstein, University of California, Los Angeles.

Seattle—July 21

"The How and Why of Space Exploration," Dr. Von Braun, George C. Marshall Space Center, Huntsville, Ala.

Seattle—April 27

"PERT," R. D. Archibald, Hughes Aircraft, Culver City, Calif.

Engineering Writing and Speech

Northern New Jersey—September 21

"Documentation, Storage and Retrieval of Information," C. L. Engleman, C-E-I-R, Inc., Arlington, Va.

Industrial Electronics

Chicago—September 12

"A Novel Electropneumatic Temperature Controller," L. R. Axelrod, Power Regulator Co., Skokie, Ill.

Information Theory

San Francisco—September 12

"A Practical Look at Information Theory," W. W. Peterson, University of Florida, Gainesville, Fla.

Instrumentation

Chicago—September 20

"Techniques for High Speed Testing of Audio Amplifiers in Production," E. B. Bockenfeld, Hammond Organ Co.

Washington, D. C.—October 2

"FM and PM Interference Cancellation Techniques," D. R. Ludwig, General Electronic Labs, Silver Spring, Md.

Microwave Theory and Techniques

Albuquerque-Los Alamos—June 20

"Precision Reflectometer Measurements," W. E. Little, Sandia Corp., Albuquerque.

Product Engineering and Production

Boston—September 19

"High Density Electronics Interconnections"—a Panel Discussion, J. Staller, Sylvania; S. Francis, Francis Associates and Sippican Corp.; E. J. Duggan, MIT Inst. Lab.; R. Swigget, Photo Circuits Corp.; R. A. Curran, Dielox Div. of Electralab.

Reliability and Quality Control

Los Angeles—September 18

"Element Redundancy," C. A. Wiley, Hughes Aircraft Co.

"Trade-off Studies Involving Switch Reliability and Redundancy," H. McCormick, Hughes Aircraft Co.

Washington, D. C.—September 14

"Probabilistic Models for Reliability Analysis of Space Programs," Dr. W. W. Wolman, NASA, Washington, D. C.

Space Electronics and Telemetry

Albuquerque—June 13

"Bioelectronics and Medicine," Dr. A. H. Schwichtenburg, Lovelace Clinic.

San Francisco—September 19

"Multiple Frequency Antenna System for Satellite Tracking and Communication," L. G. Ettling, Philco Corp., Palo Alto.

Vehicular Communications

Chicago—September 20


"Extender Operation—Built-In Ignition Noise Suppression for FM Radio Receivers," J. Germain, Motorola, Inc., Chicago.


Use Your IRE Directory—It's valuable


*ENVIRONMENTALIZED














TEKTRONIX® OSCILLOSCOPE

THAT'S BUILT TO TAKE IT

DC-TO-24 MC WITH DUAL-TRACE UNIT • DC-TO-30 MC WITH FAST-RISE UNIT

ELECTRICAL CHARACTERISTICS SIMILAR TO THE TEKTRONIX TYPE 545 OSCILLOSCOPE

* DEPENDABLE OPERATION
WHILE SUBJECT TO THESE ENVIRONMENTS:

TEMPERATURE from —40°C to +55°C/71°C • VIBRATION to 5 G's, 55 cps, 0.03" peak-to-peak • SHOCK of 400-pound hammer drop • ALTITUDE to 20,000 feet • RADIO INTERFERENCE from 15 kc to 400 mc.

* RELIABLE PERFORMANCE
AFTER STORAGE IN THESE ENVIRONMENTS:

TEMPERATURE from —65°C to +85°C • ALTITUDE to 50,000 feet • FUNGUS for 28 days • HUMIDITY for 10 days at 95% relative humidity from +18°C to +65°C • RAIN CONDITIONS of 5 minutes steady dripping.

For those applications not demanding such environmental capabilities, the Type 945 will perform with even greater reliability and flexibility.

The Type 945 will accept any of 17 Tektronix letter-series plug-ins for use in commercial applications.

Type 945 Oscilloscope (without plug-ins)	$2850
Type MC Dual-Trace Plug-In Unit	$ 475
Type ML Fast-Rise Plug-In Unit	$ 425

U.S. Sales Prices, f.o.b. Beaverton, Oregon

For complete specifications of the new environmentalized oscilloscope—*or a demonstration in your own environment*—please call your Tektronix Field Engineer.

Tektronix, Inc. *P. O. BOX 500 · BEAVERTON, OREGON / MItchell 4-0161 · TWX—BEAV 311 · Cable: TEKTRONIX*

TEKTRONIX FIELD OFFICES: Albuquerque, N. Mex. • Atlanta, Ga. • Baltimore (Towson) Md. • Boston, Lexington, Mass. • Buffalo, N.Y. • Chicago (Park Ridge), Illinois • Cleveland, Ohio • Dallas, Texas • Denver, Colo. • Detroit (Lathrup Village) Mich. • Endicott (Endwell) N.Y. • Greensboro, N.C. • Houston, Texas • Indianapolis, Ind. • Kansas City, Missouri • Los Angeles (Culver City) • Los Angeles (Encino • West Los Angeles) • Minneapolis, Minn. • Montreal, Quebec, Canada • New York City Area (Albertson, L.I., N.Y. • Montclair, Conn. • Union, N.J.) • Orlando, Fla. • Philadelphia, Pa. • Phoenix, Ariz. • Portland, Oreg. • Poughkeepsie, N.Y. • San Diego, Calif. • San Francisco, Calif. Area (Lafayette, Palo Alto) • Seattle, Wash. • Syracuse, N.Y. • Toronto (Willowdale) Ont., Canada • Washington, D.C. Area

ENGINEERING REPRESENTATIVES: Kentron Hawaii Ltd., Honolulu, Hawaii. Tektronix is represented in twenty-five overseas countries by qualified engineering organizations.

European and African countries, the countries of Lebanon and Turkey, please contact TEKTRONIX INTERNATIONAL A.G., Terrassenweg 1A, Zug, Switzerland, for the name of your local engineering representative.

Other Overseas areas, please write or cable directly to Tektronix, Inc., International Marketing Department, P. O. Box 500, Beaverton, Oregon, U.S.A. Cable: TEKTRONIX

NEWS New Products

Plasma Spray Coater

Several improvements in plasma spray coating notably in the control and flow of plasma powders, permit exact duplication of coatings, according to **Engineering Div., Metco, Inc.,** 1101 Prospect Ave., Westbury, L. I., N. Y. The system has three components: console, with automatic controls, including fail-safe devices; powder feeder that permits exact duplication of coatings; simplified spray gun with one-piece nozzle and all-purpose electrode, both in fixed positions that eliminate need for adjustment. The system permits flame spray speeds with most materials of 5 to 15 lbs. per hour with deposit efficiency of 65% to 80%. Tungsten carbide, has a deposit of 75%.




The gun consists of six basic interchangeable, parts and handle. It is light enough ($3\frac{1}{4}$ lbs.) to be operated by hand, sturdy enough to be machine mounted, small enough for spraying internal bores down to 5″ID. Nitrogen, argon or helium can be used as the plasma gas. The gun has no moving parts, requires no adjustments. There are no soldered joints exposed to heat. Nozzle and electrode positions are fixed and foolproof. Tap water, at ordinary pressure, is used as a coolant and no heat exchanger is required.

A new unit has been designed to feed powder to the gun at a constant rate with extreme accuracy, by means of a positive mechanical metering device. A gas stream carries powder to the gun without flutter irrespective of the amount of powder in the hopper or the wear on components of the hopper. Thus any given coating can be precisely duplicated. Volume is controlled by a simple knob, with a wide range of settings.

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

The powder is fed from a hopper which holds approximately 1 hour of spray time. It is open to the atmosphere and therefore refillable while the gun is in use. It contains a non-spill valve assembly which prevents powder from spilling when the hopper is removed from the feeder. The valve operates automatically when the hopper is removed. The feeder mechanism is cleaned by running without the hopper in position.



The non-spill feature is very helpful for laboratory use where tests are being run, and also in production, as a quick weighing of the powder in the cannister, before and after use, shows how much has been used. Those who change powders frequently can attach the non-spill powder valve assembly to the standard container in which the powder is shipped and stored.

The following materials and mixtures thereof have been sprayed with the standard apparatus on various shaped objects and mandrels and are now available.

Materials	*Melting Point F°*
Aluminum Oxide	3700
Calcium Zirconate	4250
Chromium	3435
Chromium Carbide	3434
Cobalt-Chromium Carbide (blend)	2715–3434
Cobalt	2715
Cobalt-Zirconia (blend)	2715–4700
Magnesium Zirconate	3830
Molybdenum	4760
Nickel	2650
Nickel-Alumina (blend)	2650–3700
Titania-Alumina (blend)	3490–3700
Titanium Oxide	3490
Tungsten	6170
Tungsten Carbides	5200
Zirconium Oxide (approx.) (stabilized)	4700
Zirconium Silicate (approx.)	4390
Rare Earth Oxides (above)	4000

Jerrold Sweep Signal Generator


The price of the Jerrold Model 900-B Sweep Signal Generator should be $1980 instead of $1880 as shown in the 1962 IRE DIRECTORY advertisement. Readers should correct their copies accordingly.

Fixed Resistor Data Sheet

Data Sheet 185, just released by **CTS Corp.,** Elkhart, Ind., illustrates, describes and tabulates extensive tests of a new 0.050″ diameter×0.030″ thick solid cermet high temperature, high stability fixed resistor, using MIL-R-10509D, Characteristic B(RN60) as a guide to evaluation.

Power Supplies

New 24-volt and 50-volt power equipment, featuring non-aging silicon power rectifiers that help reduce cabinet size by as much as 50 percent, has been announced by **Raytheon Co., Industrial Operations,** Richards Avenue, South Norwalk, Conn.




Single-Phase Battery Charger

All Raytheon S-Series power supplies provide stable and filtered dc, regulated to within ±1 percent of the rated value with loads from zero to 100 percent and ac line variations from 95 to 130 volts. Complete overload and short circuit protection is built into the design.

Full particulars on Raytheon's new S-Series power equipment may be obtained from Roger Curtis at the firm.

(Continued on page 82A)



STILL OPERATIVE!

TI GROWN-JUNCTION TRANSISTORS in satellite survive torture treatment: The satellite fell from atop a missile carrier and bounced across a launching pad into a LOX- and kerosene-filled ditch. The fuel in the ditch ignited and the satellite burned for several hours. Result—TI transistors are still operative... dramatic proof of the high reliability of TI units under extreme conditions.

Here's Long-term Proof of TI Grown-Junction Transistor Reliability

● *Only Texas Instruments offers life-test data from lots that have been continuously on operating life test for over five years* — showing an extremely low average failure rate of less than 5×10^{-6}. More than *six-million life-test hours* give you the industry's greatest source of reliability data for predicting TI transistor performance.


● *Successful applications* in thousands of circuits over the years testify to the *consistent* reliability of these TI units.

● *Independent Quality and Reliability Assurance* department augments TI's own production and testing know-how... *independently* measuring device reliability at every manufacturing stage. Approximately one-million life-test hours *monthly* offer continuous verification of TI grown-junction reliability.

● *Low cost* of TI grown-junction transistors is made possible through industry's wide acceptance and usage of these units in many applications, enabling TI to provide fast, cost-saving production in large quantities. Added savings in time and money too, through *one-source purchasing* from TI's complete line of military and industrial grown-junction types.

Take advantage of the predictable reliability of these devices in your low frequency and switching designs. Call your local TI sales office or TI distributor now for immediate delivery in sample or production quantities.

Write on your company letterhead for TI grown-junction reliability data, application notes, data sheets or engineering assistance.



TRANSISTOR PRODUCTS DIVISION

TEXAS INSTRUMENTS
INCORPORATED
13500 N. CENTRAL EXPRESSWAY
P. O. BOX 5012 • DALLAS 22, TEXAS

18594

the sign of excellence in scientific and engineering books

TRANSISTOR CIRCUIT ANALYSIS

By Maurice V. Joyce and Kenneth K. Clarke
Polytechnic Institute of Brooklyn

"This book is definitely recommended for the transistor circuit engineer to serve him as an excellent circuit reference guide. . . . it is refreshing to review a book that is so well prepared and presented . . ." (Proceedings of the IRE)

This book presents the basic methods of analysis involved in the understanding and design of junction transistor circuitry. It limits transistor models to a small number that are easily interrelated. Previously unpublished material on emitter-follower transient responses, video and distributor amplifiers is included.

461 pp., 362 illus., 1961—$10.75

LINEAR CIRCUITS

By Ronald E. Scott
Northeastern University

"The purpose of this book is to provide depth in network theory in the beginning course with a minimal allotment of time. To this end, the author had directed himself with noteworthy perception, clarity and enthusiasm . . . merits careful examination by all teachers of network theory." (Proceedings of the IRE)

A valuable reference work because of its depth and scope, this book is available in a complete one-volume edition, or in two separate parts which cover, respectively, "Time Domain Analysis" and "Frequency Domain Analysis."

Parts 1 and 2, $6.75 each; Complete, 928 pp., 1088 illus. $11.75

- **Order from your bookstore or from the address below.**

. . . . . New from Addison-Wesley! Examination copies gladly provided. Write to 523 South St., Reading, Mass.

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 80A)

Miniature TWT

A miniature traveling wave tube that will provide a new high in power and broadened bandwidth for space communication systems is now in pilot production at the **Sperry Electronic Tube Div., Sperry Rand Corp.,** Gainesville, Fla., it was announced here today.

The amplifier—called the STX-186—can produce more than ten watts over frequency ranges from 5000 to 11,000 megacycles to hike the power of a great number of signals between a satellite and earth or between satellites tens of thousands of miles apart.

Details of the new tube were revealed by Dr. Warren Menke, engineering section head at Sperry's Great Neck, N. Y., plant, in a paper delivered at the annual IRE Electron Devices Conference in Washington on October 28.

To generate the high output power, engineers perfected an electron beam-focusing structure to assure the exact aiming of highly concentrated electrical energy down the length of the tube. Tiny permanent magnets made of a specia alloy are slipped like a row of precisely spaced finger rings over the tube to form the focusing structure.


The new traveling wave tube weighs a pound and is nine inches long. This miniaturization was achieved, Dr. Menke stated, while realizing a 40-db gain within the diminutive tube. Current units are priced at approximately $3500.

To ensure maximum efficiency between ten and 20 watts of power, engineers held the tube's beam voltage to 2200 volts. This was an important consideration in the reduction of the size, weight and complexity of the associated power supplies. Dr. Menke explained.

The STX-186 is a second-generation extension of an earlier and lower power *X*-band traveling-wave tube designed for electronic radar jamming systems. It is the first available version of the STX-182 experimental tube announced by Sperry last spring.

Silicon Controlled Rectifier

A new all-diffused, low-current Silicon Controlled Rectifier has been announced by the **General Electric Co., Rectifier Components Dept.,** West Genesee St., Auburn, N. Y.



Known as the C5, the device is available immediately from stock in eight types in the standard JEDEC TO-5 housing.


The C5 is the most completely specified SCR of its type in the industry. The specification sheet provides 11 separate curves.

GE application engineers say the new device will be used as both a sensitive signal amplifier and power switching element in the low power switching control circuits. The C5 may also be operated as a high voltage PNP transistor.

The eight models differ by forward breakover voltages which range from 25 volts for the C5U to 400 volts for the C5D. The devices in the C5 series will accommodate transient peak reverse voltages up to 500 volts. The average forward current rating of the new device is 1 ampere dc at 82°C case temperature. The maximum gate current to fire is 200 microamperes at 25°C. The peak one cycle, non-recurrent surge current is 18 amperes. The new SCR's are now available to original equipment manufacturers in medium quantities in the 25 volt model, for example, at $5.50. The 300 volt model is available in large quantities at $22.50.

Additional electrical and mechanical characteristics of the C5 series are contained in brochure 150.10. Copies of the brochure together with more information on these devices may be obtained by writing to the firm.

(Continued on page 84A)




UNCHALLENGED LEADERSHIP
in the application of
Semiconductor Devices
for
REGULATED POWER SUPPLIES

MILITARY • INDUSTRIAL • LABORATORY
GROUND • AIRBORNE • SPACE

Write For Catalog

POWER DESIGNS
1700 SHAMES DRIVE
WESTBURY, L. I., N. Y.
EDgewood 3-6200 Area Code 516



MONEL Alloy 404 . . . a new nonmagnetic alloy that can be multiple brazed in wet hydrogen

During multiple brazing operations, furnace atmospheres must contain enough water vapor to prevent the brazing alloy from wetting the fixtures. Yet the parts to be brazed must remain wettable to insure free flow, even after two or three trips through the furnace.

MONEL* Alloy 404 is a nickel-copper composition in which residual elements are held to low levels, to provide a clean, wettable surface to the brazing alloy even after continued exposure to wet hydrogen. And it retains the basic properties of MONEL Alloy 400 . . . low vapor pressure, strength, ductility, corrosion resistance.

Brazed three times in wet hydrogen — The test assembly above illustrates the excellent brazing properties of MONEL Alloy 404. It was built up in three slow passes through the furnace using hydrogen with a dew point of +70°F. On the third pass, the brazing alloy still flowed the full length of the joint.

The low magnetic permeability of MONEL Alloy 404 is not significantly affected by processing and fabrication, making it particularly suited for electronic parts. In any commercial form, size, or temper the permeability will not exceed a value of 1.1 at 27°F when measured using a field strength of 0.5 oersted. A nominal or typical value is about 1.01 at 27°F. (1.004 at room temperature using a field strength of 200 oersteds).

The thermal expansion of MONEL Alloy 404 is about the same as that of MONEL Alloy 400, and is sufficiently close to that of many other alloys frequently used in the construction of radio tubes to permit the firing of composite metal structures with a negligible amount of distortion. MONEL Alloy 404 also retains much of its strength at "out-gassing" temperatures.

For more information about this new alloy—write for our bulletin—Basic Data — MONEL Alloy 404. *Registered trademark

HUNTINGTON ALLOY PRODUCTS DIVISION
The International Nickel Company, Inc.
Huntington 17 West Virginia

INCO

MONEL® Nickel-Copper Alloys



NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 82A)

Custom Cabinets of Standard Design

Dahlstrom Manufacturing Corp., Jamestown, N. Y., has announced the introduction of the Unicabinet, a custom built cabinet of standard design.




The Unicabinet is an electronic rack cabinet of unusually rugged construction, designed to meet the widest possible variety of electronic housing requirements. Because the cabinet is custom built, the electronic engineer can specify depth, width, finish, trim, door location, panel location, drilling, fan mounting, ventilation ducting, and many other criteria without significant expense, and ordinarily without tool charge.

It is anticipated that the Unicabinet will be used in place of many custom design cabinets, making it unnecessary to design a cabinet for the exact application involved. Also, the item will be used in place of many standard rack cabinets in places where it has formerly been necessary to modify these cabinets considerably before they can be used.

The design includes heavy 11 gauge vertical posts in "arrowhead" configuration integrally welded both to its one-piece top and its one-piece base. Panels and doors are available in both flush mounted and surface mounted stylings. Side panels are normally fastened in place by removable screw fastenings, but can be continuously welded if required. The cabinet will meet most military specifications, and provisions have been made for RF shielding and metalizing as may be necessary.

The cabinet is styled with modern, clean, straight lines and is available in any color, texture, or trim desired enabling the purchaser to develop an individualized styling that will clearly identify his product line or in-plant equipment.

A new six-page four-color brochure describing the cabinet in full details is now available by writing Dahlstrom Manufacturing Corp., Jamestown, N. Y., Attention: Mr. R. Q. Quintus Anderson, Vice President in Charge of Sales.



TERMINAL BOARDS

Kulka Military Terminal Boards were designed by the Bureau of Ships according to MIL-T-16784B. They are made to BUSHIPS 9000-S6505-73214 drawings, with latest revisions, and BUORD S64101.

Kulka Military Boards are available as single row, double row, or through connected type units, and are molded of Type MAI-60 glass-filled alkyd resin according to the latest revision of M-14 specifications.

Kulka offers the complete line of these Military Boards, along with a wide selection of hardware accessories...



The complete catalog on Military Terminal Boards.... Write for your FREE copy...

KULKA ELECTRIC CORP.

633-643 SO. FULTON AVENUE, MOUNT VERNON, N. Y.

Magnetostrictive Delay Line

The 6053 has been designed by **Ferranti Electric, Inc., Electronics Div.,** Industrial Park No. 1, Plainview, Long Island, N. Y., to provide a package to accommodate the frequent requirements for magnetostriction delay lines with large numbers of pre-set taps.

A common application is in correlators of various types. Ferranti has had extensive experience with multi tapped lines over a period of about four years and the 6053 incorporates many features which have been developed during that period. The construction permits easy and precise adjustment of the tap positions and this can be very important when as many as 100 settings have to be made on each line.

It is a very compact package when compared to the elaborate package required to do the same job in the system using an assemblage of lumped constant lines and amplifiers. Compared to that method, the 6053 also offers very substantial cost savings. The advantages derive from the inherently broad band characteristics of magnetostriction delay lines and their large delay/bandwidth product.

The 6053 is available to order with 90 day delivery period. Prices vary appreciably according to the number of taps required.

(Continued on page 86A)

IMAGINATION




IMAGINATION . . . AN IMPORTANT COMPONENT IN EVERY HONEYWELL METER

If hard work and technical skill were the only requirements, almost anyone could build superior meters. But in many meter applications, success depends on the disciplined imagination of gifted designers and engineers. This is where Honeywell is outstanding. We can design and assemble panel instruments to solve any specific problems you may have. In fact, there's an excellent chance that we've already done so. ■ To find out more about quality instruments from Honeywell, get in touch with our representative in your area. He's listed in the classified pages of your telephone directory. Or contact us directly:
Precision Meter Division, Minneapolis-Honeywell Regulator Company, Manchester, New Hampshire, U.S.A. In Canada, Honeywell Controls Limited, Toronto 17, Ontario. HONEYWELL INTERNATIONAL
Sales and service offices in all principal cities of the world.

Honeywell

H Precision Meters

accuracies to one part in 10 billion



new... solid state

SRA SERVO PHASE SHIFTER

When the new Model SRA is combined with its companion unit, the Model VLA Receiver Phase Comparator, it becomes possible to automatically measure and standardize frequencies to *an accuracy of one part in ten billion.* Measurements may be permanently displayed on a strip-chart recorder.

Even inexpensive local oscillators will give extreme accuracy as the Model SRA adds phase correction to the oscillator output to phase lock the signal with a multiple of the received standard frequency.

Only 3½" high, the Model SRA is completely modular in construction. Meets environmental requirements of MIL-E-400B.

SPECIFICATIONS

INPUTS	(1) Phase detector voltage from Model VLA (2) 2 x RF signal voltage from Model VLA (3) 2 x RF synthesized voltage from Model VLA
PHASE OUTPUT FOR RECORDER	0.5 milliampere to ± 0.5 milliampere output into 1000 ohms corresponding to 100 microsecond phase shift.
DIGITAL READOUT	Calibrated in microseconds
SIGNAL LEVEL	Output of 3 v max. into 1000 ohms provided for recorder
POWER	19 v d-c from VLA
SIZE	3½" H x 19" W x 17½" D Weight 29 lbs.

SRA PRICE **$1485.00**

For complete technical information, write:

SPECIFIC PRODUCTS
21051 Costanso Street
or
P.O. Box 425
Woodland Hills, California
Phone: Diamond 0-3131

NEWS New Products


These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 84A)

Amplifiers can be supplied to drive the line, to amplify (and sum, if required) the outputs or to inter-connect a series of cascaded line.

Pallet and Shroud Packaging

Zero Manufacturing Co., 1121 Chestnut St., Burbank, Calif., announces development of a new system for pallet and shroud packaging heavy, fragile components such as rocket engines, klystron tubes, missiles and other equipment. The new system mates a lightweight aluminum modular container—providing maximum environmental protection to various MIL specifications—to a steel or aluminum pallet that is easy to handle, has necessary shock mounting and permits complete access to the component.



The bottomless modular container has a male closure, while mounted on the pallet is a gasketed environmental female closure; the shroud simply fits to the pallet by this method and is securely latched. In the application shown, the pallet has rugged cantilever supports and reinforced flanged cradles equipped with 8 shear mounts for mounting and shock protecting about a 5-ton component.

The system is re-usable many times. The pallet can also be converted for use as an in-plant dolly. Component accessories can also be attached while it is still mounted on the cradle. The system can be adapted to practically any component size or weight. Using modular containers for shrouds is a cost saving factor since any size container can be built from modules and other standard parts requiring no special tooling or fabricating set-ups.

For further information, write to Joe E. Daniels, at the firm.

An Introduction To Delay Lines

Computer Devices Corp., 6 W. 18 St., Huntington Station, N. Y., has published a four-page dissertation entitled "An Introduction to Delay Lines." This paper provides a simple, non-technical presentation. Delay lines of all currently popular types are described, simplified theories of operation are shown, applications are discussed and attainable characteristics are related to size and prices. It should be of interest to technical as well as non-technical personnel who deal in these versatile components.


Also available is a new catalog sheet which describes a complete series of standard magnetostrictive delay lines covering the range from 2 to 5000 μsec.

Two types of packaging are described—the ML type which are long, thin configurations having delays up to 100 μsec and operating in the longitudinal mode, and the MT type which consist of slab configurations operating in the torsional mode, with delays from 20 to 5000 μsec.

Tuneable RF Probe

An RF probe, featuring smooth and precise tuning adjustment, has been announced by **Narda Microwave Corp.,** Plainview, L. I., N. Y.

Designated Model 229B, the probe is designed for use with all waveguide and coaxial slotted lines that have the standard ¾" diameter mounting hole.




The new instrument features a fine wire probe, adjustable in depth over a wide range by a fine-pitch threaded knob. The fine wire probe is actually an extension of the center conductor of a coaxial line which is provided with both shunt and series tuning elements for tuning over the range of 900 to 18,000 Mc. Either standard microwave crystals or Narda N-601B Bolometers may be used and an RF output is also available to enable the unit to be used with microwave receivers or other external detectors.

The probe is priced at $145; the RF Output (Model 229-427) is priced at $25. Both are available from stock.


Note: This firm moved its entire plant from Mineola, N. Y. to Plainview, L. I., N. Y., on October 21, 1961. The new telephone number is: Area Code 516, GE 3-9000. TWX: HKVL 5444. Western Union: FAX, Hicksville, N. Y.

L-Band Circulator Switches

Hyletronics Corp., Burlington, Mass., announces new L-band ferrite circulator switches. Used as non-reciprocal SPDT switches, they have applications in receiver protection, antenna switching, and radiometry. Designed to operate below



(Continued on page 88A)



Sanborn® FIFO—fully transistorized, shown actual size

1 MILLISECOND RECOVERY TIME *after a 14-volt overload. Time base, 1/2 ms/div; amplitude, 2% of full scale. A small AC signal was mixed with the overload to increase visibility of recovery trace.*

NEW 0-10 KC Floating Input-Floating Output DC AMPLIFIER

The new FIFO (floating input—floating output) is a fully transistorized amplifier designed especially for obtaining data from wide bandwidth transducers. A single FIFO used with an input scanner can amplify data from many transducers, or the outputs of any number of FIFO amplifiers may be sampled.

Model 860-4000, with gain of 1000, is particularly useful for extracting low level signals from a high noise level. Model 860-4000P (with grounded output isolated from input) can deliver ±5 volts at ±100 ma and is suitable for driving high frequency galvanometers. Both FIFO models have a high common mode rejection ratio and, as illustrated by the 'scope photo, exceptional overload recovery capability.

The FIFO amplifier is available in a portable case with individual power supply. Two channels with individual power supplies are available on a 3½″ x 19″ panel for rack mounting, or you can mount eight amplifiers in 7″ x 19″ with a Sanborn Model 868-500F 8-channel power supply.

Contact the Sanborn Industrial Sales-Engineering representative nearest you or write the main office in Waltham for complete information and engineering assistance.

SPECIFICATIONS: MODEL 860-4000 FIFO AMPLIFIER

Isolated, floating, guarded input — 100 meg. impedance min. at DC

Isolated, floating output — impedance less than 35 ohms

Bandwidth DC to 3 db down at 10 KC

Max. Gain of 1000 — 10 mv in gives ±10 volts out across 1000 ohms (floating). Optional Model 860-4000P with power output isolated from input can deliver ±5 volts at ±100 ma at ground potential

Linearity ±0.1% of 10-volt floating output at DC

High Common Mode Rejection — 160 db at DC, 120 db at 60 cps, 100 db at 400 cps, with 1000 ohms unbalance at source

Drift 2 uv, Noise 7 uv RMS

Specifications subject to change without notice.

INDUSTRIAL DIVISION
SANBORN COMPANY
175 Wyman Street, Waltham 54, Massachusetts
A SUBSIDIARY OF HEWLETT-PACKARD COMPANY



For DC to 100 cps bandwidth

DATA PREAMPLIFIER 860-1500S

Has floating, guarded input and floating output; delivers ±5 volts across 2000 ohms; linearity ±0.05% of full scale (5 volts); bandwidth DC to 3 db down at 100 cps; rejection ratio 10^6:1 with 5000-ohm source unbalance at 60 cycles. Either fixed gain between 10 and 2000, or with attenuator to provide any selected gain within this range. Amplifier has less than 2 uv drift and less than 3 uv peak-to-peak noise.

SECON PRECISION
POTENTIOMETER
Wire
from 37 to over
600 ohms per cmf

Secon can provide the exact precious metal potentiometer winding alloy for your requirements . . .

- Low temperature coefficient of resistance.
- High tensile strength.
- Low noise.
- Supplied bare or enameled.
- Long life.

For more information please write today to Secon Metals Corporation, 7 Intervale Street, White Plains, N. Y. (WHite Plains 9-4757).

SECON METALS
RELIABLE WIRE FOR
THE HEART OF YOUR COMPONENT

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.


(Continued from page 86A)

ferromagnetic resonance to reduce drive requirements, they can be switched n times down to 30 μsec. High speed switching is accomplished through the use of thin-walled ground planes in the strip-transmission line to eliminate the shorted turn effect and eddy current losses. Model SL1 exhibits over 20 db of isolation and less than 0.5 db insertion loss over the band 1250–1350 Mc.

Model SL2 is also available at 1420 Mc and provides greater than 30 db of isolation and less than 0.2 db insertion loss.

Delivery is from four to six weeks.

Transistor Test



The Dynatran Electronics Corp., 178 Herricks Road, Mineola, N. Y., announces its new line of unit instruments that provide direct meter readings of the various RF parameters of mesa, drift and surface barrier transistors. The instruments can provide measurements of the 20 megacycle current gain, the collector capacitance and the extrinsic base resistance-collector capacitance product. These unit instruments are available as either individual rack mounted units or as plug-in units that mount in a bias supply cabinet.

Static, Self-Contained Battery Charger

A completely static, self-contained battery charger for electric utility, railway communication and signalling, and industrial applications, has been announced by the **Rectifier-Capacitor Div., Fansteel Metallurgical Corp.**, North Chicago, Ill.



It employs a transistor, magnetic amplifier circuit and silicon rectifiers. The unit maintains its output voltage from no load to full load within ± 1 per cent of the adjusted nominal voltage with ± 10 per cent changes in line voltage.

The charger is suitable for lead-acid and nickel-cadmium batteries. It is available in standard models with charging rates up to 100 amperes. Special units are available on request. Input is 115/230 volts ac. Efficiency ranges from 75 to 80 per cent.

A current-limiting circuit eliminates the possibility of damaging the charger or battery when it is connected to a completely discharged battery. Equalizing charge required to balance the plates of lead-acid batteries can be applied through a manual control.

In normal operation, with the battery floated across the output, the charger delivers regulated dc power to relays, pilot lights, tripping or closing coils, or carrier equipment. The charger also maintains the battery at full charge for emergency use. During overload or high demand, the battery supplements the charger while the current limiting circuit protects the charger.

Optional equipment includes an ac failure relay, equalizer timer, meters, and ground detector indicators. Prices for complete units start at $200.00.

(Continued on page 90A)



HIGH PURITY ELEMENTS

SOUTH PLAINFIELD, N. J., Dec. 1 -- ASARCO CENTRAL RESEARCH LABORATORIES, USING SPECIAL REFINING AND ANALYTICAL TECHNIQUES, HAVE SUCCEEDED IN PURIFYING SELENIUM SO THAT NO NICKEL OR IRON CAN BE DETECTED AT 5 PARTS IN 100,000,000. LEVELS OF OTHER IMPURITIES IN ASARCO HIGH PURITY ELEMENTS CAN AT TIMES BE MORE SPECIFICALLY LIMITED TO MEET CUSTOMERS' SPECIAL REQUIREMENTS.

ASARCO HIGH PURITY ELEMENTS ANALYSES as of DEC. 1, 1961

Impurities sometimes found at maximum levels in parts per million
(< denotes less than ppm indicated)

	Element and Grade		Bi	Cu	Fe	As	Pb	Ag	Tl	Sn	Te	Au	Na	Cl	Cd
	ANTIMONY	A-60	<1	<1	<1	<2	<1								
✓	ARSENIC	A-60		<1											
	BISMUTH	A-58		2	1		1	2						<1	
	CADMIUM	A-60		<1	<1		1								
	COPPER	A-58	No Impurities Detectable by Spectrographic Analysis												
	GOLD	A-59		<1	<1		<1	1							
	INDIUM	A-58		<1			1		<1	1					
	LEAD	A-59	<1	<1	<1										
	SELENIUM	A-58		<1		<1					1			<1	
	SILVER	A-59		<1	<1		<1								
	SULFUR	A-58											1	1	
	TELLURIUM	A-58		<1	<1										
✓	THALLIUM	A-60		1	1		<1	<1					2	<1	
	ZINC	A-59		<1	<1		<1								<1

✓ *Denotes element improved since last published analyses.*

ASARCO

The analyses above are among pertinent data compiled by Asarco's Central Research Laboratories in an up-to-date catalogue now available to users of high purity elements. For a copy, write on your company letterhead to American Smelting and Refining Company, 120 Broadway, New York 5, N. Y.

IS *YOUR* COMPANY ON THE *OFFENSE* FOR *DEFENSE?*

***SIGNAL** is your introduction to the men who control government's growing $6.5 billion radio-electronics spending*

Never before have our armed forces so badly needed the thinking and products of the electronics industry. Advertising in SIGNAL, the official journal of the *Armed Forces Communications and Electronics Association*, puts you in touch with almost 11,000 of the most successful men in the field—every one a prospect for your defense products!

Share in the defense and the profits! Company membership in the AFCEA, with SIGNAL as your spokesman, puts you in touch with government decision-makers!

SIGNAL serves liaison duty between the armed forces and industry. It informs manufacturers about the latest government projects and military needs, while it lets armed forces buyers know what *you* have to offer to contribute to our armed might. SIGNAL coordinates needs with available products and makes developments possible.

But SIGNAL is more than just a magazine. It's *part of an over-all plan!*

A concerted *offensive* to let the government, which has great faith in industry and the private individual producer, know exactly what's available to launch its far-sighted plans. Part of this offensive is the giant AFCEA National Convention and Exhibit (to be held next year in Washington, D.C., June 12-14). Here, you can *show* what you have to contribute directly to the important buyers. Your sales team meets fellow manufacturers and military purchasers and keeps "on top" of current government needs and market news.

Besides *advertising* in SIGNAL which affords year-round exposure by focusing your firm and products directly on the proper market . . . besides *participation* in the huge AFCEA National Convention and Exhibit . . the over-all plan of company membership in the AFCEA *gives your firm a highly influential organization's experience and prestige to draw upon.*

As a member, you join some 175 group members who feel the chances of winning million dollar contracts are worth the relatively low investment of time and money. On a local basis, you organize your team (9 of your top men with you as manager and team captain), attend monthly chapter meetings and dinners, meet defense buyers, procurement agents and sub-contractors. Like the other 59 local chapters of the AFCEA, your team gets to know the "right" people.

In effect, company membership in the AFCEA is a "three-barrelled" offensive aimed at putting your company in the "elite" group of government contractors —the group that, for example in 1957, for less than $8,000 (for the full AFCEA plan) made an amazing total of *459.7 million dollars!*

This "three-barrelled" offensive consists of

(1) Concentrated advertising coverage in SIGNAL, the official publication of the AFCEA;

(2) Group membership in the AFCEA, a select organization specializing in all aspects of production and sales in our growing communications and electronics industry; and

(3) Attending AFCEA chapter meetings, dinners and a big annual exposition for publicizing your firm and displaying your products.

If *you're* in the field of communications and electronics . . . and want prestige, contacts and exposure . . . let SIGNAL put your company on the *offense* for *defense!* Call or write for more details—now!

SIGNAL

Wm. C. Copp & Associates
72 West 45th Street,
New York 36, New York
MUrray Hill 2-6606
Boston · Chicago · Minneapolis · Los Angeles · San Francisco

BPA

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 88A)

Magnesium Oxide Crystals

Relatively large, high purity, single crystals of Magnorite fused magnesia are now being produced by **Norton Co., Research and Development Dept.,** Worcester 6, Mass. Developmental quantities of these crystals, with dimensions up to $\frac{3}{4}$", are now available.



The electronic properties of large single crystals of magnesia have been recognized for some time. They have, however, been difficult to make in a consistent size and quality range. Techniques developed by John Scott of the Chippawa, Ontario, section of Norton's Research & Development Dept. have made it possible to produce crystals of predetermined quality. The process also permits making crystals with definite percentages of known impurities. The "doped" crystals exhibit different electronic characteristics when the impurities consist of certain metallic transition elements.

At the present time, the major fields of application of these crystals seem to be in the field of electronics where laser and maser studies are being conducted. The Electron Spin Resonance is being studied as a function of the impurity concentration level of various metallic elements. Magnesia's refractoriness permits development for high temperature applications. Its ability to transmit infra red radiation at elevated temperatures is unsurpassed.

Crystals larger than $\frac{3}{4}$" have been produced and may be available for experimental work. Norton has generated optically clear lenses of 3" diameter from multi-crystal pieces of magnesia.

The techniques developed in the laboratory can be expanded into commercial production should the demand develop.

"Doped" magnesia crystals containing the major impurity at the approximate level indicated are experimentally available as follows: Fe_2O_3—0.05%; Co_2O_3—0.10; NiO—0.03; Cr_2O_3—0.05; Mo_2O_3—0.08; Al_2O_3 0.50; TiO_2 0.02; ZrO_2—0.03; UO_2—0.03; V_2O_5—0.09.

The infra red transmission characteristics appear to be unaffected by the presence of these doping agents at the level indicated.

For further information write to the firm.

(Continued on page 92A)

Use Your IRE Directory

The Highest Sensitivity
and the lowest noise.....

Advanced electronic research by Hitachi technicians has now resulted in the development of a superb frame grid type twin triode (6R-HH8) with excellent high gain and low noise characteristics. As a component of the tuner, the 6R-HH8 ensures an excellent picture with a remarkable degree of definition.

fig. 1 Gain characteristics







fig. 2 Noise characteristics





Frame Grid (6R-HH8)

Hitachi also produces other receiving tubes and components for television which, when used together with the new 6R-HH8, cannot fail to earn any maker a market reputation even better than he currently enjoys.



Automatic tube testing equipment

Hitachi, Ltd.
Tokyo Japan
Cable Address: "HITACHY" TOKYO

SPRAGUE
PIEZO-
ELECTRIC
CERAMIC
ELEMENTS




ELEMENTS FOR ALL APPLICATIONS AS WELL AS COMPLETE TRANSDUCER ASSEMBLIES FOR MOST APPLICATIONS, SUCH AS UNDERWATER SOUND AND VARIOUS ORDNANCE AND MISSILE DEVICES.



Sprague-developed mass production and quality-control techniques assure lowest possible cost consistent with utmost quality and reliability. Here too, complete fabrication facilities permit prompt production in a full, wide range of sizes and shapes.

Look to Sprague for today's most advanced ceramic elements — where continuing intensive research promises new material with many properties extended beyond present limits.



YOUR INQUIRIES ARE INVITED

WRITE FOR LITERATURE

SPRAGUE ELECTRIC COMPANY
235 Marshall Street, North Adams, Mass.

SPRAGUE®
THE MARK OF RELIABILITY

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 90A)

Band-Pass Filter

A new band-pass filter to provide pure sinusoidal reproduction of the fundamental input has been announced by **Circuit Dyne Corp.**, a subsidiary of **Telonic Industries, Inc.**, 480 Mermaid St., Laguna Beach, Calif.



Available in versions covering all RDB telemetering channels from 400 cps to 70,000 cps in standard bandwidths of ±7.5% and ±15%, the retriever provides 50-db minimum attenuation at and above the second harmonic of the input's lower band-edge, and the same attenuation at and below one-half the upper band-edge. Band-edge response is held to within 2 db of center frequency response and the output will contain less than 1% harmonic distortion with second harmonics of up to three times the fundamental amplitude. Therefore, an arbitrary wave-chain fed into the filter with its fundamental frequency within the pass band will produce a pure fundamental frequency sine-wave output.

Insertion loss of the filter at center frequency is less than 3 db for all channels above No. 7, less than 6 db for channels 4, 5, 6, and 7, and less than 9 db for channels 1, 2, and 3. Standard impedances are either 1000 or 10,000 ohms and input voltage is 20 v rms, 100 v peak-to-peak maximum.

Parallel connection of several different channels to the same source or load may be made with degrading the filter's electrical characteristics.

The unit, model FB-1, is housed in a hermetically sealed can equipped with a standard 7-pin miniature tube socket. Standard versions are priced at $20 to $60 depending on characteristics and quantity; delivery in 5 weeks. Special models with various frequencies, bandwidths, and impedances are available. For complete data, contact the Marketing Department.


test all your
semiconductors
with
DYNATRAN
instruments

Write for information about industry's most complete line of standard and custom designed instruments for semiconductor testing.

DYNATRAN
electronics corporation
178 HERRICKS ROAD
MINEOLA, NEW YORK
PIoneer 1-4141

Instrument Pen Uses Ink Cartridges

A new universal marking system using a smooth-writing pen, replaceable cartridge ink supply and sealed capillary system given a clean, legible record without blotting, smearing, running or dripping.



Manufactured by the **Technical Products and Instruments Div., The Esterbrook Pen Co.**, 200 Cooper St., Camden, N. J., the new pen is installed in place of present marking devices in less than 10 minutes. It provides uninterrupted writing up to months at a time, operation under environmental extremes, and substantial savings in maintenance time.

Known as the Mark-Trol universal conversion kit, it is said to replace over 90 per cent of the present marking systems now in use and is especially adapted to in-


dustrial circular chart recorders and meters.

An easily replaced plastic cartridge ink supply reduces servicing problems of manually filled systems, and eliminates the possibility of breakage present in bag and glass ink supply devices. The sealed capillary system eliminates the problems of dust, dirt, moisture, and mold which clog open bucket or trough systems. Cartridge contains a large supply of ink, extending change cycle from days to months.

The conversion kit consists of one stylus (4 sizes available), capillary tubing, universal adapter, cartridge holder, mounting bracket, pressure sensitive tape, and 4 plastic ink cartridges in a choice of 5 high-visibility ink colors. For details contact the firm.

Gregg Named by Gorham Electronics

Robert S. Gregg has been named Foundry Superintendent of **Gorham Electronics Div., Gorham Corp.,** 333 Adelaide Ave., Providence, R. I., in an announcement by George S. Blome, Division General Manager.




Gregg was most recently associated with the Aluminum Co. of America as Works Superintendent of Alcoa's Bridgeport Connecticut Foundry. Previously, he held the position of Staff Metallurgist, Senior Metallurgical Engineer, and Assistant Works Superintendent for the same company.

A graduate of Renssalaer Polytechnic Institute, where he received the degree of Bachelor of Metallurgical Engineering, Gregg has also served as Instructor of Metallurgy at the University of Bridgeport. Gorham Electronics is engaged in the field of microwave components and antenna subsystems.

Rowe Joins Tenney Aero-Space

Irwin Rowe has joined the **Aero-Space Div. of Tenney Engineering., Inc.,** Union, N. J., as a project engineer, Frank H. Gardner, Manager of the division, announced. Tenney is a major manufacturer of orbital and environmental simulation test equipment. Rowe, a 1954 graduate of the City College of New York, holds professional engineering licenses in New York and New Jersey. He is a member of the New York State Society of Professional Engineers and membership chairman of the Mid-Jersey Section of the American Society of Mechanical Engineers.



Rowe came to Tenney from Air Reduction Co., Inc. Before that he was with Western Electric Co. and with New York City in engineering capacities.

Zuck New VP for General Atronics

General Atronics Corp., One Bala Ave., Bala-Cynwyd, Pa., as part of its current expansion and diversification program, has named a new divisional vice-president. He is Ray A. Zuck, who will head the instrument division of Atronics' new Electronic Tube and Instrument Div. at Wyndmoor, Pa. The tube and Instrument Division was acquired by Atronics last month through merger of Electronic Tube Corporation into the Bala-Cynwyd, Pennsylvania, electronics firm, specialists in systems and product engineering for government, industry, and education.



Zuck, who previously directed product engineering for the Atronic Products Division at West Conshohocken, Pennsylvania, will be responsible for engineering, production and sales in his new post at the instrument division, which designs and produces oscilloscopes and oscilloscope recording cameras.

(Continued on page 94A)

Send for your FREE

1962 HEATHKIT CATALOG

The world's biggest kit catalog



- NEW KITS
- NEW STYLING
- NEW GUARANTEE
- NEW NO MONEY DOWN TERMS

Save up to 50% on Stereo Hi-Fi, Test Instruments, Amateur Radio, Marine, Educational and General Interest items that we *guarantee* you can build. Over 250 different kits illustrated with specifications, schematics and full descriptions in this new 100 page catalog. Send for your free copy today! Send your friends' names too.

HEATHKIT by Daystrom

World's Largest Manufacturer of Electronic Kits

HEATH COMPANY
Benton Harbor 4, Michigan


Please send FREE 1962 Heathkit Catalog

NAME

ADDRESS

CITY ZONE STATE

PRECISE, RELIABLE POWER SUPPLIES IN A WIDE CHOICE OF OUTPUT RANGES



SM GROUP

Optional 0.1% or 0.01% regulation:

Three rack sizes: 8¾" H, 5¼" H, and 3½" H. Impervious to operational damage: circuit protection is an inherent function of input transformer and regulator characteristics.

3½" PANEL HEIGHT

0.1% REGULATION MODELS	DC OUTPUT RANGE VOLTS	AMPS	0.01% REGULATION MODELS
SM 14-7M	0-14	0-7	SM 14-7MX
SM 36-5M	0-36	0-5	SM 36-15MX
SM 75-2M	0-75	0-2	SM 75-2MX
SM 160-1M	0-160	0-1	SM 160-1MX
SM 325-0.5M	0-325	0-0.5	SM 325-0.5MX

5¼" PANEL HEIGHT

SM 14-15M	0-14	0-15	SM 14-15MX
SM 36-10M	0-36	0-10	SM 36-10MX
SM 75-5M	0-75	0-5	SM 75-5MX
SM 160-2M	0-160	0-2	SM 160-2MX
SM 325-1M	0-325	0-1	SM 325-1MX

8¾" PANEL HEIGHT

SM 14-30M	0-14	0-30	SM 14-30MX
SM 36-15M	0-36	0-15	SM 36-5MX
SM 75-8M	0-75	0-8	SM 75-8MX
SM 160-4M	0-160	0-4	SM 160-4MX
SM 325-2M	0-325	0-2	SM 325-2MX

FOR COMPLETE SPECIFICATIONS ON MORE THAN 175 STANDARD MODEL POWER SUPPLIES, SEND FOR KEPCO CATALOG B-611.

kepco inc.

131-42 SANFORD AVENUE

FLUSHING 52, N. Y.

IN 1-7000 • TWX #NY4-5196

Engineers who know
–SPECIFY
Q-max*
A-27
SUPERFINE
LOW-LOSS RF LACQUER

• Q-max, an extremely low loss dielectric impregnating and coating composition, is formulated specifically for application to VHF and UHF components. It penetrates deeply, seals out moisture, provides a surface finish, imparts rigidity and promotes stability of the electrical constants of high frequency circuits. Its effect upon the "Q" of RF windings is practically negligible.

• Q-max applies easily by dipping or brushing, dries quickly, adheres well; meets most temperature requirements. Q-max is industry's standard RF lacquer. Engineers who know specify Q-max! Write for new catalog.

*Registered Trademark

Q-max Corporation
MARLBORO • NEW JERSEY
Telephone: HOpkins 2-3636


NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 93A)

Interstage Delay Module

Navigation Computer Corp., Valley Forge Industrial Park, Norristown, Pa. has developed the Model M11 Interstage Delay Module. Navcor manufacturers a complete line of digital logic modules and digital systems.



The Interstage Delay Module is used with the Model M10 One-Megacycle Flip-Flop Module. It has five inductive delay circuits which provide a fixed delay of 0.75 microsecond for each interstage carry pulse from the Model M10. It also has OR gates and AND gates for reading information into the flip-flops in parallel.

The M Series Megacycle Modules are completely compatible with Navcor 300 Series Modules. You can build entire high-speed systems with M Series Modules, or you can combine them with 300 Series Modules to build systems which use high-speed circuitry only where necessary.

Transistor Heat Dissipator

A transistor heat dissipator for printed circuit board applications has been announced by the **Thermalloy Co.,** of 2130 Irving Blvd., Dallas, Texas. Known as the #2210, this is designed to fit all transistors in the TO-5, 9 case styles. A design feature permits use of the #2210 with case sizes made by all manufacturers and eliminates the need to match the dissipator to the individual diameter of the transistor case.



The "Positive Contact" feature provides the optimum heat path between the transistor and dissipator. Tightening the gland nut firmly clamps both sides of the transistor weld flange, the point of maximum heat. Heat is then conducted to the fin area where it is removed by either natural conduction or forced air cooling. Low in price, the 02210 sells for 22¢ each in production quantities. These new dissipators are available now from stock.

Thermolloy Company was organized in 1958 and produces a complete line of finned and stud mounted heat sinks and dissipators for transistors.

General Purpose Integrator

Texas Research and Electronic Corp., Meadows Building, Dallas, Texas, introduced a General Purpose Integrator, designated the GPI-100. This instrument utilizes a solion tetrode as the integrating element. It is battery-powered and portable, weighing 5½ pounds and measuring 6½" ×8"×8". Accurate to 1%, the GPI-100 has an input impedance of 10 K, a frequency response from dc to kc, and accepts inputs to 1 volt. The integral is read out on a 1% meter with both a 100 volt-second and 1000 volt-second range. Optional features include an input amplifier, time averaging and digital readout. Price $475. Availability 30 days.

(Continued on page 98A)

CPO-1


CONTROLLED PRECISION OSCILLATOR

AN/URA-31


TMC Model CPO-1 (AN/URA-31) is a precision signal generator tunable from 1.75 to 33.75 megacycles in 100 cycle steps with an overall stability and accuracy of 1 part in 10^8 per day.

The CPO-1 is used in laboratories and production facilities to provide precise RF frequencies. It is also used operationally as the control oscillator in a transmitter or receiver to create a highly stable transmission system.

For additional information about the CPO-1 and other test equipment, please contact



The Test Equipment Division Of
THE TECHNICAL MATERIEL CORPORATION
World Wide Suppliers of Electronic Communications Equipment
and Subsidiaries MAMARONECK, NEW YORK
OTTAWA, CANADA • ALEXANDRIA, VIRGINIA • GARLAND, TEXAS • LA MESA, CALIFORNIA • POMPANO BEACH, FLORIDA



If protective devices fail to protect, costly burnouts may result. Or, if they open needlessly, equipment is put out-of-service. In either case, users may blame the trouble on the equipment and not on the faulty protective device.


To guard against this happening to your equipment, specify BUSS and FUSETRON fuses. Each and every fuse is tested in a sensitive electronic device that automatically rejects any fuse not correctly calibrated, properly constructed and right in all physical dimensions.

Should you have a special problem in electrical protection, where you might be in doubt as to the proper fuse to use, BUSS places at your service the facilities of the world's largest fuse research laboratory and its staff of engineers.

To get full data for your files, write for the BUSS bulletin on small dimension fuses and fuseholders. Form SFB.

1261

BUSSMANN MFG. DIVISION, *McGraw-Edison Co.,* **UNIVERSITY AT JEFFERSON, ST. LOUIS 7, MO.**



ENERGY CONVERSION

controlled by leadership

This is a portrait of experienced hands. Thirty years study in the art of controlling electron behavior in electron devices *under all conditions* gives RCA outstanding experience. In the new areas of energy conversion—Thermoelectrics, Solar Cells, and Thermionics—it is natural to consult this reigning leadership. On the one hand, it can implement your own research and development. On the other, it can advance the state of the art.

Write: RCA Electron Tube Division,
Space Components, Lancaster, Pa.

RCA®

The Most Trusted Name in Electronics

WHAT'S HAPPENING IN LONDON?



Model of the 500-foot television and radio-telephony tower now rising over Central London for the General Post Office.

Follow progress across the Atlantic through WIRELESS WORLD — Britain's leading magazine for electronics, radio and television, with by far the largest readership among British scientists and technologists. Regular contents include authoritative articles on theory and practice, circuit and equipment design, scientific and manufacturing applications; reviews of new products; reports of conferences and exhibitions; industrial and professional news.

Wireless World
ELECTRONICS · RADIO · TELEVISION

ELECTRONIC TECHNOLOGY is Britain's foremost authority on advanced developments in radio, radar, television and all forms of telecommunications. Original papers, both theoretical and practical, are contributed by leading scientists and technologists. For all who must have the latest information on British and European research, ELECTRONIC TECHNOLOGY is an indispensable medium.

Electronic technology

MAIL THIS COUPON TODAY

TO: BRITISH PUBLICATIONS INC., 30 EAST 60TH STREET, NEW YORK 22, N.Y.

Please enter my/our subscription to WIRELESS WORLD/ELECTRONIC TECHNOLOGY for:—

- ☐ WIRELESS WORLD 12 MONTHS (12 ISSUES) ... $5.50
- ☐ ELECTRONIC TECHNOLOGY 12 MONTHS (12 ISSUES) ... $9.50
- ☐ BILL ME LATER
- ☐ WIRELESS WORLD 36 MONTHS (36 ISSUES)...$11.00 (A SAVING OF $5.50)
- ☐ ELECTRONIC TECHNOLOGY 36 MONTHS (36 ISSUES)...$19.00 (A SAVING OF $9.50)
- ☐ CHECK/M.O. FOR $..... ENCLOSED

NAME .....

ADDRESS .....

.....

CITY .....

ZONE..... STATE.....

PRO.IRE

CRITICAL MOMENTS! LONG before the SCRAMBLE


a successful mission begins on the ground

Critical moments pass during the pre-flight check of the all-weather F-105D Thunderchief, and its equipment. Of vital importance are the "eyes" of the F-105D . . . Nasarr (North American Search and Range Radar). The ground support equipment which checks out the receivers in Nassarr includes **STODDART COAXIAL TURRET ATTENUATORS.**

Stoddart wide-range attenuators have been selected for their efficiency and dependability in this and other applications which require:

- Ruggedness
- Close tolerances
- Low VSWR
- Light weight
- Small size
- Rapid changing of db values
- Easy "Pull-Turn-Push" operation
- Guaranteed reliability

Stoddart attenuators are precision made — competitively priced.



Prompt delivery

Send for Attenuator Catalog AT-4

STODDART
AIRCRAFT RADIO CO., INC.


6644 Santa Monica Blvd., Hollywood 38, Calif.; HOllywood 4-9292
serving 33 countries in Radio Interference control

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 94A)

Chopper Input Transformer




A new line of high impedance chopper input transformers with balanced windings and magnetic and electrostatic shielding is now available from **James Electronics, Inc.,** 4050 No. Rockwell St., Chicago 18, Ill. Specially designed leads simplify plugging or soldering into p.c. boards. Transformers are available in step-up and step-down configurations for use in transistor, Nuvistor and tube circuitry. Can be used with solid state, mechanical and photosensitive choppers. Available in miniature ($1\frac{1}{4}$" seated height) and microminiature ($\frac{3}{4}$" seated height) sizes. Transformers will meet industrial and military (MIL-T-27A) specifications.

Prices range from $8.75 to $18.00 each with delivery from stock for sample quantities.

Solar Cells

Thumbnail-sized solar cells—frequently used in space vehicles to transform light into electrical energy—are being used to generate impulses in a new commercial electronic computer system developed by **Equipment & Systems Div., Burroughs Corp.,** Detroit 32, Mich.

The cells were adapted to supply power for reading punched cards in the Burroughs B200 computer series introduced last month.




While solar cells in space vehicles use the sun as their light source, their counterparts in computers perform the energy conversion function in response to artificial light.


In the computer's card reading unit, a row of lamps are positioned opposite a series of solar cells. When a card passes between the lamps and the cells, light passes to the solar cells through the punched out

(Continued on page 100A)

FOR DIRECTING, CONTROLLING, AND MEASURING RF ENERGY... DIELECTRIC'S PRODUCTS SATISFY EVERY PERFORMANCE NEED

FILTERS, DIPLEXERS & DUPLEXERS







. . . for all applications, waveguide or coaxial. In addition to its standard line of single- and double-tuned coaxial resonators which may be combined in many ways, *Dielectric* designs special networks for any power level, low to very high.

Illustrated is a network to isolate 20 kw commands to and 0.002 microvolt signals from a space vehicle, simultaneously. Built for Space Technology Laboratories, Inc., one of these giants is installed in the giant Jodrell Bank radio telescope. Also shown is a miniaturized balanced duplexer handling 10 kw average and weighing only five pounds.

For further information, specify proposed applications.

DIRECTIONAL COUPLERS






. . . provide for coupling external measuring and monitoring equipment to coaxial and waveguide r-f transmission systems. The range of coupling ratio is roughly 30 to 80 db, depending on model and frequencies. Directivity of standard models is $\geq$ 30 db, but $\geq$ 40 db can be supplied. Output source impedance is 50 ohms. Maximum power output is 4 watts for 3⅛" and larger coaxial models, 1 watt for smaller lines; 2 watts for 1½" x 3" and larger waveguide, 1 watt for smaller guides.

Request Bulletin No 61-5

PHASE SHIFTERS




. . . for any line size and impedance, and any degree of sophistication. Of particular interest is *Dielectric's* line of common-case, coaxial-line phase shifters which eliminate sliding joints in the outer conductor. Power handling capacity and life are both enhanced.

Phase shifters are available in manual and remote-control models, with or without provision for remote position indicating devices. All are characterized by low VSWR and wow, high power capability, and variable, linear phase shift.

Request Bulletin No. 61-7



RIGID TRANSMISSION LINE




. . . in lengths up to 30 feet, copper or aluminum outer conductors. Standard sizes are ⅞, 1⅝, 3⅛, 6⅛, 9$\frac{3}{16}$ inches in all standard impedances from 25 to 200 ohms. Special sizes are available such as 9, 10, 12, 16 inches. Two basic styles: Quick-Clamp Type 40 featuring flange connections that swivel to any rotational angle, quick positive assembly by tightening only two bolts, and piloted flanges eliminating centering rings; or when specifications stipulate, the EIA (RETMA) Type 70 bolted-flange lines offering the same electrical characteristics.

Request Catalog No. 61-4

SLOTTED LINES & DIFFERENTIAL PROBES

. . . for measuring VSWR to 1.002 accuracy, the first and only major breakthrough in slotted-line measurement techniques. Improves resolution up to ten times that obtained with E-field probes. Available in 3⅛", 6⅛", and 9$\frac{3}{16}$" 50-ohm line sizes, other sizes and impedance on special order. Adapters and reducers to other line sizes can be supplied.

Request Bulletin No. 61-8



For applications in the public entertainment field, DIELECTRIC products are available from the Radio Corporation of America. For all other applications, contact DIELECTRIC directly.

Areas of DIELECTRIC capability in coaxial, waveguide and open wire techniques . . .
TRANSMISSION LINE & COMPONENTS • NETWORKS
SWITCHES • TEST EQUIPMENT • R&D ENGINEERING

dial *DIELECTRIC for solutions to communications problems*

DIELECTRIC PRODUCTS ENGINEERING CO., INC.


RAYMOND, MAINE Tel. No. OL 5-4555

now...find, identify, analyze noise & interference 1kc—25mc FAST!

dependable CERTIFIED SPECIFICATIONS for accurate data

...just one of the many ways to use


PANORAMIC's economical SPA-3/25 SPECTRUM ANALYZER



Widely used for high-speed location, identification and analysis of random and discrete signals, the SPA-3/25 automatically separates and measure the frequency and amplitude of signals in spectrum segments up to 3mc wide, selectable anywhere between 1 kc and 25mc (usable down to 200 cps). Direct readouts of frequency distributions and amplitudes of signals are provided respectively on calibrated X and Y axes of a 5" long-persistence CRT. The SPA-3/25 samples the spectrum at a 1-60 cps rate.

PANORAMIC presentation of the Model SPA-3/25

1. permits quick location of signals, minimizes chances of missing weak signals or holes in the spectrum
2. speeds up measurements by eliminating tedious point-by-point plots
3. enables fast, reliable detection of comparatively low level discrete signals present in random spectra through use of adjustable narrow IF bandwidths and correlation techniques
4. allows identification and subsequent analysis of dynamic characteristics of modulated signals and noise.



Noise spectrum analysis using internal video smoothing filter presents noise envelope average versus frequency in readily appreciated form. Internal marker pips are 500kc apart.

SPECIFICATIONS:

Frequency Range: 1 kc—25mc in 2 bands
Sweepwidth: Variable, calibrated from 0 to 3mc
Center Frequency: Variable, calibrated from 0 to 23.5mc
Markers: Crystal controlled, 500kc and harmonics to 25mc
Resolution: Variable, 200 cps to 30 kc
Sweep Rate: Variable, 1 cps to 60 cps
Amplitude Scales: 20 db linear, 40 db log, 10 db square law (power)
High Sensitivity: 20 μv full scale deflection
Attenuator: 100 db calibrated
Response Flatness: ± 10% or ± 1 db
Input Impedance: 72 ohms. High impedance probe-PRB-1—Optional

The SPA-3/25's great flexibility makes it a valuable tool in a wide range of applications. Write, wire or phone NOW for detailed specifications and NEW CATALOG DIGEST.

Put your name on our mailing list for "THE PANORAMIC ANALYZER," featuring application data.

the pioneer is the leader

Panoramic electronics, inc.

Formerly Panoramic Radio Products, Inc

522 So. Fulton Avenue, Mount Vernon, N.Y.
Phone: OWens 9-4600. TWX: MT-V-NY-5229
Cables: Panoramic, Mount Vernon, N.Y. State

WE CATALOG IN eem electronic engineers master
Sec. 2900

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 98A)

areas in the card, causing electrons within the cell to jump across an intracellular junction.

This electron activity generates energy in the form of electrical voltage and current. Solar cells, because they are completely self-sufficient power sources, eliminate the need for companion devices to generate electrical energy.

This results in more compact design than is possible with conventional methods, in which photodiodes are used in tandem with additional components.

Low Pressure Gage


The Model 8007, a small, rugged, sensitive low pressure gage, was developed by **Aero Mechanism, Inc.,** 7750 Burnet Ave., Van Nuys, Calif., for wide application in ground support and flight equipment and many critical commercial installations.



Exceptional sensitivity normally found in larger units is achieved through their specially designed and built noncorrosive sensing diaphragm. All seals are metallic. Range 0 to 40″ of water; accuracy and repeatability ±1″ of water; operating temperature −65 to 185°F; hysteresis 0.5″ water; shock and vibration resistance per MIL-E-5272C; diameter 2″; length 3.9″; weight 12 oz. Contact the firm directly for details.


Thin-Walled Coil Bobbin

The photograph shows a one-piece laminated glass cloth coil bobbin, the same bobbin after winding and sealing, and the vertical gyro of which the wound unit is a part.



This bobbin has an overall length of only 0.698″, and I.D. of 0.218″ and a wall thickness of 0.020″. To one end of the bob-


(Continued on page 104A)



STANDARD

33 KILOGAUSS IN A 12″ MAGNET

Fields up to 33 kilogauss, (0.7 inch gap, 1″ diameter) are attainable in the standard Model L-128 Electromagnet. This performance is achieved at only 5 KW of power by the use of special alloy pole caps. Even higher field strengths are possible in smaller working gaps. Send for complete details.



Harvey-Wells Corporation, specialists in the field of high precision electromagnets, is rapidly expanding its engineering and field service staffs in order to better serve our many customers.

Examples of recent custom magnets designed and fabricated by Harvey-Wells Corporation include: a magneto-hydro-dynamic, (MHD) magnet weighing 58,000 lbs; an iron-clad high field solenoid generating in excess of 50,000 gauss over a 2 inch diameter with approximately 200 Kilowatts of power; a 90°, 25 inch radius, magnetic spectrometer magnet of high precision; a 7 INCH GAP WIDTH, 20 KG magnet with an 8 inch diameter; A large precision electromagnet optimumly coned down to a 15 inch diameter to generate in excess of 30 kilogauss across a 1 inch gap.

CUSTOM

To meet the power requirements of these special magnets, a 20 kilowatt power supply with a stability rating of 1 part in 10^5 will soon be added to our standard product line. Custom engineered power supplies as high as 250 KW, with slightly reduced stabilities are also presently being designed.

Harvey-Wells Corporation is actively expanding their group of specialists in magnet optics and invites inquiries on beam handling systems as well as other custom magnets or magnet system requirements. Please use the coupon below for further information.

HARVEY-WELLS CORPORATION
Magnetics Division, 43 Kendall St., Framingham, Mass.

I am interested in _____

NAME _____

POSITION _____


COMPANY _____

ADDRESS _____


CITY _____

HARVEY-WELLS CORPORATION P.O. BOX 189 FRAMINGHAM, MASSACHUSETTS TR 2-4365

VERY NARROW TO VERY WIDE



SWEEP WIDTHS*



...ALL IN ONE INSTRUMENT

NEW JERROLD® 900B

SWEEP SIGNAL GENERATOR

Here's the last word in versatility and precision, the ultimate instrument for all your IF-VHF-UHF requirements. The new Jerrold 900B offers unusual stability in sweep widths as narrow as 10 kc and as wide as 400 mc. Frequency range 500 kc to 1200 mc.

$1980.00 *f.o.b. Philadelphia***

- **Built-in crystal-controlled harmonic markers at 1, 10, and 100mc intervals.**
- **Each marker output individually controls from front panel.**
- **Built-in variable-gain dc-coupled scope preamplifier with 200X gain.**
- **Built-in precision attenuator from zero to 50db in 10db steps.**
- **Accurately calibrated frequency dial.**
- **High-level metered output.**

Write for complete technical data.

*Illustration of scope at left shows typical communications receiver response 4 kc bandwidth at 7 mc. Illustration at right shows typical distributed amplifier response 2-220 mc.


***Prices and specifications subject to change without notice.*

JERROLD **ELECTRONICS CORPORATION**
Industrial Products Division, Dept. ITE-123.
The Jerrold Building, Philadelphia 32, Pa.

Jerrold Electronics (Canada) Ltd., Toronto •
Export Representative: Rocke International, New York 16, N.Y.

- COMPLETELY TRANSISTORIZED
- ECONOMICAL • COMPACT
- NO MAINTENANCE
- NO ADJUSTMENTS
- NO CALIBRATION

SEMI-CONDUCTOR RELAY



PROVEN!

The SCR 601 Relay is a high-speed, solid-state switching mechanism designed for signalling applications. PROVIDES complete input, output and ground circuit isolation. Control circuit is a floating 2-terminal transformer winding. Output contacts are floating SEMI-CONDUCTOR CIRCUITS that are magnetically switched by current flow in the input winding. Power for positive control of the switching circuits is provided by an integral dc-to-dc converter whose AC circuits are opened and closed by input-coil current. Required power is equal to bias power employed in mechanical signalling relays.

The model illustrated is a direct replacement for the WE-255A. Other models available for replacing AE202, 3, 4A Series, Sigma 72 or similar signalling relays.


A variety of mechanical configurations and sizes is available in polarized and non-polarized relays. Less than $100.00 in small quantities. Large quantities at greater discounts.

For complete information write Rixon for Engineering Bulletin No. 77 and Product Bulletin SCR601.

RIXON
ELECTRONICS, INC.
2121 Industrial Parkway
Montgomery Industrial Park
Silver Spring, Md. MAyfair 2-2121

Please clip coupon below and use right now.

WHO MAKES POWER TRANSISTORS LIKE DELCO RADIO MAKES POWER TRANSISTORS?



nobody

You see, Delco has made more power transistors than anybody else around. We've made them in all sizes. Diamond and round base. Industrial and military. In a wide variety of parameters. For endless applications. With high reliability. ■ Sometime—perhaps today—you may be looking for a transistor that's not in our catalog . . . or any catalog. You may need samples or production quantities. Chances are we already have it, and at a price you'll like. ■ Clip the coupon, fill in the information and mail to our nearest office, listed below. Your inquiry will be processed immediately.

GENTLEMEN: I need a power transistor that will meet these specifications.

Collector diode voltage_____

Emitter diode voltage_____

Emitter current (continuous)_____

Base voltage_____

Saturation voltage_____

Thermal resistance (junction to case)_____

Thermal capacity for pulses in the 1 to 10 millisecond range_____

Collector to emitter voltage_____

Estimated quantity required_____

My name_____

Company_____

Street address_____

City_____ Zone_____ State_____

Union, New Jersey
324 Chestnut Street
MUrdock 7-3770

Santa Monica, California
726 Santa Monica Blvd.
UPton 0-8807

Chicago, Illinois
5750 West 51st Street
POrtsmouth 7-3500

Detroit, Michigan
57 Harper Avenue
TRinity 3-6560

Syracuse, New York
1054 James Street
GRanite 2-2668


Division of General Motors
Kokomo, Indiana


DELCO RADIO

Give your products
MORE RELIABILITY and
BETTER PERFORMANCE with
FREED
QUALITY
IN STOCK FOR IMMEDIATE DELIVERY

CONSTANT VOLTAGE TRANSFORMERS.

Meets Military Specifications
No Tubes
No Moving Parts
Accurate Regulations
Fast Response
Fully Automatic


MIL Type


Commercial Type


Here at last is a hermetically sealed magnetic voltage regulator that will provide constant output voltage regardless of line and/or load changes.


SUPPLIED EITHER MIL. OR COMMERCIAL				
CAT. #	INPUT VOLT.	LINE FREQ.	OUTPUT VOLT.	OUTPUT VA.
MCV- 620L	95-130 v	60 cps.	115	20
MCV- 670L	95-130 v	60 cps.	115	70
MCV-6130L	95-130 v	60 cps.	115	130
MCV- 670F	95-130 v	60 cps.	6.4	70
MCV-6130F	95-130 v	60 cps.	6.4	130
MCV- 420F	95-130 v	400 cps.	6.4	20

MAGNETIC AMPLIFIERS

- Hermetically Sealed To MIL Specifications
- No Tubes
- Direct Operation from Line Voltage
- Fast Response
- Long Life Trouble Free Operation
- Phase Reversible Output

Power Gain 2×10^8


Transistor Preamp. MAT-1 Wt. 10 oz.
Mag. Amp. MAF-5 Wt. 18 oz.
Motor



PARTIAL LISTING ONLY
WRITE FOR FURTHER INFORMATION ON THESE UNITS OR SPECIAL DESIGNS.
Send for NEW 48 page transformer catalog. Also ask for complete laboratory test instrument catalog.

FREED TRANSFORMER CO., INC.
1720 Weirfield St., Brooklyn (Ridgewood) 27, N. Y.

NEWS New Products

(Continued from page 100A)

bin is laminated a metal washer. An extension of the fiberglass bobbin's core wall 0.010" thick protrudes through the washer and insulates its I.D. To improve adhesion, the washer has tiny countersunk holes through which the resin flows and sets up in the shape of tiny rivets.

The bobbin is wound with 6,500 turns of #42 wire and is encapsulated with a modified epoxy resin. The coil is used in the solenoid for erecting the gyro which is part of the PB 20 autopilot system manufactured by **Eclipse-Pioneer Division of The Bendix Corp.** The washer is the point of contact for the coil spring which pushes the plunger back into position.

All wound bobbins are tested for 100,000 cycles during a ten-hour period prior to assembly in the solenoid. In the laboratory, life tests of 16,000,000 cycles have been made at the rate of 1,000 cycles per minute.

In use, the gyro is covered by warranty for 1,000 hours of operation, or approximately 1,000,000 cycles.

The bobbin is manufactured by a technique developed by **Silicone Insulation, Inc.,** Bronx 61, N. Y. The process involves the making of a preform under controlled heat and pressure in a matched metal mold. After curing in the mold and being removed, the bobbin is ground to size.

This type of coil bobbin is used because of its mechanical strength, the thin wall required and its electrical properties. It is full Class "H" insulation. One-piece glass-cloth bobbins are being made in round and rectangular shapes and range upward in size from tiny, close-tolerance parts like the one illustrated. The bobbins may have any number of flanges, with or without holes, slots, affixed terminals or other devices.

New Alumina Ceramics Firm


Alberox Corp., Industrial Park, New Bedford, Mass., formed earlier this year, will manufacture and sell high purity alumina ceramic shapes and ceramic-to-metal seals, serving the electrical, electronics, chemical and allied industries. The broad product line will include such items as high voltage terminal bushings, vacuum tube cavities and output windows, power cable end seals and other precision ceramic products where high strength, good shock resistance, and high dimensional, electrical and chemical stability are required.

The Board of Directors is comprised of Herman H. Frahme; William E. Coykendall, Jr., Vice President; Robert A. Barker of William A. M. Burden & Co.; Bache McE. Renshaw of Joseph Walker & Sons; and Richard E. Hart of Clark Dodge & Co.

(Continued on page 130A)

**Use Your IRE Directory—
It's valuable!**

Get the Mark Approach to
MICROWAVE
ON 6 TO 8 kmc.



If you're "going microwave", write for Bulletin 620 on significant new developments from Mark Products . . . for example:

PARABOLIC ANTENNAS with exclusive **ISOPOLARIZED FEED*** . . . offering important electrical features along with exceptional mechanical stability and lightweight construction, provided by heliarc welded back frame and feed supports.

NEW! SIMPLE POLARIZATION ADJUSTMENT . . . ISOPOLARIZED FEED allows for 360 degrees of continuous polarization adjustment without rotating dish or feed horn!

NEW! DUAL POLARIZED ADAPTER . . . adapts the standard MARK Parabolas to dual polarization at any time in the field.

EASE OF INSTALLATION . . . flexible mounting with horizontal roof mounts and vertical pipe mounts.


RELIABLE ELECTRICAL CHARACTERISTICS . . . assured by holding tight precision parts tolerances and thorough quality control at every step of the production process.

DE-ICING . . . by MARK'S Heated Radomes . . . or use MARK'S unheated radomes . . . installation stays clean either way.

*Patent Number 2,996,714

MARK also manufactures antennas for 2 Way Communications in the VHF and UHF bands . . . point to point Grid Parabolas for 450 to 2200 mcs . . . rail and mobile units.

Mark Products makes the most rugged parabolic antenna structure!



MARK offers complete engineering and antenna research service

MARK PRODUCTS CO.

Dept. IE-12 • 5439 W. Fargo Ave. • ORchard 5-1500 • Skokie, Ill.

Positions Open

The following positions of interest to IRE members have been reported as open. Apply in writing, addressing reply to company mentioned or to Box No. . . .

The Institute reserves the right to refuse any announcement without giving a reason for the refusal.

Proceedings of the IRE
1 East 79th St., New York 21, N.Y.

PROFESSORS

The Air Force Institute of Technology, Wright Patterson Air Force Base, Ohio, has a vacancy in the Department of Mathematics. Most of the work is at advanced undergraduate and graduate level. One quarter out of four free of teaching duties for research or other academic pursuits, plus vacation. Working conditions comparable to those in leading universities. Employment will be effected in accordance with Civil Service regulations. Rank and salary will depend upon qualifications of applicant and may be anywhere between assistant professor, GS-11, $7,560.00 and full professor, GS-14, $12,210.00. Applications should be made on Standard Form 57, available at any Post Office or by letter to Head of the Department of Mathematics, Institute of Technology, Wright Patterson AF Base, Ohio.

GRADUATE ASSISTANTSHIPS

Research and Graduate Assistantships in Instrumental Sciences leading to a M.S. degree in Instrumental Sciences. Engineering and Physics majors with strong background in instrumentation. Course work in fundamental principles and theory of basic instrumentation and process control. Research work in many fields such as high vacuum, electron and ion generation, mass spectrometry and gas chromatography, and process instrumentation. Stipend $2100 to $2400 for twelve months. Send transcript and vitae to: Head, Electronics and Instrumentation, University of Arkansas, Graduate Institute of Technology, P.O. Box 3017, Little Rock, Arkansas.

SOLID STATE RESEARCH

Opening for Ph.D. in physical chemistry, physics or metallurgy. We are producers of highest quality silicon and one of our chief research interests in this field is vapor-deposited single-crystal layers. We are interested in having as accurate and comprehensive information as possible on such structures and on their possible application to devices. We are already engaged in electrical and optical studies and are most desirous of deepening and broadening these studies. A sufficiently qualified applicant would have ample opportunity for choosing and exploiting directions as well as specific problems of interest. Other fields of research in semiconductors are gallium arsenide, germanium and thermoelectric materials. Reply in confidence to Box 2060.

SENIOR MATHEMATICIAN—STATISTICIAN

Supervisory position for a Senior Mathematician experienced in the use of Gaussian, Exponential, Gamma and Weibull Distributions for reliability predictions on electronic circuitry. Apply to Melpar, Inc., 3013 Arlington Blvd., Falls Church, Va.

MEDICAL ELECTRONICS

A rapidly expanding medical school requires an engineer to head an electronics development service. A graduate degree with an interest in

(Continued on page 106A)

expansion at ***VITRO*** *creates new career positions in*

ADVANCED DEVELOPMENT
•
SYSTEMS
•
DESIGN

. . . and an unusual opportunity for pleasant and rewarding living

If you are a talented engineer or physicist, it will pay you to check one of the new and permanent career positions at Vitro Electronics.


The assignments are exciting and include state-of-the-art level work. You have to be creative, capable of developing original concepts, and you should have experience in one of the following areas: design of receivers, transmitters and associated equipment in the RF and microwave fields, particularly 30 - 3000 m.c. regions; solid state circuitry and printed circuit applications; parametric and other low noise preamplifiers; spectrum display equipment, signal generators, microwave components, wide band IF and Video amplifiers and TV circuitry, and phase measuring equipment.

Our facilities are located in Silver Spring, Maryland, a residential suburb of Washington, D. C., affording you a choice of country, suburban or city living. Public schools are excellent and five nearby universities offer graduate courses. The cultural pleasures of the Nation's Capital are just minutes away, and the countryside provides every opportunity for sports, from mountain climbing to boating and fishing on the Chesapeake Bay.

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

Address your inquiry to:
Mr. D. R. Statter, Director of Industrial Relations

Vitro ELECTRONICS
A Division of the Vitro Corporation of America
PRODUCERS OF NEMS-CLARKE EQUIPMENT
919 JESUP-BLAIR DRIVE, SILVER SPRING, MD.
(Suburb of Washington, D.C.)



The

INSTRUMENTATION LABORATORY of MIT

with a staff of over 1000 under the direction of Dr. C. Stark Draper, is engaged in the conception and perfection of fully automatic flight and guidance control systems for missiles and space vehicles.

The Laboratories achievements are numerous. They include the **POLARIS** inertial guidance system for the Navy; **SINS,** The Ship Inertial Navigation System and basic theory, components and systems for the Air Force's **TITAN** and the earlier **THOR** missile. At the present time, studies for **NASA** are being carried out, including the development of the guidance and navigation system for the Moon Space **PROJECT APOLLO.**

The increased responsibilities of the Laboratory have created several rewarding assignments for work in research and development.

Graduate courses may be taken for credit while earning full pay.

Areas of current interest include:

- ANALYSIS OF SYSTEMS AND COMPONENTS
- HIGH PERFORMANCE SERVOMECHANISMS
- POWER SUPPLIES AND MAGNETIC AMPLIFIERS
- DIGITAL AND ANALOG COMPUTERS
- ELECTRO-MECHANICAL COMPONENTS
- TRANSISTOR CIRCUITRY AND PULSE CIRCUITRY
- RESEARCH, DESIGN AND EVALUATION OF GYROSCOPE INSTRUMENTS
- COMPUTER PROGRAMMING AND SIMULATOR STUDIES
- OPTICS, ASTRONAUTICS AND MANY OTHER AREAS

CALL OR WRITE HOWARD A. MILLER, PERSONNEL OFFICER

INSTRUMENTATION LABORATORY

MASSACHUSETTS INSTITUTE OF TECHNOLOGY

68 ALBANY STREET BLD. 12A

CAMBRIDGE 39, MASS.

UNiversity 4-6900, EXT. 3544

An equal opportunity employer.

Positions Open

(Continued from page 105A)

the bio-medical field or a B.S. degree with considerable applicable experience is required. Contact Dr. John Schuder, University of Missouri, Medical Center, Columbia, Missouri.

COGNITIVE SYSTEMS SCIENTIST

A staff opening exists in the Computer Research Department of the Cornell Aeronautical Laboratory which will permit a resourceful, imaginative scientist to participate in research programs on cognitive, self-organizing and adaptive systems.

The several active and expanding programs now underway were developed from—but are not limited in scope by—the earlier conception and development of perceptrons at this not-for-profit research organization. Current analytical and experimental work includes pattern recognition problems such as those encountered in photo interpretation, target classification, and speech recognition.

In the past we have found that electrical engineers, mathematicians, and psychologists with training and/or experience in such areas as information theory, statistics, adaptive control systems, advanced programming, automata theory, brain models and learning mechanisms—frequently possess suitable capabilities and interests. We invite your application. Salaries are competitive with offerings of private industry, working conditions are excellent, and outstanding talent is appropriately rewarded. Contact A. P. Rentschler, Cornell Aeronautical Laboratory, Inc., 4455 Genesee Street, Buffalo 21, N.Y.

CREATIVE ENGINEER

Nation's leading manufacturer of high speed solid state counting, timing and frequency measuring instrumentation seeks imaginative young engineer to design and develop digital and pulse instruments and systems. Outstanding opportunity for technical growth and advancement.

One to two years' experience in transistor application of digital and pulse techniques plus BSEE or equivalent are required. Send resume to: Personnel Manager, Computer Measurements Company, 12970 Bradley Avenue, San Fernando, California.

PRODUCTION MANAGER—ELECTRONIC EQUIPMENT

Require a man with at least 10 years experience in direct management of male and female assemblers, wiremen and testers, working on both military and commercial electronic equipment.

Must be familiar with military specifications for workmanship and know cost cutting techniques. Should be experienced in estimating labor hours and maintaining budgeted hours via strict production control.

This man will run the entire wiring and assembly operation (up to 100 people) and will be a part of the top management team. Salary open. Contact George W. Fellendorf, President, Planetronics, Inc., Easton, Pennsylvania.


TECHNICAL WRITER

Technical Writer to work with scientific, engineering and public relations personnel. BS in engineering or physics. Nuclear experience desirable. Send resume to Mgr. of Employment, General Atomic Div., General Dynamics Corp., P.O. Box 608, San Diego 12, Calif.

(Continued on page 113A)

ENGINEERS & SCIENTISTS:

One way to measure the challenge of a long-term assignment: Examine the program's mission.



MORE THAN 27 MILLION CUBIC MILES OF AIRSPACE MANAGEMENT!*

If you have been seeking professional challenge of this magnitude, and your experience is in any of the areas listed, we urge you to get in touch with us.

- COMMUNICATION SYSTEMS
- OPERATIONS ANALYSIS
- SYSTEM EQUIPMENT ANALYSIS
- WEAPONS INTEGRATION
- APPLIED MATHEMATICS
- TELECOMMUNICATIONS SYSTEMS DESIGN
- PROGRAMMING ANALYSIS
- ENGINEERING WRITING
- ANTENNA & MICROWAVE COMPONENTS
- EQUIPMENT EVALUATION
- INFORMATION PROCESSING & DISPLAY SYSTEMS

*Using the hypothetical example of a 412-L system covering Australia alone, a rough approximation of the airspace to be managed may be arrived at by multiplying the continent's area (roughly, 2.97 million miles) by the 9.4 miles of altitude within easy reach of today's aircraft.

In concept, 412-L is an electronic air weapons control system providing *universal* air space management – outside the continental United States.

It will consist of a closely coordinated network of data acquisition stations, data processing and display centers and weapon bases. It provides the tools for effective and flexible airspace management – continent-wide or in single-point defense. Vital detection and tracking information is supplied automatically to human decision-makers within seconds. Effective direction of both manned and unmanned weapons, including return of manned aircraft to base, is a system function.

Managing the over-all 412-L program is the task of General Electric's weapon system management team, under the direction of the U.S. Air Force's Electronic Supporting System Project Office. The Air Force and G.E. direct the 412-L program from system concept and development, through the buying, producing, installation and checkout of complete operating equipments.

Write in strict confidence to Mr. P. W. Christos, Div. 53-ML, DEFENSE SYSTEMS DEPARTMENT, General Electric Company, Northern Lights Office Building – Syracuse, New York



DSD DEFENSE SYSTEMS DEPARTMENT
A Department of the Defense Electronics Division

An Equal Opportunity Employer

GENERAL ELECTRIC



Now's the time to get the bugs out

Once a spacecraft has been launched to the Moon or planets, there's no turning back. No time for a change in plans.

That's why reliability men are so essential at Cal Tech's Jet Propulsion Laboratory. They look for failure right up to the countdown—on the drawing boards, on the prototypes, on the spacecraft itself. They find the bugs and get rid of them.

JPL scientists and engineers like to have reliability men around. Not because their job is made easier (mostly, it's the other way around), but because they can't settle for anything less than success.


They care. They care about what's out there in space. What the Moon is made of. If there's life on other planets. They care, too, about America's role as leader in space.

Do you care? Would you care to know how your special talent might be used in JPL's world of other world exploration? Write us about yourself. We'd care to know.

JET PROPULSION LABORATORY
4804 OAK GROVE DRIVE, PASADENA, CALIFORNIA
Operated by California Institute of Technology for the National Aeronautics & Space Administration

All qualified applicants will receive consideration for employment without regard to race, creed or national origin / U. S. citizenship or current security clearance required.

Lenkurt Electric's engineers create unique telecommunications systems for industrial, telephone, and defense requirements. Working in an independent and creative atmosphere, they have every opportunity to further their formal education, live in the West's outstanding climate, and enjoy unlimited cultural pursuits. Qualified *communications engineers* are now being added to the staff in the specialized fields of:



solid state circuitry • data transmission

sales • mobile radio • data transmission

Qualified specialists in these fields should send a resume or call collect to: *E. Jack Shannahan, Employment Manager · Lenkurt Electric Co., Inc. · 1105 County Road · San Carlos, California. LY 1-8461, Ext 281*

LENKURT ELECTRIC

Subsidiary of

GENERAL TELEPHONE & ELECTRONICS

GENERAL SYSTEM

E. E. SUPERVISOR

TV or CRT DISPLAY to $18,000

Major electronics firm located in the Northeast has opening for an engineer with 10 years TV camera or CRT display design and development experience. Duties include supervision of a group of design engineers plus production engineering responsibility, project cost control, proposal writing and other related activities. Our staff is aware of this opening.

Write Box 2063, Institute of Radio Engineers, 1 East 79th St., New York 21, N.Y.

An equal opportunity employer.

The

Avco Everett Research Laboratory

A number of select positions are now available on the Research Staff for Senior Physicists (theoretical and/or experimental).

Magnetohydrodynamics, high temperature gas dynamics, re-entry physics, space technology, satellite recovery technology and electric propulsion for space flights are presently part of the stimulating research carried out at the Laboratory.

Openings exist for:

Plasma Physicists to perform research in Magnetohydrodynamics and its application to space vehicle propulsion.

Physicists to perform research in areas of radiation phenomena in shock heated gases.

If you have a graduate degree and interested in working in a technically stimulating environment with excellent facilities and experimental support write or send brief resume to:

R. E. McDonald, *Personnel Manager*

AVCO EVERETT RESEARCH LABORATORY

A DIVISION OF AVCO CORPORATION
2385 Revere Beach Parkway
Everett 49, Massachusetts

As always all qualified applicants will receive consideration for employment without regard to race, creed, color, or national origin.

ELECTRONICS ENGINEERS

YOU can Contribute Now to Many Advanced Projects in SSB Communications

Over the past several years, most of the military HF, SSB development contracts have gone to General Dynamics/Electronics. This response to the Company's broad technical competence has resulted in steady, solid growth, creating important positions for talented engineers in advanced design, development and production of mobile communications equipment. The current press of recently accelerated military procurements has further increased staff requirements in the following areas.

SYNTHESIZERS

Working knowledge of SSB techniques is preferred, but FM and AM experience with sufficient background in synthesizer-oscillators will be considered. Must be capable of leading work in advanced development and sophisticated frequency standard designs and able to conceive and develop novel and unconventional ideas.

RECEIVERS

Requires strong background in transistor circuit design and in arrangement of circuits into complete communications systems. Will be responsible for the design of advanced SSB receivers.

POWER AMPLIFIERS

6 to 10 years electronics experience required with emphasis on high power vacuum tube amplifier design. Experience in SSB linear amplifier techniques is desirable.

RELIABILITY

To make reliability analyses of circuits and components for military electronic equipment. Requires BSEE with 4 years experience in engineering design plus 4 years in reliability.

■ If you would like to know how contributions to General Dynamics/Electronics' unique capabilities can advance *your* future, submit a detailed resume to Mr. M. J. Downey.

GD

GENERAL DYNAMICS | ELECTRONICS

1476 N. Goodman St., Rochester 3, New York

An Equal Opportunity Employer

Westinghouse

announces immediate openings for

TUBE ENGINEERS

The expansion of our Electronic Tube Division to meet the growing demands of the commercial, industrial and military markets has created several outstanding opportunities for experienced ENGINEERS. Salaries are open, depending on experience and qualifications. The plant is located in Elmira, N.Y. . . . a delightful community for work and recreation in the Finger Lakes region of upstate New York.

Experience in any of the following areas is desirable:

- **MICROWAVE TUBES & DEVICES**

  Senior Engineers with experience in design or manufacture of MAGNETRONS, KLYSTRONS, TRAVELING WAVE TUBES and other microwave tubes and devices.

- **IMAGE TUBES**

  Design or manufacture of STORAGE TUBES, CAMERA TUBES and other imaging devices.

- **CATHODE RAY TUBES**

  Design or manufacture of black and white PICTURE TUBES, and INDUSTRIAL and MILITARY TUBES.

Write or send resume to:

William Kacala,
Technical Recruiting,
P.O. Box 284, Elmira, N.Y.
or phone collect
Elmira, REgent 9-3611

An Equal Opportunity Employer

Westinghouse
ELECTRONIC TUBE DIVISION — ELMIRA, NEW YORK

Philco WDL has immediate and challenging engineering positions open in Discoverer, Midas and Advent programs in these categories:

Data systems engineering

Technical Staff — communications and data systems

Systems test planning

Systems reliability analysis

Design Engineering — surface and vehicle electronics

Human factors and operations analysis

Field tracking station activation

Tracking and control systems design

Logistics and station support

And others

U. S. citizenship or current transferable Department of Defense clearance required.

if your future is for growing...

People at Philco's Western Development Laboratories are proud of their achievements, secure in the steady growth of their company, enthusiastic about their future.

In just four years, Philco WDL has expanded from a staff of 18 to more than 2,000. At the end of this year WDL will open a new 250,000-square-foot facility which will accommodate a continually expanding complement of engineers, scientists and supporting staff members.

Philco WDL, the space organization which designed and built the Courier satellite, conducts an ever-growing development program in tracking, satellite instrumentation, communications, data processing and command—moving hand in hand with the federal government in space exploration and space age defense.

Your growth with a growing company, ideal living on the Northern California Peninsula, professional and monetary advancement commensurate with your own ability—these are some of the advantages and satisfactions of working at Philco Western Development Laboratories.

If yours is one of the fields listed at the left, write today to Mr. W. E. Daly, in confidence, of course, Department R-12.

This new 250,000-square-foot addition to Philco Western Development Labs is further indicative of your future there.



EQUAL EMPLOYMENT OPPORTUNITY FOR ALL QUALIFIED APPLICANTS

PHILCO®
Famous for Quality the World Over

WESTERN DEVELOPMENT LABORATORIES
3875 Fabian Way, Palo Alto, California

RESEARCH ENGINEERS AND PHYSICISTS

UNUSUAL OPPORTUNITIES FOR PROFESSIONAL CAREERS.
CHALLENGING THEORETICAL PROBLEMS IN:

- **Theory of Communications**
- **Self-Adaptive Systems**
- **Satellite Systems Studies**
- **Nuclear Weapons Effects**
- **Space Physics**
- **Operations Research**

- Owned and Managed by Employee-Scientists
- Southwest Climate • Low Population Density
- Wide Range of Benefits Including Profit Sharing
- Emphasis Placed on Theoretical Concepts
- No Hardware Development • Advanced Degree Desirable

ADDRESS INQUIRIES TO:

THE Dikewood CORPORATION

4805 Menaul Blvd. N.E. **Albuquerque, N.M.**

ELECTRONICS DIVISION

of Space Technology Laboratories, Inc.

Offers Immediate Assignments in Southern California

The continuing growth and diversification of Space Technology Laboratories, Inc. creates immediate career openings in the Communication, Electromechanical, Guidance, and Space Physics Laboratories of STL's Electronics Division.

In supporting STL's expanding contributions to the Advent, OGO, Atlas, Titan, and Minuteman programs, this division's responsibilities include analysis, design, and development of advanced guidance, control, and communications systems—at every phase from applied research through electronic product and ground support equipment design.

Immediate career opportunities exist here for outstanding engineers and scientists in the fields of:

- Digital computers
- Logical design
- Communication systems analysis
- Parts application
- Electronic packaging
- Electromechanical systems development
- Ground support circuit design
- Systems design and integration
- Equipment systems—checkout and evaluation
- Support equipment systems design
- Control systems analysis
- Electromechanical design
- Space communications systems
- Telemetry systems design
- Antenna systems
- R-F transistor equipment design
- Transistor circuit design
- Guidance systems analysis
- Materials and processes
- Reliability
- Aerospace ground equipment design

All qualified applicants, regardless of race, creed, color or national origin, are invited to communicate with Dr. R. C. Potter, Manager of Professional Placement and Development.

SPACE TECHNOLOGY LABORATORIES, INC.
a subsidiary of Thompson Ramo Wooldridge Inc.
P. O. Box 95005-I, Los Angeles 45, California

ENGINEERS
PHYSICISTS
MATHEMATICIANS

SYSTEMS EVALUATION POLARIS SYSTEM

The Applied Physics Laboratory of The Johns Hopkins University has responsibilities in the evaluation of the Polaris Missile System. We invite you to consider the following career appointments:

Senior Mathematicians

Duties will involve statistical analysis of complex test data for performance, reliability and operation evaluations. A background in physics or electrical engineering is desirable.

Project Engineers

For field test operations involving a team effort of Contractor, Navy and APL Personnel. Work will include launch and flight data acquisition analysis and monitoring of shipboard activities related to the Polaris Missile System. Prefer engineers with considerable background of project level responsibilities.

Systems Engineers

APL has several positions available on the associate and senior levels for men with experience in electrical engineering, physics, mechanical engineering, dynamics, or computer engineering. Will perform systems work related to fire control, navigation, missiles, and submarine controls. Assignment involves field work and contact with the Navy and Contractor Personnel.

Systems Analysts

Respondents must have heavy theoretical background and ability to read and understand telemetry records. Will perform basic analysis of systems related to fire control, navigation, missiles, and submarine controls. May also be required to simulate and solve orbit and doppler equations. Associate and senior level appointments.

Data Requirements, Instrument Engineers

Positions require a physicist or electrical engineer with experience in evaluation, data acquisition and testing of instrumentation installations. Will analyze sub-systems such as guidance, propulsion, controls, boosters, and inertial systems individually and as integral parts of over-all systems to derive data requirements and instrumentation. Duties involve some field work.

APL will provide you with a professional atmosphere conducive to creative effort as well as the tools and technical support required to tackle these and related problems. Our facilities are located in Silver Spring, a residential suburb of Washington, D. C., offering you a choice of country, suburban or city living.

For additional details, direct your inquiry to: Professional Staff Appointments

The Applied Physics Laboratory
The Johns Hopkins University

8603 Georgia Avenue, Silver Spring, Md.

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

Positions Open

(Continued from page 106A)

ASSISTANT PROFESSOR

Ph.D.s required with interests in circuits, electromagnetic theory or controls, in expanding Graduate and Undergraduate School. Applications from abroad invited. Apply to Chairman, Department of Electrical Engineering, Villanova University, Villanova, Pa.

ASSISTANT or ASSOCIATE PROFESSOR

Assistant or Associate Professor with Ph.D. in Electrical Engineering or Physics. Interest in Electronics, Microwaves, Solid State, Circuit Theory, or Computers. Active research and graduate program with opportunities for outside consulting. May start February 1 or September 1, 1962. Send resume to W. P. Smith, Chairman Electrical Engineering Department, University of Kansas, Lawrence, Kansas.

CRITICAL VACANCIES AT GRIFFISS AIR FORCE BASE, ROME, N. Y.

Electronic Engineer	GS-7	$6345 pa.
Industrial Engineer	GS-9	$6435 pa.
Electrical Engineer	GS-9	$6435 pa.
Librarian	GS-9	$6435 pa.
Supply Comm. Mgt. Officer	GS-11	$7560 pa.
Supply Requirements Officer	GS-11	$7560 pa.
Supply Distr. Officer	GS-11	$7560 pa.
Supv. Electrical Eng.	GS-11	$7560 pa.
Industrial Engineer	GS-11	$7560 pa.
Supv. Tech. Manuals Writer (Electronics)	GS-12	$8955 pa.

Critical vacancy in the position of Electronics

(Continued on page 116A)

ENGINEERS MATHEMATICIANS PHYSICISTS

Engineering-Physics Co. has recently embarked upon new fields of research and development. Singular opportunities exist for engineers and scientists who have the resourcefulness, imagination and technical background to assume a responsible role. All qualified applicants will be considered for employment regardless of race, creed, color or national origin.

Projects include studies and developmental work on:

INSTRUMENTATION
MAGNETOHYDRODYNAMICS
ELECTROMECHANICAL DEVICES
SYSTEMS CONCEPT & DEVELOPMENT

Address inquiries to Dr. Vincent Cushing

EPCO ENGINEERING-PHYSICS COMPANY

5515 Randolph Road
Rockville, Maryland



THE FIRST SUCCESSFUL MICROWAVE SOLID-STATE TRANSMITTER WITH POWER CAPABILITY ADEQUATE FOR SATELLITE APPLICATION A DEVELOPMENT BY THE SCIENTISTS AT AMHERST LABORATORIES


The objective assigned to the Amherst Laboratories' scientists was this:
Advance the state-of-the-art of microwave space vehicle transmitters by increasing performance, reducing size, reducing weight and increasing reliability.
The time was June 1960. One year later, these objectives had been reached *and exceeded by a wide margin.*
The result: a solid-state transmitter applicable for satellite use, operating within the S-band, about half the size of a carton of cigarettes, and with a life expectancy of two years.
This significant achievement is representative of many challenges currently being met by the scientists at Amherst Laboratories.

PAPER ON REQUEST: The paper which explains the new techniques employed in development of the new microwave Solid-State Transmitter authored by W. J. Maciag is available to engineers and scientists on request. Write for the paper entitled "Solid State, S-band Single Side Band Suppressed Carrier Transmitter"

AMHERST LABORATORIES • 1181 WEHRLE DRIVE • WILLIAMSVILLE, NEW YORK
AN EQUAL OPPORTUNITY EMPLOYER

SYLVANIA ELECTRONIC SYSTEMS
Government Systems Management
for GENERAL TELEPHONE & ELECTRONICS
GENERAL SYSTEM

"Shrinking the Universe . . . through Communications"



Here are exceptional opportunities in:

SURFACE BASED ELECTRONICS

The Columbus Division of North American Aviation is developing a major product line in Surface Based Electronic Systems. This work encompasses Communications and Radar Systems, Data Processing Systems, and Command and Control Systems. Here is an opportunity to join an established company with complete weapon system facilities. Excellent growth potential exists in the following fields:

Radar & Communications Systems

Minimum desirable background includes B.S. in E.E. with 5 years or more of experience in design analysis of advanced communications systems, high powered transmitters, antennas, R.F. transmission lines and propagation.


Project Engineers For R & D

To act as project leaders in research activity for the development of phased array antenna systems and for advanced design of radar and communications systems. Minimum desirable background M.S. in E.E. with 8 years or more of direct experience.

Systems Analysis

Senior engineers to perform advanced systems analysis and operations analysis on surface based electronic systems, aircraft drones, missiles and electronic countermeasures. Minimum desirable background B.S. in Engineering or Math plus 5 years or more of related experience.

Please send resume to: North American Aviation, The Professional & Technical Employment Office, Box IR-420, 4300 East Fifth Avenue, Columbus 16, Ohio, Attn: H. Keever, Manager



All qualified applicants will receive consideration for employment without regard to race, creed, color, or national origin.

COLUMBUS DIVISION
NORTH AMERICAN AVIATION

e·m·r

Maximum Responsibility FOR CREATIVE ENGINEERS WITH FOLLOW-THROUGH CAPABILITIES

By maintaining a reputation for technical engineering excellence and a position of leadership in research and development, Electro-Mechanical Research, Inc. (e-m-r) has become the largest of all companies specializing in telemetry systems. Today, with the space age bringing new and vital significance to the field of electronics, e-m-r affords mature engineers an environment for maximum responsibility and personal growth.

SYSTEMS ENGINEERS — DIGITAL (Telemetry)

The full weight of the e-m-r engineering approach is brought to bear on these demanding positions. A high level of engineering creativity and skill is required. Most important, there must be a real desire to participate in the entire digital systems effort, including synthesis, development and construction of "custom systems". Compensation proportionate to "follow-through" ability.


Minimum of 3 years experience in detailed design in such areas as digital circuits — using semiconductors and magnetic elements — transistor implemented low level amplifiers, ferrite core memories, logic design of digital computer, analog to digital converters, feed-back amplifiers, servomechanisms, and RF transmitters and receivers — 100 to 1000 megacycle range.

Direct confidential inquiries to
ROLAND E. HOOD, JR.
Personnel Manager, Systems Division

electro-mechanical research, inc.
P. O. Box 3041-T
Sarasota, Florida

An equal opportunity employer

RW IS PIONEERING



To us, *pioneering* means something important: coping with unknowns; showing the way for others to follow. A pioneer is the last one you'd ever expect to find on Cloud Nine. He's a practical, no-nonsense fellow who knows better than anybody else that a clever new device is no good unless it's useful—and it works. So it is with respect for a great tradition that we say RW is a pioneer in the field of information processing and retrieval.

Today, Closed Loop control is a growing trend in the process industries. RW developed and installed the world's first Closed Loop system three years ago, and has led the field ever since.

A few years from now, it will be commonplace to have "polymorphic" systems linking multi-computer complexes all over the world. RW was the first to build a "polymorphic" computer system; the one developed for the Air Force has been in operation at Canoga Park for many months.

Before long, "stored logic" computers may be GI equipment for all the services. Today, RW engineers and programmers are creating and discovering new applications for AN/UYK-1's, the only militarized "stored logic" computers ever built.

Some day, consoles permitting people to communicate directly with computers will be a familiar sight in military command control centers and corporation headquarters. Today, RW's man-machine communication consoles are the only functioning hardware of their kind in existence.

If you are a computer development engineer, a programmer, or a systems analyst of the practical pioneer type, you are invited to inquire about immediate openings in these and other advanced projects at RW, an equal opportunity employer. Contact Mr. R. J. Kremple at

Thompson Ramo Wooldridge Inc. **RW** Division
8433 Fallbrook Ave., Canoga Park, Calif., Diamond 6-6000

Digital Project Engineers

EPSCO is seeking engineers to assume major responsibilities in the fields of Computer Control, PCM Telemetry, Automatic Checkout and Monitoring, Analog to Digital Conversion equipment and systems.

From systems conception, to logical design to circuit configuration . . . tomorrow's hardware is our concern today. There's something to be said about being at the right place, at the right time. We sincerely believe that for the engineer with experience and interest in the digital field, Epsco's advanced programs offer responsibility for honest engineering design achievement.

Our unique salary and benefit program includes stock options for singular achievement and senior responsibilities.

For further information on the above positions please write:

MR. JOHN ESSERIAN

Epsco incorporated

275 Massachusetts Avenue, Cambridge, Massachusetts

"An equal opportunity employer"

PHYSICS AND CHEMISTRY OF SOLIDS

The new Sperry Rand Research Center in Sudbury, Massachusetts, is seeking scientists at the Ph.D. level with an interest in doing publishable basic work in the fields of:

CRYSTAL GROWTH
OPTICAL STUDIES
MAGNETIC RESONANCE
DEFECT STUDIES
ENERGY CONVERSION
ELECTRICAL TRANSPORT STUDIES

Our new laboratory located 25 miles west of Boston offers a basic research environment with maximum freedom to pursue fundamental ideas.

For further information write:
Frederick M. Swope, Jr.

SPERRY RAND
RESEARCH CENTER

Box 400 Sudbury, Massachusetts

'An equal opportunity employer'

Positions Open

(Continued from page 113A)

Engineer, GS-11, $7560 per annum. Contact Industrial Relations Department, U. S. Naval Air Station, Quonset Point, R. I.

SENIOR ELECTRONICS ENGINEER

Excellent opportunity exists for professional advancement with small research organization. Seeking B.S.E.E. or M.S.E.E. with 4 to 10 years experience including design work in R. F. and microwave fields in the 30 to 3000 MC regions. Interest in Project Management responsibilities desired. Contact Richard A. Johnson, Vice President, Systems Research Laboratories, Inc., 500 Woods Drive, Dayton 32, Ohio. Phone 244-4051.

MAGNETIC CORED COMPONENTS

Electrical Engineer with design experience involving components for pulse circuitry with emphasis on filters, R. F. coils and pulse transformers. A background involving the uses of ferrite and powdered iron cores is highly desirable. Send complete resume and salary requirements with first letter to Paul E. Dicker, Chief Engineer, Aladdin Electronics, Nashville 10, Tennessee.

ELECTRONIC MUSICAL INSTRUMENT ENGINEER

Graduate Electrical Engineer to join research group on electronic musical instruments. One to three years electronic experience required, with some musical background desirable. Write Albert Meyer, Engineering & Research Dept., The Baldwin Piano Co. 1801 Gilbert Ave., Cincinnati 2, Ohio.

EDUCATION AND RESEARCH IN BIO-MEDICAL ENGINEERING

An educational program designed to prepare life and physical scientists, doctors of medicine, and engineers for research in life systems through the current period of transition of biological sciences from the natural history stage of inquiry by inductive empiricism to that of inquiry by deductively formulated theory. An intensive four-term (12-month) preparation in methods of logical thought, mathematics, physics, and electrical theory for doctors of medicine and biologists, and one-term (3-month) preparation in life sciences for engineers, makes possible joint course work in the final three terms (nine months). Thesis research on biological systems is conducted at the Presbyterian Hospital by teams drawn from both disciplines. The program leads to a graduate degree at Drexel. Limited stipend and scholarship funds are available. Assistance with fellowship application to National Institutes of Health is offered. For information, James W. Dow, M. D., Dept. of Bio-medical Engineering, Drexel Institute of Technology, 15 North 32 St., Philadelphia 4, Pa.

ANTENNA ENGINEERS

Experienced Antenna Engineers, Physicists, B.S., M.S., Ph.D. Citizens of U.S.A. Very challenging theoretical, applied research and engineering problems on ground, missile, satellite and deep space probe antenna systems. Write H. W. Haas, Physical Science Laboratory, New Mexico State University, University Park, New Mexico.

OVERSEAS

Robert College, in Istanbul, Turkey, presents a challenge in education where East meets West. An opportunity to contribute significantly to the

(Continued on page 118A)

Scientists and engineers in research

CAREER OPPORTUNITIES IN A NEW FIELD

SEMICONDUCTOR CIRCUITS

IBM Thomas J. Watson Research Center

The new IBM Thomas J. Watson Research Center in Yorktown, N.Y., is undertaking important new long-range projects requiring scientists and engineers with experience in, or relating to, semiconductor circuitry. Research projects under way are directed toward purely scientific goals as well as toward developing technology for engineering advanced information handling systems.

The position involves the proposing, experimental exploration, and evaluation of circuits which have a high degree of probability of lending themselves to fabrication into integrated circuitry by means of advanced semiconductor technologies including expitaxial crystal growth from the vapor phase. The work will be done in close cooperation with device fabrication scientists and the ultimate aims include consideration of integrated of preconnected computer circuits wherein transmission lines are treated as integral parts.

An advanced degree or equivalent in E.E. or Physics is desirable. We prefer experience in circuits using semiconductor devices as applied to large high-speed computers.

The Thomas J. Watson Research Center at Yorktown, N.Y., is located in pleasant, rural Westchester County countryside, just 35 miles from New York City. The Research Center was designed to provide the best possible working environment for scientists and engineers engaged in advanced research studies. The location provides excellent schools and housing. IBM offers a fully paid benefits program that is setting the pace for industry today. All qualified applicants will receive consideration for employment without regard to race, creed, color, or national origin.

The standard information relative to location, benefits, etc., should be included as well. Please write, outlining your education and experience, to:

Mr. J. B. Farrington, Dept. 645M
Thomas J. Watson Research Center
P.O. Box 218
Yorktown Heights, New York

IBM

INTERNATIONAL BUSINESS MACHINES CORPORATION



NEW OPPORTUNITIES and warm winter SUNSHINE can be yours at MOTOROLA in PHOENIX

Motorola's widely-diversified activities in advanced military electronics assure engineers and scientists the fullest measure of growth potential—in the immediate future and in the years ahead. As a member of a project team, you participate in challenging state-of-the-art assignments spanning a broad field of engineering concepts. Your career will prosper at Motorola in Phoenix, where initiative and creativity earn recognition and rewards.

Your family will prosper, too, in a dry, sunny climate that's world-famous. You can play golf, swim, enjoy patio barbecues every month of the year. There are many near-by lakes for boating, water-skiing and fishing. Skin diving and deep-sea fishing are sports you can enjoy any weekend in the warm waters of Old Mexico.

Investigate the new career opportunities at Motorola in Phoenix.

POSITIONS IMMEDIATELY AVAILABLE

- **Systems Test Equipment Design**
- **Communications and Navigation**
- **Systems Analysis and Preliminary Design**
- **Missile and Space Guidance and Control**
- **Digital Circuitry Design**
- **Microwave and Radar**
- **Reliability and Components**
- **Solid State**

Write Phil Nienstedt (Dept. 1201)

MOTOROLA

MILITARY ELECTRONICS DIVISION, WESTERN CENTER

P. O. Box 1417, Scottsdale, Arizona

Motorola also offers opportunities at
Chicago, Illinois, and at Culver City and Riverside, California

An Equal Opportunity Employer

THE
"YOUNG GIANT"
OF THE ELECTRONICS INDUSTRY

SANDERS ASSOCIATES, Inc. OFFERS YOU THESE CAREER ADVANTAGES

Creation of new engineering positions with good growth potential is as much a part of Sanders Associates as the development of new engineering techniques – upon which the Company was founded just 10 years ago.

Fresh, non-conventional approaches toward solution of both old and new problems have enabled Sanders to grow from 11 founding engineers to over 2400 employees... to open 3 new facilities within the last year ...and to acquire a contract backlog in excess of $100 million, largely for production of Sanders-developed systems.

Still further pioneering and expansion are planned in advanced areas of phased array radar, pulse doppler radar systems, space radar and communications systems, creating positions for Engineers interested in and qualified for working at the threshold of the state of the art.

NEW FACILITIES
Plainview, L. I., New York
Burlington, Mass.
Washington, D. C.

SANDERS' ACHIEVEMENTS
FLEXPRINT® flexible printed circuits, for which Sanders holds the basic patent; TRI-PLATE® microwave products; PANAR® radar

Positions Are Open for the Following:

SENIOR SYSTEMS ENGINEERS
With 5 or more years experience in communications, reconnaissance or satellite systems and equipments, specifically in transistor circuit design, analysis or development of digital equipments, man-machine control systems, receivers (HF through UHF), data storage and display devices or mathematical analyses related to such equipment. BS or MS in EE or Physics.

RECEIVER DESIGN ENGINEERS
For design and development of receivers for military applications. Experience should include design of low noise front ends, IF strips, AGC circuitry and application of image rejection techniques – all transistorized. BS in EE or Physics with 3 to 8 years experience.

CIRCUIT DESIGN ENGINEERS
To translate conventional wire circuits into flexible and/or rigid printed circuitry and to design circuitry layout and approaches for printed circuits. EE, ME or ChE with printed circuit background.

TRANSMITTER DESIGN ENGINEERS
For design and development of transmitters (VHF, UHF and microwave), tubes, pulse modulators, power in excess of 1 kilowatt – for military and airborne applications.

Resumes should be addressed to R. W. McCarthy.

SANDERS ASSOCIATES, INC.

An Equal Opportunity Employer

NASHUA, NEW HAMPSHIRE
(About an hour from downtown Boston)

®REGISTERED U. S. TRADEMARK

Positions Open

(Continued from page 116A)

development of a young republic is available to specialists in engineering, business administration and economics, the sciences, and the humanities. Graduate degrees required. Address inquiries to Dr. Howard P. Hall, Vice President, Robert College, Bebek Post Box 8, Istanbul, Turkey; with copy to the Near East College Association, 548 Fifth Avenue, New York 36, N. Y.

ENGINEER

$115 week approx. College grad. with a major in either electrical or mechanical engineering. Work involves investigating major appliances and building products in laboratory of national magazine. Prefer some experience but will consider recent college graduate. Veteran or Draft Deferred. Send typed resume to Hearst Magazines, Personnel Office, 309 West 56 Street, New York 19, N. Y.

TELEVISION BROADCAST TECHNICIAN

Opportunities for video technician with group television stations. Write G. G. Jacobs, Corinthian Broadcasting Corp., 302 South Frankfort, Tulsa, Okla.

BIO-MEDICAL RESEARCH

The Department of Physiology and Pharmacology seeks a young man interested in biomedical research. Prefer a recent graduate with extensive background in circuit theory to assist in developing instrumentation for bio-medical re-

(Continued on page 122A)

"I'M A
Bread and Butter
ENGINEER"

"Sure I want a challenging job . . . but I also want commensurate compensation. My last job was big on challenge—short on income. Abbott's showed me where I could find both. They introduced me to some of the more progressive engineering outfits, and Abbott's reputation helped me to land a stimulating bread and butter job."

For over 37 years, the nation's major corporations have relied on Abbott's for key engineering, scientific and administrative personnel. Abbott's receives first call when significant career opportunities occur. Why not make Abbott's your personal representative?

Positions available with salary ranges from $10,000 to $30,000. All service charges paid by our client organizations. All negotiations conducted in strict confidence.

MR. LOUIS A. KAY

ABBOTT'S

EMPLOYMENT SPECIALISTS
150 Tremont Street, Boston 11, Massachusetts
HAncock 6-8400

TROPOSPHERIC SCATTER DESIGN ENGINEERS

Collins Radio Company, pioneer in the development of tropospheric scatter communications and a leading supplier of scatter equipment and systems, has several attractive openings for engineers experienced in communication equipment design.

These positions are in the design of tropospheric scatter equipment, parametric amplifiers and FM detection devices. Those selected will work in Collins' new research and development facility, located near Dallas.

Minimum requirements include a degree in electrical engineering and at least two years' design experience in scatter, microwave or UHF equipment. These are minimum requirements; more responsible positions are available for those qualified.

Send resume, in confidence,
to Ben Jeffries,
Collins Radio Company,
Dallas, Texas

COLLINS

An equal opportunity employer



the inner FIRE...

The fire within that made you become an engineer—has it become quenched, or does your work add new fuel every day? One of our employer clients has a challenge that can set your creative fire burning.


Typical Opportunities

GENERAL MGR. **$25,000**
CHIEF ENGR. **$22,000**
SALES MGR. **$20,000**
HUMAN FACTORS MGR. **$16,000**

Send your resume today.

Guilford

Personnel Service
Scientific Personnel Specialists
please note new address
Equitable Building
Baltimore 2, Maryland
MUlberry 5-4340



IONOSPHERIC PROPAGATION and HF COMMUNICATIONS

If you have the background, the imagination and the desire to contribute to important programs in these fields, you are invited to join a carefully selected team of outstanding scientists and engineers now contributing significantly to current knowledge through advanced research.

These programs are being conducted at our ELECTROPHYSICS LABORATORIES in the SUBURBAN WASHINGTON, D. C. area, ideally located from the viewpoint of advanced study which may be conducted at one of several nearby universities; for readily available housing in pleasant residential neighborhoods; and for the general amenities of living offered by this important Metropolitan center.

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

OUR PRESENT NEEDS ARE FOR:

SENIOR IONOSPHERIC PHYSICISTS Ph.D. preferred, with several years' experience in the study of Ionospheric phenomena. Should be familiar with present knowledge of upper atmosphere physics and possess an understanding of current programs using rockets and satellites for studies in F-region and beyond. Qualified individuals with supervisory abilities will have an exceptional opportunity to assume project leadership duties on HF projects already under way involving F-layer propagation studies backed by a substantial experimental program.

SENIOR DEVELOPMENT PHYSICISTS Advanced degree in Physics or E.E. preferred. Must be familiar with latest techniques in the design of advanced HF receivers and transmitters and possess working knowledge of modern HF networks employing ferrites and metallic tape cores. Strong theoretical background in modern linear circuit theory desired. Will carry out laboratory development and implementation of new HF communications systems.

SENIOR ELECTRONIC ENGINEERS Advanced degree in E.E. preferred. Must be familiar with conventional pulse circuit designs and applications. Technical background should include substantial experience in data process and data recovery systems using both analog and digital techniques. Knowledge of principles and application of modern information theory including correlation techniques helpful. Will be responsible for the design of sub-systems.

JUNIOR ELECTRONIC ENGINEERS To assist Senior Engineers and Scientists in the development of HF communications and data process equipment. Should have formal electronics schooling and 2 years' experience in circuit design checkout or analysis of HF communications, Radar Pulse, Analog/Digital or Data Recovery equipment. Construction of prototypes of new and interesting equipment and design of individual components of communications and data processing systems will comprise the major efforts of selected applicants.


FIELD STATION ENGINEERS B.S.E.E. or equivalent, consisting of combined civilian or military technical school, with work experience. Presently employed as a field engineer or project engineer with a valid 1st or 2nd Class FCC license and a good command of some of the following: Radar, preferably high power; HF long-distance communications systems; Tropospheric or Ionospheric scatter systems. Must be willing to accept assignments in areas where dependents are not permitted for periods of up to one year. Differential paid for overseas assignments.

For a prompt reply to your inquiry, please forward resume in confidence to:
W. T. WHELAN, Director of Research & Development

ACF ELECTRONICS
DIVISION

ACF INDUSTRIES

DEPT. A-2, HYATTSVILLE, MARYLAND



THE *EXCEPTIONAL* **MAN**

when the position you wish to fill is vital to your organization . . .

when the man you seek requires all the attributes of leadership . . . plus the ability to make significant technical contributions to the work for which he will be responsible . . .

when you need a man who can command the respect of his associates and subordinates because of his intimate knowledge of and first-hand experience in their fields . . .

when you need a man who is well educated and trained in the specialized fields of knowledge you require . . .

you need The Exceptional Man.

Let us locate him for you.

Charles A. Binswanger INCORPORATED **ASSOCIATES**

EXECUTIVE SEARCH SPECIALISTS

44 FRANKLIN BUILDING • BALTIMORE 2, MD. • PLAZA 2-5013

PHYSICISTS

Theoretical Studies in

PLASMA PHYSICS
NUCLEAR PHYSICS
ASTROPHYSICS
MAGNETOHYDRODYNAMICS

The Physics Section of Republic's Missile Systems Division is broadening its program of research in the above areas. The larger part of these studies are sponsored by Government agencies; a considerable portion are company financed. All are broadly related to problems of defense or space exploration.

Holders of advanced degrees, preferably PhD, are invited to inquire about senior staff appointments now available. *All work is of a theoretical nature,* and publication of results in appropriate scientific journals is encouraged.

Address inquiries, treated in strictest confidence, of course, to

Mr. Paul Hartman
Technical Employment Supervisor

MISSILE SYSTEMS DIVISION

REPUBLIC AVIATION CORPORATION

223 Jericho Turnpike, Mineola, Long Island, N. Y.

An Equal Opportunity Employer

Increased technical responsibilities in the field of range measurements have required the creation of new positions at the Lincoln Laboratory. We invite inquiries from senior members of the scientific community interested in participating with us in solving problems of the greatest urgency in the defense of the nation.

RADIO PHYSICS and ASTRONOMY

RE-ENTRY PHYSICS

PENETRATION AIDS DEVELOPMENT

TARGET IDENTIFICATION RESEARCH

SYSTEMS:
Space Surveillance
Strategic Communications
Integrated Data Networks

NEW RADAR TECHNIQUES

SYSTEM ANALYSIS

COMMUNICATIONS:
Techniques
Psychology
Theory

INFORMATION PROCESSING

SOLID STATE
Physics, Chemistry, and Metallurgy

• *A more complete description of the Laboratory's work will be sent to you upon request.*

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

Research and Development

LINCOLN LABORATORY

Massachusetts Institute of Technology

BOX 16

LEXINGTON 73, MASSACHUSETTS

Communications, Sensing Systems and Cybernetics in a unique role at

AEROSPACE CORPORATION

Aerospace Corporation is chartered exclusively to serve the United States Government in applying the full resources of modern science and technology to advanced space and ballistic missile systems.

As the civilian link uniting the Air Force-scientific-industrial team organized for this mission Aerospace Corporation provides: advanced systems analysis and planning; theoretical and experimental research; initial systems engineering, initial technical direction and general technical supervision.

COMMUNICATIONS

Scientists and engineers working in this area are concerned with: the analysis of digital, analog and voice communication techniques; statistical studies of communications systems; information theory; tracking and telemetry links; antenna design; orbit determination; command and control systems; and secure communications and anti-jam techniques.

SENSING SYSTEMS

Visual-Optical Sensors Work in this area concerns advanced cameras, lenses, exposure timing devices, film and emulsions, photo analyses and copy devices, and image transducers. Scientists and engineers here are concerned with: scoring and miss-distance indication, information theory analysis of photo-visual problems; photographic tracking; spectrophotometry; densitometry and sensitometry; and optical reproduction systems analysis.

Infrared and Ultraviolet Sensors Assignments in this area include investigations of position sensing, guidance, and other systems. This work provides requirements for advanced component and technique considerations including optical design, detector devices, and like areas of interest.

High Frequency, Laser & Optical Radar Activities here concern advanced components and techniques related to: tracking and aiming; ECM and CCM techniques, frequency agility systems; noise correlation systems; propagation and attenuation factors; target reflectivity and scattering; and beam power density effects.

AUXILIARY POWER SYSTEMS

Utilizing chemical and nuclear sources, fuel cells, solar cells, and solar thermal engines, these Aerospace Corporation scientists and engineers are concerned with: weight and efficiency as related to missile power systems for instrumentation and control; and with orbital or space vehicle systems for communication, instrumentation, and control.

CYBERNETICS

In this area scientists and engineers are concerned with: powered flight, free flight and re-entry attitude controls; energy management systems; vehicle launch and general control systems; inertial platforms; accuracy analysis; guidance equations for rocket vehicles; homing and radio guidance; stellar or radio-aided inertial guidance; and the geodetic and geophysical aspects of inertial guidance.

Today more men with advanced degrees are needed to meet growing responsibilities. Immediate assignments exist for highly skilled scientists and engineers knowledgeable in interdisciplinary problem solving.


All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin and are urged to contact: Mr. George Herndon (OSborne 9-4661, Extension 1171), Aerospace Corporation, Room 109, P.O. Box 95081, Los Angeles 45, California.



AEROSPACE CORPORATION

Organized in the public interest and dedicated to providing objective leadership in the advancement and application of space science and technology for the United States Government.

LIMITED WARFARE




A CONTINUING SEARCH FOR NEW KNOWLEDGE AT CORNELL AERONAUTICAL LABORATORY

Within recent months an ever increasing group of authoritative voices has been heard in a plea for enhanced ability to stamp out limited wars rapidly. Now recognized as that aspect of our preparedness in most critical need of technological advancement, the demand is being felt for new concepts in the areas of quick destruction, wide dispersal of small forces, highly creative use of camouflage, great mobility of troops and weapons, and the ability to capitalize on the cover afforded by night and bad weather. Today, as for some 15 years past, an important segment of CAL's technical effort is devoted to such tasks.

Current studies include tactical weapon systems, combat information and control systems, reconnaissance and surveillance, combat force mobility, CBR warfare, countermeasures, penetration aids, and new munitions concepts. CAL's searching look into the battlegrounds of the future includes more than a dozen research and development projects aimed at solving problems of limited warfare. They are problems that offer attractive opportunities for engineers and scientists. If you are interested in becoming a member of one of our small, closely knit research teams working on far-reaching scientific and technological programs, write today for a free copy of our factual, illustrated employment prospectus entitled "A Community of Science."

CORNELL AERONAUTICAL LABORATORY, INC.
of Cornell University
Buffalo 21, N.Y.



FREE REPORT

J. P. Rentschler L.W.
CORNELL AERONAUTICAL LABORATORY, INC.
Buffalo 21, New York
Please send me a copy of "A Community of Science."

Name _____

Street _____

City _____ Zone _____ State _____

☐ Please include employment information.

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

Positions Open

(Continued from page 118A)

search. Interested persons should communicate with: Albert F. Kelso, Ph.D., Dept. of Physiology and Pharmacology, c/o Chicago College of Osteopathy, 1122 East 53 Street, Chicago 15, Ill.

BROADCAST ENGINEERS

The United States Information Agency seeks Electronics Engineers with Communications or Broadcasting Systems experience for its Voice of America. The positions are located in Washington, D. C. and abroad. Domestic assignments are mainly concerned with the design and planning of broadcasting systems and transmitting plants up to 1000 kilowatts.

Foreign positions are of a construction management type.

Broadcasting and Communications Systems cover frequency ranges in the medium and high frequency bands.

Foreign Service appointments will be made at the entrance level of $10,785 per annum and range to $12,025 plus overseas allowances. Appointment levels for domestic service: $8955, $10,635, $12,210, $13,730 and range to $15,030 per annum commensurate with background and experience.

Relocation expenses paid in accordance with government regulations.

Applicants *must* be American citizens.

Please send background resume or application for Federal Employment (SF-57) to: Employment Branch, U.S. Information Agency, Washington 25, D. C.

(Continued on page 124A)

ELECTRONICS ENGINEERS WITH RADAR EXPERIENCE

Silver Springs, Maryland

Armour Research Foundation, a leading independent research organization, offers exceptional long term opportunities for experienced electronics engineers who wish to work in Silver Springs, Maryland (convenient to both Washington and Baltimore areas). The Foundation is now forming a highly competent technical group to aid in the development of an advanced radar-missile system. Present assignments involve primarily circuit design and experimental system work. Applicants must have at least a B.S. degree in Electrical Engineering with an above average academic record and several years of radar experience.

Work on this program offers exceptional opportunities for professional and personal growth. Staff members receive attractive salaries, up to four weeks vacation, generous insurance and retirement benefits, and tuition paid graduate study. All qualified applicants will receive consideration for employment without regard to race, creed, color, or national origin. Please reply in confidence to Mr. S. M. Ream.

ARMOUR RESEARCH FOUNDATION
ELECTROMAGNETIC COMPATIBILITY ANALYSIS CENTER
N.E.E.S. ANNAPOLIS, MARYLAND



Ph.D's, MS's, BSEE's

Exceptional opportunities with

SYLVANIA

near

SAN FRANCISCO

Sylvania Mountain View, 40 minutes south of San Francisco, offers you challenging scientific work on defense systems, plus ideal living conditions.

The work involves systems studies, design and development in frequency ranges from DC to daylight; it offers growth into scientific or management positions of responsibility.

Immediate openings exist in the following fields:

Reliability Analysis
Operations Research
Systems Analysis, Design
Design and Development of:
  Antennas, Receivers, Transmitters, Transceivers, Servos
Analog Computers
Mechanical Design
Field Engineering

Sophisticated San Francisco's theatres, restaurants and major league sports are minutes away. The Pacific Ocean is near; hunting, fishing and skiing 3 hours' drive.

Furthering your education? Sylvania encourages, sponsors graduate study at Stanford and other nearby institutions.

Send resumé to Wayne Pearson, Sylvania, Box 188, Mountain View, California

U.S. citizenship required.
An equal opportunity employer.

SYLVANIA ELECTRONIC SYSTEMS
Government Systems Management
for GENERAL TELEPHONE & ELECTRONICS

GENERAL SYSTEM

COMPUTERS AND CONTROL SYSTEMS

- OPTICAL SPECIALISTS
- LOGIC DESIGNERS
- PROJECT ENGINEERS
- ADVANCED ELECTRONICS

Scientists and engineers needed with experience in all phases of digital computer and control system design.

Systems organization, logic design, magnetic core and drum memories, dynamic analysis, and electro-optical correlation devices. Also advanced areas such as high-speed tunnel-diode techniques, thin films, and hybrid analog-digital techniques. Applications include airborne digital equipment, numerical machine control, photogrammetric equipment, and special-purpose control computers. Both commercial and military programs, emphasizing advanced development and research. We think you will find this work unusually stimulating and satisfying. Comfortable and pleasant surroundings in suburban Detroit.

If interested, please write or wire A. Capsalis, Research Laboratories Division, The Bendix Corporation, Southfield, Michigan.

Research Laboratories Division

THE Bendix CORPORATION

An equal opportunity employer

Kollsman

Continued Expansion in AEROSPACE SYSTEMS

Creates New Opportunities in Research, Development and Engineering

STAFF ENGINEERS

For creative staff engineering in air data systems, pressure sensors and transducers, optical electronic systems, digital computers and sensors, solid state physics, logical design, systems analysis and synthesis, infrared and visual scanning techniques, information theory, systems development for navigation and guidance of aircraft, missiles and space vehicles, and heat transfer analyses.

DEVELOPMENT ENGINEERS

For project engineering assignments on automatic navigation, air data and flight control systems and devices. Also assignments in ground support equipment in the above areas, as well as in our new ordnance equipment group. Experience in electromechanical/optical systems desirable.

An Equal Opportunity Employer

Please forward resume, in confidence, to Mr. Donald Svenson.

Kollsman Instrument Corporation

A Subsidiary of Standard Kollsman Industries Inc. 80-08 45th AVE., ELMHURST 73, QUEENS, NEW YORK

Positions Open

(Continued from page 122A)

CRITICAL VACANCIES AT GRIFFISS AIR FORCE BASE, ROME, N. Y.

Management Analyst	GS-7	$5355 pa.
Contract Assistant	GS-7	$5355 pa.
Electronic Engineer	GS-7	$6345 pa.
Research Psychologist (Physiological, Experimental & Engineering)	GS-7	$5355 pa.
Librarian (Physical, Sciences & Engineering)	GS-9	$6435 pa.
Technical Manuals Writer	GS-9	$6435 pa.
General Supply Officer	GS-9	$6435 pa.
Industrial Engineer	GS-9	$6435 pa.
Research Psychologist (Physiological, Experimental & Engineering)	GS-9	$6435 pa.
Management Analyst	GS-11	$7560 pa.
Traffic Mgt. Specialist	GS-11	$7560 pa.
Industrial Engineer	GS-11	$7560 pa.
Supv. Tech. Manuals Writer (Electronics)	GS-12	$8955 pa.
Electronic Engineer (2)	GS-12	$8955 pa.
Electrical Engineer	GS-11	$7560 pa.
Mechanical Engineer	GS-12	$8955 pa.
General Engineer	GS-12	$8955 pa.

AUDIO ENGINEER

BSEE or BS Physics. 3 to 5 years experience in the design and development of moving coil microphones and/or miniature dynamic speakers. Manufacturing experience desirable. Progressive company manufacturing electroacoustic transducers in the Metropolitan area. Salary competitive. Send complete resume to Box 2062.

Positions Wanted

By Armed Forces Veterans

In order to give a reasonably equal opportunity to all applicants and to avoid overcrowding of the corresponding column, the following rules have been adopted:

The IRE publishes free of charge notices of positions wanted by IRE members who are now in the Service or have received an honorable discharge. Such notices should not have more than five lines. They may be inserted only after a lapse of one month or more following a previous insertion and the maximum number of insertions is three per year. The IRE necessarily reserves the right to decline any announcement without assignment of reason.

Address replies to box number indicated, c/o IRE, 1 East 79th St., New York 21, N.Y.

ELECTRICAL ENGINEER

Electrical Engineer desires challenging position in R&D work requiring professional competence. Experience in wire communications, data processing and transmission, programming, microwave systems, teaching, technical writing and supervision. Prefer area where graduate study is available. Will forward detailed resume on request. Box 3959 W.

SALES ENGINEER

Desires position as sales engineer in southeastern U.S. Over 10 years in radio and elec-

(Continued on page 126A)



it's already TOMORROW at Westinghouse!

Step into the future at Westinghouse-Baltimore . . . an engineers' company. Live and work with tomorrow's tools to open whole new fields of technology. Work with the nation's top engineers and scientific minds on challenging projects that span the electronic spectrum . . . molecular electronics, Pulse Doppler radar, 3-D radar, underwater sound, advanced weapons systems such as Typhon, and others. Your professional growth is encouraged at Westinghouse, where you have the opportunity to pursue advanced degrees at Johns Hopkins University and the University of Maryland under our Advanced Education Program.

Why don't you talk with Westinghouse about outstanding opportunities in these fields:

Weapons Systems Analysis
Microwave Techniques
Solid State Devices
Applied Physics
Computer Research


Send resume to: Mr. J. F. Caldwell, Dept. 449

Westinghouse
BALTIMORE
P.O. Box 746, Baltimore 3, Md.
AIR ARM • ELECTRONICS • ORDNANCE
An Equal Opportunity Employer

DECISION AND THE RANDOM CHANNEL

For some time now a firm mathematical discipline, Statistical Decision Theory, has been applied to optimize signal reception in many important communication situations. Its most conspicuous success has been in the restricted problem of the reception of a (not too large) number of exactly known signals corrupted by additive independent gaussian noise with a known covariance function. Optimum reception in this case may be obtained through use of a correlation (or matched filter) receiver which uses replicas of the known signals stored either as waveforms or as the impulse responses of linear, time-invariant filters.

When faced with the lack of specific knowledge of channel parameters, decision theory is less authoritative in specifying the form of the receiver. In this more difficult case, it is sometimes plausible to use an adaptive approach and estimate the possible waveforms which could exist at the receiver before noise is added, and to crosscorrelate the noisy received waveforms against these estimates. In fact, the application of decision theory to a channel which can be described by a multidimensional gaussian process with a zero mean and known covariance function, leads specifically to an adaptive receiver which generates reference waveforms from such estimates.



$$y(t) = \int_0^t x(\tau)\, h(t,\tau)\, d\tau + n(t)$$

Generalized model of a communication channel.

At the Philco Research Center, scientists are continuing to study adaptive techniques. Typical programs include 1.) the problems of communicating over channels whose statistics may be both poorly known and changing; and 2.) investigation of non-parametric methods of statistical inference which are not greatly sensitive to unknown parameters.

The Research Division offers attractive staff positions to scientists in a number of areas in addition to communication theory. Electrodynamics, plasma physics, ultramicrowaves, optical communications, and the physics of materials are among the areas of current interest. Letters of application or inquiry may be addressed to:


Mr. W. P. Diefenbach
Personnel Director
Philco Research Center
Blue Bell, Penna.

RESEARCH CENTER
PHILCO®
Famous for Quality the World Over

An equal opportunity employer

ELECTRICAL ENGINEERS

for advanced studies of high-performance electrical propulsion systems...



Great interest has been aroused by our unusual oscillating-electron ion engine which produces a high-velocity, electrically-neutral plasma beam. Since this electrically-neutral stream eliminates the space-charge effect, there is no theoretical limit to the thrust capability of the device. ● Past successes and current progress with this device, (and in other areas of plasma research) now require a material expansion in this entire effort. As a result, a number of very attractive Senior Positions are being created for electrical propulsion specialists — particularly physicists with advanced degrees and experience. ● These positions should have particular appeal to those interested in studies of high-energy plasma sources, diagnostic techniques and other basic investigations that will lead to practical space propulsion devices. Included are both theoretical and experimental investigations of factors that determine plasma potentials, ionization and power efficiencies. ● This program is of the long-range sustained type with both corporate and government sponsorship. Superior facilities and assistance are available for numerical computation and experimental work. Publication of papers is encouraged as is close contact with related university research. ● Salary levels, benefits and the semi-academic approach will appeal to experienced men with demonstrated abilities.

You are invited to contact Mr. W. B. Walsh, Personnel Department

RESEARCH LABORATORIES
UNITED AIRCRAFT CORPORATION
400 Main Street, East Hartford 8, Conn.

All qualified applicants will receive consideration for employment without regard to race, creed, color, or national origin.

Positions Wanted

By Armed Forces Veterans

(Continued from page 124A)

tronics including radio and TV broadcasting, missile instrumentation and most recently, electro-mechanical instrumentation sales engineering. Box 3960 W.

ENGINEER—MANAGER

Age 37, P.E., 11 yrs. Electro-Mechl. Mfg. as Chief Engineer, Manager of Eng., General Manager, Vice-President, including Overseas Assignments. Air Force Vet. Location open including Overseas. Box 3962 W.

SALES REPRESENTATIVE

Physicist and Engineer with twelve years experience, four in sales, is desirous of forming sales representative organization selling instruments and components in the Metropolitan New York area. Age 36, married. Would be willing to consider participation by manufacturers who prefer to make an investment. Box 3963 W.

DESIGN ENGINEER—MANAGER

B.S.E.E. in 1941, also graduate work in specialty. 15 years experience in design and management of antennas, microwave assemblies, and military electronics systems, including ECM, aircraft C & N, and radar. Eight years of large corporation management experience. Prefer suburban area in Mid-Atlantic region. Box 3964 W.

SALES MANAGER

B S.E.E., 8 yrs. experience in Electronic Component sales plus two years experience as

(Continued on page 130A)

ENGINEERS
RESEARCH & DEVELOPMENT

Growing Research and Development Division seeks qualified engineers for equipment development. Work concerns glass container manufacturing process. Excellent opportunity to grow with organization. Stable career opportunities in company famous for extensive research and development operations. New laboratories in attractive Chicago exurban location.

Electronics-Instrumentation

M.S. in Electrical Engineering, Electronics, or Physics plus minimum 5 years experience. Be in charge of new instrumentation and electronics laboratory and be responsible for growth of laboratory in terms of personnel and equipment. Facility will use and develop instrumentation for data gathering, develop automatic inspection instrumentation and systems for process and machine control.

Please submit a complete resume covering personal data, education, work history, and present salary. All replies will be handled in the strictest confidence.

CONTINENTAL CAN CO., INC.
Hazel-Atlas Glass Research
& Development Dept.
Plainfield, Illinois
R. P. Eichhorn

ANTENNA & PROPAGATION ENGINEERS: To carry on theoretical & experimental studies of advanced nature for all radio frequency bands. EE's. (Advanced degree preferred.) Minimum of 6 years experience. C

Ground Support Electronic Systems Engineer

Design and development of ground electronic systems through the RF spectrum for application in the support systems of re-entry or space vehicles. A technical specialist position requiring a BSEE, 6 years experience and a background in such fields as communications, telemetry or radar.

Y

Senior Staff Consultant

for all System Level Experimentation in Electronics for all MSVD programs

System problems include: stabilization and attitude control of satellites and re-entry vehicles; space/ground communications; orbit navigation and control; mid-course and terminal spacecraft navigation and guidance.

An advanced degree is essential for this outstanding opportunity for high level, original work; also a substantial background in systems design. Experience in radar & communications helpful. E

MANAGER

ADVANCED MISSILE & SATELLITE ELECTRONICS

A Significant Opportunity for an Engineer with a Record of Achievement. An advanced degree – MS or PhD and a minimum of 10 years applicable experience is mandatory for the highly competent and creative man required for this position. He will guide an organization responsible for the development of very advanced components for missile & satellite applications. These include incoders, command circuitry, transmitters, digital electronics, etc.

Q

IMMEDIATE OPENINGS AT THE MISSILE & SPACE VEHICLE DEPARTMENT

PHILADELPHIA, PENNSYLVANIA

Your inquiry is invited regarding any of the positions — encompassing many areas of space science and engineering — listed on this page. Please use the INQUIRY CARD provided for your convenience. A prompt answer is guaranteed; your confidence will be respected.

ADVANCED SYSTEMS ENGINEERING

ECM SUB-SYSTEMS for Advanced Reconnaissance Vehicles

Contribute substantially to synthesis & analysis of these systems, utilizing familiarity with RF interference jammers, scanning receivers, modulation techniques, electronic decoys, etc. M

Essentials for this position: Physics or Electronics Degree plus a minimum of 5 years related experience.

Diversified Assignments for Design Engineers

Logic Circuit Design

Provide high level technical evaluation of digital techniques as applied to automatic programming systems for checkout equipment and airborne instrumentation. Requires EE with broad digital background from systems philosophy to final design. S

Digital Components & Circuits

Design and evaluate A/D and D/A converters, multiplexers, parity check generators, digital storage devices, binary counters, etc., for both airborne and ground digital equipment. EE with 2-5 years experience. T

TELECOMMUNICATIONS CONSULTANT

TO LEAD STUDIES AND PRELIMINARY DESIGNS INVOLVING ALL ELEMENTS OF INTERCONTINENTAL COMMUNICATIONS SYSTEMS: COMMUNICATION CENTRAL SWITCHING CENTERS, LOAD ANALYSIS, ETC. QUALIFICATIONS: PHD OR DEEP EXPERIENCE IN COMMUNICATIONS SYSTEMS SYNTHESIS AND PLANNING. THE CALIBRE MAN SOUGHT FOR THIS IMPORTANT POSITION WILL HAVE PUBLISHED PAPERS IN RELATED FIELDS.

W

RADAR SYSTEMS U

Re-Entry Guidance & Space Navigation

Apply radar systems principles to problems of re-entry-guidance and space navigation; define parameters of the technical concept and maintain project control over full engineering effort. Requires EE, strong background in radar systems.

GENERAL ELECTRIC

All qualified applicants will continue to receive consideration for employment without regard to race, creed, color, or national origin.

PROFESSIONAL EXPERIENCE (Two most recent or most applicable jobs)

Company_____ Position _____

Years of experience (from)_____ (to)_____ Salary_____ Assigned Duties _____

Company_____ Position_____

Years of experience (from)_____ (to)_____ Salary_____ Assigned Duties _____

PERSONAL DETAILS

Name_____

Home Address _____ City_____

State_____ Telephone_____ U.S. Citizen Yes ☐ No ☐

Education

Undergraduate College _____ Degree _____ Year of Graduation _____

Graduate College _____ Degree _____ Year of Graduation _____

Position Objective (primary job preference, level of responsibility, salary expectations) _____

464-L

I am interested in the following position(s)

Navigation & Control	E, H
Instrumentation & Communication	C, E, Q, S, T, W
Systems Analysis	M
Advanced Systems	H, M
Ground & Space Support	Y
Analog & Digital Techniques	Q, S, T

Simply circle the appropriate letters of those positions that meet your professional interests and qualifications, fill in the questions to the left — attach a resume if you have one handy — and airmail to:

Mr. Frank Wendt
Missile & Space Vehicle Department
General Electric Company
3198 Chestnut Street
Philadelphia 4, Pennsylvania

GENERAL ELECTRIC

SCIENTISTS
ENGINEERS
CALIFORNIA

offers you and your family

- A world center of the electronic industry for CAREER ADVANCEMENT
- The High Sierra and the Pacific Ocean for RECREATION
- Some of the nation's finest public schools for your CHILDREN
- World Famous Universities for ADVANCED STUDY
- MAJOR CULTURAL CENTERS

while living in such places as

Exciting San Francisco
Fabulous Southern California
Cultural Palo Alto

companies pay interview, relocation and agency expenses

submit resume in confidence to:

PROFESSIONAL & TECHNICAL RECRUITING ASSOCIATES
(a division of the
Permanent Employment Agency)
825 San Antonio Rd.
Palo Alto, Calif.

SYSTEMS ENGINEERS

ORDNANCE RESEARCH LABORATORY

ELECTRONICS ENGINEERS

FUNDAMENTAL AND APPLIED RESEARCH
Acoustics — Noise Reduction
Electronics — Network Theory
Information Theory

★ ★ ★

DESIGN OF ELECTRONIC INSTRUMENTATION

★ ★ ★

APPLICATION AND DESIGN OF ANALOGUE AND DIGITAL COMPUTERS

★ ★ ★

Opportunities for Graduate Study
Faculty Appointments for Qualified Applicants
Excellent Working and Living Conditions

Send Resume to

Arnold Addison, Personnel Director
ORDNANCE RESEARCH LABORATORY
THE PENNSYLVANIA STATE UNIVERSITY
Box 30
University Park, Pennsylvania

All qualified applicants considered regardless of race, creed, color, or national origin.

ELECTRONIC ENGINEERS
FEDERAL AVIATION AGENCY
DUTY IN ALASKA

Career opportunities with the Federal Aviation Agency in Alaska. Apply the latest knowledge of electronics to air traffic control, avionics, telecommunications, and air navigation aids in the installation, modification and maintenance of electronic systems on Federal airways.

Additional training provided at Government expense, to keep abreast of technical advancements in the Electronics Field, through assignment to the Federal Aviation Agency training center located at Oklahoma City, Oklahoma.

FRINGE BENEFITS ACCRUING TO FEDERAL EMPLOYEES:

ANNUAL LEAVE	HEALTH INSURANCE
SICK LEAVE	COMPENSATION FOR INJURY ON JOB
MILITARY LEAVE	UNEMPLOYMENT COMPENSATION
HOME LEAVE	25 PER CENT COST-OF-LIVING ALLOWANCE
RETIREMENT	
LIFE INSURANCE	

REQUIREMENTS

Applicants must be United States Citizens and possess BSEE degree from accredited engineering school or demonstrate comparable background through Civil Service Engineering examination. In addition to minimum experience and training requirements, applicant must have had professional engineering experience as indicated below for each grade:

Grade	*Base Salary*	*Gross Salary*	*Experience Required*
GS-5	$5,335.00	$6,668.75	None
GS-7	6,345.00	7,931.25	1 Year
GS-9	6,435.00	8,043.75	2 Years
GS-11	7,560.00	9,450.00	3 Years

Gross salary includes 25 percent Alaskan cost-of-living allowance which is non-taxable for Federal Income Tax purposes. Engineers in travel status away from the Anchorage headquarters receive a travel allowance. The best qualified applicant will be selected regardless of race, color, creed or national origin.

Applicants who meet the above requirements should write to:

FEDERAL AVIATION AGENCY,
P.O. BOX 440
ANCHORAGE, ALASKA



A panoramic concept on space... you find it at Lockheed

Long experience and proven capability give Lockheed a great advantage: perspective on space. This results in programs that cover the broad spectrum of aerospace dynamics; that present the most far-reaching technological problems; that offer endless creative challenge to Scientists and Engineers; that give them new concepts to explore—new goals to reach.

This far-ahead program in the concepts and vehicles of space creates a climate most favorable to advancement in the state of the art as well as in professional status.

Scientists and Engineers with an eye to a secure and rewarding future will find these openings at Lockheed worthy of serious consideration: Aerodynamics; thermodynamics; dynamics; electronic research; servosystems; electronic systems; physics (theoretical, infrared, plasma, high energy, solid state, optics); electrical and electronic design; structural design (wing, empennage, fuselage); human engineering; reliability; wind tunnel design. Write today to Mr. E. W. Des Lauriers, Manager Professional Placement Staff, Dept. 1812, 2402 N. Hollywood Way, Burbank, California. An equal opportunity employer.

LOCKHEED *CALIFORNIA COMPANY*

A DIVISION OF LOCKHEED CORPORATION

ADVANCED SYSTEMS DEVELOPMENT

Emerging now from three years' intensive effort at International Electric is a computer-based communication system that equals the state-of-the-art. This system was made possible by our systems management capability, which includes the design, development, production monitoring and installation of advanced electronic systems. Our continuing progress will be determined by our ability to advance the state-of-the-art in our design and development of future systems.

This requires the application of creativity and technical experience by engineers, mathematicians and physicists. To our recently organized Development Division we seek to add *Development Specialists* with at least six years' association with large projects. They will evolve requirements for systems users, working in such areas as air traffic control, ASW, satellite control and command and control systems, and in such projects as information retrieval, man/machine communications and advanced computer utilization.

Digital Equipment Engineers are needed to translate systems requirements into system hardware. We seek E.E.'s with at least five years' experience to work in such areas as logical design; core, drum and tape memories; peripheral equipment; and large-scale switching center techniques.

If you have the experience and interest in either of these programs, and wish to associate yourself with the professional challenges offered by them, please send resume to Manager of Technical Staffing, Dept. PO.

INTERNATIONAL ELECTRIC CORPORATION

An Associate of International Telephone and Telegraph Corporation

Rte. 17 & Garden State Parkway
Paramus, New Jersey

An equal opportunity employer.

Positions Wanted

By Armed Forces Veterans

(Continued from page 126A)

Project Engineer for Component Manufacturer. Successful record in increasing sales. Tripled sales in present territory in three years. Box 3965 W.

PRODUCTION MANAGER

Mgt. Executive, 39, M.I.E., B.M.E., 15 years varied experience. El/Mech Industries, seeking plant production Manager level opportunity with/without investment. Tau Beta Pi; Pi Tau Sigma. Box 3972 W.

PATENT ATTORNEY

Electronics and mechanical arts, 4 years corporate and 1 year law firm experience, writing and prosecuting applications, interferences, infringement studies and licensing. 6 years engineering experience including transistor circuitry and aircraft instruments. Interested in position in New York City area. Box 3973 W.

ELECTRONICS TECHNICIAN

Graduate RCA Institute V7 course, Age 24, Single. Willing to relocate in United States or abroad, Member IRE, Resume upon request. Box 3974 W.

FREE LANCE TECHNICAL WRITER

Experience and degrees in electronic engineering and physics. Associate in St. Paul and Milwaukee. Box 3975 W.

FREE LANCE TECHNICAL WRITER

Experience and degrees in electronic engineering and physics. Associate in St. Paul and Milwaukee. Box 3976 W.

ENGINEER/PILOT

BSEE '60. Age 29. Former USAF pilot, presently ANG pilot, hold commercial license (multi-engine). 16 months field engineering experience with computer type checkout equipment for missile systems. Speak, write and read Spanish fluently. Seeks challenging position in Spanish speaking country or Europe. Box 3977 W.

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 104A)

Tantalum and Mylar Capacitors

Gulton Industries, Inc., 212 Durham Ave., Metuchen, N. J., will begin marketing Faradyne solid tantalum and tubular mylar type capacitors.

The arrangement between Gulton and Faradyne Electronics Corp., Belleville, N. J., will complement Gulton's present line of ceramic types.

These solid tantalum capacitors feature high reliability in low voltage transistorized circuits in a range from 1.0 μf to 47.0 μf at voltage ratings up to 35 volts

(Continued on page 132A)



CIRCUIT DESIGN

If this is your career interest, we have projects involving digital computers of extremely small size. Let us tell you more about this — confidentially. Write to Mr. Harry Laur — Research and Engineering Staff.

Qualified applicants will be considered regardless of race, creed, color or national origin.

LITTON SYSTEMS, INC. Data Systems Division
Canoga Park, California



VITAL: command and control systems which collect, transmit, process and display information to military commanders responsible for compressed-time decisions.

THE MITRE CORPORATION

is now engaged in designing and developing computer-based command and control systems which collect, sort, transmit, and display information vital to those who make command decisions. SAC's Command and Control System, SAGE, BMEWS, NORAD, MIDAS and other urgent military programs are all within the scope of MITRE'S system integration work.

Formed in 1958, MITRE is an independent nonprofit corporation with a growing technical staff engaged in systems planning, engineering and management for the Air Force Electronic Systems Division.

You are invited to join this scientific community and participate in important work which is performed in an atmosphere of objectivity and free inquiry.

Engineers and scientists interested in the vital field of command and control technology may inquire about openings in:

- **Operations Research**
- **Communications**
- **Human Factors**
- **System Cost Analysis**
- **Econometrics**
- **Radar Systems and Techniques**
- **System Analysis**
- **Advanced System Design**
- **Computer Technology**
- **Mathematics**
- **Air Traffic Control System Development**
- **Antenna Design Microwave Components**

Write in confidence to: VICE PRESIDENT — TECHNICAL OPERATIONS, THE MITRE CORPORATION, Post Office Box 208, Dept. MZ4, Bedford, Massachusetts

An equal opportunity employer

Boeing openings for SYSTEMS TEST ENGINEERS

The steady expansion of missile and space projects at Boeing, including the Dyna-Soar manned space glider and the Minuteman solid-fuel ICBM, offers outstanding career openings for Systems Test Engineers. Positions are available now in the Aero-Space Division for engineers meeting these minimum requirements: a B.S. degree in Electrical Engineering, Mathematics or Physics, plus at least three years of applicable experience.

Assignments offering exceptional opportunities for advancement are available in the area of data systems development, design and application in the field of airborne ground telemetry or transducer equipment, or in the field of test data processing as related to pulse circuitry. There are assignments also in the application of digital techniques to the processing of test data.

Salaries are competitively commensurate with education and experience. These positions are in Seattle, in the uncongested Pacific Northwest, famous for mild year-round climate, unexcelled recreational facilities, housing and schools.

Send your resume today to Mr. William B. Evans, The Boeing Company, P.O. Box 3707-PRN, Seattle 24, Washington. The Boeing Company is an equal opportunity employer.

BOEING

NEWS New Products

(Continued from page 130A)

DCW. In addition to standard types meeting or exceeding MIL-C-26655A and MIL-C-26655/2, known as "Faratans," other types are available. Each type of solid tantalum capacitor has been designed for low leakage current, a low dissipation factor and low noise level.

Tubular mylar capacitors in the line are offered particularly for applications requiring high reliability, small size and light weight. In small compact cases, these capacitors have a capacitance range of from 0.001 μf to 2.0 μf and are available at voltages up to 600 volts DCW. The dissipation factor at 25°C and 1000 cps does not exceed 1 per cent, and operation in temperatures up to 125°C is possible, depending on voltage rating. These capacitors are designed to meet or exceed military requirements. After moisture tests in accordance with MIL-STD 202A (methods 102 and 106) Faradyne mylar capacitors will withstand 250 per cent rated voltage for one second and have an insulation resistance greater than 10,000 megohms at 25°C.

In addition to standard types, solid tantalum and tubular mylar capacitors are available in special configurations and capacitance values upon request. Further information may be obtained by writing to the firm.

(Continued on page 136A)

DESIGNED to **FIND** the creative **ENGINEER** and **SCIENTIST** **IN THE $18-$35,000 RANGE**

PRINCIPAL SCIENTISTS

- Physical Electronics, gas plasma, MHD or microwave tube to develop R & D group.
- Thermionics and related problems as applied to plasma physics.
- Plasma, nuclear and astrophysics. Work in a purely theoretical group and act as Corporate Consultant to other divisions.
- Telemetry GSE Program Mgr. Medium sized Co. with rapid growth. Excellent Opportunity.

All Expenses Paid by Employer Clients

CROSS COUNTRY CONSULTANTS

Personnel Search Specialists

225 E. Redwood St., Baltimore 2, Md.
LExington 9-6604

ARIZONA
Phoenix

"Opportunity & Ideal Living"

GOODYEAR AIRCRAFT CORPORATION
Arizona Division

ELECTRONIC CIRCUITRY

Radar Circuitry, Data Processing, Analog Computer Circuitry, Control Systems.

THEORETICAL PHYSICIST

Background in Electromagnetic Theory and Plasma Physics, Ph.D. Preferred.

EXPERIMENTAL PHYSICIST

Background in Physical Optics, Classical Mechanics, Microwaves, and Information Theory or Quantum Mechanics and Statistical Mechanics, Ph.D. Preferred.

ELECTRONIC PACKAGING

"All qualified applicants will receive consideration for employment without regard to race, creed, color, or national origin."

Request Application or Send Resume to:

B. A. Watts, Engineering Personnel
Goodyear Aircraft Corp.
Litchfield Park, Arizona

Similar Positions at Goodyear Aircraft Corporation, Akron, Ohio

Engineering Section Head
For Solid State Power Supplies

Here is an ideal opening for an experienced Engineer seeking a true growth position. The competent individual selected to fill this important opening will be responsible for technical direction of engineering staff engaged in design & development of solid state power supplies. He should possess superior technical capability plus ambition and proven administrative skills. Starting salary is most generous, benefits are liberal and advancement opportunities are assured.


Direct your inquiries in fullest confidence to:
Director of Employee Relations

THE DAVEN COMPANY
A Subsidiary of General Mills
530 West Mt. Pleasant Ave., Livingston, New Jersey
An Equal Opportunity Employer

career opportunities

ACF
ELECTRONICS

a company on the move!
ACF Electronics is expanding dynamically. We invite qualified Electronic Engineers to check a career appointment in the following areas:



ADVANCED DIGITAL SYSTEMS

Advanced development of digital computer techniques and solid state devices on navigational, tactical and training projects for aircraft, missile and aerospace simulator systems.

WORLDWIDE FIELD OPERATIONS

Installation, maintenance, operation and instruction on company and competitor electronic equipments, including communications, computers, radar and simulator systems. Assignments in this country and abroad.

Our modern facilities are located in residential suburbs of Washington, D. C. and New York City, affording you a choice of city, suburban or country living. Advanced study under tuition refund may be conducted at several nearby universities.

For details, contact: Mr. A. C. Sugalski, Manager, Professional Staffing, Dept. A-16 at our Riverdale facility.

ACF ELECTRONICS
DIVISION
ACF INDUSTRIES

Riverdale, Md. • Paramus, N.J.

an equal opportunity employer

Career Opportunities in

SEMICONDUCTOR TECHNOLOGIES

IBM THOMAS J. WATSON RESEARCH CENTER

The new IBM Thomas J. Watson Research Center in Yorktown, N.Y., is undertaking important new long-range projects requiring scientists and engineers with experience in, or relating to, various aspects of semiconductor research. Research projects under way are directed toward purely scientific goals . . . as well as toward developing technology for advanced information handling systems.

SEMICONDUCTOR COMPOUND CHEMISTRY

Several openings exist for Physical and Inorganic Chemists to conduct research on the preparation and purification of materials, and to study their physical properties. Experience is highly desirable, but not necessary.

SEMICONDUCTOR VAPOR GROWTH

Applicants should be familiar with studies of vapor growth reactions in general as well as vapor growth junction technologies. An advanced degree in Physical Chemistry, Metallurgy or Physics is desirable, but a B.S. with a strong background in related technology will be considered.

SEMICONDUCTOR CIRCUITS

The position involves the proposing, experimental exploration, and evaluation of circuits which have a high degree of probability of lending themselves to fabrication into integrated circuitry by means of advanced semiconductor technologies including epitaxial crystal growth from the vapor phase. This work will be done in close cooperation with device fabrication scientists. The ultimate aims of this activity include consideration of integrated or preconnected computer circuits wherein transmission lines are treated as integral parts. An advanced degree or equivalent in Electrical Engineering or Physics is desirable. We prefer experience in circuits using semiconductor devices as applied to large high-speed computers.

SEMICONDUCTOR CRYSTAL GROWTH

This is an outstanding opportunity for a person with an advanced degree or equivalent experience in Physical Metallurgy or Chemistry. The person who can fill this position must be able to take charge of a semiconductor crystal growing activity and carry out a program of research on related problems. Experience should include the preparation of solid state materials and a background in semiconductor physics.

The Thomas J. Watson Research Center at Yorktown, N.Y., is located in pleasant, rural Westchester County countryside, just 35 miles from New York City. The Research Center was designed to provide the best possible working environment for scientists and engineers engaged in advanced research studies. The location provides excellent schools and housing. IBM offers a fully paid benefits program. All qualified applicants will receive consideration for employment without regard to race, creed, color, or national origin.

Please write, outlining your education and experience to:

Mr. J. B. Farrington, Dept. 645M
Thomas J. Watson Research Center
P.O. Box 218
Yorktown Heights, New York

IBM

INTERNATIONAL BUSINESS MACHINES CORPORATION

ENGINEERS SCIENTISTS MANAGERS

New long term diversified development and design contracts create unusually attractive opportunities at the Link Division of General Precision, Inc. Qualified men, proficient in broad systems and equipments engineering, will be interested in these commercial and military projects. Both aircraft and space vehicle systems are involved. Excellent salaries and ideal living in the Binghamton, New York area will attract the qualified professional man or manager seeking advancement opportunity and challenging work.

— laboratory precision measurement, visual displays and special projects including G.S.E., simulators and checkout equipment. —electro-optical precision measurement systems. — 12-15 years mechanical design, electronic packaging, model shop construction, and department supervision in military programs. Direct product design department, model shop, product programs and advanced development.

SENIOR & JUNIOR ENGINEERS

— visual systems projects. —optical, electro-optical measuring, inspection and scanning systems. —periscopic, projection and relaying lens, analysis of optical problems, laboratory proposals. —transistor circuits, switching circuits, computer logic, "NOR" logic, direct-coupled transistor logic, proposals. —electronic systems project responsibility. Supervise design, test and verification of prototype model and preparation of engineering data. —analog computing devices, audio systems, transistorized amplifiers, radio aids, radio navigation, aircraft communications. — program digital computers, digital systems design. —define problems, program and solve equations of flight simulation, specify components, initiate requirements for design and configuration of electronic and electro-mechanical systems. — systems desig of servos, hydraulics, missiles, life support systems. — systems design of mechanisms, structures, hydraulics, electro-mechanical packaging, materials, plastics. — simulation, project responsibility for computation of equations, defining motion and engine performance of aircraft, specification interpretation, concept determination, data search and liaison, data analysis and processing, test guide inception and computation. — process raw aerodynamic coefficient data and engine data into equation form for electronic simulation, engine performance calculations, test guide to check simulator. —airframe and spacecraft performance, stability and control, engine performance, analog simulation and digital computations.

All positions require an appropriate degree—advanced degree is highly desirable for managerial and senior positions. Minimum experience required is 4 years—an additional 4 years experience is required for managerial and senior positions.

Qualified men are invited to phone collect (RAymond 3-9311) or write Mr. James T. Gibbons. An equal opportunity employer.

LINK DIVISION
GENERAL PRECISION, INC.

Binghamton, New York

ELECTRONIC ENGINEERS

Research and Development

Armour Research Foundation, one of the largest independent research organizations, offers exceptional opportunities in Chicago for qualified Electronics research engineers to work on a variety of industrial and military research projects in the fields of

RADAR

ANTENNAS

CIRCUIT DEVELOPMENT

MICROWAVES

GUIDANCE & CONTROL

PROPAGATION

COMMUNICATION

SIGNAL PROCESSING

SEMICONDUCTOR DEVICES

MEASUREMENT TECHNIQUES

Minimum requirements include a B.S. degree in Electrical Engineering with above average academic grades. Research experience in one of the above fields is highly desirable, though not absolutely necessary.

Our environment combines the better features of academic and industrial research and offers you the opportunity to work on advanced research programs.

Staff members receive attractive salaries, up to 4 weeks vacation, generous insurance and retirement benefits, and tuition paid graduate study. Our Chicago location offers excellent cultural and recreational advantages. All qualified applicants will receive consideration for employment without regard to race, creed, color, or national origin. Please reply in confidence to Mr. S. M. Ream.

ARMOUR RESEARCH FOUNDATION
OF ILLINOIS INSTITUTE OF TECHNOLOGY
TECHNOLOGY CENTER, CHICAGO 16, ILL.



Sometime in 1963 Surveyor will land on the moon

Work on Project Surveyor, one of the most important in our nation's space program, is now underway at Hughes. It is an urgent, demanding project. The engineer or scientist who qualifies for a position on Project Surveyor will have opportunities for technical accomplishment and personal growth which are seldom offered.

At the same time, he will gain unique background which can insure his future in the expanding space fields.

Project Surveyor is just one of Hughes' efforts in space work. It involves the design and development of a spacecraft which will "soft" land on the moon and gather, analyze and transmit back to earth information about the moon's surface, subsurface and atmosphere. Other Hughes space work includes: ARPAT (terminal anti-ballistic missile defense), BAMBI (anti-ballistic missile defense feasibility study), COLIDAR and SYNCOM (space communications systems), Space Propulsion Systems and Space Power Systems.

Hundreds of openings exist for imaginative junior and senior engineers and physicists. Experience is preferred, but not required. Representative openings include:

CONTROLS ENGINEERS Concerns hydraulics, airborne computers, and other controls related areas for: missiles and space vehicles, satellites, radar tracking, control circuitry, controls systems, control techniques, transistorized equalization networks and control servomechanisms.

CIRCUIT DESIGNERS Involves analysis and synthesis of systems for: telemetering and command circuits for space vehicles, high efficiency power supplies for airborne and space electronic systems, space command, space television, guidance and control systems, and many others.

SYSTEMS ANALYSTS To consider such basic problems as: the requirements of manned space flight; automatic target recognition requirements for unmanned satellites or high speed strike reconnaissance systems; IR systems requirements for ballistic missile defense.

Immediate openings also exist for Power and Propulsion Engineers, Analytical and Design Engineers, Structures Engineers, Heat Transfer Engineers, Equipment Installation Engineers, Electromagnetic Theory Specialists and Antenna Specialists.

Inquire today. Your reply will be treated with strict confidence. Please airmail your resume to **Robert A. Martin, Supervisor of Scientific Employment, Hughes Aircraft Company, 11940 West Jefferson Blvd., Culver City 58, California.**


Creating a new world with ELECTRONICS

HUGHES

HUGHES AIRCRAFT COMPANY
AEROSPACE DIVISIONS
An equal opportunity employer.

INFORMATION PROCESSING RESEARCH

APPLIED RESEARCH LABORATORY



Pictured above is the Applied Research Laboratory's new building which was recently occupied. The Laboratory is the central research facility for Sylvania Electronic Systems.

The Applied Research Laboratory is located in Waltham, Massachusetts, a suburb of Boston, convenient to Harvard, M.I.T., Boston University, Brandeis, Northeastern, and several other colleges and universities offering outstanding programs for advanced study and professional growth.

We should like to add to our staff qualified personnel with advanced training and creative experience in the Information Processing Research area. In particular, experience in advanced computer and data processing technology, applied mathematics and mathematical physics, statistics, statistical decision theory, speech or pattern recognition, perception and learning theory, applied linguistics and information theory is desirable. Three areas are presently of utmost importance.

(1) CHARACTER RECOGNITION – instrumentation of page and form readers, design of recognition logics for statistically distorted printing.

(2) SPEECH RECOGNITION – computer simulation and intelligibility testing of analyses of speech via expansions of series of orthonormal functions for machine recognition and bandwidth compression.

(3) PERCEPTION AND LEARNING THEORY – analysis of models of automata and human perception in learning, their experimental evaluation and ultimate instrumentation (bionics) and their applications.

Efforts are equally divided between instrumentation, experiment, and theoretical analyses.

Additional information may be obtained by writing Dr. Donald B. Brick
Applied Research Laboratory

SYLVANIA ELECTRONIC SYSTEMS
Government Systems Management
for GENERAL TELEPHONE & ELECTRONICS

40 Sylvan Road—Room H-12—Waltham 54, Mass.

An Equal Opportunity Employer


NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 132A)

Computer Simulator Tests Memory Systems

Rese Engineering, Inc., "A" and Courtland Streets, Philadelphia 20, Pa., announces Model 2032 Memory System Exerciser, an automatic, high speed digital computer simulator that tests and evaluates, for a wide range of operating parameters, complete memory systems, in laboratory analysis and production testing. Of modular construction and with unusually versatile logic organization, the 2032 simulates exact computer environment for testing, during the development, prototype and production stages of coincident-current and word organized core, twistor, rod, multi-apertured and thin film memories.



Operating with address to address cycle times continuously variable from 100 to 3 microseconds, Model 2032 accommodates random access memories or serial buffers with address capacities to 16,384 words and word lengths to 48 bits. Binary or Binary coded Decimal address capability of the 2032 permits rapid changeover from one type of address logic to the other. Memories with separate "X" and "Y" address inputs are accommodated by a split address counter.

Model 2032 Memory System Exerciser incorporates four major functional sections: Timing Generation, Word Generation, Address Generation, and Word Register and Error Detection.

Timing Generation controls the 2032 as well as the memory under test. In addition to the Exerciser's internal pulses, there are six general purpose pulses for use in the memory under test. They may be used as the Read Pulse, Write Pulse, Sense Amplifier Strobes, etc. The location and width of these pulses are variable and easily controlled.

Word Generation controls the word length and the data contained in each word. This section generates a variety of patterns as well as one "ones," all "zeros," and the standard checkerboard patterns. The Generator will supply other selected patterns such as 2, 4, 8, 16 or 32-bit repetitive pattern based on the address counter. The pattern can contain any number of "ones" or "zeros" provided there is only one transition from logical "zero" to logical "one," and only one transition from logical "one" to logical "zero." Patterns can be complemented four times in any pass through the memory at any four addresses that can be selected by any four bits of the address counter. The combination of arbitrary "one" and "zero" selection, 2, 4, 8, 16, or 32-bit repetitive patterns, and the complementing feature combine to effect exceptionally versatile programming capability. Word pulse output position and width is controlled by one of the six timing pulses in the Timing Generation portion of the Exerciser.

The address Generator is designed for widest possible application and consists of a 14-bit binary counter which is organized to be used in any of three modes selected by one three-position switch: as a binary coded decimal counter: as two seven-bit counters, in memories with two modes of address; or as a straight binary counter. The address counter can be set to count between any two addresses selected by two sets of switches. One set selects the initial address and the other set selects the maximum address. This feature permits closer examination of any portion of the memory under test. A level output and a pulse output are available from the address counter. The position and width of the pulse output is controlled by one of the six general purpose timing pulses.

(Continued on page 138A)

NCR

*National**

PHYSICAL RESEARCH AND ENGINEERING

Continued growth and lasting stability underline the excellent professional opportunities at NCR's Engineering and Research Center in Dayton, Ohio. Projects in progress require personnel for the following positions:

SEMI-CONDUCTOR PHYSICIST

Ph.D. with 2-4 years of experience in semi-conductor development and applied research.

MAGNETICS RESEARCH PHYSICIST

Ph.D. with 2-4 years of research and development experience in field of magnetics.

SOLID STATE ELECTRONICS

Ph.D. or M.S. in Physics with 2-4 years experience in Solid State Physics and Electronics.

LOW TEMPERATURE ELECTRONICS

Ph.D. or M.S. in Physics with experience in low temperature field to work in cryotron research program.

PHYSICAL CHEMIST

Ph.D. with background and experience in materials preparation, in particular—magnetic materials, thin films, inorganics, or semi-conductors.

To be considered for one of the above openings or others that may match your particular professional training, write now to: Mr. Thomas Wade, Technical Placement, The National Cash Register Company, Main and K Streets, Dayton 9, Ohio.

AN EQUAL OPPORTUNITY EMPLOYER

ENGINEERS

NOW—CHOOSE YOUR ASSIGNMENT AND LOCATION THROUGH OUR NATION-WIDE PLACEMENT SERVICE

SALARIES $9,000 to $20,000

We can offer you a large selection of diversified positions with America's foremost electronic organizations WITH NO COST TO YOU.

SOME POSITIONS FOR RESIDENT NON-CITIZENS AND CANADIANS

WHAT WE DO FOR YOU—

Take all the work from you—no need for you to write to five or six companies, fill out applications for each one, only to find there is no job that interests you. We do all that for you, find the job that you want—in the location you want—we work with over 250 companies—all over the country.

ALL WE ASK YOU TO DO—

Send us 3 complete resumes, telling us your present and desired salary; the kind of work you want and where you would like to live. That is all you have to do!

THEN YOU—

Wait to hear from us or our clients. There is no need to write directly to any companies, as we do all that for you and at absolutely NO COST TO YOU!

Engineering managers, systems, projects, and design and development engineers:

INDICATE YOUR AREAS OF INTEREST

- ☐ Transmitters
- ☐ Servos
- ☐ Displays
- ☐ Satellite Tracking
- ☐ Weapon Systems Analysis
- ☐ Antennas
- ☐ Receivers
- ☐ Analog and Digital Devices
- ☐ Radar Techniques
- ☐ Logic Design
- ☐ IF Devices
- ☐ Reliability
- ☐ Microwave
- ☐ Engineering Reports
- ☐ Structures
- ☐ Precision Mechanisms

A National Electronic Placement Service Established in 1937. You are assured of prompt and completely confidential service by forwarding three resumes to HARRY L. BRISK (Member IRE)

APS Accredited Personnel Service

Employment Counselors Since 1937

Department A


12 South 12th St., Philadelphia 7, Penna. WAlnut 2-4460

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 136A)

The memory Word Register is a flip-flop register used to staticize the memory output. For checking, this register is compared with the Word Generation portion of the Exercise. Depending on the mode of operation, when an error occurs, the Exerciser will stop or count the error and continue. If it stops in the Error Stop mode, the indicator lights on the front panel show which address is in error and which bit of the word is in error. If the Exerciser is in the Error Count mode, memory errors are recorded on an error counter located on the front panel.



HIGH VOLTAGE ENGINEERING CORPORATION

The dynamic leader in the research, development, and manufacture of Particle Accelerators now serving the academic, medical, and industrial needs throughout the world . . . cordially invites you to discuss career opportunities presently available in our Applied Physics, and Engineering Divisions from the senior to junior levels.

APPLIED PHYSICS

EXPERIMENTAL PHYSICISTS . . . Career opportunities immediately exist for physicists whose experience and interest relate to ion and electron optics, high vacuum systems and techniques, and beam handling. An appreciation for applications, engineering, and production would be desired.

APPLIED PHYSICISTS . . . To apply basic analytical knowledge to calculations regarding magnetic systems in conjunction with research and development of particle accelerators, BS or MS degree in Math, Engineering or Physics and demonstrated ability to do analytical work in an applied capacity required.

ENGINEERING

ELECTRICAL ENGINEERS . . . To design and develop basic electronic amplifiers and stabilization systems, magnetic field measuring devices, and control systems. Good basic knowledge of electronic circuit theory required.

ELECTRONIC DESIGN ENGINEERS . . . To design amplifiers, power supplies, etc., working with project concerned with the design and development of tandemaccelerators.

Employment will be at the modern, fully equipped research facilities of High Voltage Engineering Corporation where our outstanding technical staff has produced the world's most advanced line of particle accelerators and associated devices.

Please direct resume
in confidence to Mr. Louis J. Ennis,
Assistant Personnel Manager,
P.O. Box 98

HIGH VOLTAGE ENGINEERING CORP.

BURLINGTON, MASSACHUSETTS

(12 Miles North of Boston)

All qualified applicants will receive consideration for employment without regard to race, creed, color or national origin.

Delay Line Network

A new multi-tap high accuracy delay line with excellent high frequency response is announced by **Columbia Technical Corp.,** Woodside 77, N. Y. The unit, Type CTC-1068 "Q-Line," has an 8 Mc bandwidth for an overall delay of 6.3 microseconds, at an impedance level of 200 ohms. The resulting rise time is 0.08 microsecond, thus yielding a delay-to-rise time ratio of about 80:1.



The new Q-Line has 63 taps spaced at 0.1 microsecond intervals. Overall delay as well as tap delay accuracy are ±1%. The temperature coefficient of delay is 30 PPM/°C. Housed in a 5″×5″×4″ steel case, the unit is hermetically sealed and designed to withstand saltspray, humidity, shock and vibration requirements per MIL-STD-202B.

The combination of wide bandwidth, electric accuracy with high stability and ruggedness of construction make Type CTC-1068 "Q-Line" ideally suited for critical applications, such as airborne computer installations. Full information may be obtained by writing the manufacturer.

AFC Systems

Orion Electronic Corp., 108 Columbus Ave., Tuckahoe, N. Y., announces the development of its AFC units for frequency control applications. Designated as Series C units, a typical transistorized AFC unit for missile application is shown in the accompanying illustration. Only high temperature components are employed, such as silicon transistors, tantalytic capacitors, and so forth to insure high temperature operation of 125°C. This particular AFC unit is designed to keep the difference signal between the two oscillators within a prescribed error for wide variations in their characteristics.

(Continued on page 140A)

OPTICAL COMMUNICATIONS Gordon Jacobs, an Electronics Laboratory communications engineer, recently reported that a ruby laser burst system using 350 watts of primary power can provide a range of 10,000 nautical miles at 400 bits per second. In an experimental system development at the Laboratory a KDP crystal was used to modulate the light source frequencies up to 200 mc. The optical receiver utilized a multiplier phototube. Mr. Jacobs stated that future improvements in light sources offer an enormous potential for optical communications. A considerable technical effort is required in many areas: e.g. atmospheric propagation, wide-band modulation and wide-band detection.

ADAPTIVE NEURON COMPONENT Thomas Bray, of the Electronics Devices & Networks group, presented a paper a short time ago describing "An Electro-Optical Shift Register" which employs an adaptive neuron component. This artificial neuron utilizes optoelectronic elements as analog multipliers. (Extremely low volume is an advantage of this Shift Register: a 20-input component consisting of more than 40 analog multipliers and 20 analog memory elements occupies about 2.5 cubic inches.) This work of Mr. Bray's is part of the Laboratory's endeavor in the field of new logic and memory techniques development.

A SCHEME TO CREATE A "RADIOWAVE ATMOSPHERE" NEAR THE MOON ...has been proposed by Dr. Frank Dickey, radar consultant with the Laboratory. He suggested "a powerful earth-based transmitter be employed to beam microwave energy at the moon. The interaction of incident and reflected energy near the lunar surface would create a stationary radiowave pattern...which would be sensed by an incoming spacecraft. This new technique can provide a simple, lightweight device capable of performing all sensory functions needed to achieve soft lunar landings." (First reported at IRE Convention in March 1961, theoretical work is continuing on this concept.)

THE CARDIAC PACEMAKER Electronics Laboratory engineers, headed by Jerome J. Suran, Manager of the Electronic Applications Laboratory, developed this device to control the beat of the human heart. It is the first surgically implantable unit whose rate can be adjusted by the patient to accommodate strenuous activities, such as stair-climbing. Its successful use was described in the May '61 issue of LIFE MAGAZINE. A continuing program of cooperation with medical researchers is now part of the Laboratory effort. It includes work on mechanisms that will stimulate other muscles which have suffered deterioration (from paralytic disease or injury) and the development of new diagnostic techniques.

RESEARCH ENGINEERS AND SCIENTISTS...

Can You Define Boundaries For Electronics?

Investigators at General Electric's Electronics Laboratory believe that no technology is so "remote" that it may not one day contribute to advances in one of the many diverse areas conveniently labeled "electronics" today. The "oneness" of all science is a matter of conviction at the Laboratory, to both Staff Members and Management. The result is an enriching collaboration among individuals trained in many fields, from biochemistry to microwaves, from molecular physics to metallurgy, from geophysics to thermionics ■ Indicative of the breadth of the Laboratory's interests and accomplishments are the above abstracts on recent investigations by members of the staff. Some of this work is now being carried into advance development stages ■ Scientists and engineers (with PhD or MS) attracted by an opportunity to pursue investigations in a stimulating intellectual climate with colleagues from many fields are invited to inquire about opportunities to explore • NEW SOLID STATE DEVICES; APPLICATIONS TO COMPUTER TECHNOLOGY; ADVANCED MICROELECTRONIC CIRCUITRY; MAGNETIC THIN FILMS; SUPERCONDUCTIVE FILMS • NEW APPROACHES TO ELECTRONIC SIGNAL PROCESSING • NEW DATA PROCESSING TECHNIQUES, USING THEORIES OF AUTOMATA, ADAPTIVE SYSTEMS AND OTHERS • PHYSICAL PHENOMENA WITH POTENTIAL FOR MICROWAVE AND COHERENT OPTICAL DEVICES • NEW APPROACHES TO CONTROL SYSTEMS USING NON-LINEAR, ADAPTIVE AND OTHER TECHNIQUES • ORGANIC AND INORGANIC CHEMISTRY: NEW MATERIALS AND PROCESSES (B S degree acceptable) • ADVANCED DEVELOPMENT IN HIGH POWER AND DIGITAL SOLID STATE CIRCUITRY • ADVANCED DEVELOPMENT IN MEASUREMENT INSTRUMENTATION ■ Write in confidence to: Mr. Richard J. Sullivan, Dept. 53-L, General Electric's Electronics Laboratory, Electronics Park, Syracuse, New York.

"An Equal Opportunity Employer."

GENERAL ELECTRIC

PROFESSIONAL CONSULTING SERVICES

Advertising rates

Professional Consulting Service Cards.

1 insertion	$ 30.00
12 insertions	$240.00

50% discount to IRE members on 3 or more consecutive insertions.

In IRE DIRECTORY $30.00 flat rate

New rate effective January 1962
1 insertion $35.00
12 insertions $300.00
50% discount to IRE members on
3 or more consecutive insertions.
In IRE DIRECTORY $35.00 flat rate
1 inch only, no cuts or display type.

Advertising restricted to professional engineering and consulting services by individuals only. No product may be offered for sale, and firm names may not be mentioned in cards.

Prof. D. S. BUGNOLO, Sc.D.
Consultant
Satellite & Space Communication
Propagation, Antennas, Information Theory
61 Lillian Place Red Bank, N.J.
SHadyside 7-1549

SIDNEY FRANKEL, Ph.D.
& associates
Engineering Research • Technical Consultation
Feasibility Studies
Communication and Control Systems
Radio and Radar Techniques
1165 Saxon Way Menlo Park, Calif.
DAvenport 6-9166

Proposals Research Development
Reports Prototype Units
DR. A. W. FRIEND, P. E.
CONSULTING ENGINEER
AND PHYSICIST
5903 City Avenue TEnnyson 9-3098
Philadelphia 31, Pa. MOhawk 4-0275

Consultation • Development • Product Planning
STEVEN GALAGAN
Consulting Engineer
Antennas—Microwave Components & Devices—
Interference Control & Reduction—Propagation
Studies—Microwave Relay—Feasibility Studies
30 Whittier Road . . . Wellesley Hills 81, Mass.
CEdar 5-6530

EARL GREENBERG & associates
TRANSISTOR CIRCUITS and CONTROLS
Digital and Analog Devices
Design - Development - Prototype Construction
11-16 154th Street Whitestone, New York
HIckory 5-2459

LEON HILLMAN
Engineering Staff and Laboratory
• Instrumentation • Control Systems
• Electronic Research and Development
255 County Rd., Tenafly, N.J LOwell 7-3232

Engineering • Consulting • Proposal Assistance
S. HIMMELSTEIN
and staff
Magnetic Recording Systems
Computer Peripheral Equipments
Transports, Drums, Discs, Photoreaders, Circuitry
3300 West Peterson, Chicago 45 • IRving 8-9850

LEONARD R. KAHN
Consultant in Communications and Electronics
Single-Sideband and Frequency-Shift Systems
Diversity Reception - Stereophonic Systems
Television Systems
81 South Bergen Place, Freeport, L.I., N.Y.
FReeport 9-8800

THIN FILM and other MICROCIRCUITS
designed & developed
Distributed Parameter Networks;
Deposition Tech.
2414 Reedie Drive, Silver Spring, Md.
M. A. KARP
staff and associates
Phone: 565-2896, Silver Spring, Md.

NEWS New Products

These manufacturers have invited PROCEEDINGS readers to write for literature and further technical information. Please mention your IRE affiliation.

(Continued from page 138A)



Because of special considerations of every system, each Orion Series C unit must be engineered to the specific system. In the typical missile application it was necessary to amplify just the pulse difference frequency by the use of an IF amplifier to drive a discriminator. The output of the discriminator is a video signal which is amplified polarity clamped, peak detected, and fed through an emitter follower to the control of a small power supply. A separate sweep generator is employed to generate a sawtooth wave for lock-on when the proper difference signal is not received.

Orion Series C units are being made available in three distinct types: miniature tubes, subminiature tubes or transistors.

Since each unit must be designed for a specific application, the manufacturer suggests that system details be furnished for an engineering analysis to determine requirements for the AFC units. Typical electrical data are presently available and may be secured by writing the manufacturer.

LEONARD J. LYONS
Consulting Mechanical Engineer
COOLING—HEATING—FLUID FLOW
Analysis and Testing
Heat Transfer & Thermodynamic Problems
3710 Crestway Dr. AXminster 1-5446
Los Angeles 43, California

LEN MAYBERRY
ELECTRONICS CONSULTING ENGINEER
Laboratories and Staff
Transistorized Modular Equipment
Product Design • Test Equipment Design
111 South Oak Street ORegon 8-4847
Inglewood, California

Telecommunications Consulting Engineers
"Worldwide Experience"
V. J. Nexon and staff
WIRE, CARRIER, RADIO, MICROWAVE,
TROPO SCATTER
Feasibility Studies, Terrain Surveys, System Design, Job Supervision, Government Proposals, Market Research, Product Planning.
U.S. 46 & Cisco, Denville, N.J. OAkwood 7-7400

E. M. OSTLUND & associates
Electronic Engineers
Radio—Microwave—Carrier—
Communication—Control—
Systems and Equipment
Consulting—Research—Development
ANDOVER, NEW JERSEY
Tel: PArkway 9-6635 P.E.N.J.

NATHAN GRIER PARKE
and staff
Consulting Applied Mathematicians
Research • Analysis • Computation
Bedford Road • Carlisle, Massachusetts
Area Code 617 • EMerson 9-3818

PAUL ROSENBERG
& associates
Established 1945
Consultation, Research & Development
in Applied Physics
100 Stevens Ave., Mt. Vernon, New York
MOunt Vernon 7-8040 Cable: PHYSICIST

MYRON M. ROSENTHAL
& staff
Microwave & Electronic Systems
19 Brookline Dr., North Massapequa, N.Y.
PErshing 5-2501

Analysis—Research—Design
Electronics and Automation
GARDNER H. SLOAN
R & D Consultant
Electrical Engineer, Physicist
One Story Street Harvard Square
Cambridge 38, Mass. Eliot 4-0766

HAROLD A. WHEELER
Laboratories and Engineering Staff
Consultation—Research—Development
Radar and Communication Antennas
Microwave Assemblies and Components
Main office: Great Neck, N. Y. HUnter 2-7876
Antenna Laboratory: Smithtown, N. Y.

Advertising Index

IRE News and Radio Notes 14A
IRE People 40A
Industrial Engineering Notes 28A
Meetings with Exhibits 8A
Membership 68A
News—New Products 80A
Positions Open 105A
Positions Wanted by Armed Forces Veterans 124A
Professional Group Meetings 76A
Section Meetings 72A
Table of Contents 1A-2A

DISPLAY ADVERTISERS

ACF Industries, Inc., ACF Electronics Div. 119A, 133A
ATR Electronics, Inc. 52A
Abbott's Employment Specialists 118A
Academic Press 70A
Accredited Personnel Service 137A
Addison-Wesley Publishing Co., Inc. 82A
Aerospace Corporation 121A
Airborne Instruments Laboratory, Div. of Cutler-Hammer, Inc. 4A
Airpax Electronics, Inc. 30A
Alden Products Company 40A
Allegheny Ludlum Steel Corp. 48A-49A
American Smelting & Refining Co. 89A
Amperex Electronic Corp. 71A
Armed Forces Communications & Electronics Association 90A
Armour Research Foundation, Illinois Institute of Technology 122A, 134A
Arnold Engineering Co. 35A
Associated Iliffe Press, Ltd. 97A
Avco Corporation, Everett Research Lab. 108A

Ballantine Laboratories, Inc. 62A
Bell Telephone Laboratories 6A
Bendix Corp., Research Laboratories Div. 124A
Binswanger Associates, Charles A. 120A
Bliley Electric Company 34A
Boeing Company 132A
Bomac Laboratories, Inc. 17A
Boonton Electronics Corp. 143A
Bugnolo, D. S. 140A
Burroughs Corp., Electronic Tube Div. 11A
Bussmann Mfg. Div., McGraw-Edison Co. 95A

CTS Corporation 55A
Capitol Radio Engineering Institute 52A
Carborundum Company 77A
Cinch Mfg. Co., Howard B. Jones Div. 64A
Clairex Corporation 36A
Clare and Co., C. P. 38A-39A
Clevite Electronic Components, Div. of Clevite Corp. 27A
Clifton Precision Products Co., Inc. 51A
Cohn Mfg. Co., Inc., Sigmund 66A
Collins Radio Co. 119A
Columbus Div., North American Aviation, Inc. 114A
Continental Can Co., Inc., Hazel-Atlas Glass Research & Dev. Div. 126A
Cornell Aeronautical Lab., Inc. 122A
Corning Glass Works 19A
Cross Country Consultants 132A

Interstate Electronics is delivering the most reliable ENERGY STORAGE ELECTROLYTIC CAPACITORS *in the industry* SANGAMO




TYPE DCM ELECTROLYTIC CAPACITORS are especially designed for use as energy storage components in DC circuitry where peak power requirements exceed the maximum output of the associated power supply. They operate under high temperature conditions, minimize ripple voltage and add stability and long life to low voltage power supplies.

That's why many computer manufacturers use the SANGAMO DCM. That's why you gain by turning to SANGAMO for your capacitor needs.

Complete data on Type DCM Capacitors is detailed in SANGAMO'S *Engineering Catalog 2231. Write us for your copy.*

"Definitely Dependable"

INTERSTATE ELECTRONICS, Inc.
227 Fulton Street, New York 7, N.Y. • BEekman 3-8780...TWX, N.Y.1,4478
Specialists in Military & Industrial Electronic Components



Outstanding...
IN EVERY RESPECT
THE Vactronic 450 LINE

Specially designed for high vacuum applications in research, production and testing.

Kingpin of the Vactronic 450 Line, the HVE-450, the most compact evaporator now available... providing clean, convenient and effective control of varied high vacuum operations.

Also available from Vactronic... the HVS-450 precision-built, high efficiency Vacuum Station and the dependable HVBS-450 Basic Vacuum System, furnishing Manual or Pneumatic control... a complete complement of the following high vacuum components separately available:

HVP-450 Oil Vapor Diffusion Pump, CBF-450 Baffle, CVP-450 Cold Trap, CVS-450 and AVS-450 High Vacuum Valves, and RGH-450-NP Roughing Manifold.

Experienced Engineering . . . Advanced Design . . . Critical Construction

Send for special brochure describing the 450 Line

Vactronic
LAB. EQUIPMENT, INC.
East Northport, Long Island, New York

SCR 584 RADARS AUTOMATIC TRACKING RADAR

Our 584s in like new condition, ready to go, and in stock for immediate delivery. Ideal for research and development, airway control, GCA, missile tracking, balloon tracking, weather forecasting, antiaircraft defense tactical air support. Write us. Fully Desc. MIT Rad. Lab. Series, Vol. 1, pps. 207-210, 228, 284-286.



Full azimuth and elevation sweeps 360 degrees in azimuth. 210 degrees in elevation. Accurate to 1 mil. or better over system. Complete for full tracking response. Angle acceleration rate: AZ, 9 degrees per second squared EL, 4 degrees per second squared. Angle slewing rate: AZ 20 degrees per sec. EL. 10 degrees per sec. Can mount up to a 20 ft. dish. Angle tracking rate: 10 degrees per sec. Includes pedestal drives, selsyns, potentiometers, drive motors, control ampildynes. Excellent condition. Quantity in stock for immediate shipment. Ideal for missile & satellite tracking, antenna pattern ranges, radar system, radio astronomy, any project requiring accurate response in elevation and azimuth.
Complete description in McGraw-Hill Radiation Laboratory Series, Volume 1, page 284 and page 209, and Volume 26, page 233.

TOPWALL HYBRID JUNCTION. 8500-9600 mc 1x.5 wg size. Broad banded better than 16%. Aluminum casting. $15.00 new Crossover output. 1x.5 wg size. $5.00 new.
BROAD BAND BAL MIXER using short slot-hybrid. Pound type broad band dual balanced crystal holder. 1x5 wg size. $25. New.

WESTERN ELECTRIC TD-2 MICROWAVE LINK 4 KMC CRYSTAL OSC.

Basic crystal oscillator multiplying thru 2C37 cavities and 416B cavities with crystal stability output 3700-4200 MCS. New.

2C40 LIGHTHOUSE CAVITY

AN/APW-11A transmitter cavity for 2C40. Complete S band coverage at max. power. Temperature compensated. New $77.50 ea.

AN/AAS-6

Infrared Detection System, complete. New $5500.

VD-2 PPI REPEATER

Floor standing console with rotating yoke PPI. 7BP7CRT. 4, 20, 80, 200 mile ranges. Will display or repeat any PPI info locally or remote. New & Complete. With inst. book $375 ea.

MIT MODEL 9 PULSER 1 MEGAWATT-HARD TUBE

Output pulse power 25 KV at 40 amp. Max. duty ratio: 002. Uses 6C21 pulse tube. Pulse duration .25 to 2 microsec. Input 115 volts 60 cycle AC. Includes power supply in separate cabinet and driver. Fully guaranteed as new condition. Full Desc. MIT. Rad. Lab. Series "Pulse Generators."

500 KW PULSER

5C22 Hydrogen Thyratron Modulator. 22 KV at 28 amps. W/HV & Fil supplies. 3 pulse length rep rates: 2.25 usec 300 pps. 1.75 usec 550 pps. .4 usec 2500 pps. 115V 60 cy AC input.

MIT MODEL 3 PULSER

Output: 144 kw (12 kv at 12 amp.) Duty ratio: 001 max. Pulse duration: .5 1 and 2 micro sec. Input: 115 v 400 to 2000 cps and 24 vdc. $325 ea. Full desc. Vol. 5 MIT Rad. Lab. series pg. 140.

2 MEGAWATT PULSER

Includes Rectifier xfmr 5800/7000 V, 2.2/2.55-KV; Resonant charging choke 150 cy. 30 H 12 Amp. Ins. 17 KV; Capacitor network 17E2-2-300-25P2T; Capacitor. 04Mfd. 17KVDC; Transformer 4400 V to 22,000 V; Fil. Xfmr. & Filter choke 5.1 V 18 Amp. 6 H .21 Amp. DC; 4C35 pulser, 3B24W (6 each), WL1B41 gap tube. Price new type MD-53/APS20C $1125 00.

AN/TPS-ID RADAR

500 kw 1220-1359 mcs. 160 nautical mile search range P.P.I. and A Scopes. MTI. thyratron mod. 5J26 magnetron. Like new. Complete system incl. spare parts and gas generator field supply.

AN/TPS-10D HEIGHT FINDER

250 KW X-Band 60 & 120 mile ranges to 60,000 feet. Complete.

10 CM. WEATHER RADAR SYSTEM

US Navy Raytheon, 275 KW peak output S band. Rotating yoke Plan position Indicator. Magnetron supplied for any S band frequency specified, incl. Weather Band. 4, 20 and 80 mile range, 360 degree azimuth scan. Sensitive rcvr using 2K28/707B and 1N21B. Supplied brand new complete with instruction books and installation drawings. Can be supplied to operate from 32VDC or 115 volts. Price $975. Ideal for weather work. Has picked up clouds at 50 miles. Weight 488 lbs.

AN/APS-15B 3 CM RADAR

Airborne radar. 40 kw output using 725A magnetron. Model 3 pulser. 30 in. parabola stabilized antenna. PPI scope. Complete system. $1200 each. New.

10KW 3 CM. X BAND RADAR

Complete RF head including transmitter, receiver, modulator. Uses 2J42 magnetron. Fully described in MIT Rad. Lab. Series Vol. I, pps. 616-625 and Vol. II, pps. 171-185 $375. Complete X Band Radar System also avail., inclu. 360-deg. antenna, PPI, syn pwr supply. Similar to $17,000 weather radar now in use by airlines. $750 complete.

225 KW X-BAND RF

4J50 Magnetron RF Generator with dummy load & Dir. Cplr. Variable rep rates. Variable power output 115 V 60-cycle AC input. New. $2400 complete.

L BAND RF PKG.

20 KW peak 990 to 1040 MC. Pulse width .7 to 1.2 micro sec. Rep rate 180 to 420 pps. Input 115 vac. Incl. Receiver $1200.

WESTINGHOUSE 3CM RADAR

Complete X band system oper. from 115 v 60 cy ac with 40 kw power output 2J55 magnetron. Ranges 0-1.5, 4, 16, 40 miles. Includes installation waveguide. An ideal system for lab school, demonstration or shipboard. $1800. New with spares.

60 MC I.F. STRIP

—95 DBM sensitivity. 130 DB gain. 1 MC & 5 MC band widths. Mfg. Texas Instruments. $125 each w/tubes.

RADIO RESEARCH INSTRUMENT CO.
550 FIFTH AVE., NEW YORK
JUDSON 6-4691

Advertising Index

Daven Company 132A
Delco Radio Div., General Motors Corp. 29A, 103A
Dialight Corporation 34A
Dielectric Products Engineering Co., Inc. 99A
Dikewood Corporation 112A
Dynatran Electronics Corp. 92A

Eastman Kodak Company 25A
Electro-Mechanical Research, Inc. 114A
Engineering-Physics Co. 113A
Epsco, Inc. 116A
Esse Radio Company 66A

F X R, Div. of Amphenol-Borg Electronics Corp. 56A
Fairchild Semiconductor Corp. 13A
Federal Aviation Agency 128A
Federation Nationale des Industries Electroniques 74A
Frankel, Sidney 140A
Freed Transformer Co., Inc. 104A
Friend, A. W. 140A

Galagan, Steven 140A
General Applied Science Laboratories, Inc. 143A
General Dynamics/Electronics, Div. of General Dynamics Corp. 110A
General Electric Co., Defense Systems Dept. 107A
General Electric Co., Electronics Lab. 139A
General Electric Co., Heavy Military Electronics Dept. 63A
General Electric Co., Missile & Space Vehicle Dept. 127A
General Electric Co., Semiconductor Products Dept. 44A-45A
General Radio Company ..... Cover 4
Goodyear Aircraft Corp., Arizona Div. 132A
Gould-National Batteries, Inc. 12A
Greenberg, Earl 140A
Guilford Personnel Service 119A

Hamilton-Electrona, Inc. 21A
Harvey-Wells Corporation 101A
Heath Company 93A
Hewlett-Packard Company 47A
High Voltage Engineering Corp. 138A
Hillman, Leon 140A
Himmelstein, S. 140A
Hitachi, Ltd. 91A
Hughes Aircraft Co., Aerospace Engineering Div. 135A
Hughes Aircraft Co., Market Development Div. 58A-59A
Huntington Alloy Products Div., International Nickel Co., Inc. 83A

Institute of Radio Engineers 69A
International Business Machines Corp. 117A, 133A
International Telephone & Telegraph Corp., International Electric Co., Div. 130A
Interstate Electronics, Inc. 141A

Jerrold Electronics Corp. 102A
Jet Propulsion Laboratory, Calif Inst. of Technology 109A
John Hopkins University, Applied Physics Laboratory 112A
Jones Electronics Co., Inc., M. C. 75A

Kahn, Leonard R. 140A
Karp, M. A. 140A
Kay Electric Company 9A
Kearfott Div., General Precision, Inc. 8A
Keithley Instruments, Inc. 78A
Kepco, Inc. 93A
Kin Tel, Div. of Cohu Electronics, Inc. 28A

Advertising Index

Knights Company, James 88A
Kollsman Instrument Corp. 124A
Kulka Electric Corp. 84A

Lambda Electronics Corp. 67A
Lapp Insulator Co., Inc. 32A
Lenkurt Electric Co., Inc. 108A
Link Div., General Precision, Inc. 134A
Litton Systems, Inc., Data Systems Div. 130A
Lockheed California Co., Div. of Lockheed Aircraft Corp. 129A
Lyons, Leonard J. 140A

Magnetic Metals Company 37A
Mark Products Co. 104A
Massachusetts Institute of Technology, Instrumentation Lab. 106A
Massachusetts Institute of Technology, Lincoln Lab. 120A
Mayberry, Len 140A
Measurements, McGraw-Edison Div. 144A
Micon Electronics, Inc. 84A
Microtran Company, Inc. 10A
Microwave Associates, Inc. 7A
Midland Mfg. Co. 53A
Millen Mfg. Co., Inc., James 76A
Minneapolis-Honeywell Reg. Co., Precision Meter Div. 85A
Minneapolis-Honeywell Reg. Co., Semiconductor Div. 23A

Expedite your


PLASMA STUDIES

and get more comprehensive results by using GASL computer programs such as these:

- Subsonic flow fields about blunt nosed axisymmetric bodies.
- Supersonic flow fields about blunt nosed two and three dimensional bodies for real gas in thermal equilibrium or with frozen atom chemistry.
- Temperature, frozen speed of sound, entropy, partition functions, equilibrium constants, mass fractions for equilibrium air.
- Non equilibrium ionized wakes
- Two-dimensional or axisymmetric inviscid flow past a body or through a nozzle for non-equilibrium mixtures of O_2, N_2, NO. O, N.

If your problem is in: Steady and Non-Steady Aerodynamics, Propulsion. Acoustics, Structural Dynamics . . . we can probably help you.

General Applied Science Laboratories, Inc.
Merrick and Stewart Aves.
Westbury, L. I., N. Y. • EDgewood 3-6960




THE LEADER
in R.F. Voltage Measurements at Low Level
from 10 KC to 600 MC

MODEL 91-CA
300 microvolts to 3 volts
Price: $495

MODEL 91-C
1000 microvolts to 3 volts
Price: $395

ALSO MANUFACTURERS OF THE FOLLOWING INSTRUMENTS:



DC Millivoltmeter | Inductance Bridge | Capacitance Bridge | UHF Grid Dip Meter

Boonton ELECTRONICS Corp.
Morris Plains, N. J. • JEfferson 9-4210

STANDARD SIGNAL GENERATOR

MODEL 65-B

RANGE 75 KC to 30 MC



Individually Calibrated Scale

OUTPUT: Continuously variable, .1 microvolt to 2.2 volts.

OUTPUT IMPEDANCE: 5 ohms to .2 volt, rising to 15 ohms at 2.2 volts.

MODULATION: From zero to 100%. 400 cycles, 1000 cycles and provision for external modulation. Built-in, low distortion modulating amplifier.

POWER SUPPLY: 117 volts, 50-60 cycles, AC.

DIMENSIONS: 11" high, 20" long, 10¼" deep, overall.

WEIGHT: Approximately 50 lbs.

PRICE OF THE MODEL 65B IS $875.00. PRICES F.O.B. BOONTON, NEW JERSEY.


MANUFACTURERS OF

Standard Signal Generators
Pulse Generators
FM Signal Generators
Square Wave Generators
Vacuum Tube Voltmeters
UHF Radio Noise & Field Strength Meters
Capacity Bridges
Megohm Meters
Phase Sequence Indicators
Television and FM Test Equipment

EXTENDED *FREQUENCY RANGE*

with these STANDARD SIGNAL GENERATORS

MODEL 80
2 Mc to 400 Mc
$590.00
MODEL 80-R
5 Mc to 475 Mc
$625.00



FEATURES

- Direct-Reading scales and dials; individually calibrated.
- Convenient microvolt and DBM output scales.
- Accurate indication of output voltages at all levels.
- Low residual FM due to hum and noise.
- Provision for external pulse modulation.

SPECIFICATIONS

FREQUENCY RANGE: (Model 80) 2 to 400 Mc in 6 bands. (Model 80-R) 5 to 475 Mc in 6 bands.

FREQUENCY ACCURACY: ± 0.5%

FREQUENCY DRIFT: Less than .1% after warm-up.

OUTPUT VOLTAGE: Continuously variable from 0.1 to 100,000 microvolts (−7 to −127 DBM).

OUTPUT ACCURACY: ±10% at 0.1 volt from 5 to 200 Mc. ±15% at 0.1 volt from 200 to 475 Mc.

MODULATION: AM is continuously variable from 0 to 30%. Internal modulation, 400 and 1000 cycles. External modulation, 50 to 10,000 cycles.

RESIDUAL FM: Less than 500 cps at 450 Mc for Model 80-R, and correspondingly lower for both models at lower frequencies.

POWER SUPPLY: 117v, 50-60 cycles, 70 watts.

Laboratory Standards **MEASUREMENTS**
A McGraw-Edison Division
BOONTON, NEW JERSEY

Advertising Index

Mitre Corporation 131A
Motorola, Inc., Military Electronics Div. 117A
Motorola Semiconductor Products, Inc. 31A

Narda Microwave Corp. 33A
National Cash Register Co. 137A
Nexon, V. J. 140A

Ordnance Research Laboratory, Pennsylvania State University 128A
Ostlund, E. M. 140A

Pace Electrical Instruments Co., Inc. 60A
Panoramic Electronics, Inc. 100A
Parke, Nathan Grier 140A
Pergamon Press, Inc. 66A
Permanent Employment Agency, Professional and Technical Recruiting Associates 128A
Philco Corp., Lansdale Div. ..... Cover 3
Philco Corp., Research Center 125A
Philco Corp., Western Development Labs. 111A
Polarad Electronics Corp. 65A
Power Designs, Inc. 82A
Precision Apparatus Co., Inc. 60A
Prodelin, Inc. 54A

Q-max Corporation 94A

Radio Corp. of America, Electron Tube Div. 96A
Radio Research Instrument Co. 142A
Ramo-Wooldridge Corporation 115A
Raytheon Company, Microwave and Power Tube Div. 43A
Republic Aviation Corp. 120A
Rixon Electronics, Inc. 102A
Rosenburg, Paul 140A
Rosenthal, Myron M. 140A

Sanborn Company 87A
Sanders Associates, Inc. 118A
Secon Metals Corporation 88A
Sensitive Research Instrument Corp. 72A
Simplex Wire & Cable Co. 57A
Sloan, Gardner H. 140A
Space Technology Labs., Inc. 112A
Specific Products 86A
Sperry Rand Research Center 116A
Sprague Electric Company 3A, 5A, 41A, 92A
Stoddart Aircraft Radio Co., Inc. 98A
Sylvania Electric Products Inc., Amherst Laboratories 113A
Sylvania Electric Products Inc., Applied Research Laboratory 136A
Sylvania Electric Products Inc., Electronic Systems Div. 123A

Technical Materiel Corp. 94A
Tektronix, Inc. 79A
Texas Instruments Incorporated, Transistor Products Div. 81A
Thermo Electron Engineering Corp. 46A
Transco Products, Inc. 50A

United Aircraft Corp., Research Labs. 126A
United Transformer Corp. ..... Cover 2

Vactronic Lab. Equipment, Inc. 141A
Vitro Electronics Div., Vitro Corp. of America 105A

Weinschel Engineering Co., Inc. 42A
Western Electric Co., Inc. 61A
Western Gold & Platinum Co. 68A
Westinghouse Electric Corp., Baltimore Div. 125A
Westinghouse Electric Corp., Electronic Tube Div. 110A
Wheeler, Harold A. 140A
Wright Div., Sperry Rand Corp. 73A

Index to

PROCEEDINGS OF THE IRE

Volume 49, 1961

TABLE OF CONTENTS

Contents of Issues 2

Index to Authors 9

Index to Subjects 11

Nontechnical Index 18

Index to Book Reviews 23



The Institute of Radio Engineers, Inc.
1 East 79 Street, New York 321, N.Y.

PROCEEDING OF THE IRE
CONTENTS OF VOLUME 49—1961

Volume 49, Number 1, January, 1961

Walter R. G. Baker, 1892-1960 1
Lloyd V. Berkner, President, 1961 2
Poles and Zeros 3
The Computer Issue, *Harry T. Larson, Guest Editor* 4
Steps Toward Artificial Intelligence, *Marvin Minsky* 8
Self-Organizing Systems—A Review and Commentary, J. K. *Hawkins* 31
The Simulation of Neural Elements by Electrical Networks Based on Multi-Aperture Magnetic Cores, *A. E. Brain* 49
Developments in the Logical Organization of Computer Arithmetic and Control Units, *F. S. Beckman, F. P. Brooks, Jr., and W. J. Lawless, Jr.* 53
High-Speed Arithmetic in Binary Computers, *O. L. MacSorley* 67
Statistical Analysis of Certain Binary Division Algorithms, *C. V. Freiman* 91
Computer Memories: A Survey of the State-of-the-Art, *Jan A. Rajchman* 104
A Computer Subsystem Using Kilomegacycle Subharmonic Oscillators, *I. Abeyta, F. Borgini, and D. R. Crosby* 128
A Survey of Tunnel-Diode Digital Techniques, *R. C. Sims, E. R. Beck, Jr., and V. C. Kamm* 136
Calculated Waveforms for Tunnel Diode Locked Pair, *H. R. Kaupp and D. R. Crosby* 146
Magnetic Film Memory Design, *J. I. Raffel, T. S. Crowther, A. H. Anderson, and T. O. Herndon* 155
The Development of the Flexible-Disk Magnetic Recorder, *R. T. Pearson* 164
Pattern Recognition Using Autocorrelation, *L. P. Horwitz and G. L. Shelton, Jr.* 175
Computer Generated Displays, *R. T. Loewe, R. L. Sisson, and Horowitz* 185
Digital Data Communication Techniques, *J. M. Wier* 196
Arbitrary Boolean Functions of *N* Variables Realizable in Terms of Threshold Devices, *Oscar B. Stram* 210
Correction to "Anomalies in the Absorption of Radio Waves by Atmospheric Gases," *A. W. Straiton and C. W. Tolbert* 220
Flow Table Logic, *P. R. Low and G. A. Maley* 221
Cyclic Codes for Error Detection, *W. W. Peterson and D. T. Brown* 228
Statistical Analysis of Logic Circuit Performance in Digital Systems, *E. Nussbaum, E. A. Irland, and C. E. Young* 236
Transient Analysis of Cryotron Networks by Computer Simulation, *Munro K. Haynes* 245
High-Density Digital Magnetic Recording Techniques, *A. S. Hoagland and G. C. Bacon* 258
A New Active-Passive Network Simulator for Transient Field Problems, *Walter J. Karplus* 268
Algebraic Function Calculations Using Potential Analog Pairs, *Merle L. Morgan* 276
The Evolution of Programming Systems, *William Orchard-Hays* 283
Advanced Computer Applications, *W. F. Bauer, D. L. Gerlough and J. W. Granholm* 296
Computers in Automatic Control Systems, *John G. Truxal* 305
Digital Computer Equipment for an Advanced Bombing, Navigation and Missile Guidance Subsystem for the B-70 Air Vehicle, *T. B. Lewis* 313
Digital Simulation in Research on Human Communication, *Edward E. David, Jr.* 319
Correction to "A Unified Analysis of Range Performance of CW, Pulse, and Pulse Doppler Radar," *J. J. Bussgang, P. Nesbeda, and H. Safran* 329
European Electronic Data Processing—A Report on the Industry and the State-of-the-Art, *Isaac L. Auerbach* 330
Correspondence:
Shift of Peak Voltage with Temperature in Tunnel Diodes, *R. P. Nanavati* 349
Optimum Performance of Learning Machines, *A. Gamba* 349
Shot Noise in Tunnel-Diode Amplifiers, *L. S. Nergaard* 350
Experimental Tunnel-Diode Mixer, *J. C. Greene and E. W. Sard* 350
Subharmonic Generation with Nonlinear Reactance—A Circuit Analysis, *D. B. Leeson* 351
The Cryosistor—A New Low-Temperature Three-Terminal Switch, *Ivars Melngailis* 352
Universal Representation of Electromagnetic Parameters in Presence of DC Magnetic Fields, *M. P. Bachynski, T. W. Johnston, and I. P. Shkarofsky* 354
Gain Bandwidth Relations in Negative Resistance Amplifiers, *R. Aron and E. W. Sard* 355
Determination of Probability Density Functions for Sums of Variables by Laplace Transformation, *V. H. Seliger* 356
Applying the Chordal-Hop Theory of Ionospheric Long-Range Propagation to Echo-Signal Delay, *Hans J. Albrecht* 356
Minimization of the Maximum Amplitude in Frequency Multiplexing, *D. R. Anderson* 357
The Equivalence of the Taylor-Cauchy and Laurent-Cauchy Transform Analysis with Conventional Methods, *E. V. Bohn and A. A. Wolf* 358
Rotating Polarization and Periodic Bodies, *J. J. Mikulski* 361
On Phase Distortion in a Ferrimagnetic Limiter, *J. Brown* 362
Correction to "Evidence of Satellite-Induced Ionization Effects Between Hemispheres," *John D. Kraus* 363
Multiple Diversity with Nonindependent Fading, *John N. Pierce* 363
Differential Phase Shifts in Ferrite Dielectric Loaded Coaxial Lines at 2200 Mc, *James J. Rowley* 364
A Broadband Termination for IF Coaxial Lines, *K. S. Stull, Jr.* 365
A Practical Compact UHF Isolator, *D. Bruce Swartz* 366
Spectrum of Exponential Message Lengths, *J. Aein and J. Salz* 366
Translation of a Historic Paper on Diversity Reception, *Bruce B. Barrow* 367
Experimental Proof of Focusing at the Skip Distance by Backscatter Records, *H. F. Bates, R. D. Hunsucker, L. Owren, and K. Bibl* 369
A Note on the Radiation Resistance of a Thin Linear Antenna, *R. Bhaduri and S. Malik* 370
Boolean Functions Realizable with Single Threshold Devices, *C. K. Chow* 370
A 6-megacycle Cryotron Ring Oscillator, *M. L. Cohen* 371
Gain Measurements on a Forward Wave Crossed-Field Amplifier, *R. J. Collier* 372
The Measurement of Tunnel Diode Junction Capacitance, *U. S. Davidsohn* 372
A Technique for Cascading Tunnel Diode Amplifiers, *C. O. Harbourt and P. M. Chirlian* 373
On the Choice of Constants in the Fourier Transform Pair, *R. S. Johnson and J. L. Hammond* 375
On the Definition of Noise Performance, *D. R. Rhodes* 376
Comment on "On the Definition of Noise Performance," *Thomas E. Talpey* 376
Simplified Cesium Frequency Stabilizer, *A. P. Sheppard, R. E. Johnson, J. J. Gallagher, and V. E. Derr* 377
Further Developments in Tapered Ladder Antennas, *A. F. Wickersham, Jr., R. E. Franks, and R. L. Bell* 378
Comments on the History of Parametric Transducers, *L. Pungs* 378
WWV and WWVH Standard Frequency and Time Transmissions, *National Bureau of Standards* 379
Stability Criterion for Amplifier Moving in Space, *H. E. Stockman* 379
The Scattering of Short Electromagnetic Pulses by a Conducting Sphere, *E. M. Kennaugh* 380
The Significance of Transients and Steady-State Behavior in Nonlinear Systems, *C. H. Knapp* 380
Photon Propelled Space Vehicles, *T. C. Tsu, D. C. Hock, F. N. McMillan and A. R. Tanguay* 381
Contributors 381
Books 389
Scanning the TRANSACTIONS 393
Abstracts of IRE TRANSACTIONS 394
Abstracts and References 401

Volume 49, Number 2, February, 1961

Poles and Zeros 417
John F. Byrne, Vice President, 1961 418
Scanning the Issue 419
Circuit Considerations Relating to Microelectronics, *J. J. Suran* 420
Some Technical Aspects of Microwave Radiation Hazards, *W. W. Mumford* 427
A Very-Low-Frequency (VLF) Synchronizing System, *Chesley H. Looney, Jr.* 448
Exact Solution of a Time-Varying Capacitance Problem, *J. R. Macdonald and D. E. Edmonson* 453
Supplement to IRE Standards on Graphical Symbols for Electrical Diagrams, 1954 467
Pseudo-Rectification and Detection by Simple Bilateral Nonlinear Resistors, *J. E. Bridges* 469
The Amplitude Distribution and False Alarm Rate of Noise After Post-Detection Filtering, *S. Thaler and S. A. Meltzer* 479
IRE Standards on Radio Transmitters: Definitions of Terms, 1961 486
The Quadratic Invariances of a Generalized Network, *M. C. Pease* 488
Experiments on Magnetic Tape Readout with an Electron Beam, *M. M. Freundlich, S. J. Begun, D. I. Breitzer, J. B. Gehman, and J. K. Lewis* 498
Correspondence:
A Varactor Diode Parametric Standing-Wave Amplifier, *H. Brett, F. A. Brand, and W. G. Matthei* 509
Three-Terminal Variable Capacitance Semiconductor Device, *L. J. Giacoletto* 510
A High-Performance X-Band Parametric Amplifier, *B. T. Vincent* 511
WWV and WWVH Standard Frequency and Time Transmissions, *National Bureau of Standards* 512
Binary Error Rates in Fast Fading FDM-FM, *D. E. Johansen* 513
Capacity of Continuous Information Channel Corrected for Time or Phase Jitter, *Leonard S. Schwartz* 513
Note on the Visualization of Impedance Transformations by Means of Three-Dimensional Plastic Sphere Models, *E. F. Bolinder* 514
A Hollow-Beam Focusing System, *Philip M. Lally* 514
Endfire Antennas, *G. Broussaud and E. Spitz* 515
Beam Interception and Limiting Gain in Adler Tubes, *T. Wessel-Berg and K. Blötekjær* 516

Rise-Time Measurements in MgO Cold Cathode Diodes, *Alan Sussman* ... 517
Stripline Y-Circulators for the 100 to 400 Mc Region, *G. V. Buehler and A. F. Eikenberg* ... 518
Limitations of the AND-OR to Majority-Logic Conversion Technique, *Charles W. Sutherland* ... 519
Correction to "Negative *L* and *C* in Solid State Masers," *R. L. Kyhl* ... 519
Discussion on Tunable Maser Hybrids, *J. Reed and G. J. Wheeler* ... 519
10.8 KMC Germanium Tunnel-Diode, *G. Dermit, H. Lockwood, and W. Hauer* ... 519
The Noise Figure of Negative-Conductance Amplifiers, *Frederick W. Brown* ... 520
Nonuniform Sampling and External Approximation, *J. L. Stewart* ... 521
Space-Charge Potentials in Depressed-Collector Design, *C. C. Wang and R. Von Gutfeld* ... 522
A Helix-Type Variable Capacitor, *Y. Yamamoto* ... 522
Quartz AT-Type Filter Crystals for the Frequency Range 0.7 to 60 Mc, *R. Bechmann* ... 523
Early History of Parametric Transducers, *A. Bloch* ... 524
An Interaction Circuit for Traveling-Wave Tubes, *P. J. Crepeau and I. Itzkan* ... 525
An Experiment of Ion Relaxation Oscillation in Electron Beams, *Y. Koike and Y. Kumagai* ... 525
Can the Social Sciences Be Made Exact? *A. A. Mullin, G. W. Zopf, Jr., and L. V. Berkner* ... 526
Phase Stability of Oscillators, *Klaus H. Sann* ... 527
Failure Character of Receiving Tubes Due to Deterioration, *Yoshihiro Saito* ... 528
History of the Cross Antenna, *Grote Reber* ... 529
A Note on the Relationship Between the Geomagnetic and the Geographic Axes, *H. Unz* ... 530
Contributors ... 530
Books:
"Self-Organizing Systems," Marshall C. Yovits and Scott Cameron, Eds., *Reviewed by P. M. Kelly* ... 533
"Wave Generation and Shaping," by Leonard Strauss, *Reviewed by Leslie L. Burns* ... 533
"Electronic Maintainability, Vol. 3," F. L. Ankenbrandt, Ed., *Reviewed by Ralph R. Batcher* ... 533
"An Introduction to Transistor Circuits," by E. H. Cooke-Yarborough, *Reviewed by Arthur P. Stern* ... 534
"Manual of Mathematical Physics," by Paul I. Richards, *Reviewed by Sergei A. Schelkunoff* ... 534
"Analysis and Design of Feedback Control Systems, 2nd ed.," by George J. Thaler and Robert G. Brown, *Reviewed by Felix Zweig* ... 534
"Electromagnetic Energy Transmission and Radiation," by Richard B. Adler, Lan Jen Chu, and Robert Fano, *Reviewed by E. C. Jordan* ... 534
"Analog and Digital Computer Technology," by Norman R. Scott, *Reviewed by A. D. Scarbrough* ... 535
"Waves in Layered Media," by Leonid M. Brekhovskikh, *Reviewed by Samuel Silver* ... 535
"Coupled Mode and Parametric Electronics," by William H. Louisell, *Reviewed by Hubert Heffner* ... 535
"The Arc Discharge," by H. de B. Knight, *Reviewed by G. H. Reiling* ... 536
Recent Books ... 536
Scanning the TRANSACTIONS ... 537
Abstracts of IRE TRANSACTIONS ... 538
Abstracts and References ... 545

Volume 49, Number 3, March, 1961

Poles and Zeros ... 561
Ralph Bown, Winner of the IRE Founders Award ... 562
Ernst A. Guillemin, Winner of the IRE Medal of Honor ... 563
Scanning the Issue ... 564
Date Line, New York Coliseum, *Managing Editor* ... 565
Selective Erasure and Nonstorage Writing in Direct-View Halftone Storage Tubes, *N. H. Lehrer* ... 567
Cross-Relaxation Masers, *G. S. Bogle* ... 573
Correction to "Automatic Phase Control: Theory and Design," T. J. Rey ... 590
Traveling-Wave Parametric Amplifier Analysis Using Difference Equations, H. Zucker ... 591
IRE Standards on Video Techniques: Measurement of Resolution of Camera Systems, 1961 ... 599
Effects of Electrons and Holes on the Transition Layer Characteristics of Linearly Graded *P-N* Junctions, *C. T. Sah* ... 603
IRE Standards on Electrostatographic Devices, 1961 ... 619
Correction to "Interplanetary Telemetering," *Robert H. Dimond* ... 621
Correspondence:
One-Tunnel-Diode Flip-Flop, *R. A. Kaenel* ... 622
Shot Noise in Tunnel Diode Amplifiers, *L. S. Nergaard and J. J. Tiemann* ... 622
Effect of Higher Harmonic Components on the Performance of the Traveling-Wave Parametric Amplifier, *Shigebumi Saito* ... 623
The Reactance Tube as a Parametric Frequency Divider and Amplifier, *R. A. Elco and J. Nee* ... 624
Cavity Modes in an Optical Maser, *W. G. Wagner and G. Birnbaum* ... 625
A Proposed Doppler-Helitron Oscillator, *B. W. Hakki* ... 626
Noise Considerations for Hybrid Coupled Negative-Resistance Amplifiers, *J. C. Greene* ... 626
A New Exact Method of Nonuniform Transmission Lines, *Iwao Sugai* ... 627
Vectors for Waves and Electrons, *Iwao Sugai* ... 628
WWV and WWVH Standard Frequency Transmissions, *National Bureau of Standards* ... 629
On Stable Parametric Amplifiers, *Frank A. Olson* ... 629
Comments on "Relativity: Blessing or Blindfold," *R. M. Bevensee and M. Ruderfer* ... 630
The Significance of Transients and Steady-State Behavior in Nonlinear Systems, *P. Dorato and S. Doba, Jr* ... 631
Band-Pass Measurements of a Lunar Reflection Circuit, *R. P. Ingalls, L. E. Bird and J. W. B. Day* ... 631
Single-Sideband Communication, *J. Makris* ... 632
Noise Generated in the Ion Sheath of a Probe, *Katsunori Shimada* ... 632
Zero-Point Energy as the Source of Amplifier Noise, *A. E. Siegman* ... 633
Technique for Amplitude Modulating a Van Atta Radar Reflector, *Louis H. Bauer* ... 634
A Mechanical Model of the Minkowski Representation of Lorentz Space, *E. Folke Bolinder* ... 635
Calculation of the Rise and Fall Times in the Alloy Junction Transistor Switch Based on the Charge Analysis, *Y. Cho* ... 636
Noise and Bandwidth Considerations of Kompfner Dip Couplers for Electron Beam Parametric Amplifiers, *N. C. Chang* ... 637
The Significance of Transients and Steady-State Behavior in Nonlinear Systems, *W. J. Hartman and A. A. Wolf* ... 637
Analysis of Transient and Steady-State Behavior, *J. S. T. Huang* ... 638
A Possibility for Determining the Existence of a Permanent Form of Magnetic Field-Aligned Ionization Irregularities, *Ray L. Leadabrand* ... 639
Value Engineering—1959, *H. N. MacCarthy and R. R. Batcher* ... 640
Variable Capacitance Diodes Used as Phase-Shift Devices, *R. M. Searing* ... 640
Model Parameter Controls for an Adaptive System, *E. Kinnen* ... 641
Reduction of Beam Noisiness by Means of a Potential Minimum Away from the Cathode, *W. M. Mueller* ... 642
Vertical Incident Doppler Ionogram, *T. Ogawa, S. Ando and A. Yoshida* ... 643
Dispersive Properties of Broad-Band Antennas, *J. K. Pulfer* ... 644
A Low-Loss, Semiconductor Microwave Switch, *D. L. Rebsch* ... 644
Subsurface Communication Systems, *Leland I. Anderson* ... 645
A Cyclotron Wave Amplifier with Magnetic Pumping, *P. N. Robson* ... 645
Bi-Signal Amplification by a Forward Wave Crossed-Field Amplifier, *R. J. Collier* ... 646
The Ineffectiveness of Absorbing Coatings on Conducting Objects Illuminated by Long Wavelength Radar, *M. Laikin, R. E. Hiatt, K. M. Siegel, and H. Weil* ... 646
A Simplified Technique for the Determination of Output Transforms of Multiloop, Multisampler, Variable-Rate Discrete-Data Systems, *Julius T. Tou* ... 646
Transistor Upper Noise Corner Frequency, *Harry F. Cooke* ... 648
A Note on Instantaneous Spectrum, *Donald R. Rothschild* ... 649
An Analysis of Recent Measurements of the Atmospheric Absorption of Millimetric Radio Waves, *C. W. Tolbert and A. W. Straiton* ... 649
Contributors ... 651
1961 IRE International Convention ... 652
Books:
"Statistical Theory of Communication," by Y. W. Lee, *Reviewed by T. M. Burford* ... 690
"Electrical Engineering Problems," by E. M. Williams and F. J. Young, *Reviewed by Samuel Seely* ... 690
"Field Theory of Guided Waves," by Robert E. Collin, *Reviewed by Seymour B. Cohn* ... 690
"Computer Logic," by Ivan Flores, *Reviewed by C. T. Leonde* ... 690
"Foundations of Electrodynamics," by Parry Moon and Domina Eberle Spencer, *Reviewed by J. R. Whinnery* ... 691
"Space Research," H. K. Kallmann Bijl, Ed., *Reviewed by G. E. Mueller* ... 691
"Electronic Circuit Analysis, Vol. 1, Passive Networks," by Phillip Cutler, *Reviewed by I. O. Ebert* ... 691
"Dictionary of Electronics," by Harley Carter, *Reviewed by Millard W. Baldwin, Jr* ... 692
"Statistical Theory and Methodology in Science and Engineering," by K. A. Brownlee, *Reviewed by W. R. Bennett* ... 692
Scanning the TRANSACTIONS ... 693
Abstracts of IRE TRANSACTIONS ... 694
Abstracts and References ... 705
Translations of Russian Technical Literature ... 720

Volume 49, Number 4, April, 1961

John V. L. Hogan, 1890–1960 ... 721
Franz Ollendorff, Vice President, 1961 ... 722
Poles and Zeros ... 723
Scanning the Issue ... 724
Transistor Internal Parameters for Small-Signal Representation, *R. L. Pritchard, J. B. Angell, R. B. Adler, J. M. Early, and W. M. Webster* ... 725
A Noise Investigation of Tunnel-Diode Microwave Amplifiers, *A. Yariv and J. S. Cook* ... 739
Tunnel-Diode Microwave Oscillators, *F. Sterzer and D. E. Nelson* ... 744
Three-Layer Negative-Resistance and Inductive Semiconductor Diodes, *W. W. Gärtner and M. Schuller* ... 754
A Low-Noise *X*-Band Radiometer Using Maser, *J. J. Cook, L. G. Cross, M. E. Bair, and R. W. Terhune* ... 768
An Analysis of the Magnetic Second-Subharmonic Oscillator, *A. Lavi and L. A. Finzi* ... 779
Properties of Tropospheric Scattered Fields, *N. R. Ortwein, R. U. F. Hopkins, and J. E. Pohl* ... 788
Correspondence:
Behavior of Thermal Noise and Beam Noise in a Quadrupole Amplifier, *R. Adler and G. Wade* ... 802
Tunnel Diode Large-Signal Simulation Study, *S. B. Geller and P. A. Mantek* ... 803
Radar Sensitivity with Degenerate Parametric Amplifier Front End *J. C. Greene, W. D. White, and R. Adler* ... 804

Determination of Noise Temperature of a Gas-Discharge Noise Source for Four-Millimeter Waves, *W. Jasinski and G. Hiller*... 807
A Direct Graphical Solution for the Flux Distribution in a Magnetic Parallel Circuit, *Shlomo Karni*... 808
Comparative Figures of Merit for Available Varactor Diodes, *K. Siegel*... 809
Capacitance Coefficients for Varactor Diodes, *R. D. Weglein and S. Sensiper*... 810
Note on a Balun: Solution by a Tapered Potential, *C. C. Eaglesfield* 810
Energy Fluxes from the Cyclotron Radiation Model of VLF Radio Emission, *W. B. Murcray and J. H. Hope*... 811
Interpretation of the Transmission Line Parameters with a Negative-Conductance Load and Application to Negative-Conductance Amplifiers, *C. T. Stelzried*... 812
WWV and WWVH Standard Frequency and Time Transmissions, *National Bureau of Standards*... 813
Minimum Power Set by Quantum Effects, *L. P. Bolgiano, Jr. and W. M. Gottschalk*... 813
Corrections and Coordination of Some Papers on Noise Temperature, *Edwin Dyke*... 814
Small-Signal Space-Charge Density in Drifting Ion-Neutralized Rectilinear-Flow Beams Immersed in an Axial Magnetic Field of Finite Magnitude, *V. Bevc*... 815
The External Electromagnetic Fields of Shielded Transmission Lines, *J. D. Meindl and E. R. Schatz*... 816
Duality as Applied to Transformers, *Paul G. Griffith*... 816
Transient Behavior of Aperture Antennas, *B. R. Mayo and C. Polk* 817
RF Focusing of an Electron Stream, *C. K. Birdsall, G. W. Rayfield, E. Sugata, M. Terada, and K. Ura*... 819
A Wide-Band Single-Diode Parametric Amplifier Using Filter Techniques, *A. G. Little*... 821
Dynamic Response of Rihaczek's Constant Phase Nonlinear Filter, *M. G. Pelchat and A. W. Rihaczek*... 822
D'Alembert's Method for Nonuniform Transmission Lines, *Iwao Sugai*... 823
A Broad-Band Spherical Satellite Antenna, *John D. Dyson*... 824
A Nondegenerate S-Band Parametric Amplifier with Wide Bandwidth, *G. Schaffner and F. Voorhaar*... 824
Waveguide Harmonic Generators, *John Brown*... 825
A Complete Transistor Equivalent Circuit, *R. H. Beeson*... 825
The Tunnel Diode as a Highly Sensitive Microwave Detector, *M. D. Montgomery*... 826
Comments on "An Analysis of Cryotron Ring Oscillators," *T. H. Cheng*... 827
Discussion of "Fourier Series Derivation," *C. D. Ferris and C. P. Gadsden*... 827
Microwave Bistable Circuits Using Varactor Diodes, *C. L. Heizman* 829
Mismatched Interconnection of Transistor Feedback Amplifiers, *E. M. Cherry*... 830
General Matched-Filter Analysis of Linear FM Pulse Compression, *Charles E. Cook*... 831
Gain vs Bandwidth Limits for Esaki Diode Amplifiers, *J. S. Logan*. 832
Some Electron Trajectories in a Nonuniform Magnetic Field, *T. N. Chin*... 832
On the Fourier Transform Constants, *Christopher P. Gadsden*... 833
A Nearly Optimum Wide-Band Degenerate Parametric Amplifier, *M. Gilden and G. L. Matthaei*... 833
Measurement of the Number of Impurities in the Base Layer of a Transistor, *H. K. Gummel*... 834
Elimination of Crossover Distortion in Class-B Transistor Amplifiers, *James J. Faran, Jr.*... 834
A Broad-Band Tunnel-Diode Amplifier, *N. F. Moody and A. G. Wacker*... 835
Self-Setting Cross-Correlator, *J. A. Jurenko, Jr., and F. L. Burson*. 836
A Technique for the Development of Permanent Visual Images on Magnetic Tape, *Howard R. Padgitt*... 836
Effect of Fluctuations in Density on the Esaki Effect, *D. G. Dow*.. 837
Contributors... 838
IRE Awards, 1961... 841
Books:
"Solid State Physics in Electronics and Telecommunications, Vol. 4, Magnetic and Optical Properties, Part 2," M. Desirant and J. L. Michiels, Eds., *Reviewed by Ronald F. Soohoo*... 852
"Transistors—Principles, Design and Applications," by Wolfgang W. Gärtner, *Reviewed by V. R. Saari*... 852
"La Modulation de Fréquence," by Jean Marcus, *Reviewed by M. Arditi*... 852
"An Introduction to Statistical Communication Theory," by David Middleton, *Reviewed by Norman Abramson*... 853
"The Control of Multivariable Systems," by Mihajlo D. Mesarović, *Reviewed by N. H. Choksy*... 853
"Information Retrieval and Machine Translation, Part I," Allen Kent, Ed., *Reviewed by Gerard Salton*... 853
"Linear Systems Analysis," by Paul E. Pfeiffer, *Reviewed by R. P. Burr*... 854
"Principles of Semiconductor Device Operation," by A. K. Jonscher, *Reviewed by Howard E. Tompkins*... 854
Scanning the Transactions... 855
Abstracts of IRE Transactions... 856
Abstracts and References... 865
1960 IRE Transactions Index... *Follows page* 876

Volume 49, Number 5, Part I, May, 1961

Poles and Zeros... 877
E. Finley Carter, Director, 1961–1963... 878
Scanning the Issue... 879
Low-Noise Amplifiers for Centimeter and Shorter Wavelengths, *G. Wade*... 880
General Relativity for the Experimentalist, *Robert L. Forward*... 892
A Matched Amplifier Using Two Cascaded Esaki Diodes, *Donald R. Hamann*... 904
Network Synthesis with Negative Resistors, *H. J. Carlin and D. C. Youla*... 907
Fluctuation Noise in Semiconductor Space-Charge Regions, *L. J. Giacoletto*... 921
Electrodeless Measurement of Semiconductor Resistivity at Microwave Frequencies, *H. Jacobs, F. A. Brand, J. D. Meindl, N. Benanti, and R. Benjamin*... 928
Accuracy and Limitations of the Resistor Network Used for Solving Laplace's and Poisson's Equations, *J. R. Hechtel and J. A. Seeger* 933
Optimum Capacitor Charging Efficiency for Space System, *P. M. Mostow, J. L. Neuringer, and D. S. Rigney*... 941
A Gas-Discharge Microwave Power Coupler, *Robert W. Olthuis*... 949
Correspondence:
Proposal for a Pulsed Ferromagnetic Microwave Generator, *M. W. Muller*... 957
RF-Induced Negative Resistance in Junction Diodes, *James C. McDade*... 957
Note on Coherence vs Narrowbandedness in Regenerative Oscillators, Masers, Lasers, etc., *M. J. E. Golay*... 958
Note on the Probable Character of Intelligent Radio Signals from Other Planetary Systems, *M. J. E. Golay*... 959
VHF Satellite Signals Received at Extra Optical Distances, *Lloyd J. Anderson*... 959
WWV and WWVH Standard Frequency and Time Transmissions, *National Bureau of Standards*... 960
A Ruby Laser with an Elliptic Configuration, *M. Ciftan, C. F. Luck, C. G. Shafer, and H. Statz*... 960
C-Band Nondegenerate Parametric Amplifier with 500-Mc Bandwidth, *J. Kliphuis*... 961
Backward-Wave Radiation from Periodic Structures and Application to the Design of Frequency-Independent Antennas, *P. E. Mayes, G. A. Deschamps, and W. T. Patton*... 962
K_a-Band Ferrite Amplifier, *Roy W. Roberts*... 963
Equivalent Circuits for a Thermoelectric Converter, *E. L. R. Webb*. 963
A Method for Generating Signals of Arbitrary Yet Frequency-Independent Phase Differences, *O. K. Nilssen*... 964
The Operation of Radio Altimeters Over Snow-Covered Ground or Ice, *W. R. Piggott*... 965
High-Efficiency Variable-Reactance Frequency Multiplier, *T. Utsunomiya and S. Yuan*... 965
Parametric Up-Converter Tunable Over an 18:1 Frequency Band, *G. P. Shepherd and D. G. Kiely*... 966
Parametric Amplification by Charge Storage, *D. L. Hedderly*... 966
Approximate Method of Calculating Electromechanical Coupling Factor, *M. Marutake*... 967
A Simple Method of Generating Nanosecond Pulses at *X* Band, *J. K. Pulfer and B. G. Whitford*... 968
Whistlers Excited by Sound Waves, *K. Rawer and K. Suchy*... 968
Power Carried by the Cyclotron Waves and the Synchronous Waves on a Filamentary Electron Beam, *Shigebumi Saito*... 969
Parametric Variable-Capacitor Motor, *Harry E. Stockman*... 970
The Doppler Effect and Inertial Systems, *Kurt Toman*... 971
Envelope Probability as a Function of E/N_0, *Lee E. Davies*... 971
8- and 11-Gc Nanosecond Carrier Pulses Produced by Harmonic Generation, *A. F. Dietrich*... 972
A Variable Dual Reactance Traveling-Wave Parametric Amplifier, *Robert D. Wanselow*... 973
Parametric-Excited Resonator Using Junction Transistor, *Yohan Cho*... 974
Noise Performance and Stability of a Hybrid-Coupled Tunnel Diode Amplifier, *Wolfgang M. Feist*... 975
Millimeter-Wave Field-Displacement-Type Isolators with Short Ferrite Strips, *K. Ishii, J. B. Y. Tsui, and F. F. Y. Wang*... 975
Effect of Filament Magnetic Field on the Electron Beam from a Pierce Gun, *A. S. Gilmour, Jr.*... 976
Contributors... 977
Books:
"Control System Analysis and Synthesis," by John J. D'Azzo and Constantine H. Houpis, *Reviewed by G. A. Biernson*... 980
"Complex Variables and the Laplace Transform for Engineers," by Wilbur R. LePage, *Reviewed by E. Folke Bolinder*... 980
"Relativistic Electron Theory," by M. E. Rose, *Reviewed by Frank Herman*... 981
"Electromagnetic Fields and Waves," by Robert V. Langmuir, *Reviewed by D. J. Angelakos*... 981
"Analytical Techniques for Non-Linear Control Systems," by John C. West, *Reviewed by John G. Truxal*... 981
"Automatic Translation," by D. Yu. Panov, *Reviewed by Laurence B. Heilprin*... 981
"Radio Transmitters," by Laurence F. Gray and Richard Graham, *Reviewed by Warren B. Bruene*... 982
Recent Books... 982
Scanning the Transactions... 983
Abstracts of IRE Transactions... 984
Abstracts and References... 991

Volume 49, Number 6, June, 1961

Poles and Zeros... 1005
William G. Shepherd, Director, 1960–1962... 1006
Scanning the Issue... 1007
Why in the World in Europe?, *Bruce B. Barrow*... 1008
Frequency Allocations for Space Communications, *Joint Technical Advisory Committee*... 1009
A Low-Noise Microwave Quadrupole Amplifier, *A. Ashkin*... 1016

Correction to "Digital Simulation in Research on Human Communication," *Edward E. David, Jr.* 1020
Tapered Distributed RC Lines for Phase-Shift Oscillators, *W. A. Edson* 1021
Submillimeter Wave Radiometry, *M. W. Long and W. K. Rivers, Jr.* 1024
Results of a Long-Range Clock Synchronization Experiment, *F. H. Reder, M. R. Winkler, and C. Bickart* 1028
High-Frequency Power in Tunnel Diodes, *G. Dermit* 1033
Design Theory of Optimum Negative-Resistance Amplifiers, *E. S. Kuh and J. D. Patterson* 1043
A General Steady-State Analysis of Power-Frequency Relations in Time-Varying Reactances, *R. G. Smart* 1051
Error Statistics and Coding for Binary Transmission Over Telephone Circuits, *A. B. Fontaine and R. G. Gallager* 1059
Correction to "European Electronic Data Processing," *I. L. Auerbach* 1065
Communications Satellites Using Arrays, *R. C. Hanson* 1066
Correspondence:
Nonreciprocal Parametric Amplifier Circuits, *L. David Baldwin* 1075
A Millimeter-Wave Esaki Diode Amplifier, *C. A. Burrus and R. Trambarulo* 1075
Two-Wire Millimeter-Wave Surface Transmission, *K. Ishii, J. B. Y. Tsui, and J. D. Horgan* 1076
Computer Simulation of a Television Coding Scheme, *S. C. Kitsopoulos and E. R. Kretzmer* 1076
Secondary Electron Emission and the Satellite Ionization Phenomenon, *D. B. Medved* 1077
Tunable *S*-Band Traveling-Wave Maser for Telemetry Systems, *S. Okwit, J. G. Smith, and F. R. Arams* 1078
Measurements on Resonators Formed from Circular Plane and Confocal Paraboloidal Mirrors, *Elmer H. Scheibe* 1079
A Solid-State Analog to a Traveling-Wave Amplifier, *George H. Heilmeier* 1079
The Equivalent Noise Current of Esaki Diodes, *R. A. Pucel* 1080
A Junction-Transistor Frequency Divider, *W. D. Ryan and H. B. Williams* 1081
Sideband Correlation of Lunar and Echo Satellite Reflection Signals in the 900-Mc Range, *Roy E. Anderson* 1081
The Teflon Waveguide Plunger, *Akira Okaya* 1083
A New Microwave Power Amplifier, *P. A. Clavier* 1083
A Superposition Property of Angle Modulation, *J. W. Goodman* 1084
Cerenkov Radiation in a Dielectric Tube Waveguide, *B. W. Hakki and P. D. Coleman* 1084
Autocorrelation Pattern Recognition, *Richard Y. Kain* 1085
Closed-Form Solution for the Output of a Finite-Bandwidth Pulse-Compression Filter, *J. DiFranco* 1086
Silicon Epitaxial Microcircuit, *W. Glendinning, C. Marlett, J. Allegretti, and D. Shombert* 1087
On the Integration and Summation of Trigonometric and Exponential Functions, *Nelson M. Blachman* 1088
The Old and the New, *Benjamin F. Miessner* 1089
Generating a Rotating Polarization, *S. R. Penstone and A. W. Adey* 1089
A Comparison Between Theoretical and Experimental Data on Phase Velocity of VLF Radio Waves, *James R. Wait* 1089
Reflection and Transmission of Conductive Films, *Martin V. Schneider* 1090
A Mechanism for Direct Adjacent Channel Interference, *Clyde L. Ruthroff* 1091
Tunnel-Diode Binary Counter Circuit, *Hanoch Ur* 1092
New Ways to Trigger Avalanche Pulse Circuits, *H. G. Dill* 1093
Discussion of "Combined AM and PM for a One-Sided Spectrum," *R. M. Golden, M. R. Schroeder, and N. B. Chakrabarti* 1094
Approximate Solution to Semiconductor Noise as a Queuing Problem, *Thomas L. Saaty* 1095
Taylor-Cauchy Transforms for Analysis of Varying-Parameter Systems, *Y. H. Ku* 1096
Correction to "Laurent-Cauchy Transforms for Analysis of Linear Systems Described by Differential-Difference and Sum Equations," *Y. H. Ku and A. A. Wolf* 1097
Correction to "Taylor Cauchy Transforms for Analysis of a Class of Nonlinear Systems," *Y. H. Ku, A. A. Wolf, and J. H. Dietz* 1098
Low-Noise Electron Guns and the 6L6 Effect, *S. Yadavalli* 1098
Digital Radiometer, *Sander Weinreb* 1099
Some Recent Papers in Threshold Logic, *R. O. Winder* 1100
WWV and WWVH Standard Frequency and Time Transmissions, *National Bureau of Standards* 1100
Gallium Antimonide Esaki Diodes for High-Frequency Applications, *C. A. Burrus* 1101
Contributors 1102
Report of the Secretary—1960 1104
Books:
"Frequency-Power Formulas," by Paul Penfield, Jr., *Reviewed by Samuel Seely* 1108
"Plasma Physics," by James E. Drummond, *Reviewed by John M. Richardson* 1108
"High Frequency Applications of Ferrites," by J. Roberts, *Reviewed by John H. Rowen* 1108
"Design for a Brain," 2nd Edition, by W. Ross Ashby, *Reviewed by Frank Rosenblatt* 1108
"Fundamentals of Signal Theory," by John L. Stewart, *Reviewed by C. A. Desoer* 1109
"The McGraw-Hill Encyclopedia of Science and Technology," *Reviewed by Gustave Shapiro* 1109
"Boolean Algebra and Its Applications," by J. Eldon Whitesitt, *Reviewed by Robert Serrell* 1110
"Modern Mathematics for the Engineer," Second Series, Edwin F. Beckenbach, Ed., *Reviewed by Bernard Friedland* 1110
Scanning the TRANSACTIONS 1110
Abstracts of IRE TRANSACTIONS 1111
Abstracts and References 1118
Translations of Russian Technical Literature 1132

Volume 49, Number 7, July, 1961

Poles and Zeros 1133
L. C. Van Atta, Director, 1961–1963 1134
Scanning the Issue 1135
The Interplay of Electronics and Vacuum Technology, *J. M. Lafferty and T. A. Vanderslice* 1136
New Concepts in Thermoelectric Device Design, *W. H. Clingman* 1155
IRE Standards on Piezoelectric Crystals: Measurements of Piezoelectric Ceramics, 1961 1161
The Field-Effect Tetrode, *H. A. Stone, Jr. and R. M. Warner, Jr.* 1170
An Experimental Study of Bistatic Scattering from Some Small Absorber-Coated, Metal Shapes, *R. J. Garbacz and D. L. Moffatt* 1184
IRE Standards on Video Techniques: Definitions of Terms Relating to Television, 1961 1193
The Elimination of Intersymbol Interference by Input Signal Shaping, *I. Gerst and J. Diamond* 1195
Correspondence:
Generation of Nanosecond Carrier Pulses at *X*-Band with Tunnel Diodes, *L. U. Kibler* 1204
Circuit Control of Tunnel-Diode Negative-Resistance Characteristics, *W. N. Carr and A. G. Milnes* 1204
Sensitivity of the Degenerate Parametric Amplifier, *J. T. de Jager and B. J. Robinson* 1205
Stability Criteria for Tunnel Diodes, *L. I. Smilen and D. C. Youla* 1206
On the Possibility of Drift-Tunnel Oscillations in High-Power Klystrons, *K. Tomiyasu* 1207
Noise in Beam-Type Parametric Amplifiers, *Eugene I. Gordon* 1208
Pull-In Frequency of the Phase-Controlled Oscillator, *A. J. Goldstein and C. J. Byrne* 1209
Fourier Series Derivation: A Comment, *P. A. Clavier* 1209
Traveling-Wave Maser with Instantaneous Bandwidths in Excess of 100 Mc, *S. Okwit and J. G. Smith* 1210
The Propagation of Wide-Band Signals Through the Ionosphere, *H. Staras* 1211
Noise Measure of Lossy Tunnel-Diode Amplifier Stages, *A. van der Ziel* 1211
Noise Measure of Distributed Negative-Conductance Amplifiers, *A. van der Ziel* 1212
Full Binary Adder With One Tunnel Diode, *B. Rabinovici and C. A. Renton* 1213
Parametric Amplification with a Low Frequency Pump, *G. Franklin Montgomery* 1214
100-Mc Tunnel-Diode Ring Counter, *Fred P. Heiman* 1215
Concerning the Partition Theory and Associated Transform Methods, *E. V. Bohn* 1215
A Theoretical Comparison of Average- and Spot-Noise Figure in Transistor Amplifiers, *J. A. Ekiss and J. W. Halligan* 1216
The Calculation of Cutoff Frequencies of Minority-Carrier Transport Factors in Drift Transistors when the Mobiliities are not Constant, *T. Sugano and F. Koshiga* 1218
Logarithmic Compression of Binary Numbers, *David H. Schaefer* 1219
Converter Efficiency and Power Output of a Tunnel-Diode Relaxation Oscillator, *Shyh Wang* 1219
Vertical Incidence Doppler Ionogram, *J. W. Findlay, T. Ogawa, S. Ando, and A. Yoshida* 1220
On Scattering Matrices Normalized to Complex Port Numbers, *D. C. Youla* 1221
TM Modes in Parallelogramic Waveguides, *R. J. Doviak, D. J. Lewis, and P. P. Lombardini* 1222
A Nondirectional Ferrite Rod Antenna Arrangement Suitable for AM Radios, *O. K. Nilssen* 1222
"Noisemanship"—The Art of Measuring Noise Figures Nearly Independent of Device Performance, *J. C. Greene* 1223
A Liquid-Helium-Cooled Coaxial Termination, *C. T. Stelzried* 1224
Additional Negative-Resistance Oscillation Modes, *W. N. Carr and T. C. Matty* 1225
Tunnel-Diode Down Converters, *Don G. Peterson* 1225
Excess Noise in Microwave Mixer Crystals, *B. G. Bosch, W. A. Gambling, and T. H. Wilmshurst* 1226
WWV and WWVH Standard Frequency and Time Transmissions, *National Bureau of Standards* 1227
On the Hues Seen in Fox-Color Images, *H. E. Kallmann* 1228
Relative Error Analysis, *John B. Peatman* 1229
Autocorrelation Properties of Convoluted Optimum Finite Code Groups, *D. C. Coll* 1230
An *L*-Band Traveling-Wave Parametric Amplifier, *S. J. Tetenbaum, F. A. Olson, and A. Savarin* 1230
Contributors 1231
Books:
"High-Frequency Magnetic Materials—Their Characteristics and Principal Applications," by W. J. Polydoroff, *Reviewed by D. L. Fresh* 1233
"Linear Circuits, Part I: Time-Domain Analysis; Part 2: Frequency-Domain Analysis," by R. E. Scott, *Reviewed by T. W. Culpepper* 1233
"Principles of Feedback Control," by C. H. Wilts, *Reviewed by Richard G. Buscher* 1233
"Electronic Equipment Reliability," by G. W. A. Dummer and N. Griffin, *Reviewed by M. Raphelson* 1234
"Mathematical Handbook for Scientists and Engineers," by Granino A. Korn and Theresa M. Korn, *Reviewed by Anthony B. Giordano* 1234
"1959 Digest of Literature on Dielectrics," by Louis J. Frisco and Thomas D. Callinan, Eds., *Reviewed by P. N. Wolfe* 1234
"The International Dictionary of Physics and Electronics, Second

Edition," Walter C. Michels, Editor-in-Chief, *Reviewed by R. F. Shea* ... 1235
"Design Fundamentals of Analog Computer Components," by R. M. Howe, *Reviewed by J. E. Sherman* ... 1235
"Solid State Physics in Electronics and Telecommunications, Vol. 2. Semiconductors, Part II," M. Désirant and J. L. Michiels, Eds., *Reviewed by Arthur P. Stern* ... 1235
"Semiconductor Abstracts, Vol. VI—1958 issue" J. J. Bulloff and C. S. Peet, Eds., *Reviewed by J. A. Sluss, Jr.* ... 1236
"Field Theory for Engineers," by Parry Moon and Domina Eberle Spencer, *Reviewed by James R. Wait* ... 1236
"Terrain Scattering Properties for Sensor System Design (Terrain Handbook II)," by R. L. Cosgriff, W. H. Peake, and R. C. Taylor, *Reviewed by Keeve M. Siegel* ... 1236
"Linear Graphs and Electrical Networks," by Sundaram Seshu and Myril B. Reed, *Reviewed by Philip F. Ordung* ... 1237
"Physics of Semiconductors," by A. F. Ioffe, *Reviewed by Lloyd T. DeVore* ... 1237
Recent Books ... 1237
Scanning the TRANSACTIONS ... 1238
Abstracts of IRE TRANSACTIONS ... 1239
Abstracts and References ... 1246

Volume 49, Number 8, August, 1961

Poles and Zeros ... 1261
Anthony B. Giordano, Director, 1961–1962 ... 1262
Scanning the Issue ... 1263
Antiferroelectric Ceramics with Field-Enforced Transitions: A New Nonlinear Circuit Element, *Bernard Jaffe* ... 1264
Large-Signal Circuit Theory for Negative-Resistance Diodes, in Particular Tunnel Diodes, *M. Schuller and W. W. Gärtner* ... 1268
IRE Standards on Solid-State Devices: Definitions of Terms for Nonlinear Capacitors, 1961 ... 1279
Self-Oscillation in a Transmission Line with a Tunnel Diode *J. Nagumo and M. Shimura* ... 1281
IRE Standards on Solid-State Devices: Measurement of Minority-Carrier Lifetime in Germanium and Silicon by the Method of Photoconductive Decay ... 1292
Detection Range Predictions for Pulse Doppler Radar, *S. A. Meltzer and S. Thaler* ... 1299
Low-Level Garnet Limiters, *F. R. Arams, M. Grace, and S. Okwit* 1308
Correspondence:
The Silicon Cryosar, *H. Izumi* ... 1313
Noise Figure and Stability of Negative Conductance Amplifiers *Alan C. Macpherson* ... 1314
Tunnel-Diode One-Shot and Triggered Oscillator, *T. W. Flowerday and D. D. McKibbin* ... 1315
A Tunnel-Diode Slot Transmission Amplifier, *Melvin E. Pedinoff* 1315
Neural Analogs, *L. D. Harmon and A. E. Brain* ... 1316
On Self-Organizing Systems, *P. D. Coleman* ... 1317
Stable Low-Noise Tunnel-Diode Frequency Converter, *F. Sterzer and A. Presser* ... 1318
Thin-Film Cryotrons, *V. L. Newhouse and H. H. Edwards* ... 1318
Are Electronics Engineers Educated? *R. W. Johnson* ... 1319
A Note on Sugai's Class of Solutions to Riccati's Equation, *David C. Stickler* ... 1320
A New RMS Describing Function for Single-Valued Nonlinearities, *J. E. Gibson and K. S. Prasanna-Kumar* ... 1321
A Proposed Test of the Constancy of the Velocity of Light, *Pascal M. Rapier* ... 1322
Notes on the Structure of Logic Nets, *Robert M. Stewart* ... 1322
Suppression of Emission from Portions of Barium-Activated Tungsten Dispenser Cathodes and Adjoining Electrodes, *R. Levi and E. S. Rittner* ... 1323
Transmission Line Model, *J. D. Wallace* ... 1324
Antenna Siting Tests at 3480 and 9640 Mc on a 173-Mile Tropospheric Scatter Path, *N. D. La Frenais and W. J. Lucas* ... 1325
On the Linear Circuit Aspects of Cryotrons, *P. M. Chirlian and V. A. Marsocci* ... 1326
A Method for Determining the Base Voltage and Contact Resistance of a Conductivity-Modulated Diode, *J. M. Swartz and H. C. Gorton* ... 1326
Receivers with Zero Intermediate Frequency, *M. D. Rubin* ... 1327
A Magnetic Shield for Beam Frequency Standards, *F. S. Barnes* 1328
A Monopulse Instrumentation System, *Frederic P. Storke, Jr.* ... 1328
A Traveling-Wave Maser Using Chromium-Doped Rutile, *E. S. Sabisky and H. J. Gerritsen* ... 1329
Shaping of Distributed RC Networks, *B. L. H. Wilson and R. B. Wilson* ... 1330
Proposed Technique for Modulation of Coherent Light, *A. K. Kamal and S. D. Sims* ... 1331
A Generalization of "Mutual Information," *N. M. Blachman* ... 1331
A Broad-Band Termination for IF Coaxial Lines, *A. Susini and F. A. Ferger* ... 1332
Tracking and Display of Earth Satellites, *A. Van Gelder, Jr.* ... 1332
High-Level Microwave Detector Using Avalance Injection, *H. M. Day and A. C. MacPherson* ... 1333
Coherent Generation of Microwave Power by Annihilation Radiation of a Prebunched Beam, *B. W. Hakki and H. J. Krumme* ... 1334
WWV and WWVH Standard Frequency and Time Transmissions, *National Bureau of Standards* ... 1335
Self-Educating Machines for Recognition and Classification of Patterns, *P. A. Clavier* ... 1335
On Parametric Amplification in Transistors, *J. Lindmayer, C. Wrigley, V. W. Vodicka, and R. Zuleeg* ... 1335
Multiple Burst Detection, *Francis Corr* ... 1337
An Analytical Expression for Describing the Write Process in Magnetic Recording, *T. C. Ku* ... 1337
A Potential Microwave Computer Element, *R. W. Couch, A. F. Rashid, and R. Spence* ... 1338
A Solution to the Shannon Switching Game, *A. Lehman* ... 1339
The Wide Tuning Range of Backward Traveling-Wave Parametric Amplifiers, *H. Hsu and S. Wanuga* ... 1339
Correction to "Negative Resistance in Transistors Based on Transit-Time and Avalanche Effects," *R. A. Pucel and H. Statz* ... 1340
Correction to "Communications Satellites Using Arrays," *R. C. Hansen* ... 1340
Contributors ... 1341
Books:
"Transistor Circuit Analysis," by M. V. Joyce and K. K. Clarke, *Reviewed by J. T. Lynch and J. J. Karew* ... 1343
"IRE Dictionary of Electronic Terms and Symbols (Compiled from IRE Standards)," *Reviewed by R. F. Shea* ... 1343
"Printed Circuits—Their Design and Application," by J. M. C. Dukes, *Reviewed by Thomas A. Prugh* ... 1343
"Line Waves and Antennas," by R. G. Brown, R. A. Sharpe, and W. L. Hughes, *Reviewed by Carl E. Smith* ... 1344
"Time-Harmonic Electromagnetic Fields," by Roger F. Harrington, *Reviewed by Charles H. Papas* ... 1344
"Theory of Microwave Valves," by S. D. Gvozdover, *Reviewed by C. W. Barnes* ... 1344
"Lectures on Communication System Theory," Elie J. Baghdady, Ed., *Reviewed by M. R. Aaron* ... 1345
"Electronic Drafting Handbook," by Nicholas M. Raskhodoff, *Reviewed by R. T. Haviland* ... 1345
"Electronics," by P. M. Chirlian and A. H. Zemanian, *Reviewed by W. R. Hill* ... 1346
"Progress in Semiconductors, Vol. 5," A. F. Gibson, F. A. Kröger, and R. F. Burgess, Eds., *Reviewed by W. M. Bullis* ... 1346
"Essentials of Dielectromagnetic Engineering," by H. M. Schlicke, *Reviewed by Charles F. Pulvari* ... 1347
"Radio Waves in the Ionosphere," by K. G. Budden, *Reviwed by M. G. Morgan* ... 1347
"Scientific Russian," by James W. Perry, *Reviewed by S. D. Browne* 1347
"Electrical Noise" by W. R. Bennett, *Reviewed by H. A. Haus* ... 1348
Recent Books ... 1348
Scanning the TRANSACTIONS ... 1348
Abstracts of IRE TRANSACTIONS ... 1349
Abstracts and References ... 1358

Volume 49, Number 9, September, 1961

Poles and Zeros ... 1373
A. B. Bereskin, Director, 1961–1962 ... 1374
Scanning the Issue ... 1375
The IRE International Activities Committee, *R. L. McFarlan* ... 1376
Reflections of a Communication Engineer, *Marcel J. E. Golay* ... 1378
An Analysis of the Modes of Operation of a Simple Transistor Oscillator, *J. F. Gibbons* ... 1383
Actual Noise Measure of Linear Amplifiers, *K. Kurokawa* ... 1391
IRE Standards on Radio Interference: Methods of Measurement of Conducted Interference Output to the Power Line from FM and Television Broadcast Receivers in the Range of 300 kc to 25 Mc, 1961 ... 1398
The Delay-Lock Discriminator—An Optimum Tracking Device, *J. J. Spilker, Jr. and D. T. Magill* ... 1403
A Sequential Detection System for the Processing of Radar Returns, *Aaron A. Galvin* ... 1417
Correspondence:
Minimum Time for Turn-Off in Four-Layer Diodes, *M. A. Melehy* ... 1424
Microwave Amplification in Electrostatic Ring Structures, *J. C. Bass* ... 1424
Diode Reverse Characteristics at Low Temperatures, *Alvin S. Clorfeine* ... 1425
Maser Action in Ruby by Off-Resonance Pumping, *F. Arams and M. Birnbaum* ... 1426
Reverse Charactierstics of Low-Lifetime Germanium Diodes, *A. Blicher and I. H. Kalish* ... 1427
The Negative Resistances in Junction Diodes, *Ibrahim Hefni* ... 1427
Pattern Recognition by Moment Invariants, *Ming-Kuei Hu* ... 1428
Temperature Dependence of the Peak Current of Germanium Tunnel Diodes, *A. Blicher, R. M. Minton, and R. Glicksman* ... 1428
On the Possibility of Rejecting Certain Modes in VLF Propagation, *James R. Wait* ... 1429
A Neuristor Prototype, *A. J. Cote, Jr.* ... 1430
A Two-Step Algorism for the Reduction of Signal Flow Graphs, *Amos Nathan* ... 1431
A Synthesis Procedure for an *n*-Port Network, *D. Hazony and H. J. Nain* ... 1431
An Interpretation of "Paired Echo Theory" for Time-Domain Distortion in Pulsed Systems and an Extension to the Radar "Uncertainty Function," *J. V. DiFranco and W. L. Rubin* ... 1432
Radar Scattering Cross Section—Applied to Moon Return, *H. S. Hayre* ... 1433
Gain Saturation in a Traveling-Wave Parametric Amplifier, *A. Jurkus and P. N. Robson* ... 1433
WWV and WWVH Standard Frequency and Time Transmissions, *National Bureau of Standards* ... 1434
Correction to "Measurements on Resonators Formed from Circular Plane and Confocal Paraboloidal Mirrors," *Elmer H. Scheibe* 1434
On the Cascaded Tunnel-Diode Amplifier, *P. M. Chirlian* ... 1434
The Determination of the Image Response in a Superheterodyne with Regard to Noise-Factor Measurement, *M. Piattelli* ... 1435
The Effect of Nonsymmetrical Doping on Tunnel Diodes, *F. D. Shepherd and A. C. Yang* ... 1435

Reconstruction Error and Delay for Amplitude-Sampled White Noise, *D. S. Ruchkin* 1436
Relativity and the Clock Paradox, *A. Roth* 1437
Electron Radiation Damage in Unipolar Transistor Devices, *B. A. Kulp, J. P. Jones and A. F. Vetter* 1437
Negentropy Revisited, *P. A. Clavier* 1438
Optical Erasure of EL-PC and Neon-PC Storage Elements, *J. A. O'Connell and B. Narken* 1438
A Magnetically Tunable Microwave-Frequency Meter, *George H. Theiss* 1439
A Bistable Flip-Flop Circuit Using Tunnel Diode, *V. Uzunoglu* 1440
Microwave Determination of Semiconductor-Carrier Lifetimes, *H. A. Atwater and H. Jacobs* 1440
Antigravity, *Robert L. Forward* 1442
On the Nomenclature of TE_{01} Modes in a Cylindrical Waveguide, *C. T. Tai* 1442
On Minimum Reading Times for Simple Current-Measuring Instruments, *P. F. Howden* 1443
Gyromagnetic Resonance of Ferrites and Garnets at UHF, *J. Deutsch and H. G. Maier* 1443
One-Tunnel-Diode Binary, *A. L. Whetstone, S. Kounosu, and R. A. Kaenel* 1445
Notes on "Fourier Series Derivation," *Jenö Takács* 1446
Theoretical Techniques for Handling Partially Polarized Radio Waves with Special Reference to Antennas, *H. C. Ko* 1446
Laurent-Cauchy Transforms, *Johann Tschauner* 1447
Pickard's Regenerative Detector, *Ralph W. Burhans* 1447
Temperature Effects on GaAs Switching Transistors, *E. D. Haidemenakis, J. A. Mydosh, N. Almeleh, R. Bharat, and E. L. Schork* 1448
Comments on "Operation of Radio Altimeters Over Snow-Covered Ground or Ice," *Amory H. Waite, Jr* 1449
A Simple Calibration Technique for Vibrating Sample and Coil Magnetometers, *N. V. Frederick* 1449
Frequency Modulation of a Reflex Klystron with Minimum Incidental Amplitude Modulation, *Walter R. Day, Jr* 1449
Analog Study of Posicast Control by Relay Systems, *Chiao-yao She* 1450
Elimination of Ionospheric Refraction Effects, *Lt. José M. Brito-Infante* 1451
Antenna-Beam Configurations in Scatter Communications, *Alan T. Waterman, Jr* 1452
An Extended Definition of Linearity, *L. A. Zadeh* 1452
Thickness-Shear Mode Quartz Cut with Small Second- and Third-Order Temperature Coefficients of Frequency (RT-Cut), *R. Bechmann* 1454
Restrictions in Synthesis of a Network with Majority Elements, *Saburo Muroga* 1455
Satellite Supported Comminication at 21 Megacycles, *Raphael Soifer* 1455
Contributors 1457
Books:
"Sequential Decoding," by J. M. Wozencraft and B. Reiffen, *Reviewed by Robert A. Short* 1458
"Fundamentals of Modern Physics," by Robert Martin Eisberg, *Reviewed by C. W. Carnahan* 1458
"Mechanical Waveguides," by Martin R. Redwood, *Reviewed by John E. May, Jr* 1458
"Error Correcting Codes," by W. W. Peterson, *Reviewed by Norman Abramson* 1459
"Magnetic Tape Instrumentation," by Gomer L. Davies, *Reviewed by S. J. Begun* 1459
"Circuit Analysis," by Elias M. Sabbach, *Reviewed by Ian O. Ebert* 1459
"Advances in Electron Tube Techniques," David Slater, Ed., *Reviewed by George A. Espersen* 1460
"Information Retrieval and Machine Translation," Part II, Allen Kent, Ed.; "Advances in Documentation and Library Science Series," Vol. 3, Jesse H. Shera, General Editor, *Reviewed by Gerard Salton* 1460
"Management Control Systems," D. G. Malcolm and A. J. Rowe, Eds.; L. F. McConnell, General Editor, *Reviewed by James J. Lamb* 1461
Scanning the TRANSACTIONS 1461
Abstracts of IRE TRANSACTIONS 1462
Abstracts and References 1470

Volume 49, Number 10, October, 1961

Poles and Zeroes 1485
Daniel E. Noble, Director, 1961 1486
Scanning the Issue 1487
Time-Varying Networks, I, *L. A. Zadeh* 1488
Compatible Single Sideband, *Leonard R. Kahn* 1503
Magnetic Circuits Employing Ceramic Magnets, *J. C. Helmer* 1528
Electron Trigonometry—a New Tool for Electron-Optical Design, *Kurt Schlesinger* 1538
New FM-AM Method of Compression, Expansion, and Multiplication, *W. R. Aiken and C. Süsskind* 1550
IRE Recommended Practices on Audio and Electroacoustics: Loudspeaker Measurements, 1961 1553
Coincidence Techniques for Radar Receivers Employing a Double-Threshold Method of Detection, *K. Endresen and R. Hedemark* 1561
Correspondence:
Antenna and Receiving-System Noise-Temperature Calculation, *L. V. Blake* 1568
Nonsymmetrical Properties of Nonlinear Elements in Low- and High-Impedance Circuits, *A. L. Helgesson* 1569
Improved Tungsten Evaporation Filament for Gold-Silver Alloy, *Frank G. Pany* 1570
Some Operating Characteristics of Flash-Pumped Ruby Lasers, *John C. Cook* 1570
Repetitive Hair-Trigger Mode of Optical Maser Operation, *M. L. Stitch, E. J. Woodbury, and J. H. Morse* 1571
WWV and WWVH Standard Frequency and Time Transmissions, *National Bureau of Standards* 1572
Correction to "Stable Low-Noise Tunnel-Diode Frequency Converter," *F. Sterzer and A. Presser* 1572
Lossy Coupling in Parametric Amplifier, *Krzysztof Grabowski* 1573
Discussion of Calculation of False Alarm Rate, *W. M. Rogers, Jr., S. Thaler, and S. Meltzer* 1573
Microwave Radiation Hazards, *Thomas G. Custin* 1574
Power Limiting in the 4-kMc to 7-kMc Frequency Range Using Lithium Ferrite, *F. C. Rossol* 1574
Phase Inverters Utilizing Controlled Superconductors, *P. M. Chirlian and V. A. Marsocci* 1574
A Ferrimagnetic Limiter-Isolator, *J. Brown and G. R. Harrison* 1575
On the Impedance of Long Wire Suspended Over the Ground, *James R. Wait* 1576
Masers, Lasers, and the Ether Drift?, *C. W. Carnahan* 1576
Matrix Analysis of Networks Having Infinite-Gain Operational Amplifiers, *Amos Nathan* 1577
A Self-Balancing Current Meter and Recorder, *John W. Moore* 1578
Reciprocal Relations in an *N*-Slab Dielectric, *R. Hollis* 1579
Construction of Probability Densities from Their Moments, *P. A. Clavier* 1580
A Simple Passive-Element Electrical Analog to a Gyro, *Robert W. Redlich* 1580
Measurement of Tunnel-Diode Conductance Parameters, *Bent Christensen* 1581
Experiments with Nonreciprocal Parametric Devices, *A. Korpel and P. Desmares* 1582
New Form of Plasma Dispersion Formula Usable for Analog Computing, *H. Porsche and K. Rawer* 1582
The Expanded Reactance Series Resonator—"ERSER," *E. O. Willoughby* 1583
Representation of Propagation Parameters for the Plasma in a Magnetic Field, *R. E. Haskell and E. H. Holt* 1584
Study of Electromagnetic Wave Polarization in Magneto-Plasmas by a Matrix Method of Crystal Optics, *R. E. Haskell and E. H. Holt* 1584
A Decoding Procedure for Double-Error Correcting Bose-Ray-Chaudhuri Codes, *R. B. Banerji* 1585
Nonrealizability of the Complex Transformer, *R. W. Newcomb* 1585
Tunnel-Diode Super-Regenerative Parametric Motor, *Harry E. Stockman* 1586
An Adaptive Communications Filter, *C. S. Weaver* 1587
Contributors 1588
Books:
"Wave Propagation in a Turbulent Medium," by V. I. Tatarski, *Reviewed by Ralph Bolgiano, Jr* 1590
"Semiconductor Devices and Applications," by R. A. Greiner, *Reviewed by Nick Holonyak, Jr* 1590
"Philosophical Impact of Contemporary Physics," by Milič Čapek, *Reviewed by Frank Herman* 1591
"Microwave Ferrites," by P. J. B. Clarricoats, *Reviewed by E. H. Turner* 1591
"Foundation for Electric Network Theory," by Myril B. Reed, *Reviewed by Bede Liu* 1591
"Plasma Acceleration—The Fourth Lockheed Symposium on Magnetohydrodynamics," Sidney W. Kash, Ed., *Reviewed by Conrad H. Hoeppner* 1591
"Transmission of Information," by Robert M. Fano, *Reviewed by Georges A. Deschamps* 1592
"Digital Applications of Magnetic Devices," Albert J. Meyerhoff, Ed., *Reviewed by A. H. Bobeck* 1592
Scanning the TRANSACTIONS 1593
Abstracts of IRE TRANSACTIONS 1594
Abstracts and References 1598

Volume 49, Number 11, November, 1961

Poles and Zeroes 1613
M. W. Bullock, Director, 1961-1962 1614
Scanning the Issue 1615
The Cryosistor—A Field-Effect Controlled Impact Ionization Switch, *I. Melngalis and A. G. Milnes* 1616
A New Semiconductor Tetrode—The Surface-Potential Controlled Transistor, *C. T. Sah* 1623
Correction to "Statistical Analysis of Certain Binary Division Algorithms," *C. V. Freiman* 1634
The Pulsed Ruby Maser as a Light Amplifier, *P. P. Kisliuk and W. S. Boyle* 1635
Correction to "The Elimination of Intersymbol Interference by Input Signal Shaping," *I. Gerst* 1639
Inductance in Thin-Film Superconducting Structures, *Norman H. Meyers* 1640
Reduction of the Frequency-Temperatures Shift of Piezoelectric Resonators by Mechanical Stress, *E. A. Gerber and M. H. Miles* 1650
Fundamental Limitations to Optical Doppler Measurements for Space Navigation, *R. H. Norton and R. L. Wildey* 1655
Timing Potentials of Loran-C, *R. H. Doherty, G. Hefley, and R. F. Linfield* 1659
A Provisional Ground Conductivity Map for Canada, *G. Clement Ireland* 1674
Correspondence:
Tunnel-Diode Series Resistance, *E. L. Bonin and J. R. Biard* 1679

Some Measurements on an Iris Beam Waveguide, *J. R. Christian and G. Goubau* ... 1679
Ionospheric Contributions to the Doppler Shift at VHF from Near-Earth Satellites, *William H. Guier* ... 1680
WWV and WWVH Standard Frequency and Time Transmissions, *National Bureau of Standards* ... 1681
Persistent-Current Memory Circuit, *W. C. Stewart, H. A. Owens, M. S. P. Lucas, and C. R. Vail* ... 1681
A *C*-Band Parametric Amplifier with Large Bandwidth, *B. T. Vincent, Jr.* ... 1682
Multiple Reflections of Microwaves Propagating Through a Semiconductor Medium, *H. Jacobs, F. A. Brand, J. D. Meindl, and R. Benjamin* ... 1683
Correlation Optical Radar, *M. Katzman and E. Frost* ... 1684
Unidirectional Lower Sideband Parametric Amplifier Without Circulator, *G. B. H. Thompson* ... 1684
One-Tunnel-Diode Flip-Flop HF Behavior, *Henry Guckel* ... 1685
Additional Information on "An Interaction Circuit for Traveling-Wave Tubes," *R. M. White, C. K. Birdsall, D. E. Chaffee, P. J. Crepau, and I. Itzkan* ... 1686
Comments on "Design Theory of Optimum Negative-Resistance Amplifiers," *H. J. Carlin, L. I. Smilen, D. C. Youla, E. S. Kuh, and J. D. Patterson* ... 1687
Noise in Tunnel-Diode Mixers, *Shih-Fang Lo* ... 1688
Comments on "Tunnel-Diode Microwave Oscillators," *G. Fuller, G. W. H. Wooding, D. Sterzer, D. E. Nelson* ... 1689
Gravitational Fields, *Jovan Djurić* ... 1689
The *gh*-Field Theory, *Jovan Djurić* ... 1690
X-Band Electronically-Variable Attenuator, *P. L. Fleming* ... 1690
A Method of Displaying Ultra-Fast Limit Cycles or Three-Parameter Trajectories, *William T. Rhoades* ... 1691
An Extension of Newtonian Relativity to Include Electromagnetic Phenomena, *Pascal M. Rapier* ... 1691
Maser Terminology, *William R. Mallory* ... 1692
Technique for Amplitude Modulating a Van Atta Radar Reflector, *William F. Bahret* ... 1692
Some Ladder Networks Representing Certain Transcendal Numbers—Classroom Note, *F. Reza* ... 1693
Performance Degradation of Linear FM-Pulse-Compression Systems Due to the Doppler Effect, *H. O. Ramp and E. R. Wingrove, Jr.* ... 1693
Doppler-Shift Effects in Space Propagation, *R. P. Haviland* ... 1694
Comment on Shot-Noise Smoothing Mechanism Proposed by LaRosa and Wilhelmsen, *C. A. Lee and A. Yariv* ... 1695
Vacuum-Tube Networks, *George D. O'Neill* ... 1695
Flow-Graphs and Tapered Transmission Lines, *Frank M. Brown* ... 1696
Large Signal Interaction Between a Spiraling Electron Beam and the TE_{10} Rectangular Waveguide Mode, *W. L. Dickson, C. C. Johnson, and R. W. Grow* ... 1696
On Backward-Wave Oscillator Stabilization, *R. B. Clark and W. D. Comstock* ... 1697
Education and Creativity, *B. F. Miessner* ... 1697
A Simple Method for the Supervision of the Orbital Period of Artificial Satellites, *P. R. Arendt and L. H. Manamon* ... 1698
Comments on "A Theoretical Comparison of Average- and Spot-Noise Figure in Transistor Amplifiers," *Paul J. Bénéteau* ... 1699
The Directional Coupler Core of an Arbitrary, Lossless, Reciprocal 4-Port, *W. K. Kahn and R. L. Kyhl* ... 1699
Spectral Response of a Nonlinear Device, *William B. Ribbens* ... 1700
On a Mathematical Description of Noisy Measurement System Performance, *J. L. Hammond, Jr.* ... 1701
The Delta Function and the Fourier Integral, *A. W. McMurtrey* ... 1702
An Electronically Tunable Up-Converter, *George L. Matthaei* ... 1703
The Linearized Transfer Function of a Phase-Locked Loop Containing an IF Amplifier, *R. Lawhorn and C. S. Weaver* ... 1704
Infrared Fluorescence and Stimulated Emission of Nd^{+3} in $CaWO_4$, *L. F. Johnson and K. Nassau* ... 1704
Maser Oscillation Observed from HCN Maser at 88.6 kMc, *Dietrich Marcuse* ... 1706
High-Speed Silicon Computer Diodes as RF Switches, *R. E. Aitchison* ... 1707
Use of a Coherent Memory Filter in Spectral Measurements of Atmospheric Whistlers, *J. Capon and M. R. Weiss* ... 1707
Injection Efficiency in Double Diffuse Transistors, *Melvin Klein* ... 1708
Antenna Size for a Space Vehicle, *C. S. Lorens* ... 1708
Input-Output Relationships for Multisampled Loop Systems, *George G. Lendaris* ... 1709
Contributors ... 1710
Books:
"Adaptive Control Processes: A Guided Tour," by Richard Bellman, *Reviewed by L. A. Zadeh* ... 1712
"The Physical Theory of Transistors," by Leopoldo B. Valdes, *Reviewed by M. A. Clark* ... 1712
"An Introduction to the Principles of Communication Theory," by John C. Hancock, *Reviewed by Warren D. White* ... 1713
"Proceedings of URSI Thirteenth General Assembly," John P. Hagen, Ed., *Reviewed by E. C. Jordan* ... 1713
"The Antenna," by H. Thourel, *Reviewed by Seymour B. Cohn* ... 1713
"Antenna Engineering Handbook," Henry Jasik, Ed., *Reviewed by George Sinclair* ... 1714
"Electronic Circuits, Signals and Systems," by S. J. Mason and H. J. Zimmerman, *Reviewed by W. H. Huggins* ... 1714
Recent Books ... 1715
Scanning the TRANSACTIONS ... 1715
Abstracts of IRE TRANSACTIONS ... 1716
Abstracts and References ... 1726

Volume 49, Number 12, December, 1961

Poles and Zeros ... 1741
B. R. Tupper, Director, 1961–1962 ... 1742
Open Letter from the President, *Lloyd B. Berkner* ... 1743
Introduction to The Plasma Issue, *D. G. Dow and E. W. Herold* ... 1747
Plasma Physics—An Elementary Review, *M. P. Bachynski* ... 1751
Oscillations and Noise in Low-Pressure DC Discharges, *F. W. Crawford and G. S. Kino* ... 1767
Ionic and Plasma Propulsion for Space Vehicles, *G. R. Brewer, M. R. Currie, and R. C. Knechtli* ... 1789
Transmission of Electromagnetic Waves Through an Ionized Layer in the Presence of a Strong Magnetic Field, *T. P. Harley and G. Tyras* ... 1822
The Use of Magnetic Fields in the Elimination of the Re-Entry Radio Blackout, *H. Hodara* ... 1825
RF Reflectance of Plasma Sheaths, *Leonard S. Taylor* ... 1831
Correction to "A Small-RF-Signal Theory for an Electrostatically Focussed Traveling-Wave Tube," *W. W. Siekanowicz* ... 1836
Mutual Coupling of Two Thin Infinitely-Long Slots Located on a Perfectly Conducting Plane in the Presence of a Uniform Plasma Layer, *James S. Yee* ... 1837
Antenna Noise Temperature in Plasma Environment, *M. P. Bachynski, I. P. French, and G. G. Cloutier* ... 1846
Generalized Appleton-Hartree Equation for Any Degree of Ionization and Application to the Ionosphere, *I. P. Shkarofsky* ... 1857
The Electrical Conductivity of a Partially Ionized Gas, *Dipak L. Sengupta* ... 1872
Interaction of Microwaves in Gaseous Plasmas Immersed in Magnetic Fields, *K. V. Narasinga Rao, J. T. Verdeyen, and L. Goldstein* ... 1877
Frequency Conversion in a Microwave Discharge, *J. R. Baird and P. D. Coleman* ... 1890
A Plasma Microwave Energy Detector, *R. L. Taylor and S. B. Herskovitz* ... 1901
Interaction of a Modulated Electron Beam with a Plasma, *G. D. Boyd, R. W. Gould, and L. M. Field* ... 1906
A Method of Measurement of Flame Attenuation at 200 Mc, *Albert W. Biggs* ... 1917
Electrical Characteristics of a Penning Discharge, *J. C. Helmer and R. L. Jepsen* ... 1920
Generation and Application of Highly Ionized Quiescent Cesium Plasma in Steady State, *J. Y. Wada and R. C. Knechtli* ... 1926
A New Approach to Thermionic Energy Conversion: Space Charge Neutralization by an Auxiliary Discharge, *W. Bernstein and R. C. Knechtli* ... 1932
Correspondence:
Stability Criteria for a Tunnel-Diode Amplifier, *H. Boyet, D. Fleri, and C. A. Renton* ... 1937
Discussion of a Deflection System for a Flat Television Picture Tube, *H. Gruenberg and E. G. Ramberg* ... 1938
A Resonant Slot Parametric Amplifier, *J. W. Amoss and G. P. Rodrigue* ... 1939
Low-Frequency Noise in Backward Diodes, *W. C. Follmer* ... 1939
An Extremely Wideband Tunable *S*-Band Parametric Amplifier, *Martin Grace* ... 1940
A Tunnel-Diode Frequency Multiplier with Gain, *F. S. Barnes and L. Morris* ... 1940
Generation of Microwave Harmonics in an Electrodeless Discharge at Low Pressure, *C. B. Swan* ... 1941
A Ruby Laser Exhibiting Periodic Relaxation Oscillations, *R. E. Johnson, W. H. McMahan, F. J. Oharek, and A. P. Sheppard* ... 1942
Broad-Band *S*-Band Parametric Amplifier, *Kenneth M. Johnson* ... 1943
Magnetoresistive Effect as a Possible Memory Device, *C. Pettus and T. Young* ... 1943
A Generalized Hildebrand's Method for Nonuniform Transmission Lines, *Iwao Sugai* ... 1944
The Radar Cross Section of the Moon, *T. B. A. Senior and K. M. Siegel* ... 1944
WWV and WWVH Standard Frequency and Time Transmissions, *National Bureau of Standards* ... 1945
Notice of Frequency Adjustment WWV/WWVH ... 1945
Rebuttal to "A Note on Sugai's Class of Solutions to Riccati's Equation," *Iwao Sugai* ... 1946
On the Hues Seen in Fox-Color Images, *C. Burckhardt and M. J. O. Strutt* ... 1946
A Stability Test for Linear Discrete Systems in Table Form, *E. I. Jury and J. Blanchard* ... 1947
A Stability Test for Linear Discrete Systems Using a Simple Division, *E. I. Jury* ... 1948
Duality of Planar Networks, *J. R. James* ... 1949
Schwarz's Lemma and Linear Passive Systems, *F. M. Reza* ... 1950
Discussion of "Forward Scattering by Coated Objects Illuminated by Short Wavelength Radar," *J. Fisch, K. M. Siegel, and R. E. Hiatt* ... 1951
Inductive Probability as a Criterion for Pattern Recognition, *Bernard Harris* ... 1951
Law for Noise Loading of Multivoice-Channel FD Systems, *C. A. Parry* ... 1952
Reliability Factors in Thermoelectric Generator Design, *M. R. Seiler and T. S. Shilliday* ... 1952
A Proposed Test of the Constancy of the Velocity of Light, *C. K. Gordon, Jr.* ... 1953
Narrow-Band and Wide-Band Noise Figures, *Paul J. Bénéteau* ... 1954
Design of a Helium-Neon Gaseous Optical Maser, *C. F. Luck, R. A. Paananen, and H. Statz* ... 1954
A Critical Note on "Steady-State Analysis of Circuits Containing a Periodically Operated Switch," *J. M. Layton* ... 1955
Cyclic Codes and Transition Coding, *Francis Corr* ... 1956
A Transistor Equivalent Circuit, *Vasil Uzunoglu* ... 1957
A DC Pumped Amplifier with a Two-Dimensional Field Structure, *J. C. Bass* ... 1957

Miniaturized S-Band Isolator, *D. Bruce Swartz* 1958
Pole-Zero Sensitivity Relationships, *W. E. Newell* 1959
A Waveguide In-Line Ferrite Rotary Joint, *H. Saltzman and A. Rossero* 1959
Signal-to-Noise Ratios in Photoelectric Mixing, *B. M. Oliver* 1960
Efficiency of Frequency Multipliers Using Charge-Storage Effect, *D. J. Roulston* 1961
Transistor Storage Time in Circuits with Speed-Up Capacitors, *R. P. Nanavati and R. J. Wilfinger* 1962
Improvement in the Performance of an Automatic Noise Figure Meter with a Liquid-Nitrogen-Cooled Termination, *C. T. Stelzried* 1963
A Tunnel-Diode Wide-Band Frequency Doubling Circuit, *Frank D. Neu* 1963
A Note on Antenna Breakdown, *E. L. Tarca* 1964
Contributors 1965
Books:
"Satellite Environment Handbook," Francis S. Johnson, Ed., *Reviewed by M. G. Morgan* 1970
"Handbook of Thermophysical Properties of Solid Materials, Vol. IV," A. Goldsmith, T. E. Waterman, and H. J. Hirschhorn, Eds., *Reviewed by James G. Harper* 1970
"Static Relays for Electronic Circuits," Richard F. Blake, Ed., *Reviewed by R. P. Burr* 1971
"Thermoelectricity: Science and Engineering," by R. R. Heikes and R. W. Ure, *Reviewed by W. H. Clingman* 1971
"Transistors and Active Circuits," by J. G. Linvill and J. F. Gibbons, *Reviewed by Victor H. Grinich* 1971
Recent Books 1971
Scanning the TRANSACTIONS 1972
Abstracts of IRE TRANSACTIONS 1973
Abstracts and References 1979
1961 PROCEEDINGS OF THE IRE INDEX ..... *Follows page* 1994
1961 IRE INTERNATIONAL CONVENTION RECORD INDEX ..... *Follows page* IRE INDEX 24

INDEX TO AUTHORS

Listings are by month and page, and include authors of papers, authors of correspondence items (C), and reviewers of books (B).

A

Aaron, M. R. (B) Aug 1345
Abeyta, I. Jan 128
Abramson, N. (B) Apr 853, (B) Sep 1459
Adey, A. W. (C) Jun 1089
Adler, R. (C) Apr 802, (C) Apr 804
Adler, R. B. Apr 725
Aein, J. (C) Jan 366
Aiken, W. R. Oct 1550
Aitchison, R. E. (C) Nov 1707
Albrecht, H. J. (C) Jan 356
Allegretti, J. (C) Jun 1087
Almeleh, N. (C) Sep 1448
Amoss, J. W. (C) Dec 1939
Anderson, A. H. Jan 155
Anderson, D. R. (C) Jan 357
Anderson, L. I. (C) Mar 645
Anderson, L. J. (C) May 959
Anderson, R. E. (C) Jun 1081
Ando, S. (C) Mar 643, (C) Jul 1220
Angelakos, D. J. (B) May 981
Angell, J. B. Apr 725
Arams, F. R. (C) Jun 1078, Aug 1308, (C) Sep 1426
Arditi, M. (B) Apr 852
Arendt, P. R. (C) Nov 1698
Aron, R. (C) Jan 355
Ashkin, A. Jun 1016
Atwater, H. A. (C) Sep 1440
Auerbach, I. L. Jan 330, Jun 1065

B

Bachynski, M. P. (C) Jan 354; Dec 1751, 1846
Bacon, G. C. Jan 258
Bahret, W. F. (C) Nov 1692
Bair, M. E. Apr 768
Baird, J. R. Dec 1890
Baldwin, L. D. (C) Jun 1075
Baldwin, M. W., Jr. (B) Mar 692
Banerji, R. B. (C) Oct 1585
Barnes, C. W. (B) Aug 1344
Barnes, F. S. (C) Aug 1328, (C) Dec 1940
Barrow, B. B. (C) Jan 367, Jun 1008
Bass, J. C. (C) Sep 1424, (C) Dec 1957
Batcher, R. R. (B) Feb 533, (C) Mar 640
Bates, H. F. (C) Jan 369
Bauer, L. H. (C) Mar 634
Bauer, W. F. Jan 296
Bechmann, R. (C) Feb 523, (C) Sep 1454
Beck, E. R., Jr. Jan 136
Beckman, F. S. Jan 53
Beeson, R. H. (C) Apr 825
Begun, S. J. Feb 498, (B) Sep 1459
Bell, R. L. (C) Jan 378
Benanti, M. May 928
Bénéteau, P. J. (C) Nov 1699, (C) Dec 1954
Benjamin, R. May 928, (C) Nov 1683
Bennett, W. R. (B) Mar 692
Berkner, L. V. (C) Feb 526, Dec 1743
Bernstein, W. Dec 1932
Bevc, V. (C) Apr 815
Bevensee, R. M. (C) Mar 630
Bhaduri, R. (C) Jan 370
Bharat, R. (C) Sep 1448
Biard, J. R. (C) Nov 1679
Bibl, K. (C) Jan 369
Bickart, C. Jun 1028
Biernson, G. A. (B) May 980
Biggs, A. W. Dec 1917
Bird, L. E. (C) Mar 631
Birdsall, C. K. (C) Apr 819, (C) Nov 1686
Birnbaum, G. (C) Mar 625
Birnbaum, M. (C) Sep 1426
Blachman, N. M. (C) Jun 1088, (C) Aug 1331
Blake, L. V. (C) Oct 1568
Blanchard, J. (C) Dec 1947
Blicher, A. (C) Sep 1427, (C) Sep 1428
Bloch, A. (C) Feb 524
Bloembergen, N. (B) Jan 389
Blötekjaer, K. (C) Feb 516
Bobeck, A. H. (B) Oct 1592
Bogle, G. S. Mar 573
Bohn, E. V. (C) Jan 358, (C) Jul 1215
Bolgiano, L. P., Jr. (C) Apr 813
Bolgiano, R., Jr. (B) Oct 1590
Bolinder, E. F. (C) Feb 514, (C) Mar 635, (B) May 980
Bonin, E. L. (C) Nov 1679
Bonn, T. H. (B) Jan 392
Borgini, F. Jan 128
Bosch, B. G. (C) Jul 1226
Boyd, G. D. Dec 1906
Boyet, J. (C) Dec 1937
Boyle, W. S. Nov 1635
Brain, A. E. Jan 49, (C) Aug 1316
Brand, F. A. (C) Feb 509, May 928, (C) Nov 1683
Breitzer, D. I. Feb 498
Brett, H. (C) Feb 509
Brewer, G. R. Dec 1789
Bridges, J. E. Feb 469
Brito-Infante, J. M. (C) Sep 1451
Brooks, F. P., Jr. Jan 53
Broussaud, G. (C) Feb 515
Brown, D. T. Jan 228
Brown, F. M. (C) Nov 1696
Brown, F. W. (C) Feb 520
Brown, J. (C) Jan 362, (C) Apr 825, (C) Oct 1575
Browne, S. D. (B) Aug 1347
Bruene, W. B. (B) May 982
Buehler, G. V. (C) Feb 518
Bullis, W. M. (B) Aug 1346
Burkchardt, C. (C) Dec 1946
Burford, T. M. (B) Mar 690
Burhans, R. W. (C) Sep 1447
Burns, L. L. (B) Feb 533
Burr, R. P. (B) Apr 854, (B) Dec 1971
Burrus, C. A. (C) Jun 1075, 1101
Burson, F. L. (C) Apr 836
Buscher, R. G. (B) Jul 1233
Bussgang, J. J. Jan 329
Byrne, C. J. (C) Jul 1209

C

Capon, J. (C) Nov 1707
Carlin, H. J. May 907, (C) Nov 1687
Carnahan, C. W. (B) Sep 1458, (C) Oct 1576
Carr, W. N. (C) Jul 1204, 1225
Chaffee, D. E. (C) Nov 1686
Chakrabarti, N. B. (C) Jun 1094
Chang, N. C. (C) Mar 637
Cheng, T. H. (C) Apr 827
Cherry, E. M. (C) Apr 830
Chin, T. N. (C) Apr 832
Chirlian, P. M. (C) Jan 373, (C) Aug 1326, (C) Sep 1434, (C) Oct 1574
Cho, Y. (C) Mar 636, May 974
Choksy, N. H. (B) Apr 853
Chow, C. K. (C) Jan 370
Christensen, B. (C) Oct 1581
Christian, J. R. (C) Nov 1679
Ciftan, M. (C) May 960
Clark, M. A. (B) Nov 1712
Clark, R. B. (C) Nov 1697
Clavier, P. A. (C) Jun 1083, (C) Jul 1209, (C) Aug 1335, (C) Sep 1438, (C) Oct 1580
Clingman, W. H. Jul 1155, (B) Dec 1971
Clorfeine, A. S. (C) Sep 1425
Cloutier, G. G. Dec 1846
Cohen, M. L. (C) Jan 371
Cohn, S. B. (B) Mar 690, (B) Nov 1713
Coleman, P. D. (C) Jun 1084, (C) 1317, Dec 1890
Coll, D. C. (C) Jul 1230
Collier, R. J. (C) Jan 372, (C) Mar 646
Comstock, W. D. (C) Nov 1697
Cook, C. E. (C) Apr 831
Cook, J. C. (C) Oct 1570
Cook, J. J. Apr 768
Cook, J. S. Apr 739
Cooke, H. F. (C) Mar 648
Corr, F. (C) Aug 1337, (C) Dec 1956
Cote, A. J., Jr. (C) Sep 1430
Couch, R. W. (C) Aug 1338
Crawford, F. W. Dec 1767
Crepeau, P. J. (C) Feb 525, (C) Nov 1686
Crosby, D. R. Jan 128, 146
Cross, L. G. Apr 768
Crowther, T. S. Jan 155
Culpepper, T. W. (B) Jul 1233
Currie, M. R. Dec 1789
Custin, T. G. (C) Oct 1574

D

David, E. E., Jr. Jan 319, Jun 1020
Davidsohn, U. S. (C) Jan 372
Davies, L. E. (C) May 971
Day, H. M. (C) Aug 1333
Day, J. W. B. (C) Mar 631
Day, W. R., Jr. (C) Sep 1449
de Jager, J. T. (C) Jul 1205
Dermit, G. (C) Feb 519, Jun 1033
Derr, V. E. (C) Jan 377
Deschamps, G. A. (C) May 962, (B) Oct 1592
Desmares, P. (C) Oct 1582
Desoer, C. A. (B) Jun 1109
Deutsch, J. (C) Sep 1443
DeVore, L. T. (B) Jul 1237
Diamond, J. Jul 1195
Dickson, W. L. (C) Nov 1696
Dietrich, A. F. (C) May 972
Dietz, J. H. (C) Jun 1098
DeFranco, J. V. (C) Jun 1086, (C) Sep 1432
Dill, H. G. (C) Jun 1093
Dimond, R. H. Mar 621
Djurić, J. (C) Nov 1689, 1690
Doba, S., Jr. (C) Mar 631
Doherty, R. H. Nov 1659
Dorato, P. (C) Mar 631
Doviak, R. J. (C) Jul 1222
Dow, D. G. (C) Apr 837, Dec 1747
Dyke, E. (C) Apr 814
Dyson, J. D. (C) Apr 824

E

Eaglesfield, C. C. (C) Apr 810
Early, J. M. Apr 725
Ebert, I. O. (B) Mar 691, (B) Sep 1459
Edmondson, D. E. Feb 453
Edson, W. A. Jun 1021
Edwards, H. H. (C) Aug 1318
Eikenberg, A. F. (C) Feb 518
Ekiss, J. A. (C) Jul 1216
Elco, R. A. (C) Mar 624
Endresen, K. Oct 1561
Espersen, G. A. (B) Sep 1460

F

Faran, J. J., Jr. (C) Apr 834
Feist, W. M. (C) May 975
Ferger, F. A. (C) Aug 1332
Ferris, C. D. (C) Apr 827
Field, L. M. Dec 1906
Findlay, J. W. (C) Jul 1220
Finzi, L. A. Apr 779
Fisch, J. (C) Dec 1951
Fleming, P. L. (C) Nov 1690
Fleri, D. (C) Dec 1937
Flowerday, T. W. (C) Aug 1315
Follmer, W. C. (C) Dec 1939
Fontaine, A. B. Jun 1059
Forward, R. L. May 892, (C) Sep 1442
Franks, R. E. (C) Jan 378
Frederick, N. V. (C) Sep 1449
Freiman, C. V. Jan 91, Nov 1634
French, I. P. Dec 1846
Fresh, D. L. (B) Jul 1233
Freundlich, M. M. Feb 498
Friedland, B. (B) Jun 1110
Frost, E. (C) Nov 1684
Fuller, G. (C) Nov 1689

G

Gadsden, C. P. (C) Apr 827, 833
Gallager, R. G. Jun 1059
Gallagher, J. J. (C) Jan 377
Galvin, A. A. Sep 1417
Gamba, A. (C) Jan 349
Gambling, W. A. (C) Jul 1226
Garbacz, R. J. Jul 1184
Gärtner, W. W. Apr 754, Aug 1268
Gehman, J. B. Feb 498
Geller, S. B. (C) Apr 803
Gerber, E. A. Nov 1650
Gerlough, D. L. Jan 296
Gerritsen, H. J. (C) Aug 1329
Gerst, I. Jul 1195, Nov 1639

Giacoletto, L. J. (C) Feb 510, May 921
Gibbons, J. F. Sep 1383
Gibson, J. E. (C) Aug 1321
Gilden, M. (C) Apr 833
Gilmour, A. S., Jr. (C) May 976
Giordano, A. B. (B) Jul 1234
Glendinning, W. (C) Jun 1087
Glicksman, R. (C) Sep 1428
Golay, M. J. E. (C) May 958, 959; Sep 1378
Golden, R. M. (C) Jun 1094
Goldstein, A. J. (C) Jul 1209
Goldstein, L. Dec 1877
Goodman, J. W. (C) Jun 1084
Gordon, C. K., Jr. (C) Dec 1953
Gordon, E. I. (C) Jul 1208
Gorton, H. C. (C) Aug 1326
Gottschalk, W. M. (C) Apr 813
Goubau, G. (C) Nov 1679
Gould, R. W. Dec 1906
Grabowski, K. (C) Oct 1573
Grace, M. Aug 1308, (C) Dec 1940
Granholm, J. W. Jan 296
Greene, J. C. (C) Jan 350, (C) Mar 626, (C) Apr 804, (C) Jul 1223
Griffith, P. G. (C) Apr 816
Grow, R. W. (C) Nov 1696
Gruenberg, H. (C) Dec 1938
Guckel, H. (C) Nov 1685
Guier, W. H. (C) Nov 1680
Gummel, H. K. (C) Apr 834

H

Haidemenakis, E. D. (C) Sep 1448
Hakki, B. W. (C) Mar 626, (C) Jun 1084, (C) Aug 1334
Halligan, J. W. (C) Jul 1216
Hamann, D. R. May 904
Hammond, J. L., Jr. (C) Jan 375, (C) Nov 1701
Hansen, R. C. Jun 1066, (C) Aug 1340
Hansucker, R. D. (C) Jan 369
Harbourt, C. O. (C) Jan 373
Harley, T. P. Dec 1822
Harmon, L. D. (C) Aug 1316
Harper, J. G. (B) Dec 1970
Harris, B. (C) Dec 1951
Harrison, G. R. (C) Oct 1575
Hartman, W. J. (C) Mar 637
Haskell, R. E. (C) Oct 1584
Hauer, W. (C) Feb 519
Haus, H. A. (B) Aug 1348
Haviland, R. P. (C) Nov 1694
Haviland, R. T. (B) Aug 1345
Hawkins, J. K. Jan 31
Haynes, M. K. Jan 245
Hayre, H. S. (C) Sep 1433
Hazony, D. (C) Sep 1431
Hechtel, J. R. May 933
Hedderly, D. L. (C) May 966
Hedemark, R. Oct 1561
Heffner, H. (B) Feb 535
Hefley, G. Nov 1659
Hefni, I. (C) Sep 1427
Heilmeier, G. H. (C) Jun 1079
Heilprin, L. B. (B) May 981
Heiman, F. P. (C) Jul 1215
Heizman, C. L. (C) Apr 829
Helgesson, A. L. (C) Oct 1569
Helmer, J. C. Oct 1528, Dec 1920
Herman, F. (B) May 981, (B) Oct 1591
Herndon, T. O. Jan 155
Herold, E. W. Dec 1747
Herskovitz, S. B. Dec 1901
Hiatt, R. E. (C) Mar 646, (C) Dec 1951
Hill, W. R. (B) Aug 1346
Hiller, G. (C) Apr 807
Hoaglund, A. S. Jan 258
Hock, D. C. (C) Jan 381
Hodara, H. Dec 1825
Hoeppner, C. H. (B) Oct 1591
Hollis, R. (C) Oct 1579
Holonyak, N., Jr. (B) Oct 1590
Holt, E. H. (C) Oct 1584
Hopkins, R. U. F. Apr 788
Horgan, J. D. (C) Jun 1076
Horowitz, P. Jan 185
Horwitz, L. P. Jan 175
Howden, P. F. (C) Sep 1443
Hsu, H. (C) Aug 1339
Hu, M.-K. (C) Sep 1428
Huang, J. S. T. (C) Mar 638
Huggins, W. H. (B) Nov 1714

I

Ingalls, R. P. (C) Mar 631
Ireland, G. C. Nov 1674
Irland, E. A. Jan 236
Ishii, K. (C) May 975, (C) Jun 1076
Itzkan, I. (C) Feb 525, (C) Nov 1686
Izumi, I. (C) Aug 1313

J

Jacobs, H. May 928, (C) Sep 1440, (C) Nov 1683
Jaffe, B. Aug 1264
James, J. R. (C) Dec 1949
Jasinski, W. (C) Apr 807
Jaumot, F. E., Jr. (B) Jan 390
Jepsen, R. L. Dec 1920
Johansen, D. E. (C) Feb 513
Johnson, C. C. (C) Nov 1696
Johnson, K. M. (C) Dec 1943
Johnson, L. F. (C) Nov 1704
Johnson, R. E. (C) Jan 377, (C) Dec 1942
Johnson, R. S. (C) Jan 375
Johnson, R. W. (C) Aug 1319
Johnston, T. W. (C) Jan 354
Jones, J. P. (C) Sep 1437
Jordan, E. C. (B) Feb 534, (B) Nov 1713
Jurenko, J. A., Jr. (C) Apr 836
Jurkus, A. (C) Sep 1433
Jury, E. I. (C) Dec 1947, 1948

K

Kaenel, R. A. (C) Mar 622, (C) Sep 1445
Kahn, L. R. Oct 1503
Kahn, W. K. (C) Nov 1699
Kain, R. Y. (C) Jun 1085
Kalish, I. H. (C) Sep 1427
Kaltmann, H. E. (C) Jul 1228
Kamal, A. K. (C) Aug 1331
Kamm, V. C. Jan 136
Karew, J. J. (B) Aug 1343
Karni, S. (C) Apr 808
Karplus, W. J. Jan 268
Katzman, M. (C) Nov 1684
Kaupp, H. R. Jan 146
Kelly, P. M. (B) Feb 533
Kennaugh, E. M. (C) Jan 380
Kibler, L. U. (C) Jul 1204
Kiely, D. G. (C) May 966
Kim, W. H. (B) Jan 389
Kinnen, E. (C) Mar 641
Kino, G. S. Dec 1767
Kisliuk, P. P. Nov 1635
Kitsopoulos, S. C. (C) Jun 1076
Klein, M. (C) Nov 1708
Kline, M. (B) Jan 390
Kliphuis, J. (C) May 961
Knapp, C. H. (C) Jan 380
Knechtli, R. C. Dec 1789, 1926, 1932
Ko, H. C. (C) Sep 1446
Koike, Y. (C) Feb 525
Korpel, A. (C) Oct 1582
Koshiga, F. (C) Jul 1218
Kounosu, S. (C) Sep 1445
Kraus, J. D. (C) Jan 363
Kretzmer, E. R. (C) Jun 1076
Krumme, H. J. (C) Aug 1334
Ku, T. C. (C) Aug 1337
Ku, Y. H. (C) Jun 1096, 1097, 1098
Kuh, E. S. Jun 1043, (C) Nov 1687
Kulp, B. A. (C) Sep 1437
Kumagai, Y. (C) Feb 525
Kurokawa, K. Sep 1391
Kyhl, R. L. (C) Feb 519, (C) Nov 1699

L

Lafferty, J. M. Jul 1136
La Frenais, N. D. (C) Aug 1325
Laikin, M. (C) Mar 646
Lally, P. M. (C) Feb 514
Lamb, J. J. (B) Sep 1461
Larson, H. T. Jan 4
Lavi, A. Apr 779
Lawhorn, R. (C) Nov 1704
Lawless, W. J., Jr. Jan 53
Layton, J. M. (C) Dec 1955
Leadabrand, R. L. (C) Mar 639
Lee, C. A. (C) Nov 1695
Leeson, D. B. (C) Jan 351
Lehrer, N. H. Mar 567
Lehman, A. (C) Aug 1339
Lendaris, G. G. (C) Nov 1709
Leondes, C. T. (B) Mar 690
Levi, R. (C) Aug 1323
Lewis, D. J. (C) Jul 1222
Lewis, J. K. Feb 498
Lewis, T. B. Jan 313
Lindmayer, J. (C) Aug 1335
Linfield, R. F. Nov 1659
Lippel, B. (B) Jan 391
Little, A. G. (C) Apr 821
Liu, B. (B) Oct 1591
Lo, S.-F. (C) Nov 1688
Lockwood, H. (C) Feb 519
Loewe, R. T. Jan 185
Logan, J. S. (C) Apr 832
Lombardini, P. P. (C) Jul 1222
Long, M. W. Jun 1024
Looney, C. H., Jr. Feb 448
Lorens, C. S. (C) Nov 1708
Low, P. R. Jan 221
Lucas, M. S. P. (C) Nov 1681
Lucas, W. J. (C) Aug 1325
Luck, C. F. (C) May 960, (C) Dec 1954
Lynch, J. T. (B) Aug 1343

M

Macdonald, J. R. Feb 453
MacCarthy, H. N. (C) Mar 640
Macpherson, A. C. (C) Aug 1314, 1333
MacSorley, O. L. Jan 67
Magill, D. T. Sep 1403
Maier, H. G. (C) Sep 1443
Makris, J. (C) Mar 632
Maley, G. A. Jan 221
Malik, S. (C) Jan 370
Mallory, W. R. (C) Nov 1692
Manamon, L. H. (C) Nov 1698
Mantek, P. A. (C) Apr 803
Marcuse, D. (C) Nov 1706
Marsocci, V. A. (C) Aug 1326, (C) Oct 1574
Martlett, C. (C) Jun 1087
Marutake, M. (C) May 967
Matthaei, G. L. (C) Apr 833, (C) Nov 1703
Matthei, W. G. (C) Feb 509
Matty, T. C. (C) Jul 1225
May, J. E., Jr. (B) Sep 1458
Mayes, P. E. (C) May 962
Mayo, B. R. (C) Apr 817
McDade, J. C. (C) May 957
McFarlan, R. L. Sep 1376
McKibbin, D. D. (C) Aug 1315
McMahan, W. H. (C) Dec 1942
McMillan, F. N. (C) Jan 381
McMurtrey, A. W. (C) Nov 1702
Medved, D. B. (C) Jun 1077
Mehl, W. (B) Jan 389
Meindl, J. D. (C) Apr 816, May 928, (C) Nov 1683
Melehy, M. A. (C) Sep 1424
Melngailis, I. (C) Jan 352, Nov 1616
Meltzer, S. A. Feb 479, Aug 1299, Oct 1573
Meyers, N. H. Nov 1640
Miessner, B. F. (C) Jun 1089, (C) Nov 1697
Mikulski, J. J. (C) Jan 361
Miles, M. H. Nov 1650
Milnes, A. G. (C) Jul 1204, Nov 1616
Minsky, M. Jan 8
Minton, R. M. (C) Sep 1428
Moffatt, D. L. Jul 1184
Montgomery, G. F. (C) Jul 1214
Montgomery, M. D. (C) Apr 826
Moody, N. F. (C) Apr 835
Moore, J. W. (C) Oct 1578
Morgan, M. G. (B) Aug 1347, (B) Dec 1970
Morgan, M. L. Jan 276
Morris, L. (C) Dec 1940
Morse, J. H. (C) Oct 1571
Mostov, P. M. May 941
Mueller, G. E. (B) Mar 691
Mueller, W. M. (C) Mar 642
Muller, M. W. (C) May 957
Mullin, A. A. (C) Feb 526
Mumford, W. W. Feb 427
Murcray, W. B. (C) Apr 811
Muroga, S. (C) 1455
Mydosh, J. A. (C) Sep 1448

N

Nagumo, J. Aug 1281
Nain, H. J. (C) Sep 1431
Nanavati, R. P. (C) Jan 349, (C) Dec 1962
Narasinga Rao, K. V. Dec 1877
Narken, B. (C) Sep 1438
Nassau, K. (C) Nov 1704
Nathan, A. (C) Sep 1431, (C) Oct 1577
Nee, J. (C) Mar 624
Nelson, D. E. Apr 744, (C) Nov 1689
Nergaard, L. S. (C) Jan 350, (C) Mar 622
Nesbeda, P. Jan 329
Neu, F. D. (C) 1963
Neuringer, J. L. May 941
Newcomb, R. W. (C) Oct 1585
Newell, W. E. (C) Dec 1959
Newhouse, V. L. (C) Aug 1318
Nilssen, O. K. (C) May 964, (C) Jul 1222
Norton, R. H. Nov 1655
Nussbaum, E. Jan 236

O

O'Connel, J. A. (C) Sep 1438
Ogawa, T. (C) Mar 643, (C) Jul 1220
Oharek, F. J. (C) Dec 1942
Okaya, A. (C) Jun 1083
Okwit, S. (C) Jun 1078, (C) Jul 1210, Aug 1308
Oliver, B. M. (C) Dec 1960
Olson, F. A. (C) Mar 629, (C) Jul 1230
Olthuis, R. W. May 949
O'Neill, G. D. (C) Nov 1695
Orchard-Hays, W. Jan 283
Ordung, P. F. (B) Jul 1237
Ortwein, N. R. Apr 788
Owen, H. A. (C) Nov 1681
Owren, L. (C) Jan 369

P

Paananen, R. A. (C) Dec 1954
Padgitt, H. R. (C) Apr 836
Pany, F. G. (C) Oct 1570
Papas, C. H. (B) Aug 1344
Parry, C. A. (C) Dec 1952
Patterson, J. D. Jun 1043, (C) Nov 1687
Patton, W. T. (C) May 962
Pearson, R. T. Jan 164
Pease, M. C. Jan 488
Peatman, J. B. (C) Jul 1229
Pedinoff, M. E. (C) Aug 1315
Pelchat, M. G. (C) Apr 822
Penstone, S. R. (C) Jun 1089
Peterson, A. P. G. (B) Jan 390
Peterson, D. G. (C) Jul 1225
Peterson, W. W. Jan 228
Pettus, C. (C) Dec 1943
Piattelli, M. (C) Sep 1435
Pierce, J. N. (C) Jan 363
Piggott, W. R. (C) May 965
Pohl, J. E. Apr 788
Polk, C. (C) Apr 817
Pope, J. H. (C) Apr 811
Porsche, H. (C) Oct 1582
Prasanna-Kumar, K. S. (C) Aug 1321
Presser, A. (C) Aug 1318, (C) Oct 1572
Pritchard, R. L. Apr 725
Prugh, R. A. (B) Aug 1343
Pucel, R. A. (C) Jun 1080, (C) Aug 1340
Pulfer, J. K. (C) Mar 644, (C) May 968
Pulvari, C. F. (B) Aug 1347
Pungs, L. (C) Jan 378

R

Rabinovici, B. (C) Jul 1213
Raffel, J. I. Jan 155
Rajchman, J. A. Jan 104
Ramberg, E. G. (C) Dec 1938
Ramp, H. O. (C) Nov 1693
Raphelson, M. (B) Jul 1234
Rapier, P. M. (C) Aug 1322, (C) Nov 1691
Rashid, A. F. (C) Aug 1338
Rawer, K. (C) May 968, (C) Oct 1582
Rayfield, G. W. (C) Apr 819
Reber, G. (C) Feb 529
Rebsch, D. L. (C) Mar 644
Reder, F. H. Jun 1028
Redlich, R. W. (C) Oct 1580
Reed, J. (C) Feb 519
Reiling, G. H. (B) Feb 536

Renton, C. A. (C) Jul 1213, (C) Dec 1937
Rey, T. J. Mar 590
Reza, F. M. (C) Nov 1693, (C) Dec 1950
Rhoades, W. T. (C) Nov 1691
Rhodes, D. R. (C) Jan 376
Ribbens, W. B. (C) Nov 1700
Richardson, J. M. (B) Jun 1108
Rigney, D. S. May 941
Rihaczek, A. W. (C) Apr 822
Rittner, E. S. (C) Aug 1323
Rivers, W. K., Jr. Jun 1024
Roberts, R. W. (C) May 963
Robinson, B. J. (C) Jul 1205
Robson, P. N. (C) Mar 645, (C) Sep 1433
Rodrigue, G. P. (C) Dec 1939
Rogers, W. M., Jr. (C) Oct 1573
Rosenblatt, F. (B) Jun 1108
Rossero, A. (C) Dec 1959
Rossol, F. C. (C) Oct 1574
Roth, A. (C) Sep 1437
Rothschild, D. R. (C) Mar 649
Roulston, D. J. (C) Dec 1961
Rowen, J. H. (B) Jun 1108
Rowley, J. J. (C) Jan 364
Rubin, M. D. (C) Aug 1327
Rubin, W. L. (C) Sep 1432
Ruchkin, D. S. (C) Sep 1436
Ruderfer, M. (C) Mar 630
Russell, F. A. (B) Jan 392
Ruthroff, C. L. (C) Jun 1091
Ryan, W. D. (C) Jun 1081

S

Saari, V. R. (B) Apr 852
Saaty, T. L. (C) Jun 1095
Sabisky, E. S. (C) Aug 1329
Safran, H. Jan 329
Sah, C. T. Mar 603, Nov 1623
Saito, S. (C) Mar 623, (C) May 969
Saito, Y. (C) Feb 528
Salton, G. (B) Apr 853, (B) Sep 1460
Saltzman, H. (C) Dec 1959
Salz, J. (C) Jan 366
Sann, K. H. (C) Feb 527
Sard, E. W. (C) Jan 350, 355
Savarin, A. (C) Jul 1230
Scarbrough, A. D. (B) Feb 535
Schaefer, D. H. (C) Jul 1219
Schaffner, G. (C) Apr 824
Schatz, E. R. (C) Apr 816
Scheibe, E. H. (C) Jun 1079, (C) Sep 1434
Schelkunoff, S. A. (B) Feb 534
Schlesinger, K. Oct 1538
Schneider, M. V. (C) Jun 1090
Schork, E. L. (C) Sep 1448
Schroeder, M. R. (C) Jun 1094
Schuller, M. Apr 754, Aug 1268
Schwartz, D. B. (C) Jan 366
Schwartz, L. S. (C) Feb 513
Searing, R. M. (C) Mar 640
Seeger, J. A. May 933
Seely, S. (B) Mar 690, (B) Jun 1108
Seiler, M. R. (C) Dec 1952
Selinger, V. H. (C) Jan 356
Sengupta, D. L. Dec 1872
Senior, T. B. A. (C) Dec 1945
Sensiper, S. (C) Apr 810
Serrell, R. (B) Jun 1110
Shafer, C. G. (C) May 960
Shapiro, G. (B) Jun 1109
She, C.-Y. (C) Sep 1450
Shea, R. F. (B) Jan 392, (B) Jul 1235, (B) Aug 1343
Shelton, G. L., Jr. Jan 175
Shepherd, F. D. (C) Sep 1435
Shepherd, G. P. (C) May 966
Sheppard, A. P. (C) Jan 377, (C) Dec 1942
Sherman, J. E. (B) Jul 1235
Shilliday, T. S. (C) Dec 1952
Shimada, K. (C) Mar 632
Shimura, M. Aug 1281
Shkarofsky, I. P. (C) Jan 354, Dec 1857
Shombert, D. (C) Jun 1087
Short, R. A. (B) Sep 1458
Siegel, K. M. (C) Mar 646, (C) Apr 809, (B) Jul 1236, (C) Dec 1945, 1951
Siegman, A. E. (C) Mar 633
Siekanowicz, W. W. Dec 1836
Silver, S. (B) Feb 535
Sims, R. C. Jan 136
Sims, S. D. (C) Aug 1331
Sinclair, G. (B) Nov 1714
Sisson, R. L. Jan 185
Sluss, J. A., Jr. (B) Jul 1236
Smart, R. G. Jun 1051
Smilen, L. I. (C) Jul 1206, (C) Nov 1687
Smith, C. E. (B) Jan 391, (B) Aug 1344
Smith, J. G. (C) Jun 1078, (C) Jul 1210
Soifer, R. (C) Sep 1455
Soohoo, R. F. (B) Apr 852
Spence, R. (C) Aug 1338
Spilker, J. J., Jr. Sep 1403
Spitz, E. (C) Feb 515
Staras, H. (C) Jul 1211
Statz, H. (C) May 960, (C) Aug 1340, (C) Dec 1954
Stelzried, C. T. (C) Apr 812, (C) Jul 1224, (C) Dec 1963
Stern, A. P. (B) Feb 534, (B) Jul 1235
Sterzer, D. (C) Nov 1689
Sterzer, F. Apr 744, (C) Aug 1318, (C) Oct 1572
Stewart, H. A. (C) Nov 1681
Stewart, J. L. (C) Feb 521
Stewart, R. M. (C) Aug 1322
Stickler, D. C. (C) Aug 1320
Stitch, M. L. (C) Oct 1571
Stockman, H. E. (C) Jan 379, (C) May 970, (C) Oct 1586
Stone, H. A., Jr. Jul 1170
Storke, F. P., Jr. (C) Aug 1328
Straiton, A. W. Jan 220, (C) Mar 649
Stram, O. B. Jan 210
Strutt, M. J. O. (C) Dec 1946
Stull, K. S., Jr. (C) Jan 365
Suchy, K. (C) May 968
Sugai, I. (C) Mar 627, 628, (C) Apr 823; (C) Dec 1944, 1946
Sugano, T. (C) Jul 1218
Sugata, E. (C) Apr 819
Suran, J. J. Feb 420
Susini, A. (C) Aug 1332
Süsskind, C. Oct 1550
Sussman, A. (C) Feb 517
Sutherland, C. W. (C) Feb 519
Swan, C. B. (C) Dec 1941
Swartz, D. B. (C) Dec 1958
Swartz, J. M. (C) Aug 1326
Swenson, G. W., Jr. (B) Jan 391

T

Tai, C. T. (C) Sep 1442
Takács, J. (C) Sep 1446
Talpey, T. E. (C) Jan 376
Tanguay, A. R. (C) Jan 381
Tarca, E. L. (C) 1964
Taylor, L. S. Dec 1831
Taylor, R. L. Dec 1901
Terada, M. (C) Apr 819
Terhune, R. W. Apr 768
Tetenbaum, S. J. (C) Jul 1230
Thaler, S. Feb 479, Aug 1299, (C) Oct 1573
Thiess, G. H. (C) Sep 1439
Thompson, G. B. H. (C) Nov 1684
Tiemann, J. J. (C) Mar 622
Tolbert, C. W. Jan 220, (C) Mar 649
Toman, K. (C) May 971
Tomiyasu, K. (C) Jul 1207
Tompkins, H. E. (B) Apr 854
Tou, J. T. (C) Mar 646
Trambarulo, R. (C) Jun 1075
Truxal, J. G. Jan 305, (B) May 981
Tschauner, J. (C) Sep 1447
Tsu, T. C. (C) Jan 381
Tsui, J. B. Y. (C) May 975, (C) Jun 1076
Turner, E. H. (B) Oct 1591
Tyras, G. Dec 1822

U

Unz, H. (C) Feb 530
Ur, H. (C) Jun 1092
Ura, K. (C) Apr 819
Utsunomiya, T. (C) May 965
Uzunoglu, V. (C) Sep 1440, (C) Dec 1957

V

Vail, C. R. (C) Nov 1681
Vanderslice, T. A. Jul 1136
van der Ziel, A. (C) Jul 1211, 1212
Van Gelder, A., Jr. (C) Aug 1332
Verdeyen, J. T. Dec 1877
Vetter, A. F. (C) Sep 1437
Vincent, B. T., Jr. (C) Feb 511, (C) Nov 1682
Vodicka, V. W. (C) Aug 1335
Von Gutfeld, R. (C) Feb 522
Voorhaar, F. (C) Apr 824

W

Wacker, A. G. (C) Apr 835
Wada, J. Y. Dec 1926
Wade, G. (C) Apr 802, May 880
Wagner, W. G. (C) Mar 625
Wait, J. R. (C) Jun 1089, (B) Jul 1236, (C) Sep 1429, (C) Oct 1576
Waite, A. H., Jr. (C) Sep 1449
Wallace, J. D. (C) Aug 1324
Wang, C. C. (C) Feb 522
Wang, F. F. Y. (C) May 975
Wang, S. (C) Jul 1219
Wanselow, R. D. (C) May 973
Wanuga, S. (C) Aug 1339
Warner, R. M., Jr. Jul 1170
Waterman, A. T., Jr. (C) Sep 1452
Weaver, C. S. (C) Oct 1587, (C) Nov 1704
Webb, E. L. R. (C) May 963
Webster, W. M. Apr 725
Weglein, R. D. (C) Apr 810
Weinreb, S. (C) Jun 1099
Weiss, M. R. (C) Nov 1707
Wessel-Berg, T. (C) Feb 516
Wheeler, G. J. (C) Feb 519
Whetstone, A. L. (C) Sep 1445
Whinnery, J. R. (B) Mar 691
White, R. M. (C) Nov 1686
White, W. D. (C) Apr 804, (B) Nov 1713
Whitford, B. G. (C) May 968
Wickersham, A. F., Jr. (C) Jan 378
Wiel, H. (C) Mar 646
Wier, J. M. Jan 196
Wildey, R. L. Nov 1655
Wilfinger, R. J. (C) Dec 1962
Williams, H. B. (C) Jun 1081
Willoughby, E. O. (C) Oct 1583
Wilmshurst, T. H. (C) Jul 1226
Wilson, B. L. H. (C) Aug 1330
Wilson, R. B. (C) Aug 1330
Winder, R. O. (C) Jun 1100
Wingrove, E. R., Jr. (C) Nov 1693
Winkler, M. R. Jun 1028
Wolf, A. A. (C) Jan 358, (C) Mar 637, (C) Jun 1097, 1098
Wolfe, P. N. (B) Jul 1234
Woodbury, E. J. (C) Oct 1571
Wooding, G. W. H. (C) Nov 1689
Wrigley, C. (C) Aug 1335

Y

Yadavalli, S. (C) Jun 1098
Yamamoto, Y. (C) Feb 522
Yang, A. C. (C) Sep 1435
Yariv, A. Apr 739, (C) Nov 1695
Yee, J. S. Dec 1837
Yoshida, A. (C) Mar 643, (C) Jul 1220
Youla, D. C. May 907; (C) Jul 1206, 1221; (C) Nov 1687
Young, C. E. Jan 236
Young, T. (C) Dec 1943
Yuan, S. (C) May 965

Z

Zadeh, L. A. (C) Sep 1452, Oct 1488, (B) Nov 1712
Zopf, G. W., Jr. (C) Feb 526
Zucker, H. Mar 591
Zuleeg, R. (C) Aug 1335
Zweig, F. (B) Feb 534

INDEX TO SUBJECTS

Listings are by month and page. Authors and paper titles may be determined from the tables of contents in the front part of this index.

A

Absorption, Atmospheric, of Millimetric Waves: Mar 649
Absorption of Waves by Atmospheric Gases, Anomalies in, Correction: Jan 220
Adaptive Communications Filter: Oct 1587
Adaptive System, Model Parameter Controls for: Mar 641
Adder, Full Binary, with One Tunnel Diode: Jul 1213
Adler Tubes, Beam Interception and Limiting Gain in: Feb 516
Algebraic Function Calculations Using Potential Analog Pairs: Jan 276
Allocations, Frequency, for Space Communications: Jun 1009
Altimeters, Operation Over Snow-Covered Ground or Ice: May 965, Sep 1449
Amplification:
  Microwave, in Electrostatic Ring Structures: Sep 1424
  Parametric, by Charge Storage: May 966
  Parametric, in Transistors: Aug 1335
  Parametric, with a Low-Frequency Pump: Jul 1214
Amplifiers:
  Backward Traveling-Wave Parametric, Wide Tuning Range of: Aug 1339
  Beam-Type Parametric, Noise in: Jul 1208
  Broad-Band *S*-Band Parametric: Dec 1943
  Cascaded Tunnel-Diode: Sep 1434
  C-Band Nondegenerate Parametric, with 500-Mc Bandwidth: May 961
  C-Band Parametric, with Large Bandwidth: Nov 1682
Circuits, Nonreciprocal Parametric: Jun 1075
Class-B Transistor, Elimination of Crossover Distortion in: Apr 834
Cyclotron Wave, with Magnetic Pumping: Mar 645
DC Pumped, with a Two-Dimensional Field Structure: Dec 1957
Degenerate Parametric, Sensitivity of: Jul 1205
Distributed Negative-Conductance, Noise Measure of: Jul 1212
Electron Beam Parametric, Kompfner Dip Couplers for: Mar 637
Extremely Wideband Tunable Parametric: Dec 1940
Forward Wave Crossed-Field, Bi-Signal Amplification by: Mar 646

Forward Wave Crossed-Field, Gain Measurements on: Jan 372
Front End, Degenerate Parametric, Radar Sensitivity with: Apr 804
High-Performance *X*-Band Parametric: Feb 511
Hybrid Coupled Negative-Resistance, Noise Considerations for: Mar 626
Hybrid-Coupled Tunnel Diode, Noise Performance and Stability of: May 975
Infinite-Gain Operational, Matrix Analysis of Networks Having: Oct 1577
K_a-Band Ferrite: May 963
L-Band Traveling-Wave Parametric: Jul 1230
Light, Pulsed Ruby Maser as: Nov 1635
Linear, Actual Noise Measure of: Sep 1391
Low-Noise, for Centimeter and Shorter Wavelengths: May 880
Low-Noise Microwave Quadrupole: Jul 1016
Matched, Using Two Cascaded Tunnel Diodes: May 904
Millimeter-Wave Tunnel Diode: Jun 1075
Moving in Space, Stability Criterion for: Jan 379
Nearly Optimum Wide-Band Degenerate Parametric: Apr 833
Negative Conductance, Noise Figure and Stability of: Aug 1314
Negative-Conductance, Noise Figure of: Feb 520
Negative-Conductance, Transmission Line Parameters: Apr 812
Negative Resistance, Gain Bandwidth Relations in: Jan 355
New Microwave Power: Jun 1083
Noise, Zero-Point Energy as the Source of: Mar 633
Nondegenerated *S*-Band Parametric, with Wide Bandwidth: Apr 824
Optimum Negative-Resistance: Jun 1043, Nov 1687
Parametric, Lossy Coupling in: Oct 1573
Parametric, Reactance Tube as: Mar 624
Quadrupole, Thermal and Beam Noise in: Apr 802
Resonant Slot Parametric: Dec 1939
Stable Parametric: Mar 629
Stages, Lossy Tunnel-Diode Noise Measure of: Jul 1211
Transistor, Average and Spot Noise Figure in: Jul 1215, Nov 1699
Transistor Feedback, Mismatched Interconnection of: Apr 830
Traveling-Wave Parametric, Analysis: Mar 591
Traveling-Wave Parametric, Gain Saturation in: Sep 1433
Traveling-Wave, Solid-State Analog to: Jun 1079
Tunnel Diode:
Broad-Band: Apr 835
Cascading: Jan 373
Gain vs Bandwidth Limits for: Apr 832
Microwave, Noise Investigation of: Apr 739
Shot Noise in: Jan 350, Mar 622
Slot Transmission: Aug 1315
Stability Criteria for: Dec 1937
Unidirectional Lower Sideband Parametric: Nov 1684
Varactor Diode Parametric Standing-Wave: Feb 509
Variable Dual Reactance Traveling-Wave Parametric: May 973
Wide-Band Single-Diode Parametric, Using Filter Techniques: Apr 821
Amplitude and Phase Modulation, Combined, for a One-Sided Spectrum, Discussion: Jun 1094
Amplitude Modulating a Van Atta Radar Reflector: Mar 634, Nov 1692
Angle Modulation, Superposition Property of: Jun 1084
Antennas:
and Receiving-System Noise-Temperature Calculation: Oct 1568
Aperture, Transient Behavior: Apr 817
Beam Configurations in Scatter Communications: Sep 1452
Breakdown: Dec 1964
Broad-Band, Dispersive Properties of: Mar 644
Broad-Band Spherical Satellite: Apr 824
Cross, History: Feb 529
Endfire: Feb 515
Frequency-Independent, Backward-Wave Radiation and the Design of: May 962
Noise Temperature in Plasma Environment: Dec 1846
Nondirectional Ferrite Rod, for AM Radios: Jul 1222
Siting Tests on a Tropospheric Scatter Path: Aug 1325
Size for a Space Vehicle: Nov 1708
Tapered Ladder: Jan 377
Techniques for Handling Partially Polarized Waves with Reference to: Sep 1446
Thin Linear, Radiation Resistance of: Jan 370
Antiferroelectric Ceramics with Field-Enforced Transistions: Aug 1264
Antigravity: Sep 1442
Appleton-Hartree Equation for Any Degree of Ionization: Dec 1857
Arrays, Communications Satellites Using: Jun 1066, Aug 1340
Atmospheric Absorption of Millimetric Waves: Mar 649
Atmospheric Gases, Anomalies in the Absorption of Waves by, Correction: Jan 220
Attenuator, *X*-Band Electronically-Variable: Nov 1690
Autocorrelation Pattern Recognition: Jun 1085
Avalanche Effects, Negative Resistance in Transistors Based on Transit-Time and, Correction: Aug 1340
Avalanche Injection, High-Level Microwave Detector Using: Aug 1333
Avalanche Pulse Circuits, New Ways to Trigger: Jun 1093

B

Backscatter Records, Proof of Focusing at the Skip Distance by: Jan 369
Backward Traveling-Wave Parametric Amplifiers, Wide Tuning Range of: Aug 1339
Backward-Wave Oscillator Stabilization: Nov 1697
Backward-Wave Radiation and the Design of Frequency-Independent Antennas: May 962
Balun Solution by a Tapered Potential: Apr 810
Beams:
Frequency Standards, Magnetic Shield for: Aug 1328
Immersed in an Axial Magnetic Field, Small-Signal Space-Charge Density in: Apr 815
Interception and Limiting Gain in Adler Tubes: Feb 516
Noisiness, Reduction by a Potential Minimum Away from Cathode: Mar 642
Prebunched, Coherent Generation of Microwave Power by Annihilation Radiation: Aug 1334
Binary Division Algorithms, Certain, Statistical Analysis: Jan 91, Nov 1634
Binary Error Rates in Fast Fading FDM-FM: Feb 513
Binary Numbers, Logarithmic Compression of: Jul 1219
Binary One-Tunnel-Diode: Sep 1445
Binary Transmission Over Telephone Circuits, Error Statistics and Coding for: Jun 1059
Blackout, Re-Entry Radio, Magnetic Fields in Elimination of: Dec 1825
Bombing, Navigation and Missile Guidance Subsystem, Digital Computer Equipment for: Jan 313
Boolean Functions Realizable in Terms of Threshold Devices: Jan 210
Boolean Functions Realizable with Single Threshold Devices: Jan 370

C

Camera Systems, Measurement of Resolution, IRE Standards: Mar 599
Canada, Ground Conductivity Map for: Nov 1674
Capacitance:
Coefficients for Varactor Diodes: Apr 810
Diodes, Variable, Used as Phase-Shift Devices: Mar 640
Problem, Time-Varying, Exact Solution: Feb 453
Semiconductor Device, Three-Terminal Variable: Feb 510
Tunnel Diode Junction, Measurement: Jan 372
Capacitors:
Charging Efficiency, Optimum, for Space System: May 941
Helix-Type Variable: Feb 522
Motor, Parametric Variable: May 970
Nonlinear, Definitions of Terms, IRE Standards: Aug 1279
Capacity of Continuous Information Channel Corrected for Time or Phase Jitter: Feb 513
Cathodes, Barium-Activated Tungsten Dispenser, Suppression of Emission from: Aug 1323
Cathode Diodes, MgO Cold, Rise-Time Measurements: Feb 517
Cavity Modes in an Optical Maser: Mar 625
Ceramic Magnets, Magnetic Circuits Employing: Oct 1528
Ceramics, Antiferroelectric, with Field-Enforced Transitions: Aug 1264
Ceramics, Piezoelectric, on Measurements, IRE Standards: Jul 1161
Cerenkov Radiation in a Dielectric Tube Waveguide: Jun 1084
Cesium Frequency Stabilizer, Simplifier: Jan 377
Cesium Plasma, Ionized, Generation and Application: Dec 1926
Channel, Continuous Information, Capacity Corrected for Time Phase or Jitter: Feb 513
Charge Storage, Parametric Amplification by: May 966
Circuit, Complete Transistor Equivalent: Apr 825
Circuit Considerations Relating to Microelectronics: Feb 420
Circuit, Tunnel-Diode Wide-Band Frequency Doubling: Dec 1963
Circuits, Microwave Bistable, Using Varactor Diodes: Apr 829
Circulators, Stripline Y, for 100 to 400 Mc: Feb 518
Clock Paradox, Relativity and: Sep 1437
Clock Synchronization Experiment, Long-Range: Jun 1028
Coaxial Lines, Ferrite Loaded, Differential Phase Shifts in: Jan 364
Coaxial Lines, IF, Broad-Band Termination for: Jan 365, Aug 1332
Coaxial Termination, Liquid-Helium-Cooled: Jul 1224
Codes:
Cyclic, and Transition Coding: Dec 1956
Cyclic, for Error Detection: Jan 228
Double-Error Correcting Bose-Ray-Chaudhuri, Decoding Procedure for: Oct 1585
Groups, Convoluted Optimum Finite, Autocorrelation Properties: Jul 1230
Coding, Error Statistics and, for Binary Transmission Over Telephone Circuits: Jun 1059
Coding Scheme, Television, Computer Simulation: Jun 1076
Coherence vs Narrowbandedness in Regenerative Oscillators, Masers, Lasers: May 958
Coincidence Techniques for Radar Receivers Employing a Double-Threshold Detection: Oct 1561
Collector Design, Depressed, Space-Charge Potentials in: Feb 522
Color Images, Fox, Hues Seen in: Jul 1228, Dec 1946
Combined Amplitude and Phase Modulation for a One-Sided Spectrum, Discussion: Jun 1094
Communications:
Engineer, Reflections of a: Sep 1378
Human, Digital Simulation in Research on: Jan 319, Jun 1020
Satellite Supported, at 21 Megacycles: Sep 1455
Single-Sideband: Mar 632
Space, Frequency Allocations for: Jun 1009
Systems, Subsurface: Mar 645
Techniques, Digital Data: Jan 196
Compatible Single Sideband: Oct 1503
Compression, Expansion, and Multiplication, FM-AM Method: Oct 1550
Compression, Logarithmic, of Binary Numbers: Jul 1219
Computers:
Applications, Advanced: Jan 296
Arithmetic and Control Units, Logical Organization of: Jan 53
Binary, High-Speed Arithmetic in: Jan 67
Element, Potential Microwave: Aug 1338
Equipment, Digital, for Bombing, Navigation and Missile Guidance Subsystem: Jan 313
Generated Displays: Jan 185
in Automatic Control Systems: Jan 305
Issue, Introduction: Jan 4
Memories: Jan 104
Simulation of a Television Coding Scheme: Jun 1076
Simulation, Transient Analysis of Cryotron Netowrks by: Jan 245
Subsystem Using Kilomegacycle Subharmonic Oscillators: Jan 128
Conductance Parameters, Tunnel-Diode Measurement: Oct 1581

Conductivity of Partially Ionized Gas: Dec 1872
Control, Automatic Phase, Theory and Design, Correction: Mar 590
Control, Posicast, Analog Study: Sep 1450
Control Systems, Automatic, Computers in: Jan 305
Converters:
Efficiency and Power Output of a Tunnel-Diode Relaxation Oscillator: Jul 1219
Thermoelectric, Equivalent Circuits for: May 963
Tunnel-Diode Down: Jul 1225
Tunnel-Diode Frequency: Aug 1318, Oct 1572
Cosmology and Information Theory: Sep 1378
Counter Circuit, Tunnel-Diode Binary: Jun 1092
Counter, 100-Mc Tunnel-Diode Ring: Jul 1215
Coupler, Gas-Discharge Microwave Power: May 949
Couplers, Kompfner Dip, for Electron Beam Parametric Amplifiers: Mar 637
Coupling Factor, Calculating Electromechanical: May 967
Creativity, Education and: Nov 1697
Cross Antenna, History: Feb 529
Cross-Correlator, Self-Setting: Apr 836
Cryosar, Silicon: Aug 1313
Cryosistor Field-Effect Controlled Impact Ionization Switch: Nov 1616
Cryosistor Three-Terminal Switch: Jan 352
Cryotrons:
Linear Circuit Aspects: Aug 1326
Networks, Transient Analysis by Computer Simulation: Jan 245
Ring Oscillator, 6-Megacycle: Jan 371
Ring Oscillators, Comments: Apr 827
Thin-Film: Aug 1318
Crystals, Microwave Mixer, Excess Noise in: Jul 1226
Crystal Optics, Polarization in Magneto-Plasmas by: Oct 1584
Crystals, Quartz AT-Type Filter, for 0.7 to 60 Mc: Feb 523
Current-Measuring Instruments, Simple, Minimum Reading Times for: Sep 1443
Current Meter, Self-Balancing, and Recorder: Oct 1578
Cyclotron and Synchronous Waves on a Filamentary Electron Beam, Power Carried by: May 969
Cyclotron Radiation Model of VLF Emission, Energy Fluxes from: Apr 811
Cyclotron Wave Amplifier with Magnetic Pumping: Mar 645

D

Data Processing, European: Jan 330, Jun 1065
Data Systems, Multiloop, Multisampler, Variable-Rate Discrete, Output Transforms of: Mar 646
Deflection System for a Flat Television Picture Tube: Dec 1938
Delay-Lock Discriminator: Sep 1403
Delta Function and Fourier Integral: Nov 1702
Describing Function, New RMS, for Single-Valued Nonlinearities: Aug 1321
Detection:
Multiple Burst: Aug 1337
Pseudo-Rectification and, by Bilateral Nonlinear Resistors: Feb 469
Range Predictions for Pulse Doppler Radar: Aug 1299
System, Sequential, for Processing Radar Returns: Sep 1417
Detectors:
High-Level Microwave, Using Avalanche Injection: Aug 1333
Highly Sensitive Microwave, Tunnel Diode as: Apr 826
Pickard's Regenerative: Sep 1447
Plasma Microwave Energy: Dec 1901
Dielectric, *N*-Slab, Reciprocal Relations in: Oct 1579
Digital Computer Equipment for Bombing, Navigation and Missile Guidance Subsystem: Jan 313
Digital Data Communication Techniques: Jan 196
Digital Magnetic Recording Techniques, High-Density: Jan 258
Digital Radiometer: Jun 1099
Digital Simulation in Research on Human Communication: Jan 319, Jun 1020
Digital Techniques, Tunnel-Diode: Jan 136
Diodes:
Available Varactor, Comparative Figures of Merit for: Apr 809
Backward, Low-Frequency Noise in: Dec 1939
Conductivity-Modulated, Base Voltage and Contact Resistance of: Aug 1326
Four-Layer, Minimum Time for Turn-Off in: Sep 1424
High-Speed Silicon Computer, as RF Switches: Nov 1707
Inductive Semiconductor, Three-Layer Negative Resistance and: Apr 754
Junction, Negative Resistances in: Sep 1427
Junction, RF-Induced Negative Resistance in: May 957
Low-Lifetime Germanium, Reverse Characteristics: Sep 1427
MgO Cold Cathode, Rise-Time Measurements: Feb 517
Reverse Characteristics at Low Temperatures: Sep 1425
Varactor, Capacitance Coefficients for: Apr 810
Varactor, Microwave Bistable Circuits Using: Apr 829
Varactor Parametric Standing-Wave Amplifier: Feb 509
Directional Coupler Core of an Arbitrary, Lossless, Reciprocal 4-Port: Nov 1699
Discharges:
Auxiliary, Thermionic Energy Conversion by Space Charge Neutralization: Dec 1932
Electrodeless, Generation of Microwave Harmonics in: Dec 1942
Microwave, Frequency Conversion in: Dec 1890
Penning, Electrical Characteristics of: Dec 1920
Low-Pressure DC, Oscillations and Noise in: Dec 1767
Discriminator, Delay-Lock: Sep 1403
Display, Tracking and, of Satellites: Aug 1332
Displaying Ultra-Fast Limit Cycles or Three-Parameter Trajectories: Nov 1691
Displays, Computer Generated: Jan 185
Distortion, Crossover, Elimination in Class-B Transistor Amplifiers: Apr 834
Distortion, Time-Domain, in Pulsed Systems, Interpretation of Paired Echo Theory for: Sep 1432
Distributed Negative-Conductance Amplifiers, Noise Measure of: Jul 1212
Distributed RC Networks, Shaping of: Aug 1330
Diversity, Multiple, with Nonindependent Fading: Jan 363
Diversity Reception, Translation of a Historic Paper on: Jan 367
Division Algorithms, Binary, Statistical Analysis, Correction: Nov 1634
Doppler Effect and Inertial Systems: May 971
Doppler Effect, Performance Degradation of Pulse-Compression Systems Due to: Nov 1693
Doppler Ionogram, Vertical Incidence: Jul 1220, Mar 643
Doppler Measurements, Optical, for Space Navigation, Limitations: Nov 1655
Doppler Radar, Pulse, Detection Range Prediction for: Aug 1299
Doppler-Shift Effects in Space Propagation: Nov 1694
Doppler Shift from Satellites, Ionospheric Contributions: Nov 1680

E

Echo-Signal Delay, Applying Chordal-Hop Theory of Ionospheric Lond-Range Propagation to: Jan 356
Educated, Are Electronics Engineers?: Aug 1319
Education and Creativity: Nov 1697
Electromagnetic Fields, External, of Shielded Transmission Lines: Apr 816
Electromagnetic Parameters, Representation in Presence of DC Magnetic Fields: Jan 354
Electromagnetic Phenomena, Extension of Newtonian Relativity to Include: Nov 1691
Electromagnetic Waves, Transmission Through an Ionized Layer in the Presence of Magnetic Field: Dec 1822
Electromechanical Coupling Factor, Calculating: May 967
Electron Beams:
Filamentary, Power Carried by Cyclotron and Synchronous Waves on: May 969
from a Pierce Gun, Effect of Filament Magnetic Field: May 976
Ion Relaxation Oscillation in: Feb 525
Magnetic Tape Readout with: Feb 498
Modulated, Interaction with a Plasma: Dec 1906
Parametric Amplifiers, Kompfner Dip Couplers for: Mar 637
Spiraling, Large Signal Interaction with Rectangular Waveguide Mode: Nov 1696
Electron Emission, Secondary, and Satellite Ionization Phenomenon: Jun 1077
Electron Guns, Low-Noise, and the 6L6 Effect: Jun 1098
Electron-Optical Design, Electron Trigonometry for: Oct 1538
Electron Radiation Damage in Unipolar Transistor Devices: Sep 1437
Electron Stream, RF Focusing of: Apr 819
Electron Trajectories in a Nonuniform Magnetic Field: Apr 832
Electron Trigonometry, Electrical-Optical Design: Oct 1538
Electrons and Holes, Effects on the Transition Layer Characteristics of Linearly Graded *P-N* Junctions: Mar 603
Electrostatographic Devices, IRE Standards: Mar 619
Energy Conversion, Thermionic, by Space Charge Neutralization by an Auxilary Discharge: Dec 1932
Engineers, Electronics, Are they Educated?: Aug 1319
Envelope Probability as a Function of E/N_o: May 971
Epitaxial Microcircuit, Silicon: Jun 1087
Erasure, Optical, of EL-PC and Neon-PC Storage Elements: Sep 1438
Error:
Analysis, Relative: Jul 1229
Detection, Cyclic Codes for: Jan 228
Rates, Binary, in Fast Fading FDM-FM: Feb 513
Statistics and Coding for Binary Transmission Over Telephone Circuits: Jun 1059
Esaki Effect, Effect of Fluctuations in Density on the: Apr 837
Ether Drift, Masers and Lasers: Oct 1576
Europe, IRE Activities in: Jun 1008
European Data Processing: Jan 330, Jun 1065
Expansion, Compression, and Multiplication, New FM-AM Method: Oct 1550
Exponential Functions, Trigonometric and, Integration and Summation: Jun 1088

F

False Alarm Rate Calculation: Oct 1573
False Alarm Rate of Noise after Post-Detection Filtering: Feb 479
Failure Character of Receiving Tubes Due to Deterioration: Feb 528
Ferrimagnetic Limiter-Isolator: Oct 1575
Ferrimagnetic Limiter, Phase Distortion in: Jan 362
Ferrites:
Amplifier, K_a-Band: May 963
and Garnets at UHF, Gyromagnetic Resonance of: Sep 1443
Lithium, Power Limiting Using: Oct 1574
Loaded Coaxial Lines, Differential Phase Shifts in: Jan 364
Rod Antenna, Nondirectional, for AM Radios: Jul 1222
Rotary Joint, Waveguide In-Line: Dec 1959
Ferromagnetic Microwave Generator, Pulsed: May 957
Field-Effect Controlled Impact Ionization Switch, Crosistor: Nov 1616
Field-Effect Tetrode: Jul 1170
Field, *gh*, Theory: Nov 1690
Fields, Gravitational: Nov 1689
Filament, Tungsten Evaporated, for Gold-Silver Alloy: Oct 1570
Film Croytrons, Thin: Aug 1318
Film Memory, Magnetic, Design: Jan 155
Films, Conductive, Reflection and Transmission Jun 1090
Filters:
Adaptive Communications: Oct 1587
Crystals, Quartz AT-Type, for 0.7 to 60 Mc: Feb 523
Pulse-Compression, Closed-Form Solution for Output of: Jun 1086
Rihaczek's Constant Phase Nonlinear, Dynamic Response: Apr 822
Filtering, Post-Detection, Noise After: Feb 479
Flame Attentuation at 200 Mc, Measurement: Dec 1917
Flat Television Picture Tube, Deflection System for: Dec 1938
Flip-Flop Circuit, Bistable, Using Tunnel Diode: Sep 1440

Flip-Flop HF Behavior, One-Tunnel-Diode: Nov 1685
Flip-Flop, One-Tunnel-Diode: Mar 622
Flow Graphs and Tapered Transmission Lines: Nov 1696
Flow Graphs, Signal, Algorism for Reduction of: Sep 1431
Flow Table Logic: Jan 221
Fluorescence, Infrared, and Stimulated Emission of Nd^{+3} in $CaWO_4$: Nov 1704
Focusing, RF, of an Electron Stream: Apr 819
Focusing System, Hollow-Beam: Feb 514
Fourier Integral, Delta Function and: Nov 1702
Fourier Series Derivation: Apr 827, Jul 1209, Sep 1446
Fourier Transform Constants: Apr 833
Fourier Transform Pair, Choice of Constants in: Jan 375
Frequency:
Allocations for Space Communications: Jun 1009
and time Transmissions, WWV and WWVH Standard: Jan 379, Feb 512, Mar 629, Apr 813, May 960, Jun 1100, Jul 1227, Aug 1335, Sep 1434, Oct 1572, Nov 1681, Dec 1945
Conversion in a Microwave Discharge: Dec 1890
Converter, Tunnel-Diode: Aug 1318, Oct 1572
Divider, Junction-Transistor: Jun 1081
Divider, Parametric, Reactance Tube as: Mar 624
Division Systems, Multivoice-Channel, Noise Loading of: Dec 1952
Doubling Circuit, Tunnel-Diode Wide-Band: Dec 1963
Meter, Magnetically Tunable Microwave: Sep 1439
Modulation of a Reflex Klystron with Minimum Amplitude Modulation: Sep 1449
Multiplexing, Minimization of Maximum Amplitude in: Jan 357
Multiplier, Tunnel-Diode, with Gain: Dec 1940
Multiplier, Variable-Reactance: May 965
Multipliers Using Charge-Storage Effect, Efficiency of: Dec 1961
Stabilizer, Simplified Cesium: Jan 377
Standards, Beam, Magnetic Shield for: Aug 1328
Temperature Shift of Piezoelectric Resonators, Reduction: Nov 1650

G

Gallium Animonide Tunnel Diodes for High-Frequency Applications: Jun 1101
Garnet Limiters, Low-Level: Aug 1308
Garnets, Ferrites and, at UHF, Gyromagnetic Resonance of: Sep 1443
Gas-Discharge Microwave Power Coupler: May 949
Gas-Discharge Noise Source for Four-Millimeter Waves, Noise Temperature of: Apr 807
Gas, Partially Ionized, Conductivity of: Dec 1872
Gaseous Plasmas Immersed in Magnetic Fields, Interaction of Microwaves in: Dec 1877
Generating Signals of Arbitrary Yet Frequency-Independent Phase Differences: May 964
Generation, Coherent, of Microwave Power by Annihilation Radiation of a Prebunched Beam: Aug 1334
Generation of Microwave Harmonics in an Electrodeless Discharge: Dec 1941
Generator, Pulsed Gerromagnetic Microwave: May 957
Geomagnetic and the Geographic Axes, Relationship Between: Feb 530
Gold-Silver Alloy, Tungsten Evaporation Filament for: Oct 1570
Graphical Solution for the Flux Distribution in a Magnetic Parallel Circuit: Apr 808
Graphical Symbols for Electrical Diagrams, IRE Standards, Supplement: Feb 467
Graphs, Signal Flow, Alorism for Reduction of: Sep 1431
Gravitational Fields: Nov 1689
Ground Conductivity Map for Canada: Nov 1674
Guidance, Missile, Digital Computer Equipment for: Jan 313
Gyro, Passive-Element Electrical Analog to: Oct 1580
Gyromagnetic Resonance of Ferrites and Garnets at UHF: Sep 1443

H

Halftone Storage Tubes, Direct-View, Selective Erasure and Nonstorage Writing in: Mar 567
Harmonic Generation, 8- and 11-Gc Nanosecond Carrier Pulses Produced by: May 972
Harmonic Generators, Waveguide: Apr 825
Harmonics, Microwave, Generation in an Electrodeless Discharge: Dec 1941
Helium-Neon Gaseous Optical Maser: Dec 1954
Hildebrand's Method for Nonuniform Transmission Lines: Dec 1944
Holes, Effects of Electrons and, on the Transition Layer Characteristics of Linearly Graded *P-N* Junctions: Mar 603
Hues Seen in Fox-Color Images: Jul 1228, Dec 1946
Human Communication, Digital Simulation in Research on: Jan 319, Jun 1020

I

Image Response in a Superheterdyne Receiver: Sep 1435
Images, Fox-Color, Hues Seen in: Jul 1228, Dec 1946
Images, Permanent Visual, on Magnetic Tape: Apr 836
Impact Ionization Switch, Cryosistor Field-Effect Controlled: Nov 1616
Impedance of Long Wire Suspended Over the Ground: Oct 1576
Impedance Transformations, Visualization by Plastic Sphere Models: Feb 514
Inductance in Thin-Film Superconducting Structures: Nov 1640
Inductive Semiconductor Diodes, Three-Layer Negative-Resistance and: Apr 754
Inertial Systems, Doppler Effect and: May 971
Information Channel, Continuous, Capacity Corrected for Time or Phase Jitter: Feb 513
Information, Mutual, Generalization: Aug 1331
Information Theory, Cosmology and: Sep 1378
Infrared Fluorescence and Stimulated Emission of Nd^{+3} in $CaWO_4$: Nov 1704
Instrumentation System, Monopulse: Aug 1328
Instruments, Simple Current-Measuring, Minimum Reading Times for: Sep 1443
Integration and Summation of Trigonometric and Exponential Functions: Jun 1088
Intelligence, Artificial, Steps Toward: Jan 8
Intelligent Signals from Other Planetary Systems, Probable Character: May 959
Interference, Intersymbol, Elimination by Input Signal Shaping: Jul 1195, Nov 1639
Interference, Direct Adjacent Channel, Mechanism for: Jun 1091
Interference Output from FM and Television Receivers, Measurement, IRE Standards: Sep 1398
Intermediate Frequency, Zero, Receivers with: Aug 1327
International Activities Committee, IRE: Sep 1376
Interplanetary Telemetering, Correction: Mar 621
Intersymbol Interference by Input Signal Shaping, Elimination: Jul 1195, Nov 1639
Ion Relaxation Oscillation in Electron Beams: Feb 525
Ion Sheath of a Probe, Noise Generated in: Mar 632
Ionic and Plasma Propulsion for Space Vehicles: Dec 1789
Ionization:
Appleton-Hartree Equation for Any Degree of: Dec 1857
Effects, Satellite-Induced, Between Hemispheres, Correction: Jan 363
Irregularities, Magnetic Field Aligned: Mar 639
Phenomenon, Satellite, Secondary Electron Emission and: Jun 1077
Switch, Cryosistor Field-Effect Controlled Impact: Nov 1616
Ionized Cesium Plasma, Generation and Application of: Dec 1926
Ionized Gas, Partially, Conductivity of: Dec 1872
Ionized Layer, Transmission of Electromagnetic Waves in the Presence of Magnetic Field: Dec 1822
Ionogram, Vertical Incidence Doppler: Mar 643, Jul 1220
Ionosphere, Propagation of Wide-Band Signals Through: Jul 1211
Ionospheric Contributions to Doppler Shift from Satellites: Nov 1680
Ionospheric Long-Range Propagation, Applying Chordal-Hop Theory to Echo-Signal Delay: Jan 356
Ionospheric Refraction Effects, Elimination: Sep 1451
IRE:
Activities in Europe: Jun 1008
Convention: Mar 565
International Activities Committee: Sep 1376
President, Open Letter from: Dec 1743
Isolators:
Compact UHF: Jan 366
Ferrimagnetic Limiter: Oct 1575
Millimeter-Wave Field-Displacement-Type: May 975
Miniaturized *S*-Band: Dec 1958

J

Junctions, Linearly Graded *P-N*, Effects of Electrons and Holes on Transition Layer: Mar 603

K

Klystron, Reflex, Frequency Modulation, with Minimum Amplitude Modulation: Sep 1449
Klystrons, Drift-Tunnel Oscillations in: Jul 1207
Kompfner Dip Couplers for Electron Beam Parametric Amplifiers: Mar 637

L

Laplace and Poisson Equations, Resistor Network for Solving: May 933
Laplace Transformation, Probability Density Functions for Sums of Variables by: Jan 356
Lasers:
Flash-Pumped Ruby, Operating Characteristics: Oct 1570
Masers, and the Ether Drift: Oct 1576
Oscillators, Masers, Regenerative, Coherence vs Narrowbandedness in: May 958
Ruby, Exhibiting Periodic Relaxation Oscillations: Dec 1942
Ruby, with an Elliptic Configuration: May 960
Laurent-Cauchy Transform Analysis: Jan 358
Laurent-Cauchy Transforms: Sep 1447
Laurent-Cauchy Transforms for Analysis of Linear Systems, Correction: Jun 1097
Learning Machines, Optimum Performance: Jan 349
Light Amplifier, Pulsed Ruby Maser as: Nov 1635
Light, Coherent, Proposed Technique for Modulation of: Aug 1331
Light, Velocity of, Proposed Test of Constancy: Aug 1322, Dec 1953
Limiter, Ferrimagnetic, Phase Distortion in: Jan 362
Limiter-Isolator, Ferrimagnetic: Oct 1575
Limiters, Low-Level Garnet: Aug 1308
Linear Discrete Systems, Stability Test for: Dec 1947, 1948
Linear Systems, Laurent-Cauchy Transforms for Analysis of, Correction: Jun 1097
Linearity, Extended Definition: Sep 1452
Lithium Ferrite, Power Limiting Using: Oct 1574
Logarithmic Compression of Binary Numbers: Jul 1219
Logic Circuit Performance, Statistical Analysis: Jan 236
Logic Conversion, AND-OR to Majority, Limitations: Feb 519
Logic, Flow Table: Jan 221
Logic Nets, Structure: Aug 1322
Logic, Threshold, Recent Papers: Jun 1100
Logical Organization of Computer Arithmetic and Control Units: Jan 53
Loop Systems, Multisampled, Input-Output Relationships: Nov 1709
Loran-C, Timing Potentials of: Nov 1659
Lorentz Space, Minkowski Representation, Mechanical Model: Mar 635
Loudspeaker Measurements, IRE Recommended Practices on: Oct 1553
Lunar and Echo Satellite Reflection Signals, Sideband Correlation: Jun 1081
Lunar Reflection Circuit, Band-Pass Measurements: Mar 631

M

Machines, Self-Educating, for Recognition and Classification of Patterns: Aug 1335
Magnetic Circuits Employing Ceramic Magnets: Oct 1528

Magnetic Fields
Aligned Ionization Irregularities: Mar 639
DC, Representation of Electromagnetic Parameters in Presence of: Jan 354
in the Elimination of the Re-Entry Radio Blackout: Dec 1825
Interaction of Microwaves in Gaseous Plasmas Immersed in: Dec 1877
Nonuniform, Electron Trajectories in: Apr 832
Propagation Parameters for Plasma in: Oct 1584
Transmission of Electromagnetic Waves Through an Ionized Layer in the Presence of: Dec 1822
Magnetic Film Memory Design: Jan 155
Magnetic Parallel Circuit, Graphical Solution for the Flux Distribution in: Apr 808
Magnetic Pumping, Cyclotron Wave Amplifier with: Mar 645
Magnetic Recorder, Flexible-Disk: Jan 164
Magnetic Recording, Expression for Describing the Write Process in: Aug 1337
Magnetic Recording Techniques, High-Density Digital: Jan 258
Magnetic Second-Subharmonic Oscillator: Apr 779
Magnetic Shield for Beam Frequency Standards: Aug 1328
Magnetic Tape, Permanent Visual Images on: Apr 836
Magnetic Tape Readout with an Electron Beam: Feb 498
Magnetometers, Sample and Coil, Calibration Technique for Vibrating: Sep 1449
Magneto-Plasmas, Polarization by Crystal Optics: Oct 1584
Magnetoresistive Effect as a Memory Device: Dec 1943
Majority Elements, Restrictions in Synthesis of a Network with: Sep 1455
Masers:
Action in Ruby by Off-Resonance Pumping: Sep 1426
Cross-Relaxation: Mar 573
Helium-Neon Gaseous Optical: Dec 1954
Hybrids, Tunable: Feb 519
Lasers, and the Ether Drift: Oct 1576
Lasers, Oscillators, Regenerative, Coherence vs Narrowbandedness in: May 958
Low-Noise *X*-Band Radiometer Using: Apr 768
Operation, Optical, Repetitive Hair-Trigger Mode: Oct 1571
Optical, Cavity Modes in: Mar 625
Oscillation Observed from HCN Maser at 88.6 kMc: Nov 1706
Pulsed Ruby, as Light Amplifier: Nov 1635
Solid State, Negative *L* and *C* in, Correction: Feb 519
Terminology: Nov 1692
Traveling-Wave, Using Chromium-Doped Rutile: Aug 1329
Traveling-Wave, with Instantaneous Bandwidths in Excess of 100 Mc: Jul 1210
Tunable *S*-Band Traveling-Wave, for Telemetry: Jun 1078
Matrix Analysis of Networks Having Infinite Gain Operational Amplifiers: Oct 1577
Memories:
Circuit, Persistent-Current: Nov 1681
Computer: Jan 104
Device, Magnetoresistive Effect as: Dec 1943
Filter, Coherent, Use in Measurements of Whistlers: Nov 1707
Magnetic Film, Design: Jan 155
Message Lengths, Exponential, Spectrum: Jan 366
Meter, Magnetically Tunable Microwave-Frequency: Sep 1439
Meter, Self-Balancing Current, and Recorder: Oct 1578
Microcircuit, Silicon Epitaxial: Jun 1087
Microelectronics, Circuit Considerations Relating to: Feb 420
Microwave Radiation Hazards: Oct 1574
Microwave Radiation Hazards, Technical Aspects: Feb 427
Microwaves Propagating Through a Semiconductor Medium, Multiple Reflections of: Nov 1683
Millimetric Waves, Atmospheric Absorption: Mar 649
Minkowski Representation of Lorentz Space, Mechanical Model: Mar 635
Minority-Carrier Lifetime, Measurement by Photoconductive Decay, IRE Standards: Aug 1292
Missile Guidance, Bombing and Navigation Subsystem, Digital Computer Equipment for: Jan 313
Mixer Crystals, Microwave, Excess Noise in: Jul 1226
Mixer, Experimental Tunnel-Diode: Jan 350
Mixers, Tunnel-Diode, Noise in: Nov 1688
Mixing, Photoelectric, Signal-to-Noise Ratios in: Dec 1960
Modulating, Amplitude, Van Atta Radar Reflector: Mar 634
Modulation, Angle, Superposition Property of: Jun 1084
Modulation, Combined Amplitude and Phase, for a One-Sided Spectrum, Discussion: Jun 1094
Modulation of Coherent Light, Proposed Technique: Aug 1331
Monopulse Instrumentation System: Aug 1328
Moon, Radar Cross Section of: Dec 1944
Motor, Parametric Variable-Capacitor: May 970
Motor, Tunnel-Diode Super-Regenerative Parametric: Oct 1586
Multiplexing, Frequency, Minimization of Maximum Amplitude in: Jan 357
Multiplication, Compression, and Expansion, New FM-AM Method: Oct 1550
Multiplier, Frequency, Variable-Reactance: May 965

N

Navigation, Bombing and Missile Guidance Subsystem, Digital Computer Equipment for: Jan 313
Navigation, Space, Limitations to Optical Doppler Measurements for: Nov 1655
Negative-Conductance Amplifiers:
Distributed, Noise Measure: Jul 1212
Noise Figure: Feb 520
Noise Figure and Stability: Aug 1314
Transmission Line Parameters: Apr 812
Negative *L* and *C* in Solid State Masers, Correction: Feb 519
Negative Resistance:
Amplifiers, Gain Bandwidth Relations in: Jan 355
Amplifiers, Hybrid Coupled, Noise Considerations: Mar 626
Amplifiers, Optimum: Jun 1043, Nov 1687
and Inductive Semiconductor Diodes, Three-Layer: Apr 754
Characteristics, Tunnel-Diode, Circuit Control: Jul 1204
Diodes, Large-Signal Circuit Theory: Aug 1268
in Junction Diodes: Sep 1427
Oscillation Modes, Additional: Jul 1225
RF-Induced, in Junction Diodes: May 957
Negative Resistors, Network Synthesis with: May 907
Negentropy Revisited: Sep 1438
Networks:
Distributed RC, Shaping of: Aug 1330
Generalized, Quadratic Invariances of: Feb 488
Having Infinite-Gain Operational Amplifiers, Matrix Analysis: Oct 1577
Ladder, Representing Transcendental Numbers: Nov 1693
n-Port, Synthesis Procedure: Sep 1431
Planar, Duality of: Dec 1949
Resistor, for Solving Laplace and Poisson Equations: May 933
Synthesis with Negative Resistors: May 907
Time-Varying, I: Oct 1488
Neural Analogs: Aug 1316
Neural Elements, Simulation by Networks Based on Magnetic Cores: Jan 49
Neuristor Prototype: Sep 1430
Newtonian Relativity, Extension to Include Electromagnetic Phenomena: Nov 1691
Noise:
After Post-Detection Filtering: Feb 479
Amplifier, Zero-Point Energy as the Source of: Mar 633
Amplitude-Sampled White, Reconstruction Error and Delay for: Sep 1436
Considerations for Hybrid Coupled Negative-Resistance Amplifiers: Mar 626
Excess, in Microwave Mixer Crystals: Jul 1226
Figure:
and Stability of Negative Conductance Amplifiers: Aug 1314
Average and Spot, in Transistor Amplifiers, Comment: Nov 1699
Meter, Automatic, with a Liquid-Nitrogen-Cooled Termination, Performance: Dec 1963
Narrow-Band and Wide-Band: Dec 1954
of Negative-Conductance Amplifiers: Feb 520
Transistor Amplifiers, Comparison of Average and Spot: Jul 1215
Fluctuation, in Semiconductor Space-Charge Regions: May 921
Generated in the Ion Sheath of a Probe: Mar 632
in Beam-Type Parametric Amplifiers: Jul 1208
in Tunnel-Diode Mixers: Nov 1688
Investigation of Tunnel-Diode Microwave Amplifiers: Apr 739
Low-Frequency, in Backward Diodes: Dec 1939
Measure, Actual, of Linear Amplifiers: Sep 1391
Measure of Distributed Negative-Conductance Amplifiers: Jul 1212
Measure of Lossy Tunnel-Diode Amplifier Stages: Jul 1211
Oscillations and, in Low-Pressure DC Discharges: Dec 1767
Performance and Stability of a Hybrid-Coupled Tunnel Diode Amplifier: May 975
Performance, Definition: Jan 376
Semiconductor, as a Queuing Problem, Approximate Solution: Jun 1095
Temperature, Antenna, in Plasma Environment: Dec 1846
Temperature Calculation, Antenna and Receiving System: Oct 1568
Temperature, Corrections and Coordination of Some Papers on: Apr 814
Temperature of a Gas-Discharge Noise Source for Four-Millimeter Waves: Apr 807
Thermal and Beam, in a Quadrupole Amplifier: Apr 802
Noisemanship: Jul 1223
Noisy Measurement System Performance, Mathematical Description: Nov 1701
Nomenclature of TE_{0l} Modes in a Cylindrical Waveguide: Sep 1442
Nonlinear Capacitors, Definitions of Terms, IRE Standards: Aug 1279
Nonlinear Device, Spectral Response: Nov 1700
Nonlinear Elements, Nonsymmetrical Properties: Oct 1569
Nonlinear Filter, Rihaczek's Constant Phase, Dynamic Response: Apr 822
Nonlinear Reactance, Subharmonic Generation with: Jan 351
Nonlinear Resistors, Bilateral, Pseudo-Rectification and Detection by: Feb 469
Nonlinear Systems, Taylor-Cauchy Transforms for Analysis of, Correction: Jun 1098
Nonlinear Systems, Transients and Steady-State Behavior: Jan 380; Mar 631, 637
Nonlinearities, Single-Valued, A New RMS Describing Function for: Aug 1321

O

Old and the New: Jun 1089
Optical Design, Electron, Electron Trigonometry for: Oct 1538
Optical Doppler Measurements for Space Navigation, Limitations: Nov 1655
Optical Erasure of El-PC and Neon-PC Storage Elements: Sep 1438
Optical Maser, Cavity Modes: Mar 625
Optical Maser, Helium-Neon Gaseous: Dec 1954
Optical Maser Operation, Repetitive Hair-Trigger Mode: Oct 1571
Optical Radar, Correlation: Nov 1684
Optics, Crystal, Polarization in Magneto-Plasmas by: Oct 1584
Oscillations:
and Noise in Low-Pressure DC Discharges: Dec 1767
Drift-Tunnel, in Klystrons: Jul 1207
Ion Relaxation, in Electron Beams: Feb 525
Maser, Observed from HCN Maser at 88.6 kMc: Nov 1706
Modes, Additional Negative Resistance: Jul 1225
Self, in a Transmission Line with a Tunnel Diode: Aug 1281
Oscillators:
Cryotron Ring, Comments: Apr 827
Doppler-Helitron: Mar 626
Kilomegacycle Subharmonic, Computer Subsystem Using: Jan 128
Magnetic Second-Subharmonic: Apr 779
Masers, Lasers, Regenerative, Coherence vs Narrowbandedness in: May 958
Phase-Controlled, Pull-In Frequency of: Jul 1209

Phase-Shift, Tapered Distributed RC Lines for: Jun 1021
Phase Stability of: Feb 527
Six-Megacycle Cryotron Ring: Jan 371
Stabilization, Backward-Wave: Nov 1697
Transistor, Modes of Operation: Sep 1383
Triggered, Tunnel-Diode One-Shot and: Aug 1315
Tunnel-Diode Microwave: Apr 744, Nov 1689

P

Paired Echo Theory for Time-Domain Distortion in Pulsed Systems, Interpretation: Sep 1432
Parametric Amplification by Charge Storage: May 966
Parametric Amplification in Transistors: Aug 1335
Parametric Amplification with a Low-Frequency Pump: Jul 1214
Parametric Amplifiers:
Backward Traveling-Wave, Wide Tuning Range of: Aug 1339
Beam-Type, Noise in: Jul 1208
Broad-Band *S*-Band: Dec 1943
C-Band Nondegenerate, with 500-Mc Bandwidth: May 961
C-Band, with Large Bandwidth: Nov 1682
Circuits, Nonreciprocal: Jun 1075
Degenerate, Sensitivity: Jul 1205
Electron Beam, Kompfner Dip Couplers for: Mar 637
Extremely Wideband Tunable: Dec 1940
Front End, Degenerate, Radar Sensitivity with: Apr 804
High-Performance *X*-Band: Feb 511
L-Band Traveling-Wave: Jul 1230
Lossy Coupling in: Oct 1573
Nearly Optimum Wide-Band Degenerate: Apr 833
Nondegenerate *S*-Band, with Wide Bandwidth: Apr 824
Resonant Slot: Dec 1939
Stable: Mar 629
Traveling-Wave, Analysis: Mar 591
Traveling-Wave, Effect of Higher Harmonic Components on: Mar 623
Traveling-Wave, Gain Saturation in: Sep 1433
Unidirectional Lower Sideband: Nov 1684
Variable Dual Reactance Traveling-Wave: May 973
Wide-Band Single-Diode, Using Filter Techniques: Apr 821
Parametric Devices, Nonreciprocal, Experiments with: Oct 1582
Parametric-Excited Resonator Using Junction Transistor: May 974
Parametric Frequency Divider and Amplifier, Reactance Tube as: Mar 624
Parametric Motor, Tunnel-Diode Super-Regenerative: Oct 1586
Parametric Standing-Wave Amplifier, Varactor Diode: Feb 509
Parametric Transducers, History: Jan 378, Feb 524
Parametric Up-Converter Tunable Over an 18:1 Frequency Band: May 966
Parametric Variable-Capacitor Motor: May 970
Partition Theory and Associated Transform: Jul 1215
Pattern Recognition:
Autocorrelation: Jun 1085
by Moment Invariants: Sep 1428
Inductive Probability as a Criterion for: Dec 1951
Using Autocorrelation: Jan 175
Patterns, Self-Educating Machines for Recognition and Classification of: Aug 1335
Penning Discharge, Electrical Characteristics: Dec 1920
Phase Control, Automatic: Theory and Design, Correction: Mar 590
Phase-Controlled Oscillator, Pull-In Frequency of: Jul 1209
Phase Differences, Arbitrary Yet Frequency-Independent, Generating Signals of: May 964
Phase Distortion in a Ferrimagnetic Limiter: Jan 362
Phase Inverters Utilizing Controlled Superconductors: Oct 1574
Phase-Locked Loop, Transfer Function: Nov 1704
Phase-Shift Oscillators, Tapered Distributed RC Lines for: Jun 1021
Phase Stability of Oscillators: Feb 527
Phase Velocity of VLF Waves: Jun 1089
Photoconductive Decay, Measurement of Minority-Carrier Lifetime by, IRE Standards: Aug 1292
Photoelectric Mixing Signal-to-Noise Ratios in: Dec 1960
Photon Propelled Space Vehicles: Jan 381
Pickard's Regenerative Detector: Sep 1447
Picture Tube, Flat Television, Deflection System for: Dec 1938
Piezoelectric Ceramics, Measurements, IRE Standards: Jul 1161
Piezoelectric Resonators, Reduction of Frequency-Temperature Shift of: Nov 1650
Planetary Systems, Other, Probable Character of Intelligent Signals from: May 959
Plasmas:
Dispersion Formula Usable for Analog Computing: Oct 1582
Environment, Antenna Noise Temperature in: Dec 1846
Gaseous, Immersed in Magnetic Fields, Interaction of Microwaves in: Dec 1877
in a Magnetic Field, Propagation Parameters for: Oct 1584
Interaction of a Modulated Electron Beam with: Dec 1906
Ionized Cesium, Generation and Application: Dec 1926
Issue, Introduction: Dec 1747
Layer, Mutual Coupling of Two Slots in the Presence of: Dec 1837
Magneto, Polarization by Crystal Optics: Oct 1584
Microwave Energy Detector: Dec 1901
Physics, Elementary Review: Dec 1751
Propulsion, Ionic and, for Space Vehicles: Dec 1789
Sheaths, RF Reflectance of: Dec 1831
Poisson Equations, Laplace and, Resistor Network for Solving: May 933
Polarization in Magneto-Plasmas by Crystal Optics: Oct 1584
Polarization, Rotating, and Periodic Bodies: Jan 361
Polarization, Rotating, Generating: Jun 1089
Polarized Waves, Partially, Techniques for Handling, with Reference to Antennas: Sep 1446
Pole-Zero Sensitivity Relationships: Dec 1959
Posicast Control, Analog Study: Sep 1450
Potential Analog Pairs, Algebraic Function Calculations Using: Jan 276
Power Coupler, Gas-Discharge Microwave: May 949
Power Limiting Using Lithium Ferrite: Oct 1574
Power, Microwave, Coherent Generation by Annihilation Radiation of a Prebunched Beam: Aug 1334
Probability Densities, Construction from Their Moments: Oct 1580
Probability Density Functions for Sums of Variables by Laplace Transformation: Jan 356
Programming Systems, Evolution: Jan 283
Propagation:
of Wide-Band Signals Through the Ionosphere: Jul 1211
Parameters for Plasma in a Magnetic Field: Oct 1584
Space, Doppler-Shift Effects in: Nov 1694
VLF, Possibility of Rejecting Certain Modes in: Sep 1429
Propulsion, Ionic and Plasma, for Space Vehicles: Dec 1789
Pulse Circuits, Avalanche, New Ways to Trigger: Jun 1093
Pulse-Compression Filter, Closed-Form Solution for the Output of: Jun 1086
Pulse Compression, Linear FM, Matched-Filter Analysis: Apr 831
Pulse-Compression Systems, Performance Due to Doppler Effect: Nov 1693
Pulse Doppler Radar, Detection Range Predictions for: Aug 1299
Pulsed Systems, Interpretation of Paired Echo Theory for Time-Domain Distortion in: Sep 1432
Pulses, 8- and 11-Gc Nanosecond Carrier, Produced by Harmonic Generation: May 972
Pulses, Nanosecond Carrier, Generation at *X*-Band with Tunnel Diodes: Jul 1204
Pulses, Nanosecond, Generating at *X* Band: May 968

Q

Quadrupole Amplifier, Low-Noise Microwave: Jun 1016
Quadrupole Amplifier, Thermal and Beam Noise in: Apr 802
Quantum Effects, Minimum Power Set by: Apr 813
Quartz AT-Type Filter Crystals for 0.7 to 60 Mc: Feb 523
Quartz Thickness-Shear Mode Cut, with Temperature Coefficients of Frequency: Sep 1454
Queuing Problem, Semiconductor Noise as a, Approximate Solution: Jun 1095

R

Radar:
Correlation Optical: Nov 1684
Cross Section of the Moon: Dec 1944
CW, Pulse, and Pulse Doppler, Range Performance of, Correction: Jan 329
Forward Scattering by Coated Objects Illuminated by: Dec 1951
Ineffectiveness of Absorbing Coatings: Mar 646
Pulse Doppler, Detection Range Predictions for: Aug 1299
Receivers Employing a Double-Threshold Detection, Coincidence Techniques: Oct 1561
Reflector, Van Atta, Amplitude Modulating: Mar 634
Returns, Sequential Detection System for Processing: Sep 1417
Scattering Cross Section, Applied to Moon Return: Sep 1433
Sensitivity with Degenerate Parametric Amplifier Front End: Apr 804
Radiation:
Annihilation, of a Prebunched Beam, Coherent Generation of Microwave Power by: Aug 1334
Cerenkov, in a Dielectric Tube Waveguide: Jun 1084
Damage, Electron, in Unipolar Transistor Devices: Sep 1437
Hazards, Microwave: Oct 1574
Hazards, Microwave, Technical Aspects: Feb 427
Radiometer, Digital: Jun 1099
Radiometer, Low-Noise *X*-Band, Using Maser: Apr 768
Radiometry, Submillimeter Wave: Jun 1024
Reactance:
Series Resonator, Expanded: Oct 1583
Tube as a Parametric Frequency Divider and Amplifier: Mar 624
Variable, Frequency Multiplier: May 965
Time-Varying, Power-Frequency Relations in: Jun 1051
Reading Times, Minimum, for Simple Current-Measuring Instruments: Sep 1443
Receiver, Superheterodyne, Image Response: Sep 1435
Receivers, FM and Television, Measurement of Interference of Output, IRE Standards: Sep 1398
Receivers with Zero Intermediate Frequency: Aug 1327
Recognition and Classification of Patterns, Self-Educating Machines for: Aug 1335
Recorder, Fexible-Disk Magnetic: Jan 164
Recorder, Self-Balancing Current Meter and: Oct 1578
Recording, Magnetic, Expression for Describing the Write Process in: Aug 1337
Recording Techniques, High-Density Digital Magnetic: Jan 258
Rectification, Pseudo, and Detection by Bilateral Nonlinear Resistors: Feb 469
Re-Entry Radio Blackout, Magnetic Fields in Elimination of: Dec 1825
Reflections, Multiple, of Microwaves Propagating Through a Semiconductor Medium: Nov 1683
Reflections of a Communication Engineer: Sep 1378
Reflector, Van Atta Radar, Amplitude Modulating a: Mar 634, Nov 1692
Refraction Effects, Ionospheric, Elimination: Sep 1451
Relativity:
and the Clock Paradox: Sep 1437
Blessing or Blindfold, Comments: Mar 630
General, for the Experimentalist: May 982
Newtonian, Extension to Include Electromagnetic Phenomena: Nov 1691
Resistance, Negative, Optimum Amplifiers, Comments: Nov 1687
Resistance, Tunnel-Diode Series: Nov 1679
Resistivity, Semiconductor, Electrodeless Measurement: May 921

Resistor Network for Solving Laplace and Poisson Equations: May 933
Resistors, Bilateral Nonlinear, Pseudo-Rectification and Detection by: Feb 469
Resistors, Negative, Network Synthesis with: May 907
Resonance, Gyromagnetic, of Ferrites and Garnets at UHF: Sep 1443
Resonators:
Expanded Reactance Series: Oct 1583
Formed from Circular Plane and Confocal Paraboloidal Mirrors, Measurements: Jun 1079, Sep 1434
Parametric-Excited, Using Junction Transistor: May 974
Piezoelectric, Reduction of Frequency-Temperature Shift of: Nov 1650
Riccati's Equation, Sugai's Class of Solutions: Aug 1320, Dec 1946
Ring Structures, Electrostatic, Microwave Amplification in: Sep 1424
Ruby Laser with an Elliptic Configuration: May 960
Ruby, Maser Action by Off-Resonance Pumping: Sep 1426

S

Sampling, Nonuniform, and External Approximation: Feb 521
Satellites:
Antenna, Broad-Band Spherical: Apr 824
Communications, Using Arrays: Jun 1066, Aug 1340
Induced Ionization Effects Between Hemispheres, Correction: Jan 363
Ionization Phenomenon, Secondary Electron Emission and: Jun 1077
Ionospheric Contributions to Doppler Shift from: Nov 1680
Reflection Signals, Lunar and Echo, Sideband Correlation: Jun 1081
Signals, VHF, Received at Extra Optical Distances: May 959
Supervision of the Orbital Period of: Nov 1698
Supported Communication at 21 Megacycles: Sep 1455
Tracking and Display: Aug 1332
Scatter Path, Tropospheric, Antenna Siting Tests on: Aug 1325
Scatter Communications, Antenna-Beam Configurations in: Sep 1452
Scattered Fields, Tropospheric: Apr 788
Scattering:
Bistatic, from Absorber-Coated Metal Shapes: Jul 1184
Cross Section, Radar, Applied to Moon Return: Sep 1433
Forward, by Coated Objects Illuminated by Radar, Discussion: Dec 1951
Matrices Normalized to Complex Port Numbers: Jul 1221
of Short Electromagnetic Pulses by a Conducting Sphere: Jan 380
Schwarz's Lemma and Linear Passive Systems: Dec 1950
Self-Educating Machines for Recognition and Classification of Patterns: Aug 1335
Self-Organizing Systems: Aug 1317
Self-Organizing Systems—A Review and Commentary: Jan 31
Semiconductors:
Carrier Lifetimes, Microwave Determination: Sep 1440
Device, Three-Terminal Variable Capacitance: Feb 510
Medium, Multiple Reflections of Microwaves Propagating Through: Nov 1683
Noise as a Queuing Problem, Approximate Solution: Jun 1095
Resistivity, Electrodeless Measurement at Microwave Frequencies: May 921
Space-Charge Regions, Fluctuation Noise in: May 921
Shannon Switching Game, Solution: Aug 1339
Shield, Magnetic, for Beam Frequency Standards: Aug 1328
Shot Noise in Tunnel-Diode Amplifiers: Jan 350, Mar 622
Shot-Noise Smoothing Mechanism, Comment: Nov 1695
Signal Flow Graphs, Algorism for Reduction: Sep 1431
Signals, Intelligent, from Other Planetary Systems, Probable Character: May 959
Silicon Cryosar: Aug 1313
Silicon Epitaxial Microcircuit: Jun 1087
Simulation:
Computer, of a Television Coding Scheme: Jun 1076
Computer, Transient Analysis of Cryotron Networks by: Jan 245
Digital, in Research on Human Communication: Jan 219, Jun 1020
of Neural Elements by Networks Based on Magnetic Cores: Jan 49
Study, Tunnel-Diode Large-Signal: Apr 803
Simulator, Active-Passive Network, for Transient Field Problems: Jan 268
Single-Sideband Communication: Mar 632
Single Sideband, Compatible: Oct 1503
Skip Distance, Proof of Focusing by Backscatter Records: Jan 369
Slots, Two, Mutual Coupling in the Presence of Plasma Layer: Dec 1837
Social Sciences, Can They Be Made Exact?: Feb 526
Sound Waves, Whistlers Excited by: May 968
Space-Charge Density, Small-Signal, in Beams Immersed in an Axial Magnetic Field: Apr 815
Space-Charge Potentials in Depressed-Collector Design: Feb 522
Space-Charge Regions, Semiconductor, Fluctuation Noise in: May 921
Space Charge Neutralization by an Auxiliary Discharge, Thermionic Energy Conversion by: Dec 1932
Space Communications, Frequency Allocations for: Jun 1009
Space Navigation, Limitations to Optical Doppler Measurements: Nov 1655
Space Propagation, Doppler-Shift Effects: Nov 1694
Space System, Optimum Capacitor Charging Efficiency for: May 941
Space Vehicle, Antenna Size for: Nov 1708
Space Vehicles, Photon Propelled: Jan 381
Spectral Response of a Nonlinear Device: Nov 1700
Spectrum, Instantaneous: Mar 649
Spectrum of Exponential Message Lengths: Jan 366
Spectrum, One-Sided, Combined Amplitude and Phase Modulation for, Discussion: Jun 1094
Sphere Models, Plastic, Visualization of Impedance Transformations by: Feb 514
Stability Test for Linear Discrete Systems: Dec 1947, 1948
Standards:
Beam Frequency, Magnetic Shield for: Aug 1328
Definitions of Television Terms, IRE: Jul 1193
Definitions of Terms for Nonlinear Capacitors, IRE: Aug 1279
Electrostatographic Devices, IRE: Mar 619
Graphical Symbols of Electrical Diagrams, Supplement, IRE: Feb 467
Measurement of Minority-Carrier Lifetime by Photoconductive Decay, IRE: Aug 1292
Measurement of Output from FM and Television Receivers, IRE: Sep 1398
Measurement of Resolution of Camera Systems, IRE: Mar 599
Measurements of Piezoelectric Ceramics, IRE: Jul 1161
Transmitter Terms, IRE: Feb 486
Steady-State Analysis of Circuits Containing a Periodically Operated Switch: Dec 1955
Steady-State Behavior, Transient and, Analysis: Mar 638
Steady-State Behavior, Transients and, in Nonlinear Systems: Mar 631
Storage Elements, EL-PC and Neon-PC, Optical Erasure of: Sep 1438
Storage Tubes, Direct-View Halftone, Selective Erasure and Nonstorage Writing in: Mar 567
Stripline *Y*-Circulators for 100 to 400 Mc: Feb 518
Subharmonic Generation with Nonlinear Reactance: Jan 35
Subsurface Communication Systems: Mar 645
Sugai's Class of Solutions to Riccati's Equation: Aug 1320, Dec 1946
Summation, Integration and, of Trigonometric and Exponential Functions: Jun 1088
Superconducting Structures, Thin-Film, Inductance in: Nov 1640
Superconductors, Controlled, Phase Inverters Using: Oct 1574
Superheterodyne Receiver, Image Response: Sep 1435
Surface-Potential Controlled Transistor: Nov 1623
Surface Transmission, Two-Wire Millimeter Wave: Jun 1076
Switches:
Alloy Junction Transistor, Rise and Fall Times in: Mar 636
Cryosistor Field-Effect Controlled Impact Ionization: Nov 1616
Cryosistor Three-Terminal: Jan 352
Low-Loss, Semiconductor Microwave: Mar 644
RF, High-Speed Silicon Computer Diodes as: Nov 1707
Switching Game, Shannon, Solution: Aug 1339
Switching Transistors, GaAs Temperature Effects on: Sep 1448
Synchronization Experiment, Long-Range Clock: Jun 1028
Synchronizing System, Very-Low-Frequency: Feb 448
Synthesis of a Network with Majority Elements, Restrictions in: Sep 1455
Synthesis Procedure for an *n*-Port Network: Sep 1431

T

Taylor-Cauchy and Laurent-Cauchy Transform Analysis, Equivalence with Conventional Methods: Jan 358
Taylor-Cauchy Transforms for Analysis of Nonlinear Systems, Correction: Jun 1098
Taylor-Cauchy Transforms for Analysis of Varying-Parameter Systems: Jun 1096
Teflon Waveguide Plunger: Jun 1083
Telemetering, Interplanetary, Correction: Mar 621
Telemetry, Tunable *S*-Band Traveling-Wave Maser for: Jun 1078
Telephone Circuits, Binary Transmission Over, Error Statistics and Coding for: Jun 1059
Television Coding Scheme, Computer Simulation: Jun 1076
Television Picture Tube, Flat, Deflection System for: Dec 1938
Television Terms, Definition, IRE Standards: Jul 1193
Termination, Liquid-Nitrogen-Cooled, Performance of an Automatic Noise Figure Meter with: Dec 1963
Tetrode, Field-Effect: Jul 1170
Thermionic Energy Conversion by Space Charge Neutralization by an Auxiliary Discharge: Dec 1932
Thermoelectric Converter, Equivalent Circuits for: May 963
Thermoelectric Device Design, New Concepts: Jul 1155
Thermoelectric Generator Design, Reliability Factors in: Dec 1952
Thin-Film Cryotrons: Aug 1318
Thin-Film Superconducting Structures, Inductance in: Nov 1640
Time-Domain Distortion in Pulsed Systems, Interpretation of Paired Echo Theory for: Sep 1432
Time Transmissions, WWV Standard: Jan 379, Feb 512, Mar 629, Apr 813, May 960, Jun 1100, Jul 1227, Aug 1335, Sep 1434, Oct 1572, Nov 1681, Dec 1945
Time-Varying Capacitance Problem, Exact Solution: Feb 453
Time-Varying Networks, I: Oct 1488
Time-Varying Reactances, Power-Frequency Relations in: Jun 1051
Timing Potentials of Loran-C: Nov 1659
Tracking and Display of Satellites: Aug 1332
Transducers, Parametric, History: Jan 378, Feb 524
Transform, Associated, Partition Theory and: Jul 1215
Transformer, Complex, Nonrealizability: Oct 1585
Transformers, Duality as Applied to: Apr 816
Transient and Steady-State Behavior, Analysis: Mar 638
Transient Field Problems, Active-Passive Network Simulator for: Jan 268
Transients and Steady-State Behavior in Nonlinear Systems: Mar 631, 637
Transistors:
Amplifiers, Average- and Spot-Noise Figure in: Jul 1215, Nov 1699
Based on Transit-Time and Avalanche Effects, Negative Resistance in, Correction: Aug 1340
Devices, Unipolar, Electron Radiation Damage: Sep 1437
Double Diffused, Injection Efficiency in: Nov 1708
Drift, Cutoff Frequencies of Minority-Carrier Transport Factors in: Jul 1218

Equivalent Circuit: Dec 1957
Equivalent Circuit, Complete: Apr 825
GaAs Switching, Temperature Effects on: Sep 1448
Internal Parameters for Small-Signal Representation: Apr 725
Number of Impurities in Base Layer of: Apr 834
Oscillator, Modes of Operation: Sep 1383
Parametric Amplification in: Aug 1335
Storage Time in Circuits with Speed-Up Capacitors: Dec 1962
Surface-Potential Controlled: Nov 1623
Switch, Alloy Junction, Rise and Fall Times in: Mar 636
Upper Noise Corner Frequency: Mar 648
Transition Layer, Effects of Electrons and Holes on: Mar 603
Transmission Lines:
Model: Aug 1324
Nonuniform, D'Alembert's Method: Apr 824
Nonuniform, Exact Method: Mar 627
Nonuniform, Hildebrand's Method: Dec 1944
Self-Oscillation with a Tunnel Diode: Aug 1281
Shielded, External Electromagnetic Fields of: Apr 816
Tapered, Flow-Graphs and: Nov 1696
Transmitters, Definitions of Terms, IRE Standards: Feb 486
Traveling-Wave Amplifier, Solid-State Analog to: Jun 1079
Traveling-Wave Maser, Tunable *S*-Band, for Telemetry: Jun 1078
Traveling-Wave Maser Using Chromium Doped Rutile: Aug 1329
Traveling-Wave Maser with Instantaneous Bandwidths in Excess of 100 Mc: Jul 1210
Traveling-Wave Parametric Amplifiers:
Analysis: Mar 591
Backward, Wide Tuning Range of: Aug 1339
Effect of Higher Harmonic Components on: Mar 623
Gain Saturation in: Sep 1433
L-Band: Jul 1230
Variable Dual Reactance: May 973
Traveling-Wave Tube, Electrostatically Focussed, Small-RF-Signal Theory for, Correction: Dec 1836
Traveling-Wave Tubes, Interaction Circuit for: Feb 525, Nov 1686
Trigonometric and Exponential Functions, Integration and Summation: Jun 1088
Trigonometry, Electron—Electron-Optical Design: Oct 1538
Tropospheric Scattered Fields: Apr 788
Tube Networks, Vacuum: Nov 1695
Tubes, Adler, Beam Interception and Limiting Gain in: Feb 516
Tubes, Receiving, Failure Character Due to Deterioration: Feb 528
Tungsten Evaporation Filament for Gold-Silver Alloy: Oct 1570
Tunnel Diodes:
Amplifiers:
Broad-Band: Apr 835
Cascaded: Sep 1434
Cascading: Jan 373
Gain vs Bandwidth Limits for: Apr 832
Hybrid-Coupled, Noise Performance and Stability of: May 975
Millimeter-Wave: Jun 1075
Shot Noise in: Jan 350, Mar 622
Stability Criteria for: Dec 1937
Stages, Lossy, Noise Measure: Jul 1211
Using Two Cascaded, Matched: May 904
as Highly Sensitive Microwave Detector: Apr 826
Binary Counter Circuit: Jun 1092
Binary, One: Sep 1445
Bistable Flip-Flop Circuit Using: Sep 1440
Conductance Parameters, Measurement: Oct 1581
Digital Techniques: Jan 136
Down Converters: Jul 1225
Effect of Nonsymmetrical Doping: Sep 1435
Equivalent Noise Current of: Jun 1080
Flip-Flop: Mar 622
Flip-Flop HF Behavior: Nov 1685
Frequency Converter: Aug 1318, Oct 1572
Frequency Multiplier with Gain: Dec 1940
Full Binary Adder With One: Jul 1213
Gallium Antimonide, for High-Frequency Applications: Jun 1101
Generation of Nanosecond Carrier Pulses at *X*-Band with: Jul 1204
High-Frequency Power in: Jun 1033
Junction Capacitance, Measurement: Jan 372
Large-Signal Circuit Theory for: Aug 1268
Large-Signal Simulation Study: Apr 803
Locked Pair, Calculated Waveforms for: Jan 146
Microwave Amplifiers, Noise Investigation: Apr 739
Microwave Oscillators: Apr 744, Nov 1689
Mixer, Experimental: Jan 350
Mixers, Noise in: Nov 1688
Negative-Resistance Characteristics, Circuit Control of: Jul 1204
One-Shot and Triggered Oscillator: Aug 1315
Relaxation Oscillator, Converter Efficiency and Power Output of: Jul 1219
Ring Counter, 100-Mc: Jul 1215
Self-Oscillation in a Transmission Line with: Aug 1281
Series Resistance: Nov 1679
Shift of Peak Voltage with Temperature in: Jan 349
Slot Transmission Amplifier: Aug 1315
Stability Criteria for: Jul 1206
Super-Regenerative Parametric Motor: Oct 1586
Temperature Dependence of Peak Current of: Sep 1428
Wide-Band Frequency Doubling Circuit: Dec 1963
10.8 KMC Germanium: Feb 519

U

Up-Converter, Electronically Tunable: Nov 1703
Up-Converter, Parametric, Tunable Over an 18:1 Frequency Band: May 966

V

Vacuum Technology, Electronics and: Jul 1136
Vacuum-Tube Networks: Nov 1695
Value Engineering—1959: Mar 640
Van Atta Radar Reflector, Amplitude Modulating: Mar 634, Nov 1692
Varactor Diodes:
Available Comparative Figures of Merit for: Apr 809
Capacitance Coefficients for: Apr 810
Microwave Bistable Circuits Using: Apr 829
Parametric Standing-Wave Amplifier: Feb 509
Varying-Parameter Systems, Taylor-Cauchy Transforms for Analysis of: Jun 1096
Vectors for Waves and Electrons: Mar 628
Velocity of Light, Proposed Test of Constancy: Aug 1322, Dec 1953
Very-Low-Frequency Synchronizing System: Feb 448
Visual Images, Permanent, on Magnetic Tape: Apr 836
VLF Emission, Energy Fluxes from Cyclotron Radiation Model: Apr 811
VLF Propagation, Possibility of Rejecting Certain Modes in: Sep 1429
VLF Waves, Phase Velocity of: Jun 1089

W

Waveguides:
Cylindrical, Nomenclature of TE_{0l} Modes in: Sep 1442
Dielectric Tube, Cerenkov Radiation in: Jun 1084
Harmonic Generators: Apr 825
In-Line Ferrite Rotary Joint: Dec 1959
Iris Beam, Measurements: Nov 1679
Mode, Rectangular, Large Signal Interaction With Spiraling Electron Beam: Nov 1696
Parallelogramic, TM Modes in: Jul 1222
Plunger, Teflon: Jun 1083
Whistlers Excited by Sound Waves: May 968
Whistlers, Use of Coherent Memory Filter in Measurements of: Nov 1707
Wire, Long, Impedance of, Suspended Over the Ground: Oct 1576
WWV and WWVH Standard Frequency and Time Transmissions: Jan 379, Feb 512, Mar 629, Apr 813, May 960, Jun 1100, Jul 1227, Aug 1335, Sep 1434, Oct 1572, Nov 1681, Dec 1945

NONTECHNICAL INDEX

Abstracts and References

January 401–415
February 545–559
March 705–719
April 865–876
May 991–1004
June 1118–1131
July 1246–1260
August 1358–1372
September 1470–1484
October 1598–1612
November 1726–1740
December 1979–1994

Abstracts of TRANSACTIONS

January 394–400
February 538–544
March 694–704
April 856–864
May 984–990
June 1111–1117
July 1239–1245
August 1349–1357
September 1462–1469
October 1594–1597
November 1716–1725
December 1973–1978

Awards

Baker, W. R. G., Prize Award:
M. Clynes: Jan 20A, Apr 842
Diamond, Harry, Memorial Award:
H. L. Brueckmann: Jan 20A, Apr 842
Fellow Awards:
Adams, P. R.: Apr 843
Adams, R. J.: Apr 843
Adorian, P.: Apr 843
Aigrain, P.: Apr 843
Attwood, S. S.: Apr 843
Axelby, G. S.: Apr 843
Bagno, S.: Apr 843
Belevitch, V.: Apr 843
Berger, F. B.: Apr 843
Blake, G. A.: Apr 844
Bracewell, R. N.: Apr 844
Bramhall, F. B.: Apr 844
Bruene, W. B.: Apr 844
Christensen, J. W.: Apr 844
Clark, J. W.: Apr 844
Darnell, P. S.: Apr 844
Dike, S. H.: Apr 844
Dodds, W. J.: Apr 844
Doelz, M. L.: Apr 845
Dunlap, W. C., Jr.: Apr 845
Elliott, R. S.: Apr 845
Ference, M., Jr.: Apr 845
Filipowsky, P.: Apr 845
Fisher, J. F.: Apr 845
Flowers, H. L.: Apr 845
Godley, P. F.: Apr 845
Gordon, W. E.: Apr 845
Gray, A. R.: Apr 846
Greibach, E. H.: Apr 846
Grieg, D. D.: Apr 846
Harris, C. M.: Apr 846
Hastings, C. E.: Apr 846
Hector, L. G.: Apr 846
Heyd, J. W.: Apr 846
Hickman, R. W.: Apr 846
Jeffers, C. L.: Apr 846
Jensen, A. S.: Apr 847
Keller, A. C.: Apr 847
Ku, Y. H.: Apr 847
LaGrone, A. H.: Apr 847
Lakatos, E.: Apr 847
Lee, Y. W.: Apr 847
Leedy, H. A.: Apr 847
Lenzer, E.: Apr 847
Lubkin, S.: Apr 847
Maxwell, D. E.: Apr 848
McCann, G. D.: Apr 848
McFarlan, R. L.: Apr 848
Mohr, M. E.: Apr 848
Nicoll, F. H.: Apr 848
O'Bryan, H. M.: Apr 848
Oliner, A. A.: Apr 848
O'Neal, R. D.: Apr 848

Ports, D. C.: Apr 848
Post, E. A.: Apr 849
Reed, M. B.: Apr 849
Richman, D.: Apr 849
Robertson, S. D.: Apr 849
Romnes, H. I.: Apr 849
Ronci, V. L. Apr 849
Rosenberg, P. Apr 849
Sanders, R. C., Jr.: Apr 849
Schwartz, L. S.: Apr 849
Sears, R. W.: Apr 850
Shapiro, G.: Apr 850
Smith, T. A.: Apr 850
Somers, R. M.: Apr 850
Stodola, E. K.: Apr 850
Strieby, M. E.: Apr 850
Tice, T. E.: Apr 850
Tomota, M.: Apr 850
van Duuren, H. C. A.: Apr 850
Wickizer, G. S.: Apr 851
Wischmeyer, C. R.: Apr 851
Zarem, A. M.: Apr 851
Ziegler, H. K.: Apr 851
Founders Award:
R. Bown: Jan 20A, Apr 841
Liebmann, Morris N., Memorial Prize:
L. Esaki: Jan 20A, Apr 841
Medal of Honor:
E. A. Guillemin: Jan 20A, Apr 841
Morlock, William J., Professional Group on Bio-Medical Electronics Prize Award:
B. Chance: Jan 22A, Apr 842
Thompson, Browder J., Memorial Award:
E. Goto: Jan 20A, Apr 841
Zworykin, V. K., Prize Award:
P. C. Goldmark: Jan 22A, Apr 842

Calendar of Coming Events

January 14A
February 14A
March 14A
April 14A
May 14A
June 14A
July 14A
August 14A
September 14A
October 14A
November 14A
December 14A

Committees

Membership Lists: Jun 30A, Oct 35A
Representatives:
in Schools: Jun 42A, Oct 46A
on Other Bodies: June 44A, Oct 50A

Front Covers

Antiferroelectric Circuit Element: August
Compatible Single-Sideband: October
Frequency Allocations for Space Communications: June
IRE International Activities: September
IRE International Convention: March
Machines That Learn: January
Magnetic Tape Readout with an Electron Beam: February
Plasma: December
Radiograph of Ion Pump Cathode: July
Subharmonic Oscillator Analysis: April
Surface-Potential Controlled Transistor: November
Technique for Reducing Noise in Beams: May

Frontispieces

Bereskin, A. B.: Sep 1374
Berkner, L. V.: Jan 2
Bown, R.: Mar 562
Bullock, M. W.: Nov 1614
Byrne, J. F.: Feb 418
Carter, E. F.: May 878
Giordano, A. B.: Aug 1262
Guillemin, E. A.: Mar 563
Noble, D. E.: Oct 1486
Ollendorff, F.: Apr 722
Shepherd, W. G.: Jun 1006
Tupper, B. R.: Dec 1742
Van Atta, L. C.: Jul 1134

IRE People

Aaron, B. D.: Feb 34A
Abraham, L. G., Jr.: May 32A
Adams, R.: May 32A
Adams, R. T.: Nov 44A
Adler, R. B.: Mar 64A
Affel, H. A.: Aug 74A
Aiken, H. H.: Aug 85A
Alberts, H. C.: Jul 32A
Alexander, D. C.: Nov 44A
Algase, L. I.: Nov 44A
Anderson, T. N.: Jan 70A, Jul 32A
Angello, S. J.: Jul 32A
Askanas, C.: Apr 70A
Bacon, E. J.: Jan 70A
Bailey, A. D.: Oct 56A
Bailey, S. L.: Mar 64A
Ballard, B. G.: Apr 70A
Basarab, J., Jr.: Jan 70A
Bateman, G. H.: Oct 56A
Beers, Y.: Dec 40A
Begovich, N. A.: Jul 32A
Beinhocker, G. D.: Nov 44A
Beizer, H. H.: Feb 34A
Benson, S. E.: Sep 66A
Berkner, L. V.: Feb 34A
Bernstein, J. L.: Sep 66A
Bernstein, J. M.: Nov 44A
Bertan, H. S.: Feb 38A
Black, G.: Oct 56A
Black, P. B.: Dec 40A
Blanchard, J. W.: Oct 56A
Bliss, W. R.: Dec 40A
Bloomenthal, S.: Aug 76A
Blumkin, R.: Mar 64A
Boggs, G. E.: Sep 68A
Bond, H. A.: Jun 58A
Borchardt, R. L.: Dec 42A
Borgen, H.: May 32A
Bowie, R. M.: Apr 70A
Bowman, D. S.: Apr 78A
Braverman, R.: Sep 68A
Breitwiesser, C. J.: Sep 68A
Brenner, A.: Feb 36A
Brick, D. B.: Jun 58A
Bridges, W. A.: May 32A
Brinda, J., Jr.: Jan 70A
Brock, E. G.: Sep 70A
Brooks, F. E.: Jul 36A
Brooks, L. P.: Aug 81A
Brown, W. J.: Mar 66A
Buchak, K. R.: Sep 70A
Bulkley, D. D.: Mar 64A
Burnett, B. B.: Aug 78A
Butterfield, F. E.: Nov 46A
Campbell, D. B.: Apr 72A
Caryotakis, G.: Mar 66A
Castriota, L. J.: Jun 58A
Chatterton, J. B.: Sep 72A
Chipp, R. D.: Aug 78A
Christian, H. S.: Oct 56A
Christiansen, D.: Feb 38A
Ciral, J. L.: Nov 46A
Clarke, G. M.: Jan 72A
Constant, P. C., Jr.: Jan 72A
Cook, L. J.: Jul 38A
Cooper, A. E.: Dec 42A
Cooper, M.: Dec 42A
Cranna, N. G.: Nov 46A
Cranshaw, R. H.: Jul 44A
Crosby, M. G.: Jan 76A
Crumb, S. F.: May 35A
Currie, M. R.: Apr 72A
Dacey, G. C.: Nov 50A
Daugherty, R. M.: Jan 76A
Davies, G. L.: Nov 48A
Davis, J. C., Jr.: Dec 52A
Davis, J. J.: Jun 60A
Davy, S. J.: Feb 38A
Deal, D. L.: Dec 42A
De Bolt, A. L.: Feb 40A
Dellinger, J. H.: Feb 40A
Deming, R. L.: Nov 50A
Devey, G. B.: Mar 66A
Diamond, J. R.: Oct 58A
Dickieson, A. C.: Jun 60A
DiJulius, J. R., Jr.: Dec 42A
DiToro, M. J.: Apr 76A
Doersam, C. H.: Jun 64A
Donner, J. B.: Nov 53A
Drake, W. W., Jr.: May 35A
Driskell, R. O.: Apr 78A
Dudeney, P. N.: Dec 46A
DuHamel, R.: Jul 42A
Easton, I. G.: Apr 80A
Edwards, P. G.: Jul 44A
Elias, H. J.: Feb 42A
Elkins, C. E.: Feb 44A
Elkort, D. S.: Feb 44A
Ely, P. C., Jr.: Oct 65A
Enenstein, N. H.: Jun 64A
Esaki, L.: Nov 53A
Ettenberg, M.: Oct 58A
Evander, H. S.: Apr 80A, Jul 54A
Faflick, C. E.: Nov 54A
Fahringer, W. H.: May 36A
Fank, F. B.: Mar 70A
Fano, R. M.: Jul 50A
Fast, S.: Feb 44A
Field, L. M.: Oct 58A
Finch, T. R.: May 36A
Findley, L. D.: Jan 76A, Mar 72A
Fink, D. G.: Jul 50A
Finke, H. A.: May 40A
Fleming-Williams, B. C.: Jan 91A
Fletcher, J. C.: Sep 74A
Flowers, H. L.: Dec 46A
Fowler, C. J.: Jan 106A
Franco, G. A.: Jun 64A
Freseman, W. L.: Jul 58A
Friedman, L.: Apr 78A
Fromm, W. E.: Jun 69A
Fubini, E. G.: Jul 56A
Fulenwider, J. E.: Nov 56A
Gale, M.: Feb 46A
Gamara, N. J.: Apr 80A
Gardenhour, A. J.: Aug 81A
Garner, D. L.: Oct 62A
Garr, D. E.: Feb 46A
Gentry, K. M.: Apr 83A
Germain, J.: Dec 50A
Giacoletto, L. J.: Mar 72A
Gilden, M.: Jul 120A
Gilson, R. J.: Aug 83A
Ginsberg, I.: Aug 83A
Ginsburg, C. P.: Jan 80A
Goldsborough, R. R., Jr.: Jun 74A
Gonzalez-Correa, E.: Jan 86A
Gottfried, P.: Nov 60A
Grad, P. P.: May 43A
Graham, R. R.: Apr 84A
Green, E. I.: Jan 79A
Green, R. S.: Dec 50A
Greenhalgh, K. D.: Dec 52A
Grimes, D. M.: Apr 86A
Gross, T. A. O.: Dec 52A
Guillemin, E. A.: Feb 48A
Gunther, F. A.: Mar 80A
Hamaan, O. F.: Apr 88A
Hammond, C. R.: Jan 85A
Hance, H. V.: Mar 84A
Handelsman, M.: May 38A
Hannan, P. W.: Jul 120A
Harley, J. M.: Dec 54A
Hart, G. W.: Oct 62A
Hartley, J. T.: Jun 74A
Haughawout, J. H.: Mar 86A
Hauser, H. H.: Jun 77A
Hauser, J. R.: May 40A
Hechtel, J. R.: Jun 77A
Heins, J. L.: Feb 48A
Heller, D. M.: Oct 62A
Hellmann, R. K.: May 46A
Hennies, S. R.: Dec 54A
Henning, R. E.: Oct 65A
Herre, J. L.: Jan 86A
Hessinger, P. S.: Dec 56A
Higgins, W. T.: Nov 60A
Hilgedick, W. C.: Dec 56A
Hirsch, R. B.: Sep 84A
Hoffman, C. H.: May 43A
Hogan, W. D.: Oct 66A
Holce, T. J.: Oct 81A
Holmlund, B. A.: Feb 48A
Holonyak, N., Jr.: Feb 52A
Homan, R. E.: Jul 120A
Hopfer, S.: Jun 79A
Horak, R. J.: Nov 60A
Houlroyd, G. F.: Jun 138A
Houseworth, G. H.: Dec 56A
Howell, R. L.: Aug 85A
Hughes, G. E.: Aug 86A
Hull, D. R.: Oct 65A
Hunter, G. T.: Aug 86A
Hutter, R. G. E.: Apr 86A
Isbister, E. J.: Apr 83A
Jackson, P. W.: Jan 88A
Jacobs, C. E., Jr.: Mar 88A
Jacobsen, T. L.: Apr 90A
Jacobus, H. R.: Mar 88A
Jatras, S. J.: Jun 138A
Jervis, E. W., Jr.: Jul 123A
Jesty, L. C.: Jan 91A
Jiles, C. W.: May 46A
Johnson, J. H.: Jun 138A
Johnson, L. P.: Oct 66A
Johnson, R. M.: Jan 91A
Joyce, W. F.: Oct 68A
Kahn, L.: Oct 68A
Kalmus, H. P.: Mar 90A
Kaltman, A. H.: Jun 138A
Kamen, I.: Sep 76A

Kandoian, A. G.: Feb 48A
Karlsruher, G. W.: Nov 62A
Karns, K. B.: Sep 44A
Kaye, H. W.: Nov 62A
Kellogg, L. H.: Jan 91A
Kelly, L. J.: Sep 76A
Kendall, R.: May 46A, Sep 44A
Kent, R. L.: Oct 69A
Keyes, J. C.: Oct 70A
Kimball, J. L.: Dec 56A
Kimmel, R. O.: Mar 92A
Kinsman, R. G.: Oct 70A
Kirsch, W. A.: Oct 70A
Knoob, G. B.: Jul 124A
Koch, D. G.: Dec 56A
Koch, J. A.: Apr 90A
Koontz, R. H.: Sep 44A
Kosowsky, D. I.: Sep 90A
Kovach, L. D.: Oct 72A
Krassner, G. N.: Jan 92A
Krim, N. B.: Dec 59A
Kropp, C. W.: Apr 90A
Kulka, E. R.: Aug 54A
Lack, F. R.: Jun 140A
LaHiff, W. J.: Sep 78A
LaMontagne, R. S.: Jun 140A
Lapin, S. P.: Feb 50A
Larson, D. E.: Apr 90A
Laurent, G. J.: Jan 104A
LaVier, E. C.: Aug 86A
Law, H. B.: Mar 92A
Lawton, B. E.: Apr 94A
Lazier, W. A.: Feb 52A
Lee, D. N.: Jun 142A
Lehan, F. W.: Sep 78A
Lehr, P. N.: Jan 102A
Lehr, S.: Feb 52A
Leifer, M.: Jun 142A
Lesk, I. A.: Feb 54A
Levine, S. W.: Sep 80A
Lillibridge, E. H.: Nov 68A
Lind, E. R.: Dec 59A
Lindstrom, R. G.: May 48A
Lintner, P. D.: Oct 81A
Lippitt, K. H.: Oct 72A
Llewellyn, F. B.: Oct 72A, Nov 62A
Lockwood, R. C.: Oct 72A
Loughlin, R. G.: Feb 56A
Lovenstein, A. J.: Aug 54A
Low, W. C.: Mar 97A
Lowy, M. A.: Jun 142A
Lundberg, W. R.: Nov 68A
Lurie, W. B.: Jun 148A
Lynch, W. A.: Oct 73A
Lynn, L. H.: Dec 59A
Lyons, H.: Mar 99A
Madeson, A. H.: Feb 54A
Magid, M.: Feb 54A
Mainberger, W. A.: Nov 68A
Mannel, W. M.: Mar 95A
Marcuvitz, N.: May 48A, Sep 80A
Margolin, A. R.: Nov 70A
Markowitz, R. S.: Jan 106A
Martin, L.: May 50A, Oct 73A
Martinson, F. L.: Oct 74A
Mason, W. P.: Jan 124A
McClellan, G. B.: Nov 70A
McDavitt, M. B.: Jul 120A
McGaughey, R. P.: May 50A
McLucas, J. L.: Jan 124A
Mehr, M. H.: Aug 54A
Mika, J. I.: Sep 84A
Miller, K. M.: Aug 56A
Minichiello, R.: Jan 128A
Mischler, E.: Nov 74A
Moore, E. F.: Nov 70A
Moore, K. A.: Jan 130A
Morin, L. A.: Oct 81A
Mortenson, K. E.: Apr 94A
Mueller, W. M.: Jan 134A
Munushian, J.: Dec 60A
Myers, W. D.: Feb 56A
Newell, D. E.: Nov 64A
Nichols, A. D.: Apr 96A
Nishball, J. L.: Oct 74A
Norton, J. M.: Feb 36A
Novikoff, E. B.: Oct 74A
Noyes, A., Jr.: Apr 96A
Nussbaum, M.: Jan 106A
O'Brien, T. H.: Oct 74A
Ogletree, W. A.: Dec 60A
Okada, S.: Dec 60A
O'Maley, J. B.: Feb 56A
Orth, R. T.: Jun 150A
Osborne, H. S.: Mar 101A
Othmer, R. E.: Feb 56A
Packard, A. C.: Sep 86A
Packard, R. H.: Jan 134A
Peck, D. B.: Feb 56A
Peirce, J. R.: Sep 44A
Pepper, J. R.: Jun 142A
Peter, R. W.: Mar 104A
Peterson, E. F.: Aug 86A
Peterson, R. M.: Apr 96A
Peterson, R. W.: Dec 60A
Peth, R.: Dec 60A
Pike, N.: Oct 76A
Plouffe, R. L.: Sep 46A
Pollack, H. W.: Oct 76A
Porter, C. R.: Nov 72A
Portmann, P. A.: Mar 106A
Ports, D.: Nov 72A
Poss, E.: Jan 134A
Postman, M. H.: May 54A
Pote, A. J.: Nov 74A
Price, V. G.: Mar 106A, Aug 54A
Pritchard, B. D.: Sep 46A
Pritchett, W. S.: Sep 46A
Raber, S.: Mar 110A
Raemer, H. R.: Aug 56A
Rajchman, J. A.: Nov 74A
Redlien, H. W., Jr.: Aug 60A
Reed, J.: Sep 46A
Reese, J. R.: Oct 76A
Reuman, W. H.: Nov 76A
Rexroat, L. D.: Nov 78A
Rizzi, P. A.: Aug 60A
Robbins, A.: Oct 76A
Robinson, J. A.: Feb 58A
Rogell, P. S.: Sep 46A
Romig, H. G.: Oct 77A
Rosen, B.: Oct 78A
Rosen, H.: May 52A
Rosen, H. H.: Jan 138A
Ross, F. L.: Oct 78A, Nov 78A
Ross, P. C.: Aug 62A
Rothstein, J.: Dec 62A
Rous, W. H.: Mar 110A
Rubin, M.: Feb 58A
Rudnick, S. L.: Feb 58A
Rugge, R. A.: Feb 61A
Rydz, J. S.: May 52A
Sabel, A. R.: May 54A
Saline, L. E.: Nov 78A
Schaefer, H. W.: Mar 110A
Schooley, A. H.: Sep 86A
Schulz, E. H.: Dec 62A
Schutz, G. C.: Sep 88A
Schwartz, W. L.: Jul 60A
Shamos, M. H.: Oct 78A
Shapiro, L. D.: May 52A
Sheingold, L. S.: Jun 146A
Shepherd, M., Jr.: Oct 80A
Sherr, S. I.: Nov 87A
Shuttleworth, E., III: Apr 96A
Sichak, W.: Oct 78A
Siegel, K. M.: Mar 114A
Sink, R. L.: Sep 48A
Sirrine, R. C.: Feb 64A, Sep 48A
Sisson, R. L.: Sep 52A
Skifter, H. R.: Feb 61A
Slawson, W. J.: Mar 124A
Smith, D. M.: Oct 80A
Smith, R. T.: Jul 60A, Oct 80A
Smith, W. W.: Oct 81A
Smock, W. W.: Nov 82A
Sommer, A. H.: Mar 92A
Soufal, F. H.: Sep 56A
Spencer, G. W.: Sep 56A
Sprague, R. C.: Apr 100A
Stack, B. R.: Jun 150A
Staras, H.: Aug 64A
Steier, H. P.: Sep 58A
Steigman, P.: Oct 81A
Stein, P.: Sep 88A
Stein, S.: Jan 140A
Stelzer, I.: Jan 142A
Stevens, F. R.: Dec 52A
Stopek, S.: Nov 82A
Storer, J. E.: Jan 140A, Aug 64A
Strain, D. C.: Oct 81A
Strauss, R.: Feb 64A
Stromsted, E. A.: Sep 88A
Stryker, E. M.: Sep 58A
Sturgeon, W. S.: Nov 87A
Sugarman, R. H.: Jul 118A
Suits, G.: Dec 64A
Sullivan, A. H., Jr.: Sep 88A
Sutliff, C. N.: Aug 66A
Swain, R. G.: Jan 144A
Swinyard, W. O.: May 58A
Tackett, W. F.: Nov 87A
Tanguay, A. R.: Sep 58A
Taylor, R. B.: Sep 62A
Terhune, H. R.: Mar 112A
Thomas, E.: Oct 82A
Tidball, R. M.: Sep 90A
Tomash, E.: Apr 96A
Torn, L. J.: May 56A
Tuttle, B. R.: Nov 88A
Twersky, V.: Apr 100A
Tyler, E. M.: Nov 88A
Utlaut, W. F.: Jun 146A
Van Allen, J. A.: Oct 82A
Van Atta, L. C.: Oct 84A
van Duuren, H. C. A.: May 56A
Vang, J. P.: Jan 144A, Nov 88A
Van Rennes, A. B.: Aug 66A
Venaglia, E. J.: Sep 90A
Walker, R. M.: Apr 100A
Walling, G. P.: Sep 64A
Walzer, F.: Nov 88A
Wambsganss, B.: Nov 90A
Warner, W. V.: Jan 146A
Warren, L. H.: Dec 64A
Weglein, R. D.: Dec 66A
Weiner, J. R.: Jan 148A
Weinhouse, N.: Oct 82A
Weir, W. R.: Aug 68A
Weisz, W. J.: Nov 90A
Welkowitz, W.: Aug 68A
Wheeler, F. K. B.: Feb 56A
Wheeler, H. A.: Mar 116A
Wheeler, J. L.: Aug 70A
White, D. R. J.: May 58A
White, J. R.: Dec 66A
Whybark, D. L.: Jul 120A
Wiesner, J. B.: Feb 64A, Mar 121A
Willenbrock, F. K.: Sep 90A
Willey, F. G.: Jan 148A
Williams, A. B.: Nov 92A
Wilson, W. H.: Oct 86A
Wissemann, H. J.: Oct 86A
Witting, E. G.: Oct 84A
Wolff, J. R.: Sep 64A
Woodcock, E. L.: Feb 66A
Worch, A. B.: Feb 66A
Wren, A. W., Jr.: Apr 100A
Wright, W. V.: Feb 68A
Wunderlich, N. E.: Apr 100A
Yoder, J. R.: Aug 70A
Young, F. C.: Sep 92A
Young, R. W.: Aug 74A
Zacharias, J. R.: Feb 64A, Apr 100A
Zopf, D. O.: Mar 118A
Zuleeg, R.: Feb 68A

News and Notices

Adaptive Control Systems Symposium Held on L.I.: Feb 18A
Aerospace Symposium Announces Session Topics: Jul 15A
AIEE Announces 1962 Winter Meeting: May 14A
AIEE Receives NSF Grant for Russian Journals: Sep 18A
Air Force MARS Eastern Technical Net Broadcast Schedules: Jan 15A, Feb 18A, Mar 18A, Apr 18A, May 18A, Jun 14A, Sep 16A, Nov 15A, Dec 22A
Analog Computation, International Conference on, to be Held in Belgrade: Mar 18A
Auerbach Receives Philadelphia Section Award: Apr 20A
Automation, Congress on, to Meet in Turin: Aug 18A
Biophysical Society Plans February Meeting: Feb 14A
Biophysical Society to Meet in Washington, D.C.: Dec 15A
British IRE Convention on Radio and Space: Jul 18A
Canadian Conference, Call for Papers Issued By: May 15A
Canadian Conference, IRE, Announces New Meeting Dates: Apr 14A
Canadian Conference, IRE, to Meet in October: Jul 16A
Chicago Spring Conference Announces June Meeting: May 15A
CISPR Conference in Philadelphia: Sep 15A
Communications Conference to Meet in Philadelphia: Jun 16A
Components Conference to Meet in May: Apr 20A
Copenhagen Symposium on Electromagnetic Theory, Registration for: Dec 22A
Delco Announces New Silicon Digital Models: Sep 14A
Denver Research Institute Announces Symposium: Apr 16A
ECCANE Announces Schedule of Sessions: Oct 15A
EJCC 1961 Issues Call for Papers: Jun 20A
Electrically Exploded Wires Topic of Fall Conference: Jun 16A

Electron Devices Meeting, Papers Solicited for: Jun 18A
Electronic Components, Conference on, Call for Papers Issued: Aug 16A
Electronic Reliability, Second New York Conference: Sep 16A
Engineering Writing and Speech National Symposium to be in Michigan: Sep 18A
Engineering Writing and Speech Symposium Issues Call for Papers: May 18A
Eta Kappa Nu Honors Young Engineers: Jan 16A
French Radio and Television Exhibition: Sep 16A
German Electrotechnicians to Hold Convention: Jan 15A
Gifford, R. P., Appointed Member of JTAC: Jun 18A
GLOBECOM V Meets in Chicago: May 18A
Goldsmith Honored by SMPTE: Dec 14A
Gordon Research Conferences to Include July Session on Semiconductors: May 14A
Guy, R. F., Receives NAB Award: Jun 15A
"HERO" Congress to be Held in May: Apr 15A
IEE 1962 International TV Conference: Sep 15A
IFAC, Second Congress Call for Papers: Nov 15A
IFIPS Announces 1962 Congress: Jun 18A
Index to IRE INTERNATIONAL CONVENTION RECORD, 1961: Dec 1
Index to IRE PROCEEDINGS, 1961: Dec 1
Index to IRE TRANSACTIONS, 1960: Apr follows 876
Industrial Electronics Symposium Will Emphasize Supplier-User Cooperation: Jun 14A
Information and Decision Processes, Third Symposium on, Purdue Will Sponsor: Mar 14A
Information Theory Symposium to be Held in Brussels: Dec 16A
Interference Reduction and Electronic Compatibility Conference in Chicago: Sep 14A
Ionization of the Air, International Conference on: Jun 20A
IRE Announces 1961 Awards: Jan 20A
IRE Banquet, Make Reservations Now: Dec 14A
IRE Begins Work in Nuclear Instrumentation: Apr 18A
IRE Dictionary Now Available: Jul 16A
IRE Elects Officers for 1961: Jan 14A
IRE International Convention, 1962, Call for Papers: Jul 16A, Aug 14A, Sep 14A, Oct 15A
IRE INTERNATIONAL CONVENTION RECORD and Order Form: Apr 24A
IRE International Convention Set for March: Jan 14A
IRE Miscellaneous Publications Available: May 16A, Oct 18A
IRE Nominations for 1962 Officers and Directors: Jul 14A
IRE PROCEEDINGS, Special Issue on Plasmas, Call for Papers: Mar 16A
IRE Standards, Current: Dec 16A
IRE Student Affairs Secretary Appointed: Dec 16A
JACC Announces Additions to Program: Jun 16A
JACC 1962 Deadlines Announced: Oct 18A
Joint Computer Conference, Call for Papers: Sep 16A
JTAC Forms Committee on Space Communications: Feb 14A
JTAC Pays Tribute to Dr. Hogan: May 18A
Kansas City Section Schedules Fall Symposium: Jun 16A
Las Vegas Symposium, Call for Papers for: May 16A
MAECON Symposium Program Announced: Oct 16A
Magnetism and Magnetic Materials, Conference on, Will Meet in Phoenix: Jun 15A
Magnetism Conference Plans Near Completion: Jul 15A
Magnetohydrodynamics, Symposium on, Call for Papers: Dec 20A
Mathematics Research Center Plans April Symposium: Feb 18A
Medical Electronics, International Conference on, Issues Call for Papers: Feb 15A
Medical Electronics Conference, Program Sessions Announced for: Jul 14A
Medicine and Biology, Joint Executive Committee on, Seek Conference Location: Oct 20A
Microelectronics and Systems Call for Papers: Jan 18A
Microwave Tube Congress, Call for Papers: Dec 14A
MIL-E-CON Advisors, Admiral Burke Heads: Feb 14A
MIL-E-CON Call for Papers: Jan 18A
MIL-E-CON 1961, Program Highlights of, Announced: Apr 15A
MIL-E-CON 1962, Call for Papers: Dec 16A
Military Electronics, Winter Convention to be Held in Los Angeles: Jan 20A
MIT Announces Special Summer Session: Jun 15A
MIT Announces Summer Session on Radio Astronomy: Mar 16A
NAECON Call for Papers Issued by Annual: Jan 18A
NAECON 1962, Call for Papers: Dec 15A
NAECON Plans Spring Meeting: Feb 16A
NAECON Publications Now Available: Aug 14A
NBS Radio Propagation Journal, Broadened Scope for: Oct 14A
NEC Announces Conference Dates: Mar 14A
NEC Announces 1961 Executive Officers: Feb 16A
NEC Issues Call for Papers: May 15A
NEREM 1961 Issues Call for Papers: Apr 18A
NEREM 1961 Program Expanded: Nov 14A
Nonlinear Magnetics, Conference on, Call for Papers: Jul 15A
Nonlinear Magnetics, Conference on, Scheduled for November: May 18A
North Carolina Section Symposium Program Announced: Oct 16A
NTC, 1961, Announces Program Sessions: May 16A
Operations Research and Management Sciences Groups to Meet: Oct 18A
Optimum and Adaptive Control System Theory, Graduate Institute on: Dec 22A
PGEWS Announces September Conference: Aug 18A
PGHFE Plans Spring Meeting: Mar 15A
PGMTT *Digests* Available in Limited Quantity: Aug 15A
PGMTT National Symposium Issues Call for Papers: Aug 14A
PGMIL 1962 Winter Convention Announcement and Call for Papers: Oct 16A
PGPEP Announces June Conference: Apr 16A
PGRFI To Hold June Conference: May 18A
PGVC Announces Awards Presented at Annual Conference: Feb 16A
PGVC Announces 12th Annual Conference: Jul 16A, Aug 15A
PGVC Conference Call for Papers: Sep 18A
P.I.B. Symposium Announced: Dec 18A
Plasma Sheath Symposium to Meet in April: Oct 14A
Quantum Electronics, Conference on, to be Held in California: Mar 15A
Radar Symposium, Seventh Annual, Scheduled for Spring: Mar 16A
Radio Propagation Course Announced by NBS: Apr 20A
Reliability and Quality Control Symposium Issues Call for Papers: Mar 18A
Reliability, Conference on, New York Chapter to Hold: Aug 16A
Reliability Course, Canadian, Sponsored by PGRQC and ASQC: Oct 14A
Reliability Problems, NYU Hosts Conference on: Mar 16A
Reliability Training Course to be Held in Syracuse: Apr 14A
Seventh Region to Hold Annual Conference: Mar 15A
Solid-State Circuits, 1962 Conference on, Issues Call for Papers: Aug 15A
Soviet Physics-Doklady to Appear Monthly: May 18A
SSB Dinner, Tenth Annual: Mar 16A
SWIRECO Announces Program Moderators: Apr 14A
SWIRECO 1962, Call for Papers: Aug 16A
SWIRECO Plans Nearing Completion: Feb 16A
Telecommunications Exhibit to be Held in Lisbon: Jan 15A
TIMS to Meet in Brussels: Apr 16A
TRANSACTIONS Binders Now Available: May 15A
URSI Symposium on Electromagnetic Theory: Aug 16A
URSI-IRE Fall Meeting and Geomagnetic Conference Announces for October: Sep 18A
WESCON Adopts System to Ease Distribution of Exhibitor Literature: Jun 18A
WESCON Call for Papers: Jan 20A, Feb 15A, Mar 14A, Apr 15A
WESCON 1961, Changes Indicated for Program: Apr 16A
Wiesner, J. B. Awarded EIA Medal of Honor: Jun 16A
Zitelli Wins Seventh Region Achievement Award: Sep 16A

Obituaries

Baker, W. R. G.: Jan 1
Carter, Philip S.: Jul 18A
Clothier, C. M.: Feb 18A
de Forest, Lee: Oct 22A
Ferguson, S. A.: Apr 22A
Gamzon, R. R.: Dec 24A
Goode, Harry H.: Jan 16A
Hanson, O. B.: Nov 15A
Hogan, J. V. L.: Feb 18A, Apr 721
Hollmann, H. E.: Apr 20A
Howe, G. W. O.: Feb 20A
Kranz, H. E.: Nov 15A
MacDonald, W. A.: Oct 20A
McIlwain, K.: Jun 20A
Potter, E. Vernon: Jan 16A
Tallman, O. G.: Jun 20A
Werner, R. V.: Apr 22A

Photographs

ANE Annual Luncheon (*left to right*), Dodington, S., Hallaby, N. (principal speaker), and Berkner, L. V.: Jul 15A
Auerbach, I. L., receives plaque at Fellows' Night banquet from W. T. Sumerlin: Apr 20A
Australian Institution of Radio Engineers, convention organized by: Jun 18A
Bailey, G. W., receiving citation: Jan 14A
Berkner, L. V., addresses members of New York Section: Mar 15A
Byrne, J. F., and Rubel, J. H., at meeting of Los Angeles Section of the IRE: Mar 18A
Chicago Spring Conference on Broadcasting and Television Receivers, Meeting of Joint Briefing Session: May 14A
Communications Symposium, Seventh National, meeting of the Executive Committee: Jun 15A
Crone, W. R., Student Affairs Secretary: Dec 16A
Curtiss, A. N., Chairman, 1961 Winter Convention on Military Electronics: Jan 20A
Easton, R. L., and Votaw, M. T., receive 1960 IRE Professional Group on Reliability and Quality Control Award from P. K. McElroy: Apr 16A
Electrical Techniques in Medicine and Biology, 13th Annual Conference, Exhibits: Jan 20A
Goldsmith, A. N., receives honorary SMPTE membership: Dec 14A
Greenwood, J. H., receives Scott Helt Award of PGB from R. Guy: Dec 24A
Haggerty, P. E., IRE President-Elect, and Chase, W. H., AIEE President, at AIEE Fall Meeting: Dec 14A
Hornbeck, J. A., Welch, H. W., Jr., and Wing, A. K., Jr., at PGED Meeting: Jan 15A
IRE International Convention:
Annual IRE Banquet, a view of: May 13A
Banquet, principal speakers at: May 13A
Berkner, L. V., presents IRE Medal of Honor to E. A. Guillemin: May 13A
Berkner, L. V., presents Professional Group on Bio-Medical Electronics Prize Award to B. Chance: May 12A
Bown, R., is presented with the 1961 IRE Founders Award by L. V. Berkner: May 12A
Byrne, J. F., Berkner, L. V., Bailey, G. W., and Olendorff, F., at opening press conference: May 12A
Coliseum, view of exhibits: May 12A
Noble, D. E., toastmaster; Haggerty, P. E., principal speaker; and Wischmeyer, C. R., spokesman for the newly-elected Fellows, at the Annual Banquet: May 13A
Israel National Convention of Electronic Engineers, Fourth, Forum of the, and Annual Meeting of the IRE Israel Section: Jun 14A
Kimball, C. N., receiving the Kansas City Section Award: Jan 20A
MIL-E-CON Planning Committee: Jan 18A
Military Electronics 1962 Winter Convention Steering Committee: Oct 16A
MIL-E-CON Awards Luncheon; Witting, E. G., presents W. B. Glendinning with the M. Barry Carlton Award: Sep 15A
MIL-E-CON Panel Discussion (*left to right*), Ankenbrandt, F. L., Wakelin, J. H., Rubel,

J. H., McMillan, B., and Witting, E. G.: Sep 16A
MTT Annual Banquet (*left to right*), Ports, D., Conroy, P. R., Shapiro, G., and Sand, T.: Aug 15A
NEREM 1961 Proclamation Issued by Governor Volpe of Massachusetts: Nov 14A
Pasadena Subsection, April meeting of: Jul 16A
PGPEP 5th Annual Conference, High School Students Award Exhibits: Sep 18A
Washington Section Annual Banquet, distinguished guests at: Apr 18A
Zitelli, L. T., receives Seventh Region Award: Sep 16A

Poles and Zeros

Anniversary Issue: Nov 1613
Awards: Mar 561
Career Brochure: Aug 1261
Collaboration Clarification: Mar 561
Dreams May Come True: Dec 1741
E&A-ECPD: Oct 1485
ECPD and IRE: Jul 1133
Editorial Faux Pas: Nov 1613
Ex-Editor Month: Nov 1613
Information Retrieval: Aug 1261
International Scene: Jun 1005
International Standardization: Jul 1133
IRE Dictionary: Jan 3
Iteration: Feb 417
Membership: Jan 3, Jun 1005
Miscellany: Jan 3
Musical Chairs: Sep 1373
New Faces of 1961: Mar 561
"New Idea": Mar 561
The Old and the New: Feb 417
Plasma: Dec 1741
Professional Groups: May 877
Radio: Sep 1373
Reminder: Jan 3
Satellite Communications: Apr 723
Second Round: Jan 3
Section News: Dec 1741
Student Affairs: Dec 1741
Switzerland and Chile: Mar 561
Travel Still Broadens: Nov 1613
Tutorial: Dec 1741
WESCON 1961: Aug 1261
WWV and WWVH: Apr 723

Professional Groups

Chairmen and Editors:
January 28A
March 24A
May 24A
July 18A
September 30A
November 22A
December 15A
News:
Antennas and Propagation: Feb 15A, Dec 15A
Antennas and Propagation and Microwave Theory and Techniques: Apr 14A, Dec 15A
Automatic Control: Apr 14A
Bio-Medical Electronics: Jan 22A, Jun 16A, Jul 16A
Circuit Theory and Information Theory: Sep 15A
Communications Systems: Aug 18A, Dec 15A
Component Parts: Jul 16A
Component Parts and Electron Devices: Aug 18A
Electronic Computers: Jan 22A, Jun 16A
Engineering Management: Feb 15A, Jun 16A
Engineering Writing and Speech: Apr 14A
Human Factors in Electronics: Feb 15A
Information Theory: Jun 16A, Dec 15A
Microwave Theory and Techniques: Feb 15A, Dec 15A
Military Electronics: Apr 14A
Nuclear Science: Aug 18A
Radio Frequency Interference: Jan 22A, Apr 14A, Jul 16A, Dec 15A
Space Electronics and Telemetry: Sep 15A
Vehicular Communications: Sep 15A

Programs

Bio-Medical Research, Symposium on Facilities for, PGBME-AIEE-ISA-University of Nebraska, Oct 26–27, 1961, Omaha, Neb.: Oct 24A
Broadcast and Television Receivers, Chicago Spring Conference on, PGBTR—Chicago Section, Jun 19–20, 1961, Des Plaines, Ill.: Jun 22A
Circuit Theory, Fifth Midwest Symposium on, PGCT, May 6, 8–9, 1961, Urbana, Ill.: Apr 28A
Electromagnetics and Fluid Dynamics of Gaseous Plasma, Symposium on, Dept. of Aerospace Engrg.—Microwave Res. Inst.—PGED—PGMTT—PGNS—Inst. of Aerospace Sciences—Polytech. Inst. Brooklyn, Apr 4–6, 1961, New York, N. Y.: Mar 20A
Electron Devices Meeting, 1961, PGED, Oct 26–28, 1961, Washington, D.C.: Oct 26A
Engineering Management, Ninth Annual Conference, PGEM—AIEE—*et al.*, Sep 14–15, 1961, New York, N. Y.: Aug 30A
Engineering Writing and Speech, National Symposium on, PGEWS, Oct 16–17, 1961, East Lansing, Mich.: Oct 22A
Global Communications, Fifth National Symposium on (GLOBECOM V), PGCS—AIEE, May 22–24, 1961, Chicago, Ill.: Apr 30A
Industrial Electronics Symposium, PGIE—AIEE—ISA, Sep 20–21, 1961, Boston, Mass: Aug 32A
IRE Canadian Electronics Conference, Region 8, Oct 2–4, 1961, Toronto, Canada: Sep 20A
IRE International Convention, Mar 20–23, 1961, New York, N.Y.: Mar 652
Joint Automatic Control Conference, AIChE—AIEE—ASME—IRE—ISA, June 28–30, 1961, Boulder, Colo: May 22A
Joint Nuclear Instrumentation Symposium, PGNS—PGI—AIEE—ISA—*et al.*, Sep 6–8, 1961, Raleigh, N. C.: Aug 28A
Magnetism and Magnetic Materials, Seventh Conference on, IRE—AIEE—AIP—ONR—AIME, Nov 13–16, 1961, Phoenix, Ariz.: Nov 16A
Magnetohydrodynamics, Second Symposium on Engineering Aspects of, AIEE—AIR—IRE—University of Pennsylvania, Mar 9–10, 1961, Philadelphia, Pa.: Feb 20A
Military Electronics, Fifth National Convention on (MIL-E-CON 1961), PGMIL, Jun 26–28, 1961, Washington, D.C.: Jun 22A
PGMTT, 1961, National Symposium, PGMTT, May 15–17, 1961, Washington, D. C.: Apr 28A
National Communications, Seventh Symposium, PGCS—Rome-Utica Section, Oct 2–4, 1961, Utica, N. Y.: Sep 24A
National Electronics Conference, IRE—AIEE—*et al.*, Oct 9–11, 1961, Chicago, Ill.: Sep 26A
Northeast Electronics Research and Engineering Meeting, IRE Region 1, Nov 14–16, 1961, Boston, Mass.: Oct 30A
PGPEP Conference, Fifth Annual, PGPEP, Jun 14–15, 1961, Philadelphia, Pa.: May 20A
Radio Fall Meeting, 1961, PGED—BTR—RQC—EIA, Oct 30–Nov 1, 1961, Syracuse, N. Y.: Oct 28A
Radio Frequency Interference, Third National Symposium on, PGRFI, Jun 12–13, 1961, Washington, D. C.: Jun 28A
Reliability and Quality Control, Eighth National Symposium on, PGRQC—AIEE—ASQC—EIA, Jan 9–11, 1962, Washington, D. C.: Dec 24A
Seventh Region IRE Technical Conference and Electronic Exhibits, Region 7, Apr 26–28, 1961, Phoenix, Ariz.; Apr 26A
Solid State Circuits Conference, International, PGCT—AIEE—University of Pennsylvania, Feb 15–17, 1961, Philadelphia, Pa.: Jan 22A
Space Electronics and Telemetry, National Symposium on, PGSET, Sep 6–8, 1961, Albuquerque, N. Mex.: Aug 28A
SWIRECO, Thirteenth Annual, Region 6, Dallas Memorial Auditorium, Apr 19–21, 1961, Dallas, Tex.: Mar 20A
Western Electric Show and Convention (WESCON 1961), Los Angeles and San Francisco Sections—WEMA, Aug 22–25, 1961, San Francisco, Calif.: Aug 20A
Western Joint Computer Conference, PGEC—AIEE—ACM, May 9–11, 1961, Los Angeles, Calif.: Apr 35A

Report of the Secretary

Letter to the Board of Directors, 1960: Jun 1104

Scanning the Issue

February 419
March 564
April 724
May 879
June 1007
July 1135
August 1263
September 1375
October 1487
November 1615

Scanning the Transactions

January 393
February 537
March 693
April 855
May 983
June 1110
July 1238
August 1348
September 1461
October 1593
November 1715
December 1972

Sections and Subsections

Chairmen and Secretaries:
January 28A
March 24A
May 24A
July 20A
September 32A
November 22A
News:
Crescent Bay Subsection Established: Aug 18A
France Section Established: Dec 18A
Geneva Section Established: Feb 14A
Victoria Subsection Established: Jun 16A

Translations of Russian Technical Literature

January 416
February 560
March 720
June 1132

INDEX TO BOOK REVIEWS

Adaptive Control Processes: A Guided Tour, by R. Bellman (*Reviewed by L. A. Zadeh*): Nov 1712

Advances in Electron Tube Techniques, D. Slater, Ed. (*Reviewed by G. A. Esperson*): Sep 1460

Alternating-Current Circuits, 4th ed., by R. M. Kerchner and G. F. Corcoran (*Reviewed by W. H. Kim*): Jan 389

Analog and Digital Computer Technology, by N. R. Scott (*Reviewed by A. D. Scarbrough*): Feb 535

Analogue and Digital Computers, A. C. D. Haley and W. E. Scott, Advisory Eds. (*Reviewed by T. H. Bonn*): Jan 392

Analysis and Design of Feedback Control Systems, 2nd ed., by G. J. Thaler and R. G. Brown (*Reviewed by F. Zweig*): Feb 534

Analytical Techniques for Non-Linear Control Systems, by J. C. West (*Reviewed by J. G. Truxal*): May 981

Antenna Engineering Handbook, H. Jasik, Ed. (*Reviewed by G. Sinclair*): Nov 1714

Antenna, The, by H. Thourel (*Reviewed by S. B. Cohn*): Nov 1713

Arc Discharge, The, by H. de B. Knight (*Reviewed by G. H. Reiling*): Feb 536

A. R. R. L. Antenna Book, The, by the Headquarters Staff of the American Radio Relay League, Inc. (*Reviewed by C. E. Smith*): Jan 391

Automatic Translation, by D. Yu. Panov (*Reviewed by L. B. Heilprin*): May 981

Basic Electrical Measurements, 2nd ed., by M. B. Stout (Title only): July 1237

Basic Physics of the Solar System, by V. M. Blanco and S. W. McCluskey (Title only): Nov 1715

Basics of Analog Computers, by T. D. Truitt and A. E. Rogers (Title only): May 982

Boolean Algebra and Its Applications, by J. E. Whitesitt (*Reviewed by R. Serrell*): Jun 1110

British Miniature Electronic Components and Assemblies Data Annual 1961–62, G. W. A. Dummer and J. M. Robertson, Eds. (Title only): Aug 1348

Circuit Analysis, by E. M. Sabbach (*Reviewed by I. O. Ebert*): Sep 1459

Classical Mechanics, 2nd ed., by H. C. Corben and P. Stehle (Title only): Feb 536

Complex Variables and the Laplace Transform for Engineers, by W. R. LePage (*Reviewed by E. F. Bolinder*): May 980

Computer Logic, by I. Flores (*Reviewed by C. T. Leondes*): Mar 690

Control of Multivariable Systems, The, by M. D. Mesarović (*Reviewed by N. H. Choksy*): Apr 853

Control System Analysis and Synthesis, by J. J. D'Azzo and C. H. Houpis (*Reviewed by G. A. Biernson*): May 980

Coupled Mode and Parametric Electronics, by W. H. Louisell (*Reviewed by H. Heffner*): Feb 535

Design for a Brain, 2nd ed., by W. R. Ashby (*Reviewed by F. Rosenblatt*): Jun 1108

Design Fundamentals of Analog Computer Components, by R. M. Howe (*Reviewed by J. E. Sherman*): Jul 1235

Dictionary of Automatic Control, by R. J. Bibbero (Title only): Feb 536

Dictionary of Electronics, by H. Carter (*Reviewed by M. W. Baldwin, Jr.*): Mar 692

Dielectrics, 1959 Digest of Literature on, L. J. Frisco and T. D. Callinan, Eds. (*Reviewed by P. N. Wolfe*): Jul 1234

Digital Applications of Magnetic Devices, A. J. Meyerhoff, Ed. (*Reviewed by A. H. Bobeck*): Oct 1952

Digital Computer and Control Eng neering, by R. S. Ledley (*Reviewed by B. Lippel*): Jan 391

Digital Computer Fundamentals, by T. C. Bartee (Title only): Feb 536

Electrical Engineering Problems, by E. M. Williams and F. J. Young (*Reviewed by S. Seely*): May 690

Electrical Noise, by W. R. Bennett (*Reviewed by H. A. Haus*): Aug 1348

Electromagnetic Energy Transm'ssion and Radiation, by R. B. Adler, Lan Jen Chu, and R. Fano (*Reviewed by E. C. Jordan*): Feb 534

Electromagnetic Fields and Waves, by R. V. Langmuir (*Reviewed by D. J. Angelakos*): May 981

Electromechanical Components for Servomechanisms, by S. A. Davis and B. K. Ledgerwood (Title only): Dec 1971

Electronic Circuit Analysis, Vol. 1, Passive Networks, by P. Culter (*Reviewed by I. O. Ebert*): Mar 691

Electronic Circuits, Signals, and Systems, by S. J. Mason and H. J. Zimmerman (*Reviewed by W. H. Huggins*): Nov 1714

Electronic Drafting Handbook, by N. M. Raskhodoff (*Reviewed by R. T. Haviland*): Aug 1345

Electronic Equipment Reliability, by G. W. A. Dummer and N. Griffin (*Reviewed by M. Raphelson*): Jul 1234

Electronic Maintainability, Vol. 3, F. L. Ankenbrandt, Ed. (*Reviewed by R. R. Batcher*): Feb 533

Electronics, by P. M. Chirlian and A. H. Zemanian (*Reviewed by W. R. Hill*): Aug 1346

Electronics and Nucleonics Dictionary, by N. M. Cooke and J. Markus (*Reviewed by R. F. Shea*): Jan 392

Electrostatic Propulsion, Vol. 5 in Progress in Astronautics and Rocketry, D. B. Langmuir, E. Stuhlinger, and J. M. Sellen, Jr., Eds. (Title only): Dec 1971

Elementary Differential Equations, by W. T. Martin and E. Reissner (Title only): Dec 1971

Elements of Nuclear Engineering, by G. Murphy (Title only): Jul 1237

Elsevier's Dictionary of Automation, Computers, Control, and Measuring, W. E. Clason, Ed. (Title only): Jul 1237

Engineering Approach to Gyroscopic Instruments, An, by E. J. Siff and C. L. Emmerich (Title only): May 982

Error Correcting Codes, by W. W. Peterson (*Reviewed by N. Abramson*): Sep 1459

Essentials of Dielectromagnetic Engineering, H. M. Schlicke (*Reviewed by C. F. Pulvari*): Aug 1347

Field Theory for Engineers, by P. Moon and D. E. Spencer (*Reviewed by J. R. Wait*): Jul 1236

Field Theory of Guided Waves, by R. E. Collin (*Reviewed by S. B. Cohn*): Mar 690

Finite-Difference Methods for Partial Equations, by G. E. Forsythe and W. R. Wasow (Title only): Feb 536

Foundation for Electric Network Theory, by M. B. Reed (*Reviewed by B. Liu*): Oct 1591

Foundations of Electrodynamics, by P. Moon and D. E. Spencer (*Reviewed by J. R. Whinnery*): Mar 691

Frequency-Power Formulas, by P. Penfield, Jr. (*Reviewed by S. Seely*): Jun 1108

Fundamentals of Modern Physics, by R. M. Eisberg (*Reviewed by C. W. Carnahan*): Sep 1458

Fundamentals of Signal Theory, by J. L. Stewart (*Reviewed by C. A. Desoer*): Jun 1109

Handbook of Thermophysical Properties of Solid Materials, Vol. IV, A. Goldsmith, T. E. Waterman, and H. J. Hirschhorn, Eds (*Reviewed by J. G. Harper*): Dec 1970

High Frequency Applications of Ferrites, by J. Roberts (*Reviewed by J. H. Bowen*): Jun 1108

High-Frequency Magnetic Materials—Their Characteristics and Principal Applications, by W. J. Polydoroff (*Reviewed by D. L. Fresh*): Jul 1233

Inertial Guidance, by C. S. Draper, W. Wrigley and J. Hovorka (Title only): Feb 536

Information Retrieval and Machine Translation, Part I, A. Kent, Ed.; Advances in Documentation and Library Science Series, Vol. 3, J. H. Shera, General Ed. (*Reviewed by G. Salton*): Apr 853

Information Retrieval and Machine Translation, Pt. II, D. Slater, Ed.; Advances in Documentation and Library Science Series, Vol. 3, J. H. Shera, General Ed. (*Reviewed by G. Salton*): Sep 1460

International Dictionary of Applied Mathematics, The (Title only): Feb 536

International Dictionary of Physics and Electronics, The, 2nd ed., W. C. Michels, Ed. (*Reviewed by R. F. Shea*): Jul 1235

Introduction to Ceramics, by W. D. Kingery (Title only): May 982

Introduction to Elementary Particle Physics, R. E. Marshak and E. C. G. Sudarshan (Title only): Aug 1348

Introduction to the Principles of Communication Theory, An, by J. C. Hancock (*Reviewed by W. D. White*): Nov 1713

Introduction to Statistical Communication Theory, An. by D. Middleton (*Reviewed by N. Abramson*): Apr 853

Introduction to Transistor Circuits, An, by E. H. Cooke-Yarborough (*Reviewed by A. P. Stern*): Feb 534

IRE Dictionary of Electronic Terms and Symbols (Compiled from IRE Standards) (*Reviewed by R. F. Shea*): Aug 1343

Lectures on Communication System Theory, E. J. Baghdady, Ed. (*Reviewed by M. R. Aaron*): Aug 1345

Line Waves and Antennas, by R. G. Brown, R. A. Sharpe, and W. L. Hughes (*Reviewed by C. E. Smith*): Aug 1344

Linear Circuits, Part 1: Time-Domain Analysis; Part 2: Frequency-Domain Analysis, by R. E. Scott (*Reviewed by T. W. Culpepper*): Jul 1233

Linear Graphs and Electrical Networks, by S. Seshu and M. B. Reed (*Reviewed by P. F. Ordung*): Jul 1237

Linear Systems Analysis, by P. E. Pfeiffer (*Reviewed by R. P. Burr*): Apr 854

Magnetic Tape Instrumentation, by G. L. Davis (*Reviewed by S. J. Begun*): Sep 1459

Management Control Systems, D. G. Malcolm, A. J. Rowe, Eds.; L. F. McConnell, General Ed. (*Reviewed by J. J. Lamb*): Sep 1461

Manual of Mathematical Physics, by P. I. Richards (*Reviewed by S. A. Schelkunoff*): Feb 534

Mathematical Handbook for Scientists and Engineers, by G. A. Korn and T. M. Korn (*Reviewed by A. B. Giordano*): Jul 1234

McGraw-Hill Encyclopedia of Science and Technology, The (*Reviewed by G. Shapiro*): Jun 1109

Mechanical Waveguides, by M. R. Redwood (*Reviewed by J. E. May, Jr.*): Sep 1458

Microwave Ferrites, by P. J. B. Clarricoats (*Reviewed by E. H. Turner*): Oct 1591

Modern Mathematics for the Engineer, 2nd Series, E. F. Beckenbach, Ed. (*Reviewed by B. Friedland*): Jun 1110

Modulation de Frequence, La, by J. Marcus (*Reviewed by M. Arditi*): Apr 852

NMR and EPR Spectroscopy (Title only): Jul 1237

Noise Reduction, by L. L. Beranek (*Reviewed A. P. G. Peterson*): Jan 390

Nuclear Engineering, by G. Cahen and P. Treille (Title only): Jul 1237

Optics of the Electromagnetic Spectrum, by C. L. Andrews (*Reviewed by M. Kline*): Jan 391

Philosophical Impact of Contemporary Physics, by M. Čapek (*Reviewed by F. Herman*): Oct 1591

Physical Principles of Astronautics, The, by A. I. Berman (Title only): Aug 1348

Physical Theory of Transistors, The, by L. B. Valdes (*Reviewed by M. A. Clark*): Nov 1712

Physics of Semiconductors, by A. F. Ioffe (*Reivewed by L. T. De Vore*): Jul 1237

Plasma Acceleration—The Fourth Lockheed Symposium on Magnetohydrodynamics, S. W. Kash, Ed. (*Reviewed by C. H. Hoeppner*): Oct 1591

Plasma Physics, by J. E. Drummond (*Reviewed by J. M. Richardson*): Jun 1108

Power Reactor Technology, by J. K. Pickard, F. H. Warren, W. W. Lowe and S. McLain (Title only): Jul 1237

Principles of Astronautics, by M. Vertregt (Title only): May 982


Principles of Control Systems Engineering, by V. Del Toro and S. R. Parker (*Reviewed by F. A. Russell*): Jan 392

Principles of Feedback Control, by C. H. Wilts (*Reviewed by R. G. Buschner*): Jul 1233

Principles of Illumination, by H. Cotton (Title only): May 982

Principles of Inertial Guidance, by C. J. Savant, Jr., R. C. Howard, C. B. Solloway, and C. A. Savant (Title only): Jul 1237

Principles of Semiconductor Device Operation, by A. K. Johscher (*Reviewed by H. E. Tompkins*): Apr 854
Printed Circuits—Their Design and Application, by J. M. C. Dukes (*Reviewed by T. A. Prugh*): Aug 1343
Probability and Experimental Errors in Science, by L. G. Parratt (Title only): Dec 1971
Proceedings of the 1959 Computer Applications Symposium, A. Ungar, Ed. (Title only): Feb 536
Proceedings of the Second International Conference on Operational Research (Title only): Dec 1971
Proceedings of URSI Thirteenth General Assembly, J. P. Hagen, Ed. (*Reviewed by E. C. Jordan*): Nov 1713
Progress in Semiconductors, Vol. 5, A. F. Gibson, F. A. Kröger, and R. F. Burgess, Eds. (*Reviewed by W. M. Bullis*): Aug 1346
Progress in Very High Pressure Research, F. P. Bundy, W. R. Hibbard, Jr., and H. M. Strong, Eds (Title only): Nov 1715
Radio Amateur's Handbook, The, 38th ed., by the Headquarters Staff of the American Radio Relay League (Title only): May 982
Radio Transmitters, by L. F. Gray and R. Graham (*Reviewed by W. B. Bruene*): May 982
Radio Waves in the Ionosphere, by K. G. Budden (*Reviewed by M. G. Morgan*): Aug 1347
Relativistic Electron Theory, by M. E. Rose (*Reviewed by F. Herman*): May 981
Satellite Environment Handbook, F. S. Johnson, Ed. (*Reviewed by M. G. Morgan*): Dec 1970
Scandinavian Research Guide, Vols. 1–2 (Title only): May 982
Scientific Russian, by J. W. Perry (*Reviewed by S. D. Browne*): Aug 1347
Self-Organizing Systems, M. C. Yovits and S. Cameron, Eds. (*Reviewed by P. M. Kelly*): Feb 533
Semiconductor Abstracts, Vol. VI—1958 Issue, J. J. Bulloff and C. S. Peet, Eds. (*Reviewed by J. A. Sluss, Jr.*): Jul 1236
Semiconductor Devices and Applications, by R. A. Greiner (*Reviewed by N. Holonyak, Jr.*): Oct 1590
Sequential Decoding, by J. M. Wozencraft and B. Reiffen (*Reviewed by R. A. Short*): Sep 1458
Silicon Carbide—A High Temperature Semiconductor, J. R. O'Connor and J. Smiltens, Eds. (Title only): Feb 536
Solid State Physics in Electronics and Telecommunications, Vol. 2, Semiconductors, Part II, M. Desirant and J. L. Michiels, Eds. (*Reviewed by A. P. Stern*): Jul 1235
Solid State Physics in Electronics and Telecommunications, Vol. 3, Magnetic and Optical Properties, Part I, M. Desirant and J. L. Michiels, Eds. (*Reviewed by N. Bloembergen*): Jan 389
Solid State Physics in Electronics and Telecommunications, Vol. 4, Magnetic and Optical Properties, Part 2, M. Desirant and J. L. Michiels, Eds. (*Reviewed by R. F. Soohoo*): Apr 852
Space Astrophysics, W. Liller, Ed. (Title only): Aug 1348
Space Research, H. K. Kallmann Bijl, Ed. (*Reviewed by G. E. Mueller*): Mar 691
Static Relays for Electronic Circuits, R. F. Blake, Ed. (*Reviewed by R. P. Burr*): Dec 1971
Statistical Theory and Methodology in Science and Engineering, by K. A. Brownlee (*Reviewed by W. R. Bennett*): Mar 692
Statistical Theory of Communications, by Y. W. Lee (*Reviewed by T. M. Burford*): Mar 690
Surface Chemistry of Metals and Semiconductors, The, H. C. Gatos, Ed., with the assistance of J. W. Faust, Jr., and W. J. LaFleur (*Reviewed by W. Mehl*): Jan 389
Terrain Scattering Properties for Sensor System Design (Terrain Handbook II), by R. L. Cosgriff, W. H. Peake, and R. C. Taylor (*Reviewed by K. M. Siegel*): Jul 1236
Theory of Microwave Valves, by S. D. Gvozdover (*Reviewed by C. W. Barnes*): Aug 1344
Thermoelectricity, P. H. Egli, Ed. (*Reviewed by F. E. Jaumot, Jr.*): Jan 390
Thermoelectricity: Science and Engineering, by R. R. Heikes and R. W. Ure (*Reviewed by W. H. Clingman*): Dec 1971
Time-Harmonic Electromagnetic Fields, by R. F. Harrington (*Reviewed by C. H. Papas*): Aug 1344
Topology, by J. G. Hocking and G. S. Young (Title only): Nov 1715
Transform Calculus for Electrical Engineers, by R. Legros and A. V. J. Martin (Title only): Aug 1348
Transistor Circuit Analysis, by M. V. Joyce and K. K. Clark (*Reviewed by J. T. Lynch and J. J. Karew*): Aug 1343
Transistors—Principles, Design and Applications, by W. W. Gärtner (*Reviewed by V. R. Saari*): Apr 852
Transmission of Information, by R. M. Fano (*Reviewed by G. A. Deschamps*): Oct 1592
Traveling-Wave Engineering, by R. K. Moore (*Reviewed by G. W. Swenson, Jr.*): Jan 391
Wave Generation and Shaping, by L. Strauss (*Reviewed by L. L. Burns*): Feb 533
Wave Propagation in a Turbulent Medium, V. I. Tatarski (*Reviewed by R. Bolgiano, Jr.*): Oct 1590
Waves in Layered Media, by L. M. Brekhovskikh (*Reviewed by S. Silver*): Feb 535



2N2187
Matched pair of
Philco type
2N2185 SPAT
Choppers, in
TO-18 Packages.

New PHILCO matched Silicon Choppers

HELP A MISSILE "FLY" TWICE




Philco SPAT* choppers, industry's most reliable telemetry multiplex switches, assure highest fidelity in multiplexing data from a missile's many sensors such as strain gauges and thermocouples—data that is the only legacy of a multi-million dollar missile flight. For this data is used in post-flight simulations which, in effect, make the missile "fly" twice.

Philco's missile-proved SPAT choppers are produced on industry's only fully-automatic chopper transistor production line—to assure the uniformity so important to matched pairs.

Only Philco Choppers offer you these 6 advantages:

1. *Low Offset Current—1 nanoampere maximum;*
2. *Low Offset Voltage—50 μvolts maximum (for the matched pair);*
3. *Guaranteed Match over a temperature range—25° to 85° C;*
4. *Guaranteed maximum offset voltage for a wide range of base current values;*
5. *High gain-bandwidth product;*
6. *Meet all requirements of MIL-S-19500B.*

TYPICAL CHOPPER CIRCUIT



2N2185 CHARACTERISTICS

Emitter Voltage, BV_{ECO}	−30 volts
Collector Cutoff Current I_{CBO} (V_{CB}=−10V)	.001 μa max.
Emitter Cutoff Current I_{EBO} (V_{EB}=−10V)	.001 μa max.
Offset Voltage V_{EC} (I_B=−200 μa, I_E=0)	1.5 mv max.
Offset Voltage V_{EC} (2N2187 Matched pair, I_B=−1 ma at all temperatures from 25°C to 85°C.)	50 μv max.

To assure maximum reliability in systems for telemetry, multichannel communications, analog computers, and other low level data handling applications, be sure to specify Philco SPAT choppers. There's a Philco SPAT chopper for every application. You can choose from seven types (2N2181 through 2N2187).

For complete data, write Department IRE 1261.

Philco
SPAT Choppers
are immediately
available from
your Philco Industrial
Semiconductor Distributor.

PHILCO®

Famous for Quality the World Over

LANSDALE DIVISION • LANSDALE, PENNSYLVANIA


SOLID-STATE CENTER U.S.A.™

**Philco Corporation Trademark for Silicon Precision Alloy Transistor*

The Counter with a Memory *also writes*

The G-R Counter's unique storage circuits vast simplify graphic analog recording. To decode t Counter's output to a d-c analog voltage you simp add G-R's all electronic Digital-to-Analog Converte

For those desiring tabulated digital data, a Da Printer is available which connects directly to t Counter (no modifications or adaptor kits required



Type 1521-A Graphic-Level Recorder

1130-A Digital Time and Frequency Meter

Measurement Ranges:
Frequency: dc to 10 Mc
Period: 10μsec to 10^7 sec
Time Interval: 1μsec to 10^7 sec
Also measures 10 periods, frequency ratios, phase shifts, pulse characteristics, and counts random events.

Display:
8 digits intermittent; 4 digits continuous readout (previous count displayed continuously during counting interval; changes to new value wh count is completed).

Sensitivity: 0.25v rms

Accuracy: ±1 count ± time-ba stability. A variety of plug time-base generators a available with short-term s bilities ranging from 1 part 10^8/min to 1 part in 10^9/mi

Price: From $2,585 to $2,950 pending on time-base ge erator desired.


1134-A Digital-to-Analog Converter $595

Will drive any standard 1 ma (or 100 mv) recorder

- High Accuracy —
  Linearity: ±0.05% of full scale
  Stability: ±0.02% for ±15% line voltage variations; ±0.03% for ambient temperature changes over the range from 0 to 50 C.
- All Electronic — No mechanical data printer required to convert counter output to steady analog signal. Operates directly from the G-R Counter's internal storage system.
- Either 1 ma or 100 mv outp Connects readily to most strip-chart recorders.
- Records first 3, last 3, or l 2 digits of the G-R Counte 4-digit continuous disp which may be set to read a four consecutive digits count over the range fr dc to 10 Mc.

1132-A DATA PRINTER, $1450, for unattended measurements

Provides permanent printed records on adding machine tape. The printer has a 12-column register capacity, eight of which are used to print counter output. The remaining four columns can be used to display additional data such as time from a digital clock. Printing rate is adjustable from one print every twenty seconds to three prints per second. A keyboard and print-command bar allow numbers to be typed manually between automatic prints. An output for driving an IBM summary punch is available as a special option.



GENERAL RADIO COMPANY

WEST CONCORD, MASSACHUSETTS

NEW YORK, WOrth 4-2722	CHICAGO	PHILADELPHIA	WASHINGTON, D. C.	SYRACUSE	SAN FRANCISCO	LOS ANGELES	ORLANDO, FLA.	IN CANADA
District Office in Ridgefield, N. J. WHitney 3-3140	Oak Park VIllage 8-9400	Abington HAncock 4-7419	Silver Spring JUniper 5-1088	Syracuse GLenview 4-9323	Los Altos WHitecliff 8-8233	Los Angeles HOllywood 9-6201	Orlando GArden 5-4671	Toronto CHerry 6-217